

# Electronic Design. 2

VOL. 26 NO.

FOR ENGINEERS AND ENGINEERING MANAGERS — WORLDWIDE


JAN. 18, 1978

**Mini and microcomputers** have become lookalikes that make the distinction often meaningless. Whether you need a computer on a chip, on a board, or in

a box, the many choices can be confusing. But if you ask the right questions, you can find the best values ever for your money. For help, GOTO 24.



# The First Modular Precision Pot...



... 10 turn precision,  
in a 5/8" square package.

Now custom design precision in your equipment! Bourns modular line of 10-turn wire-wound potentiometers offers virtually infinite selection of standard options, with specs that are unequaled in any other line of modular controls, potentiometers and switches.

**SMALL SIZE**—The 5/8" square design saves up to 35% of panel space compared to standard circular models. Position them closer or in an area simply not possible before now.

**LOW ASSEMBLY COSTS**—Easy and economical mounting on P.C. boards. Only Bourns offers a choice of P.C. pins or solder lugs!

**MANY OPTIONS**—Single shafts of 1/8" or 1/4" diameter are each available in 3 standard lengths, or choose dual concentric shaft options - all with plain or locking bushings. Specify to your application and gang up to two modules.


You'll find these smaller modular precision pots offer the same electrical specs as the larger circular types - such as independent linearity of only  $\pm 0.25\%$ .

**"FEEL-APPEAL"**—As with Bourns other styles of controls and switches, this precision line offers the same smooth, consistent feel. The low rotational torque is still only .3 to 2.0 oz. inch!

**CALL TODAY**—for complete information on this versatile off-the-shelf, modular constructed potentiometer. Find out how to custom design precision in your equipment at standard cost and leadtime.

**MODULAR PRECISION... BEAUTIFUL!**

TRIMPOT PRODUCTS DIVISION, BOURNS, INC., 1200 Columbia Avenue, Riverside, CA 92507, Telephone 714 781-5122—TWX 910 332-1252.



International Marketing Offices: European Headquarters — Switzerland 042/23 22 42 • Belgium 02/218 2005 • France 01/2039633 • Germany 0711/24 29 36 • Italy 02/32 56 88 • Netherlands 70/87 44 00 • United Kingdom 01/572 6531 • Norway 2/71 18 72 • Sweden 764/20 110 • Japan 075/921 9111 • Australia 02/55-0411 03/95-9566 • Israel 77 71 15/6/7

**For Immediate Application — Circle 130**  
**or for Future Application — Circle 230**

When we surveyed the pulse generator market, we discovered that what many of you wanted was unavailable: a Wavetek pulse generator

Model 801 takes care of that.

It's a 50 MHz pulse generator with independent width, rate, and delay controls. It's a versatile instrument, with double pulse

capability, a pulse burst mode, and a pulse reconstruction feature. But above all, it's a Wavetek, as you can see, and as you can tell by the low price (just \$995).

We could go on about the fixed ECL, TTL, and  $\overline{\text{ECL}}$  outputs, and the variable outputs up to plus and minus 20 volts. Or the adjustable rise/fall from less

than 5 nanoseconds. But this is an ad, not a data sheet. So why not circle our reader service number and get all the specs on Wavetek's first pulse generator. WAVETEK, 9045 Balboa Avenue, P.O. Box 651, San Diego, CA 92112. Telephone: (714) 279-2200, TWX 910-335-2007.

**WAVETEK®**

CIRCLE NUMBER 2

# Nobody ever put one of these on a pulse generator before.



# The only Double-Balanced Mixers with a 2-YEAR GUARANTEE\*

featuring Hi-Rel tested diodes -


Introduced in 1971 at \$7.95 . . .

still only

# \$7.95

(500 pieces)

\$9.95 (1-49)



\*including diodes!

Yes, a two-year guarantee for hermetically sealed DBM's is now a reality . . . made possible by an accelerated-life diode screening program adopted at Mini-Circuits.

Each Schottky diode used in Mini-Circuits' SRA-1 mixers is now preconditioned by the HTRB (High Temperature Reverse Bias) technique, previously reserved almost exclusively for semiconductors assigned to space applications. With HTRB testing, each diode is operated for 168 hours at 150°C with one volt reverse bias applied.

To screen out "infant mortality", the diodes are deliberately stressed to accelerate aging and to force time-related failure modes to take their toll. In conventional testing or "baking", the diode does not experience anywhere near the stress encountered with the HTRB program. Hence, the ability at Mini-Circuits' to locate the potentially-unreliable diodes before they are assembled into SRA-1 units. And, with double-balanced mixers, the overall reliability hinges almost entirely on the diodes used.

Yes, the HTRB procedure costs us more and screens out more devices. But our goal is to improve reliability to a level unmatched for off-the-shelf DBM's at no increase in cost to our customers. You — our customers by your overwhelming confidence in our product line have made us the number one supplier of DBM's in the world.

## WE'VE GROWN

Customer acceptance of our products has been so overwhelming, we've been forced to move to larger facilities — THANKS.

**International Representatives:** □ **AFRICA:** Aftra (PTY) Ltd. P.O. Box 9813, Johannesburg 2000, S. Africa □ **AUSTRALIA:** General Electronic Services, 99 Alexander Street, New South Wales, Australia 2065 □ **ENGLAND:** Dale Electronics, Dale House, Wharf Road, Frimley Green, Camberley Surrey □ **EASTERN CANADA:** B.D. Hummel, 2224 Maynard Avenue, Utica, NY 13502 (315) 736-7821 □ **FRANCE:** S.C.I.E. - D.I.M.E.S. 31 Rue George - Sand 91120 Palaiseau, France □ **GERMANY, AUSTRIA, SWITZERLAND, DENMARK:** Industrial Electronics GMBH 6000 Frankfurt/Main Klüberstrasse 14 West Germany □ **INDIA:** Gaekwar Enterprise, Kama Mahal, M.L. Dananukar Marg, Bombay 400 026, India □ **ISRAEL:** Vectronics, Ltd., 69 Gordon Street, Tel-Aviv, Israel □ **NETHERLANDS, BELGIUM, LUXEMBOURG:** Coimex Veldweg II, Hattem, Holland

OUR NEW ADDRESS  
AND PHONE NO. IS:

**Mini-Circuits**

MINI-CIRCUITS LABORATORY  
A Division of Scientific Components Corp.

2625 East 14th Street Brooklyn, New York 11235 (212) 769-0200  
Domestic and International Telex 125460 International Telex 620156

□ **NORWAY:** Datamatik AS, Ostensjoveien 62, Oslo 6, Norway □ **SINGAPORE & MALAYSIA:** Electronics Trading Co. (PTE) Ltd., 87 Bukit Timah Road, Singapore 9, Malay Peninsula □ **SWEDEN:** Intergrad Elektronik AB, Box 43, S-18251, Djursholm, Sweden

**U.S. Distributors:** □ **NORTHERN CALIFORNIA:** PENNSTOCK Co., Foothill Office Center, 105 Fremont Avenue, Los Altos, CA 94022 (415) 948-6533 □ **SOUTHERN CALIFORNIA, ARIZONA:** Crown Electronics, 11440 Collins Street, No. Hollywood, CA 91601 (213) 877-3550  
**NEW YORK:** MICROWAVE DISTRIBUTORS COMPANY  
61 Mall Drive, Commack, N.Y. 11725 516 543-4776

To earn your continuing support, we are now employing HTRB Hi-Rel testing for every diode used in the SRA-1, at no increase in cost to you. So, for the same low price of \$7.95, you can purchase our SRA-1, with a two-year guarantee, including diodes.

To ensure highest system reliability demand highest quality diodes on your source-control drawings and purchase orders. Specify SRA-1 mixers, with HTRB tested diodes from Mini-Circuits... where low price now goes hand-in-hand with unmatched quality.

### MODEL SRA-1

Freq. range (MHz) LO - 0.5-500, RF 0.5-500, IF dc-500

Conversion loss (dB)	Typ.	Max.
One octave from band edge	5.5	7.0
Total range	6.5	8.5
Isolation (dB)	Typ.	Min.
Lower band edge to one decade higher	LO-RF 50	45
Mid range	LO-RF 45	35
Upper band edge to one octave lower	LO-RF 45	30
	LO-IF 40	25
	LO-RF 35	25
	LO-IF 30	20

Min. Electronic attenuation (20 mA) 3 dB

Signal, 1 dB compression level + 1 dBm

Impedance all ports 50 ohms



World's largest manufacturer of Double-Balanced Mixers

---

## NEWS

- 19 **News Scope**
- 24 **Time was when a mini was a mini, a micro was a micro, and the picking was easy. Not any more—A special report.**
- 34 **CRT terminals will be more complex, but simpler to build.**
- 36 **As test and measuring instruments spread out, safety concerns grow.**
- 40 **In optical communications, progress is slow but steady.**
- 49 **Washington Report**

---

## TECHNOLOGY

- 60 **Microprocessor Basics: Part 21.** Let 4-bit microcomputers do the simple jobs. They cost less than 8-bit units and offer almost as much processing power.
- 72 **When one  $\mu$ P controls another,** the interface becomes the focal point. Base the boundary on an IEEE-488 general-purpose bus, and speed data flow.
- 78 **Multiplying with a microcomputer** can be a drag. A simple multiplier/shifter can speed up signed 12-bit multiplications by a factor of ten.
- 86 **It's time to convert to complex-BCD.** However, CPUs can work more efficiently if a hardware converter replaces software for time-data conversion.
- 94 **Synchronizing giant generators** by hand can create expensive fireworks. But a mini closes the large circuit breakers with precision.
- 100 **Compute delay times of ALU adders.** Knowing they're fast is not good enough—it takes a trip through the delay path to calculate actual speed.
- 104 **Ideas for Design:**  
Twin-tee filter rejects more than 70 dB with capacitance-multiplier circuit. Switching supply converts  $-60$  V to  $+5$  and  $\pm 6.3$  V with 83% efficiency. Current inverters make current sources out of monolithic d/a sink outputs.
- 111 **International Technology**

---

## PRODUCTS


- 115 **Components:** Mass-produced precise and stable resistors surpass wire-wound units.
- 116 **Components:** Low-cost, flashing red LED has built-in IC timing circuit.
- 134 **Modules & Subassemblies:** Field-repairable i-f strips cut purchase and inventory costs.
- 136 **Modules & Subassemblies:** First 16-bit support boards mate with TI microcomputer.
- 122 Instrumentation
- 126 Micro/Mini Computing
- 133 Microwaves & Lasers
- 138 Power Sources
- 140 ICs & Semiconductors
- 142 Data Processing
- 146 Packaging & Materials

---

## DEPARTMENTS

- 55 **Editorial:** Protecting the members
- 7 Across the Desk
- 148 Application Notes
- 148 Bulletin Board
- 150 New Literature
- 157 Employment Opportunities
- 160 Advertisers' Index
- 160 Information Retrieval Card

**Cover:** Photo by Doug Doering, courtesy of Texas Instruments.



THE AM2903 HAS 2 DATA INPUT PORTS INSTEAD OF 1, AND THE DATA SHIFTER OCCURS IMMEDIATELY AFTER THE ALU INSTEAD OF AT THE RAM INPUT. THESE 2 CHARACTERISTICS MAKE THE REGISTER SUCH AS MULTIPLY, COMMON FUNCTIONS SUCH AS MULTIPLY, DIVIDE, NORMALISE, AND ARITHMETIC SHIFT ARE BUILT INTO THE PART, SAVING BOTH HARDWARE AND MICROCODE OVER OTHER DEVICES.

THE AM2903 ARCHITECTURE DIFFERS FROM THE AM2901 IN ONLY 2 WAYS, IS.

Advanced Micro Devices' new Am2903. It's a four-bit CPU slice with sixteen internal working registers, two address architecture, multi-function arithmetic logic unit and shifting logic.

**AND NOW,  
THE  
SUPERSLICE.™**

And if that's not enough, hang on.  
The Am2903's register file is expandable. If sixteen registers aren't enough, add as many working registers as you want and still retain the two-address architecture.

For those of you who think two-address architecture isn't enough, we made three-address operation possible in the Am2903. For those of you who hate using SSI and MSI, we put all the extra hardware to do 2's complement multiply and divide right inside the chip.

And we couldn't resist a few extra touches like built-in, floating-point normalize and parity.

Call, write or wire Advanced Micro Devices.

The magic word is Superslice™.


## Advanced Micro Devices



Multiple technologies. One product: excellence.  
901 Thompson Place, Sunnyvale, California 94086  
Telephone (408) 732-2400

CIRCLE NUMBER 4

# the widest selection of SCR power supplies in the whole wide world



The off-the-shelf selection is almost endless, with 1- and 3-phase rack-mounted power supplies from 500 to 10,000 watts DC. Call for complete information and prices, or write for our catalog.



## **ELECTRONIC MEASUREMENTS INC.**

405 Essex Road, Neptune, N.J. 07753  
Phone (New Jersey) 201-922-9300 (Toll free) 800-631-4298  
*Specialists in Power Conversion Equipment*

### **Publisher**

William Maass

### **Editors**

Editorial Offices  
50 Essex St.  
Rochelle Park, NJ 07662  
(201) 843-0550  
TWX: 710-990-5071  
(HAYDENPUB ROPK)  
Cable: Haydenpubs Rochellepark

**Editor-in-Chief** George Rostky

### **Managing Editors:**

Ralph Dobriner  
Michael Elphick

### **Senior Associate Editor**

Stanley Runyon

### **Associate Editors:**

Sid Adlerstein  
Nicholas Bodley  
Dave Bursky  
Morris Grossman  
Gene Heftman  
Andy Santoni  
Max Schindler

### **Contributing Editors:**

Peter N. Budzilovich, Jules H. Gilder,  
Sidney Moskowitz, Nathan Sussman

### **Editorial Field Offices**

#### **East**

Jim McDermott, Eastern Editor  
P.O. Box 272  
Easthampton, MA 01027  
(413) 527-3632

#### **West**

Dick Hackmeister, Western Editor  
8939 S. Sepulveda Blvd., Suite 414  
Los Angeles, CA 90045  
(213) 641-6544  
TWX-1-910-328-7240  
Dave Barnes, Western Editor  
465 S. Mathilda, Suite 302  
Sunnyvale, CA 94086  
(408) 736-6667

### **Editorial Production**

Marjorie A. Duffy, Production Editor  
James Keane, Copy Editor

### **Art**

**Art Director,** William Kelly  
Richard Luce, Anthony J. Fischetto

### **Business Manager**

Thomas E. Vachon

### **Production**

**Manager,** Dollie S. Viebig  
Helen De Polo, Nancy Hurey

### **Circulation**

**Director,** Barbara Freundlich  
**Senior Assistant,** Gail Stone

### **Information Retrieval**

Paula Greenleaf

### **Advertising Promotion**

Judith Nappo

### **Reprints**

Maxine Sassano



# Across the desk

## Can't save money without losing money

Your article on calculators for the blind (ED No. 20, Sept. 27, 1977, p. 32) was the most thorough we've seen. But we do take exception to the implication that technological wizardry can significantly reduce costs. For example, you stated, "Incorporating microprocessors into these systems promises to substantially reduce costs—but in future designs."

Our SPEECH+ calculator contains two one-chip microprocessors, a TI TSM-1000 and a custom microcontroller. Keeping costs low was a major design goal. The speech synthesizer itself consists of but two integrated circuits: the microcontroller and a 16-k ROM, so it is no more complicated than the \$100 architecture proposed in your article.

The cost problem is *economic*, not technical. The one-to-two-order-of-magnitude price difference between calculators for the blind and the sighted is small compared to the ratio of market sizes. The \$10 pocket calculator is only possible with mass production for a market of tens of millions. With a market in the low thousands as we have, such economy of scale is not possible. Development and tooling costs must be recovered over a relatively small number of units, distribution costs are proportionally higher, parts buys are small, and manufacturing costs are relatively high. We know of no way to circumvent these iron laws of economics short of losing money.

Also, the dedicated microcontroller in our speech synthesizer is manufactured by Silicon Systems, Inc., Santa Ana, CA, not Texas Instruments. We would also like to point out that the SPEECH+ speech-synthesis technolo-

gy was licensed from Prof. Forrest Mozer of Berkeley, CA.

*J.S. Brugler, Ph.D.*  
*Vice President Engineering*  
*Robert E. Savoie, Ph.D.*  
*Research Scientist*

Telesensory Systems, Inc.  
3408 Hillview Ave.  
P.O. Box 10099  
Palo Alto, CA 94304

## Misplaced credit

Jim McDermott's article on talking and Braille calculators (ED No. 20, Sept. 27, 1977, p. 80) contains a minor error that is "major" to me. In describing the Speech Plus calculator he explains that "the synthesizer uses two custom LSI circuits, one of which is a 16-k MOS ROM. The other is a dedicated Texas Instruments' microcontroller. . ."

The dedicated microcontroller used for speech synthesis was developed and is produced by Silicon Systems Incorporated of Irvine, California, not by TI.

*Jim Meyer*  
*Director of Marketing*

Silicon Systems Inc.  
16692 Hale Ave.  
Irvine, CA 92714


## A few stages less

Your News Scope article, "BBD Time Delay Sets Record at 4096 Stages" (ED No. 18, Sept. 1, 1977, p. 20), has two inaccuracies. According to the "IEEE Standards for Charge Transfer Devices," P-582, a stage of a BBD encompasses the whole portion covering a bit or element of charge. So over-all delay is the product of the number of stages

*(continued on page 152)*

Electronic Design welcomes the opinions of its readers on the issues raised in the magazine's editorial columns. Address letters to Managing Editor, Electronic Design, 50 Essex St., Rochelle Park, NJ 07662. Try to keep letters under 200 words. Letters must be signed. Names will be withheld upon request.

## Need a custom Power Supply fast?



## Hop on the Design-As-You-Order express!

With our miniaturized building-block approach, a custom power supply from someone else is a standard from Arnold Magnetics. You design from over 1200 mix and match configurations, and your power supply is potted and burn-in tested before delivery. Let us fill your special needs fast, and save you engineering charges too.

### Look under our hood.

**INPUTS** — Single or dual —

- AC: 50 to 500 Hz
- DC: 12, 28, 48 or 115 VDC

**MULTIPLE OUTPUTS** — Up to 10

- 3 to 400 watts
- Up to 3.9 watts per cubic inch
- Efficiencies to 80%

**REGULATION** — Line and load to 0.1%

### There's more.

**HIGH VOLTAGE SUPPLIES** — Outputs to 5000 VDC

**SPECIAL NEEDS?** We have the design and manufacturing capability to handle them and save time and resources.


Don't miss the Design-As-You-Order express... call or write for more information today!



**Arnold Magnetics Corporation**

11520 W. Jefferson Blvd.  
Culver City, Ca. 90230 • (213) 870-7014

# Stop wasting space and dollars.



# Use our faster 8K ROM.

**Monolithic Memories' new 6280-2 bipolar 8K ROM costs \$10 in volume and guarantees 55nS T<sub>AA</sub>.**

**The 6275-1 bipolar 16K ROM, with 110nS access time, gives you the best speed/density product going.**

You're no longer forced to specify a 4K ROM to get access speeds below 70nS. Our new 6280-2 1024x8 bit ROM ends that with 55nS maximum access time in commercial grade models, or 70nS access in MIL-temp models. Slower versions (6280-1 at 100nS max. T<sub>AA</sub>) are available in volume at prices down to \$8.50.

For higher density applications we've got 9K (6260-1) and 10K (6255-1) ROMs, both with 100nS access.


Or for the ultimate in bipolar ROM density, look into our 6275-1 bipolar 16K ROM, the world's fastest at 110nS access. All are available in open collector or tri-state outputs and in commercial or MIL-temp ranges.

## Flexible design with bipolar speed.

Already working with a 20-pin 4K ROM? That's okay.

Our 6280-2 is available in 20-pin, 22 or 24-pin packages, with pinouts designed as drop-in replacement for whatever you're using. And the 22 and 24-

pin versions have compatible PROMs available off the shelf. Add to this the inherent speed and simplicity of Monolithic Memories' bipolar technology for a total design package you can't beat.



## Design in now, plug in 5 weeks.

Delivery on most orders is five weeks from receipt of your bit pattern. Masking charge is only \$750 per pattern in minimum quantities of 100 pieces.

## From the undisputed world leader in bipolar memories.

Every year since its incorporation in 1970, Monolithic Memories has delivered more bipolar read only memory than any other company in the world. We introduced the first 1K PROM, the first 2K PROM, the first 4K PROM and the first 8K PROM. Look for much more from Monolithic Memories. Call (408) 739-3535 TWX 910-339-9229 or write 1165 East Arques Avenue, Sunnyvale, CA 94086.

## For technical assistance see your Monolithic Memories' area representative:

- |  |   |
|--|---|
| <b>ALABAMA</b><br>Huntsville<br>Rep. Inc.<br>(205) 881-9270  | <b>MINNESOTA</b><br>Minneapolis<br>Nortec Sales<br>(612) 835-7414   |
| <b>ARIZONA</b><br>Scottsdale<br>Summit Sales<br>(602) 994-4587   | <b>MISSOURI</b><br>Ballwin<br>Rush and West<br>(314) 394-7271   |
| <b>CALIFORNIA</b><br>Culver City<br>Electronics<br>(213) 870-9191<br>Mountain View<br>Thresum Associates<br>(415) 965-9180<br>San Diego<br>Littlefield & Smith<br>(714) 455-0055 | <b>NEW JERSEY</b><br>Teaneck<br>R. T. Reid Assoc.<br>(201) 692-0200<br><b>NEW YORK</b><br>Rochester<br>L-Mar Associates<br>(716) 328-5240<br>Syracuse<br>L-Mar Associates<br>(315) 437-7779 |
| <b>COLORADO</b><br>Wheatridge<br>Waugaman Associates<br>(303) 423-1020   | <b>NORTH CAROLINA</b><br>Raleigh<br>Rep. Inc.<br>(919) 851-3007   |
| <b>CONNECTICUT</b><br>North Haven<br>Comp Rep Associates<br>(203) 239-9762   | <b>OHIO</b><br>Cincinnati<br>Makin Associates<br>(513) 871-2424<br>Mentor<br>Makin Associates<br>(216) 464-4330   |
| <b>FLORIDA</b><br>Altamonte Springs<br>Dyne-A-Mark<br>(305) 831-2097<br>Clearwater<br>Dyne-A-Mark<br>(813) 441-4702<br>Fort Lauderdale<br>Dyne-A-Mark<br>(305) 771-6501          | <b>OREGON</b><br>Portland<br>N. W. Marketing<br>(503) 297-2581  |
| <b>GEORGIA</b><br>Tucker<br>Rep. Inc.<br>(404) 938-4358  | <b>PENNSYLVANIA</b><br>Oreland<br>CMS Marketing<br>(215) 885-5106   |
| <b>ILLINOIS</b><br>Rolling Meadows<br>Sumer<br>(312) 394-4900  | <b>TENNESSEE</b><br>Jefferson City<br>Rep. Inc.<br>(615) 475-4105   |
| <b>INDIANA</b><br>Indianapolis<br>Electro Reps<br>(317) 255-4147   | <b>TEXAS</b><br>Dallas<br>West & Associates<br>(214) 661-9400   |
| <b>IOWA</b><br>Cedar Rapids<br>S & O Sales<br>(319) 393-1845   | <b>UTAH</b><br>Salt Lake City<br>Waugaman Associates<br>(801) 363-0275  |
| <b>KANSAS</b><br>Olathe<br>Rush and West<br>(913) 764-2700   | <b>WASHINGTON</b><br>Bellevue<br>Northwest Marketing<br>(206) 455-5846  |
| <b>MARYLAND</b><br>Baltimore<br>Monolithic Sales<br>(301) 296-2444<br>Rockville<br>Monolithic Sales<br>(301) 340-2130  | <b>WISCONSIN</b><br>Milwaukee<br>Sumer<br>(414) 259-9060  |
| <b>MASSACHUSETTS</b><br>Needham Heights<br>Comp Rep Associates<br>(617) 444-2484   | <b>CANADA</b><br>ONTARIO<br>Milton<br>Cantec<br>(416) 624-9696  |
| <b>MICHIGAN</b><br>Grosse Pointe<br>Greiner Associates<br>(313) 499-0188   | <b>OTTAWA</b><br>Cantec<br>(613) 225-0363<br><b>QUEBEC</b><br>Pierre Ponds<br>Cantec<br>(514) 620-3121  |

# Monolithic Memories

Bipolar is our business.

# Intel delivers the micro components designers

There's no more efficient way to solve your interface and control requirements for microcomputer-based systems than our peripheral components.

They're single-chip solutions to even the most complicated operations, integrating

**"I can accomplish almost any I/O function with one chip using Intel's versatile peripheral interfaces and dedicated device controllers."**



up to 22,000 transistors per chip to replace circuit boards full of discrete logic with a single component. Result: you cut parts cost, reduce package count and board space, and simplify both development and operating software.

We've designed each of these peripheral chips to be an intelligent, programmable component in your system and to perform most functions with minimal cpu supervision. The resulting decrease in cpu overhead provides your system with higher performance and increased throughput.

The dedicated function components below are available now, with more on the way. Here's a brief description of their versatility.

8271 Programmable Floppy Disk Controller. Provides full control of up to four standard or minifloppy drives. (Available early 1978.)

8273 SDLC/HDLC Protocol Controller. For SDLC and HDLC communications.

8275 Programmable CRT Controller. Provides fully buffered interface and control of almost any raster scan CRT display.

8278/8279 Programmable Keyboard/Display Interfaces. Keyboard/sensor array input scan, and output scan for LED, incandescent and other displays.

128-key or 64-key input.

8251A Programmable Communications Interface. Industry standard USART for synchronous or asynchronous serial data

transmission, including bisync.

8253 Programmable Interval Timer. Contains three independent 16-bit counters, programmable modes from dc to 2MHz.

8255A Programmable Peripheral Interface. General purpose I/O interface with 24 individually programmable I/O pins.

8257 Programmable DMA Controller. Provides four-channel, high speed direct memory access independent of CPU.

8259 Programmable Interrupt Controller. Handles eight levels of vectored priority interrupt. Expandable to 64 levels.

# computer peripheral are talking about.

UPI-41™ is Intel's Universal Peripheral Interface, bringing distributed intelligence to microcomputer systems for the first time.

Actually a highly integrated, user-programmable microcomputer, UPI-41 is a new solution that obsoletes custom LSI and specialized discrete designs for interfacing most low and medium speed peripherals with an MCS-80™, MCS-85™ or MCS-48™ microcomputer.

Intel delivers UPI-41 in two versions that make it easy for you to implement your own designs. The 8741 includes an erasable and reprogrammable 1K-byte EPROM, for development, testing and low volume production. Then the 8041, with masked ROM, provides maximum economy in high volume.

We've taken the UPI-41 concept a step further with the 8278, described at left. The 8278 is the first of several preprogrammed 8041's that we've adapted to specialized applications.

Because UPI-41 is a microcomputer, we've given it the same high level of support we give all our microcomputers. UPI-41 is supported by our

Prompt™ 48 Design Aid, the Intellec® microcomputer development system with resident UPI-41/MCS-48 Macro Assembler. Plus appli-

**"And, for my special I/O requirements, Intel's UPI-41 Universal Peripheral Interface is user programmable to control nearly any other peripheral device."**

cations assistance worldwide, full documentation, training classes, design seminars and a rapidly expanding users' software library.

Intel's peripheral components, and the MCS-80, -85 and -48 microcomputers they support, are available through:

Almac/Stroum, Component Specialties, Cramer, Hamilton/Avnet, Harvey Electronics, Industrial Components, Pioneer, Sheridan, L.A. Varah, Wyle/Elmar-Liberty and Zen-tronics. For your copy of our Peripheral Data Handbook use the reader service card or write: Intel Corporation, 3065 Bowers Ave., Santa Clara, CA 95051. Telephone: (408) 987-8080.

**intel® delivers.**

CIRCLE NUMBER 8



# Precision quad op amps. *Precision.*

PMI's new OP-09 and OP-11 are pin-compatible with the un-precision quads now on the market.

The quad op amp has finally come of age. With the introduction of the OP-09 and OP-11, PMI has made it a truly workable reality. Consider:

## Low $V_{OS}$ and other goodies.

Since quads can't be nulled—there aren't enough pins available—the user is at the mercy of whatever input offset voltage ( $V_{OS}$ ) he happens to get. PMI refined the manufacturing process to get  $V_{OS}$  under control. We came up with the lowest  $V_{OS}$  of any quad op amp made today.

At the same time, we gave the OP-09 and OP-11 the highest gain and the lowest drift of any quad op amp. We expanded bandwidth, reduced offset and supply current, and increased the slew rate. Here it is in black and white:

## OP-09/OP-11 Features

	TYP.	MIN./MAX.
• Low $V_{OS}$	0.30 mV	0.5 mV MAX.
• Low offset current	8.0 nA	20 nA MAX.
• Low supply current (Total for all 4)	3.5 mA	6 mA MAX.
• Voltage gain	250K	100K MIN.
• Slew rate	1.0 V/ $\mu$ S	0.7 V/ $\mu$ S MIN.
• Matched positive and negative slew rate for low distortion.		
• Bandwidth		2.0 MHz MIN.

## We make them match.


Another important advantage: we guarantee that all four op amps will match in terms of  $V_{OS}$  and CMRR. Here's how we specify them:

## Matching Characteristics

Parameter	Symbol	OP-09A/E OP-11A/E			OP-09B/F OP-11B/F			Units
		Min	Typ	Max	Min	Typ	Max	
Input Offset Voltage Match	$\Delta V_{OS}$	—	0.5	0.75	—	0.8	2.0	mV
Common Mode Rejection	$\Delta CMRR$	—	1.0	20	—	1.0	20	$\mu$ V/V
Ratio Match		94	120	—	94	120	—	dB

(Match exists between all four amplifiers)

DUAL INSTRUMENTATION AMPLIFIER 2 OP AMP DESIGN  
(1/2 CIRCUIT SHOWN)



These matching dc characteristics should interest you. They reduce distortion, improve system performance, and simplify your design. But that's not all.

We've given all four op amps symmetrical positive and negative slew rates—an important thing to keep in mind for audio system design.


It's fair to say that the OP-09 and OP-11 are the most accurate, most advanced and the only **precision** quad op amps on the market. And they **are** on the market—available now, today.

Like to check one out? Be our guest. Just drop us a line on your company's stationery, telling us if you'd prefer an OP-09 (4136 pinout) or an OP-11 (148/4741 pinout). We'll be glad to send literature and a sample.

Precision Monolithics Incorporated  
1500 Space Park Drive  
Santa Clara, California 95050  
(408) 246-9222.  
TWX: 910-338-9222  
Cable MONO.



CIRCLE NUMBER 9



# Introducing Shugart's SA450 double-sided minifloppy. 440 Kbytes on-line without a flip.



**Why flip?** Nobody delivers this much on-line data storage from a single minifloppy disk drive with total compatibility. Nobody but Shugart offers a complete family of minifloppy disk products. Now a single minidiskette™ can carry operating system software, application programs or about 220 pages of text. All available on-line. Reach 440 Kbytes (unformatted) with random access speed. Without flipping media.

**Two heads are better than one.** The proprietary Shugart head design allows you to read and write both sides of the minidiskette. So you can write and read larger data files without the delays and risks that come from additional diskette handling. **We promised. We delivered.** The SA450 delivers true upward expansion based upon the industry standard 35 track format. This proven *Format With a Future* allows you to use single or double-sided minidiskettes without sacrificing the margin that you've come to expect with the minifloppy.

**Proven technology—single or double density.** The Shugart SA450 minifloppy disk drive has the same compact size and low weight as the original minifloppy—the Shugart SA400. And it's electrically, mechanically, and media compatible. Double density (MFM/M<sup>2</sup>FM) is standard, but you can also operate single density on one side or two. **There's more.** The unique direct-drive spiral cam actuator.

Low heat dissipation, write protect, activity light, die cast base plate, and DC drive motor, too. But you get the idea. Nobody makes more minifloppy disk drives than Shugart. Over 25,000 have been installed since we introduced the little guy in September 1976. Nobody can claim more experience. So if you want 440 Kbytes of on-line storage, big

drive data integrity, with proven reliability—and you're into word processing, intelligent terminals, small business systems or home computing—you'll love the SA450. Why flip? You can have the real double-sided minifloppy from the people who started the minifloppy revolution. Shugart.



 Shugart Associates


415 Oakmead Parkway, Sunnyvale, California 94086  
Telephone: (408) 733-0100  
West Coast Sales/Service: Telephone: (408) 252-6860  
East Coast Sales/Service: Telephone: (617) 890-0808  
Europe Sales/Service: 3, Place Gustave Eiffel, Silic 311  
94588 Rungis, France Telephone: (1) 686-00-85

™minidiskette trademark of Shugart Associates.

**The Leader  
In Low Cost  
Disk Storage.**

# Recalibrate.

(Your thinking and your budget)



Our new 5100/5101A calibrators can calibrate VTVMs, VOMs, 3½-, 4½- and most 5½-digit DMMs around, in a fraction of the time it takes you now! (It's a cal lab in a box! All at an average price under \$9,000.)

For \$10,000 to \$15,000, you could invest in an intricate maze of instruments that takes a wizard to operate. Or, you could fill a room with computer-based hardware and expensive talent. About \$100,000 worth.

### The Fluke $\mu$ P-controlled alternative.

We've designed the new 5100A and 5101A for production test, QA and cal lab applications that need large system flexibility at a fraction of large system cost.

The heart of our new meter calibrators is a microprocessor that eliminates mechanical switches—the largest contributor to failure in conventional calibrators.


And, you can enter your tolerances

in dB, volts or percent. The  $\mu$ P converts for you! For safety, store current or voltage limits and protect both your operator and the meter being calibrated.

Microprocessor control also facilitates scaling (for linearity checking), and makes your calibrator a *rangeless* instrument, always selecting the proper range for maximum resolution, *automatically!*

### Automation or economy? Fluke has both.

The 5100A is perfect for manual bench operation or integration into your existing cal system to upgrade it to Fluke standards of calibration



excellence. Priced at \$6,995\*, you save dollars but don't sacrifice accuracy or overall performance.

For perfection in automated calibration, you'll want the 5101A with its *mini-tape cassette reader*, a unique new feature that allows you to store up to 58 calibration settings, including limits and tolerances. Only \$8,995\*.

Both models have a friendly calculator-type keyboard. And, both have the RS232 or IEEE 488 system options you want for remote operation or hard-copy printouts of results.

Call (800) 426-0361, toll free. Ask for complete technical specs or the location of your local Fluke office or representative. Or, write: John Fluke Mfg. Co., Inc., P.O. Box 43210, Mountlake Terrace, WA 98043. In Europe: Fluke (Nederland) B.V., P.O. Box 5053, Tilburg, The Netherlands. (013) 673973. Telex: 52237.

\*U.S. price only.

## Command Performance: Demand Fluke Calibrators.




FOR LITERATURE CIRCLE 11

FOR DEMONSTRATION CIRCLE 12  
ELECTRONIC DESIGN 2, January 18, 1978



# How to connect with a mother board.



Here's connector versatility: straight in or right angle connection from wire harness or PCB.

Here's military airborne and aerospace quality with total interconnect capability, in eighteen sizes.

And in many variations of hardware and terminations including dip solder, solder cup, Wire Wrap\*, crimp removable, and flexible circuitry, all on .100 contact centers. The versatility of the AirBorn WTB-WTD series connectors offers flexibility in your design and total interconnect capability.

\*Wire Wrap is a registered trademark of Gardner-Denver.

**AirBorn, Inc.**

4321 AirBorn Drive Addison, Texas 75001 (214) 233-2000

CIRCLE NUMBER 270


# HYBRID



## OUR NEGATIVE 5-AMP ADJUSTABLE REGULATOR IS PUTTING A LOT OF 1-AMPS OUT OF WORK.

Throw away the shoehorn! It no longer takes five 1-amp voltage regulators and a handful of components to get to 5 amps. Which means you can get better specs. In less time. Using less room. At less cost.

And get this: The part that makes it all possible, a negative 5-amp adjustable voltage regulator, is available from Fairchild. A major hybrid supplier capable of high volume production.



### NOT JUST YOUR REGULAR REGULATOR.

Our  $\mu A79HG$  is a general purpose regulator capable of supplying in excess of 5 amps over a  $-24\text{ V}$  to  $-2.2\text{ V}$  output range. It has full thermal overload and short-circuit protection. It's packaged in a hermetically sealed 4-pin TO-3 package that provides 50 W power dissipation.

The regulator consists of a monolithic chip driving a discrete series pass element and short-circuit detection transistors. And that's not all. Our  $\mu A79HG$  needs no electrical insulator because its case is isolated.

ELECTRICAL CHARACTERISTICS:  $T_J = 25^\circ\text{C}$ ,  $I_{OUT} = -2.0\text{ A}$  unless otherwise specified

CHARACTERISTIC	CONDITION	MIN	TYP	MAX	UNITS
Input Voltage Range		-40		-7.0	V
Nominal Output Voltage Range	$V_{IN} = V_{OUT} - 5\text{ V}$	-24		-2.23	V
Line Regulation	$V_{IN} = -7\text{ V to } -40\text{ V}$		0.4	1.0	% ( $V_{OUT}$ )
Load Regulation	$V_{IN} = V_{OUT} - 10\text{ V}$ , $I_{OUT} = -10\text{ mA to } -5\text{ A}$		0.7	1.0	% ( $V_{OUT}$ )
Control Pin Current				3.0	$\mu\text{A}$
Quiescent Current	$V_{IN} = -10\text{ V}$			5.0	mA
Ripple Rejection	$V_{IN} = -8.5\text{ V to } -18\text{ V}$ $V_{OUT} = -5\text{ V}$ , $f = 120\text{ Hz}$		50		dB
Output Noise Voltage	$10\text{ Hz} \leq f \leq 100\text{ kHz}$ , $V_{OUT} = -5\text{ V}$			200	$\mu\text{V}$
Dropout Voltage	$I_{OUT} = -5\text{ A}$			2.0	V
Peak Output Current	$V_{IN} = -10\text{ V}$			8	A
Control Pin Voltage (Reference)	$V_{IN} = -10\text{ V}$	-2.35		-2.11	V

### SO MUCH FOR SO LITTLE.


With all this performance, you'd expect a large price tag. But our  $\mu A79HGKC$  costs only \$7.15 in quantities of 100. That's about 30% less than equivalent hermetic 1-amp regulators.

To find out more about our negative 5-amp adjustable voltage regulators (or any of our other hybrids), write or call your Fairchild sales office, distributor or representative today. Or, use the number at the bottom of this ad to call our Hybrid Products people direct. Fairchild Camera & Instrument Corp., 464 Ellis St., Mountain View, CA 94042. Tel: (415) 962-3771. TWX: 910-379-6435.

**FAIRCHILD**

**CALL US ON IT.  
(415) 962-3771**

# DESIGN BECKMAN CONVERTERS IN. DESIGN PROBLEMS OUT.



## Our new line is 8-bit microprocessor compatible with true 12-bit performance. And that's not just another line.

Presenting our new CMOS 12-bit DACs and ADCs. They're the first to offer complete 8-bit microprocessor compatibility. Real 12-bit accuracy. And CMOS or TTL logic compatibility, all in a single competitively-priced package.

They're exceptionally accurate, so put them to your toughest test. We did. And that's why we can guarantee  $\pm 0.012\%$  linearity over the full operating temperature range for each model in the 7545 or 7555 series. Gain and offset are also guaranteed over the full operating temperature range for the 7546 series. When you select 7546 DACs or 7556 ADCs with built-in reference and output buffers or comparators, gain and offset specifications are also guaranteed.

All series can operate in a serial or parallel mode. And they can be alternately switched from one mode to the other.

Both the DAC input registers and the ADC three-state output registers can accept either TTL logic levels using a +5 volt supply or CMOS logic levels using supply levels from +5 to +15 volts.


Simplify your 8-bit microprocessor interface. Put exceptional accuracy to work, and minimize your overall system error. Come to Beckman, the converter source. Call your local Beckman representative. To get his number, or immediate technical literature, call (714) 871-4848, ext. 1776. The price of designing accuracy in doesn't have to be out of hand.

# BECKMAN<sup>®</sup>

CIRCLE NUMBER 251

# Alternate Timebase Display

Gives you the whole picture for \$1425.\*



Continuous indication of where DELAYED T.B. measurements are taken.

- Eliminate BACK-AND-FORTH SWITCHING
- Forget MIXED-SWEEP limitations

The PM 3214 is the latest addition to the Philips oscilloscope family. At 25 MHz and 2mV sensitivity, the PM 3214 incorporates all the triggering facilities found on the latest, most expensive oscilloscopes available: AC, DC, TV and an auto position that derives its trigger from the peak to peak signal input. Trigger selection from either channel, line and external sources as well as composite triggering for ASYNCHRONOUS signals.

Composite triggering in A-B mode derives its source from the differential signal, allowing measurement of signals riding on high AC or DC components.

The 18.5 lb. portable is double insulated and even has an internal battery option. Supplied with two probes and a protective front cover, the PM 3214 is a money saving solution to many oscilloscope requirements.


If you don't need DELAYED TIMEBASE the economy priced PM 3212 has all the triggering and overall performance of the PM 3214 at only \$1,155.00\*.

For immediate detailed information utilize our toll-free Hotline number: 800 631-7172. (New Jersey residents call collect), or contact: Philips Test & Measuring Instruments, Inc.

In the U.S.:  
85 Mc Kee Drive  
Mahwah, New Jersey 07430  
Tel. (201) 529-3800

In Canada:  
6 Leswyn Road  
Toronto, Ontario, Canada M6A 1K2  
Tel. (416) 789-7188

\*U.S. Domestic prices only



# PHILIPS

# SGS-ATES PNP RF PRODUCT RANGE

The SGS-ATES range of silicon PNP devices for VHF/UHF offers the following specific advantages over well-established equivalent germanium types:




very low noise figure

higher linearity with low cross modulation distortion

higher power dissipation and maximum junction temperature

higher stability and reliability even under extreme environmental conditions

replaces germanium types directly pin-to-pin

Devices	Applications	$V_{CE0}$ (V)	$I_C$ max (mA)	$f_T$ (GHz)	$I_C$ (mA)	$V_{CE}$ (V)	$P_G$ (dB)	and	NF (dB)	$f$ (GHz)	Equivalent germanium types	Package
<b>BF479S</b>	Amplifier for PIN-Diode tuner	25	50	1.3	8	10	15	3.5	0.8	AF379		
<b>BF479</b>	High current VHF-UHF amplifier	25	50	1.4	10	10	18	3.5	0.8	AF279-AF367		
<b>BF679</b>	UHF AGC amplifier	35	30	1	3	10	15	3.5	0.8			
<b>BF679M</b>	UHF mixer-oscillator	35	30	1	3	10	15	4	0.8			
<b>BF679S</b>	Low noise UHF AGC amplifier	35	30	1	3	10	16	3	0.8			
<b>BF680A</b>	UHF mixer-oscillator	35	30	0.65	3	10	12	5	0.8			AF280-AF369
<b>BFT95</b>	Wide-band amplifier up to 1.5 GHz	15	50	5	15	10	12	2	1	AF106-AF306		
<b>BFT96</b>	Medium-power amp. up to 1.5 GHz	15	100	5	50	10	10	4	1			
<b>BFT95H</b>	Wide-band amplifier for hybrids	15	50	5	15	10	12	2	1		Lead formed T plastic	
<b>BF324</b>	VHF-FM tuner	35	30	0.4	1	10	-	3	0.1	AF109	TO 92	
<b>BF414</b>	VHF-FM Low noise	30	25	0.4	1	10	-	2	0.1			
<b>BF506</b>	VHF mixer-oscillator	35	30	0.4	1	10	17	2.5	0.2			
<b>BF509</b>	VHF AGC amplifier	35	30	0.7	3	10	18	2	0.2			
<b>BF272A</b>	UHF AGC amplifier	35	20	0.85	3	10	15	3.5	0.8	AF239	TO 72	
<b>BF316A</b>	UHF mixer-oscillator	35	20	0.6	3	10	12	5	0.8			
<b>BF516</b>	RF general purpose	35	20	0.8	3	10	12	4	0.8			
<b>BFR38</b>	VHF-UHF amplifier	35	20	1	3	10	14	3.5	0.8			
<b>BFR99</b>	Low cross-mod. VHF-UHF amplifier	25	50	2.3	10	15	10	3.5	0.8			



SGS-ATES Semiconductor Corporation - 79, Massasoit Street - Waltham, MA 02154 - Tel: (617) 891-3710 - Telex 923495 WHA.

Representatives: ARMATEL, Toronto (Canada) - BLACKBURN ASSOC., Dallas TX - BOYLE ASSOC., Reston VA - CERCO, San Diego CA - C.H. NEWSON & ASSOC. INC., Philadelphia PA - DYNE-A-MARK CORP., Clearwater FL, Ft. Lauderdale FL, Maitland FL - ELCOM INC., Englewood CO, Salt Lake City UT - FIAT ENGINEERING, Bellwood IL - GREINER ASSOC. INC., Grosse Pointe Park MI - HECHT, HENSCHEN & ASSOC., Phoenix AZ - IMTECH INC., Cleveland OH, Dayton OH - J-SQUARE MARKETING INC., Westbury NY - KEBCO, Maryland Heights MO - LATTROONICS MFG. REP., Indianapolis IN - LOREN F. GREEN ASSOC., Minneapolis MN - MEXEL, Mexico (Mexico) - NORTHMAR INC., Seattle WA - REP. INC., Huntsville AL, Jefferson City TN, Tucker GA, Raleigh NC - RICAL ASSOC., Santa Ana CA - S.F. FOSTER CO. INC., Pompey NY, Webster NY - SHAW-TECH INC., Mountain View CA - STONE COMPONENTS SALES, Needham MA

# Your new 1 MHz LC testing problem solver



## It's unbelievable at \$2685


**The new GR 1687 Megahertz Digibridge™ — microprocessor-based automatic LC measurement with keyboard control.**

You will find some exciting features that are really new in 1 MHz testing, like two test speeds; ten automatic limit comparison bins for sorting; continuous, average and single component test modes; operator selection of four different types of display; and a five full-digit readout for L and C.

Another important new feature. The microprocessor automatically compensates for any stray capacitance or inductance at the test probe tip or test fixture. Now, with no error factor at the DUT connection, you're going to obtain a new kind of reliable and consistent testing accuracy. A further plus. The DUT connection is Kelvin.

- **Automatically measures Ls & Q, Cs & D, Cs & Rs, Cp & Gp**
- **0.1% Accuracy for C**  
**0.2% Accuracy for L**
- **Autoranging** takes the guesswork out of setting the proper range.
- **IEEE 488 bus option:** provides both IEEE 488 interface and autohandler output for a handler, printer or bench-top calculator system.
- **10 Bins for sorting.** Set any symmetrical (e.g.:  $\pm 1\%$ ,  $\pm 5\%$ ) or asymmetrical (e.g.:  $-20\% + 80\%$ ,  $-30\% + 10\%$ ) limits you desire.
- **Two test speeds** to suit every testing application.
- **Three test modes:** select continuous, average (displays average value of 10 measurements), or single.
- **Four types of display:** programmed bin limits, measured values, deviation measurement ( $\Delta L$  or  $\Delta C$ ), or bin number.

- **Five full-digit display** for L and C. Four full-digit display for Q, D, R and G. All numbers go to 9.
  - **Wide measurement values** allow you to test a greater number of component types. Test L from 00.001 to 99999  $\mu\text{H}$ ; C from 00.001 to 99999 pF, Q from 00.01 to 999.9, D from .0001 to 9.999, R from 00.01  $\Omega$  to 999.9 K $\Omega$ , and G from 00.01  $\mu\text{S}$  to 999.9 mS.
  - **External bias** from 0 to 60 V can be supplied.
  - **Optional Kelvin test fixture** tests radial and axial lead components.
  - **Automatic self-check/diagnostics** on power-up.
- The GR 1687 represents a new era in 1 MHz testing. Contact your GenRad sales office.







 **GenRad**

300 BAKER AVENUE, CONCORD, MASSACHUSETTS 01742 • ATLANTA 404 394-5380 • BOSTON 617 646-0550  
CHICAGO 312 884-6900 • DALLAS 214 234-3357 • DAYTON 513 294-1500 • LOS ANGELES 714 540-9630 • NEW YORK (NY) 212 964-2722,  
(NJ) 201 791-8990 • SAN FRANCISCO 408 965-0662 • WASHINGTON, DC 301 948-7071 • TORONTO 416 252-3395 • ZURICH (01) 55 24 20

# SGS-ATES NPN RF PRODUCT RANGE

SGS-ATES production includes a variety of RF NPN silicon transistors, as shown in the following table. Some of these products, which are intended for well-established solutions, are second sourced by SGS-ATES. In addition, constant research and development provide a steady flow of new products for new and more sophisticated applications. The latest of these new products is the BFW 94 for ultralinear wide band applications up to 1.5 GHz.

Devices	Applications	V <sub>cb0</sub> (V)	L <sub>V<sub>ce0</sub></sub> (V)	I <sub>c max</sub> (mA)	f <sub>T</sub> (GHz)	I <sub>c</sub> (mA)	V <sub>OE</sub> (V)	P <sub>G</sub> (dB)	NF (dB)	f (GHz)	Package
<b>BFW92</b>	Wide band amplifier	25	15	50	1.6	25	5	16	4	0.5	
<b>BFR90</b>	Wide band amplifier up to 1.5 GHz	20	15	25	5	14	10	19.5	2.4	0.5	
<b>BFR90A</b>	Wide band amplifier up to 1.5 GHz	20	15	25	5	14	10	13.5	2.2	1	
<b>BFR91*</b>	Wide band amplifier up to 1.5 GHz	15	12	50	5	30	5	16.5	2	0.5	
<b>BFR96*</b>	Medium power amplifier up to 1.5 GHz	20	15	100	5	50	10	16	3.3	0.5	
<b>BFW94</b>	Ultralinear wide band amplifier	25	20	200	3	80	7.5	14	5	0.5	4 leads, plastic
<b>BFR36</b>	Ultralinear CATV-MATV output	40	30	200	1.4	70	15	16	4	0.2	
<b>BFW16A</b>	Ultralinear CATV-MATV output	40	25	200	1.4	70	15	16	5	0.2	
<b>BFW17A</b>	Ultralinear CATV-MATV output	40	25	200	1.3	70	15	16	6	0.2	
<b>2N3866</b>	VHF-UHF power amplifier and oscillator	55	30	500	1	50	15	10	—	0.4	
<b>2N4427</b>	VHF-UHF power amplifier and oscillator	40	20	500	1	50	15	—	—	—	
<b>2N5109</b>	Ultralinear CATV-MATV output	40	20	200	1.3	50	15	16	3	0.2	
<b>BFX89</b>	Wide band amplifier	30	15	50	1.2	25	5	12	6.5	0.5	
<b>BFY90</b>	Wide band amplifier	30	15	50	1.4	25	5	13	5	0.5	
<b>2N918</b>	Amplifier and oscillator	30	15	50	0.8	4	10	21	5	0.2	
<b>2N2857</b>	VHF-UHF amplifier	30	15	50	1.2	5	6	16	3.8	0.45	
<b>2N3600</b>	VHF amplifier	30	15	50	1	5	6	22	4	0.2	
<b>2N3839</b>	Low noise UHF-VHF	30	15	50	1.4	5	6	17	3	0.45	
<b>2N5179</b>	VHF-UHF amplifier	20	12	50	1.4	5	6	21	3	0.2	

\*Available in 1977



SGS-ATES Semiconductor Corporation - 79, Massasoit Street - Waltham, MA 02154 - Tel. (617) 891-3710 - Telex 923495 WHA.

Representatives: ARMATEL, Toronto (Canada) - BLACKBURN ASSOC., Dallas TX - BOYLE ASSOC., Reston VA - CERCO, San Diego CA - C.H. NEWSON & ASSOC. INC., Philadelphia PA - DYNE-A-MARK CORP., Clearwater FL - Ft. Lauderdale FL - Maitland FL - ELCOM INC., Englewood CO - Salt Lake City UT - FIAT ENGINEERING, Bellwood IL - GREINER ASSOC. INC., Grosse Pointe Park MI - HECHT, HENSCHEN & ASSOC., Phoenix AZ - IMTECH INC., Cleveland OH - Dayton OH - J-SQUARE MARKETING INC., Westbury NY - KEBCO, Maryland Heights MO - LATRONICS MFG. REP., Indianapolis IN - LOREN F. GREEN ASSOC., Minneapolis MN - MEXEL, Mexico (Mexico) - NORTHMAR INC., Seattle WA - REP. INC., Huntsville AL - Jefferson City TN - Tucker GA - Raleigh NC - RICAL ASSOC., Santa Ana CA - S.F. FOSTER CO. INC., Pompey NY - WEBSTER NY - SHAW-TECH INC., Mountain View CA - STONE COMPONENTS SALES, Needham MA



# Miproc 16-AS, micropower to give you high-speed faster.

Internationally acclaimed Miproc-16 with a compute-rate of up to 4 million instructions per second is the fastest 16-bit microcomputer card family available.

Now supplied with an OEM chassis package, Miproc-16 is even more quickly brought into action.

This cost-effective application system, named Miproc-16 AS, has room for one, two or even three Miproc-16 CPU's. Smartly styled and equipped with add-in 13-slot card bay modules, fans and power supply, this new OEM chassis package eases the way into high speed microcomputing.

## Instruction Power

Up to 170 instructions including multiply/divide and bit manipulation give Miproc-16 formidable processing capability.

## 16-bit Power

16-bit program words make programming easy. 16-bit data words maintain high precision in arithmetic operations.

## Addressing Power

16-bit dual memory architecture gives 65k words of directly addressable program memory *and* 65k words of data memory with 8 powerful address modes.

## Interrupt Power

Multilevel, priority vectored interrupt system handles context changes in less than 2 microseconds.

## I/O Power

256 directly addressable I/O channels with data I/O rates of up to 1.7 megabytes/sec. under program control, and up to 20 megabytes/sec. for DMA.

## High Speed Processing Power

The unique dual memory architecture combines with high speed Schottky TTL technology to execute most instructions in a single machine cycle.

## Software Power

Easy to use cross-assemblers for mainframe or minicomputer make programming faster, *and* PL-MIPROC, a super-efficient high level assembly language.

## Hardware Power

Comprehensive range of processor, memory and interface cards backed up by sophisticated hardware development aids.

## Ruggedized Power

Miproc can be configured to meet any known military specification.



**PLESSEY  
MICROSYSTEMS**

Plessey Canada  
300 Supertest Rd.  
Downsview, Ontario  
Canada M3J 2M2

Tel: (416) 661-3711

Phil Burnley  
Plessey Microsystems  
1641 Kaiser Avenue  
Irvine, Calif. 92714, USA

Tel: (714) 540-9931

David Garrison  
Plessey Microsystems  
Suite 408, 11141 Georgia Avenue  
Wheaton, Maryland 20902, USA

Tel: (301) 949-1664



CIRCLE NUMBER 256


CIRCLE NUMBER 257 ►




# SGS-ATES RF COMPLEMENTARY PAIRS

SGS-ATES experience in RF silicon technology enables electronic circuit designers to employ optimally matched complementary NPN/PNP devices, reducing the number of inductors and transformers in the RF amplifier stage and allowing advanced solutions in UHF and microwave applications; crossmodulation and second order intermodulation products are minimized to meet the requirements of today's CATV/MATV systems.

PNP	NPN	Applications	Package
<b>BFR99</b>	<b>BFY90</b>	Low noise VHF-UHF wide band amplifier	TO 72 
<b>BFT95</b>	<b>BFR90</b> <b>BFR90A</b> <b>BFR91</b>	Low noise wide band amplifier up to 1.5 GHz	T plastic 
<b>BFT96</b>	<b>BFR96</b>	Driver or output stage for wide band amp. up to 1.5 GHz	



The chart shows that the SGS-ATES range of complementary RF transistors can cover all MATV/CATV and telecommunications applications.




PNP  
NPN



SGS-ATES Semiconductor Corporation - 79, Massasoit Street - Waltham, MA 02154 - Tel. (617) 891-3710 - Telex 923495 WHA

Representatives: ARMATEL, Toronto (Canada) - BLACKBURN ASSOC., Dallas TX - BOYLE ASSOC., Reston VA - CERCO, San Diego CA - C.H. NEWSON & ASSOC. INC., Philadelphia PA - DYNE-A-MARK CORP., Clearwater FL, Ft. Lauderdale FL, Maitland FL - ELCOM INC., Englewood CO, Salt Lake City UT - FIAT ENGINEERING, Bellwood IL - GREINER ASSOC. INC., Grosse Pointe Park MI - HECHT, HENSCHEN & ASSOC., Phoenix AZ - IMTECH INC., Cleveland OH, Dayton OH - J-SQUARE MARKETING INC., Westbury NY - KEBCO, Maryland Heights MO - LATRONICS MFG. REP., Indianapolis IN - LOREN F. GREEN ASSOC., Minneapolis MN - MEXEL, Mexico (Mexico) - NORTHMAR INC., Seattle WA - REP. INC., Huntsville AL, Jefferson City TN, Tucker GA, Raleigh NC - RICAL ASSOC., Santa Ana CA - S.F. FOSTER CO. INC., Pompey NY, Webster NY - SHAW-TECH INC., Mountain View CA - STONE COMPONENTS SALES, Needham MA



## **“THE GOLD BOOK IS ACCURATE, WELL RESEARCHED, AND COMPLETELY UP TO DATE”**

... says Kenneth B. Boothe, Senior Sales Engineer, Microdyne Corporation.

Apparently Mr. Boothe is camera shy, but he set his copy of the GOLD BOOK on top of some of Microdyne's equipment and sent us the photo to make his point:

**“As part of my sales activities at Microdyne, I receive many requests from our foreign sales representatives to provide them with U.S. manufacturing sources for various items we do not supply that can be used in RF Telemetry and Satellite Earth Terminal Systems. With this information, our representatives and their customers are often able to put together complete systems meeting specific requirements at minimum cost. At the same time, the probability of selling our system-interfaced receivers is considerably enhanced.**

**“When responding to requests of this type, I find the GOLD BOOK to be extremely helpful in locating specific manufacturers who might otherwise be difficult and time consuming to find. Furthermore, I have yet to receive a manufacturing source request that I have been unable to locate in the GOLD BOOK. Your publication is accurate, well researched and completely up to date. I highly recommend it as a standard reference.”**

**Kenneth B. Boothe  
Senior Sales Engineer**

**MICRODYNE  
CORPORATION**

# When a masterpiece is shown, the reasons it is one, often times aren't apparent.

ROSITE® moldings are presently being used by thousands of engineers in many innovative and masterful designs. Inside this XEROX 3100 copier there are 12 different ROSITE glass polyester moldings. They replace die-cast aluminum and other metal fabrications effecting economy and weight reduction helping make the 3100 copier a better product.

Each ROSITE molding was selected for a combination of reasons: dimensional accuracy (tolerances to  $\pm .0005$  per inch) to eliminate machining—dimensional stability (creep resistance) at elevated temperatures and wear resistance through millions of cycles to assure long life—plus electrical insulation properties and a UL flammability rating of 94V-0.

Perhaps we can help you realize some of your ideas, too.

**This concept of replacing metal with ROSITE works in many areas.**



## Rostone Corporation

2729 South Concord Road • Lafayette, Indiana 47902 • 317/474-2421

**CUSTOM ENGINEERED PLASTIC MOLDINGS**

XEROX® and 3100® are trademarks of Xerox Corporation.

# Elastoplastic silicone resin. The conformal coating with imagination.

When you want a conformal coating that's more than a coating, use Dow Corning® R-4-3117 elastoplastic silicone. It lets you expand your imagination for improving and protecting your product's performance.


## Strong and flexible.

Elastoplastic silicone helps your product take abuse from tough environments. And it gives, without giving in. This smooth, hard, clear coating also keeps your product clean by resisting dirt pickup.

## Works well, hot or cold.

When you need a coating that takes the heat (up to 390 F/200 C), puts up with the cold (down to -85 F/-65 C), or both—elastoplastic silicone won't disappoint you.





**Keeps out moisture.**

Because moisture permeability is extremely low, water or humidity won't spoil your product's performance.



**Repairable.**

Unlike some conformal coatings, ours lets you make repairs to your product. All or part of the coating can be removed to get to a problem area. After it's fixed, just re-apply the coating.



**Excellent dielectric stability.**

Elastoplastic silicone keeps its dielectrics from power through microwave frequencies. Even in high-humidity application.



**Three easy ways to use.**

Apply elastoplastic silicone the way you want. Brush, flow coat, or dip it on. As thin or thick as you need. For thicker films, you simply recoat it.

And choose the noncorrosive cure to match your process. At room temperature or under heat acceleration.

**Try some.**

By now, you've probably already imagined places you could use this versatile conformal coating. And you're sure to think of more.

That's why we'd like you to try some for yourself. For samples or complete product information on Dow Corning elastoplastic resin coating, fill out and mail the coupon below.

I want to see how I can benefit from elastoplastic silicone resin.

- Send complete product literature.
- I'd like to talk to a sales representative about getting a sample for evaluation.

Name \_\_\_\_\_  
 Title \_\_\_\_\_  
 Company \_\_\_\_\_  
 Address \_\_\_\_\_  
 City \_\_\_\_\_ State \_\_\_\_\_ Zip \_\_\_\_\_  
 Telephone \_\_\_\_\_

Mail to: Dow Corning Corporation,  
Dept. B-7539,  
Midland, Michigan 48640.

**DOW CORNING**


DOW CORNING

# When you're small you've got to be tough to last.

This rugged little  $\frac{1}{8}$ -watt fixed resistor (.145 L x .062 D) is hard to beat in durability. It's the Type BB... part of a family that has passed nearly 800 million unit test hours without a single failure. It's small enough to be mounted on .300 by .100 hole centers, eight in the same space as one dual in-line package. It takes transient pulses that would knock out most any film resistor of similar dimensions. Performance is exceptionally consistent from one resistor to the next. We have the space-saving resistors you need. Our distributors have them when your need is now.

## *Tough, high reliability*

Proved in nearly 800 million unit test hours without failure.




## *Pulse handling*

characteristics offer outstanding protection against transient surges.

## *Low TCR*

typically less than 200 PPM over normal operating temperature range of +15°C to +75°C.



## Quality in the best tradition.



**ALLEN-BRADLEY**  
Milwaukee, Wisconsin 53204

CIRCLE NUMBER 260

CONTACT YOUR  
ALLEN-BRADLEY DISTRIBUTOR OR  
WRITE TO ELECTRONICS DIVISION

EC146

# Industry asked us for hundreds of variations of these switches. Evidently we're pushing the right buttons.

And we intend to keep pushing them.

So that every time one of your new ideas creates a design problem, MICRO SWITCH will be ready with the miniature manual switch that solves it.

At last count, we offered hundreds.

The Series 8 lineup of miniature manuals includes toggles, pushbuttons, paddles and lighted or unlighted rockers. They're UL listed at 6 amps, 125 VAC. And every one is available in a low energy version as well.

Choose terminal variations ranging from solder to quick-connect to PC board or wire wrap. There's also a choice of panel and bushing-sealed pushbuttons and toggles. And non-threaded bushings on PC mounted toggles. Even colored sleeves and integral colored tips for the toggles.

And of course, you'll find one feature you won't find anywhere else—the quality you've come to expect from MICRO SWITCH. Series 8 switches are inspected to a 1% Acceptable Quality Level (AQL).

That's quality you can put your finger on.


For your immediate product needs, see your nearest MICRO SWITCH Authorized Distributor. If you have other requirements, contact a MICRO SWITCH Branch Office or call 815/235-6600.

## MICRO SWITCH

FREEPORT, ILLINOIS 61032  
A DIVISION OF HONEYWELL

MICRO SWITCH products are available world-wide through Honeywell International.


CIRCLE 150 FOR DATA



**MEPCO/ELECTRA**

**GPR 5000X**

**RESISTOR...  
ONE SIZE  
ONE STYLE**



**For all general purpose applications**

Until now, buying General Purpose resistors meant trading off one requirement to get another—buying 2 or more styles to cover your resistance requirements—giving up board space to get more power dissipation.

**MEPCO/ELECTRA'S GPR 5000X** has changed all that. Now you can get everything you need for all your general purpose applications — automotive, consumer, computer—in just one resistor style, one resistor size. Reduce your resistor inventory.

**MEPCO/ELECTRA GPR 5000X:**

**DUAL RATED**— $\frac{1}{4}W$  &  $\frac{1}{2}W$ .

One resistor can be used in both  $\frac{1}{4}$  and  $\frac{1}{2}W$  applications, which means dual power handling capability in the smallest possible size.

**BROADER RESISTANCE RANGE**—  $10\Omega$  to  $22M\Omega$

Widest resistance range for any resistor with comparable tolerance and T.C.'s.

**REPLACES RL07 AND RL20**—

Perfect replacement for both these MIL styles with the added plus of a broader resistance range, dual rated ... and at a better price.

**CWV**—350V Max.

**STANDARD TOLERANCE**—2%

**STANDARD T.C.**— $\pm 200$  PPM

In the market for a true general purpose resistor that offers "trade-ups" rather than "trade-offs"? Find out about GPR 5000X. For more information ... "Call M/E" at (817) 325-7871. Or write **MEPCO/ELECTRA Inc.**, P.O. Box 760, Mineral Wells, Texas 76067.



CIRCLE NUMBER 15



JANUARY 18, 1978

## E-beam + X-ray litho = high-density circuits

By combining both E-beam and X-ray lithography processes, engineers at Rockwell International's Electron Devices Group expect to solve production problems encountered with the high-density fabrication methods—resolution, processing speed, and resist composition, for starters.

Although either technique can be used to obtain very fine line widths, E-beam techniques by themselves would just take too long to mass-produce wafers, says George Pulliam, Director of Physical Sciences at the Anaheim-based facility. However, E-beam techniques do offer the flexibility of being able to alter the pattern being drawn on the fly—different adjustments can be made on the same wafer under computer control of the electron beam.

Soon, the E-beam process will be used to make a master pattern and then X-ray processing along with a step-and-repeat sequence will generate a complete wafer mask from the master. At this point, however, this combined technology isn't ready to be applied to a production line.

Right now the resists used on the

wafers are too slow or don't have the necessary resolution. Development speed of the resist must go up so that exposure time for the wafer can go down. The shortened exposure time will result in less harm to the semiconductor material, which can be irreparably damaged by E-beam and X-ray bombardment.

As the devices on chips get smaller, speed increases and power decreases. But that isn't all. Certain "edge effects" and threshold voltages are becoming more of a factor in device design. In some of the large devices of, say, a year or two ago the effects could be ignored. To handle new factors such as these, new device models will have to be developed so that performance predictions can be made more accurately before sample devices are made.

Still, work on the E-beam/X-ray process has reached the point where a 4-megabit magnetic-bubble memory on a single chip is considered feasible for late 1978 or early 1979 production. The chip is expected to be about 0.4 in.<sup>2</sup> and have a serial data transfer rate of about 0.5 MHz.

## IC flowmeter measures blood in two directions

A totally implantable pulsed-Doppler blood-flowmeter is the first to measure blood-vessel diameter and bidirectional flow. But it wouldn't have been possible without IC chips to hold the Doppler electronics.

Like pulsed-Doppler radar, the ultrasonic system, designed at Stanford University's Integrated Circuits Laboratory, in Palo Alto, CA, telemeters both velocity and range information. It uses range data to measure diameter and volume flow as well as blood-velocity profiles. Bidirectional velocities are shown at 16 points along the vessel's inner diameter.

Bidirectionality is needed because blood flow may reverse during part of

each heart cycle and turbulence may cause local reversals at other times. Ultimately, the tiny unit may be implanted in an unborn lamb to provide new information on fetal heart functions—up to and even during birth.

Designed to transmit data on command for six months or more, the implantable system consists of four packages connected by Teflon-covered wires: Doppler electronics, a transducer, a battery and an output-data coil (antenna).

The Doppler electronics, with over 200 linear circuit components on two 3-mm-square custom IC chips, has only eight discrete parts. Mounted on a hybrid substrate in a hermetic can and

encapsulated, they occupy only  $2.9 \times 3.8 \times 0.8$  cm.

"This pulsed Doppler design is so complex, it would have been impossibly bulky without custom ICs and hybrid interconnect," says Dr. James Knutti, co-designer of the system. One Doppler IC generates the pulsed 6-MHz ultrasonic signal and quadrature reference signals; the other receives the Doppler-shifted signal, compares it to the references, and outputs pulse-delay and difference-frequency data to external electronics via the data coil.

Sutured against the side of a vessel, the transducer, a 3-mm-square lead-titanate-zirconate crystal, sends and receives the 25-kHz pulses of 6-MHz ultrasound.

To extend the operation of the 50-hour battery, an external rf burst turns power on. After a preselected 1-to-5 minute interval of 20-mW operation, two oscillator/counter chips encapsulated with the battery turn the power off again.

## CRT brightness boosted by tweaking gun design

A 20 to 40% increase in the brightness of an electrostatic CRT display—with no loss of resolution—has been achieved by optimizing element lengths and aperture positions and diameters in the CRT's electron gun. This higher brightness not only improves visibility in high-ambient lighting, but also increases the separation between displayed shades of gray, a feature needed in diagnostic medical ultrasound and nondestructive-testing displays.

The improvements, developed at Hewlett-Packard Co.'s Colorado Springs Division, are achieved "through a rigorous application of generally accepted ray-tracing theory and equations that don't involve any modifications in classical electron lens theory," says product manager Art Porter. Computer-aided design techniques yielded a CRT electron gun with very few stray electrons. The electron lens increases brightness by focusing more electrons on the correct spot on the screen.

Two versions of the new CRT will be available next month in HP's Model 1332A display unit. A standard version, which will cost the same as the 1332A and previous CRT, \$1400, maintains the present spot size of 0.3 mm, but with a 20 to 40% increase in brightness. An even brighter version,

the Option 530, adds \$75 to the price tag, and is two and a half times brighter than the CRT currently in the 1332A, but with only a 10 to 15% increase in spot diameter. With a spot size of 0.38 mm, this Option 530 has a specified brightness of 500 cd/m<sup>2</sup> (about 150 foot-Lamberts) at 2.5-mm/ $\mu$ s writing speed and a 60-Hz refresh rate.

In the other version, the CRT's beam current is to three times greater than for existing designs, with no increase in accelerating voltage, power consumption, or circuit complexity.

CIRCLE NO. 319

## Alarm clock wakes you up—and puts the coffee on

The most flexible "alarm clock" yet not only gets you up but turns home appliances on or off at preset times. Up to 100 line-powered appliances such as coffee makers, lights, engine-oil heaters and hi-fi systems can be handled by a central-control console via coded pulses riding on the ac line.

The Coby 1 home control center from Energy Technology Inc., Las Cruces, NM, is built around an Intel 8085 microprocessor. It can be programmed to turn equipment on or off at times that can be set up to 11 months in advance.

The control center sends coded pulses over house wiring to remote switches that go between plug-in appliances and wall sockets. In a few months, Energy Technology expects to have remotes to replace wall switches and other remotes to handle built-in equipment such as water heaters and air conditioners. Each remote will have a unique address.

Programs are entered, stored, and modified through 12 function and control keys, a 10-key numeric pad, and AM and PM keys. As commands are entered, a display lights up to confirm. The display can also review commands already stored in memory.

The display reads out year, month, day, hour, minute and second with an accuracy to five seconds per month. The calendar is preprogrammed to show the correct date until 2021.

Along with control, power supply, coding and signal-generating circuitry, the control console contains 2048 words of RAM and 2048 bytes of ROM. A rechargeable battery will keep the clock and other memory circuits working during a blackout. The battery, which recharges whenever the control console is plugged in, also allows the console to be unplugged and moved

without losing memory contents.

The suggested retail price for the Coby 1 control console is \$450, and each remote is \$45. But until the end of February, one console and one remote will go for \$399.

## Packet-switched data transmitted by radio

Packet switching, a data-communications technique usually involving copper wires or optical fibers, has taken to the airwaves. A system of packet-switched radio data links using microprocessors to route tactical messages from one mode to another has been developed to enhance tactical radio communications for military field operations. Both fixed base and mobile units can participate in the network developed by the Collins Telecommunications Div. of Rockwell International in Dallas, TX.

Packets of data with identifying headers and error-correcting trailers are broadcast from a main station and routed independently and asynchronously throughout the system. Actual transmission is spread over a wide band of frequencies to provide special safeguards against jamming and eavesdropping.

Rockwell is developing the packet-switched radio-communications system for the Advanced Research Projects Agency. So far, 28 packet radios have been built for ARPA and are being evaluated by Stanford Research Institute.

## PCBs get broken up by electron 'bullets'

How do you get rid of the toxic effects of polychlorinated biphenyls? Until recently, with great difficulty. Now, researchers at the Massachusetts Institute of Technology have discovered that high-speed electron bombardment—about 10 kilorads—significantly alters the composition of PCBs or other toxic organic compounds in water, and prevents the toxic material from building up in the food chain.

"The high-speed electrons are like bullets," according to Dr. Edward W. Merrill, professor of chemical engineering at MIT. "When they hit the water molecule, it splits into very active fragments, one of which is called the hydroxyl radical. This radical attaches itself to the trace organic compound—such as the PCB—and transforms it into a molecule, like alcohol,

which has a hydroxyl group that makes it water soluble."

PCBs are widely used as cleaning fluids for PC boards and other hardware, in electrolytic capacitors and in transformers for insulation and cooling. They are persistent toxic agents—in other words, they degrade extremely slowly in the environment and exist in water or animal tissue for a long time.

The MIT researchers also found that electron bombardment doses of about 400 kilorads may obliterate PCBs in sludge. But more experiments are needed, they point out, because the makeup of sludge varies from day to day—even from hour to hour—at any given location.

## Problem studies aimed at microwave solar energy

Two studies are being conducted to determine the negative or harmful effects of transmitting solar energy in the form of microwaves to earth stations, which would convert them into electricity. Both studies are being handled by Battelle Memorial Institute's Pacific Northwest Laboratories, Richland, WA, at the request of the Dept. of Energy and NASA.

The microwave transmissions would come from a proposed series of satellites in stationary orbits around the earth. Solar energy, caught above the earth's atmosphere would be converted into microwave energy on the satellites. Researchers have calculated that 20 to 25 satellites could have provided all of the United States' power needs in 1975.


But what problems would crop up with these microwave transmissions? One Battelle study group will try to find out if any electromagnetic or radio interference trouble would stem from such transmissions. The other group will try to uncover any potential harmful effects on the earth's environment. All work is expected to be completed by September, 1978.

## R & D spending up in '78

National spending on research and development will reach \$44.1-billion this year, according to Battelle Columbus Laboratories, Columbus, OH. That's an increase of \$3.3-billion, or 8%, over National Science Foundation estimates for 1977, but the Ohio research group says the increase will be entirely swallowed up by inflation and represents no real growth.

# DP Dialogue

Notes and observations from IBM that may prove of interest to the engineering community



## Terminal Stands the Heat at Ford Steel

Computer equipment has now moved right up to the mouth of the fiery furnace. At River Rouge, Ford Motor Company's sprawling complex of industrial plants in Dearborn, Michigan, IBM 5937 Industrial Terminals adjacent to

two huge steelmaking units — a basic oxygen furnace and an electric furnace — guide operators in the crucial step of measuring alloying ingredients into the molten metal. Because the 5937 is tolerant of extreme heat, vibration and

*Steel from the basic oxygen furnace at Ford is poured into ingot molds. An IBM 5937 Industrial Terminal helps the furnace operators control the amount of costly alloying materials they add during the heat.*

corrosive atmosphere, it can be installed where no ordinary computer terminal would work for long.

Ford Steel Division makes and processes over 10,000 tons of steel a day. In its completely integrated River Rouge facility, the division smelts ore and performs a wide variety of steel-making and finishing operations. An online computer tracks every slab of steel from the furnace right up to shipment to the customer, using data acquired through sensors in the processing machinery.

### Closing the Loop

The two IBM 5937 Industrial Terminals close the loop from the metallurgical laboratory back to the furnace operators. The loop begins at the furnace, where a small sample of the molten steel is drawn and sent to the laboratory — in another building — through a pneumatic-tube delivery system. The lab promptly analyzes the sample, and the results pass automatically from the analytical instruments to the IBM System/370 Model 148.

"When the operator is ready to add alloying ingredients," explains Earl O'Shaughnessy, general superintendent of basic oxygen furnace melting operations, "the computer flashes a chemical analysis to him that shows just how much of each additive to use."

It is this analysis that tells the furnace operator how much manganese, aluminum, carbon, silicon or other alloying material must be added to make the type of steel required of each melt.

"Before we had the 5937 terminals, the operators had to walk to a typewriter terminal in a protected environment some distance away to see the analysis," O'Shaughnessy says. "Or, if time was short, they simply added excessive amounts of these costly materials, to make sure the specifications were met."

"Putting a rugged terminal like the 5937 right out on the floor with the operators has meant significant direct dollar savings in steelmaking costs."

# CADAM<sup>®</sup>: Interactive Graphics for Design Engineers

Producing a modern aircraft can require more mechanical drawings than rivets.

Traditionally, engineers sketch, then draftsmen draft. Then engineers discover needed changes or improvements, and draftsmen draft some more. A lot more. Move a stiffener or bracket, say, two inches to the left, and a chain reaction of changes ripples through the entire set of drawings.

But now the computer has opened up a new way to meet design engineering needs with speed and reliability for a broad range of products, from high-performance aircraft to complex integrated circuits. Computer-Graphics Augmented Design and Manufacturing (CADAM), a set of interactive programs available from IBM, allows the designer to sketch directly on the screen of a graphic terminal. He defines lines and contours by pressing keys and positioning a light pen, and the computer displays what he has expressed.

Curve fitting, or reducing the design to a set of control equations, is completed iteratively at the terminal, eliminating coding, card punching, and repeated computer batch runs. Then CADAM converts the preliminary design to a dimensioned drawing with auxiliary views.

If something needs fixing — if, for example, the dimensioned drawing reveals a problem of component or subassembly compatibility — the pieces can be moved around with the light pen and CADAM will revise all of the affected drawings. And do it automatically.

® CADAM is a trademark of Lockheed—California Corp.

CADAM encourages doodling, an important source of design inspiration. The user can translate or rotate any graphic element. Or change its scale. Or stack parts, separate them, or watch moving parts move.


CADAM stores the design as it is developed, displays any element on demand, then generates the final detailed drawings. It supports complete design of the part, including structural members and such elements as ribs, stiffeners, lightening holes and fasteners. Once a design is stored in the system, CADAM analysis programs can calculate its weight or determine its structural properties. Any frequently used design element or drawing symbol can be stored and reproduced automatically wherever it is needed.

As its name implies, CADAM includes a direct link to manufacturing. It can generate a "part program" (path of travel) for the cutter of an automatic machine tool.

CADAM has cut drafting manhours drastically for engineering departments — by as much as 90 percent or more on a few special tasks. It helps prevent and correct errors and improves the quality of the engineering product. One user's experience is described below.

## Productivity Up

Northrop Corporation is one of the world's largest manufacturers of high performance jet aircraft. Today, Northrop engineers design complex aircraft parts with CADAM in a fraction of the time once spent at drafting boards.



*CADAM converts freehand sketches, made directly on the CRT screen with a light pen, into fully defined and dimensioned graphics.*

Says Northrop's Aaron Feder: "In addition to the time savings, we can identify improvements in design quality. Because changes are so easy to make at a CADAM terminal, we can keep up with changes traditionally required during the design development of an aircraft part and still release the drawing on time." Feder is manager of technical computer graphics at Northrop's Aircraft Division in Hawthorne, California.

"Before installing CADAM," Feder points out, "we ran a number of carefully controlled tests. When we saw productivity gains ranging from four to one to as high as 17 to one, for changes to a drawing, we saw the potential for CADAM and decided to adopt it."

"We compared the manhours required to prepare several types of drawings using CADAM with the time requirements using our established manual systems.

"This involved a broad sampling of different types of drawings, including layouts, structural and electrical drawings. We saw productivity gains of four to one or better on every one of 14 test problems. Even though productivity is lower in the hectic, day-to-day development design world, CADAM has still proven cost-effective.

"Once a tentative design is in the computer," Feder adds, "we can run CADAM engineering analyses: calculating weights and determining the capabilities of the design aircraft and the dynamic behavior of its structure.

"The data required for this kind of analysis is already in our System/370 as a byproduct of the graphic design effort. That means another major savings in manhours, the elimination of a significant source of error, and the assurance that all departments are working from the same data."



*Engineers at Northrop Corp. use computer graphics to speed the structural design of high-performance jet aircraft.*

# Fast Answers to Tough Energy Questions

"Suppose the government made major changes in national energy policy," speculates Prof. John J. Donovan of MIT. "What would be the economic impact on each region of the U.S.? How would the economy change if the fuel supply were to be altered? If prices were to change? What effective actions can be taken by homeowners, industry and public policymakers?"

To help provide prompt answers to such questions, the Generalized Management Information System (GMIS) was jointly developed by IBM, MIT Sloan School of Management and the MIT Energy Laboratory. IBM provided staff support and the use of a System/370 Model 158 at its Cambridge Scientific Center. GMIS has been used to analyze conservation strategy in, for example, the consumption of energy for residential heating across the United States. And it has been used to produce programs and a data base for energy policy analysis in New England. Called the New England Energy Management Information System (NEEMIS), this application was developed through a collaborative effort among MIT, the New England Regional Commission (a Federal-New England states partnership) and IBM.

What can the homeowner do? According to Donovan, an associate professor at the Sloan School: "An econometric model shows that, for a homeowner in the Northeast or upper Midwest, a thermostat setting of 65 degrees (daytime) and 55 at night—or 63 around the clock—will save 15 percent of his energy costs.

"Other computer models produced using GMIS suggest measures for commercial buildings. For some institutions in the Boston area, these models identified ways to reduce energy costs by 40 percent (of which 20 percent required no capital improvements).

"To answer questions like these," he continues, "the Energy Laboratory has



*Most homeowners today want to keep warm without wasting energy. At MIT, computer simulation has shown that a 24-hour thermostat setting of 63 degrees saves as much fuel as a night setting of 55 degrees.*

collected data and computer programs from government research, professional and technical groups, and university research efforts. A user can scan the data base interactively to locate and define the needed data and select a suitable modeling system.

"GMIS is a universal bridge to this diverse collection of data: Whatever type of analysis is to be used—a simulation or a regression analysis, for instance—GMIS provides the interface between the required language and the data."

Users with terminals in their offices are now working out solutions interac-

tively. Using programs created under GMIS, engineers in the government of the state of Maine are conducting studies to determine the best use of the money available for energy conservation.

GMIS data has helped the New England region avert a proposed oil tariff by demonstrating its negative economic effects there.

"Sound public and private policymaking and resource management require prompt, accurate information on many such issues," Donovan says. "GMIS is designed expressly as a tool to provide that information."

## FORTRAN and Logic Programming Aids

Three program products available from IBM simplify the programming of engineering and scientific applications:

**1. FORTRAN Interactive Conversion Aid** facilitates the conversion of non-System/370 FORTRAN dialects into System/370 FORTRAN IV executable source code.

**2. APL Decision Table Processor (DTABL)** converts a decision table (a powerful method of notation for complex logic) into an executable program.

**3. FORTRAN Interactive Subroutine Library (FISLIB)** makes FORTRAN a truly interactive tool for any application that requires human judgment during the course of the program.

For more information on these and other IBM program products, contact your local IBM branch office or write to the Editor of DP Dialogue at the address on the right.

*DP Dialogue is designed to provide you with useful information about data processing applications, concepts and techniques. For more information about IBM products or services, contact your local IBM branch office, or write Editor: DP Dialogue, IBM Data Processing Division, White Plains, N.Y. 10604.*

Data Processing Division




Photo courtesy Data General Corp.

Time was when  
a mini was a mini,  
a micro was a micro,  
and the picking was  
easy. Not any more.

Should the computer in your next equipment be a minicomputer or a microcomputer? A year or two ago, you would have answered the question much faster. You would have known that:

- Minis come in boxes, micros don't
  - Minis are "turnkey," micros aren't
  - Minis cost more than micros
  - Minis are larger than micros
  - Minis are faster than micros
  - Minis use longer words than micros
- Minis offer more software support
  - Minis can address more memory

But now these "truths" have become "maybes." There are enough exceptions to make you stop and examine each fact before you decide which road to take.

"The real difference between the two groups is the marketing approach," says Adolf Monosson, President of American Used Computer Corp. (Boston, MA). He would keep microcomputers in the hands of designers: "If a businessman's  $\mu$ C fails, he can't afford to take the hardware and his data to a technician." But Ed Zander, Manager of Data General's Micro Prod-

ucts Marketing Group, disagrees. "We provide the same maintenance for the microNova as for the Nova."

Both are right, but full support is still more the exception than the rule for  $\mu$ Cs. Although  $\mu$ Cs have by now infiltrated practically all mini applications, the bulk of the micro business does not come from end users, but from OEMs like you. But while you often choose your own computer configuration (Fig. 1) and write much of your own software, you may not always have the time.

If you opted for a small "turnkey" system a year or two ago, you would probably have wound up with a minicomputer. But today half the microcomputer models on the market come ready to plug-in and run. On the other hand, many minicomputer makers have retaliated by shedding their minis' power supplies and housings.

#### A matter of dollars and sense

While you can no longer tell a mini from a micro by its looks, perhaps you can tell them apart by their price tag?

"A micro is a mini at half the price," quips Hugh O'Neill of New Engineering Systems (Peacehaven, England). In fact, the cost difference between minis

and micros can be much larger. According to Ronald Todd, President of ECD (Cambridge, MA), his company's \$2500 MicroMind II outperforms minis in the \$40,000 class.

But the price difference can also be quite small. Data General's smallest Nova costs \$2600, while the minimum microNova configuration goes for \$1995. DEC's LSI-11 microcomputers (Fig. 2) go for \$634 to \$1594, while the Naked Mini of Computer Automation sells for \$548, and Interdata's 516, single-board mini costs \$898 (all in quantities of 100).

Computers in various degrees of address are obviously not aimed at the end-user, unless he happens to be a hobbyist (i.e. often an engineer after hours). Yet, it seems that mini makers don't compete very hard for that big OEM market. Fig. 3 shows clearly why most minicomputer makers are more interested in expanding the top of their line, than in fending off microcomputer inroads at the low end.

The low-end mini with its established software support is, however, still a viable alternative in some OEM applications. "Only for high-volume designs does it pay the OEM to duplicate existing mini capability," comments Bill Rosser, Vice President for




Photo courtesy Process Computer Systems, Inc.

Corporate Development at Perkin-Elmer Data Systems, Interdata's parent. With increasing volume, the economics shift to the special-purpose micro, and eventually (in the high thousands) to the custom-LSI chip, a descendent of hard-wired logic.

#### Smaller is better

Often size is more important than price, and there the microcomputer has a clear lead. After all, the smallest computers are one-chip micros. And Texas Instruments Chairman, Mark Shepherd Jr. predicts that by 1982 or 1983 TI will have a single-chip 32-bit  $\mu$ P with 1 Mbit of on-board memory.

Size is also the major distinction between minis and micros for Data General's Ed Zander. "But when the size is comparable, it's just a marketing decision whether to call the machine a micro or a mini," he adds (see Fig. 4).

So, it has become very hard to distinguish minis clearly from micros by such external characteristics as housings, price or size. But will the important operating characteristics—speed, addressable memory, throughput—clear up the picture?

"While microcomputers are LSI devices, minis are largely based on MSI

chips, and that's inherently a faster technology," states Ned Chang, Senior Marketing Vice President of Wang Laboratories. Gary Cole, PDP8 Product Planning Manager at DEC, concurs. "Bipolar technology and separate buses give minis a speed advantage over the mostly NMOS-based micros."

Victor Maxted, Minicomputer Marketing Manager of Raytheon's Data Systems Co. estimates that minis execute instructions about twice as fast as micros; in data transfer rate, the difference is even bigger: Mbytes/s for the minis, compared with 10 to 100 kbyte/s for the micros.

Paul Wintz, President of Wintek (Lafayette, IN) offers the following comparison:

	6800-based microcomputer
Cycle time	1000 ns
Throughput	$1.6 \times 10^4$ bit/s
16-bit multiply	2 ms

	PDP11/45 minicomputer
Cycle time	200 ns
Throughput	$6.4 \times 10^6$ bit/s
16-bit multiply	5 $\mu$ s

And that does not include the effect of many minis' powerful microinstructions, which can require whole sub-

routines in a  $\mu$ C.


But some additional chips can boost the speed of a micro to give minis a good run for their money. Advanced Micro Devices' 9511 math chip reportedly increases the performance/price ratio of a  $\mu$ C by a factor of ten. And Hewlett-Packard's silicon-on-sapphire technology—although at present limited to HP instruments—is going to improve speed in general, while reducing power consumption.

Intel's new peripheral chips are eliminating some of the  $\mu$ Cs' I/O restrictions, and throughput is catching up generally. Take the well-stacked, suitcase-size  $\mu$ C Micral C (Fig. 4) from R2E (Orsay, France), which claims a transfer rate of 920 kbyte/s—higher than the PDP11/45's.

Meanwhile, another "absolute truth" is beginning to wreak havoc with definitions of minicomputers and microcomputers.

#### Putting in their 8 bits' worth

"I suggest we call computers with 16 bits or more minis, and anything less micros," says Dwight D. Carlson, President of PCS (Saline, MI). If he could persuade his industry to accept that definition, life would be easier for the




1. OEMs often build their own microcomputers and integrate them into their systems. In Foxboro Co.'s VIDEOSCOPE, the logic cards are at top left, the CRT is at top right, and the power supply is at the bottom.

digital designer. But then, how do you label a 16-bit machine that's put together from 4-bit slices like AMD's 2901? Or TI's promised 32-bit computer on a single chip? Or a  $\mu$ C with address, instruction, and data word lengths both above and below 16 bits?

And then there are  $\mu$ Cs like the Intel SBC80/20. By using a bus-master chip on the board, Intel can parallel up to 16 of these boards, communicating over a 16-bit bus. "They can even use a mini as a slave," says Jim Medlin, Intel Application Engineer. So, he offers a different definition: "Minis can develop their own software, while micros can't."

But some micros can. "Learning to design good software takes 5 to 10 years," says DEC's Gary Cole. And it seems that chip makers like Intel have now accumulated that knowledge, and are duplicating the evolution 10 years ago of minicomputers into full-fledged systems.

Because programming time is so expensive, more and more higher-level languages are being implemented in microcomputer systems. Although Basic and Pascal are current favorites, compilers for PL/I and Fortran derivatives have found their way into  $\mu$ C operating systems. But software houses like FORTH Inc. are developing



2. The LSI-11/2 microcomputer from DEC can operate many programs developed for the PDP-11, at a fraction of the mini's cost. The operating system contains Fortran, Basic, APL and FOCAL.

new languages, better tuned to  $\mu$ P architecture. "We find the compact code of  $\mu$ FORTH ideal for our microcomputer products," says Robert Winder, Director, MOS Systems at RCA (Somerville, NJ).

### Software no paper tiger

While  $\mu$ C-system software is getting better, what about application software? For large customers, a  $\mu$ C vendor may provide software assistance, but most OEMs have to design their own, often using the chip makers' development system.

Microcomputer-based software development, however, may not be the best approach. Compilation is slow, and diagnostics limited. According to Mike Rooney, President of Boston Systems Office (Boston, MA), "99.9% of all programmers make mistakes. A development system on a large computer can make it a lot easier to find and correct them—and maybe as much as 10 to 50 times cheaper."

Cross-assemblers run mostly on minicomputers, and are also available on several time-sharing systems. But before you commit yourself to any one, get a benchmark—development costs can vary by more than an order of magnitude between systems.

Another problem with  $\mu$ C-software development is the profusion of instruction sets, and the frequent chip improvements. "If only they kept the instructions and pin-out constant!" laments Foxboro's Corporate Research Manager Richard Caro.

So a large OEM like Foxboro Co. (Foxboro, MA) is designing its own  $\mu$ Cs for industrial controls from bit slices and other LSI chips. "That way we retain control over our software," explains Caro.

### All sorts of memories

The amount of addressable memory is another bone of contention between minis and micros. "A microprocessor's 40-pin DIP certainly imposes limitations on the microcomputer," comments DEC's Gary Cole. But multiple-chip CPU sets and multiplexed address/data buses help to overcome this limitation. And Texas Instruments now puts its SPB 9900 microprocessor in 64-pin DIPs to gain more bus lines.

So, here too, the distinction between micros and minis is fading. Directly addressable memory of 64 kbytes is no longer a rarity for a  $\mu$ C. ECD's Micro-



# We say they're the industry standards. And the 118,723 people who've bought them will back us up.

The Fluke 8000A, 8600A and 8800A digital multimeters. Far and away the industry leaders, both in sales and performance.

They're why Fluke is #1 in multimeters. Worldwide.

**8000A 3½ digit DMM.** More people use the 8000A than any other DMM ever built. And there are good reasons. Specifications are guaranteed for 1 year for 5 measurement functions in 26 ranges. Input overload protection on all ranges. Basic accuracy is 0.1%. MTBF is 21,000 hours. And the 8000A comes in many versions: high current, low-ohms, with analog meter, or milliamperesecond. \$325.\*

**8600A 4½ digit DMM.** The 8600A is the prestige DMM in the portable class, featuring high accuracy and full auto-ranging.

Five ranges each of ac and dc volts to 1200V with 0.02% dc and 0.2% ac accuracy. Five ranges each of ac and dc current to 2A with 0.1% dc and 0.3% ac accuracy. Six ranges of resistance to 20 MΩ with 0.1% accuracy. AC bandwidth to 100 kHz. And demonstrated 10,000-hr MTBF. \$549.\*

**8800A 5½ digit DMM.** The 8800A is a unique portable, laboratory standard digital multimeter. It has, for example, a dc accuracy of 0.005%. Full autoranging. And it's fully guarded. Zero stability is better than 10 μV for 90 days. Isolated 4 terminal ohms. A demonstrated MTBF of 10,000 hours. \$985.\*




So now you have a rough idea of why the 8000A, 8600A and 8800A DMMs are the industry standards.

But to really find out how good they are, ask almost anyone nearby. He's probably using one of our DMMs right now.

And he'll be able to tell you why Fluke is #1 in DMMs. Worldwide.

For data out today, dial our toll-free hotline, 800-426-0361. John Fluke Mfg. Co., Inc., P.O. Box 43210, Mountlake Terrace, WA 98043. Fluke (Nederland) B.V., P.O. Box 5053, Tilburg, The Netherlands. Phone: (013) 673-973. Telex: 52237.

\*U.S. price only.




## Fluke DMMs. Standards for the industry.



FOR LITERATURE CIRCLE 17

FOR DEMONSTRATION CIRCLE 18




3. In total dollars, microcomputers are still “small fry”—compared with minis and mainframes—as this chart from Perkin-Elmer’s Data Systems shows. It was compiled for the 1977 market.

Mind 2 is even said to access 64 Mbytes. And it’s almost common practice to treat all peripherals as memory. “We use the I/O ports on our micros now only for special functions,” says Doug Cassell, Marketing Vice President of Control Logic (Framingham, MA).

Just as the minicomputer’s development depended on dropping core prices, the continuing reduction of semiconductor memory prices will largely determine the microcomputer’s future development—not so much because lower memory prices open up new applications, but because they affect software development.

While memory was scarce, machine and assembly languages prevailed. But by now the cost of software already outweighs that of hardware more often than not, and the ratio is steadily getting worse. What’s the answer?

Some  $\mu$ C designers are venturing into territory not previously cultivated by minis. J. T. Boren, Marketing Manager at Sperry Univac predicts a new breed of much more cost-effective, solution-oriented machines, with software-dominated architecture. Other industry experts echo this forecast. But nobody is ready to say just how that software/hardware merger will be im-



4. Fully dressed, minis and micros are often hard to tell apart. Perkin-Elmer’s Interdata 516 (top) is a mini-computer, while Data General’s microNova is a micro. Why? Because their makers say so.

plemented in practical systems.

In any case, the next breakthrough in data processing will probably come in CPU architecture. Except for scientific applications (which constitute a tiny share of the data processing market), typically 90% of processing time is taken up with data sorting or storing. And today’s address-oriented CPU architecture is ill-suited for that task.

So, what will the data-processing system of the future look like? It makes little sense to build a \$50,000 system around a \$10 processor. Terminals, disc drives, and peripherals of all kinds could perform 60% of a computer’s processing load, according to Larry MacPherson of Interdata, a Perkin-Elmer subsidiary (Oceanport, NJ). So, it’s much more sensible to distribute processing activities throughout the system as in Intel’s 80/20  $\mu$ C.

One 80/20-based micro system, Realistic Controls’ Z//300 supports up to 480 terminals, with 1.2 billion bytes of memory. A Z//300 can take care of inventory, payroll, scheduling, shipping, and general ledger. Even at maximum configuration, terminal reaction time will not exceed 4 seconds, says Dr. Leroy Anderson, Realistic’s General Manager. Many a mini would be proud of such performance. ■■



5. This well-stacked  $\mu$ C in a suitcase contains a plasma display, floppy drive and printer. It comes from R2E (France), and obviously speaks Le Basic.

(continued on page 30)

# Whether you use an MDS or a computer for microprocessor-based system development, you need this Logic State Analyzer to speed debugging.



HP's 1611A quickly spots those hard-to-find software problems and hardware malfunctions in your microprocessor-based system; whether you use time share, minicomputer or MDS for system development. In any case, you'll want a powerful stand-alone logic state analyzer for rapid hardware and software debugging. HP's 1611A can help you get your system into production quickly and help lower your development costs.

**Debug your program on operating hardware.** With real-time viewing, you analyze your system's actual operation. You can monitor at normal speed or stop the microprocessor and give control to the 1611A for single- or multiple-keyed steps. You can choose either mnemonic or absolute (op codes) so that you can examine the listing in the microprocessor code. And if you're using an MDS for system development, you can operate independently, allowing other users to work on software development.

**Pinpoint virtually any specific event.** Trigger on an address, data, external signal or any combination of the three to pinpoint a specific location within the program. And you can get a direct readout of the actual elapsed time or the number of events between selected points in your program. Add to all this, range trigger, selective store, sequential trigger, min/max totalizing of elapsed time or events, and you have a logic state analyzer that lets you capture those elusive events quickly.

For \$5200\*, get a better understanding of your system using HP's 1611A. Your local HP field engineer has all the details. Give him a call today.

## NOW AVAILABLE

8080	6800	Z80	F8	6502	8085	1802	General Purpose		
✓	✓	✓	✓						

These microprocessor "Personality Modules", priced at \$1250\* each, let you adapt the 1611A for today's key microprocessors. Watch for more to become available early in 1978.

\* Domestic U.S.A. price only.

087/16



1507 Page Mill Road, Palo Alto, California 94304

For assistance call: Washington (301) 948-6370, Chicago (312) 255-9800, Atlanta (404) 955-1500, Los Angeles (213) 877-1282


CIRCLE NUMBER 19

(continued from page 28)

Companies	Circle number	Microcomputer				Minicomputer		Other products
		Chip	Board	System	Devel. sys.	Boards	Systems	
Advanced Micro Devices	451	•	•		•			
American Microsystems	452	•	•		•			•
Apple Computer	453			•				
Applied Data Communications	454			•	•			
Applied Systems Corp.	455		•	•	•	•	•	•
Automated Computer Systems	456			•				
Bedford Computer Systems	457		•	•				
Boston Systems Office	458				•		•	•
Burroughs Corp.	459						•	
Byte Inc.	460		•	•				
Central Data	461		•					
Computer Automation	462			•		•		
Control Data	463						•	•
Control Logic	464		•	•	•			
Cramer Electronics	465				•			
Cromemco	466		•	•				
Data General	467	•	•	•	•	•	•	•
Datanumerics	468		•	•				
Digimetric	469		•	•				
Digital Equipment	470		•	•		•	•	•
Digital Group	471			•				
E & L Instruments	472		•		•			•
ECD Corp.	473			•				
Electronic Control Technology	474		•	•				•
Electronic Memories & Magn.	475		•	•				
Fairchild Instr. & Controls	476	•	•	•				
Ferranti	477	•		•				
Futuredata (Microkit)	478			•	•			
General Automation	479		•	•				
General Instruments	480	•	•	•				
Gnat Computers	481		•	•	•			
GRI Computer Corp.	482						•	
Harris Computers	483						•	
Harris Semiconductors	484	•			•			
Heurikon Corp.	485		•	•	•			•
Hewlett-Packard	486				•	•	•	•
Honeywell	487						•	•
Hughes Solid State Div.	488	•						
Iasis Inc.	489		•					
IBM Corp.	490						•	•
IMS Inc.	491							•
Imsai	492		•	•				
Infinite Inc.	493		•	•				•
Information Control	494		•	•	•			
Intel	495	•	•		•	•		•
Intersil	496	•	•	•	•			
IT&T	497	•						
Microcomputer Associates	498		•	•	•			

# What makes GE low current, low cost SCR's last so long?

## A "24 Kt." mountdown.



Hard, gold-eutectic solder holds the pellet firmly in place in every General Electric C103, C203 and C106 SCR. The rugged mountdown resists thermal fatigue and environmental stresses far better than common soft solder or conductive epoxies.

Additionally, GE's patented Power Glass passivation provides contamination-free inorganic protection of the pellet junction. You get low level leakage current with improved DC blocking life stability. Hermetic reliability at plastic prices.

Want proof? GE C103 SCR's (.8 amps up to 200 v) have successfully withstood over 1.6 million hours of accumulated blocking and storage life testing. The popular GE C106 SCR's (4 amps, up to 600 volts), have over 12 years of impressive life test results. The new TO-92 packaged C203 SCR's (.8 amps, up to 400 volts) — JEDEC registered

2N5060-64 — can be expected to register similar high levels of reliability.

Ruggedness. Reliability. It's the kind of competitive edge you expect from the world's leading manufacturer of SCR's. (The company that invented and perfected the plastic SCR.)

Call or write your nearest GE electronic component sales engineer or any authorized GE distributor for more information. Or write General Electric Co., Electronics Park 7-49, Syracuse, N.Y. 13201.

222-05

**There's more  
to GE semiconductors  
than meets the eye**

**GENERAL  ELECTRIC**

(continued from page 30)

Companies	Circle number	Microcomputer				Minicomputer		Other products
		Chip	Board	System	Devel. sys.	Boards	Systems	
Microdata	499						•	•
MITS, Inc.	500		•	•				
Modcomp	501						•	
Monolithic Memories	502	•						
Monolithic Systems	503		•	•	•			
MOS Technology	504	•	•					
Mostek	505	•	•	•	•			
Motorola	506	•	•	•	•			
Multisonics	507		•	•	•			
muPro, Inc.	508		•	•	•			
National Semiconductor	509	•	•		•			•
NEC Microcomputers Inc.	510	•	•		•			
North Star Computers	511		•	•				
Ohio Scientific	512			•				
Omnibyte	513		•					
Omron	514			•				
Panasonic	515	•			•			
PC/M Inc.	516		•	•				
Perkin-Elmer (Interdata)	517					•	•	•
Plessey	518		•					
Prime Computer	519						•	
Process Computer Systems	520		•		•			
Processor Technology	521			•				
Pro-Log Corp.	522		•		•			•
Quay	523		•	•				
Raytheon Data Systems	524	•					•	
RCA Solid State Div.	525	•	•	•	•			
RCI/Data	526		•	•				
Relational Memory Systems	527		•	•				
Rockwell International Inc.	528	•	•	•	•			
R2E America	529			•				
Scientific Microsystems	530	•	•	•				
Signetics	531	•	•	•	•			
Southwest Technical Products	532		•	•				
Space Byte Corp.	533		•	•	•			
Sperry-Univac (Varian)	534						•	
Technical Design Labs	535			•				
Tektronix	536			•	•			•
Texas Instruments	537	•	•		•	•	•	•
Toshiba	538	•						
Three Phoenix	539			•				•
Wang Laboratories	540						•	•
Warner & Swasey	541		•	•	•			
Western Digital	542	•	•					
Wintek	543		•	•	•			
Wyle Laboratories	544		•	•	•			•
Zilog	545	•	•	•	•			

What's TRW up to now?

# Metal film with muscle.

Our Metal Glaze™ resistors are rated 2 to 4 times mil spec power, yet retain precision resistor characteristics.

Now, with both strength and precision, you can take advantage of these thick film resistors and standardize on one size. Or benefit from an improved safety factor. For example, our 1/8W 1% device will handle 1/2W @ 70° C, or up to 40W pulse.

What's more, we've added a new 2W standard.

It takes 50% of the board space of the old 2W, yet is rated 3W @ 25° C. We're also in the process of substantially increasing resistance well into the megohms.


TRW metal films with muscle are available from 1/8W to 5W, 200 V to 15 KV, with 1, 2 and 5% tolerance. For standards in all types of resistors, contact your local TRW distributor. Or TRW/IRC Resistors, 401 N. Broad St., Philadelphia, Pa. 19108. (215) 922-8900, Dept. G.

**TRW IRC RESISTORS**  
ANOTHER PRODUCT OF A COMPANY CALLED TRW

™ Metal Glaze is the TRW trademark for its thick metal film resistors.

CIRCLE NUMBER 120

# READ THESE TEN CHAPTERS. AVOID CHAPTER 11.



- I want to see how a computer vendor can help me. Send me your book today.
- I'm too busy to read another book. Have your salesman come and show me the way.

Name \_\_\_\_\_  
Title \_\_\_\_\_  
Company \_\_\_\_\_  
Department \_\_\_\_\_ Phone \_\_\_\_\_  
Address \_\_\_\_\_ City \_\_\_\_\_  
State \_\_\_\_\_ Zip \_\_\_\_\_

Data General, Westboro, MA 01581, (617) 366-8911. Data General (Canada) Ltd., Ontario.  
Data General Europe, 59-65 rue de Courcelles, Paris, France. Data General Australia, Melbourne (03) 82-1361.



ED 118

We make computers that make sense

© Data General Corp., 1977



# Intel delivers 16K ROMs. In two weeks.

Finally, there's a realistic solution to your need for fast, fast delivery on 2316E 16K ROM orders. It's Intel's "OTP Program." And it puts parts in your hands just two weeks after you place your order with Intel. Not six weeks. Not four. Two weeks.

OTP is the key. It means One Time Programmable. When you place an order for a thousand or more 2316E ROMs, you'll get 25 programmed OTP 2616 EPROMs just 14 days later. That's the kind of offer only Intel can make. Then we'll ship 100 masked ROMs just six weeks A.R.O., up to 1000 more two weeks after that. No extra charge for the special service. No rushing the ROM process. And no production delays for you. The same goes for 2308 8K ROMs, using OTP 2608 EPROMs.

Call any of our sales offices, listed below, for details. When it comes to fast turnaround on ROMs, Intel means business.

**ALABAMA**  
Glen White  
Associates  
Huntsville  
(205) 883-9394

**ARIZONA**  
Intel Corp.  
Phoenix  
(602) 242-7205

**CALIFORNIA**  
Mac-1  
Berkeley  
(415) 843-7625  
Mac-1  
Cupertino  
(408) 257-9880

Mac-1  
Fountain Valley  
(714) 839-3341

Intel Corp.  
Santa Ana  
(714) 835-9642

Earle Associates, Inc.  
San Diego  
(714) 278-5441  
Intel Corp.  
Sherman Oaks  
(213) 986-9510

Intel Corp.  
Sunnyvale  
(408) 738-3870

**COLORADO**  
Intel Corp.  
Denver  
(303) 758-8086

**CONNECTICUT**  
Intel Corp.  
Danbury  
(203) 792-8366

**FLORIDA**  
Intel Corp.  
Fr. Lauderdale  
(305) 771-0600

Intel Corp.  
Orlando  
(305) 628-2393

**ILLINOIS**  
Intel Corp.  
Oakbrook  
(312) 325-9510

**IOWA**  
Technical  
Representatives, Inc.  
Cedar Rapids  
(319) 393-5510

**KANSAS**  
Technical  
Representatives, Inc.  
Lenexa  
(314) 888-0212

**MARYLAND**  
Glen White Associates  
Timonium  
(301) 252-6360  
Intel Corp.  
Timonium  
(301) 252-7742

**MASSACHUSETTS**  
Intel Corp.  
Chelmsford  
(617) 256-6567

**MICHIGAN**  
Intel Corp.  
Southfield  
(313) 353-0920

**MINNESOTA**  
Intel Corp.  
Bloomington  
(612) 835-6722

**MISSOURI**  
Technical  
Representatives, Inc.  
Hazelwood  
(314) 731-5200

**NEW JERSEY**  
Intel Corp.  
Edison  
(201) 985-9100

**NEW YORK**  
Intel Corp.  
Hauppauge  
(516) 231-3300  
Intel Corp.  
Rochester  
(716) 328-7340

T-Squared  
Pittsford  
(716) 248-5005  
T-Squared  
Syracuse  
(315) 463-8592

Intel Corp.  
Poughkeepsie  
(914) 473-2303

**NORTH  
CAROLINA**  
Glen White  
Associates  
Raleigh  
(919) 787-7016

**OHIO**  
Intel Corp.  
Dayton  
(513) 890-5350  
Intel Corp.  
Euclid  
(216) 289-0101

**OREGON**  
ES/Chase Co.  
(503) 620-9616

**PENNSYLVANIA**  
Intel Corp.  
(215) 542-9444

**TENNESSEE**  
Glen White Associates  
Jonesboro  
(615) 477-8850  
Glen White Associates  
Germantown  
(901) 754-0483

Glen White Associates  
Hickson  
(615) 842-7799

**TEXAS**  
Intel Corp.  
Houston  
(713) 771-5781

Mycrosystems  
Marketing Inc.  
Dallas  
(214) 238-7157  
Mycrosystems  
Marketing Inc.  
Houston  
(713) 783-2900

Intel Corp.  
Dallas  
(214) 241-9521

**VIRGINIA**  
Glen White Associates  
Colonial Beach  
(804) 224-4871

Glen White Associates  
Lynchburg  
(804) 384-6920

**WASHINGTON**  
ES/Chase Co.  
Seattle  
(206) 762-4824

**CANADA**  
Intel Corp.  
Ottawa, Ontario  
(613) 232-8576  
Multitek, Inc.  
Ottawa, Ontario  
(613) 825-4553

intel delivers.

CIRCLE NUMBER 21

# CRT terminals will be more complex, but simpler to build

The CRT terminals of the future will be simpler—and more complex. New LSI devices are reducing the number of circuits necessary to build simple terminal systems, even as user demand for more features is adding more and more circuitry to the terminal. So claimed Lee Felsenstein, President of LGC Engineering (Berkeley, CA), in his paper at the Mini/Micro 77 conference in Anaheim, CA.

Low-cost terminals will work with one-chip and general-purpose microprocessors, and even ordinary television receivers. Moreover, the micro-computer and specialized controller circuits will permit a minimal system to be built with less than two dozen IC packages. This is one reason terminals for low-end systems will drop from over \$600 all the way to about \$200 in another year or two.

## Personal computing cuts cost, too

Another reason is the personal computing explosion—users are looking for virtually minimal performance at minimum cost. And, since many of the personal-computing applications do not demand high resolution, a tele-

vision receiver can be used to display the data. Typical displays are 16 lines  $\times$  either 32 or 64 characters per line for alphanumeric data and up to 256  $\times$  256 points for graphic displays.

A television receiver, fed either by a modulated rf or a composite video signal, eliminates a major part of a CRT terminal's cost—the video monitor.

Meanwhile, however, applications that demand high resolution or special graphics capabilities are increasing. Thanks to microprocessors, the ability to perform editing, graphics and special functions without a remote computer is getting easier to design into terminals.

But with all this added capability, terminal complexity will also rise—but not just in hardware. Software inside the terminal has become an important design factor since the  $\mu$ P has taken over many of the control functions originally handled by hard-wired logic.

For terminals that require graphics capability, for example, new software techniques help minimize the memory needed by the display. Minimizing is necessary, since one bit of memory must be used for each dot on the screen.

Displays with resolutions of, say, 1024  $\times$  1024 or 4096  $\times$  4096 dots would require over 131,000 or 2,000,000 bytes of storage just for the display data.


One new technique, virtual bit mapping, dynamically allocates memory according to how much graphic information is to be displayed, reported Stan Davis, a project engineer at Tektronix (Beaverton, OR). Thus, on a standard alphanumeric terminal graphics capability can be integrated with functions such as forms fill-out, scrolling and text editing. Since data are stored in dynamically allocated RAM, positional changes are simple.

However, to take advantage of virtual bit mapping, powerful software must be developed to manipulate bits and allocate memory. The additional software will raise design overhead and the terminal complexity.

A typical design scenario, as suggested by Bub Bleininger, Vice President Peripherals of Microdata (Irvine, CA) will go as follows: A semiconductor manufacturer comes to a plant with an application note and samples showing how his  $\mu$ P and support chips will allow the designer to build a bus-structured CRT terminal. By themselves, the chips, power supply, keyboard and display almost make a terminal.

The  $\mu$ P system created will have expansion capabilities well beyond that of a teletypewriter replacement. So as soon as the basic terminal is finished, a proposal will be made to increase the terminal's capabilities so that it is "smart." And when that system is completed, yet another proposal will come forward for an "intelligent" terminal.

Within a few years Bleininger goes on, the simple terminal will have grown to almost a complete computer system. But in the rush to develop the various features, the inflexibility of the software will often be overlooked. Then additional hardware capability will mean little, Bleininger warns, if a terminal's operating system can't take advantage of it. ■



The bus-structured CRT terminal permits simple system expansion. Controlled by a microprocessor, the terminal can grow from "dumb" to "intelligent" just by plugging several circuits into the system bus and developing the software.

# CHECK US.

We've been coming up with better instrumentation recorders for more than 40 years. And we're willing to put our reputation on the line. So check the boxes below for the type of recording equipment you need and send us this page. We'll send you some no-nonsense specs that will stand up to the toughest comparisons you care to make.

## VISICORDER OSCILLOGRAPHS

- Graphic data acquisition system (One to 32 channels, dc to 5000 Hz, choice of eight plug-in signal conditioning modules.)
- Linescan facsimile-type recorder (DC to 8 MHz; X, Y, Y', Z axis; high resolution, broad gray scale.)
- Recording oscilloscope (DC to 10 MHz; X, Y, Y', Z axis; up to one million in/sec writing speed.)
- Light-beam galvanometer recorders (DC to 25 kHz, up to 36 channels.)

## SIGNAL CONDITIONING

- Gage control units (Multi-excitation, calibration, balance, filtering, suppression, various gain ranges.)
- Thermocouple compensation unit (Calibration, suppression and span controls.)
- Amplifier/attenuator units (Differential, single ended, multi-bandwidth, various gain ranges.)

## MAGNETIC TAPE SYSTEMS

- Large-reel portable (DC to 2 MHz, 15-inch reels.)
- Small-reel portable (DC to 1 MHz, 10½-inch reels.)
- Laboratory systems (DC to 4 MHz, 16-inch reels.)

## SIGNAL ANALYZERS

- Correlation/probability analyzers
- Fourier transform analyzers
- Histogram recorders

## INDUSTRIAL TEST SYSTEMS

- Die casting test systems
- Welding test systems
- Data communications recording systems
- Air/oil circuit breaker analyzer system

## SPECIAL MILITARY PRODUCTS

- Digital cartridge tape recorder
- Shipboard analog tape recorder
- Airborne analog tape recorder
- Special applications recording oscillographs


To get a free catalog that describes all of our instrumentation recording systems, just circle the Reader Service Number.

## WE'LL SHOW YOU A BETTER WAY.

### Honeywell

Honeywell Test Instruments Division • MS-218 • Box 5227 • Denver, Colorado 80217

CIRCLE NUMBER 22



# As test and measuring instruments spread out, safety concerns grow


Test and measuring instruments have caused relatively few accidents and injuries, but with concern growing over liability for work-place hazards, instrument safety is getting more and more attention, engineers were told at Midcon in Chicago. Not only that, but U.S. companies interested in selling their instruments abroad, especially in Europe, had better be ready to meet safety standards.

"The instrumentation and test-equipment industry has enjoyed a commendable safety record," says Donald Mader, associate managing engineer in the electrical department at Underwriters' Laboratories Inc., Melville, NY. But this record may not hold under changing conditions in the electronics industry.

Measuring instruments and testing equipment are cropping up more and more in common work places, Mader notes, which means that highly sophisticated and complex devices are being used by an ever-increasing number of employees with little or no technical training.

Richard Nute, corporate product safety engineer at Tektronix Inc., Beaverton, OR, believes that designers have a duty to design protections into equipment. "In today's world, the product must be deliberately—not incidentally—designed for safety." But there's more to it than that, according to Nute. Instrument makers are stepping up efforts not only to provide safer gear, but to protect themselves from lawsuits and government involvement in instrument design.

So far there has been no pattern to the few instrument-related accidents. That's fortunate, says Nute, because a pattern of accidents is usually the basis for legislation, such as the type leading to radiation control for microwave ov-



**You can't change the fuse** on gear equipped with this Corcom power module without first unplugging the line cord. For safety's sake, you have to pop the fuse before you change the voltage setting, too.

ens and television sets. But as more and more people have access to sophisticated electronic equipment, says Nute, the probability of a pattern of safety problems increases.

### Heading off the law

Partly to forestall restrictive laws that could hamper an instrument firm's design efforts, many firms have joined with Underwriters' Labs to write a safety standard for testing and certifying instruments. Actually, manufacturers approached UL as early as five years ago, Mader recalls, and expressed interest in submitting electrical metering and measuring equipment for investigation. At that time, UL was reluctant to become involved because some of the probes, terminals and connectors used with measuring and testing equipment could not comply with UL's historically-accepted requirements for inaccessibility of parts operating at potentials capable of delivering an electric shock. In addition, instrumentation and test-equipment operators were apparently adept at modifying and repairing their equipment without any concern for risks.

Even examining instruments for safety presents problems, says Mader, who points to two special features of instrument evaluation: Power is delivered into the equipment not only from the branch circuit supplying operating electrical energy, but also from the external circuitry supplying energy through the measuring terminals.

Also, electrical test equipment is intended either to perform a nonsafety function or is relied on ultimately to indicate or control the safe performance of other equipment.

Nevertheless, UL has been accepting submittals of test equipment since 1972, relying for guidance on two existing safety standards, the International Electrotechnical Commission (IEC) Publication 348 and the American National Standards Institute (ANSI) Publication C39.5, as well as UL standards and newly developed requirements, wherever they could be applied. Meanwhile, UL began writing its own instrument-safety standard, UL 1244.

"UL and industry are reviewing the final draft of the proposed UL 1244 standard so that it can be published soon," says Mader. Once it has been published and adopted, the standard

CASCADE®

LEGAL RULED PAD

P3-C814-CP

# CHALLENGE US.

Are you looking for a better way to monitor, condition, record or analyze data? Then challenge us. Describe your recording or signal analysis problem in the space below and send us this page. We'll get back to you with our recommendation.



**WE'LL SHOW YOU A BETTER WAY.**

**Honeywell**

Honeywell Test Instruments Division • MS-218 • Box 5227 • Denver, Colorado 80217

should become effective within 18 months. UL then plans to submit it for recognition as an American National Standard, and expects the document to be submitted to the IEC as the U.S. proposal for a revised international instrument-safety standard.

### Safety concerns are worldwide

Instrument safety is more than just a domestic concern, as U.S. instrument makers doing business abroad are finding out. In Europe, says Robert Wersen, president of Panel Components Corp., Berkeley, CA, "most industrial products are not yet subject to presale testing, but I find that more and more European institutions are requesting bids and quotations stating that certain components must be tested."

In the past few years, many instrument companies have seen most of their sales shift away from the U.S. and mainly toward Europe. To keep sales growing in Europe, U.S. firms will have to pay more attention to the increasing demand there for safety-testing products, Wersen insists.

"Most domestic companies are not actively pursuing what's taking place abroad," says Wersen. "They seem to prefer to ignore these sorts of things, or hope that they will go away." Worse yet, companies heeding European safety standards find the going tough.

One big reason for the rough road, Wersen points out, is that 16 European countries have their own national testing laboratories—each reserving the right to test any product before it can be sold in that country. A Certification Body based in Denmark is supposed to coordinate national testing efforts and help manufacturers gain international approvals by getting the testing results from one lab transferred to other labs. While this sometimes helps avoid the time and expense of separate submissions, the national testing lab of one country in many cases will still not accept the results obtained at another lab, Wersen says.

The IEC has published safety standards as well, but there are also national specifications to worry about—and the final authority in each country is the national document, not the IEC document, says Wersen. In addition, European safety standards may differ from U.S. and Canadian standards. Designers working on products aimed at international markets have to take all of the standards into account before

they start designing, or risk expensive redesigning to comply with all applicable documents.

Wersen suggests that firms interested in complying with safety standards first make sure that someone examines a prospective design's features before real designing begins. A safety engineer, involved with the design from the start, should then develop a working knowledge of the safety requirements of each country in which the company expects to sell the product. It even helps to bring working prototypes of new products to various testing agencies to determine as early as possible what might have to be changed to bring the product into compliance, says Wersen.

### Recognized parts help

Another way to simplify gaining acceptance from UL and international



**Shock protection** is provided on the Simpson 461 DMM's test leads by reversed connectors; the male end is recessed in the case and the leads house the insulated female end.

testing agencies is to use testing-lab-recognized components in new products. When the product is undergoing safety testing, such components needn't be examined separately to ensure compliance. Many UL-recognized components and lines were on display at Midcon.

For example, a line of recognized fuseholds and switches was presented by Panel Components. The firm specializes in components that have been accepted by international safety-testing agencies.

An Alpha Wire Corp. line of more than 400 multiconductor and multipaired cables for communication and control has gained both a UL listing and a Canadian Standards Association (CSA) certification. According to the Elizabeth, NJ, company, wire and cable installed properly according to the National Electrical Code and using UL-listed cable results in an installation

acceptable to the Occupational Safety and Health Administration. "Every time a user does a new installation, performs maintenance or repairs, or moves a piece of electronic equipment, he must use cable that is installed properly and that is UL-listed in order to avoid OSHA violations."

A voltage-selecting and fused connector shown by Corcom Inc., a maker of RFI power-line filters based in Chicago, is recognized under UL's components program. The connector incorporates an international-standard power-line connector, a fuseholder, an optional interference filter, and a voltage selector—a PC card that can be inserted four ways to change the wiring to the final product's power transformer primary.

The power module was developed by Hewlett-Packard Co., Palo Alto, CA. It is manufactured under license by Corcom and other firms, including The Potter Co. division of Pemcor Inc. (Wesson, MS), another Midcon exhibitor. The Corcom VS&F connector has already been incorporated into some products displayed at Midcon, including logic analyzers and transient recorders from Biomation Corp., Cupertino, CA.

The unit is designed so that the line cord blocks the sliding fuse-access door and so must be unplugged before the fuse can be removed. This prevents hazardous voltages from appearing on the fuse terminals when they are accessible.


In addition, the fuse must be removed before the transformer tap-switching card can be removed. Though this doesn't prevent mistakes, it does remind an operator that the fuse may have to be changed when the line voltage is changed.

Other products at Midcon have features aimed at protecting users from hazards. For example, a fully insulated measuring terminal and a mating connector are incorporated into the Model 461 digital multimeter from Simpson Electric Co., Elgin, IL. In this terminal design, similar to that used in the Model 60 volt-ohmmeter from Triplet Corp., Bluffton, OH, the instrument's front panel has a recessed banana plug and the test lead has a fully insulated banana jack, instead of the usual reverse assembly.

Should the test-lead pull out of the instrument, no live terminal will be exposed. According to Irv Linker, director of marketing at Simpson, the design was originally used in VOMs built for Western Electric. ■

# At 100 nanoamps...

## Our knee makes their knee look sick




If your logic circuit needs an extremely constant reference voltage, but you want to draw as little current as possible, *our new LVA zener is your only choice.*

That's right. Your only choice. Other zeners can give you a stable voltage at 50 microamps. Only we can do it at 100 nanoamps.

Teledyne low voltage avalanche zeners are available in a range of voltages from 4.7V to 10V at your tolerance requirement. Let us know what you need, and we'll give you exact specs. And the most pleasant surprise of all may be the price.

For complete information and/or evaluation samples, contact Jerry Kramer at (415) 968-9241.



### **TELEDYNE SEMICONDUCTOR**

1300 Terra Bella Avenue, Mountain View, California 94043 • (415) 968-9241

SALES OFFICES: DOMESTIC: Salem, N.H. (603) 893-9551; Stony Brook, N.Y. (516) 751-5640;

Des Plaines, IL (312) 299-6196; Los Angeles, CA (213) 826-6639; Mountain View, CA (415) 968-9241

INTERNATIONAL: Hounslow, Middlesex, England (44) 01-897-2503; Tiengen, West Germany 7741-5066;

Kowloon, Hong Kong 3-240122; Tokyo, Japan 03-403-8141

CIRCLE NUMBER 24

# Progress is slow but steady in optical communications

It still looks like years before telephone systems will really shift from copper wires to fiber optics. But as papers at the National Telecommunications Conference in Los Angeles reveal, optical-communications technology is advancing substantially on several fronts:

- Optical sources and detectors are pacing the development of optical fibers and appear ready to be transferred from the lab to the field.


- Optical cables can now be installed by the same crews who install regular cables, and with similar equipment. They can be cut and spliced in a manhole.

- Optical-telecommunications systems now operating in such cities as Los Angeles, Chicago and London are functioning well.

Lasers and light-emitting diodes, the front end of any optical communications system, have gained ground in the recent past, according to Dr. H. Takanashi of Fujitsu Labs, Kawasaki, Japan. The latest generation of Burrus-type semiconductor lasers (those with a double-heterojunction of aluminum, gallium and arsenide) have longer lifetimes (well above  $10^3$  hours), better linearity (the wiggle in the input-output transfer curve has been straightened), and higher frequency response (flat to 2 GHz) than they used to. Lasers can now be used in the field, he says.

## LEDs don't degrade as much

LEDs are improving as light-fiber optical sources, too. Specially designed for telecommunications, the devices used to degrade to their half-life within 20 hours. But by burning them in, then weeding out the ones with dark-line defects, LED half-life has zoomed to a



**LEDs used as optical transmitters** now have a half-life of a million hours at 20 C. To achieve the long life, the devices are first burned in then checked for dark-line defects. (Graph courtesy of Fujitsu Labs, Kawasaki, Japan).

million hours at 20 C (see Fig.).

On the receiving end, noise in avalanche photodiodes (APDs) has been reduced by increasing the thickness of their avalanche region. Response time has been improved without increasing the operating voltage, and APD gain-bandwidth products are up to 300 GHz and a multiplication factor of 400.

But can optical technology cope with the real telecommunications world? It can, according to Dr. J.H. Mullins of Bell Labs.

Encouraged by the success of their experimental Atlanta fiber-optic telephone link, Bell Labs engineers installed a fiber-optics system in what must be one of the severest environments available—conduits in Chicago that not only date back to 1890, but are 30 ft underground and sloshing with water from the Chicago River a block away (see ED 11, May 24, 1977, p. 21). The Chicago experiment interconnects

two Bell Company telephone-switching centers and a large commercial office building in the downtown Loop area.

"To date, the results have been excellent—they've exceeded our own hopes," Mullins reports. Twenty-four individual fibers carry all the trunk lines between the two switching centers, all the subscriber phone service for the Brunswick Building, and Bell's Picturephone video-conference facilities to boot. All communications are digital, and occur at 44.7 Mbits/s, an already-established, CCITT-approved standard data rate. A mix of LEDs and lasers is used at the front end, and avalanche photodiodes at the rear end.

The cable, designed by Bell, is modular, constructed at the factory, and fitted with optical connectors that can be connected easily in the field. Fiber ends are cut and polished at the factory, so the per-splice attenuation can be held to 0.4 dB. Over-all attenuation in the cable amounts to 5.0 dB/km,



# Here's the extra microcomputer power and speed you need in today's engineering



## Z-80 BASED COMPUTER

You see here one of the industry's fastest and most powerful microcomputers.

It's our advanced Model Z-2, designed for dedicated work.

Its power comes from using the Z-80  $\mu$ P with its powerful 158-instruction set.

Its speed comes from using a special version of the Z-80 that operates at a 4 MHz clock rate.

So with our Z-2 you not only can do more, you can do it faster. You get extra flexibility, too, because of the Z-2's S-100 bus.

## ADAPTABLE TO YOUR JOB

Further, the Z-2 is arranged so you can tailor it to your job. It has a 21-slot motherboard accessible from the front. You can quickly and easily plug in an almost endless variety of additional memory, I/O, or whatever you need for your project.

## BROAD SUPPORT

Cromemco also gives you the kind of support you need. Analog I/O, for example. And high-speed 4 MHz memory in the form of 4-kilobyte and 16-kilobyte RAM cards with a bank-select feature. Our bank-select lets you organize memory into as many as 8 banks of 64K each.

You can also have a color-graphics interface, a highly-flexible TU-ART which interfaces two terminals, PROM cards with inexpensive PROM programmer, and a joystick console with self-contained speaker for audio effects.

## INDUSTRY-STANDARD BUS

The Z-2 is designed around the industry-standard S-100 bus. That means you can plug in not only Cromemco circuit cards but those from dozens of manufacturers that support the S-100 bus.

## HEAVY DUTY

The Z-2 is ideal for engineering, production, lab, business, and educational applications. The front panel is entirely free of controls or switches (no accidental memory losses or wipe-outs).

The unit is designed for rack mount-

ing and is totally enclosed in heavy sheet metal — no plastic.


Even the power supply has the extra measure of quality Cromemco is known for — it provides 30A from +8V and 15A from +18 and -18 V. That's more than adequate for a full set of 21 circuit boards and other peripherals.

## LOW PRICE

You get the Z-2 for only \$995 (or only \$595 in kit). That includes the 4 MHz Z-80  $\mu$ P board, power supply, and full-length motherboard. You have the fast, powerful basics to supplement with whatever circuit cards your project requires.

Contact Cromemco today for the literature on this powerful and practical computer. It's already one of the industry's best-known units.

Ask, too, for our new 20-page catalog.




## Cromemco

incorporated

Specialists in computers and peripherals

2400 CHARLESTON RD., MOUNTAIN VIEW, CA 94043 • (415) 964-7400

CIRCLE NUMBER 25



## variable capacitors

... made by Johanson, of course! Quality without compromise is our target in the design and manufacture of capacitors in sizes, mounting configurations and capacitance values to meet every application. Perhaps that's why—for nearly three decades—superior variable capacitors have been synonymous with the name Johanson, where standards of excellence always come first.

Electronic accuracy through mechanical precision.

*Johanson*

MANUFACTURING CORPORATION  
Rockaway Valley Road  
Boonton, N.J. 07005  
(201) 334-2676, TWX 710-987-8367

which is 1 dB better than Bell's Atlanta installation.


### Field splicing is successful

One problem that Bell did not address in Chicago is splicing a fiber-optic cable in the field. But a fiber-optic installation between Artesia and Long Beach in southern California did.

The connection, installed by General Telephone Labs of Waltham, MA, is 5½ miles long (9 km). The cable, developed by General Cable of Union, NJ, is a steel-and-aluminum protected, plastic I-beam-shaped core. On one side of the I is a laminated plastic ribbon of six optical fibers (monofilament strands, not bundles) from Corning Glass. On the other is three pairs of insulated copper wires, which help power two repeater stations along the route.

In GTE's splicing approach, a grooved, heated anvil is positioned below the two prepared fiber ends. The fibers are anchored. As the anvil is raised, the fibers enter the grooves, and the two butt ends slide gently toward each other. Once they are in contact and under a slight bias toward each other, the junction is flooded with an index-matching glue and sealed in heat-shrinkable tubing (see photo).

The cable, after being drawn through 50 manholes and spliced at 20 places, wound up with an optical loss of 6.2 dB/km—a small premium to pay for the convenience of field splicing, considering that Bell did little better (5.0 dB/km) with its elaborate factory-prepared connections.



A grooved anvil rises from below to guide the ends of optical fibers into position for splicing. Index-matching glue is applied and the junction is sheathed in heat-shrinkable tubing. This GTE splice scheme was used in a fiber-optic link between Artesia and Long Beach, in southern California.

Back in the labs, other splicing developments are "very encouraging"; according to Mark Dakss of GTE Labs. Splice losses in the quarter-dB range are common in the lab and can be achieved with a number of different techniques. But more life-test data need to be generated to know which techniques will prove significant.

Splice options that have made it out of the lab include grinding and polishing instead of scribing and cracking to prepare the fiber ends, using micromanipulators instead of preform tubes to align the ends, and index-matching adhesion in place of electric-arc fusion to bind the ends together. ■■

### Traffic control at your fingertips



Traffic-light control programs can be modified in the field with a calculator-like handheld terminal that can be programmed in easily readable alphanumeric instead of binary. The main program in the system, the Series M developed by Siemens AG of West Germany, is loaded via paper-tape or mag tape cassettes. And since the Series M equipment can communicate with central computers via a single conductor pair, it won't cost as much as older systems. Applications include fixed-time or traffic-dependent control at individual or centrally controlled crossings.

# Featherweight Miniature Panel Mount Thermal Printer



#### DPP-7 QUICK SPECS

##### Printing Rate:

3 lines per second

##### Inputs

Full parallel BCD

TTL logic inputs, selectable positive or negative true

##### Printouts:

Six digits and sign, 99±9999,

±999999 or 9±99999

(Hexadecimal optional)

##### Input Storage

BCD data must be valid only 1.5 microseconds during print command

##### Data Capacity

9000 lines on 150 foot x 1.75 inch (44.5mm x 45m) thermal paper rolls

##### Power Supply:

Choice of: +5VDC, or 100, 115 or 230VAC, 47 to 440 Hz

##### Size Case:

4.50" wide x 2.72" high (115mm x 69mm)

##### Depth:

5V Models

6.2" (158mm)

28V, 12V or

AC Models: 8.7"

(221mm)

#### New! Datel's Model DPP-Q7

Whisper Quiet  
5 Lines/sec.

\$495

COVERED BY  
GSA CONTRACT  
NO. GS-00S-27959

Datel's new model DPP-7 Digital Panel Printer uses only 2 moving parts for OEM reliability. At only 2.3 Lbs. (1.1Kg) it is one of the lightest panel-mounting recording instruments available.

#### Includes all electronics.

The \$475\* single quantity price includes everything required for full parallel BCD/TTL data inputs *plus* an input storage register for multiplexed bus applications *plus* an AC power supply! There are no extra boards to design or bulky cables and power supplies needed. The DPP-7 is ready to use.

**Thermal printing** means no messy inks, banging hammers or twirling print-wheels. Nothing to jam or run out of ink.

**Use** the miniature DPP-7 for simple data logging systems, automatic test fixtures or with a digital panel meter for accurate unattended data measurement.

The **small size** of the DPP-7 makes it ideal for panel-mounting in analytical instruments and compact data systems. Up to six digits and sign may be printed to identify channel number and data.

The DPP-7 uses +5VDC power in a very short 6.2" (158mm) deep version or 100, 115 or 230 VAC power in an 8.7" (221mm) deep version.

\*U.S.A. domestic price only



**DATEL  
SYSTEMS, INC.**

1020 Turnpike St., Canton, MA 02021  
Tel. (617) 828-8000

• Santa Ana, CA (714) 835-2751

• LA Exchange (213) 933-7256

• Sunnyvale, CA (408) 733-2424

• Gaithersburg, MD (301) 840-9490

• Houston, TX (713) 932-1130, 1132

• Irving, TX (214) 256-4444

• Tokyo, Japan 793-1031; Osaka, Japan

(06) 354-2025 • Andover, UK (0264)


51055 • Paris, Fr. 620-06-74

• Muenchen, W. Ger. (089) 78-40-45

Send for your FREE Brochure

CIRCLE NUMBER 27

The design is imaginative  
The performance is superlative  
The price is competitive  
The name, of course, is Motorola



**MOTOROLA Data Products**

455 East North Ave. Carol Stream, Ill. 60187 312-690-1400 TWX: 910-252-4404

CIRCLE NUMBER 28

# The 8080 A/D & D/A Advantage

super-software supplied • fast, on-card DMA logic • 80 (to 256) channel expansion from just 2 cards

Datel's SineTrac 800 has it. SineTrac 800 slide-in A/D and D/A cards provide a complete analog "front-end" inside your Intel MDS-800 or SBC-80/10/20 microcomputers.

SineTrac 800 is ideal for industrial data logging, process loops, and high speed data acquisition systems.

The A/D card contains 32 single-ended or 16 differential channels with 12-bit resolution. An A/D Expander card offers 48 additional channels. Thus, two cards give 80 single-ended or 64 differential channels! Card addressing allows expansion to 256 channels. Throughput is 20 microseconds with rates up to 36,000 samples/second in DMA mode.


SineTrac D/A cards contain either 8 channels or 4 channels.

More SineTrac system advantages include on-card start and final address register/counters to save time and CPU housekeeping, and an adjustable IC scan clock with interrupt-flagged scan markers for event-triggered or internal scan starts.

The paper tape diagnostic test programs, supplied, allow channel calibration and a multi-scan accuracy test with decimal printout. The programs diagnose error conditions, give a descriptive TTY printout between selected channels, and continuously loop for scope or logic analyzer troubleshooting.

A/D or D/A cards are \$650\* (singles). Write today for complete details.

\*U.S.A. domestic prices only.



**DATEL**  
SYSTEMS, INC.  
1020 Turnpike St., Canton, MA 02021  
Tel: (617) 828-8000

Santa Ana, CA (714) 835-2751, (L.A.) (213) 933-7256 • Sunnyvale, CA (408) 733-2424  
Gaithersburg, MD (301) 840-9490 • Houston, TX (713) 932-1130 • Irving, TX (214) 256-4444  
OVERSEAS: DATEL (UK) LTD—TEL: ANDOVER (0264) 51055 • DATEL SYSTEMS SARL 620-06-74 • DATELEK SYSTEMS GmbH (089) 78-40-45

CIRCLE NUMBER 29

# Custom thick-film hybrids by Parlex

Yes! Parlex makes hybrids.

We custom-design and produce thick film components and hybrid assemblies in long and short runs.

Precision resistors, capacitors, chip and discrete semi-conductors packaged with skill and imagination. Creative space-saving assemblies that often include flex circuits and flat cable.

True, custom flex circuits, flex-hardboards, multilayers and flat laminated cable made our reputation. But now we're also your best source for custom thick film. So ask for our catalog. Better yet, send your specifications or schematic to us at Parlex.



**Parlex**  
CORPORATION  
145 Milk St., Methuen, MA 01844  
617-685-4341

CIRCLE NUMBER 48

## NEW *from the makers of high-reliability printers* AlphaNumeric Printers with a microprocessor brain!

This series of designer-styled Digitec printers delivers high contrast, easy-to-read, fade-free matrix printout and quiet operation. The "smart" microprocessor provides versatility by simplifying systems interface and using the universally accepted ASCII code set.

- Choice of serial (RS-232-C and 20mA current) with baud rates to 1200, or 8-bit parallel bus input with data rates up to 1000 characters/second.
- Up to 24 characters per line
- Double font printing for special emphasis and variable formatting for easy data analysis.
- 24-hour clock and day/month calendar.

Contact us now for more information on our complete line of numeric and alphanumeric printers.


#### ATTENTION OEM's:

As a leading supplier of OEM printers, we're flexible to your requirements and offer generous OEM discounts.

**Digitec**

**UNITED  
SYSTEMS  
CORPORATION**

918 Woodley Road, Dayton, Ohio 45403  
(513) 254-6251, TWX (810) 459-1728



Model 6310 single quantity  
ready-to-print price

**\$595.**

DIGITEC: Precision measurements to count on.

CIRCLE 151 FOR INFORMATION ONLY

CIRCLE 152 FOR DEMONSTRATION ONLY

ELECTRONIC DESIGN 2, January 18, 1978

# New, 16 Bit Microcircuit D/A Converter

Datel has it...



Two versions to choose from:

#### DAC-HP16BMC

- ▶ 16 Bit Binary Resolution
- ▶ 15 ppm/°C Max. Tempco
- ▶ ±0.003% Linearity
- ▶ 0 to +10V, ±5V Output
- ▶ 35 μsec. Settling Time

#### DAC-HP16DMC

- ▶ 4 Digit BCD Resolution
- ▶ 15 ppm/°C Max. Tempco
- ▶ ±0.005% Linearity
- ▶ 0 to +10V Output
- ▶ 15 μsec. Settling Time

**\$7750\***  
(100's)

Price, both versions: \$119.00\* (1-24)

\*U.S.A. domestic prices only

When high resolution and stability are demanded, Datel's DAC-HP series provides the performance — applications such as precision signal reconstruction, automatic test systems, and ultra-linear ramp generation. DAC-HP's excellent performance results from special low tempco nichrome thin-film resistors, laser trimmed for optimum linearity, and a low tempco zener reference circuit. Operating temperature range is 0 to 70°C, with models available for -25 to +85 and -55 to +125°C operation.


**DATEL**  
SYSTEMS, INC.

1020 TURNPIKE STREET, CANTON, MASS. 02021  
TEL. (617) 828-8000 / TWX: 710-348-0135  
TELEX: 924461

Santa Ana, (714) 835-2751, (L.A.) (213) 933-7256 • Sunnyvale, CA (408) 733-2424 • Gaithersburg, MD (301) 840-9490 • Houston, (713) 932-1130 • Irving, TX (214) 256-4444  
OVERSEAS: DATEL (UK) LTD—TEL: ANDOVER (0264) 51055 • DATEL SYSTEMS SARL 620-06-74 • DATELEK SYSTEMS GmbH (089) 78-40-45

CIRCLE NUMBER 31

# HALL OF FAME CANDIDATE



## Sprague Type 150D TANTALEX<sup>®</sup>... the industry's first solid tantalum capacitor... is still the industry leader

If there were a Capacitor Hall of Fame, the Sprague Type 150D would be a shoo-in. The "old reliable" of solid tantalum capacitors is still tough to match . . . particularly with its extended capacitance ratings and outstanding performance characteristics.

As most circuit designers know, these hermetically-sealed capacitors offer high capacitance, small size, low leakage current, and low dissipation factor, com-

bined with high stability and long life. They're furnished in 4 case sizes from only .125" D. x .250" L. to .341" D. x .750" L. and operate over the broad temperature range of -80°C to +85°C or to +125°C with derating. Capacitance values from .0047 to 1000  $\mu$ F and voltage ratings from 6 to 125 WVDC are available as standard.

These capacitors are also available to meet MIL-C-39003, Styles CSR13, CSR23, CSR33, and CSR91.

For complete technical data, write for Engineering Bulletin 3520G to: Technical Literature Service, Sprague Electric Company, 347 Marshall Street, North Adams, Mass. 01247.

**THE BROAD-LINE PRODUCER OF ELECTRONIC PARTS**

CIRCLE NUMBER 32



a  
**General  
Cable**  
subsidiary



## McDonnell Douglas tops defense-contract list

McDonnell Douglas, on the strength of its production of the F-15 fighter aircraft for the Air Force, again led all defense contractors during the past fiscal year. The firm received nearly \$2.3-billion worth of prime contracts during fiscal year 1977, which ended last Sept. 30, and \$1.3-billion of that sum came from the Air Force's Aeronautical Systems Division, which is responsible for procuring the F-15.

The figures come from a market research study prepared by Washington Communications Service, Vienna, VA. All prime contracts of \$1-million or more awarded during fiscal 1977 by the Pentagon to the top 100 defense contractors, were included in the report. Nearly \$32-million worth of contracts was recorded for the year.

McDonnell Douglas, which reached first place on the defense contractors' list for the first time in fiscal 1976, accounted for more than 7% of all prime-contract dollars awarded last year. Second place went to Boeing with \$1.4-billion, up from sixth place the year before. Rounding out the top 10, which received \$11.5-billion or nearly 36% of the total, were United Technologies Corp., Lockheed, General Electric, Grumman, Hughes, General Dynamics, Raytheon and Chrysler.

Among the predominantly electronics companies, GE received \$1.1-billion, Hughes had \$1-billion and Raytheon received \$689-million. Other electronics firms placing high were Westinghouse in 11th place with \$625-million, IBM in 15th with \$445-million, Sperry Rand in 16th with \$400-million and Honeywell in 19th with \$340-million.

## Energy Dept. spends \$7-million on solar cells

Not only has the Department of Energy ordered another 190 kilowatts of solar cells from five firms at an estimated cost of nearly \$3-million, it is also spending \$4-million more to automate solar cell production in an attempt to reduce costs.

The awards are part of the department's goal to reduce costs from the present \$11 per peak watt to \$2 per peak watt by 1982 and 50 cents by 1986, in each case as measured in 1975 dollars. (When inflation is taken into account, the current \$11 figure is almost \$13.) Previous government purchases of solar cells averaged \$21 per peak watt in early 1976 and \$15 later in the year, again in 1975 dollars.

The five solar cell suppliers are Motorola Inc., Phoenix, AZ; Sensor Technology Inc., Chatsworth, CA; Solarex Corp., Rockville, MD; Solar Power Corp., Wakefield, MA; and Arco Solar, Chatsworth, CA. Estimated cost per peak watt ranges from Motorola's \$9.49 to Solarex's \$13.16 (in 1975 dollars).

Nine firms got fabrication-study contracts: Lockheed, Sunnyvale, CA; MB Associates, San Ramon, CA; Motorola, RCA, Princeton, NJ; Sensor Technology, Chatsworth, CA; Solarex; Spectrolab, Sylmar, CA; Texas Instruments, Dallas, TX; and Westinghouse, Pittsburgh. Both programs are managed jointly by the Department of Energy and NASA's Jet Propulsion Laboratory in Pasadena.

Solar cell arrays already purchased in the program are being used to power

an irrigation system in Nebraska, a residential-scale test system at MIT's Lincoln Laboratory, an electrically operated dust-warning sign on Interstate 10 in Arizona, and automatic weather-reporting stations in Alaska, Florida, Hawaii, Maine, New Mexico and New York. Construction has begun on a 240-kW array to provide heat and electric power to Mississippi County Community College in Blytheville, AR, and a 60-kW array for military applications at Mount Laguna, CA. For more on solar cells, see "Solar Cell Technology Advances—But Slowly" in ED No. 26, Dec. 20, 1977, p. 24.

## **Aerospace sales will keep going up**


The aerospace industry experienced real growth in sales last year for the first time since 1974 and should do it again this year, according to the annual forecast of the Aerospace Industries Association.

Industry sales last year reaped \$32.4-billion—up \$2.4-billion from the previous year, reports AIA president Karl Harr. And he looks for \$34.9-billion worth of sales in 1978.

When these figures are translated into constant 1968 dollars, however, the growth is more modest: from \$15.2-billion in 1976 to \$15.7-billion in 1977 to \$16.2-billion in 1978. Industry sales in 1968 were \$26.4-billion.

Still, all four industry segments should grow during the coming year, Harr foresees. As measured in current dollars, defense receipts should grow from \$16.3-billion to \$16.9-billion, NASA funding from \$2.8-billion to \$2.9-billion, commercial sales from \$7.6-billion to \$8.9-billion, and sales of nonaerospace products from \$5.7-billion to \$6.2-billion. And for the fourth consecutive year, exports are expected to be above \$7-billion.

**Capital Capsules:** Cubic Corp. of San Diego has received \$15 million from Iran to build an **air-combat range that permits electronic scoring of simulated dog fights, which are used in fighter-pilot training.** This air-combat-maneuvering-range instrumentation (ACMRI) will help train pilots on F-4, F-5 and F-14 aircraft. Cubic has built four ranges in the United States and is building a fifth in impact statement for its controversial **Seafarer ELF communications facility to test one-way data links with submerged submarines.** As expected, the Navy chose a site near Marquette, MI, which it plans to link via leased line with the present test site at Clam Lake, WI. The Navy is expected to seek development funds in the 1979 defense budget for installing a transmitter and 130 miles of buried antenna at the Michigan location. Alternate sites in Nevada and New Mexico were rejected because construction costs would have been higher.... **The Department of Energy's Argonne National Laboratory has discovered a new particle it is calling the diproton because it appears to have two protons and an electric charge of +2.** The particle was observed during experiments with a beam of polarized protons in Argonne's Zero Gradient Synchrotron.... **The Army is going ahead with its plan to transfer the headquarters staff of its Electronic Research and Development Command from Fort Monmouth, NJ, to Adelphi, MD,** after soliciting public opinion on the subject since last summer, as required by law. However, many of the research and procurement functions will remain in New Jersey.



# Get Rolling.

If you need test and measurement instrumentation that really moves, get behind the wheels of cart-mounted instrumentation from Tektronix.

You can load the upper tier of a Tek Model 3 Lab Cart with your Tektronix Oscilloscope, put one or two TM 500 Mainframes on the lower decks and fill them with your own configuration of TM 500 modular plug-ins:

- DMMs
- Counters
- Generators
- Amplifiers
- Power Supplies
- Plug-in Scopes
- Logic Analyzers
- Word Recognizers
- Custom Plug-ins

There are over 30 TM 500 instruments to choose from, so you can assemble a configuration that handles several specialized applications or use each individual instrument for general purposes.

Your entire instrumentation system plugs into a power distribution unit requiring a single line cord.



Your probes, accessories, additional plug-ins and documentation tuck away neatly in the bottom drawer. Now you're all set to go places.

You can travel to immovable machines and probe their inner workings . . . in one trip, not several. Or slip your mobile lab down a narrow laboratory aisle to give your bench more elbow room.

Or, zip across the production floor for a scope calibration. Tek instruments, Scopemobiles™ and Lab Carts have an internal common ground, an important feature if you get into sensitive digital circuitry.

And, if you need table top working space along with cart portability choose the TEK Rack Cart Model 7.


Like a moveable desk, the Rack Cart leaves a flat surface on top for charts, files and record keeping. And, 28" of

depth inside allows room to rackmount Tektronix instrumentation to the front or rear of the cart. A special option lets you rackmount a TM 500 six wide mainframe at an upward angle for easier usage.

With a rollabout test and measurement laboratory of Tektronix instruments, you've got a lot going for you. Flexibility. Accuracy. Configurability.

So, get rolling.

Call your Tektronix Field Engineer and ask him about taking a test stroll with the TM 500 family of modular instruments. They really go together.



## TM 500 Designed for Configurability

For configurable, accurate, reliable test and measurement instrumentation, contact: Tektronix, Inc., P.O. Box 500, Beaverton, Oregon 97077, (503) 644-0161, Ext. 5283. In Europe: Tektronix Limited, P.O. Box 36, St. Peter Port, Guernsey, Channel Islands,

**Tektronix**<sup>®</sup>  
COMMITTED TO EXCELLENCE

# Go First Class

with  
**POWER/MATE**



## In any business, there can be only one number one.

Power/Mate isn't the best power supply manufacturer just because we're the biggest.

We're the biggest because we're the best.

Over 12,600 companies across the country, both large and small, have chosen us as their prime source for power supplies for just that reason.

But we know it takes more than dropping names or numbers to get business.

It takes a selection of hundreds of models in over ninety different case sizes.

From 2 volts to 150 volts. With currents to 200 amps. Switching regulated or linear.

Open-frame, enclosed, encapsulated

or lab types.

In single or multiple outputs.

It takes immediate delivery on every model we make in both our East and West Coast plants.

It takes prices that are competitive.

With no sacrifice in quality.

It takes tough standards other companies don't even try to match.

It takes a commitment to provide the kind of products and service that help us keep customers for life.

So give us a call. And let us show you the first-class product and service you've come to expect from Power/Mate that's helped put us first.





### **POWER/MATE CORP.**

514 S. River St./Hackensack, New Jersey 07601/ (201)343-6294/TWX (710) 990-5023  
17942 Skypark Circle/Irvine, California 92714/ (714)957-1606/TWX (910) 595-1766

CIRCLE NUMBER 35

**The world's largest supplier of quality power supplies.**

# A whole new connector series for I/O applications



The introduction of our new BLUE MACS® Ribbon Connectors, designed in accordance with IEEE Standard 488, represents another Ansley engineering breakthrough in lower installed cost mass termination technology.

Ansley's BLUE MACS Ribbon Connector series terminates to standard 50 mil pitch cable which provides complete compatibility with all the other connectors in the system.

The Ribbon Connector incorporates all the BLUE MACS benefits, including the 4-point TULIP® contact for maximum termination reliability, and a one-piece design for fast, low cost assembly and positive cable-to-contact alignment.

This line is added to our complete family of "D" Series connectors now available from stock in 9, 15, 25 and 37 pin configurations. In addition, we offer a wide variety of UL listed jacketed cable for external use with these connectors.

This allows you more freedom when selecting connectors for future design.


All connectors are available with a broad selection of mounting hardware to various strain relief configurations. For the full reliability/cost effectiveness story and technical data, call or write:

## T&B / Ansley

The mass termination company.

T&B/Ansley Corporation • Subsidiary of Thomas & Betts Corporation  
3208 Humboldt St. • Los Angeles, CA 90031 • Tel. (213) 223-2331  
TELEX 68-6109 • TWX 910-321-3938

CIRCLE NUMBER 36



STOCKED AND SOLD THROUGH AUTHORIZED ANSLEY DISTRIBUTORS.

International T&B/Ansley Offices: AUSTRALIA, Brookvale, (02) 938-1713 • AUSTRIA, Vienna, (222) 6232365 • CANADA, Iberville, Quebec, (514) 658-6611 • ENGLAND, Luton, (0582) 597-271 • FRANCE, Rungis, 687-23-85 • HOLLAND, Zoetermeer, (79) 214688 • ITALY, Milano, 02-4986451 • JAPAN, Tokyo, 03-354-9661 • SINGAPORE (65) 2923711 • SOUTH AFRICA, Benrose 24-8134 • SPAIN, Barcelona, (93) 212-8607 • SWEDEN, Upplands Vasby, 0760-86140 • SWITZERLAND, Hombrechtikon, (04155) 422791 • WEST GERMANY, Dreieich bei Frankfurt, 06103-8 20 21 •

# When you need LEDs or more than LEDs...



Dialight is the first place to look. We can help you do more with LEDs... because we've done more with them.

Discrete LEDs come in a variety of sizes, shapes, colors (red, yellow, green in clear or diffused), with or without built-in resistors.

Low cost logic state fault indicators for trouble shooting complex circuits. Designed for close density PC board mounting.

High-brightness bi-color LEDs (red/green) suitable for go/no-go situations. Designed with unique

lenses for the extra visibility you'll want for your most critical applications.

Snap-in mounting LED indicators reduce labor cost. Available in red, yellow or green with or without built-in resistors.

Whatever you need in LEDs, Dialight's probably got it already. For your free 60-page selector guide and listing of our nationwide stocking distributors, contact us today.

**DIALIGHT**  
A North American Philips Company

## Dialight meets your needs.

Dialight, 203 Harrison Place, Brooklyn, N.Y. 11237 (212) 497-7600

CIRCLE NUMBER 37

## Protecting the members

Well, they finally got Irwin Landes. Since he graduated with honors from Harvard Law School in 1951, Landes, a fourth-term member in the New York State Legislature, has been practicing law with great success—but without benefit of license.

They got James D'Adamo, too. For more than 20 years, D'Adamo has been using naturopathy to cure or help thousands of people with a wide range of ailments. Unfortunately, naturopathy is a school of healing that's not approved by the American Medical Association. Since D'Adamo lacked the blessings of AMA-endorsed education, he never learned that many of the patients he cured were incurable and many he helped were beyond help. So they hauled D'Adamo through the courts and made him spend thousands of dollars for legal help.

Now please don't confuse these two episodes (or hundreds of other cases of harassment of nonconformist practitioners of healing arts) with featherbedding. That malodorous practice is the effect of labor unions trying to save jobs for their members—laborers. The cases of Landes and D'Adamo stem from the American Bar Association, the lawyers' union, and the American Medical Association, the doctors' union, trying to save jobs for their members, lawyers and doctors—not laborers.

Since lawyers and doctors are higher-class folks than laborers, it stands to reason that they should have more powerful influence on law enforcement. So in most states it's unlawful for you to get legal advice or a cure for an ailment from somebody who's not a member of the club.

Now let's talk of licensing electronics engineers. That might not be a bad idea. Engineers have certainly had enough bad breaks, so it might be appealing for us to form some sort of protective club with licensing powers and great influence on the law.

Then, if anybody who's not in our club develops a significant product—especially one that threatens us competitively—we'll haul him into court. Our problems will be over.



A handwritten signature in cursive script, reading "George Rostky".

GEORGE ROSTKY  
Editor-in-Chief



# THE GREAT 4K STATIC RAM RACE

In a world of claims and counter-claims, one thing is clear. EMM SEMI is still in the lead. Of course, we not only had a healthy head start, but we field a whole family of 4K static RAMs.

We *delivered* the industry's first 4K static RAM in 1975, a full year and a half before anyone else. We are now delivering 7 basic static RAM types with many versions

of each, and producing them at a greater monthly rate than our nearest competitors combined.

By now we have more 4K static RAMs operating in a wider range of customer equipment than anyone else in the semiconductor memory business — from 10 Megabyte IBM add-on memory systems to hobbyist microprocessor kits.


Whatever your application, from mass storage to telecommunications, from medical electronics to toys and games, chances are there's an EMM SEMI static RAM just right for you. Please call or write today for full details — and ask about our byte oriented RAMs, too.

**Memory at work** **EMM SEMI, Inc.**

a subsidiary of Electronic Memories & Magnetics Corporation • 3883 N. 28th Avenue, Phoenix, Arizona 85107 • (602) 263-0202

CIRCLE NUMBER 38





## True RMS to DC isn't a big deal anymore.

The AD536 true RMS to DC converter is a monolithic IC in a 14-pin ceramic DIP. Complete and self-contained. Just plug it in and forget about external trims.

The chip is laser wafer trimmed for maximum accuracy

and stability. That means an accuracy of  $\pm 2\text{mV} \pm 0.2\%$  of reading with high crest factor and excellent bandwidth. And besides the linear DC output, you get a dB output with a 60dB dynamic range for free.

Only \$9.95 in 100s. Now that is a big deal.

For specs and samples call Doug Grant at (617) 935-5565. Analog Devices, P.O. Box 280, Norwood, MA 02062.


 **ANALOG  
DEVICES**

The real IC converter company.

Analog Devices, Inc., Box 280, Norwood, MA 02062 East Coast: (617) 329-4700; Midwest: (312) 894-3300; West Coast: (213) 595-1783;  
Texas: (214) 231-5094; Belgium: 031/37 48 03; Denmark: (02) 845800; England: 01/94 10 46 6; France: 686-7760; Germany: 089/53 03 19; Japan: 03/26 36 82 6; Netherlands: 076/879 251;  
Switzerland: 022/319704; and representatives around the world.

CIRCLE NUMBER 39

# LET'S PUT OUR HEADS TOGETHER.




The Facit 4540 Serial Matrix Printer has already made a name for itself with its standard 250 characters a second - all crisp, fullbodied and perfect throughout the 500 million characters service life of the printhead. Versatility comes from the rare 9x9 dot matrix, and the Facit 4540 offers a genuine 100% duty cycle and entire elimination of adjustment and lubrication.

The whole secret is in the unique printhead and its microprocessor controlled impact printing mechanism.

Integration of mechanics and electronics has made Facit peripheral data products world famous.

Facit 4540 extends this tradition. So let's put our heads together. To make your systems more efficient, more competitive and more in demand.



*Facit 4540 Serial Matrix Printer with the unique printhead.*




**FACIT**  
**DATA**  
**PRODUCTS**

FACIT-ADDO INC., 66 FIELD POINT RD, GREENWICH, CONN. 06830. (203) 622-9150. TELEX 96-5998.

CIRCLE NUMBER 40

# Now...LOOK at GPIB Activity:



Announcing *visible* GPIB communications at the touch of a button: the new TEKTRONIX DF2 Display Formatter. The DF2 monitors *and displays* activity on the GPIB bus as disassembled instructions in familiar IEEE 488 mnemonics.

Touch another button, and information is displayed in ASCII format, with further character decode in hex, binary, or octal—all on the same display.

**The DF2 Display Formatter works with our 7D01 Logic Analyzer: for the first time, you have a complete logic analysis tool that can deal specifically with GPIB activity. And that means GPIB design and integration is now faster. Simpler. And more convenient.**

## Designing A Controller? Use The DF2!

It's plug-to-plug compatible with GPIB controllers so you monitor commands at a glance.

## Designing Talkers/Listeners? Use The DF2!

Now it's simple to make sure talkers are responding properly to the controller and listeners are receiving correct data.

## Integrating GPIB Systems? Use The DF2!

You know monitoring and displaying bus events and their sequence are essential for effective integration of multi-vendor GPIB products. Now you have the essential tool: use the DF2 to analyze any specific data transaction you wish.

You'll also find the DF2 a powerful service tool. Observe GPIB bus activity to simplify troubleshooting and keep your system up and running properly.


The DF2 Display Formatter also provides displays in timing and mapping modes as well as state tables in binary, hexadecimal, or octal notation. Combined with the DF2, our 7D01 Logic Analyzer is the most comprehensive and versatile logic analysis tool available today. And because the 7D01 Logic Analyzer System is compatible with *any* TEKTRONIX 7000 Series oscilloscope, you may already own part of a Logic Analyzer package.

TEKTRONIX Logic Analyzers: we call them The Versatile Ones.

Now, with the unique and exclusive DF2 Display Formatter, they're more versatile than ever.

And GPIB is a lot more visible.

Call your local Tektronix Field Engineer for more information about the DF2. Or write Tektronix, Inc., P.O. Box 500, Delivery Station 76-260, Beaverton, Oregon 97077. In Europe, write Tektronix Limited, P.O. Box 36, St. Peter Port, Guernsey, Channel Islands.



**Tektronix**  
COMMITTED TO EXCELLENCE

**TEKTRONIX Logic Analyzers: The Versatile Ones**

### Let 4-bit microcomputers do the simple jobs. They cost less than 8-bit units and offer almost as much processing power. The catch? They may not be as fast.

A 4-bit dedicated microcomputer offers a less expensive alternative to an 8-bit processor—and often without any performance penalty. For example, on a single chip, the MN1400 4-bit family of microcomputers includes an ALU, a ROM, a RAM, I/O ports, a counter/timer and a clock generator—for less than half the cost of an 8-bit system. However, the 4-bit units may not operate as fast as 8-bit processors, due to word-size limitations among other things.

The MN1400 family, except for the PMOS model, operates from a 5-V supply, has a 10- $\mu$ s instruction cycle and uses 8-bit instruction words and 4-bit data words. Eight versions of the microcomputer are available, the MN1400, 1402, 1403, 1404, 1405, 1430, 1498 and 1499 (Fig. 1). The MN1400 and 1402 have internal ROM capacities of 1024 and 768 bytes, and on-chip RAM sizes of 64 and 32 nibbles, respectively. (A nibble is four bits, or half a byte.) The 1498 and 1499 have no internal ROM but can address 1024 or 2048 bytes, respectively. Both units have an internal RAM of 64 nibbles. The other four versions, including the lone PMOS circuit, offer various combinations of ROM and RAM.

The MN1499, designed to evaluate MN1400 system prototypes, comes in a 64-pin ceramic package so that all memory address and data lines are accessible without tying up any of the I/O ports. (The various combinations of I/O ports available on all the MN1400 devices are listed in Table 1, which also summarizes many of the other  $\mu$ C features.)

Both the memory and I/O lines of any MN1400 part operate asynchronously at any speed, up to the maximum data-transfer rate of the memory circuits. The counter/timer available on the MN1400 and 1499 counts up to 256 and is software-programmable. Depending on the model, as many as 75 instructions are available to the programmer, including 18 data-transfer commands, 18 arithmetic and logic instructions, nine I/O commands, and 30 program and machine-control commands.

Since an MN1400-based microcomputer forms a complete system, to understand its operation you should examine its individual sections and know

what's in each one (Fig. 2):

1. Arithmetic and logic unit: an ALU, a 4-bit accumulator, a temporary register and various flag registers.
2. Data-memory section: a RAM, and X and Y registers.
3. Program-counter section: a program counter, a mask-programmable ROM and a subroutine stack.
4. Instruction-decoder block: an instruction register and an instruction-decoding programmable-logic array.
5. Counter/timer section: an 8-bit programmable counter/timer and two input lines, SNS1 and  $\overline{\text{CSLCT}}$ .
6. I/O block: input ports A and B, output ports C, D and E, and three lines, SNS0, SNS1 and  $\overline{\text{RST}}$ .
7. Clock generator block: an internal clock generator and an input line, OSC, that permits an external clock signal to be input.

#### The microcomputer works like this. . .

All mathematical and logic operations are performed by the ALU, including addition, Boolean logic, straight transfers, and incrementing. They are performed on two 4-bit binary-data words and the results are stored in the accumulator, the Y register or the temporary register, depending on the instruction.

The accumulator in the ALU block is the MN1400's primary working register. The 4-bit temporary register, TEMP, is for storing intermediate data during program execution. It is not program-addressable and is not really "seen" by the programmer.

Three flag flip-flops are used to indicate various conditions due to arithmetic or logic operations. A carry flag is set when a carry is generated and reset when a carry is not generated during an operation. The CF can be controlled either by an ALU operation or by direct software command.

A zero flag (ZF) is set whenever the result of an operation is zero, and is reset if the result is not. A program-status flag (PS) is a one-bit flag that is controlled by software, set by the SP instruction and reset by the RP command. (For a list of the instructions, see the box on software, p. 62.)

Some multifunction instructions such as LIC, LDC, STIC and STDC increment or decrement the contents of the Y register after data transfer. And the results

---

**Bill Bottari**, Product Manager, and **Terry Kobayashi**, Product Specialist, Panasonic, 1 Panasonic Way, Secaucus, NJ 07094.

# Table 1. Comparison of microcomputer features

Features		Device	MN1400	MN1402	MN1403	MN1404	MN1405	MN1430	MN1498	MN1499
Package size (DIP)			40-pin	28-pin	18-pin	16-pin	40-pin	40-pin	40-pin	64-pin
Process technology			NMOS	NMOS	NMOS	NMOS	NMOS	PMOS	NMOS	NMOS
Number of instructions			75	57	50	48	75	75	66	75
Subroutine stack			2 level	2 level	2 level	2 level	2 level	2 level	2 level	2 level
Instruction memory size	On chip		1024 x 8 bits	768 x 8 bits	512 x 8 bits	512 x 8 bits	2048 x 8 bits	1024 x 8 bits	—	—
	External		—	—	—	—	—	—	1024 x 8 bits	2048 x 8 bits
Data memory size			64 x 4 bits	32 x 4 bits	16 x 4 bits	16 x 4 bits	128 x 4 bits	64 x 4 bits	64 x 4 bits	64 x 4 bits
On-chip counter/timer			8 bits	—	—	—	8 bits	8 bits	—	8 bits
Power-on reset circuit			Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Input ports	Parallel lines		4 bit x 1	4 bit x 2	4 bit x 1	4 bit x 1	4 bit x 2	4 bit x 2	4 bit x 1	4 bit x 2
	Sense lines		2	2	1	1	2	2	1	2
Output ports	Parallel lines		4 bit x 1	4 bit x 2	4 bit x 1	—	4 bit x 1	4 bit x 1	4 bit x 1	4 bit x 1 5 bit x 1
	PLA lines		8 bit x 1	—	—	—	8 bit x 1	8 bit x 1	—	—
	Discrete lines		12 bit x 1	5 bit x 1	4 bit x 1	6 bit x 1	12 bit x 1	12 bit x 1	9 bit x 1	12 bit x 1
Supply voltage			5 V	5 V	5 V	5 V	5 V	-15 V	5 V	5 V
Instruction cycle time			10 $\mu$ s	10 $\mu$ s	10 $\mu$ s	10 $\mu$ s	10 $\mu$ s	15 $\mu$ s	10 $\mu$ s	10 $\mu$ s


of incrementing or decrementing leave a zero in the Y register, which sets the ZF flip-flop.

In the data-memory block the RAM space is divided into four files, with 16 words in each file for the 64-word RAMs (Fig. 3). Two bits of the 3-bit X register select one of the four files. The value in the 4-bit Y register selects which of the 16 words will be accessed. Thus, all 64 RAM locations are addressed by the X and Y registers.

However, four locations (X = 0, Y = 0 to 3) can also be addressed directly by the LD and STD instructions. The former transfers the memory contents to the accumulator and the latter does the reverse. When the X register isn't used to specify a file, it is used to hold the three least significant bits of the instruction, when commanded to by the LX instruction. The output of the 4-bit Y register can also be output to a decoder that controls output port C, thus permitting I/O control.

The program-counter (PC) section includes an 11-bit counter and two 11-bit program-stack registers. The value held in the PC addresses the mask-programmable memory, which has up to 2048 locations. Unless the instruction is JMP, CAL, RET, or a conditional branch, which alter the contents of the program counter, the contents of the PC are incremented by one every instruction cycle. The CAL command saves the PC value in the stack so that when the routine being called is finished, the computer can return via the RET command to the point in the program just after the CAL command. Up to two addresses can be stored in the subroutine stack.

A conditional branch command sets the least significant eight bits of the program counter to one of 256 memory locations on the specified page of ROM. If the instruction following the branch command is not



1. These four pinout versions of the MN1400 microcomputers have varying degrees of I/O capability as well as different amounts of on-chip RAM and ROM.

## Software for the microcomputers

The instruction set for the MN1400 series of microcomputers consists of 75 commands, all of which are available on the MN1400 and 1499. The MN1402 can use only 57 of the instructions and the MN1498 can use 68 commands. All 75 are listed in the accompanying table, and each represents an 8-bit word, except for the branch commands, which require a second byte for the branch address.

Three addressing modes are available to the microcomputer programmer:

- Direct—the two least significant bits of the STD or LD instruction contain the exact memory address holding the data.
- Register indirect—the X and Y registers contain the address of the data.
- Immediate—the instruction contains the data in the four least significant bits.

A programming model of the processor consists of the RAM, ROM and associated status and X and Y registers. Learning how to take advantage of the directly accessible RAM addresses can aid your programming efforts since these locations can be used as high-speed buffers or temporary memory for storing intermediate results.

The first four locations of the RAM's lowest bank are directly addressable via instructions and are used for high-speed storage. The other locations are used for storing data, holding the flag bits, and storing the address vectors for ROM routines.

There are only slight differences in the software for each of the four microcomputers. The MN1402 and 1498 instruction sets are subsets, of course, of the 75 commands. The 1402s lack the counter/timer instructions and several data-movement commands since it is the most I/O limited of the four  $\mu$ Cs. The 1498 lacks the instructions used to manipulate the internal ROM and several I/O commands.

For programs that use subroutines, the unconditional jump (JMP) and call (CAL) instructions can summon a subroutine by setting the contents of the program counter equal to the starting address of the desired routine. The CAL instruction, though, marks a return spot by storing the current contents of the program counter in the two-level stack. After the subroutine is executed, a return (RET) instruction will remove the return address from the stack and replace it in the program counter so that the processor will return to the normal program flow at the instruction following the CAL command.

The internal ROM is divided into 256-word pages, and branch instructions use the last eight bits in the program counter to divert program flow within the current page. If the flow must be diverted from the current ROM page, a JMP instruction must be used to set all 11 bits of the program counter.


Mnemonic	Hex op code	Description
<b>Data transfer instructions</b>		
L	0D	Load accumulator with contents of memory location addressed by X and Y registers.
LD	2a	Load accumulator with contents of memory location addressed by 2-bit immediate field.
LI	5d	Load accumulator with contents of immediate field.
LIC	0E	Load accumulator with contents of memory location addressed by X and Y registers and increment contents of Y register.
LDC	0F	Load accumulator with contents of memory location addressed by X and Y registers and decrement contents of Y register.
ST	0A	Store contents of accumulator in memory location addressed by X and Y registers.
STD	2(4+a)	Store contents of accumulator in memory location addressed by 2-bit immediate field.
STIC	0B	Store contents of accumulator in memory location addressed by X and Y registers and increment contents of Y register.
STDC	0C	Store contents of accumulator in memory location addressed by X and Y registers and decrement contents of Y register.
LX	3d	Load X register with contents of immediate field.
LY	6d	Load Y register with contents of immediate field.
TAX	01	Transfer contents of accumulator to X register.
TAY	03	Transfer contents of accumulator Y register.
TYA	02	Transfer contents of Y register to accumulator.
TACU	19	Transfer contents of accumulator to most significant 4 bits of counter time.
TACL	18	Transfer contents of accumulator to least significant 4 bits of counter/timer.
TCAU	1B	Transfer contents of the most significant 4 bits of the counter/timer to accumulator.
TCAL	1A	Transfer contents of the least significant 4 bits of the counter/timer to accumulator
<b>Arithmetic and logic instructions</b>		
AND	04	The contents of the accumulator are ANDed with the contents of the memory location addressed by X and Y registers.
ANDI	7d	The contents of the accumulator are logically ANDed with the contents of immediate field.
OR	05	The contents of the accumulator are Inclusive ORed with the contents of the memory location addressed by X and Y registers.
XOR	06	The contents of the accumulator are Exclusive ORed with the contents of the memory location addressed by X and Y registers.
A	07	Add with carry the contents of memory location addressed by X and Y registers to the accumulator.
AI	8d	Add without carry the contents of the immediate field to the accumulator.

Mnemonic	Hex op code	Description
<b>Arithmetic and logic instructions (cont'd)</b>		
CPL	08	The contents of the accumulator are complemented. Binary 1's complement.
C	09	Compare contents of accumulator with contents of memory location addressed by X and Y registers (two's complement arithmetic). The accumulator remains unchanged.
CI	9d	Compare contents of accumulator with contents of immediate field (two's complement arithmetic). The accumulator remains unchanged.
CY	Ad	Compare contents of Y register with contents of immediate field (Exclusive-OR). The Y register remains unchanged.
SL	1E	Shift the contents of the accumulator left. The least significant bit becomes 0.
ICY	2C	Increment contents of Y register by one.
DCY	2D	Decrement contents of Y register by one.
ICM	2E	Increment contents of memory location addressed by X and Y registers by one.
DCM	2F	Decrement contents of memory location addressed by X and Y registers by one. (Two's complement subtraction.)
SM	Bd	Set bit(s) in contents of memory location addressed by X and Y registers. Specific bit(s) designated by 4-bit immediate field.
RM	Cd	Reset bit(s) in contents of memory location addressed by X and Y register. Specific bit(s) designated by 4-bit immediate field.
TB	Dd	Test bit(s) in contents of accumulator. Specific bit(s) designated by 4-bit immediate field.
<b>I/O instructions</b>		
INA	14	Read information present on A input port and transfer to accumulator.
INB	15	Read information present on B input port and transfer to accumulator.
OTD	12	Write and latch contents of accumulator and PS to D output port.
OTMD	11	Write and latch contents of memory location, addressed by X and Y registers, and PS to D output port.
OTE	10	Write and latch contents of accumulator to E output port.
OTIE	Fd	Write and latch contents of immediate field to E output port.
RC0	16	Reset C output line addressed by register.
SC0	17	Set C output line addressed by Y register.
CC0	13	Reset C output (CO0 through CO12).
<b>Control instructions</b>		
RC	28	Reset CF flip flop.
RP	29	Reset PS flip flop.
SC	2A	Set CF flip flop.
SP	2B	Set PS flip flop.
BS0	3B mm	On SNS0 high branch to current page address specified by the second byte.

Mnemonic	Hex op code	Description
<b>Control instructions (cont'd)</b>		
BS1	3D mm	On SF set branch to current page address specified by the second byte.
BS01	3F mm	On SNS0 high and/or SF set branch to current page address specified by the second byte.
BSN0	3A mm	On SNS0 low branch to current page address specified by the second byte.
BSN1	3C mm	On SF reset branch to current page address specified by the second byte.
BSN01	3E mm	On SNS0 low and SF reset branch to current page address specified by the second byte.
BP	E9 mm	On PS set branch to current page address specified by the second byte.
BC	E5 mm	On CF set branch to current page address specified by the second byte.
BZ	E3 mm	On ZF set branch to current page address specified by the second byte.
BPC	ED mm	On PS and/or CF set branch to current page address specified by the second byte.
BPZ	EB mm	On PS and/or ZF set branch to current page address specified by the second byte.
BCZ	E7 mm	On CF and/or ZF set branch to current page address specified by the second byte.
BPCZ	EF mm	On PS, CF and/or ZF set branch to current page address specified by the second byte.
BNP	E8 mm	On PS reset branch to current page address specified by the second byte.
BNC	E4 mm	On CF reset branch to current page address specified by the second byte.
BNZ	E2 mm	On ZF reset branch to current page address specified by the second byte.
BNPC	EC mm	On PS and CF reset branch to page address specified by the second byte.
BNPZ	EA mm	On PS and ZF reset branch to current page address specified by the second byte.
BNCZ	E6 mm	On CF and ZF reset branch to current page address specified by the second byte.
BNPCZ	EE mm	On PS, CF and ZF reset branch to current page address specified by the second byte.
JMP	4p mm	Unconditional 2 k program memory jump. The contents of the program counter is substituted with 11-bit direct address data (3 bits 1st byte, 8 bits 2nd byte).
CAL	4(8+p) mm	Unconditional 2 k program memory jump. The contents of the program counter is substituted with 11-bit direct address data (3 bits 1st byte, 8 bits 2nd byte). Return address is stored in the stack.
RET	1F	Return from subroutine. The contents of the stack is substituted into the program counter.
EC	1D	Enable counter/timer by setting E/D flip-flop.
DC	1C	Disable counter/timer by resetting E/D flip-flop.
NOP	00	No operation.

Notes: a = 2-bit data RAM address d = 3 or 4 bit data quantity mm = 8-bit instruction memory address p = 3-bit instruction memory page selector.

MN1400 SYSTEM BLOCK DIAGRAM




Symbols


Abbreviations

MPX	Multiplexer
L	Latches
C	Comparing circuit
S	Synchronizing circuit
G	Logical gates
ROM	Instruction Read Only Memory
PC	Program counter
STACK	Subroutine stack register
SP	Stack pointer
IR	Instruction register
INSTRUCTION PLA	Programmable instruction decode circuit
RAM	data RAM
X	X register
Y	Y register
4-12 DEC	Decoder. 4-bit data select one of 12 latches
ALU	Arithmetic logic unit
T/C	"Truth or Complement" circuit which complements or straight transfers data under program control
A	Accumulator
TEMP	Temporaty register. This register is not program addressable and is only used for the internal execution of program.
PS	"Program status" flag
CF	"Carry" flag
ZF	"Zero" flag
PLA	Output PLA which performs 5-bit to 8-bit data conversion
COUNTER	Programmable 8 bit counter/timer
	UP: Upper, most significant 4 bits of it
	LW: Lower, least significant 4 bits of it
E/D	Enable/disable counter/timer flip-flop
SF	Sense flip-flop
CLOCK GEN	Clock generator

2. The internal architecture of the four microcomputers looks like a complete computer system. Not only does the unit come with its RAM and ROM, but also all but one version has an 8-bit counter/timer.



3. On-board RAM space is divided into four banks of 16 locations. Three bits from the X register determine the bank and the four Y-register bits determine the specific word from the 16 words in the memory bank.



4. Four different types of I/O ports are available on MN1400-family microcomputers. The A and B ports are dedicated 4-bit input ports (a), the C port offers 12 individually controllable output lines (b), the D port uses a PLA to decode a 5-bit input into an 8-bit output (c), and the E port is a simple 4-bit latched output (d).




on the current page of memory, the JMP instruction is used to change pages after a branch instruction.

During normal operation, the instruction-decoder block performs most of the processor-control functions. A fetched instruction is stored in the instruction register and is then decoded by a programmable-logic array to generate the appropriate control signals.

### Counter and ports give flexible control

The programmable counter/timer included on four of the eight microcomputer chips consists of two cascaded 4-bit sections. The four least significant bits, LW, and the four most significant bits, UP, can be set in sequence by data-transfer commands to shift data from the accumulator to the counter/timer. To enable the counter/timer, the E/D flip-flop of the counter/timer section must be set by using an EC instruction. To disable the unit, just reset the E/D flip-flop with a DC instruction.


When the count value in the counter/timer overflows, it sets its SF flip-flop. The state of the SF flip-flop can be tested by several of the conditional branch instructions. When they detect the flag is set, they




5. By sensing switch closures on the A input port, the MN1400 microcomputer can easily control a solenoid connected to one of the port-C output lines via software.

Program (Hex)	ROM Address	Instruction Code	Label	Mnemonic	Operand	Operation
	000	60		LY	0	Y←0
	001	14	ST	INA		A←A-port
	002	E301		BZ	ST	Branch to ST when ZF=1
	004	92		CI	2	} Branch to ST when $A \geq 2$
	005	E501		BC	ST	
	007	14	L1	INA		A←A-port
	008	D2		TB	2	$A \wedge 2$
	009	E307		BZ	L1	Branch to L1 when ZF=1
	00B	17		SCO		C-port(0)←1,
	00C	14	L2	INA		A←A-port
	00D	91		CI	1	} Branch to L2 when $A < 1$
	00E	E20C		BNZ	L2	
	010	14	L3	INA		A←A-port
	011	D1		TB	1	$A \wedge 1$
	012	E210		BNZ	L3	Branch to L3 when ZF=0
	014	16		RCO		C-port(0)←0
	015	4001		JMP	ST	Jump nonconditionally to ST

6. Flow-charting the solenoid control is straightforward (a). The control program (b) makes minimal use of the



processor's computational power and logic decision capability to turn the solenoid on or off.



7. **Controlling the operation of a major appliance** such as a washing machine is well within the capabilities of the MN1400. It probably will even have power to spare for extras such as a clock and display controller.

**Table 2. Washing machine sequence**

Fully automatic operation
Water supply starts when the start switch is pushed. Processor monitors the water level. Water supply shuts off at predetermined level. Washing starts, continues for t minutes. Wash cycle ends. Water is drained from the washer. Fresh water fills the washer. Processor monitors the water level. Water supply shuts off at predetermined level. Rinse cycle for t minutes. Water is drained from the washer. Water is added to washer. Washing recommences for t minutes. Water is drained from the washer. Washer goes into spin cycle to remove major moisture. Washer shuts off.
Wash only
Water supply starts when start switch is pushed. Processor monitors the water level. Water supply shuts off at predetermined level. Washing starts, continues for t minutes. Water is drained from the washer.
Rinse only
Water is added to the washer. Water is drained as new water is added. Water is drained from the washer. Washer stops.

## A step-by-step process

Developing a program for a one-chip microcomputer requires a great deal of caution: Once the chips are made, you're stuck with the algorithm built in. Constructing the program step-by-step can help minimize the chance of error. A typical sequence for program development is shown in the accompanying figure, and can be summarized by the following eight steps:

1. Organize the inputs, outputs and RAM assignments.
2. Develop the flow chart for the desired program.
3. Generate the first sequence of assembly mnemonics for the ROM.
4. Prepare a paper tape or card-deck listing of the mnemonics.
5. Assemble the source code into an object-code listing and try to eliminate any errors that appear.
6. Simulate the final system by using the paper tape or card deck to program an emulator version of the system.
7. Debug the program and prepare the final code tape or deck to be supplied to Panasonic for final ROM patterns.
8. Give production go-ahead after final evaluation of the chips. Prototypes are produced and supplied by Panasonic for final evaluation.

can divert the program flow. External events can trigger the counter by causing low-to-high transitions on the SNS1 input pin. Each transition that occurs when the CSLCT pin is held low increments the counter by one.


The I/O block of the MN1400 family devices is one of the most flexible and extensive to be found in a 4-bit device (Fig. 4). Depending upon the model, you get the following:

- Two 4-bit parallel inputs, ports A and B.
- Two sense inputs, SNS0 and SNS1.
- Two control inputs, CSLCT and RST.
- One 4-bit parallel output, port E.
- One 8-bit PLA decoded output, port D.
- Twelve individually programmable output lines, port C.

Ports A and B, noted in Fig. 4a as A10-3 and B10-3, respectively, handle dedicated input. The data from port A are transferred to the accumulator by an INA instruction and data from port B by an INB. The sense lines can be used to control program flow—conditional branches can be executed depending on the input level to the SNS0 pin. The input logic level on this line can be tested directly, without any signal preconditioning.

The SNS1 input can be used in two ways, depending on the condition of the CSLCT pin. When high, the Control Select (CSLCT) pin permits a high signal on the SNS1 pin to set the SF flip-flop. When CSLCT is low, the counter/timer is enabled and transitions on the SNS1 input toggle the counter/timer.

Port E, the dedicated 4-bit output port, lines E00



8. To develop the program that controls the washing machine, the first step is, of course, to flow-chart the basic

operation. From these flow-charts, the details of each operating mode can be worked out.

to E03, latches the output of the accumulator when an Output to port E (OTE) instruction is executed. Data contained in an instruction can also be latched into the port by executing an Output immediate to port E (OTIE) command. The PLA decoded D output port, lines D00 to D07, accepts a 5-bit input word, latches the data, then decodes the data by using a mask-programmed PLA. The 5-bit input consists of the four bits of data from either the RAM or the accumulator and the PS flag bit. An OTD instruction transfers the accumulator contents and the PS flag into the D port latches, while an OTMD command transfers the RAM location's contents and the flag bit to the port.

Port C consists of 12 discrete-output lines, each of which can be set or reset under program control. An SCO instruction forces the output selected by the Y register to go high while an RCO instruction brings the selected line low. All 12 lines are reset if a CCO command is used.

To time the MN1400 microcomputer systems, you can use the on-chip clock or connect an external signal source to the OCS pin. Either a simple resistor/capacitor combination or a crystal can be used for the on-chip oscillator. If you use an external clock, it should operate at about 300 kHz, maximum.

A single-phase clock signal is fed into the clock circuit on the chip and broken down into three nonoverlapping phases, CP<sub>1</sub>, CP<sub>2</sub> and CP<sub>3</sub>. A machine cycle consists of all three signals going through their phases. An instruction cycle consists of a machine cycle plus the CP<sub>1</sub> phase of the clock—the instruction-fetch and execute times are included. If the instruction-fetch time is omitted, the instruction will take only 10  $\mu$ s to be executed.

### Get the processor on-line


Now that you know what makes your MN1400-based system tick, you can get it working. Many hardware and software tools are available to simplify program development and hardware debugging. For hardware development, the main tool is the MN1499, a microcomputer without any on-board ROM. For software development, Panasonic offers a cross-assembler (C support 1400), which runs on a Panasonic microcomputer system and an HS1400 hardware simulator.

The cross-assembler can generate object-code listings, possible-error statements, and a tape for hardware simulation. Able to run on several general-purpose large computer systems, the Fortran-based cross-assembler is available on card, paper tape or magnetic tape.

A complete development system based on the Panafacom PFL-16A microcomputer can be used with the cross-assembler to develop your system program and directly load the hardware simulator, which contains an MN1499. This evaluation unit is functionally identical to the MN1400 except that it requires external ROM.

However, the MN1499 evaluation circuit can also

# When you need meaningful resolution of both capacitance and loss...



# Why settle for half the answer?


The versatile Boonton Model 76A, an automatic 1 MHz capacitance bridge, solves the complete measurement problem with fully independent range selection or autoranging of both capacitance and loss. It has separate displays, automatic zero offset correction, continuously variable test level and true three-terminal measurement.

In addition to decade ranging of parallel capacitance from 2 to 2000 pF f.s. and conductance from 2 to 2000  $\mu$ S f.s., the Model 76A will compute the equivalent series capacitance and series resistance, equivalent parallel resistance, dissipation ( $\tan \delta$ ) and Q of the test specimen. And the Model 76A can also display any capacitance measurement as a deviation or as a percentage deviation against a previously entered and stored reference value.

Options include the 488 Bus Interface, BCD outputs and an internal programmable bias supply.

Now there's really no reason to settle for a bridge that gives half the answer. The Boonton 76A does it all.

For complete data and prices on the Model 76A, contact your nearest Boonton rep or write or call: Boonton Electronics, Rt. 287 at Smith Rd., Parsippany, N.J. 07054; (201) 887-5110.



help with program development:

- To interface to a static ROM with access times of 2  $\mu$ s or less, the address lines and the data lines of the MN1499 can be connected directly to the ROM lines.

- To simplify debugging, the MN1499 can be single-stepped through its instructions—just use the input RDY line in conjunction with the output SYNC line.

- The MN1499's PLA can be set up outside the chip because the D output port sends out the contents of the latches rather than an eight-line encoded signal.

To set up a working prototype system, you must combine the MN1499 or 1498 with a power supply, external ROM or PROM and the necessary control signals. A simple control application might require the microcomputer to control a solenoid. The circuit shown in Fig. 5 will be used and the program set so that the solenoid will be turned on only if SW<sub>1</sub> is closed first, then SW<sub>2</sub>. The solenoid will be turned off only if SW<sub>2</sub> is opened first and then SW<sub>1</sub> is opened.

The flow chart and the program for solenoid control are shown in Fig. 6. For the sequence control to function properly, the program first checks the input port to see if any of the switches are closed. If no switches are closed, the program loops back and checks the switches again. If any closed switches are detected, the program then checks to see if SW<sub>2</sub> is closed.

When the program checks the switch, it must make a decision—if SW<sub>2</sub> is closed, the program must loop back to the reading of the port and start over again; if SW<sub>2</sub> is open, it goes on to the next step and reads the input-port data to determine whether SW<sub>2</sub>'s line has changed state. The program then loops around the second read step until SW<sub>2</sub> is closed. Once the switch is closed, the program breaks out of the loop and drives the solenoid.

Once the solenoid is powered, the program starts another read-port sequence to check the switch status and to shut off the solenoid if the switches are opened in the proper sequence. If the switches aren't opened correctly, the solenoid stays on. When the proper sequence is detected, the program goes back to step 1 and waits for the switches to be closed in the proper sequence again.

But this solenoid application is very simple, and can easily be duplicated with several TTL packages. A more complex control application is a washing machine (Fig. 7). With a microcomputer to control all the functions and the over-all operation of the machine, reliability can be improved and eventually the cost can be reduced.

The typical operating sequence of a washing machine is outlined in Table 2. Operation can be split into three modes—fully automatic, wash only, and rinse only. The flow charts for all three are shown in Fig. 8. In each case, most of the operating sequence involves direct execution of a command and requires no decision, so the economics of using a microcomputer may be highly questionable unless the microcomputer is also used to perform auxiliary jobs such as controlling a display and a clock. ■■

# BENCHHA

**Before you design-in  
a Z-80, 6800 or 8085, compare it with  
the high performance R6500.**

Rockwell's R6500 delivers boosted performance and economics through its third-generation pipelined architecture with 13 powerful addressing modes, true indexing capability, complete decimal/binary arithmetic mode selection, on-chip clock and proven 2MHz performance. Prove it to yourself — Benchmark it!

R6500

# MARK IT!

## **R6500 offers innovative architecture and technology.**

The 8-bit R6500 is produced with N-channel, silicon gate, depletion load technology and innovative architecture. The result is smaller, faster chips to keep your system costs down and performance up.

A family of ten software compatible CPUs in 28- and 40-pin DIP packages give you the most cost-effective fit for your application. Prove it to yourself — Price it!

## **R6500 is designed for greater memory and I/O efficiency.**

Of the leading NMOS microprocessors, only the R6500 has 13 addressing modes and true indexing capability. More addressing modes coupled with an advanced instruction set makes programming the R6500 easy and efficient. Fewer program steps means lower memory cost and faster program execution.

R6500 memory-managed I/O eliminates performance bottlenecks associated with the separate I/O buses, I/O commands and register overhead required by other microprocessors.

A broad selection of memory, I/O and combination memory-I/O-timer circuits are available. And Rockwell is presently delivering the industry's first fully static 32K ROM — the R2332 — and the industry's fastest 32K ROM — the R2332-3.

## **SYSTEM 65 gets you started for less.**

SYSTEM 65 Microcomputer Development System is efficient and easy-to-use and is equipped with dual mini-floppies. It's priced at only \$4800.

ROM-resident SYSTEM 65 firmware features a two-pass assembler, text editor and symbolic debug/monitor package. Current loop, RS-232C, printer and scope sync ports are also provided. The optional USER 65 (User System Evaluator) module extends the power of SYSTEM 65 for in-circuit emulation.

Other design support includes KIM-1, TIM, timesharing cross-assembler, complete documentation and extensive applications engineering.



Industry researchers say the multiple-sourced 6500 outshipped the Z-80, 6800 and 8085 during the last quarter of 1977. Benchmark it!

For more information, contact your local Hamilton/Avnet distributor or write: D/727-C Microelectronic Devices, Rockwell International; P.O. Box 3669; Anaheim, CA 92803 or phone (714) 632-3729.



**Rockwell International**

...where science gets down to business

## Technology

**When one  $\mu$ P controls another,** the interface becomes the focal point. Base the boundary on an IEEE-488 general-purpose bus, and speed the bilateral flow of data.

When joining several microprocessor-based devices, you can solve the age-old problem of interfacing by using a general-purpose, interface-bus (GPIB) module. While the following design is aimed at an automated chemical-analysis experiment (Fig. 1), the underlying principles lend themselves to many other applications.

The system involves two microprocessor controllers. At the heart is a Tektronix GS 4051 graphic-display terminal—the master controller of the two microprocessors and the source of instructions for the second controller, an MCS 80 series microcomputer ( $\mu$ C). The MCS 80 has two major responsibilities: Handle the “handshaking” protocol requirements of the GPIB and maintain operational control of the experiment. The microcomputer system contains all power supplies, memory boards, memory-bus backplane, and several connector slots that are free for interfacing.

Design the GPIB module to plug into and operate from any memory-bus slot of the 8080-based  $\mu$ C. The interface then becomes a standard stock device available for general use.

### Proms hold addresses


In the GPIB interface, address recognition is accomplished through two 256-word fusible-link PROMs, IC<sub>1</sub> and IC<sub>2</sub> in Fig 2. The inputs to the PROMs are wired to the card-edge fingers corresponding to the memory-bus address lines, A<sub>2</sub> through A<sub>15</sub>. When previously selected address lines are asserted, the chips become qualified and their output lines go LOW.

The outputs are OR-wired together to develop the “chip-select-low” (CS) signal. Chip IC<sub>2</sub> is programmed with zero data in address 370 (all addressing is represented as octal numbers). All other memory locations are loaded to ONES, causing OR-wired outputs 9 through 12 to go LOW only when address 370 appears on address lines A<sub>8</sub> through A<sub>15</sub>.

Outputs 9 through 12 of IC<sub>2</sub> are wired to the chip-select inputs of IC<sub>1</sub>, which is programmed and wired to produce a LOW output when addresses 374 to 377 are selected on address lines A<sub>0</sub> to A<sub>7</sub>. This combined configuration causes the GPIB interface to appear as

---

**Kenneth A. Gertz**, Electronic Specialist, University of California, Lawrence Livermore Laboratory, Livermore, CA 94550.



1. **Hooking up  $\mu$ P-based equipment** calls for a general-purpose interface. Here a graphics-display terminal, itself  $\mu$ P-based, controls an MCS 80  $\mu$ C that, in turn, controls a chemical experiment.

a memory device addressed at memory-page 370, locations 374 through 377.


Out of the 8080, data flow from the memory-data lines 1 through 8 via IC<sub>3</sub>, then onto the GPIB data bus via ICs 4 through 7. Into the 8080, data flow from the GPIB data bus via ICs 4 through 7, and onto memory-bus input lines A through J via ICs 8 and 9.

Chip IC<sub>3</sub> is a versatile 8255 programmable peripheral interface, designed to be used primarily with the MCS 80. Here, the 8255 supplies eight latched outputs for data (PA<sub>0</sub> through PA<sub>7</sub>) and eight latched outputs for handshaking-control lines (PB<sub>0</sub> through PB<sub>7</sub>). To operate in this mode, you must program the 8255 to the output mode by loading its control word with the proper information. Loading the control-word address, 377 370, with a 244 will do.

### Selecting memory locations

Once peripheral-chip IC<sub>3</sub> is set in the output mode, you can load data or handshake information into the data registers by writing into the desired address





2. The general-purpose interface bus (GPIB) is designed around fusible-link PROMs (ICs 1 and 2), which recognize device addresses. Data from the  $\mu$ C to the bus flow through a programmable peripheral-interface chip (IC<sub>3</sub>). Data

from the bus into the  $\mu$ C flow through quad three-state receivers (ICs 4 through 7) and quad three-state multiplexers (ICs 8 and 9), which also handle the bus handshaking information.

location. For output data, load the memory-bus information into memory address 374 370. This places the data on outputs PA<sub>0</sub> through PA<sub>7</sub>. If the memory-bus information contains handshaking data, load it into location 375 370. This places data on outputs PB<sub>0</sub> through PB<sub>7</sub>.

ICs 4 through 7 are 3441 quad three-state transceivers, permanently enabled to allow the GPIB bus to follow the outputs of the 8255 (IC<sub>3</sub>). The receiver outputs of the 3441 chips always reflect the data states of the GPIB—a capability that becomes important when the display terminal places data on the GPIB bus. At such time, the receivers deliver the data directly to quad three-state-input multiplexers IC<sub>8</sub> and IC<sub>9</sub>.

Both the data and handshaking information are placed on the inputs of ICs 8 and 9. Which byte of

data gets placed onto the memory-input lines depends on the condition of address bit A<sub>0</sub>. If A<sub>0</sub> is HIGH, established by address 375 370, the handshaking information is placed on the memory-bus lines. If A<sub>0</sub> is LOW, the data at address 374 370 are placed on the memory-bus lines.


The 8080 instruction (input or output) determines whether data are sent to or received from the GPIB. When an output instruction appears, the 8255 chip places data on the GPIB bus. If an input instruction appears, data are read from the GPIB through ICs 8 and 9. The data and handshaking information are accessed via a flat-ribbon connector on the rear of the GPIB module. From here, the GPIB bus is cabled to the back of the computer chassis and wired to a standard GPIB 34-pin connector.

Remember that the outputs of the 8255 chip are latched. They will remain on the bus lines until the MCS 80 coding clears the device. Therefore, the bus must be released after each transfer operation by loading zeroes into the 8255 data buffers.

### Working out the protocol

The most important function of the 8080 code is to maintain the handshaking protocol for communication between the 8080 and the GS 4051. The coding also maintains the data-acquisition and peripheral control of the experiment. The code associated with the GPIB interface can be divided into address recognition, data input, and data output.

When idle, the MCS 80 runs in a monitor loop, looking for an Attention (ATN) signal asserted on the GPIB control lines. The signal is activated whenever the GS 4051 places an address command on the bus.



3. How the 8080 recognizes addresses: Routine REST<sub>1</sub> looks for ATN, which the 4051 terminal asserts when it supplies addresses for devices and operations.

The terminal must send out an address with every instruction to tell which device hanging on the bus is being instructed.

Once the program takes care of the initialization routines, it runs in the monitor loop, checking the GPIB for the ATN line at the routine labeled REST<sub>1</sub> (Fig. 3). First, the program executes a CALL ADRIN, and the eight control bits are read into the A register. If the attention line is not asserted, the program enters an EXIT routine that clears the A register, and returns to the REST<sub>1</sub> routine. The program remains in the idle loop until an ATN is recognized. Then it passes through the ATN check and continues on to the ADRIN coding.

### Two types of addresses needed

When the GS 4051 asserts the attention line, it supplies a primary and secondary address. The former address determines which device is receiving information, the latter which operation is being requested. The IEEE-488 standard defines specific protocol operations necessary to transfer this information across the bus (Fig. 4).


Once ATN is recognized, the program enters the DATAIN routine. The 8080 sets control signal NRFD HIGH, and NDAC LOW. The GS 4051 should send DAV to the bus. The 8080 will look for DAV only for an allotted length of time. If DAV doesn't appear within this period, an error condition is assumed and the search is aborted.

When DAV is recognized, the 8080 acknowledges by setting both NRFD and NDAC LOW. The  $\mu$ C then retrieves the data (primary address) from the eight data lines. As soon as the data are read, NDAC is set HIGH. The 8080 once again looks for DAV. If DAV is recognized in time, the program returns to the regular program sequence. Here, the 8080 checks the primary address to see if the 4051 is talking to the 8080 or to some other device on the bus.

If the primary address is the 8080's primary address, program flow continues to the REST<sub>2</sub> routine. CALL ADRIN is once again executed, this time in a search for the secondary address. If all the proper handshaking requirements are fulfilled in ADRIN, the program returns with the secondary address.

This secondary address can now be compared to all other valid available addresses. Each must be coded to perform a specific operation when called upon. When a secondary address is recognized, program flow enters the coding to execute that specific operation. If none of the secondary addresses match, an error condition is presented to signal an invalid secondary address.

Some GS 4051 commands may require parameter data to be sent after the secondary address. If so, the 4051 releases the attention line and places the data on the bus. When the 8080 is ready to accept the additional data, it calls the subroutine DATAIN. Notice that, without the ATN recognition section,



4. Expanded address-recognition routine and coding for handshaking control are spelled out in IEEE-488, the standard for interfacing programmable instruments.

DATAIN is identical to ADRIN. The handshaking requirements are exactly the same as those in the address-recovery program.

### The 8080 reverses its role

Up to now, the 8080 has acted as a listening device, receiving information from the GS 4051. However, there are times when the 4051 becomes the listener and the 8080 the talker. When the 4051 commands the 8080 to return data through the GPIB, the micro-computer sends the data back via the bus with DATAOT, a routine that handles all the handshaking responsibilities (Fig. 5).

In Fig. 5, the 4051 is expected to send a READ data request to the 8080. When the coding enters the DATAOT routine, the data to be sent are contained in the A register. Since the A register participates in the handshaking routines, the data are saved in memory locations until needed.

The 8080 then monitors the control lines for a legal condition. (NRFD and NDAC cannot both be HIGH.) Once the bus is legal, the data are recovered and placed on the eight data lines. The bus is then checked for NRFD HIGH, and DAV is sent LOW. The bus is once again checked, this time for an NDAC HIGH. Recognition of a HIGH completes the transfer operation, and clears the control and data lines. The program returns to its normal coding to see if more data must be sent.

Be careful when designing the interface. The 8255 peripheral chip can produce problems in the interface operation. For example, because of the latched outputs of the buffer registers, you must make sure the registers are cleared before leaving the subroutine.


With a 3446 bus transceiver, instead of the 3441, the data and control lines assert to the LOW state whenever the control word is loaded. This occurs because the 8255 ZEROs its output registers whenever the control word is loaded. Replacing the 3446 with the 3441 variety corrects the problem.)

The GS 4051 sometimes requires special treatment by the 8080 software package—for example when the 4051 sends out a PRINT statement. Since the terminal converts the primary and secondary addresses into listen addresses, special coding is required for the 8080 to recognize them.

The PRINT statement calls for timing characteristics different from some other instructions'. When the address information is on the bus, the attention lines stay asserted for more than 800  $\mu$ s. A time-out error will occur during data recovery unless you code to wait for the ATN to go away before the program proceeds to the DATAIN routine. ■■


### Acknowledgments

A special thanks to Eugene Fisher for his microcomputer-design expertise. The design described was performed under the auspices of the U.S. Energy Research and Development Administration, contract No. W-7405-Eng-48.



5. When the 8080 and 4051 exchange roles as the listener and talker, the handshaking control is assumed by the DATAOT routine.

# 8-Bit high-speed monolithic A/D



## Priced under \$100

### Off the shelf delivery:

<b>TDC-1002J</b>	<b>1000 ns</b>	<b>\$75 in 100's</b>
<b>TDC-1001J</b>	<b>400 ns</b>	<b>\$175 in 100's</b>

Two performance ranges—400 and 1000 ns conversion times: two price ranges for a wide variety of high-speed A/D applications.

Linearity is  $\pm 1/2$  of LSB. Nine clock periods per conversion. All output bits are ready one clock period after the status signal indicates "ready to convert." There are no missing codes—ever!

TDC-1001J and TDC-1002J are supplied in an 18-pin ceramic DIP package designed to operate at a commercial temperature range of 0° to 70° C.

For more information and complete specifications, call (213) 535-1831, or use this coupon.

#### TRW LSI Products

An Electronic Components Division of TRW, Inc.,  
P. O. Box 1125  
Redondo Beach, California 90278

**Please send data sheets on your 8-Bit A/D Converters.**

NAME \_\_\_\_\_

COMPANY \_\_\_\_\_

DIV/DEPT \_\_\_\_\_

MAIL CODE \_\_\_\_\_

ADDRESS \_\_\_\_\_

CITY \_\_\_\_\_

STATE \_\_\_\_\_

ZIP ED-1 \_\_\_\_\_

## **TRW** LSI PRODUCTS

...from a company called TRW

CIRCLE NUMBER 44


## Multiplying with a microcomputer

can be a drag. A simple multiplier/shifter can speed up signed 12-bit multiplications by a factor of 10 or more.

With two Am25LS14 serial/parallel multiplier chips, you can design a multiplier/shifter that will multiply much faster than 12 or 16-bit microprocessors. Multiplications that result in 24 or 32-bit numbers can take several milliseconds with a  $\mu$ P, and are often followed by time-consuming double-register shifts to obtain fixed-point scaling. But a high-speed multiplier/shifter peripheral can quicken the process by more than an order of magnitude.

Although designed to work with the PACE microprocessor, the peripheral can easily be adapted to other 12 to 16-bit computers. Using fewer than 20 ICs, the circuit of Fig. 1 performs a 12-bit signed two's

**Anthony Kolodzinski**, Staff Electronics Engineer, Fairchild Space & Defense Systems, Syosset, NY, and **David Wainland**, Electronics Engineer, FAA/NAFEC, Atlantic City, NJ. Both were employed at the Naval Surface Weapons Center, Silver Spring, MD, when the article was written.



1. Four major building blocks form the core of a multiplier/shifter. Letters a, b, c, and d refer to the more detailed diagrams in Fig. 5.

complement multiplication, and is capable of shifting the 24-bit product. The whole operation is executed under software control and takes around 100  $\mu$ s.

The multiplier/shifter uses serial multiplication, that is, the Y value is multiplied with the X value by serially shifting the Y value, one bit at a time, into the multiplier chips that hold the X value. While the Y value is being shifted into the multiplier IC, the 24-bit result gets shifted from the multiplier to the Y register, replacing the Y value. The multiplier chip calculates the product with a technique called Booth's Algorithm (see box).

The PACE timing signals (Fig. 2) control the operation over a common data/address and I/O bus, which transmits address and channel information to the decoders (Fig. 3). The data are latched when the signal BNADS occurs. A channel-decoder output CHN; and device decoder output, DEV 10 are Nanded to BIDS to provide an enable pulse that reads data into the PACE from a peripheral. A similar circuit, using the signal BODS, provides an enable pulse to output data to a peripheral. All control signals are generated by software commands.

The multiplier/shifter works in the following sequence (Fig. 4):

1. The X value is loaded into the multiplier/shifter from the computer (under software control).

2. The Y value is loaded from the computer (under software control).

3. The number of shifts, N, required to do the multiplication and then the scaling is loaded from the computer (under software control).

4. The multiplication is carried out, the result is placed into the register and the result is scaled or shifted (under internal control).

5. The result is loaded into the computer from the Y register/shifter (software controlled).

The Y register/shifter has several functions:

- It temporarily stores the Y value.
- It shifts the Y value to the X register/multiplier, least significant bit first, ready for the multiplication.
- It loads the result while shifting the Y value into the X register.

- It scales the result.

The main parts of the Y register/shifter are the shift registers (Am25LS22 chips) and flip-flop 1 (Fig. 5a).

## Whose algorithm?

Booth's algorithm is a technique that can reduce the number of operations required for multiplications. A computer multiplies by adding the multiplicand  $x$  as often to itself as the multiplier  $y$  indicates. But strings of ZEROs in the multiplier don't require any additions—only shifting. And strings of ONES can be expressed as  $2^{s+1} - 2^r$ .

For example, if  $y = 001110$ , then  $r=1$  and  $s=3$ ; so,  $y = 2^4 - 2^1$ . Instead of three additions, Booth's algorithm requires only one shift and one subtraction on the partial products.

Both the multiplier and the multiplicand are expressed by the algorithm in two's complement. This is possible for the multiplicand  $x$  because addition and subtraction logic are identical for unsigned, and two's-complement numbers. And for the multiplier  $y$ , the last operation is a subtraction if  $y$  ends in a string of ONES. So two's complement is the most logical format.

Normal binary "add and shift" multiplication is

performed by summing partial products of the form

$$\pi = \sum_{i=0}^{i=n-1} y_i \times 2^i$$

where  $n$  is the number of bits in  $y$ .

If  $y_i$  is the  $i$ -th most significant bit of an  $n$ -bit multiplier,  $y_{n-1}$  is the sign bit, and  $X$  the multiplicand, then Booth's algorithm works as follows:

1. Compare  $y_i$  with  $y_{i-1}$ . If they are equal, add  $0x$ .
2. If  $y_{i-1}$  and  $y_i=0$ , subtract  $1x$  from the partial product (i.e. add the two's complement).
3. If  $y_i=0$  and  $y_{i-1}=1$ , add  $1x$  to the partial product.


While you now have a rough idea how Booth's algorithm functions, you may want to dig deeper, and work a few examples. You'll find them in Advanced Micro Devices' *Digital Signal Processing Handbook* on p. 23, in "Understanding Booth's Algorithm in 2's Complement Digital Multiplication" by John R. Mick.

Flip-flop 1 produces the pulses that clock the registers for parallel loading and serial shifting. The computer uses a decoder (Fig. 3) to select the proper points for loading and unloading the multiplier/shifter. When the lines DEV 10, CHN 1 and BODS go from low to high, the output of NAND gate 1 goes from high to low, and the parallel inputs of the registers are enabled. With the positive going-edge of the next PACE CLK pulse, the output, Q, of flip-flop 1 goes high, and causes the parallel inputs (DATA/ADDRESS bus, Fig. 5) to be loaded with the Y value.


As BODS goes low, the NAND gate-1 output becomes high, which returns the registers to serial operation, and forces the Q-output of flip-flop 1 to go low. After the X value and the shift number, N, are loaded into their proper locations, the shift pulse generator drives the preset and clear pins (P and C) of flip-flop 1.

### The answer comes in chunks


The shift registers are activated by the positive-going edge of the output pulse of flip-flop 1. When



2. The timing diagram of the PACE  $\mu$ P governs the operation of the multiplier/shifter.



3. The decoder's primary job is to distribute the 16 data bits between the low and high-bit ICs.



4. The various multiplier/shifter operations can be easily distinguished on a scale labeled in  $\mu$ s. The shaded operations are under internal timing, and a 60- $\mu$ s delay in the software assures that they are completed.

the whole operation is completed and the 24-bit product is ready, the computer requests the answer, low-order bits first. Lines DEV 10, CHN 3, and BIDS go high, the output of NAND-gate 2 switches from high to low, three-state output is enabled, and the low order bits of the result are presented to the computer. Then DEV 10, CHN 4 and BIDS go high, and present the high-order bits to the computer.

The X register/multiplier not only stores the X-value, but also performs the multiplication. The major components of the X register/multiplier are the two Am25LS14 multiplier ICs (Fig. 5b). The computer decodes the parallel-input controls of the multiplier chips, namely lines DEV 10, CHN 0, and BODS. When they switch high, NAND-gate 1's output goes low and X is loaded. When the shift pulses begin, the Y value is shifted in and the answer is shifted out.

To complete the multiplication and scaling, the shift-pulse generator (Fig. 5c) produces the proper number of shift pulses. There are six major components in this part of the device. They are the programmable counters (74LS193), NAND-gates 1 and 2, and NOR-gates 1 and 2. The programmable counters store the number of shift pulses needed to complete the operation, and counts the shift pulses as they are gated. The gates enable and disable the shift pulses.

When the power is first applied, the counters are

at zero, the borrow lines are low, NOR-gate 1 output is high, and NAND gate 1 is disabled. The computer decodes the parallel input controls of the programmable counters when DEV 10, CHN 2, and BODS go high, and the 8-bit equivalent of the shift number N is loaded. When the parallel input control pin is activated, the eight bits are loaded, the borrow lines of the counters switch to high, and NOR-gate 1 output goes low, enabling NAND gate 1. At the same time BODS disables NOR gate 2.

Note the inverters marked "delay." When the parallel-input line is activated, the counter cannot operate. So, the pulses must be disabled until the input line is deactivated by removing BODS. After the parallel-input line is deactivated, the programmable counters must settle before the shift pulses appear. The propagation time of the inverters provides this delay. The shift-pulse generator then produces the pulses and when their number equals the number N, the counters reach zero, the borrow lines switch low, and NOR-gate 1's output goes high, which disables NAND gate 1.

#### Watch that sign





In two's complement arithmetic the multiplier's sign must be preserved during shifting operations. The Y value is a 16-bit number whose first 11 bits define the magnitude, while the last five repeat the sign. But to complete the operation, the Y value has to be shifted 25 times, so the multiplier must be extended another 8 bits to ensure a correct answer. The answer is also sign-extended during scaling.

The sign-extend control device consists of two programmable counters (74LS193), flip-flop 1 and the decoding gates (Fig. 5d). Flip-flop 1 controls the sign extended of the Y value. After eight shift pulses, output Q of flip-flop 1 goes high and removes the sign-extend from the Y value, which is now sign-extended to 24 bits. The sign-extend circuit for the answer consists of NAND gate 1, NOR gate 1, and NOR gate 2. When the counter reaches 25, the output of NAND-gate 1 switches to low, which enables NOR gate 1. When the shift pulse goes low, the NOR gate 1 output goes high, and the sign-extend for scaling is turned on. At the same time, the counters stop counting because NOR gate 2 is disabled.

The complete 12-bit multiplier/shifter is shown in Fig. 6. This circuit can also be used for 8 and 16-bit multiplications. No modifications are necessary for 8-bit numbers, but if you want to perform only 8-bit multiplications, you can eliminate some of the chips. For a 16-bit multiplier you must make some timing changes—most notably in sign-extending—and add another Am25LS22 shift register to handle the 32-bit result.


The 12-bit multiplier/shifter can also be used with other computers besides the PACE; however, vari-





5. The major building blocks of Fig. 1 are shown in more detail. Sign-extend (a) duplicates the sign bit so it is not lost during shifting, the multiplier (b) also serves as x-

register, the shifter (c) doubles as the y-register, and the shift-pulse generator (d) produces the multiplier/shifter's internal timing pulses.



ations in timing signals and buses from one computer to another may require modifications. Naturally, the software will be different.

### Avoid hardware problems

In constructing the multiplier circuit, take care to keep noise levels low. Each chip should be bypassed between the supply lead and ground with a 0.1- $\mu$ F ceramic capacitor. The board-supply input should have a 10- $\mu$ F tantalum bypass capacitor. Crosstalk problems can arise if the BIDS signal is coupled into other parts of the circuit. Care in layout of parts and shielding the BIDS line carefully should eliminate crosstalk.

The multiplier/shifter is interfaced to the computer through the multiply subroutine shown in Fig. 7. Before calling this subroutine, the values to be multiplied are stored in registers 0 and 1. The number of places to be shifted after the multiplication is stored in register 2. This sequence would look as follows:

```
LD 0,X ; load multiplier
LD 1,Y ; load multiplicand
```


```
LI 2,5 ; load number of shifts (N= 5)
JSR XMLT ; jump to multiply subroutine
```

In the multiply subroutine, the value  $19_{16}$  (25 decimal) is added to the number of shifts already stored in register 2. The extra 25 shifts are required to carry out multiplication.

The second line in Fig. 7 places the address of the multiplier/shifter (80D0) in register 3. The values to be multiplied, and the shift value are then gated into their respective locations in the multiplier/shifter. After the shift value is loaded, multiplication starts.

While the multiplier peripheral is doing its trick, the computer executes the shift instruction SHR 2,4,0. This instruction merely serves as a time delay, to make sure that the hardware multiplier/shifter is finished before the computer continues.

After the shift instruction is completed, data from the multiplier/shifter are read into the computer by two load instructions. The 16 low-order bits are read into register 1, then the eight higher order bits are loaded into register 0, with the sign of the eighth bit extended. After the multiplication and shifting, the



- IC18 - 74LS04
- IC17 - 7400
- IC16 - 74LS74
- IC15 - 7402
- IC14 - 74LS193
- IC13 - 74LS193
- IC12 - 7402
- IC11 - 74LS04
- IC10 - 7410
- IC9 - 7410
- IC8 - 74LS04
- IC5 - 74LS193
- IC4 - 74LS193

6. The over-all schematic of the multiplier is arranged the same as the block diagram of Fig. 1. The bus-pin connections are given by the colored numbers.

0000	E909	A	XMLT	ADD	2,T5
0001	CD07	A		LD	3,MULTAD
0002	D300	A		ST	0,(3) (Store X)
0003	D701	A		ST	1,1(3) (Store Y)
0004	DB02	A		ST	2,2(3) (Store Shift)
0005	2E08	A		SHR	2,4,0 (Time Delay)
0006	C703	A		LD	1,3(3) (Load Low Bits)
0007	BF04	A		LSEX	0,4(3) (Load High Bits)
0008	8000	A		RTS	
0009	80D0	A	MULTAD:	.WORD	080D0
000A	0019	A	T5:	.WORD	019
	0000			.END	XMLT


7. A simple program, written in assembly language, has only to load the values X and Y, and retrieve the answer. During the actual multiplication, it idles.

subroutine returns control to the main program.

You can reduce the software execution time for multiply/shift combinations that require only a few shifts. Connect the borrow line from the multiply/shift counter to condition bit 15 on the PACE, and replace the "SHR 2,4,0" by "WAIT: BOC OF, WAIT," to create a variable time delay. While execution with fixed time delay takes approximately 110  $\mu$ s, the variable delay can save you five to 15  $\mu$ s—a significant amount of time if you need numerous multiplications.

The alternate operation works as follows: While the multiply/shift counter is down-counting, the borrow signal remains high. The branch-on-condition instruction (BOC) tests condition-bit 15 (Borrow line). If bit 15 remains high, the computer again executes the branch-on-condition instruction. When the counter has completed down-counting, the borrow line goes low. This time bit 15 is low, so the computer executes the next instruction in the sequence, instead of repeating branch-on-condition. ■■

# INTRODUCING THE FUNNEL A TAPE DRIVE CAPABLE OF EMPTYING A FIXED DISK INTO ONE 1/4" CARTRIDGE



The Funnel lets you pack more data onto a standard 1/4" cartridge than ever before—more than enough to load and unload an entire 10 M-Byte fixed disk.

### Pay Less Than 2¢ A Kilobyte.


The Funnel out-transfers and out-stores a typical cartridge system 4 to 1. And it out-saves all systems on a cost per kilobyte basis. Featuring 4-track, serial recording at 6400 BPI, The Funnel boasts a transfer rate of 192 kilobits per second.

For OEM price quotations and more details, call 213/351-8991. Or write: The Funnel, Data Electronics, Inc., 370 N. Halstead St., Pasadena, Calif. 91107. Telex 67-5327.

Condensed from a recent independent, nationally published study.

	Typical Cassette	Double- Density Diskette	Typical 1/4" Cartridge	The Funnel
Data Transfer Rate (K Bits/sec.)	24	500	48	192
Recording Density (Bits/inch)	800	6400	1600	6400
Unformatted Capacity (M Bytes)	0.7	0.8	2.87	11.52

Add It To Your Mini System.



**WE STORE BYTES  
IN M'S NOT IN K'S**

CIRCLE NUMBER 45

# Proven problem solvers from Elco



## CARD EDGE CONNECTORS

Elco has been the supplier of reliable card edge connectors for years. Now additional sizes in the standard line and a new line of wire-wrappable connectors with .156" centers are offered. All standard contact spacings from .100" to .156" for all termination techniques are available including, QPL, military qualifications to MIL-C-21097/21 and UL recognition. And they're immediately available from your local distributor.




## 2-PIECE METAL-TO-METAL PC CONNECTORS

For the user, who needs the most reliable card-to-card connection, end-to-end, at right angles or stacking connections, we offer the greatest variety of metal-to-metal contacts and connectors available anywhere. Expect off-the-shelf delivery from our distributors on most configurations that include .050" staggered, .100" to .200" spacing, 1 to 96 contacts, various termination styles, with or without card guides and hardware for most any application. Most are mil spec, QPL and UL recognized. Connections are made by our Varicon™ contact providing hermaphroditic, gas-tight joints with millions of operating hours proving their reliability.


Elco Corporation  
2250 Park Place  
El Segundo, Ca 90245  
TWX 910-325-6602 / 213 675-3311

**G+W** Elco Corporation  
a Gulf + Western manufacturing company



## I/O AND RACK AND PANEL CONNECTORS


Meets every i/o wire size requirement from 18 to 30 AWG. They feature easy mating/unmating and locking of mated connectors with a single jack screw operation. High-density contact spacings range from .100" to .150" grids, with 20 to 165 contacts with solder, crimp, wire wrap and other terminations. Lightweight aluminum covers are available for cosmetic appeal, wire clamping and strain relief. They utilize the Varicon™ contact which has a 25 year record of reliable service.



## BACKPANEL SYSTEMS

Are you looking for compact, ready-made backpanel interconnects for your daughter cards to reduce costs? Elco offers metal plate backpanels with pc connectors for automatic and hand wire wrapping which provide built-in ground and voltage interconnections. To further simplify your task and eliminate wire wrapping, Elco offers pc backpanels in two sided and multilayer configurations providing all ground, power and signal interconnections for mounted card edge or metal-to-metal connectors with contact spacings from .100" to .156". All backpanels are custom engineered to fit your exact needs in sizes accommodating as many as 20,000 contacts.

ELCO CORPORATION'S catalogs are available upon request for any of these products. In most cases, these products are immediately available from distributor stock. For custom products or engineering assistance, we'll be glad to help you. Just call us, Elco connects . . . worldwide!



## PC CARD ENCLOSURES

The versatile Varipak® II card enclosures are constructed from standard components and will accommodate any number of cards and card sizes to meet your custom requirements. They come complete with guide plates, card guides, and connector mounting panels. Your local distributor offers immediate delivery on 64 standard models in 19" and 24" widths.

**Elco Connects!**

CIRCLE NUMBER 46



equal to five (101), add three (011) and shift one bit to the left. If the sum is less than five, shift left without adding three. After each shift, examine the BCD number being formed—only now, one 4-bit decade at a time—and add three to each decade with a value of five (0101) or greater. Then shift again. Continue this iterative process until the last, or least significant, binary bit is shifted into the least significant BCD position. At this point the BCD decades contain the correct BCD number. An example using the procedure is given in Fig. 1 for a 9-bit binary number.<sup>1,2</sup>

While units of seconds are converted with a base-10 algorithm, tens of seconds require a base-6 conversion because the number five for tens of seconds cannot be exceeded. Sixty seconds must be entered as one minute to the next higher decade. And here, it's convenient to use base-10 and base-6 algorithms simultaneously to change binary seconds to complex-BCD tens and units of seconds.

To create a complex-BCD number, you must examine not only each 4-bit decade being formed, but each 3-bit hexade (base-6) number being formed at

the same time. The 4-bit decade is handled as a base-10 conversion like the example in Fig. 1.

For a hexade, each 3-bit number having a value of three (011) or greater must have one (001) added to it before shifting. If the value is less than three, shift without adding one. Shifting and adding (where necessary) continues until the last or least significant binary bit is shifted into the least significant complex-BCD position. At this point, the BCD decades and hexades contain the correct complex-BCD number. An example of this combined procedure is given in Fig. 2 for a 9-bit binary number.

To build a complex-BCD time converter, first program hardware to perform the conversion algorithms. And with a single type of IC, you can construct a converter for days, hours, minutes and seconds.


### One ROM goes a long way

A 16-word by 4-bit read-only memory (ROM) is the only IC type needed in the design, but 90 of them are required for an entire converter. Both a modulo-10 and

	Truth Table I								Truth Table II								
	IC Module — MC 4001P								Same Module								
	INPUT				OUTPUT				INPUT				OUTPUT				
	D	C	B	A	Q7	Q6	Q5	Q4	D	C	B	A	Q7	Q6	Q5	Q4	
No Conversion	0	0	0	0	0	0	0	0	*	0	0	0	0	0	0	0	No Conversion
	0	0	0	1	0	0	0	1	*	0	0	1	0	0	0	1	
	0	0	1	0	0	0	1	0									
	0	0	1	1	0	0	1	1	*	0	1	0	0	1	0	0	
Modulo-10 Conversion	0	1	0	1	1	0	0	0	*	0	1	1	1	0	0	0	Modulo-6 Conversion
	0	1	1	0	1	0	0	1									
	0	1	1	1	1	0	1	0	*	1	0	0	1	0	1	1	
	1	0	0	0	1	0	1	1	*	1	0	1	1	1	0	0	
Don't care states (impossible inputs)	1	0	1	0	1	0	0	0									Permanent Ground "0"
	1	0	1	1	1	0	0	1									
	1	1	0	0	1	1	1	0									
	1	1	0	1	1	1	1	1									
	1	1	1	0	1	0	1	1									
	1	1	1	1	0	1	0	0									

3. Truth tables for modulo-10 and modulo-6 conversions are programmed into one 16-word ROM. Every ROM in

a binary to complex-BCD converter can be programmed with these tables.



4. A complete binary to complex-BCD converter changes binary seconds into a days, hours, minutes and seconds

time code. Only one IC type, a 16-word  $\times$  4-bit ROM, is used in the circuit.



a modulo-6 conversion algorithm can be programmed into a single ROM (see the truth table of Fig. 3 for an MC4001P ROM). Note that the six words not required for modulo-10 conversion are used to hold the modulo-6 conversion program. For modulo-6 conversion, a permanent low (0 V) is applied to the B input, and the Q<sub>5</sub> output is not used since modulo-6 numbers are only 3 bits long.

In an all-ROM complex-BCD converter (Fig. 4), conversion speed depends only on propagation delays through the ICs. Since each ROM has a delay time of 50 ns, and the longest delay path is through 22 ROMs, a conversion can be completed in 1100 ns. And 1100 ns is faster than one machine-instruction cycle of most computers. Conversion is not only fast, but easy to test also, because the circuit is entirely static (no clock). If you put a known binary-time count on the input lines, the complex-BCD outputs can be easily checked for the correct high levels (+5 V) with either indicator lights or a voltmeter.

Converting hours to days is not as easy as converting to seconds and minutes. Ordinarily, two digits for hours must be checked, 10<sup>1</sup> and 10<sup>0</sup>, which would require a modulo-24 algorithm. However, a modulo-6 conversion can replace modulo-24 if you consider every six hours one-quarter of a day. A quarter of a day, when doubled, becomes a half-day, etc. So the circuit

uses modulo-6 until the last two levels of conversion, then switches to modulo-10 to present the remaining number of hours—not as fractions of a day, but as a two-digit (00 to 23) representation of hours. The most significant digit is a two-line terminal stage that needs no conversion module. The least significant digit is generated by a modulo-10 algorithm in the last two levels of conversion.

Days are converted by a standard modulo-10 algorithm, but there is no provision for converting days to years.


If time data are to be communicated between a computer and its I/O terminals, complex-BCD signals from a terminal must be converted to binary for input to the CPU. And to change complex BCD to binary, you'll need another type of hardware converter, but it's also a static circuit that requires only a single IC type to build a complete converter.

### Anyway you look, it all adds up

A complex-BCD-to-binary converter generates serial binary bits by adding selected complex-BCD bits. The entire conversion requires only add operations, so you can use a single type of IC, an SN 7483 4-bit full adder, to build a complete converter. You'll need 31 adders to do the job, but there's no programming

**Table. Binary/complex-BCD equivalents**

Signal	Decimal			Seconds	Decimal Seconds	Octal Seconds	2 <sup>3</sup>
	Days	Hours	Minutes				
	00	00	00	00	000 000 000	000 000 000	0 000 000 000 000 000 000 000
S1				1	1	1	1
S2				2	2	2	10
S4				4	4	4	100
S8				8	8	10	1 000
S10				10	10	12	1 010
S20				20	20	24	10 100
S40				40	40	50	101 000
M1			1	0	60	74	111 100
M2			2	0	120	170	1 111 000
M4			4	0	240	360	11 110 000
M8			8	0	480	740	111 100 000
M10			10	0	600	1 130	1 001 011 000
M20			20	0	1 200	2 260	10 010 110 000
M40			40	0	2 400	4 540	100 101 100 000
H1		1	0	0	3 600	7 020	111 000 010 000
H2		2	0	0	7 200	16 040	1 110 000 100 000
H4		4	0	0	14 400	34 100	11 100 001 000 000
H8		8	0	0	28 800	70 200	111 000 010 000 000
H10		10	0	0	36 000	106 240	1 000 110 010 100 000
H20		20	0	0	72 000	214 500	10 001 100 101 000 000
D1	1	0	0	0	86 400	250 600	10 101 000 110 000 000
D2	2	0	0	0	172 800	521 400	101 010 001 100 000 000
D4	4	0	0	0	345 600	1 243 000	1 010 100 011 000 000 000
D8	8	0	0	0	691 200	2 506 000	10 101 000 110 000 000 000
D10	10	0	0	0	864 000	3 227 400	11 010 010 111 100 000 000
D20	20	0	0	0	1 728 000	6 457 000	110 100 101 111 000 000 000
D40	40	0	0	0	3 456 000	15 136 000	1 101 001 011 110 000 000 000
D80	80	0	0	0	6 912 000	32 274 000	11 010 010 111 100 000 000 000
D100	100	0	0	0	8 640 000	40 753 000	100 000 111 101 011 000 000 000
D200	200	0	0	0	17 280 000	101 726 000	1 000 001 111 010 110 000 000 000



TIME IN BINARY SECONDS

6. A full adder is the only IC type needed to build a complex-BCD-to-binary converter. Since the design isn't clocked, testing is easy.

Binary weight	Signals to be added with this binary weight					
2 <sup>0</sup>	S1					
2 <sup>1</sup>	S10 + S2					
2 <sup>2</sup>	M1 + S20 + S4					
2 <sup>3</sup>	M10 + M2 + M1 + S40 + S10 + S8					
2 <sup>4</sup>	H1 + M20 + M10 + M4 + M2 + M1 + S20					
2 <sup>5</sup>	H10 + H2 + M20 + M8 + M4 + M2 + M1 + S40					
2 <sup>6</sup>	H20 + H4 + M40 + M10 + M8 + M4 + M2					
2 <sup>7</sup>	D1 + H10 + H8 + M20 + M8 + M4					
2 <sup>8</sup>	D10 + D2 + D1 + H20 + M40 + M8					
2 <sup>9</sup>	D100 + D20 + D10 + D4 + D2 + H1 + M10					
2 <sup>10</sup>	D200 + D100 + D40 + D20 + D10 + D8 + D4 + H10 + H2 + H1 + M20					
2 <sup>11</sup>	D200 + D80 + D40 + D20 + D10 + D8 + H20 + H10 + H4 + H2 + H1 + M40					
2 <sup>12</sup>	D100 + D80 + D40 + D20 + D1 + H20 + H8 + H4 + H2					
2 <sup>13</sup>	D200 + D80 + D40 + D10 + D2 + H8 + H4					
2 <sup>14</sup>	D100 + D80 + D20 + D4 D1 + H8					
2 <sup>15</sup>	D200 + D100 + D40 + D8 + D2 + H10					
2 <sup>16</sup>	D200 + D100 + D80 + D10 + D4 + D1 + H20					
2 <sup>17</sup>	D200 + D100 + D20 + D8 + D2					
2 <sup>18</sup>	D200 + D40 + D10 + D4					
2 <sup>19</sup>	D80 + D20 + D10 + D8					
2 <sup>20</sup>	D40 + D20					
2 <sup>21</sup>	D80 + D40					
2 <sup>22</sup>	D80					
2 <sup>23</sup>	D100					
2 <sup>24</sup>	D200					

5. Complex-BCD components of binary numbers are found by reading down the binary seconds columns in Table 1. Summing the correct complex-BCD signals with full adders generates all 24 binary-seconds bits.

involved in the conversion.

The complex-BCD components of each binary number are found by constructing a chart (see Table) of binary and complex-BCD equivalents. Reading a binary-seconds column vertically tells you which complex-BCD components, when added together, form a particular binary number. Say you want to find the components of the 2<sup>3</sup> binary bit. Locate all ones in the table, by reading the 2<sup>3</sup> column from top to bottom. Project the ones across to the left side of the table and read out the complex-BCD components: S<sub>8</sub>, S<sub>10</sub>, S<sub>40</sub>, M<sub>1</sub>, M<sub>2</sub> and M<sub>10</sub>. These signals must be summed by the hardware to produce a binary 2<sup>3</sup>. Since all 24 binary digits in the table have an equivalent sum, a listing is easily made by reading down each column, and picking out the signals to represent the binary numbers. Fig. 5 shows the result of that process, a list of all complex-BCD components that must be added to generate the binary time bits.

### Adders, adders everywhere

To build a complete complex-BCD-to-binary converter (Fig. 6), interconnect 31 adders according to the add operations dictated by Fig. 5. For addition, the order of operations doesn't matter, so signals to be added can be intermixed as long as they're added with the proper binary weighting. For clarity, in Fig. 6 signal abbreviations of complex-BCD inputs are used, to eliminate crossing of lines on the schematic.

When you interconnect adders, be sure that carry bits are always a carry-in to the next more significant bit. And to avoid false values from being generated, ground unused carry-in and adder input pins. Note that the least significant binary bit, 2<sup>0</sup>, doesn't need an adder because no sums are involved, and no carries will be produced.

Buffering at the adder inputs is not required since complex-BCD output drivers can fan out to eight adder inputs. And testing a converter is similar to testing a binary to complex-BCD type, since they're both static and require only a known input to check for the correct outputs. Again, indicator lights or a voltmeter are all that are needed for test equipment.


As with a binary-to-complex-BCD converter, conversion speed is limited only by propagation delays through the ICs. The longest path is through 14 ICs, each with a 50-ns delay. So maximum delay is 700 ns. This is 400 ns faster than a binary to complex-BCD converter, and well within one instruction time of most computers. Conversion time can be made shorter, either by using faster ICs or full adders having lookahead-carry logic. ■■

### References

1. Couleur, J.F., "BIDEC—A Binary to Decimal or Decimal to Binary Converter," *IRE Transactions on Electronic Computers*, EC-7, 1958, p. 313.
2. Benedek, Z. Michael, and Moskowitz, Bert, "Convert Binary to BCD without Flip-flops," *Electronic Design*, Oct. 10, 1968, p. 58.

# The big switch

**...is to smaller, lighter switchers.**



The 100 watt MGT 5-20A: 7" x 6.4" x 3.5", 7.5 lbs.

Switching power supplies average about  $\frac{1}{3}$  the size and  $\frac{1}{4}$  the weight of linears. And in many applications that's reason enough to make the switch. But it's not the only reason. Compared to linears, switchers can cut energy consumption in half, generate far less heat, and offer better holdup protection. That's why more than 40,000 Gould switchers are already in use around the world.

Gould offers single and multiple output units with power levels from 8 to 2,250 watts. And custom designs can be provided to meet your exact specifications. You'll be backed by a high volume production capability and worldwide service network that only a \$1.5 billion company like Gould could offer.

For more information or to arrange for an evaluation unit contact Gould, Inc., Electronic Components Division, 4601 N. Arden Drive, El Monte, CA 91731. Telephone (213) 442-7755.

**Gould.**  
**The power in switching power supplies.**

 **GOULD**

CIRCLE NUMBER 48

ELECTRONIC DESIGN 2, January 18, 1978

# Same great name. Same great color.

## And now a neat new way to definitive display performance.

# DOT MATRIX


Consider the new Noritake-Ise dot-matrix line-up—  
9, 10, 16, 20 and 40-character line displays.  
Variety aimed at giving you more design potential.  
Or consider our unique 400-dot graphics display  
with 17m/m depth and low 35V drive rating.  
It's aimed at helping you think low voltage,  
portability and economy all at the same time.

In short, consider Noritake-Ise period  
for dot matrix (or segmental) displays.  
Itrons always help you design more competitively.

**itron**<sup>®</sup>



**DC209A2**  
Dimension: 41(H)×208(W)×10.5(D)mm Character Size: 9.0(H)×6.3(W)mm




**DM400A1**  
Dimension: 114(H)×130(W)×17(D)mm



**DC95A2**  
Dimension:  
24(H)×75(W)×7.2(D)mm  
Character Size:  
5.05(H)×3.55(W)mm



**FG48D6**  
Dimension:  
25.5(H)×56.5(W)×7(D)mm  
Character Size:  
8.0(H)×4.2(W)mm



**FG120S1**  
Dimension: 39(H)×138(W)×12.5(D)mm



**FG209M2**  
Dimension: 41(H)×208(W)×10.5(D)mm Character Size: 9.0(H)×5.4(W)mm

## NORITAKE CO., LTD.

Electronics Division  
1-1, Noritake-Shinmachi,  
Nishi-ku, Nagoya-Shi,  
Japan  
Phone: NAGOYA  
(052) 561-7111  
Telex: J59738 NORITAKE

**Noritake Electronics Inc.**  
Los Angeles Branch  
22410 Hawthorne Blvd.  
Torrance, Calif.  
Phone: (213) 373-6704  
Telex: 230674910

F.R. Germany  
NEUMULLER GmbH &  
München 2,  
Karlstrasse 55,  
F.R. Germany  
Phone: 089 (599) 1230  
Telex: 522106

U.K.  
ITT Component Service  
Edinburgh Way, Harlow,  
Essex, U.K.  
Phone: 0279-3351  
Telex: 81146

Europavia France  
5-Avenue, Leon Harmel 92167,  
Antony Cedex, France  
Phone: 666-21-10  
Telex: 42204381

Hong Kong  
Room 1403 Shing Loon Bldg.  
24-26 Stanley Street, Hong Kong  
Phone: 5-232420 Telex: HX83151  
Taipei  
72-9 SEC 2, JEN AI RD., Taipei  
Phone: 351-0293 Telex: 11176

Manufacturer:

**ISE ELECTRONICS CORP.**  
P.O. Box 46, Ise-shi,  
Mie-Pref., Japan  
Phone: (0596) 39-1111  
Telex: 4969523

Europe Office  
Rue De la presse 3-5 1000  
Bruxelles, Belgium  
Phone: 2178360, 2178460  
Telex: 25327, 26962

# Synchronizing giant generators

by hand can create expensive fireworks. But a mini closes the large circuit breakers with precision.

Before a power generator can be connected to a grid bus—usually in response to peak demand—it must be synchronized carefully. Otherwise, the surge of power will unleash potentially destructive forces in the generator.<sup>1</sup> And the larger the generator, the more precise the match must be.

For example, the new 600-MW generators at the Grand Coulee Dam can tolerate a phase error of only 2 degrees. Because a skilled operator typically achieves no better than a 5-degree match, large generators must be controlled automatically.

The Grand Coulee generators will be monitored and controlled by a distributed processing system whose smart remote terminal units limit-check data and control generator load and voltage. With only a small increase in the host minicomputer's memory, and some additional hardware, the control system can also sequence start-up and shut-down of individual generators. With conventional synchronizers, the cost of individual control would be prohibitive.

Field tests on a 125-MW generator<sup>2</sup> provide the design base for such a control system: When the circuit breaker connecting the incoming bus to the running bus is closed, say, with a 15-degree phase-angle mismatch, a peak power surge of 225 MW (1.8 times the generator's rated output) creates a loud bang that rocks the whole power plant. A frequency mismatch of 0.25 Hz causes a 20-MW surge, and a voltage mismatch of 1% sucks in 9 MVA of reactive power. As a result of these tests, the Bureau of Reclamation has established the following synchronization criteria, at the point of breaker closure:


- Maximum phase error—2°.
- Max frequency mismatch—0.1 Hz.
- Max voltage deviation—0.1 %.

### David controls Goliath

The synchronization control loop of the Grand Coulee control system (Fig. 1) uses step-down transformers to couple the running-bus and incoming-bus wave to the sync-module input. When commanded by

---

**William R. Berger**, Member of the Technical Staff, Communications Switching Systems Division, Rockwell International, 3330 Miraloma Avenue, Anaheim, CA 92803



1. **The synchronizer compares voltages** from two buses, and creates three outputs. One controls the generator's speed, one its voltage, and a third activates the circuit breaker, when phase and voltage are matched.

the CPU, the sync module digitizes the two waveforms and, using direct-memory access, fills a pair of image buffers. The CPU is now available to handle tasks of the remote-terminal unit.

When interrupted by the sync module, the CPU software analyzes the fresh data in the buffers and generates error signals proportional to waveform differences. Control algorithms in the software use these error signals to modify generator speed and voltage through digital-to-analog converters that drive the generator control ports. When the error signals have been reduced to prescribed limits and maintained for defined periods, the software sends a command to close the circuit breaker, which allows for the closing delay of the breaker.

### Software makes the match

The control algorithms are known as proportional-integral-derivative. Each control output is formed by summing weighted values consisting of a term proportional to the variable, a term corresponding to the integral of the variable, and one representing the derivative of the variable. The weighting coefficients,  $K_{xy}$ , are adjusted to match the response of the gener-

ator that's being synchronized (some of the coefficients are zero).

The voltage-adjust equation requires only the proportional and integral terms as follows:

$$V_{ADJ} = K_{PV} V_R + \Sigma K_{IV} V_R + V_{NL} \quad (1)$$

where

$V_R$  = relative voltage, or the difference between incoming and running-bus amplitudes.

$V_{NL}$  = voltage no-load set point.

The terms  $\Sigma K_{IV} V_R$  and  $V_{NL}$  represent the computer equivalent of the voltage integral, with the voltage no-load set point as the initial condition.

Similarly, speed-adjust output is formed as follows:

$$S_{ADJ} = K_{P\dot{\theta}} \dot{\theta}_R + K_{I\dot{\theta}} \dot{\theta}_R + S_{NL} + K_{d\dot{\theta}} \ddot{\theta}_R \quad (2)$$

where

$\dot{\theta}_R$  = relative angular velocity

$\ddot{\theta}_R$  = relative angular acceleration

$S_{NL}$  = speed no-load set point

Phase control is achieved by varying the speed-control output. First the speeds are matched, then the generator speed is allowed to slip slightly to bring the waveforms into phase correspondence. The final value of the described speed-adjust output forms the initial condition for the phase-control integral. As a result, the phase-control output is another speed control:

$$S_{ADJ} = K_{P\theta} \theta_R + \Sigma K_{I\theta} \theta_R + S_{ADJ}(s,f) + K_{d\theta} \dot{\theta}_R \quad (3)$$

where


$\theta_R$  = relative phase angle

$S_{ADJ}(s,f)$  = initial condition-final condition from speed-control Eq. 2.

### Caution—waveform crossing

The four derived quantities in the control equations,  $V_R$ ,  $\theta_R$ ,  $\dot{\theta}_R$  and  $\ddot{\theta}_R$  are obtained by analyzing the waveforms stored in the data buffers for axis crossings (Fig. 2). The time between zero crossings is inversely proportional to angular velocity  $\dot{\theta}$ . The difference between  $\dot{\theta}$  values, observed on the same channel in subsequent passes, is directly proportional to angular acceleration  $\ddot{\theta}$  over the repetition period. The peak amplitude is halfway between  $X_1$  and  $X_2$  (Fig. 3). By locating both the positive and negative peaks, the software can compensate for any dc offset and correct the resulting error in  $\theta$ .

The relative quantities required by the three control equations are simply the differences in corresponding



2. Axis crossings are the key to determining the phase difference between the generator and the grid.

values of the incoming bus and running bus—e.g. the relative phase angle  $\theta_R$  is proportional to the time between positive (or negative) zero crossings in the two image buffers.

Each of the derived quantities (Eqs. 1 to 3) contains a finite uncertainty whose magnitude can be expressed as a function of the uncertainty in the axis-crossing time. Analysis reveals that  $\theta_R$  shows the highest sensitivity to axis crossing errors. The uncertainty in the relative phase angle is equal to  $\pm 2 \omega n$ , where  $\omega$  is the angular velocity in rad/s of both waveforms at synchronization, and  $n$  is the uncertainty in the axis-crossing time, in seconds.

At an angular velocity of 377 rad/s (60 Hz), and a maximum phase uncertainty of  $0.1^\circ$ , the maximum axis-crossing uncertainty is  $\pm 2.5 \mu s$ .

Actual axis-crossing time is determined by a software routine that interpolates between two points on opposite sides of the axis. But these two points aren't simply two measured values—each is the result of averaging three samples immediately before and immediately after the sign change (Fig. 3).

With this technique, noise effects are minimized in the vicinity of the axis crossing. Because the uncertainty in the axis-crossing point is proportional to the uncertainty in the sampled voltage, and inversely proportional to the velocity of the wave at the axis crossing, a limit of  $\pm 2.5 \mu s$  requires a voltage uncer-

tainty of less than  $\pm 134$  mV—one part in 2180 when referred to the input waveform. For this resolution, a 12-bit analog-to-digital converter is needed because an 11-bit converter's error of one part in 2048 ( $=2^{11}$ ) is not quite good enough.

### Timing is everything

The averaging technique used for locating an axis crossing requires that seven samples be taken near the axis, over an interval in which the sine wave appears linear—i.e., the sine function must not deviate from its maximum slope by more than half the least significant bit (LSB). This requirement can be expressed as

$$A\omega t - A \sin \omega t \leq 1/2 \text{ LSB.}$$

By representing  $\sin \omega t$  as a power series, this equation can be solved for  $t$ , with the following result:

$$T = \sqrt[3]{\frac{3\text{LSB}}{A\omega^3}}$$

Since the waveform is symmetric about the axis, the total period of linearity is twice the calculated value. For seven samples to be taken in this linear interval, the sample period must be  $2T/7$ , or  $90 \mu\text{s}$ .


The correction signals (Eqs. 1 to 3) all stem from differences between the two bus inputs, and errors common to both channels are self-canceling. By using one a/d converter to digitize both channels, conversion errors tend to disappear. However, two conversions must then be made during each  $90 \mu\text{s}$  sample period, and the available conversion time is below  $45 \mu\text{s}$ .

The most suitable a/d converters use a successive approximation technique, which requires that the input not change by more than  $\pm 1/2$  LSB during conversion. At the maximum velocity of the given inputs, this means a 600-ns conversion period.

Because conversion times under 1 ms are expensive, a sample/hold network can be installed ahead of the converter. Again, a single network would minimize errors associated with the sample/hold network, but acquisition time would be doubled, and the software would have to correct the derived quantities for time skew. The best solution is to use one sample/hold network for each input, and then multiplex the network's outputs before conversion, even though the differential errors are higher. Allowing time for sample/hold action, multiplexer settling, and two memory access cycles leaves the a/d converter with about  $25 \mu\text{s}$  per conversion.

### Missed opportunities count

When designing the software for the synchronizer (Fig. 4), two additional problems must be considered. Since each new "image" is sampled at program request, the software might miss a sampling opportunity. To maintain an accurate time base even when this happens, the hardware keeps track of the number of missed opportunities, and stores it in a buffer location at the end of the next image sample.




3. The accuracy of axis crossings is greatly improved by averaging and interpolating test points.

As part of the final closing sequence, the software calculates the time remaining until the close command. When this period is less than the time required to process one more image pair, the program stops sampling and places the sync module in the timing mode. A number representing the time until close command is stored in the sync module. This number forms the initial condition for a precision interval timer. Once the specified time has elapsed, the sync module generates an interrupt that causes the program to transmit the close command.

Another problem stems from the circuit breaker's closing delays. A short but significant time elapses between the command to close and the actual circuit breaker closure. Since the delay is repeatable for each breaker, the software can compensate for it. Depending on the closing delay time, either of two methods of circuit-breaker closing can be used. If the relative angular velocity is small enough, the circuit breaker is commanded to close when  $\theta_R$  conforms to the synchronizing criteria. In this case the value of  $\dot{\theta}_R$  is so low that the angle can't change significantly during the closing delay. For larger values of  $\dot{\theta}_R$ , the software must calculate the time remaining until the waveforms coincide. All closing delays are subtracted from this time to determine when the closing command must be given.

For synchronizing generators at Grand Coulee Dam, Rockwell International's Communications Switching Division has chosen Interdata's 7/16 minicomputers with 48 kbytes of core. Features of this model include  $1 \mu\text{s}$  cycle time, automatic restart circuitry in case of power failure, signed multiply/divide hardware, line-synchronized clock, and binary front-panel display. Loader storage is provided for down-loading the system from the master station, and a programmable asynchronous/synchronous line adapter (PASLA) is available for interfacing to a portable programming unit like the HP2640.






4. As the flow chart shows, the synchronizer not only controls the generator's speed and voltage, but also watches for abnormal waveforms and sounds an alarm.

Synchronizer hardware is mounted on a single PC card that plugs into the minicomputer's backplane. Control logic is on the main card while the analog circuits, which consist of conditioning amplifiers, multiplexer, sample/hold networks, and the a/d converter, are mounted on a small "piggyback" board that plugs into the main card. Power for the analog circuitry is generated locally by a dc/dc converter.

The minicomputer-controlled synchronizer has been tested by the Bureau of Reclamation. Using an analog simulator to model generator response during a wide range of conditions, the system has repeatedly synchronized the generator within the limits set by the Bureau. The synchronizers should be working with the big generators by the end of 1978. ■■

**References**

1. Creager, W. P., and Justin, J. D., *Hydroelectric Handbook*, John Wiley & Sons, New York, 1950, p. 961.
2. Gish, W. B., Hamann, B. D., and Chamot, D. W., *Synchronizing Hydroelectric Generators with Minicomputers*, Bureau of Reclamation Rep. REC-ERC-74-2, January 1974, p. 2.



# POSITROL

## DIGITAL POSITIONING SYSTEM

**Motor Control System... Remote Control Set Points... Relay or Solid State Outputs... Can Be Used As Electronic Limit Switch.**

POSITROL is an absolute digital motor control system capable of positioning accuracies of .01 degrees. It can accommodate up to six set points, each with a six decade capability.

Data is not affected by power interruptions or electrical noise.

POSITROL is available with overshoot control and zero offset capability.

**LITERATURE:**

Write for descriptive literature on the Theta POSITROL Digital Positioning System



**INSTRUMENT CORPORATION**

24 Dwight Place • Fairfield, NJ 07006 • (201) 227-1700  
CIRCLE NUMBER 50

# CADNICA<sup>®</sup> POWER!



## Nickel-Cadmium Rechargeable Batteries for O.E.M. Applications

From the advanced technology of one of the world's largest battery manufacturers...CADNICA Nickel-Cadmium batteries that set new standards of performance and economy for O.E.M. applications.

Sealed CADNICA batteries withstand overcharge and overdischarge, and provide reliable service over hundreds of charge/discharge cycles. They're the

perfect power source for cordless products like tape recorders... radios... calculators... shavers... flashlights... toys... portable power tools... smoke detectors... computers... security products.

Call Sanyo... for speedy shipment from inventory... or for a power source designed to meet your special need.



# SANYO

The better life.

SANYO ELECTRIC INC. • 51 Joseph St., Moonachie, N.J. 07074 • (201) 641-2333  
Battery Division, (Dept. ED) • 1200 W. Artesia Blvd., Compton, Cal. 90220 • (213) 537-5830

CIRCLE NUMBER 51

Our Model 3001 starts at \$2,750. For that you get a signal generator that's already frequency programmable with 0.001% accuracy over the 1 to 520 MHz frequency range. If you also want to program your output power, we have a programmable attenuator option available for \$500.

If you'd like to spend a little more, add our external frequency standard option for \$150. That makes the accuracy the same as your standard. Or spend another \$500 for an internal reference frequency standard with  $5 \times 10^{-9}$  day stability. But if you want to spend much more than that, you're going to have to buy some-

body else's signal generator. Count on at least \$10,000. Frankly, we think your money would be better spent buying another Wavetek Model 3001.

Here's another advantage. If you need to get on the bus (now or later), our new Model 3910 Converter makes you GPIB compatible. But before you spend anything on any signal generator, get a demonstration of our Model 3001. That won't cost you a cent.

#### SPECIFICATIONS

Frequency Range: 1-520 MHz  
Accuracy:  $\pm 0.001\%$   
Resolution: 1 kHz

Stability: 0.2 ppm per hour  
Output Range: +13 dBm to -137 dBm

Flatness:  $\pm 0.75$  dB

AM Modulation: 0-90%


FM Deviation: 0-10 kHz and 0-100 kHz

Internal Modulation Rates:  
400 Hz and 1 kHz

WAVETEK Indiana Incorporated,  
P.O. Box 190, 66 North First Avenue,  
Beech Grove, Indiana 46107,  
Phone (317) 783-3221,  
TWX 810-341-3226.

**WAVETEK®**  
CIRCLE NUMBER 52

# You can pay a lot more for a programmable signal generator. But why?



## Compute delay times of ALU adders. Knowing they're fast is not good enough—it takes a trip through an adder's delay path to calculate its actual speed.

To design a fast arithmetic logic unit (ALU) you've got to make certain that delay through the adder components does not exceed that allowed by your system's speed requirements. Since adders come in two basic types—ripple-carry and lookahead-carry—it's important to be able to assign a speed or delay time number to each one. Although a lookahead-carry design is naturally faster than ripple-carry, you won't know how much faster until you've calculated delays through the circuit components.

Fast ALU adders can be built with arithmetic functional blocks,<sup>1</sup> allowing you to design a 16-bit adder which then serves as a system block. And arithmetic operations can be easily extended to 32 and 64-bit words by interconnecting the 16-bit system blocks. But you must first trace the delay paths of 16-bit ripple-carry and lookahead-carry schemes to see how their speed performance fits your ALU specs.

### Short delay path means high speed

High-speed arithmetic results when a 16-bit adder senses anticipated carries from each of its individual


**John R. Mick**, Manager, Digital Applications, Advanced Micro Devices, 901 Thompson Place, Sunnyvale, CA 94086.

4-bit adders. This scheme, a lookahead-carry adder (Fig. 1), is faster than ripple-carry, but an additional component, a carry-lookahead generator, such as the Am2902, is needed to achieve the higher speed. To find the actual delay time of a lookahead-carry adder, trace the path delay through its components.

The data path, from input to output, determines the time delay of a bit progressing through an adder. In Fig. 1, this path begins at the least significant 4-bit adder, goes through the carry-lookahead generator, and ends at the most significant 4-bit adder.

Because Am25LS381 adders can generate anticipated carries, carry bits are sent out to the carry-lookahead generator without having to ripple through all 16 adders in the block. Since delay through an Am2902 carry-lookahead generator is only 10 ns (Fig. 2), over-all delay of a lookahead-carry scheme is small. The longest delay occurs in a 4-bit adder (Am25LS381 or Am25LS2517) from operand inputs,  $A_i$  or  $B_i$ , to sum outputs,  $F_i$ . This delay is listed in Fig. 2 as 27 ns, and if a carry-in,  $C_n$ , from a less significant adder takes place, an additional 23-ns delay is introduced before final sum bits are available. However, as can be seen in Fig. 2, the total 16-bit delay of a lookahead adder scheme is only 60 ns.

In this lookahead scheme, delay to the most significant adder or to the next less significant 4-bit adder



1. A lookahead-carry adder's high-speed performance comes from using an Am2902 carry-lookahead generator.

Delay is reduced because a 2902 can sense anticipated carries across the entire 16-bit block.

Data-path delay of 16-bit lookahead adder (+5 V and 25 C maximum delays)				
Path	Output			Units
	F <sub>i</sub>	C <sub>n+4</sub>	OVR	
A <sub>i</sub> or B <sub>i</sub> to $\bar{G}$ or $\bar{P}$	27	27	27	ns
G <sub>i</sub> or P <sub>i</sub> to C <sub>i+j</sub> (Am2902)	10	10	10	ns
C <sub>n</sub> to F <sub>i</sub>	23	—	—	ns
C <sub>n</sub> to C <sub>n+4</sub> or OVR	—	22	22	ns
Total 16-bit delay	60	59	59	ns

2. Since path delay in a lookahead scheme is short, add operations take only 60 ns for a 16-bit word. But 12 and 16-bit adders both have 60-ns delay times since their combinatorial delay paths are the same.

Select-input delay for 16-bit adder (+5 V and 25 C maximum delays)				
Path	Output			Units
	F <sub>i</sub>	C <sub>n+4</sub>	OVR	
S <sub>i</sub> to $\bar{G}$ or $\bar{P}$	47	47	47	ns
G <sub>i</sub> or P <sub>i</sub> to C <sub>i+j</sub> (Am2902)	10	10	10	ns
C <sub>n</sub> to F <sub>i</sub>	24	—	—	ns
C <sub>n</sub> to C <sub>n+4</sub> or OVR	—	22	22	ns
Total 16-bit delay	81	79	79	ns

3. Additional time is needed to output data if an adder's operating mode is changed. The additional time occurs only in a 4-bit adder, because of propagation delays in the function select circuits of an adder.


is the same, so a 12-bit and 16-bit adder have the same delay time. This is because the same types of combinatorial delays are involved in each case.

The longest delay for a lookahead adder comes when a 16-bit block is commanded to a particular operating mode via its function-select inputs (S<sub>i</sub>). Am25LS381 and Am25LS2517 functional blocks perform eight different arithmetic/logic operations and a 21-ns delay occurs (Fig. 3) if there is a change in operating mode. Adding this delay to the 27 ns previously found for the block results in a total of 48 ns delay for an

adder. The additional 21 ns must be reflected at the sum outputs, so worst-case add time becomes 60 + 21 = 81 ns. Note, however, that all delay times in Fig. 2 are at 5 V dc and 25 C, which obviously aren't worst-case voltage and temperature conditions.

#### Serial delay path means low speed

To calculate delay time for a ripple-carry scheme, trace its delay path almost as you would the path of a lookahead adder. By computing delay for a 16-bit



4. Serial operation makes a ripple-carry scheme slower than lookahead types. Carries from the least significant

to the most significant adder must travel a long path, building up delay time in each block.

# EMR

## Frequency Response Analyzers For Every Application

From the viscous elastic properties of films and fibers, to the frequency response of hydraulic actuators . . . for the open loop response of a servo system with the loop closed, or the frequency response of the Brooklyn Bridge . . . EMR has a Frequency Response Analyzer that is just right for your application.

Take the low-cost, easy-to-use Model 1312. It's ideal for production testing and basic measurements of phase and amplitude to 20 kHz. Or choose the Model 1410, the full capability, single-channel instrument that has become the industry's standard for most engineering applications. Then there's the Model 1172, the ultimate Frequency Response Analyzer featuring all-digital signal processing, fully-isolated dual measurement channels and a computer-type keyboard entry. With the Model 1180 Plotter Interface, you can plot Bode, Nyquist, or Nichols diagrams with a conventional analog XY recorder.

Let EMR solve your frequency response problems . . . call or write for details or a demonstration.

Sangamo Weston, EMR Telemetry Division  
P.O. Box 3041, Sarasota, FL 33578  
813-371-0811

SANGAMO WESTON

Schlumberger



CIRCLE NUMBER 53

Data-path delay of 16-bit ripple-carry adder (+5 V and +25 C maximum delays)

Path	Output			Units
	F <sub>i</sub>	C <sub>n+4</sub>	OVR	
A <sub>i</sub> or B <sub>i</sub> to C <sub>n+4</sub>	36	36	36	ns
C <sub>n</sub> to C <sub>n+4</sub>	22	22	22	ns
C <sub>n</sub> to C <sub>n+4</sub>	22	22	22	ns
C <sub>n</sub> to F <sub>i</sub>	23	—	—	ns
C <sub>n</sub> to C <sub>n+4</sub> or OVR	—	22	22	ns
Total 16-bit delay	103	102	102	ns

5. Although a ripple-carry adder is slower than a lookahead, its 103-ns delay time for 16 bits is still fast by most standards.

ripple-carry adder, you can compare it directly with a 16-bit lookahead scheme for speed.

A 16-bit ripple-carry adder is built with 4-bit functional blocks having carry-output pins available. In Fig. 4, each 4-bit adder is an Am25LS2517, which replaces Am25LS381s when a carry output, C<sub>n+4</sub>, is required. Notice that no lookahead-carry generator is used, and all carry bits progress serially through 16 adders. Each C<sub>n+4</sub> carry output is connected to the succeeding adder's C<sub>n</sub>, carry input.

To compute delay time of a 16-bit ripple-carry scheme:

1. Select the longest combinatorial delay in the least significant bit adder; this path usually runs from operand inputs A<sub>i</sub> or B<sub>i</sub> to carry output C<sub>n+4</sub>.

2. Add the carry input to carry output delay as many times as necessary (twice for this 16-bit adder) to represent each intermediate 4-bit adder.

3. Add the delay from the final or most significant bit adder's carry input to sum output.

This computation is not the worst-case delay since mode changes are not included.

A delay chart (Fig. 5) shows the contribution of each adder. Here, as in a lookahead adder, the longest delay, 36 ns, is in a 4-bit adder, from operand inputs to sum outputs. Carry bits leaving the least significant adder pass serially through the next two adders, accumulating an additional 44 ns of delay. Delay through the most significant adder is 23 ns, and summing all delays gives a total of 103 ns for a 16-bit ripple-carry adder. Comparing ripple-carry and lookahead-carry delay, you find that ripple-carry is about 68% slower.

Worst-case ripple-carry delay (neglecting variations due to temperature and supply voltage) occurs when commands are changed via function select inputs. An extra 19 ns is needed to output a sum bit when the operating mode is changed and this must be added to the total delay. So the worst-case delay for a 16-bit ripple-carry scheme becomes 122 ns. ■

### References

1. Mick, John R., "Implement ALUs with Functional Blocks," *Electronic Design*, Jan. 4, 1978, pp. 120-123.

# I.F. cram course


In a nutshell, Plessey IC's will cut the costs, reduce the size, and increase the reliability of your IF strips.

Into each IC can, we've packed more functional capability than you would believe possible, especially once you've seen the prices.

Our IC's operate over the full MIL-temperature range and are a simpler, less expensive, more flexible alternative to whatever you're using now for any IF strip up to 240 MHz. Whether you're working with radar and ECM, communications, weapons control or navigation and guidance systems.

Let's go through the diagram function by function and we'll show you exactly what we mean.

**The log IF strip** is based on the Plessey SL1521, the simplest, easiest-to-use and least expensive wideband amplifier you can buy. It has a gain of 12 dB and an upper cut-off frequency of 300 MHz (our less expensive SL521 is available if you're working under 100 MHz). The SL1522 is two 1521's in parallel with a resistive divider for increasing the IF strip's dynamic range, while the SL1523 is two 1521's in series. With these devices, it takes just five cans and a single interstage filter to build a log IF strip at  $160 \pm 15$  MHz with a logging range of 90 dB,  $\pm 1$  dB accuracy,  $-90$  dBm tangential sensitivity and a video rise time of 20 nsec or less. It's reliable, inexpensive and field repairable, which is more than can be said about the hybrids or discretets you're buying now.



**On the video output,** our SL541 op amp matches the IF strip to your system, and lets you vary video sensitivity. It has the high slew rate ( $175 \text{ V}/\mu\text{sec}$ ), fast settling time (1% in 50 nsec) and high gain stability you need, with on-chip compensation so it's not tricky to use.

**For the front end,** just slip in the Plessey SL1550 to improve your noise figure, dynamic range and sensitivity. The SL1550 is a low noise, AGC-able preamp with a bandwidth of 320 MHz, 2 dB noise figure and 38 dB gain.

**And for the IF output,** the Plessey SL560 buffer amp/line driver operates up to 320 MHz with a noise figure less than 2 dB, gain of up to 40 dB, and drives 50 ohm lines with a minimum of external compensation (none in this application).

If all this looks almost too easy, send for complete details today.

When it comes to communications IC's, nobody delivers like Plessey can.



**PLESSEY SEMICONDUCTORS**

1641 Kaiser Avenue, Irvine, CA 92714.  
Telephone (714) 540-9979

**State-of-the-art brought down to earth**

## Twin-tee filter rejects more than 70 dB with capacitance-multiplier circuit

A capacitance-multiplier circuit, whose effective capacitance you can vary with a potentiometer, allows you to trim twin-tee notch filters to obtain more than 70-dB rejection. The gain of the circuit's op amp is varied with a 120-k $\Omega$  variable resistor. Signals across the filter's 0.068- $\mu$ F shunting capacitor are sensed by the amplifier and inverted. The inverted voltage is in series-aiding with the capacitor's signal swing. Consequently, increased current flows through the capacitor as if its capacitance were larger than the 0.068- $\mu$ F value (remember the old Miller effect?).

Twin-tee notch filters are excellent for removing single-frequency interference produced by 60 and 400-Hz power lines, but tuning the filters is usually difficult. Normal variable capacitors have values that are too low for use below 5 kHz and fixed capacitors limit adjustment flexibility.

The multiplier circuit's effective capacitance is

$$C_{\text{eff}} = 0.7 C (A_{\text{CL}}), \quad (1)$$

where the op-amp's gain is

$$A_{\text{CL}} = 0.2 + 0.67/x \quad (2)$$

In Eq. 2,  $x$  is a fractional number that represents the unshorted portion of the gain-setting potentiometer. Because of the high impedance of the feedback tee-resistor network, a high-value summing resistor of 3.9 M $\Omega$  can be used, which limits loading of the filter network.

The circuit's tuning range centers about the gain setting,  $x = 0.55$ , so  $C_{\text{eff}} = C$  and the null, therefore, occurs at a frequency

$$f_o = \frac{1}{\sqrt{2} \pi RC}$$

The component values in the figure tune to about 60 Hz. Of course, other values of  $f_o$  can be rejected by changing  $R$  and  $C$ , but keeping the proportionate relationships shown in the diagram.

A FET-input op amp limits the otherwise high output offset voltage that would result from any substantial input bias current in the feedback network. Although the op amp is capacitively coupled to the filter, a high offset voltage would decrease the

op-amp's signal-swing capability. For a 30% adjustment of  $C_{\text{eff}}$  the op-amp's closed-loop gain must be as high as two; therefore, only signals up to one-half the rated output voltage of the op amp can be handled by the filter without distortion.


The 3.9-M $\Omega$  summing resistor produces 1% attenuation of the low-frequency signals that pass the resistance-topped branch of the twin tee. At high frequencies, however, the signal path is through the two 0.1- $\mu$ F-capacitor branch, which isn't affected by the capacitor-multiplier circuit. To make the pass-frequency attenuation more uniform, connect a capacitor with a value of about  $C/100$  from the junction of the 0.1- $\mu$ F capacitors to ground.

### Bibliography

Wong, E. and Ott, W., *Function Circuits; Design and Applications*, McGraw-Hill, 1976.

Jerald Graeme, Manager, Monolithic Engineering, Burr-Brown Research Corp., International Airport Industrial Park, Tucson, AZ 85734.

CIRCLE NO. 311



**A gain-controlled capacitance multiplier** allows you to tune a twin-tee notch filter at low frequencies, where normal variable capacitors are impractical.




# More muscle for your microprocessor: Now there's a simpler way to trigger a triac, drive a digit, or light up a lamp.

One of our new addressable drivers can control up to eight peripheral devices in any bus-oriented system.

Next time you put a microprocessor to work, it may have more to manipulate than data. Real-world  $\mu P$  applications often require the kind of muscle that our new NE590/591 Addressable Peripheral Drivers can provide—simpler and less expensively than the usual combination of discrete power transistors and resistors. **Another First From Signetics.** Either of these new devices can give you a powerful alternative way to address and drive as many as eight different peripherals, using bits extracted directly from a bus. Each of the 8 latched Darlington outputs can drive a 250-mA load current, subject to power dissipation limitations. That's plenty of muscle for turning on (or off) LEDs, SCRs, stepping motors and a host of other commonly used peripheral components.

Most applications can be handled by the 16-pin NE590, which has 8 open-collector (current sinking) outputs. The NE591 is an 18-pin version with open-emitter (current sourcing) outputs. **Simpler Designs at Lower Costs.** A quick parts count and cost evaluation will demonstrate the device's dollar savings. The NE590N costs only \$1.95 in



100 quantity, the NE591N, \$2.45. You can do the same job with an addressable latch, but you'll need extra driver transistors and resistors that will bring your total parts cost—exclusive of assembly, testing and related expenses—to a considerably higher price.

Use NE590 or NE591 whenever you have multiple high-current peripherals to drive in any bus-oriented system. You'll simplify your design, improve reliability, reduce component and assembly costs. In short, you'll get more muscle for your money.

Addressable Peripheral Drivers. Available only from Signetics. Call your nearest distributor or send the coupon to us today for your data sheet, a sample, or quick attention to any application questions you have.

## Signetics

a subsidiary of U.S. Philips Corporation

Signetics Corporation  
811 East Arques Avenue  
Sunnyvale, California 94086  
Telephone 408/739-7700

### OTHER SIGNETICS DRIVERS

Part No.	Description	Output Current	No. of Drivers
NE582	LED digit drivers	400mA	6
ULN2001 series	Power drivers	500mA	7
NE5501 series	High-voltage power drivers	500mA	7
DS3611 series	Peripheral drivers	300mA	2
UDN5711 series	Peripheral drivers	300mA	2

To: Signetics Information Services, 811 E. Arques Ave.  
P.O. Box 9052, MS 27, Sunnyvale, CA 94086

- Send me your NE590/591 Data Sheet  
 Send me a sample of the NE590 for evaluation.  
 I need data on these other devices shown in the table:

I have an urgent requirement. Please have an applications specialist phone me at once: ( ) \_\_\_\_\_

Name \_\_\_\_\_ Title \_\_\_\_\_

Company \_\_\_\_\_ Division \_\_\_\_\_

Address \_\_\_\_\_ MS \_\_\_\_\_

City \_\_\_\_\_ State \_\_\_\_\_ Zip \_\_\_\_\_

(Note: For faster response, clip coupon to letterhead.) ED 118

# Switching supply converts -60 V to +5 and ±6.3 V with 83% efficiency

The switching-regulated dc-to-dc converter in the figure combines series-switching regulation and voltage conversion—and does it with just three signal and two power transistors and one voltage-regulator IC. With an efficiency of about 83% and regulation to within  $\pm 0.1\%$ , power output is 5 W at +6.3 V and 4 W at +5 V over an input range of -50 to -80 V (nominally -60 V).

The converter is a driven type, modified to be regulated by pulse-width modulation. Signal transistors  $Q_1$  and  $Q_2$  switch on and off alternately, driven by a 50% duty-cycle square wave. When  $Q_1$  is on, diode  $D_1$  is forward-biased and current flows through half the driver-transformer primary of  $T_1$ . The same thing happens for  $Q_2$  and  $D_2$ . The voltage developed across half the primary equals approximately  $(N_1/N_2)V_{BE}$ , where  $V_{BE}$  is the voltage across a converter power transistor,  $Q_3$  or  $Q_4$ , and  $N_1$  and  $N_2$  are the number of turns in half the primary and secondary, respectively. Capacitor  $C_3$  charges to twice the  $(N_1/N_2)V_{BE}$  voltage.

Because the voltage across  $C_3$  can't change instantaneously, the voltage across  $T_1$  gradually shifts from the conducting power transistor to the other transistor. This action produces a "dead time" that not only prevents damaging cross-conduction of the power transistors, but also reduces RFI noise. Dead time, which occurs when both power transistors don't have enough base-emitter voltage for conduction, is proportional to  $C_3$  and inversely proportional to the current from the controlled current source,  $Q_5$ .

Because inductor-input filters are used after the rectifier section,  $D_5$  through  $D_8$ , the output voltages are proportional to converter "live" time. And since dead time is inversely proportional to the controlled


source current, controlling source current controls the converter output voltage. A 723 regulator IC, loop filter and reference voltage before the current source complete the regulator loop.

The converter operates from -60 V, and the regulator operates from +19 V in the circuit shown. But, both can be made to operate from the same supply voltage. Resistor  $R_3$  helps damp out ringing in  $T_1$ . A current-limiting feature in the 723 regulator limits the maximum current from current-source  $Q_5$ ; resistor  $R_7$  determines this current. Resistors  $R_{11}$  and  $R_{12}$  average the two final output voltages for comparison with a 5.6-V reference voltage, which is determined by a selected resistor,  $R_{10}$ . Diode  $D_4$  helps minimize any overshoot occurring at turn on.

High efficiency is obtained with 1N5809 6-A rated, fast-switching rectifiers, although the output current is only 700 to 800 mA. Their low forward drops produce low switching losses. Higher efficiency can be obtained with Schottky power rectifiers.

*Philip M. Cowett, Jr., Electronic Engineer, U.S. Army, Harry Diamond Labs, 2800 Powder Mill Rd., Adelphi, MD 20783.*


CIRCLE No. 312



**A driven switching power supply** includes capacitor  $C_3$  to produce a gradual cross-over of power when switching from  $Q_1$  to  $Q_2$ . The resulting dead time

for  $Q_3$  and  $Q_4$  prevents cross-conduction and damage to the transistors, minimizes RFI and enables pulse-width modulation regulation.

# A simple warning. New LED flashes on/off all by itself.



Just apply 5 volts and our FRL-4403 flashes an attention-getting signal about three times a second. A built-in IC switches it on and off. And you can drive it directly by TTL and CMOS circuits.

Our "flasher" simplifies your design. Saves parts. Saves assembly labor. And it's priced to produce a net saving in the cost of your product.

Litronix recently affiliated with Siemens to bring you the broadest selection of optoelectronics available anywhere. For details on FRL-4403 contact Litronix, 19000 Homestead Road, Cupertino, Calif. 95014. Phone (408) 257-7910.

**From the New Giant  
in optoelectronics**

**litronix**

An affiliate of Siemens.

## Ideas for design

# Current inverters make current sources out of monolithic-IC d/a sink outputs

Convert the outputs of IC d/a converters from sinks to sources with an op-amp, floating, current inverter (see figure). Not only does the circuit provide a current-source drive from a current-sink input, it can also scale currents, to make the output much greater (or less) than the typical 2-mA full-scale d/a sink current. Virtually all IC d/a converters currently available have npn-based outputs. As a result, these converters are characteristically current sinks.

The op amp, acting as a precision, floating, current inverter, monitors an input current,  $I_{0A}$ , at its inverting input, which is the d/a's sink current.<sup>1</sup> With equal feedback resistors,  $R_1$  and  $R_2$ , the op amp then sources an equal current,  $I_{0B}$ , at its noninverting terminal. A load,  $R_L$ , can be referred to any potential within the d/a's voltage-compliance limits, as well as ground.

Currently, popular IC d/a converters include Precision Monolithics' DAC-08 (8-bit) and DAC-20 (2-digit BCD) and Analog Devices' AD561 (10-bit) units. These devices have nominal 2-mA current-sinking outputs, voltage-compliance ranges that extend to over 10 V, and output impedances of 20 M $\Omega$  or more.

An untrimmed 741 works reasonably well for 8-bit accuracy as a simple 1:1 current inverter. However, low-offset versions such as Analog Devices' AD741L or PMI's OP-02E guarantee 8-bit accuracy, and do well even to 10 bits. For micro-amp-level output (or input) currents, FET input devices such as National Semiconductor's LF355 or PMI's OP-15 should be used. Of course, if  $I_{0B}$  is to be more than a few milliamperes, a power op amp such as the Fairchild  $\mu$ A759— with an  $I_0$  to 350 mA—can be used for the floating current source and provide power output.


But no matter which op amp you select,  $R_1$  should provide a voltage drop of 1 V or more, at the maximum d/a current, to minimize the effect of op-amp offset. If output-voltage compliance is not a major factor,  $R_1$  can drop as much as 10 V, which will minimize offset-voltage errors.

Because both positive and negative feedback are used in the circuit,  $C_1$  provides more negative feedback and thus ensures stability. High d/a output impedance also helps stabilize the circuits.

### Reference

1. Gilbert, B., "Current Inverter with Wide Dynamic Range," *Analog Dialogue* 9-1, 1975.

Walter G. Jung, Consultant, Pleasantville Laboratories, Forest Hill, MD 21050. CIRCLE NO. 313



### IFD Winner of September 13, 1977

**George W. Masters**, Teledyne Microelectronics, 12964 Panama St., Los Angeles, CA 90066. His idea "Demand Power Supply Draws Low Standby Current" has been voted the most valuable of Issue Award.

**Vote for the Best Idea in this issue** by circling the number of your selection on the Reader Service Card at the back of this issue.

**SEND US YOUR IDEAS FOR DESIGN.** You may win a grand total of \$1050 (cash)! Here's how. Submit your IFD describing a new and important circuit or design technique, the clever use of a new component or test equipment, packaging tips, cost-saving ideas to our Ideas for Design editor. Ideas can only be considered for publication if they are submitted exclusively to ELECTRONIC DESIGN. You will receive \$20 for each published idea, \$30 more if it is voted best of issue by our readers. The best-of-issue winners become eligible for the Idea of the Year award of \$1000.


**LONG SCALE**  
3 1/2",  
4 1/2" Round  
3 1/2" Century



**CENTURY SERIES**  
1 1/2", 2 1/2"  
3 1/2", 4 1/2"



**WIDE-VUE**  
1 1/2", 2 1/2"  
3 1/2", 4 1/2", 8"



**BOLD-VUE<sup>®</sup>**  
2 1/2", 3 1/2"



**DIGITAL PANEL METERS**  
Low Cost series 2860  
Deluxe series 2850, 2852



**DESIGNER SERIES**  
3 1/2", 4 1/2"



**RUGGED SEAL**  
(Metal Cased)  
3 1/2", 4 1/2"  
4x6"

**RECTANGULAR**  
2 1/2", 3 1/2"  
4 1/2"



# Panel Meters Stock or Special SIMPSON has 'em!

Analog, digital, or Ana-Led<sup>®</sup>, if it's made, Simpson makes it.  
Over 1500 styles, sizes, ranges. If it's a special, we'll make it for you.

**ROUND**  
(Commercial and MIL spec)  
2 1/2", 3 1/2"  
4 1/2"



**EDGEWISE**  
3 1/2"



**ANA-LED  
SOLID STATE  
PANEL METERS**  
Bar or  
dot display



**EDGEWISE  
Barrel Type**  
1 1/2", 2 1/2"



**STACKABLE  
EDGEWISE**  
1 1/2", 2 1/2"



**RUGGED SEAL**  
3 1/2", 4 1/2"  
4x6"

**EDGEWISE**  
3 1/2"



**CONTACTLESS  
METER RELAYS**

single or double setpoint models available in DC microamp, milliamp, millivolt, AC ampere, AC voltage and temperature ranges.

SEE YOUR SIMPSON DISTRIBUTOR  
OR WRITE FOR FULL-LINE CATALOG



**SIMPSON ELECTRIC COMPANY**

853 Dundee Avenue, Elgin, Illinois 60120  
(312) 697-2260 • Cable SIMELCO • Telex 72-2416

KATY  
INDUSTRIES



INDUSTRIAL  
EQUIPMENT  
GROUP

CIRCLE NUMBER 57

# abbott

## POWER SUPPLIES

### 2,685 answers to power supply questions.

Answers to better power and thermal efficiency. Answers to size and weight reductions. Answers to available off-the-shelf covered/open frame power supplies and transformers. And price and delivery answers.

These and many more answers can be found in our three product catalogs. And they're yours. Free. Just circle reader card number. Better yet, write or call Abbott. The Power Supply Specialist.

**Power Supply Catalog** — Comprehensive 60-pager describes our full line of 1,573 hi-efficiency, hermetically sealed, single and dual output power supplies and switcher modules. Inputs of 60 and 400Hz and DC are available with outputs from 3VDC to 740VDC, 1 to 250 Watts. Prices start as low as \$174 for 2-4 units.

**Circle Card Number 90**

**Industrial Power Supply Catalog** — Some 279 of our low cost, high quality OEM power modules are detailed in this 16-pager. Includes covered/open frame, AC to DC single, dual and triple output versions, with outputs from 5 to 36VDC, 0.5 to 320 Watts. Plus DC to AC converters with 50 and 60Hz outputs. Priced as low as \$35 for up to 24 units.

**Circle Card Number 91**

**Transformer Catalog** — A 20-pager for the do-it-yourself power supply designer with instructions on how to specify for your custom units. Also covers 833 of our standard military, industrial and miniature pcb power transformers. Included are 60 and 400Hz, single phase input units, with prices starting as low as \$5.10 for up to 9 pieces.

**Circle Card Number 92**

See Power Supply Section 4000, and Transformer Section 5600, Vol. 2, of your EEM catalog; or Power Supply Section 4500, and Transformer Section 0400, Vol. 2, of your GOLD BOOK for complete information on Abbott products.

abbott

transistor

LABORATORIES, INCORPORATED

General Offices  
5200 W. Jefferson Blvd., Los Angeles 90016  
(213) 936-8185 Telex: 69-1398

Eastern Office  
1224 Anderson Ave., Fort Lee, N.J. 07024  
(201) 224-6900 Telex: 13-5332

## Video-disc system uses record-like platters

A video-disc system from Matsushita Electric Industrial Co. Ltd. uses plastic platters similar to standard audio records. As a result, the polyvinyl chloride discs can be manufactured on audio-record production equipment, so they won't cost as much as discs designed for laser, capacitive, or compression playback, like the ones proposed by Philips, RCA and Telefunken/Decca.

The Matsushita disc has a 30-cm diameter and is 2 mm thick. It spins at 450 rpm and provides 30 minutes of audio and video signals on each side with a track pitch of 4.6 microns, or 60 minutes per side with a 2.3-micron track pitch. The retail price for a one-hour disc is expected to be about 20 to 50% greater than that of conventional audio records.

The disc, which handles video and two channels of audio on a bandwidth of 10 MHz, is cut in real time with a micro-cutting stylus that is ultrasonically driven by a piezoceramic material device. With conventional mechanical cutting methods, the master disc rotates at a fraction of playing speed, so the signal must be divided propor-



tionately to permit high frequencies to be engraved.

Matsushita's video-disc system, the VISC, includes a player that is projected to sell in Japan for \$480 to \$600. The player has an NTSC color signal with a signal-to-noise ratio of 45 dB and more than 270 lines of resolution. Audio bandwidth is 20 kHz, and audio s/n is about 60 dB.

Matsushita will hold off on marketing the VISC until it gets support from software suppliers, since the company feels "strong consumer acceptance of the video-disc player will depend to a significant degree upon the easy availability and wide range of quality software."

## Grounding simplified with conductive cement

A conductive building material that mixes with cement makes it much easier to ground installations for rf transmitters, computers and similar equipment.

Normally, such installations are grounded by making connections to a network of wires buried in the ground outside and around a building. The location of these earth-electrode systems can help avoid mutual interference between equipments in the building.

With Marconite, developed by Marconi Communication Systems Ltd.

of Chelmsford, England, flooring, walls and sub-basement concrete structures can be produced with a predetermined volume resistivity. This concrete can also be used to form earth planes outside the building. Marconite can also be used in cathodic protection systems and as a high-loss tangent dielectric.

The volume resistivity varies from 0.5  $\Omega$ -cm or less for preformed, pressure-cured concrete sections to 15  $\Omega$ -cm for floors laid by hand. Where higher resistivities are required, such as for antistatic floors and high-loss dielectrics, the proportions of Marconite in the concrete mixture can be reduced by adding sand.

## Chlorinated compound for capacitors is safer

A safe nonchlorinated ester-based compound with excellent electrical properties has been developed to replace unsafe chlorinated hydrocarbons in high-voltage capacitors.

The highly toxic nature and long term stability of chlorinated hydrocarbons, commonly used as power capacitor dielectrics not only make them unsafe but also ecologically unsound. However, the new liquid, benzyl neocaprinate, has been demonstrated to be both nontoxic and easily biodegradable by common bacteria.

The compound took five years of joint research by Rhone-Poulenc, France, and ASEA, Sweden, to be developed. Rhone-Poulenc is now planning large-scale production and will make the fluid available to all capacitor manufacturers. ASEA is already producing capacitors using the fluid.

## Fiber-optic connector places/aligns fibers

A new type of optical fiber connector eliminates a major problem hampering present connectors—the high cost of precision machine assemblies required for aligning the fibers precisely. Available connectors must first accurately mount the fiber in a ferrule, then align the ferrules in an external sleeve. The new connector developed by the British Post Office at its Research Center in Martlesham Heath Ipswich aligns and locates fibers simultaneously.

In the connector, a set of three small spheres of the same size accurately self-aligns with a similar set rotated through 60°. When the two sets are pressed together the balls rotate and lock into alignment, which leaves a small hole in the center.

Connectors for a fiber of 125- $\mu$ m diameter require tungsten balls of 810- $\mu$ m diameter, mounted in the sleeve one set behind the other. These balls are readily available.

# FOR ENGINEERING MANAGERS — WORLDWIDE

NO OTHER ELECTRONICS PUBLICATION PRESENTS INDUSTRY EXECUTIVES LIKE THESE:

FRED BUCY  
JOHN FLUKE  
EDUARD PANNENBORG  
DAVID METHVIN  
JIM WOLFE  
RAY STATA  
AND MANY, MANY OTHERS

*Electronic Design* subscribers tend to move up in the ranks. That's why 66% of our qualified subscribers — worldwide — hold management titles. And that's why we regularly print articles and features of special interest to management (such as the extremely popular *Challenges to the Engineer Who Manages* series). For example, did you read "Fred Bucy of TI Speaks on Managing Innovation" in a recent issue? Where else can you find articles by well-known industry executives talking to you about engineering management problems? *Electronic Design* speaks with authority to the men in authority.

## Electronic Design. 5

Today's scientific calculators: They've got more functions and more of the hand-held ones are programmable. Some hand-helds even come with memories that retain data when they're turned off. Others include solar-array battery chargers and hard-copy printouts. Battery life is still a problem. For details, see p. 20.



FOR ENGINEERS AND ENGINEERING MANAGEMENT — WORLDWIDE!



# The \$995\* Solution to a \$100,000 Problem— Superpac!



Imagine your systems product with an intelligent front-end that combines TTY keyboard layout and CRT with the best industrial microcomputer money can buy. Now dump those scary development cost estimates in the round file. Because it's here today. At a price that's hard to believe! And behind it is the most complete line of standard industrial microcomputer hardware and software available anywhere. Microcomputer and memory boards. Digital I/O. Analog interfaces. Industrial packages. Complete Real-Time Operating System and FORTRAN compiler.

That's what PCS is all about. And that's why we've sold more industrial microcomputers than anyone else in the business.

Please send me more information about  Superpac  
 PCS single-board microcomputers  PCS packaged systems  PCS customer support capabilities.  
 Please have a salesman call.

Name \_\_\_\_\_

Title \_\_\_\_\_

Company \_\_\_\_\_

Street \_\_\_\_\_

City \_\_\_\_\_ State \_\_\_\_\_


Telephone \_\_\_\_\_ Zip \_\_\_\_\_

\*In quantities of 50



**PROCESS COMPUTER SYSTEMS, INC.**  
 750 North Maple Road  
 Saline, Michigan 48176  
 313-429-4971 TWX: 810-223-8153

# Arrow-M R Relays




The many advantages and unique capabilities of Arrow-M's R Relays are far too extensive to be covered here. Therefore, we'd like to whet your creative appetite with a few outstanding facts:

1. Arrow-M R Relays are available in 1 Form C contacts which can carry a high current capacity of 1 Ampere 20 watts, and are capable of resisting welding at higher inrush currents. The dry circuit type which can switch current as low-level as 100uA is available in addition to the power type.

2. *High Speed:* Arrow-M R Relays can be operated at 500 cycles/sec.

## The tiny power memory reed



3. Greater reliability and lower cost, due to simultaneous automatic fabrication of coil bobbin, contact and terminal.

4. In addition to the standard there are 1 coil and 2 coil latching types, which are useful for logic circuit design as a memory component.

5. Not only can they be automatically wave soldered on PC boards with a high density of electronic parts, but they are simple to clean with most degreasers and detergents without affecting maximum contact reliability.

6. *High Sensitivity:* Minimum operating power: Single Side Stable 80 mw/Bistable 40 mw

7. *Longer Life:* Mechanical: More than  $10^9$  operations. Electrical: More than  $10^6$  operations. (1A 20vdc, 0.3A 110vac)

Hungry for more information? For exact specifications on all of our relays, write or call your nearest Arrow-M office.

**Arrow-M Corporation**  
250 Sheffield Street  
Mountainside, NJ 07092  
(201) 232-4260

*Mid-Western Office:*  
600 E. Higgins Rd.  
Elk Grove Village, Ill. 60007  
(312) 593-8535

*Western Office:*  
22010 So. Wilmington Ave.  
Suites 300 & 301  
Carson, Calif. 90745  
(213) 775-3512



**Arrow-M**

Member of Matsushita Group


Relays for Advanced Technology

CIRCLE NUMBER 62

ELECTRONIC DESIGN 2, January 18, 1978

# New products

## Mass-produced precise and stable resistors surpass wire-wound units



Caddock Electronics, Inc., 3127 Chicago Ave., Riverside, CA 92507. (714) 683-5361. 1 M $\Omega$ , 0.01%: \$4.43; 1 M $\Omega$ , 0.1%: \$2.04 (1000 qty); stock.

Caddock's TF series of oxide-film resistors overcome limitations of other precision-resistor types with these five advantages of the new Tetrinox thick-film, complex-oxide technology used to make them:

1. Resistance values as high as 10 M $\Omega$ . A 10-M $\Omega$  wire-wound resistor needs over half a mile of expensive fine wire. For example, a Dale wire-wound unit (WW412,  $\pm 0.01\%$ , 0.75 W) costs about \$40 compared to \$10.32 for a  $\pm 0.01\%$  tolerance TF050N in quantities of 1000. And Vishay's ultraprecision resistors reach only to 100 k $\Omega$  in single resistors, so they're out of this race.

2. Temperature coefficients as low as 5 ppm/ $^{\circ}\text{C}$  from  $-55$  to  $105^{\circ}\text{C}$ . The TF050N's 15 ppm/ $^{\circ}\text{C}$  tempco rivals Dale's WW412's 20 ppm/ $^{\circ}\text{C}$ .

3. Long-term stabilities as low as 0.005% per 1000 hours, which is comparable to the best wire-wounds.

4. Tolerances as close as  $\pm 0.005\%$ , also comparable to the best wire-wounds (and Vishay foil units).

5. High-volume production, which costs less than the special production methods and often painstaking hand labor required when producing ultra-

fine-wire, high-resistance, wire-wound units.

The stability inherent in Tetrinox technology allows design engineers to use relaxed tolerances. Values of as high as  $\pm 0.01\%$  can be used without compromising long-term stability. To attain the same stability with other resistor types, you must often use  $\pm 0.005\%$  tolerance, according to Caddock.

Caddock's  $\pm 0.01\%$ -tolerance units can achieve a total-error-band stability of 0.02% for 1000-h operation under full load conditions—according to Caddock. Extensive tests have shown that the average drift under full load and maximum ambient temperature ( $70^{\circ}\text{C}$ ) for large test samples is less than 0.008%, or 80 ppm, after the first 1000 h.

The Tetrinox resistance film is a thick-film complex-oxide system in a glass matrix, fired onto an aluminum-oxide ceramic substrate. Caddock believes the film to be the first and only nonmetallic resistance material that can consistently produce a tempco within 5 ppm/ $^{\circ}\text{C}$  along with ultra long-time stability. Further, the material can be laser-trimmed in complex patterns without disturbing stability, whereas most thick and metal-alloy films tend to lose stability, and are thus

limited to simple cutting patterns.

Moreover, the Tetrinox film provides high sheet resistivity ranging from 500 to 50,000  $\Omega/\text{square}$ . Fine nickel-chrome alloy wire (0.0005-in. dia) provides 3200  $\Omega/\text{ft}$ , and evaporated nickel-chrome only 200  $\Omega/\text{square}$ .

Vishay's nickel-chrome foil furnishes a low 2  $\Omega/\text{square}$  in practical thicknesses. For those reasons, it takes 100 Vishay-foil, 100-k $\Omega$ , S102 resistors or half a mile of the fine wire to make a 10-M $\Omega$  resistor.

Caddock

CIRCLE NO. 306


Dale

CIRCLE NO. 307

Vishay

CIRCLE NO. 308

## Mini dry-reed switch handles 115 VA



Hamlin, Lake & Grove Sts., Lake Mills, WI 53551. W. Bruenger (414) 648-2361. \$0.58 (5000 qty).

The MRT-2 miniature dry-reed switch has a 115-VA, resistive, rating and a 0.13-in. diameter by 0.8-in. length glass case. The maximum switching voltage is 200 V and contact resistance is 0.1  $\Omega$  max. Insulation resistance is  $10^8 \Omega$ .

CIRCLE NO. 309

## Low-cost, flashing red LED has built-in IC timing circuit

Litronix Inc., 19000 Homestead Rd., Cupertino, CA 95014. Terry Snowden (408) 257-7910. P&A: See text.

Lumen for lumen, flashing indicator lights attract attention far more effectively than steady-on lights. So Litronix has put a red LED lamp, the 650-nm FRL-4403, into a T-1-3/4 envelope with an IC timer. The unit flashes on and off approximately 2.5 times a second with an almost 50% duty cycle, whenever a steady 5 V is applied to its two leads.


The built-in IC flasher eliminates external switching circuitry. Of course, the LED can be driven directly from TTL circuits; it needs only 20 mA of drive current.

The FRL-4403 can operate over a range of 2 to 10 V, but then the flashing rate varies from once per second to nine times per second.


The lamp's viewing half-angle is 45° (at the 50% intensity points), and it delivers 1.2-mcd peak intensity.

Best of all, the price is hard to beat—a low \$0.59 in quantities of 1000. The FRL-4403 is available from stock.

CIRCLE NO. 305



## Reed relay offers low thermal EMF




Coto-Coil, 65 Pavilion Ave., Providence, RI 02905. Bill Poisson (401) 467-4777.

Low thermal-EMF reed relays, CR-3300, are used in input switching. They are epoxy-encapsulated in a flame-retardant polyester case (SE-O rated), and coated with a silicone rubber to provide stress-free encapsulation. Tinned electrolytic-copper pins minimize thermal-EMF junctions at the PC-board connections. The coil and coil terminations are well isolated from the switches and shield. They provide 1500-V-rms isolation between control and signal circuits. All relays are magnetically shielded.

CIRCLE NO. 322

## Mini film/foil caps come taped or reeled




Seacor, 598 Broadway, Norwood, NJ 07648. (201) 768-6070. See text; stock to 4 wks.

Available taped or reeled for automatic-assembly operations, Type 102 capacitors use a polyester wrap with extended foil to give a noninductive characteristic. The capacitors come in values from 0.001 to 0.47  $\mu\text{F}$  at 100 to 600 V dc. Dissipation factor is 0.75% max at 1 kHz and 25 C. Operating temperature range is -40 to 125 C with voltage derated 1.5%/°C above 85 C. Size ranges from 0.197 to 0.625-in. diameter and length from 0.433 to 1.437 in. Price is \$0.063 (5000 qty) for a 0.01  $\mu\text{F}$ , 20%, 200-V unit.

CIRCLE NO. 323

## Ceramic capacitors fit with DIPs




EMCON, P.O. Box 81542, San Diego, CA 92138. Tom Sale (714) 459-4355.

Empac type 501 ceramic capacitors have a DIP configuration with maximum case height of 0.135 in., width of 0.28 in. and thickness of 0.1 in. Lead spacing meets IC-package circuitry specs. Type Z5U, X7R and COG (NPO) dielectrics with capacitances from 10 pF to 0.47  $\mu\text{F}$  are available in voltages of 25, 50 and 100 WV dc.

CIRCLE NO. 320

## Thermal reed switch senses temperature



George Ulamet, 413 Market St., Newark, NJ 07105. (201) 589-4876. \$1 (1000 qty); 6 to 8 wks.

The OHD series of thermal reed switches uses a temperature-responding ferrite as a sensing element and a reed switch as an actuating trigger. The switches are rated at 120 V ac, 0.5 A. The maximum mean differential is 10 C and operating range is from 60 to 130 C. Both open-on-rise and close-on-rise switches are available.

CIRCLE NO. 321

# How fast can you accurately measure period or frequency of this wave form?



## The old way.

(About 5 minutes)

1. Find a scope and voltmeter
2. Connect signal to scope.
3. Determine proper trigger points.
4. Connect signal to counter.
5. Select period or frequency function.
6. Select time base.
7. Set input voltage range.
8. Set input coupling to DC.
9. Connect voltmeter to trigger level output - if counter has output. (If not, good luck.)
10. Set desired trigger level.

## The easy way.

(About 5 seconds)

1. Connect signal to Racal-Dana 9000 counter.
  2. Push **P** or **FA** button.
  3. Push **TL** button.
  4. Push **AU** button.
- The rest is automatic.


## Now it's up to you.

You can continue to struggle along the old way. Or you can find out about the Racal-Dana 9000 Microprocessing Timer/Counter. The patented Auto-Trigger capability makes it the fastest and most accurate instrument in the world for the precision measurement of wave forms. Give us a call and we'll tell you how Racal-Dana systems technology can solve all your measurement problems the easy way.

**RACAL-DANA**  
Others measure by us.

## COMPONENTS

### Ceramics can replace crystals and LCs




Murata Corp. of America, 1148 Franklin Rd., S.E., Marietta, GA 30067. (404) 952-9777. \$0.30 to \$0.35 (5000 qty).

A line of piezoelectric ceramic resonators can replace quartz crystals and LC networks for audio and rf generation. These resonators are offered in two frequency ranges—195 to 600 kHz and 3 to 12 MHz. The units have a frequency tolerance of  $\pm 2$  kHz in the lower frequency ranges and  $\pm 0.05\%$  in the higher ranges. Temperature stability is 35 ppm/ $^{\circ}\text{C}$  from 195 to 600 kHz and  $\pm 20$  ppm/ $^{\circ}\text{C}$  from 3 to 12 MHz. Dimensions for the largest unit in the line (lowest frequency) are about  $13 \times 14 \times 4$  mm.

CIRCLE NO. 324

### Pushbutton code switch comes in four formats



IVO Industries, 1109 Green Grove Rd., Neptune, NJ 07753, John Becker (201) 922-3600. \$3.50; stock.

A modular bidirectional pushbutton code switch, designated C3, comes in four formats: decimal, BCD, plus/minus and BCD complement. The switch carries loads up to 0.5 A at 60 V. Switch elements snap-lock together in any combination to form a dense switching assembly that spring locks into a simple rectangular cutout. A single switch element is 0.945-in. high, 0.3-in. wide and weighs 0.158 oz.

CIRCLE NO. 325


### Inverter transformers operate at 15 to 25 kHz

Pulse Engineering, P.O. Box 12235, San Diego, CA 92112. John Kerr (714) 279-5900. \$7.60; stock.

A line of encapsulated ferrite-core inverter transformers are usable both in saturated or in driven nonsaturated states within a frequency range of 15 to 25 kHz. Output voltages of  $\pm 6$ ,  $\pm 9.5$  or  $\pm 19$  V dc can be obtained, after rectifying and filtering. Models designed for input voltages of 5, 12.6 or 29 V dc are available. Nine models provide power ratings from eight to 25 W. The transformers are packaged for PC mounting. Board space is  $0.94 \times 0.775$  in. for the 8-W unit and  $1.2 \times 1$  in. for the 25-W part. Max heights are 0.8 and 1 in., respectively.

CIRCLE NO. 326

### Thick-film circuit is audio power driver



Centralab Electronics, 5757 N. Green Bay Ave., Milwaukee, WI 53201. A.J. Koschnick (414) 228-2751. \$2.95 (1000 qty).

The audio power driver is a thick-film hybrid circuit in a Class AB quasi-complementary audio configuration that can drive a pair of external npn power transistors. By proper selection of power output transistors, audio amplifiers in the range of 3 to 35 W can be designed. The driver provides up to 150-mA drive current at low distortion (1%) over a typical bandwidth of 22 kHz.

CIRCLE NO. 327

### Chip thermistors are directly solderable

Keystone Carbon, St. Marys, PA 15857. John Brock (814) 781-1591.

Chip thermistors have silver-contact pads that can be soldered with silver-bearing soft solders by IR-reflow, hot-tip or immersion techniques. Size of chips is  $0.1 \times 0.5 \times 0.01$  to 0.06 in. thick. The small size results in low thermal mass, fast response time, and a low dissipation constant of 2.5 mW/ $^{\circ}\text{C}$ . Resistance values range from 3 to 20 k $\Omega$ .

CIRCLE NO. 328

# Call your nearest ISC sales representative.

**ALABAMA:** Huntsville  
W. A. Brown Inst. Inc. 205/539-4411  
**ARIZONA:** Phoenix  
Thorson Co. 602/956-5300  
**CALIFORNIA:** Goleta  
Thorson Co. 805/964-8751  
**CALIFORNIA:** Los Angeles  
Thorson Co. 213/476-1241  
**CALIFORNIA:** Mountain View  
Thorson Co. 415/964-9300  
**CALIFORNIA:** San Diego  
Thorson Co. 714/298-8385  
**CALIFORNIA:** Tustin  
Thorson Co. 714/544-5121  
**COLORADO:** Denver  
Thorson Co. 303/759-0809  
**FLORIDA:** Ft. Lauderdale  
W. A. Brown Inst. Inc. 305/776-4800  
**FLORIDA:** Melbourne  
W. A. Brown Inst. Inc. 305/723-0766  
**FLORIDA:** Orlando  
W. A. Brown Inst. Inc. 305/425-5505  
**FLORIDA:** Valparaiso  
W. A. Brown Inst. Inc. 904/678-7932  
**GEORGIA:** Atlanta  
W. A. Brown Inst. Inc. 404/939-1674  
**ILLINOIS:** Arlington Hts.  
Future Systems 312/640-6091  
**LOUISIANA:** Gretna  
W. A. Brown Inst. Inc. 504/366-5766  
**MARYLAND:** Bethesda  
Bartlett Assoc. 301/656-3061  
**MASSACHUSETTS:** Framingham  
Bartlett Assoc. 617/879-7530  
**MICHIGAN:** Madison Hts.  
WKM Associates 313/588-2300  
**NEW MEXICO:** Albuquerque  
Thorson Co. 505/265-5655  
**NEW YORK:** White Plains  
Bartlett Assoc. 914/949-6476  
**NORTH CAROLINA:** Durham  
W. A. Brown Inst. Inc. 919/682-2383  
**OHIO:** Cleveland  
WKM Associates 216/267-0445  
**OKLAHOMA:** Norman  
Data Marketing Assoc. 405/364-8320  
**PENNSYLVANIA:** Pittsburgh  
WKM Associates 412/892-2953  
**PENNSYLVANIA:** Wayne  
Bartlett Assoc. 215/688-7325  
**SOUTH CAROLINA:** Columbia  
W. A. Brown Inst. Inc. 803/798-3297  
**TENNESSEE:** Knoxville  
McCain Elec. Equip. 615/584-8411  
**TEXAS:** Austin  
Data Marketing Assoc. 512/451-5174  
**TEXAS:** Dallas  
Data Marketing Assoc. 214/661-0300  
**TEXAS:** Houston  
Data Marketing Assoc. 713/780-2511  
**TEXAS:** San Antonio  
Data Marketing Assoc. 512/828-0937  
**WASHINGTON:** Bellevue  
Thorson Co. 206/455-9180  
**AUSTRALIA:** Mt. Waverly, Victoria  
Anderson Digital Elec. 03-543-2077  
**CANADA:** Montreal  
Cantec Rep. 514/620-3121  
**CANADA:** Ottawa  
Cantec Rep. 613/225-0363  
**CANADA:** Toronto  
Cantec Rep. 416/624-9696  
**EUROPE:** England  
Techex, Ltd. 0202-293-115  
**EUROPE:** France  
Peritex 749-40-37  
**EUROPE:** Switzerland  
Interst, AG 031-224481  
**JAPAN:** Tokyo  
Munzing International 586-2701



**Intelligent Systems Corp.**

# \$995



Unretouched  
photograph  
of screen

**Get the jump on your competition without outspending your competition.**

We're Intelligent Systems Corporation, and we've just lowered the price of our Intecolor 8001 to \$995. So now you can upgrade the terminals in the systems you're marketing to color at black and white prices.

The fact is that the Intecolor 8001 has the best price-performance ratio of any intelligent data entry terminal on the market—color or black and white. And that can really add some punch to your sales story. So can color, not because it looks better, but because it

communicates better than black and white.

And if you're marketing your systems by promoting the stand-alone capabilities of your terminals, we've got a list of options that'll give you just about any degree of sophistication you want. Including disk storage devices, bi-directional desk-top line printers and a brand new 2708/2716 PROM programmer.

Contact the ISC rep nearest you. We guarantee delivery of your Intecolor 8001 evaluation unit for \$995 (cash-with-order) within 30 days or your money back. Or if you've seen

the Intecolor 8001 in action and you're already sold on the price and performance, we'll give you the same \$995 price for orders of 100 units or more. Get the jump on your competition without outspending your competition. Get the Intecolor 8001.




**Intelligent Systems Corp.**

5965 Peachtree Corners East  
Norcross, Georgia 30071  
Telephone 404-449-5961 TWX: 810-766-1581

## COMPONENTS

### LCD meter is housed in analog-type case




International Microtronics, 4016 E. Tennessee St., Tucson AZ 85714. Otto Fest (602) 748-7900. \$45 (100 qty).

The Model 800 LCD digital panel meter is housed in a standard 3-1/2-in. analog-meter case. The display is a 0.75-in. high transfective type. For low ambient light, or in darkness, an optional backlight is available. The meter features autozeroing, bipolar-input capability and over 1000-M $\Omega$  input impedance. Accuracy is  $\pm 0.05\%$  FS  $\pm 1$  digit.

CIRCLE NO. 329

### Mini resistance trimmers use carbon on ceramic



International Importers, 2444 S. Western Ave., Chicago, IL 60608. Jeff Swanson (312) 254-4252. \$0.10 (10,000 qty); 8 to 10 wks.

HDK trimmers are made with carbon-film resistance elements on a miniature ceramic base. The trimmers have self-supporting terminals and knobs or shafts. Resistance elements are enclosed to prevent solder and dust penetration. Perpendicular and parallel mountings are available. The power rating is 0.3 W at 70 C, and the resistance range is 200  $\Omega$  to 1 M $\Omega$ .

CIRCLE NO. 330


### Pots and resistors combined in one package

Bourns, Trimpot Products, 1200 Columbia Ave., Riverside, CA 92507. Bill Galvan (714) 781-5204.

Multifunction trimmers (MFT) combine cermet trimming potentiometers and resistor networks into one assembly. Nine configurations of the multiple trimmer and network combinations are offered. Packaged in DIPs, the assemblies are compatible with auto-insertion and automatic-test equipment. Five basic trimmer configurations in nine different models are packaged with various combinations of trimmers and resistor networks in 6, 8, 14 and 16-pin DIPs. Two models are available for op-gain trim applications.

CIRCLE NO. 331

### Digital display counter works in hostile areas



Scientific Technology, 1201 San Antonio Rd., Mountain View, CA 94043. T. Scholten (415) 965-0910. \$85; 3 wks.

A six-digit-display event counter is for severe industrial use in hostile environments. The LED display, counter circuitry and power supply are mounted in an aluminum-die NEMA 4 and 12 rated enclosure. Counting rate is up to 1 MHz and input-power sources from 12 V dc to 240 V ac can be accommodated. Standby battery power is also available. The unit accepts either contact closure or logic inputs.

CIRCLE NO. 332


### Power resistor is noninductive

Vishay Resistive Systems, 63 Lincoln Hwy., Malvern, PA 19355. (215) 644-1300.

Hermetically sealed power resistors, Model VHP-3, are noninductive and have a 2.5 ppm/ $^{\circ}$ C tempec. Inductance is typically only 0.08  $\mu$ H; rise time 1 ns; and noise  $-32$  dB. Power rating, either chassis mounted or with a heat sink, is 10 W; 3 W in free air. Maximum working voltage is 750 V, resistance range is 10  $\Omega$  to 39.2 k $\Omega$  and they are available to  $\pm 0.01\%$  tolerance.

CIRCLE NO. 333

### Capacitors are thin metallized polyester



TRW Capacitors, 301 W. "O" St., Ogallala, NE 69153. (308) 284-3611. From \$0.35; stock to 10 wks.

Lightweight metallized-polyester capacitors with a thin oval shape, types X663F and X663FR are as small as 0.93  $\times$  0.187  $\times$  0.438 in. The units are axially leaded, have a voltage range of 50 to 600 V dc and a dissipation factor of less than 1% at 1000 Hz. The capacitance values for the two types range from 0.01 to 10  $\mu$ F and the operating temperature range is  $-55$  to 100 C.

CIRCLE NO. 334

### Indicator lights offer press-to-test feature

Dialight, 203 Harrison Pl., Brooklyn, NY 11237. (212) 497-7600.

Indicator lights have a press-to-test feature that can check the lamp in a normally deenergized indicator circuit. Finger pressure on the lens cap breaks the normal circuit and connects a test circuit. The indicators are available in subminiature, miniature and large sizes for mounting holes from 0.469 to 1 in., with neon or incandescent lamps. The QPL approved lights meet the requirements of MIL-I-7961B and L-3661.

CIRCLE NO. 335



# Berg Interconnection System sews up the electronics in the Athena 2000 machine by Singer.



Berg supplied 80% of the low voltage interconnect system for the Athena 2000 sewing machine by Singer—world's first electronic push button home sewing machine.

Singer likes its new electronic design which eliminates more than 350 mechanical parts while assuring reliable performance. Singer has found it can rely on Berg . . . to supply the products and the application machines that precisely meet its interconnection needs.

Berg is experienced. We read interconnection needs like Singer reads patterns. We have the products, the background, and the back-up to do the job. Your job. Let's work on it, together. Berg Electronics Division. E. I. du Pont de Nemours & Co., New Cumberland, PA 17070—Phone (717) 938-6711.


 **BERG ELECTRONICS**  
REG. U.S. PAT. & TM. OFF.

**We serve special interests—yours!**



## INSTRUMENTATION

### Logic probe uses pulse accumulator




AVR Electronics, Box 19299, San Diego, CA 92199. (714) 447-1770. \$22.95.

The Catch-a-Pulse Experimenter uses a pulse accumulator and LEDs that respond to single pulses up to 20  $\mu$ s. The probe will accumulate multiple pulses in pulse trains with frequency response greater than 40 MHz. It is compatible with RTL, DTL, TTL, CMOS, MOS and microprocessors using a 3.5 to 15-V power supply. Thresholds are automatically programmed. LEDs indicate HI, LO, bad level, open-circuit and pulses.

CIRCLE NO. 336

### Hand-held unit debugs micros




Computer System Dynamics, 7100 Broadway, Denver, CO 80221. (801) 487-8711. \$250.

A stand-alone microcomputer system analyzer (MSA-8) is a hand-held instrument that performs firmware and hardware debugging of 8080A, 8085 and Z80 microsystems. The device connects directly to the microprocessor. Data, address and a ready signal are displayed. Single step, single-step enable, trace enable and breakpoint thumbwheel switches are provided for control. Single step, hardware breakpoint and oscilloscope trigger capabilities are also included.

CIRCLE NO. 337

### Digital multimeter reads true-rms, dBm




Data Precision, Audubon Rd., Wakefield, MA 01880. (617) 246-1600. \$279; stock.

The Model 1750 3-1/2-digit multimeter offers 36 ranges and six functions in a 0.1% basic accuracy instrument. The meter measures dBm and HI/LO excitation resistance in addition to dc and true-rms ac volts and current. The unit measures dc V from 100  $\mu$ V to 1000 V; ac V from 100  $\mu$ V to 1000 V (true rms), with a frequency response of 10 Hz to 20 kHz; and dc current from 100 nA to 10 A. Also measured are resistance from 100 m $\Omega$  to 20 M $\Omega$ , and dBm directly from -60 to +20 dBm.

CIRCLE NO. 338

# If the ins and outs of microcomputers are the problem, we have the answer.

Texas Instruments  
TM 990/100M  
compatible



## Frequency counter spans 10 Hz to 18 GHz



Hewlett-Packard, 1501 Page Mill Rd., Palo Alto, CA 94304. (415) 493-1501. \$4500.

Keyboard control, coupled with a microprocessor, allows the Model 5342A microwave counter to measure both input-signal level and input frequency simultaneously over the range of 10 MHz to 18 GHz. The operator can define his own frequency offsets with a few keystrokes for fast receiver testing. Offsets may be positive or negative, and can be stored in memory for recall and display to the user. Frequency deviations about a given value are monitored.

CIRCLE NO. 339

## Function gen operates on ac or batteries



Exact Electronics, 455 S.E. 2nd Ave., Hillsboro, OR 97123. (503) 648-6661. \$250; 2 wks.

An ac or battery operated sweep-function generator, Model 117, offers sine, square, triangle, ramp and pulse outputs. The main output is variable up to 15 V pk-pk open circuit, 7.5 V pk-pk into 600  $\Omega$ . The unit has a range of 2 Hz to 200 kHz in three steps. Control of frequency can be internal with the frequency dial, or the unit will automatically sweep over a 1000:1 (3 decade) range, either linearly or logarithmically.

CIRCLE NO. 340

## Waveform gen sweeps up or down



Krohn-Hite, Avon Industrial Park, Avon, MA 02322. (617) 580-1660. \$295; 4 wks.

The Model 1200 sweep generator sweeps up or down and delivers 20-V pk-pk sine, square and triangular waveforms from 0.2 Hz to 3 MHz. The sweep duration is adjustable from 1000 s to 1 ms. Also included are a 1500:1 manual tuning dial, 5% fine-tune vernier, variable dc offset, external VC input, control-voltage output proportional to frequency and auxiliary TTL output with less than 15-ns rise and fall.

CIRCLE NO. 341



# All of them.

If your enthusiasm for microcomputers begins to wane when you suddenly face the real world of analog signal interfacing, your worries are over. Our complete family of real-time analog I/O subsystems gives you maximum convenience and versatility with the least uncertainty and frustration.

We have the answer to your analog I/O subsystem problems. All of them. All you have to do is ask. And we'll send you complete information on the entire RTI Series.

**ANALOG DEVICES**

The real company in  $\mu$ peripherals

Analog Devices, Inc., Box 280, Norwood, MA 02062 East Coast: (617) 329-4700; Midwest: (312) 894-3300; West Coast: (213) 595-1783; Texas: (214) 231-5094; Belgium: 031/37 48 03; Denmark: (02) 845800; England: 01/94 10 46 6; France: 686-7760; Germany: 089/53 03 19; Japan: 03/26 36 82 6; Netherlands: 076/879 251; Switzerland: 022/318704; and representatives around the world.

CIRCLE NUMBER 66

# You get variety, unique design, economy and more when you specify AMP's DIP sockets.

## You get more performance.

And that's what all the features of AMP's DIP and microprocessor sockets add up to.

Take variety. You can choose from standard and low profile housings, a wide range of sizes, tin or gold plated contacts, in widths of .300", .400" or .600". And that's only the beginning.

There's design and economy. DIP socket contacts include a unique retention feature. It makes sure that every socket you insert into a pc board will stay there, even during the soldering process.

The design also prevents solder wicking problems. And with AMP automatic insertion equipment,

AMP has a better way.


the sockets can be installed at rates to meet your production needs.

And don't forget AMP's solid backup. You can count on it with the kind of personal attention your product line deserves.

So why not get AMP quality when you need DIP and microprocessor sockets. Just call Customer Service at (717) 564-0100. Or write AMP Incorporated, Harrisburg, PA 17105.

**AMP**  
INCORPORATED  
CIRCLE NUMBER 67

AMP is a trademark of AMP Incorporated.



## AMP EUROPE

**Austria** — AMP Austria. Branch of AMP Deutschland GmbH. Markgraf-Ruediger Str. 6-8, 1150 Vienna. Phone: 924191/92

**Belgium** — AMP Belgium. Branch of AMP-Holland B.V., Rue de Brabant 62-66, Brussels. Phone: 322.17.55.17

**Finland** — AMP Finland OY  
Postilokero 3, 00401 Helsinki 40  
Phone: 90/584122

**France** — AMP de France. 29 Chaussée Jules-César. Boite Postale No. 39. 95301 Pontoise France. Phone: 030 82 20, 030 92 30

**Germany** — AMP Deutschland GmbH. Ampéressstrasse 7-11, 607 Langen, B. FFM., West Germany. Phone: (06103) 7091

**Great Britain** — AMP of Great Britain Limited, Terminal House, Stanmore, Middlesex, England. Phone: 01-954-2356

**Holland** — AMP Holland B.V., Papierstraat 2-4 5223 AW 's-Hertogenbosch, Holland. Phone: (073) 125221

**Italy** — AMP Italia S.p.A., Via Fratelli Cervi 15, 10093 Collegno (Torino), Italy. Phone: 785-656

**Spain** — AMP Española, S.A., Apartado 5294. Pedro IV, 491, 495, Barcelona 5, Spain. Phone: 307-75-50

**Sweden** — AMP Scandinavia AB, Datavägen 5, 17500 Jakobsberg, Sweden, Mailing Address: Fack S-175 20 JARFALLA 1, Sweden. Phone: 0758/10400

**Switzerland** — AMP AG, Haldenstrasse 11, 6006 Luzern, Switzerland. Phone: (414) 235421, 235422, 235423

## AMP NORTH AMERICA

**Canada** — AMP OF CANADA LTD., 20 Esna Park Drive, Markham, Ontario, Ph: 416-499-1251

**Mexico** — AMP de Mexico, S.A., Apartado Postal 179, Naucalpan de Juarez, Edo. de Mexico, Phone: Mexico City 576-41-55

**Puerto Rico** — AMP OF CANADA LTD., 677 Calle de Diego, Rio Piedras, Puerto Rico 00924. Phone: (809) 766-2346

**United States** — AMP Incorporated, Harrisburg, Pa. 17105, Phone: 717-564-0100

## AMP SOUTH AMERICA

**Argentina** — AMP S.A. Argentina 4 de Febrero, 76 Villa Zagla — SAN MARTIN, Buenos Aires, Argentina, Phone: 752-4612

**Brazil** — AMP do Brasil Ltda., AV Comendador Martinelli 185, Lapa, Sao Paulo, Phone: 262-4353

## AMP PACIFIC

**Australia** — Australian AMP Pty. Limited, 155 Briens Road, Northmead, N.S.W. 2152 Australia, Mailing Address: P.O. Box 194, Baulkham Hills, N.S.W. 2153 Aus. Ph: 630-7377

**Japan** — AMP (Japan), Ltd., No. 15-14, 7-Chome, Roppongi Minato-Ku, Tokyo, Japan, Ph: 404-7171


Products and services for many specialized industries are provided by the AMPLIVERSAL Division. In the United States, this division is known as AMP Special Industries.

For Amp products and services in other countries, write: AMP International Division, Harrisburg, PA 17105, USA.



## INSTRUMENTATION

### In-circuit tester prescreens PC boards



*Teradyne, 183 Essex St., Boston, MA 02111. Bob Sigsby (617) 482-2700. From \$54,500; 12 to 16 wks.*

The L529 in-circuit tester prescreens PC boards for workmanship and component faults prior to a functional board test. The microprocessor-controlled tester includes an operator's test station, board handler and programming console. The test station includes a control panel that directs all system functions, two tape drives and a strip printer for generating diagnostic error messages. The programmer's console contains an interactive keyboard and CRT. Three tests are used for high-fault coverage on boards having up to 700 nodes: node-to-node continuity, guarded-component measurements and impedance.

CIRCLE NO. 342

### Test system checks ICs with up to 120 pins

*Fairchild Systems Technology, 1725 Technology Dr., San Jose, CA 95110. Ken Daub (408) 998-0123. \$500,000; 12 wks.*

An automatic semiconductor test system, Sentry VIII, is capable of handling devices with up to 120 I/O pins. The system will handle microprocessors, peripheral chips, bit slices, phase lock loops, RAMs, ROMs, shift registers, UARTs and digital hybrids in NMOS, CMOS, SOS, ECL, DTL, TTL and I<sup>2</sup>L. Included are 16 timing generators, expanded waveform generation and 160-ps timing resolutions. Multi-task software for simultaneous compiling, editing and testing are provided. Test programming can be created with a high-level language called FACTOR that permits the user to produce the most complex testing routines. Functional dc and ac tests can also be carried out with available stock programs.

CIRCLE NO. 343


### Modular test set analyzes data systems

*International Data Sciences, 100 Nashua St., Providence, RI 02904. (401) 274-5100. \$4,050; 8 wks.*

The Model 20910 is a modular, general-purpose test set that analyzes data-communication systems operating asynchronously up to 2400 bits/s and synchronously up to 20 kbits/s. The unit contains six modules in a rack-mounted chassis that include a transmitter, receiver, error counter, and interface modules. The device provides a three-digit display of the bit-error rate.

CIRCLE NO. 344

### F/v converter spans 10 Hz to 50 kHz




*Gould Instruments, 3631 Perkins Ave., Cleveland, OH 44114. R.F. Kerzman (216) 361-3315. \$595; 12 wks.*

A wideband frequency-to-voltage converter, Model 13-4618-20, permits direct measurement and recording of the frequency of signals from 10 Hz to 50 kHz. It detects the zero crossing of any waveform and outputs an analog dc voltage which is directly proportional to frequency. Unipolar signals which do not go through zero, such as TTL level pulses, are handled by switching-in an offset voltage of  $\pm 1$  V from the front panel. The unit responds to input signals of 10 mV to 500 V rms. Exact frequency is determined by selecting one of 36 calibrated frequency ranges, with full-scale outputs of 5.0 V dc.

CIRCLE NO. 345

## MICRO/MINI COMPUTING

### UV lamp erases EPROM chips




Ultra-Violet Products, 5100 Walnut Grove Ave., San Gabriel, CA 91778. (213) 285-3123. \$59.50.

The UVS-11E short wave lamp erases up to four EPROM chips at one time in 14 minutes. A safety interlock system protects the user against accidental UV exposure. The system comes with a holding tray for maintaining a constant exposure distance of 1 in.

CIRCLE NO. 346

### Central-processor module supplied without memory




Digital Equipment, 1 Iron Way, Marlborough, MA 01752. Don Mallinson (617) 481-7400. \$459.

A central-processor module, KD11-HA, does not contain memories and is intended for uses that require custom RAMs or ROMs. The device is part of the LSI-11/2 family of microcomputer modules. Also included in the family are memory modules with the same half-width size (5 x 8.5 in.) as the central processor. The memories are available in 4, 8, 16 and 32-kword configurations with optional byte parity.

CIRCLE NO. 347

### Memory expansion boards are for TI's CPU



Texas Instruments, P.O. Box 1443, M/S 653 (Attn: TM990), Houston, TX 77001. Alan Lofthus (713) 776-6511. \$595 (990/201), \$585 (990/206) in 1-9; stock.

Two memory expansion modules are for use with TI's TMS 9900-based CPU, the TM-990/100M. The TM990/201 board has 4 k x 16 words of EPROM and 2 k x 16 words of static RAM. The unit is expandable to 16 k x 16 words of RAM by plugging in TMS 2716 EPROMs or TMS 4045 static RAMs. The TM-990/206 board has 4 k x 16 words of static RAM, expandable to 8 k by plugging in 4045 static RAMs.

CIRCLE NO. 348

# A Vero Case History:

**Problem:** To effectively package electronic systems or sub-systems for commercial applications.

**Factors to Consider:** Strength, Flexibility, Styling, Environmental Requirements, Availability, and Cost Effectiveness.

**Obvious Solution:**

**VERO INSTRUMENT CASES**


Vero Cases are sturdily constructed of heavy gauge steel and aluminum. They are available from stock in many sizes and colors and are competitively priced.

If you have a packaging problem to solve, call or write today for full engineering specifications and prices.



**Vero Electronics, Inc.**

171 Bridge Road  
Hauppauge, N.Y. 11787  
(516) 234-0400 TWX: 510-227-8890




CIRCLE NUMBER 68

# MICRO

DIP SWITCH

# MINI

DIP SWITCH




**MICRO-DIP**...10 and 16 position miniature binary coded DIP switch designed to be mounted directly to PC Boards. Ideal for address encoding, pre-setting, PCB programming...every area of digital electronics.

Packaged in a color coded, glass-filled nylon housing with terminals on .100 x .300 centers. It occupies only one half of a standard 14-pin DIP socket.

Screwdriver slot is rotated in either direction to desired setting. Gold contacts protected by dust-seal design.

Positive detenting 10 position BCD, 16 position binary with separate common to not true bits, repeating 1 and 2 pole codes. Guaranteed life of 10,000 detent operations. Operating temperature range of  $-10^{\circ}\text{C}$  to  $+85^{\circ}\text{C}$ , contact resistance of 25 milliohms max. initial.

One year warranty.



**MINI-DIP**...new from EECO. Form A and C contact arrangements ideal for positive on/off switching and programming.

Easily actuated, positive wiping, gold contacts are packaged in a dust free glass-filled nylon housing.

Interference-fit of terminal pins and one piece housing prevent contamination. Larger cross section pins allow positive insertion into sockets and P.C. Boards.

New locking design in which .035 diameter locking rod is inserted through rockers, insures against accidental actuations.

Guaranteed life of 50,000 cycles. Operating temperature range  $-10^{\circ}\text{C}$  to  $+85^{\circ}\text{C}$ , contact resistance 25 milliohms max. initial.

Standard .100 x .300 centers allows retrofitting of other major brands of DIP switches. Available in 2-10 station Form A, 1-5 station Form C contacts.

One year warranty.

## EECO

1441 East Chestnut Avenue, Santa Ana, California 92701—Phone 714-835-6000. Distributed in U.S. by Marshall Industries, Hall-Mark, and Schweber. In Canada by R.A.E. and Penryn. Agents throughout the world.

CIRCLE NUMBER 69

**Card allows plotter use with HP System 45**

*Hewlett-Packard, 1507 Page Mill Rd., Palo Alto, CA 94304. (415) 493-1501. \$600; 12 wks.*

The HP 98040A card adds the capability of controlling incremental drum and flatbed plotters to the HP 9800 System 45 desktop computer system. The plotter interface can be used with plotters that require user-coded data inputs. It enables the System 45 to use computer ROM commands to control nearly all plotting functions. Provided with the card are pulsed  $\pm X$  and  $\pm Y$  data lines that accept data rates from about 100/s to 5000/s in discrete steps of 100/s. Pen control is possible through pulsed "pen up" and "pen down" lines. The "pen down" delay is 30 ms or 60 ms, "pen up" is 15 ms or 30 ms.


CIRCLE NO. 349

**Board set uses 6800 microprocessor**

*Adaptive Science, 1201 Park Ave., Emeryville, CA 94608. Dick Strang (415) 652-1805. From \$115/board; 6 wks.*

A set of boards using the 6800 microprocessor is available in the Type 1000 series on standard 4.5 x 6.5-in. cards. Each card has a 44-pin edge connector, and a fully buffered bus interface. Included in the set is a combination MPU/RAM board with 4 kbytes of static memory. An 8-kbyte static memory board allows system expansion if the use requires additional memory, while an 8-k ROM/PROM board provides permanent storage. A serial/TBG board offers serial I/O with selectable baud rates from 75 baud to 19.2 kbaud and a programmable counter with a crystal-controlled oscillator for time base generation. A 32-bit parallel I/O board provides active or open collector outputs and buffered inputs. Analog input is provided by a 16-channel multiplexed 12-bit ADC board with a 20- $\mu s$  conversion time. A dual 10-bit DAC board provides analog output. A two-board video set features video generation for a 64-char by 16-line display. The 7 x 9 character set includes upper and lower case with descenders.

CIRCLE NO. 350



**They're worth their weight in plastic.**


Introducing Johnson's new Micro J-80 capacitors with plastic bases.

Compared to monolithic rotor capacitors with ceramic bases, the Micro J-80 costs 30-35% less. Yet, in many aspects, its performance is equal or superior to the ceramic versions. Its one-piece stator and stator terminal provide uninterrupted current flow for greater reliability. Temperature characteristics exceed comparable units with ceramic bases by 1-2%. And Q is 300 or higher.

The Micro J-80 is available in either horizontal or vertical printed circuit mounting

styles. For more information, mail us the coupon.

Johnson's revolutionary Micro J-80. It costs like plastic, but it performs like ceramics.



**JOHNSON**

E. F. JOHNSON COMPANY, WASECA, MINN. 56093

E. F. Johnson Company, Waseca, Minn. 56093

- Please send technical information.
- Please have your salesman call on me.
- Please send samples. You can call me at \_\_\_\_\_.

Name \_\_\_\_\_

Title \_\_\_\_\_

Firm \_\_\_\_\_


Address \_\_\_\_\_

City \_\_\_\_\_ State \_\_\_\_\_ Zip \_\_\_\_\_

CIRCLE NUMBER 70



## Personal computer hooks into TV set



Umtech, 150 S. Wolfe Rd., Sunnyvale, CA 94086. Rich Melman (408) 737-2680. \$500 (retail).

The Videobrain computer comes with everything necessary to hook it up to a TV set and start running programs. The brain is an 8-bit micro-computer containing 1 kbyte of RAM and 4 kbytes of ROM. The pre-programmed cartridges can contain up to 13 kbytes of ROM or RAM. The unit has jacks for tape cassettes, printer and telephone. Built-in are the basic text and timekeeping programs. The text program allows the typing and editing of a message of 7 lines with 16 char/line.

CIRCLE NO. 356

## Systems aid in $\mu$ C product development


Futuredata Computer, 11205 S. La Cienega Blvd., Los Angeles, CA 90045. R. Scharf (213) 641-7700. \$4325 to \$7675; 2 to 4 wks.

Microcomputer product development systems, the Microsystem 12, 15 (tape-based), 20 and 36 (disc-based) are all built around Z-80  $\mu$ Ps. They include CPU with up to 56-k memory, high-speed 960-character CRT, ASCII keyboard, dual floppy disc or cassette-tape unit, operating system software and documentation. Optional accessories and software include in-circuit emulator, line printers, extended Basic, Basic compiler, RDOS (disc operating system with relocatable macro-assembler and linkage editor), and word processor. Plug-in modules permit the systems to be converted to 8080 or 6800 processors. Systems include two RS-232 serial ports, 8-bit parallel TTL I/O port, real-time clock, bootstrap in PROM, memory write-protect under software control, eight-level vectored interrupts, DMA capability and disc and tape operating systems with monitor, debugger, editor, assembler and copy utility.

CIRCLE NO. 357

# Protect your expensive switching systems. Prevent down time due to dirty contacts.


## Use MS-230 Contact Re-Nu<sup>®</sup>



### PURITY COMES FIRST

Our aerosol cleaners have the lowest residual contamination in the industry — some approaching 5-7 parts per million. The general industry range is 50-130 ppm. For only a few dollars per month you can maintain or restore continuity almost instantly to relay and switch contacts. Won't harm insulation. Leaves no residue. Non-conductive, Non-flammable. Contains no lubricant. May be shipped air transport.

For further information, call or write Miller-Stephenson, Chemical Co., Danbury, Conn. 06810 (203) 743-4447



**miller-stephenson chemical co., inc.**

Danbury, Connecticut 06810 (203) 743-4447

miller-stephenson chemical co., inc.  
Danbury, Connecticut 06810 (203) 743-4447

ED-1W



- \_\_\_\_\_ Ask our Technical Director for application information  
 \_\_\_\_\_ Send \$2 for Trial Unit of MS-230 Contact Re-Nu<sup>®</sup>  
 \_\_\_\_\_ Send literature and prices

My intended use is \_\_\_\_\_

Name \_\_\_\_\_ Title/Dept. \_\_\_\_\_

Company \_\_\_\_\_

Address \_\_\_\_\_

City \_\_\_\_\_ State \_\_\_\_\_ Zip \_\_\_\_\_

®Registered trademark.

For Industrial Use Only. Trial Unit must be sent to company address.

LOS ANGELES • CHICAGO • DANBURY, CONN. • TORONTO

CIRCLE NUMBER 71

## MICRO/MINI COMPUTING

### EPROM programmer copies masters

SMR Electronics, 3 Haven Rd., Medfield, MA 02052. S. Rudnick (617) 359-7697. \$825.

Model 7608, a self-contained programmer for type 2704 and 2708 EPROMs, is used to copy master EPROMs and to read preprogrammed memories. Program entry via panel keyboard and true hexadecimal display of addresses and data are provided. An accessory emulator unit permits loading from an external keyboard or computer. Type 2716, 2k x 8 EPROMs may be programmed in two passes using an optional adapter board. Editing capabilities allow insertion and deletion of data with resequeing prior to programming.

CIRCLE NO. 358

### 16-k RAM goes into 8080 and Z80 computers

North Star Computers, 2547 9th St., Berkeley, CA 94710. (415) 549-0858. \$399 (kit), \$459 (assembled).

A 16-k RAM board, for S-100 bus computers, can be used in both 8080 and Z80 systems operating at full speed up to 4 MHz. The board uses 200-ns dynamic RAM chips and the on-board memory refresh is invisible to the processor. Bank-switching capability is provided and the addressing of the board is switch-selectable in two 8-k sections.

CIRCLE NO. 359


### Mainframe forms basis for thrifty $\mu$ C

Integrand Research, 8474 Avenue 296, Visalia, CA 93277. Bob Frank (209) 733-9288. \$200; stock.

The Model 800 mainframe is a completely assembled and tested cabinet, motherboard, power-supply combination that allows complete freedom in building an economical computer by supplying only the chassis unit. The user can choose complementary CPU, memory, and I/O cards to complete a system. The chassis contains a 15-position S-100 motherboard, 15-slot card cage, fan, line cord, EMI filter, fuse, power and reset switches and power supply.

CIRCLE NO. 360

### Add-on memory upgrades Z80 development board




Mostek, 1215 W. Crosby Rd., Carrollton, TX 75006. (214) 241-0444. \$945; stock.

The RAM-80B add-on memory board, designated MK78108, upgrades the memory capability of the Z80-based software development board, SDB-80. Using the MK 4116 RAM, the add-on board has 16, 32, 48, or 65 kbytes of RAM. Strapping options position the decoded memory space to start on any 16-k address boundary. Also provided are ports from the two on-board MK 3881 Z80 PIO circuits. Each I/O port is fully TTL buffered and has two handshake lines per port. Logic for a "page-mode operation" permits up to 1 Mbyte to be used in a single SDB-80 system.

CIRCLE NO. 361

### Floppy-disc controller works with 8010 CPU



GSI Systems, 223 Crescent St., Waltham, MA 02154. Ed Letscher (617) 899-6688. \$495; stock.

The Model 10043 floppy-disc controller is a microprocessor-based disc control card that accepts commands from an 8010 CPU card via the 8010 backplane. The controller has an IBM-compatible format with 3328 bytes of data per track; a non-IBM-compatible high-capacity option formats each track with two sectors containing a total of 4096 bytes. When equipped for stand-alone operation, the 10043 responds to commands and transfer data via a high-speed serial RS232C port or modem. The unit can control up to four disc drives.

CIRCLE NO. 362

### $\mu$ P has double-density dual-drive floppy discs




Digital Systems, 6017 Margarido Dr., Oakland, CA 94618. John Torode (415) 428-0950. \$4995 to \$8135.

A microcomputer system with dual-drive, double-density floppy discs, Micro-2, is housed in a single cabinet with two Shugart floppy-disc drives. The single computer board has a Z80 CPU, 32 or 64-k RAM, four RS232 serial interfaces and a real-time clock. The disc controller uses either IBM 3740 format or a double-density format of 571 kbytes per diskette. With optional double-sided drives, the system can store up to 2.3 Mbytes.

CIRCLE NO. 363

### Single-board memory mates with 6800 micros



Chrislin Industries, 31312 Via Colinas, Westlake Village, CA 91361. (213) 991-2254. See text; 2 to 3 wks.

The CI6800 16-k x 8 semiconductor memory system operates with the Motorola EXORcisor and the MEC-6800 evaluation module. The memory allows expansion to 32, 48, or 64 k by interchanging the 4027, 4k x 1 dynamic-memory chip with its 16-k equivalent. The board plugs directly into existing EXORcisor connectors. Maximum processor throughput is obtained with the use of hidden refresh-control logic on board. Data access time is 300 ns, and cycle time is 750 ns. On-board memory select is available in 4-k increments up to 64 kwords. A write-disable switch makes the RAM a ROM to the outside world. OEM pricing is \$390 for 16 k x 8 and \$1230 for 64 k x 8.

CIRCLE NO. 364

**R**ight now, our Thorkom circulars are going into almost everything, everywhere.

That includes computers and medical equipment, where reliability and miniaturization are critical — all the way to automotive and marine use, where Thorkom's corrosion resistance, toughness and low cost beat out everything else available.

**There's nothing else quite like them.**

Our little high-contact-density Thorkoms are tough, lightweight and shockproof. You get a sure, positive lock, yet have a quick, easy disconnect, too. Plus: contacts are crimp removable with Mil-T-22520 tool. And there's positive polarization; they can't be mated incorrectly.

**You can get them right off the shelf.**

Our distributors have a good, deep supply. And if they can't put their hands on the Thorkom you need right now, chances are it's just a phone call away.

**Want the cable added?**

We can do it — and probably do it much faster and cheaper than you can yourself. What kind of cable? Any kind you need.



**For details...**

Use the coupon and we'll get the literature back to you. Or, if you don't want to wait, call our nearest rep or distributor. If you need a sample, they may get one to you today. Or call us: (213) 341-4330.



24 pin receptacle, shown with dip solder contacts.



12 pin square flange receptacle.



7 pin plug and receptacle, shown life size.



# Imagine where these tough little connectors can go.

**Send me** your latest Thorkom catalog. I'm thinking of using Thorkom connectors in:

- Computer equipment
- Medical instrumentation
- Automotive
- Communications
- Marine
- Aviation
- Process control
- Other (Please indicate) \_\_\_\_\_

NAME: \_\_\_\_\_ TITLE: \_\_\_\_\_

COMPANY: \_\_\_\_\_

ADDRESS: \_\_\_\_\_


CITY: \_\_\_\_\_ STATE: \_\_\_\_\_ ZIP: \_\_\_\_\_



Viking Industries, Inc., 21001 Nordhoff Street, Chatsworth, CA, U.S.A.

# Keystone

## VERSATILE THERMISTOR PROBES



Get quick response for sensing temperatures of gases, liquids and surfaces with 23 thermistor probe styles and configurations. Probes with stainless steel tips can be ordered in lengths from 1" to 4", giving you an extra dimension to customize certain standard probes. Other features include:

**Sensitivity** . . . highly sensitive to minute temperature changes . . . fast response.


**Temperature range** . . . can withstand temperatures from  $-50^{\circ}\text{C}$  to  $260^{\circ}\text{C}$ .

**Resistance values** . . . from 1K to 1 meg at  $25^{\circ}\text{C}$  . . . also miniature discs and rods of 100 ohms to 1 meg at  $25^{\circ}\text{C}$  are available.

**Tolerance on resistance** . . .  $\pm 20\%$  at  $25^{\circ}\text{C}$  is standard;  $\pm 10\%$  and  $\pm 5\%$  or tighter tolerances if desired.

**Low-cost series** . . . three inexpensive probes to answer many requirements.

**Catalog TP-739**  
... gives details on 23 probe styles and ordering information. Circle reader service card.



**Keystone**  
CARBON COMPANY  
Thermistor Division  
St. Marys, PA 15857  
814/781-1591 • Telex 91-4517  
**CIRCLE NUMBER 73**

## MICRO/MINI COMPUTING

### F8 micro is on a single board

*Comptronics, 19824 Ventura Blvd., Woodland Hills, CA 91364. (213) 340-8843. \$249 (kit), \$299 (assembled).*

The Model 1080 F8 development board is a microcomputer on an  $8 \times 13$ -in., PC board. The unit has an F8 CPU, a Fairbug PSU, a 3853 SMI,  $2 \text{ k} \times 8$  RAM, 2-MHz crystal clock and interfacing circuits. Also included are a buffered address and data bus to an S-100 memory expansion connector and sockets for 4 kbytes of 2708 memory. The unit provides 1 k of 2708 user custom monitor and 32 bits of I/O arranged in four 8-bit ports. The microcomputer has RS232 or 20-mA current-loop support circuitry and two sockets for I/O expansion.

**CIRCLE NO. 365**

### Software links PDP-8s for data exchange

*Digital Equipment, Maynard, MA 01754. John Bond (617) 897-5111. \$900; stock.*

DECnet-8 permits networking between PDP-8 systems. The package operates under the RTS/8 real-time, multitask operating system and supports as many as eight physical lines and 32 logical links. Asynchronous, synchronous, parallel, full and half-duplex lines are supported. On appropriate hardware configurations the RTS/8 implementation permits OS/8 operations as background.

**CIRCLE NO. 366**

### Flexible-disc drive has dual heads

*Memorex, San Tomas at Central Expressway, Santa Clara, CA 95052. (408) 987-2203. \$585 (OEM).*

The Model-552 disc drive has two ceramic read/write heads that allow recording or reading of data on both sides of a dual-sided flexible disc. The drive records 492 kbytes in IBM 4964 format or up to 1600 kbytes of unformatted data. Access time is 3 ms/track. The data transfer rate is 250 kbytes/s in single-density mode. With an appropriate controller, the 552 can be operated in the double-density mode with a data transfer rate of 500 kbytes/s.

**CIRCLE NO. 367**

### Add-in memory gives 32 kwords for Novas

*Monolithic Systems, 14 Inverness Dr. E., Englewood, CO 80110. (303) 770-7400. 4 wks.*

An add-in expansion memory, Model 3401, for Nova 800 and 1200 series, is expandable in 4-k steps to 32 kwords and is totally Nova hardware and software compatible. The memory is designed around the Burroughs-pinout,  $4 \text{ k} \times 1$ , NMOS static RAM, and is configured in 16-bit words. The non-volatile memory has an access time of 240 ns, with 800-ns cycle time. Memory addressing is programmable in contiguous 4-k steps.

**CIRCLE NO. 368**

### Convert 300-baud printer to 1200-baud terminal

*Datasouth Computer, 122 W. Woodlawn Rd., Charlotte, NC 28210. Jim Busby (704) 523-8500. \$635 (25-99 qty).*

A kit, Model DS120, converts a DEC LA36 300-baud teleprinter to a 1200-baud interactive terminal by replacing the standard LA36 circuit card. The kit also provides bidirectional printing at 165 char/s, and automatic carriage movement to tab over white space. An EIA interface, horizontal and vertical tabs, X-on, X-off protocol, double-wide characters, parity selection, error detection and self-test mode are also included.

**CIRCLE NO. 369**

### Audio cassette recorder can sub for paper tape


*Pacific Cyber/Metrix, 3120 Crow Canyon Rd., San Ramon, CA 94583. Ted Netoff (415) 837-5400. \$117 (kit), \$187 (assembled).*

A mag-tape interface module, 12080, allows an ordinary audio cassette recorder to be substituted for a paper-tape reader and punch in the PCM-12 microcomputer. The module uses byte-standard, self-clocking FM circuitry and allows operation at a rate three times faster than that of the reader/punch on a TTY terminal. In a system, an audio cassette can store 30,000 characters on a single side. A reader/punch module, 12070, is also available to interface the Addmaster Model 601 paper-tape reader and the Epson Model 6110 paper-tape punch to the PCM-12.

**CIRCLE NO. 370**

## MICROWAVES & LASERS

### Image-rejection mixers cover 2 to 12.4 GHz




Varian, Salem Rd., Beverly, MA 01915.  
(617) 922-6000.

The 9753 low-noise image-rejection mixers cover 2.0 to 12.4 GHz in bands up to an octave wide. Each model consists of two mixers; a 90° hybrid and a power divider combined in a single microwave IC. Compact packaging is achieved by combining the i-f quadrature network and mixers in a single housing. Minimum image reflection is 18 dB. Local oscillator level is +6 to +9 dBm. I-f frequency is dc to 300 MHz, and i-f bandwidth is any 20% band.

CIRCLE NO. 371

### Harmonic mixer accepts 0.1 to 26-GHz inputs




Millimeter, P.O. Box 5097, Santa Monica, CA 90405. (213) 823-2768.

Series 1050 harmonic mixers cover an input rf range of 0.1 to 26 GHz. Responding to even or odd orders through the 50th harmonic of the LO, the mixers provide new capabilities for systems with limited LO bandwidths or power. I-f output bandwidths are available to 1 GHz. SMA connectors are standard.

CIRCLE NO. 372

### Coaxial attenuator is compact, rugged




Telonic/Berkeley, 2825 Laguna Can-

yon Rd., Laguna Beach, CA 92652. Dick Aaron (800) 854-2436. \$30.

The tubular attenuator, Model 8207, weighs 0.5 oz and measures 1.24 long by 0.38-in. dia. and meets MIL-A3933B/III and MIL-A3933B/15. The unit has a  $\pm 0.3$ -dB flatness across its full attenuation range and a power rating of 3 W at 85 C. Over the frequency range (dc to 4.5 GHz), the impedance is 50  $\Omega$ . Standard attenuation values are 3, 6, 10, 20, 30, 40, 50 or 60.

CIRCLE NO. 373


## Need a second source on optically coupled isolators?



**HIGH SPEED ISOLATORS**  
Spectronics 6N135-6N139 are pin-for-pin replacements for respective HP6N135-139 devices.

3000 VDC Isolation!

Part No.	Input Current	Data Rate	CTR
6N135 (SCH-4350)	16 ma	1 Mbit/sec	7% (min)
6N136 (SCH-4351)	16 ma	1 Mbit/sec	19% (min)
6N138 (SCH-4370)	1.6 ma	300 Kbit/sec	300% (min)
6N139 (SCH-4371)	0.5 ma	300 Kbit/sec	400% (min)



**PHOTO SCR ISOLATORS**  
Spectronics SCS11C1-C3 are pin-for-pin replacements for respective GE H11C1-C3 devices.

5000 VDC Isolation!

PART NUMBER	TURN ON CURRENT (MAX) (I <sub>F</sub> )	FORWARD BLOCKING VOLTAGE (V <sub>DM</sub> @ R <sub>AK</sub> = 10 Kohm)
SCS11C1	11mA	200V (Min)
SCS11C3	14mA	200V (Min)


For more details and delivery information, contact Commercial Component Marketing, 830 E. Arapaho Road, Richardson, Texas 75081, (214) 234-4271.



**Spectronics**  
INCORPORATED

CIRCLE NUMBER 74

## Field-repairable i-f strips cut purchase, inventory costs



Plessey Semiconductors, 1641 Kaiser Ave., Irvine, CA 92714. Dennis Chant (714) 540-9979. \$575-\$650 (unit qty), \$350-\$475 (1000-up), depending on specific requirements; 8 wks.

A series of hybrid-circuit amplifiers for 120, 160 and 240-MHz i-f frequencies offers low cost, better protection against the environment and quicker repair than amplifiers using packaging that's supposed to be more sophisticated.

Instead of using uncased, monolithic, IC-amplifier chips, transistors and discrete and hybrid passive components on a few ceramic substrates in an aluminum shell, the Plessey PSLT series houses amplifier chips in eight 8-pin TO-5 cans. The chips are mounted on 50 x 60-mil ceramic substrates with two chip capacitors and a thin-film resistor.

The cans are mounted with discrete components on a single PC board that's mounted in a 4-1/2 x 1-3/4 x 1/2 inch aluminum shell. That's about the same size that's used for competitive amplifiers from companies like Varian and RHG.

The Plessey approach offers several advantages. The semiconductors are protected from the environment in hermetic cans. In case of failure, the canned amplifiers can be replaced individually. So, instead of stocking com-

plete amplifiers that cost \$650 to \$850 in unit quantities (for competitive units), a user can stock \$24 cataloged TO-5 amplifiers that are easy to replace in the field.

The amplifiers are intended mainly for radar receivers in electronic-warfare and electronic-countermeasures equipment, but they're suitable for a wide range of communications receivers. Bandwidths are available from about 9 to 25 percent of the center frequency. Gain is available to 100 dB and dynamic range to 70 dB.

Plessey  
RHG  
Varian

CIRCLE NO. 302  
CIRCLE NO. 303  
CIRCLE NO. 304


## 14-bit hybrid d/a has differential input

ILC Data Device, Airport International Plaza, Bohemia, NY 11716. (516) 567-5600. \$245; stock to 4 wks.

A 14-bit hybrid multiplying d/a converter, DAC-U, has differential input, a remote ground and sense capability. The device has a linearity of 0.0125% with a settling time of less than 20  $\mu$ s and maintains full resolution for two as well as four-quadrant operation.

CIRCLE NO. 374

## Digital process monitor takes nonlinear inputs




Dynamic Sciences, 7660 Gloria Ave., Van Nuys, CA 91406. Sylvia Sass (213) 893-6341. \$568; 4 wks.

The digital process monitors in the 7000 series can be programmed to accept inputs from any linear or nonlinear transducer. The meter handles transducers with multiple-valued transfer functions. The monitor is a 3½-digit instrument with 0.43-in. LED displays. It accepts current inputs of 0 to 1, 4 to 20 and 10 to 50 mA and voltage inputs of 0 to 1, 1 to 5 and 0 to 10 V. Common-mode rejection is 100 dB at 60 Hz, increasing at 20 dB/decade. Sampling rate is factory set at 3 to 5 s and is field adjustable from 40 readings/s to 1 reading/10 s. The accuracy is 0.1% FS  $\pm$  1 LSB.

CIRCLE NO. 375

## 8-bit a/d converts at rate of 20 MHz



Datel Systems, 1020 Turnpike St., Canton, MA 02021. Eugene Murphy (617) 828-8000. \$1995.


ADC-TV is an 8-bit (48 dB) a/d converter with a conversion rate of 20 MHz. Digital and analog connections are made with a 37-pin subminiature "D" connector and a 3-mm terminated coax connector. Either ECL or TTL can be chosen as well as various input-termination impedances. Conversion pulses adjust throughput for any rate up to 20 MHz and the characteristics can be optimized at popular conversion rates of 14.3 or 17.72 MHz. No time delays are required.

CIRCLE NO. 376

# Only one thing beats our Super-Mini Impact Printer...

Why stop with the data/text versatility of our 120 cps, 20-column multiple-copy mini. It works even harder as a complete system. Teamed with its own microprocessor interface and power supply, there's virtually nothing our DMPT-3 can't handle — from telemetry to process control, from unattended system recording to providing hard-copy data terminal output, even in POS and inventory control. Mated with any ASCII system, it takes either parallel or serial input at speeds up to 16 KHz or 1200 bps.

Alone or as a system, of course, the industry's smallest alphanumeric impact printer lets you economize with ordinary adding machine roll paper.



With both full alphanumeric and enhanced characters, our little workhorse calls attention to emergency conditions. And with its 75,000-line life, ink cartridge that's replaceable in seconds, you know you're set for a good, long time.

For more details, call or write today.  
**System \$452** (Printer, \$192; Controller, \$150; Power Supply, \$110);  
**\$330 complete in 100's.**


## The Whole System



**PRACTICAL AUTOMATION, INC.**  
 Trap Falls Road,  
 Shelton, Conn. 06484  
 Tel.: (203) 929-5381

CIRCLE NUMBER 75

## FIX-A-DIP & FORM-A-DIP which do you need to straighten and reform IC leads . . . or both?




**FIX-A-DIP** —used to reform any IC to a reusable state by means of a dual set of precision racks. Insert IC between teeth and strike handle to complete reform.

Works with all IC sizes of 0.3" to 0.6" and 6 to 40 pins.

**FORM-A-DIP** — used to replay any IC to its original 8 to 12° splay after burn in or testing.

Reforms to prevent falling out of insertion tools, automatic equipment or PC boards.



## Micro Electronic Systems Inc.

8 Kevin Drive, Danbury, CT 06810 Tel. (203) 746-2525, Telex 969659  
 Distributor stocked throughout the U.S.A.

See Booth #G-201 at NEPCON WEST.  
 CIRCLE NUMBER 76

**FREE!**

## EDMUND SCIENTIFIC

ELECTRONICS  
 OPTICS  
 SOLAR ENERGY  
 MAGNETS  
 LASERS



O.E.M.  
 COMPONENTS  
 LABWARE  
 MIRRORS  
 SURPLUS

## 164 PAGE CATALOG

- Over 4,000 unusual bargains for science and industry
- In-stock supplies for engineers, experimenters, research labs, hobbyists, etc.
- Order direct and save — buy with complete confidence ... every item carries the famous Edmund 30-day money-back guarantee.
- Simply mail this coupon for the newest Edmund catalog.

### RUSH LATEST FREE EDMUND CATALOG

**EDMUND SCIENTIFIC CO.**  
 Dept. DA02, Edscorp Building, Barrington, N.J. 08007

Name \_\_\_\_\_

Address \_\_\_\_\_

City \_\_\_\_\_ State \_\_\_\_\_ Zip \_\_\_\_\_

CIRCLE NUMBER 77

# MICRO PROCESSOR POWER SOURCES

REGULATED



For...

- MPUS
- RAMS
- E ROMS
- ROMS

**ONE WATT OUTPUT • COMPACT  
DIP PACKAGE • LOW NOISE  
ISOLATED • LOW PRICE**

Ultra Compact DC-DC V-PAC Power Sources\* use 5v or 12v input, provide +12, -5 regulated low noise outputs. Also available with  $\pm 12v$ , or  $\pm 15v$  output for op amps.

**SPECIFICATIONS:**

Output voltage tolerance  $\pm 5\%$   
 Output ripple \_\_\_\_\_ 30 mv, P-P max.  
 Line regulation \_\_\_\_\_ 0.3%  
 Load regulation \_\_\_\_\_ 0.3%  
 Operating temp \_\_\_\_\_ 0° to 70°C  
 Isolation \_\_\_\_\_ 10M $\Omega$  @50v  
 Price \_\_\_\_\_ \$20.20 (100pcs)

**NOW IN STOCK!**

713-666-3261	714-279-9641
914-668-9809	602-946-4437
213-673-4300	303-420-4646
714-638-4422	613-728-1821



**P.O. Box 37409/Houston, Texas 77036**  
**(713) 492-0550/TWX: 910-881-1739**  
 International: Reliability Nederland, B.V.  
 Summerhill, Nenagh, Co. Tipperary, Ireland  
 \*Trademark, Reliability, Inc.  
 Price subject to change without notice

CIRCLE NUMBER 78


## MODULES & SUBASSEMBLIES

### First 16-bit support boards mate with TI microcomputer

Analog Devices, P.O. Box 280, Norwood, MA 02062. (617) 329-4700. P&A: See text.

The first analog I/O PC boards aimed at Texas Instruments' 16-bit microcomputers—and only the second such 16-bit cards on the market—are functionally, electrically and mechanically compatible with the TI TM-990/100M  $\mu C$ . The Analog Devices RTI-1240 family consists of two output subsystems, two input subsystems and two input/output boards:

- RTI-1242—Four 12-bit analog-output channels with eight digital-output peripheral drivers.
- RTI-1243—Same as the 1242 but with eight analog output channels.
- RTI-1240-R—32 single-ended or 16 differential inputs with a resistor-programmed-gain amplifier.
- RTI-1240-S—Same as the "R" but with software-programmable gain.




■ RTI-1241-R—I/O card with inputs like 1240-R's plus two 12-bit output d/a converters.

■ RTI-1241-S—I/O card with 1240-S features plus two 12-bit d/a's.

Each card is memory-mapped, so the TI  $\mu C$  treats them as any other memory location. Prices range from \$395 and \$675 for the 1242 and 1243, respectively, to \$445 and up for the 1240 and 1241. Delivery is from stock.

CIRCLE NO. 301

### Active notch filter mounts into DIP socket




A.P. Circuit, 865 West End Ave., New York, NY 10025. Felix Ellern (212) 222-0876. \$35 (100 qty); 2 wks.

A miniaturized active notch filter, Model APN-3, measures 1.3 x 0.8 x 0.6 in. and mounts into a 24-pin DIP socket. The filter comes pretuned to eliminate a specified frequency such as 60 Hz and can be externally tuned to a different frequency with one pot. Any pretuned frequency from 1 Hz to 30 kHz can be provided. Temperature stability of the center notch frequency is 0.025%/°C.

CIRCLE NO. 377

### Multiplying d/a has 12-bit accuracy




Beckman Instruments, 2500 Harbor Blvd., Fullerton, CA 92634. Josephine Rickard (714) 871-4848. \$85 (100 qty); stock.

The 7521M CMOS 12-bit multiplying d/a converter is hermetically sealed in an 18-pin DIP and has 12-bit accuracy and resolution from -55 to 125 C. Compatible with TTL and CMOS logic, the addition of external amplifiers enables unipolar or bipolar operation. The converter consumes 20 mW from +5 to +15-V supplies. Material, construction and workmanship conform to MIL-STD-883 Method 2017 Level B.

CIRCLE NO. 378



## Keyboard uses $\mu$ C and Hall-effect keys



Micro Switch, 11 W. Spring St., Freeport, IL 61032. (815) 235-6600.

A full-function "intelligent" keyboard, Model 103SD24-1, combines a single-chip microcomputer with 103 Hall-effect key modules. The microcomputer integrates an 8-bit CPU, a ROM program, RAM, I/O lines and a time-event counter on a single chip. Additionally, a 40-pin EPROM is available that is pin-compatible with the standard ROM. Among the features are: 14 relegendable keytops for programming keys; four-mode, 8-bit USASCII code assignment; choice of serial or parallel data outputs; 8-deep FIFO character storage; N-key roll-over; timed/auto repeat for selected keys; secretary shift, and a signal for audio-feedback drive.

CIRCLE NO. 379


## Processor-panel display can be cut to length

Telesis Lab, 41½ S. Paint St., Chillicothe, OH 45601. Jim Eley (614) 773-1414. \$76; 1 to 6 wks.

The DMO-16 processor-panel display may be cut to any length between 8 to 16 digits. The numeric-display characters are 7-segment 0.3 in. LED types. Display includes drive electronics for mating to an 8-bit TTL processor output. The character address uses four bits; the remaining four bits provide the BCD data to be displayed by the addressed character. Multiplexing is done by software scanning, but for systems with hardware multiplexing, a 16 × 4 RAM is provided.

CIRCLE NO. 380

## The Titchener Difference saved 100% in internal costs and 200% in weight in this microcomputer



Digital Equipment Corp.'s PDP 11/03 microcomputer

... A real plus in your production planning because we can nearly always improve performance characteristics, reduce weight *and* lower the unit cost of the part or component! Big claim? Then you'll be more interested in what one of our customers, Digital Equipment Corp., has to say about the wire and sheet metal chassis we did for their microprocessing equipment.

"We used your wire form construction on both our PDP 11/03 and PDP 11/04 units. As a result, internal structural costs were reduced 100%; weight of the component was reduced 200%. In addition we achieved more efficient cooling, better accessibility and reduced assembly time.

Because of the success of these two designs, we'll be considering your wire forms in future work!"

That's what the Titchener Difference is all about. Want to bet we can do the same kind of thing for you? Just contact.



E. H. Titchener & Co.  
22 Titchener Place  
Binghamton, N.Y. 13902 (607) 772-1161

Creative design and production in wire, sheet metal and tubing.


# Memory Power

## Eternacell® 10 year lithium primary battery for semiconductor memories

Don't risk memory failure. Eternacell® high reliability, lithium primary batteries are the ideal standby power source for all types of volatile memory applications. The reasons:

- Steady voltage (2.9 volts per cell) at low continuous current
- Shelf life of up to 10 years
- Highest energy per unit weight and volume
- No recharging
- Hermetically sealed
- Designed for pc board mounting

For complete information and pricing write:  
Power Conversion, Inc.,  
70 MacQuesten  
Parkway South,  
Mt. Vernon, N.Y. 10550.  
Or call (914) 699-7333



Model 440  
2.9 volts  
1.0 ampere-hours  
0.64" diameter  
1.31" height

# Power Conversion

CIRCLE NUMBER 80

## NEW! INSTANT FREQUENCY DIFFERENCE!



**Tracor Model 527A measures frequency difference instantly, precisely. For precisely \$3,150.** Front-panel meter reads directly to parts per 10<sup>11</sup>. Allows adjustment of two oscillators to the same frequency, adjustment to a specific offset, determination of offset — all instantly. Plus both short-term and long-term stability analysis. Internal oscilloscope extends precision to 1 x 10<sup>-12</sup>. Reference and signal frequencies need not be the same. Write or call for full technical and application information.

**Tracor** Industrial Instruments

6500 Tracor Lane • Austin, Texas 78721 • AC 512/926-2800

CIRCLE NUMBER 81

## POWER SOURCES

### Compact dc/dc converters deliver 40 W



Semiconductor Circuits, 306 River St., Haverhill, MA 01830. Ted Brewster (617) 373-9104. \$109.95/\$104.95; stock to 2 wks.

Two encapsulated modular dc/dc converters deliver 40 W and occupy 3.5 × 2.5 × 2 in. The Model CW12-5S8000 operates from an input range of 9 to 18 V dc. The Model CW24-5S8000 accepts an 18 to 32-V-dc input range. Both models deliver a single +5 V dc at 8-A output with foldback protection. The units have respective line and load regulation of 0.5 and 1% and output ripple and noise of 13 mV rms. Both models operate with no derating from -25 to +60 C.

CIRCLE NO. 381


### Open-frame switcher gives four outputs

LH Research, 1821 Langley Ave., Irvine, CA 92714. Wally Nusslock (714) 546-5279. \$297 (100 qty); 8 wks.

The Model TM-34 switcher power supply packs 175 W of four-output-power in 13 by 6 by 2.75 in. The supply gives four output voltages from 5 to 28 V. The main output is 5 V at 20 A. Second and third outputs can be any combination of the following: 5 V at 5 A, 12 V at 5 A, 15 V at 4 A, 18 V at 3 A, 24 V at 2 A, or 28 V at 2 A. The fourth output can be any of 5, 12, or 15 V at 1.5 A. The total power may not exceed 175 W.

CIRCLE NO. 382

## Storage batteries handle high-rate discharges




Globe-Union, 900 E. Keefe Ave., Milwaukee, WI 53201. Tom Wagner (414) 228-2581.

A series of Tel/Cell storage batteries is designed for the high-rate, short-duration discharges found in switchgear and uninterruptible power systems. The Tel/Cell UPX Series line of batteries packs more power per pound for discharges of less than one hour than other battery types. Every battery is custom built for each application. The batteries range in size from 1 to 7 kW/cell and from 600 to 2000 Ah.

CIRCLE NO. 383

## Solar cells have high efficiency




Optical Coating Lab, 15251 E. Don Julian Rd., City of Industry, CA 91746. (213) 968-6581.

A line of silicon solar cells operates at high conversion efficiencies under concentrated sunlight. Tests have verified a conversion efficiency of 16.5% at a 20-sun concentration and 15% with a 50-sun concentration at 28-C cell-operating temperature. The cells are for use at concentrations of from 10 to 50 suns. Cells range up to 37 cm<sup>2</sup> in a variety of shapes.

CIRCLE NO. 384

## Triple output switcher has fourth-output option




Hewlett-Packard, 1507 Page Mill Rd., Palo Alto, CA 94304. (415) 493-1501. \$636 (100 qty); 4 wks.

A multiple-output, switching-regu-

lated power supply, HP 63312F, provides three adjustable output voltages of 5, -12 to -15, and +12 to +15 V. An optional fourth output, as specified by the customer, is offered. The 550-W modular supply has brownout-protection circuits that allow full output power with input voltage from 87 to 127 V ac. The unit's three main outputs are regulated to 0.1% for full line and load variations, with ripple and noise of 0.05 V pk-pk at the 5-V output and 0.075 V pk-pk at the dual outputs.

CIRCLE NO. 385



**L-R-C  
Gotcha!  
...and for  
only \$695  
(USA only)**

## Newest ESI "weeder" does it all —even Dissipation Factor

True measurements of reactance (L, C) and loss (D, R, G) of passive components are now practical for anyone with ESI's Model 252 Digital Impedance Meter. Check these features:

- Measures D as well as L, R, C, G, automatically
- Light weight tilt stand handle
- 0.25% basic accuracy
- Wide ranges (autoranging optional)
- 1 kHz test frequency (120 Hz optional)
- Four measurements/sec.
- External bias
- 4-terminal connection
- Analog outputs
- Low power design
- Large 3½-digit

display • Input protection • Easy calibration • Optional front panel dust cover.


Measurements are simple, fast and accurate...Set the range and connect to unknown. Four-terminal KELVIN KLIPS® are included and the 252 can be combined with ESI's Model 1412B Limits Comparator and a special test fixture for go/no go testing.



Electro Scientific Industries, 13900 N.W. Science Park Dr., Portland, OR 97229. Telephone: 503/641-4141.

CIRCLE NUMBER 82

# 6800 PROCESSOR EMULATOR



- \* IN-CIRCUIT EMULATOR
- \* SINGLE STEP
- \* BREAKPOINT
- \* TRACE MEMORY
- \* REGISTER ACCESS
- \* SELF POWERED
- \* STAND ALONE
- \* PORTABLE



GET THE BUG!

## \$1860.



**APPLIED  
MICROSYSTEMS**

11064 118th Place Northeast  
Kirkland, Washington 98033  
Phone (206) 827-9111

CIRCLE NUMBER 83

## ICs & SEMICONDUCTORS

### Sample-and-hold device gives 12-bit accuracy




Burr-Brown, P.O. Box 11400, Tucson, AZ 85734. Steve Harward (602) 294-1431. \$7.95 (1-24 qty); stock.

Contained in a TO-99 package, the SHC298 sample-and-hold amplifier combines 12-bit throughput accuracy, wideband noise less than 20  $\mu$ V rms, and a droop rate of 5 mV/min with a 1- $\mu$ F external capacitor. The unit has fully differential logic inputs for mode control, allowing inputs to be driven with a twisted pair. Input logic levels are DTL, TTL and PMOS compatible. Input impedance is greater than  $10^{10} \Omega$ , and acquisition time is less than 10  $\mu$ s. Other specs include gain error less than  $\pm 0.005\%$ , gain drift less than 4 ppm/ $^{\circ}$ C, and full power bandwidth of 125 kHz with a 1000-pF holding capacitor. Power supply range is  $\pm 4.75$  to  $\pm 18$  V.

CIRCLE NO. 386

### 1-A rectifiers have 50 to 1000-V PRV




Solid State Devices, 14830 Valley View Ave., La Mirada, CA 90638. Dee Peden (213) 921-9660. See text; stock to 2 wks.

A line of fast-recovery rectifiers, the RP1 series, has peak-reverse voltages from 50 to 1000 V at 1 A with max reverse current of 5  $\mu$ A. Max reverse-recovery time is 250 ns for PRVs up to 600 V and 500 ns for the 800 and 1000-V devices. The diffused-junction devices are packaged in molded-plastic DO-41 cases. The 50-V devices are priced at \$0.20 each and the 1000-V units are priced at \$1 each in 1000 quantity.

CIRCLE NO. 387

### 100-A transistor claims largest junction



Germanium Power Devices, Andover, MA 01810. J.Q. Adams (617) 475-5982.

A power transistor with  $I_C$  up to 100 A is based on what is believed to be the largest discrete germanium junction ever used, a 0.475-in. diameter chip. The GPD 100SC series gives high gain ( $h_{FE} = 120$  at  $-60$ -A  $I_C$ ,  $-1$ -V  $V_{CE}$ ).  $V_{CE}$  (SAT) is 0.5 V max at 100-A  $I_C$  and only 0.3 V max at 75-A  $I_C$ . The transistor is housed in a TO-68 case.

CIRCLE NO. 388

### Power transistors handle 800-MHz mobile FM

Motorola, P.O. Box 20912, Phoenix, AZ 85036. Alan Wagstaffe (602) 244-6394. \$4.90 to \$20; stock.

Four uhf Class C power transistors, ranging from 1 to 20-W continuous output, operate in the 806 to 947 MHz FM band. All devices can operate from 12.5 V mobile supplies. The MRF838 and MRF838A are 1-W, stripline studless and stud common-emitter devices. MRF840, rated at 7 W and MRF842, at 20 W, are both connected for common-base operation in a CS-12 package. Input matching is optimized for 100-MHz instantaneous bandwidth. Series equivalent input and output impedances are specified for large signal operating conditions, with power gains ranging from 6 to 8 dB.

CIRCLE NO. 389

ELECTRONIC DESIGN 2, January 18, 1978


## Single chip acts as FM i-f subsystem

Motorola, P.O. Box 20912, Phoenix, AZ 85036. Dough Fryman (602) 962-3101. \$1.75 (100 qty); stock.

The MC3357 i-f subsystem contains nearly all components, from second mixer through audio and squelch outputs, needed for narrowband FM reception. Input is a first i-f frequency, typically 10.7 MHz. An internal doubly balanced mixer, driven by a Colpitts local oscillator, produces a second i-f in the 455-kHz range. After routing this signal through an external multipole bandpass filter, the device provides a five-stage, emitter-coupled, limiting i-f amplifier chain, followed by a balanced quadrature detector. Detected audio is amplified and processed by an active filter amplifier, and squelch is detected by a noise-operated switch. Additional outputs are used for audio muting and to provide logic triggering for scanning receivers. Typical 10.7-MHz mixer input sensitivity is 5  $\mu$ V. The detector produces 350 mV of audio from a narrow 3-kHz signal deviation.

CIRCLE NO. 390

## 8-bit d/a has 85-ns settling time




Datel Systems, 1020 Turnpike St., Canton, MA 02021. Eugene Murphy (617) 828-8000. \$8/\$12; stock.

Two fast monolithic 8-bit d/a converters with 85-ns settling time are available. Model DAC-08BC comes in a 16-pin plastic DIP and operates over 0 to 70 C and the DAC-08BM is in a 16-pin ceramic DIP and operates over -55 to +125 C. Nonlinearity is held to less than 0.19% or 1/2 LSB. An external reference current programs the scale factor and can be varied, resulting in one or two-quadrant multiplying operation. The output current has a compliance of -10 to +18 V, allowing direct current-to-voltage conversion with just an output resistor.

CIRCLE NO. 391

# Data collection made easy with reliable low cost optical badge and card reader.



ALPHA-NUMERIC Model P-12

**The only reader that interchanges plastic & paper cards.** Hollerith-punched paper or plastic cards read instantly. At any insertion speed. No adjustments necessary.


**A complete package.** No code converters to add. Plugs into standard printed circuit connector. Internal or external clocking capability. All information and controls in one unit.

**No moving parts.** Won't damage cards, badges. Advanced optical sensing and electronic logic circuitry for high reliability, long life.

**Transmit at any speed.** Independent data clocking and storage enables reader to transmit at desired rate without adjustments.

**Self-checking! Can't make a mistake.** Integrated monitor signals any defect in a sensor, light source, card, number of characters or position of card. Transmits only good messages.

NUMERIC Model D-57



### Adapts to most card data collection needs.

Decicom units speed production and inventory control, cost accounting, time and attendance monitoring, library systems, etc.


*Ask us how optical reliability can improve your data collection.*

# Decicom


DECICOM SYSTEMS, INC. 250 Adams Blvd., Farmingdale, N.Y. 11735 • 516/293-9270

CIRCLE NUMBER 84


## Microcomputer products from Dynabyte




**16K FULLY STATIC RAM.** S-100 bus, 250 ns. or 450 ns. RAM access time, bank select, 4k block addressing on 4k boundaries, write protect, assembled, tested, burned in, 1 year guarantee, 250 ns.—\$555, 450 ns.—\$525.



**32K FULLY STATIC RAM.** S-100 bus, 250 ns. or 450 ns. RAM access time, 4k block addressing, 70° max. ambient operating temp., assembled, tested, burned in, 1 year guarantee, 250 ns.—\$995, 450 ns.—\$925.



**16K DYNAMIC RAM.** S-100 bus, no wait states, transparent refresh, DMA control, 350 ns. access time, assembled, tested, burned in, 1 year guarantee, \$399.



**DUMB TERMINAL,** an S-100 bus board, add keyboard and video monitor to replace stand-alone terminal and serial I/O board, saves 30-60%, 80x24 display, upper & lower case, addressable cursor, block mode, assembled, tested, burned in, 1 year guarantee, \$350.


### DYNABYTE

4020 Fabian, Palo Alto, CA 94303, (415) 494-7817, Cable "Dynabyte"

CIRCLE NUMBER 85

## MAGNETICALLY SHIELDED DATA PRESERVERS

Protect your Flexible Disks from magnetic degradation, erasure, or physical damage. Cases are designed for storage, shipment and hand carrying. A wide choice of models and capacities also available for Minidisks, Diskettes, Standard Reels, Disk Packs, Standard Cassettes.



FLOPPY DISK

SEND FOR NEW  
TP-5 CATALOG

MAGNETIC SHIELD DIV.



PERFECTION MICA CO.  
740 North Thomas Drive  
Bensenville, Ill. 60106, USA  
Phone 312 / 766-7800  
TWX 910-256-4815

CIRCLE NUMBER 86

## Smart modem replaces three different ones

*Vadic, 505 E. Middlefield Rd., Mountain View, CA 94043. (415) 965-1620. \$850.*

A microprocessor-controlled modem, the VA3467, automatically recognizes, and communicates with the Vadic VA3400 (1200 bps full duplex), the Bell 103 (300 bps full duplex), and the Bell 212 (1200 bps full duplex). It contains all the components needed for direct connection to switched telephone lines, eliminating the need to rent DAA's from the phone company. Computers capable of using the VA3400, or the Bell 103 and 212 can use the VA3467 without altering hardware or software. The smart modem satisfies every answer mode application for switched network data transmission in asynchronous data format, at rates from 0 to 1200 bps, and occupies two card slots in the standard Vadic VA1616 or VA1601 chassis. Another unique feature is the VA3467's ability to continuously test itself by turning on its transmitter, switching its receiver to the same carrier, and sending a scrambled mark into the transmitter. If the receiver doesn't get the proper signal, a flashing status light alerts the operator. The VA3467 complies with FCC registration requirements to connect directly to switched telephone lines through a phone company-supplied data jack.

CIRCLE NO. 392

## 300-Mbyte mass storage plugs into SyFA units

*Computer Automation, 18651 Von Karman, Irvine, CA 92713. (714) 833-8830. \$32,500; 16 wks.*

A 300-Mbyte mass storage device, DSK300, meets the large-scale data base requirements of SyFA network processing systems. The device offers 220 Mbytes of user accessible storage, and employs CDC 9883-91 removable-disc packs. Up to eight DSK-300s can be linked to a SyFA system, extending total user-accessible storage to 1760 Mbytes. Storage is totally compatible in format and hardware with existing SyFA systems.

CIRCLE NO. 393

## Data-acquisition device uses portable calculator




Hewlett-Packard, 1507 Page Mill Rd., Palo Alto, CA 94304. (415) 493-1501. \$1375; 12 wks.

The Model 97S I/O is based around the HP-97 programmable printing calculator and uses BCD interfacing to gather data from a wide range of instruments. Data are manipulated by user-designed programs to produce a printed report. The calculator has 224 merged-program steps, a "smart" magnetic-card reader, three levels of subroutines, labeling, indirect and relative addressing, RPN logic and a four-register automatic memory stack. Ten BCD input lines allow entry of data. Four output lines aid in the instrument control. These outputs may be set and cleared under software control.

CIRCLE NO. 394

## Smart plotter uses built-in micro



Houston Instrument, 1 Houston Sq., Austin, TX 78753. Rod Schaffner (512) 837-2820. \$3495; 4 wks.

The DP-101 intelligent plotter contains a microprocessor for the generation of vectors, characters, arcs, circles and special symbols. The unit can be used for time-sharing and attaches to any RS-232C interface. Transmission errors are automatically detected. In addition to real time applications the plotter can be driven off-line by a floppy disc or tape cassette. Included are rates of 110, 300 and 1200 baud and a 960-char data buffer. Step size is 0.005 in./step at a speed of 400 steps/s. The flatbed instrument, with vacuum holddown, uses 11 x 17-in. paper for an effective plot size of 10 x 15 in.

CIRCLE NO. 395

## Translator operates on serial data stream

Sigma Data Systems, 715 Torrey Ct., Palo Alto, CA 94303. Cliff Kirkhart (415) 494-1138.

A device which performs code translations on a serial data stream is completely self-contained, including a power supply. The serial data translator communicates via two RS-232

ports at up to 19.2 kbaud. Standard translations include ASCII, EBDIC, BAUDOT, and terminal control codes (such as cursor control). Other translations are available or may be user-programmed. The unit contains an Intel 8035 microprocessor and up to 1 k-byte of EPROM. Since the unit communicates via serial ports, it is compatible with any host computer.

CIRCLE NO. 396

# Tbar<sup>®</sup> PLUGGABLES are Relays

for printed circuit back planes


A design basic. Package your multi-circuit switching compatible with the rest of your equipment. The T-BAR 6900 printed circuit card switching module . . . we call it the PLUGGABLE . . . has been used for years to switch many circuits in little space in printed circuit systems. Available from 24 to 72 contact sets per module.

Use the PLUGGABLE to switch communications and computer circuits. Call for design help or write for dimensional literature.

**Tbar<sup>®</sup>** INCORPORATED  
SWITCHING COMPONENTS DIVISION  
141 Danbury Road • Wilton, CT 06897  
Telephone: 203/762-8351  
TWX: 710/479-3215

# strip chart recorders

- OEM MODULES
- LOW PROFILE
- PACKAGED UNITS
- PORTABLE DC



General Scannings thermal writing Strip Chart Recorders are available in a wide range of configurations and performance characteristics to meet virtually every recorder need.

You can select open-loop, velocity feedback or closed-loop operation; continuous roll or fan-feed paper; one to eight channels in channel widths of 20, 40, 50, 80 or 100mm; a variety of chart speeds; and either AC or DC operation.

Recorders can be furnished as modules for use by OEM's or fully packaged.



For complete details, circle readers' service number or write today for our full line Strip Chart Recorder Catalog.



**GENERAL SCANNING INC.**  
150 Coolidge Avenue  
Watertown, MA. 02172  
TEL: (617) 924-1010

CIRCLE NUMBER 93

## DATA PROCESSING

### Voice-data entry device is video/TTY compatible

*Threshold Technology, 1829 Underwood Blvd., Delran, NJ 08075. Joe Simmons (609) 461-9200. \$13,500.*

The Model 600 voice-data input system can be used as a direct replacement for either a video or teleprinter terminal. The Model 600 is compatible with RS232C, CCITT-V24 or 20-mA current-loop teleprinters. It allows full duplex communications via ASCII or other codes. Magnetic-tape mini-cartridge storage is provided to handle output character strings, training prompts, and speaker reference data. All voice recognition functions are controlled by the terminal. Included hardware consists of a speech-recognition processor, a 16-character alphanumeric display, two noise-canceling microphones, an operator console and a cartridge storage unit.

CIRCLE NO. 397

### Thrifty computer handles small-business data



*Info 2000 Corp., 20630 S. Leapwood Ave., Carson, CA 90746. (213) 532-1702. Under \$10,000; 2 to 4 wks.*

The Model 2000 Business System for processing small-business data consists of a Z80-based computer, dual flexible-disc drives, high-speed printer, video terminal and business-applications software. The mainframe uses the S-100 bus and contains a Z80 CPU, up to 56 kbytes of RAM, 8 kbytes of EPROM, a filtered forced-air cooling system, and power supply. The printer is a 160-char/s, 132-column line device that provides all 95 ASCII upper/lower case alphanumeric and graphic characters. The video console displays all ASCII characters with dual-display intensity and protected fields at 19,200 bits/s.

CIRCLE NO. 398

### Box checks and controls multipoint data network

*Syntech, 11810 Parklawn Dr., Rockville, MD 20852. George Fritkin (301) 770-0550.*

The System 5 provides a central computer site with the status of, and control over the performance of multipoint data communications network. The device can be used with both digital and analog networks and is independent of modem type. The device continuously scans all system components and automatically detects and reports faulty equipment. The report includes a hard copy printout of fault time, line number, remote address and failed equipment.

CIRCLE NO. 399

### Data handler gives computers mass storage

*August Technology, 2040 N. Maplewood St., Orange, CA 92665. (714) 998-1639. From \$3250; 8 to 12 wks.*

A data-handling and recording peripheral, the Model 7701 provides multiple I/O channels, data-manipulation capabilities, and can record up to 580 kbytes on a Philips cassette. The unit interfaces with the HP 9800 calculators, the Wang 2200 and the IBM 5100 computer. Having an 8080 microprocessor and up to 64 kwords of memory, the 7701 provides up to 10 TTY current-loop, synchronous or asynchronous RS-232 ports and an 8-bit parallel data bus. Data may be recorded and played back through any port on the bus at different rates. Data may also be transferred among ports without recording.

CIRCLE NO. 403

### Baud converter adjusts terminal to modem speed

*Triformation Systems, 3132 S.E. Jay St., Stuart, FL 33494. (305) 283-4817. \$995.*

The Model CB-1 is a baud rate converter which may be installed between computer terminals and modems conforming to the E.I.A. Standard RS-232-C to make them compatible with input or output speed. The device has a conversion range of 10 to 960 char/s and is capable of storing 2048 char. The unit comes equipped with an overflow alarm and indicator light.

CIRCLE NO. 404



## Tool kit or tool case, isn't it time you owned a Jensen?

A Jensen tool kit's combination of functional case, exclusive pallet design, and proven selection of professional-quality tools gets work done faster, more efficiently. Its executive appearance gives you pride in your work; gives customers confidence in your service. Assures you of front-door access to the equipment you are charged to maintain. Choose from more than 50 standard models or let us custom-design a kit to match your needs. Write or call for more information or a free catalog.



### JENSEN TOOLS AND ALLOYS

1230 SOUTH PRIEST DRIVE TEMPE, ARIZONA 85281  
(602) 968-6231

CIRCLE NUMBER 94

## IM1000 UNIVERSAL PROM PROGRAMMER



- HIGHEST PERFORMANCE/PRICE RATIO
- CAPABILITY TO PROGRAM ANY PROM FROM ALL MANUFACTURERS
- COMPACT FOR PORTABILITY
- TWO RS232 I/O PORTS FOR INTERFACING TO MICROCOMPUTER DEVELOPMENT SYSTEM OR TIMESHARE COMPUTERS
- 32000 BIT RAM FOR FULL EDITING OF PROM DATA

The IM1000 sells for \$1695. Personality Modules \$330. Contact us for a demonstration by our nationwide representatives.

TEL: 301/340-7505

**IM** International Microsystems, Inc.  
638 Lofstrand Lane  
Rockville, Md. 20850

CIRCLE NUMBER 96

## PLENTY OF POWER PACKS

Small size, hermetically sealed. Promise long life, low ripple, withstand vibration and shock. AC input, DC output. Wide variety of electrostatic and solid state applications. Standard and custom designs available. Off the shelf delivery up to 75 KVDC. Just send your specs.

Write for Technical Data.




Plastic Capacitors, Inc.  
2623 N. Pulaski Road  
Chicago, Illinois 60639  
(312) 489-2229

"Serving industry for 25 years"

CIRCLE NUMBER 95

ELECTRONIC DESIGN 2, January 18, 1978

## Smallest industrial direct digital readout Elapsed Time Indicator?



### The only big thing about it is its easily read 4-digit hourly display

Our Series 49200 Elapsed Time Indicator is the smallest industrial direct digital readout ETI we've ever made. It may be the smallest anyone has ever made. It measures a mere  $\frac{37}{64}$ " sq. x  $1\frac{1}{4}$ " long—a real space-saving way to monitor operating time in business machines, computers, peripherals and other equipment where space is limited. Despite its small size, it's exceptionally accurate, and the .075" high 4-digit hourly display is readily legible. An automatic tamper-proof latching memory stores elapsed time indications that can't be lost in event of power failure. Where size is important, the Series 49200 can be one of your best values ever. It's powered by a 1W synchronous motor, 115V ac, 60 Hz. Front or side readout. Surface or through-panel mount.

Send for information today!

A. W. HAYDON CO. PRODUCTS

NORTH AMERICAN PHILIPS CONTROLS CORP.

Cheshire, Conn. 06410 • (203) 272-0301

FOR INFORMATION, CIRCLE 97

FOR IMMEDIATE, CIRCLE 98


# SPACE · SAVER SPACE · SAVER SPACE · SAVER

The DS-Series  
Switcher from  
Digital Power!

- +Small Size
- +Light Weight
- +High Efficiency

150 Watts in  
90 Cubic Inches

- Brown-Out Protection
- Short Circuit Protection
- Drop-Out Protection
- OVP on All Units
- Exclusive 'Guardian'  
Overtemperature Protection



SINGLE 5v @ 30A	TRIPLE +5v, ± 12v
\$187	\$200
1000 Quantity	


## DIGITAL POWER

2060 The Alameda • San Jose, California 95126 • (408) 246-4337

CIRCLE NUMBER 104

## USC UPCC/REPC CONNECTORS

Draw Pull and Screwlocking. Built to MIL-C-55302 and Commercial Specifications Printed Circuit and Related Applications. REPC Connectors are Removable, Re-Entrancy, Crimp Contact Types.



1 of over 20,000 Connector Types Manufactured. Send today for UPCC-REPC-A Series 32-page Catalog.


### U.S. COMPONENTS, INC.

Leader in advanced  
engineering design

1320 Zerega Avenue, Bronx, N.Y. 10462  
(212) 824-1600 TWX 710-593-2141  
Cable: COMPONENTS, NYK

CIRCLE NUMBER 105

## Little Red Reed Relays



Pat. Pend.

**SPST- SPDT  
DPST- DPDT**

- ★ Red Flame Retardant Shell
- ★ Instrument Grade Contacts
- ★ Coto's High Reliability Testing
- ★ Premium Grade Switches
- ★ Form B or Latching Contacts
- ★ Epoxy Encapsulated
- ★ Low Water Absorption
- ★ ... and Much More!

Write or Call for Bulletin




**COTO-COIL  
COMPANY, INC.**  
59 Pavilion Ave.  
Providence, R. I. 02905  
Tel: (401) 467-4777

CIRCLE NUMBER 106

## PACKAGING & MATERIALS

Castable silicone is  
high loser at uhf




Emerson & Cuming, Canton, MA  
02021. Jeanne O'Brien (617) 828-3300.  
\$11.55/lb; stock.

Eccosorb CF-S is a castable silicone rubber that exhibits high loss in the uhf and microwave range. The product is magnetic with a high loss tangent. Also, it's nonconductive electrically, and can be poured or painted on almost any surface. When applied, the coating suppresses surface currents, reduced reflectivity of objects and lowers the Q of cavities.

CIRCLE NO. 405

Test system improves  
harnessing efficiency



T & B/Cablescan, 145 E. Emerson  
Ave., Orange, CA 92665. (714) 998-1961.  
From \$1850.

The automatic Random Work Director System, Model RWD-1000, helps harness makers maintain zero defects, increase productivity, eliminate fatigue and rework and reduce wire-identification costs. The system consists of a remote-control display, a mainframe for circuit interface and 50-wire plug-in modules. The system identifies each conductor numerically, locates termination points with lamp indicators and performs continuity testing after final assembly. A programmed back-wired harness board is interfaced to the assembly to be made. When interfacing is completed, the system is activated on all circuits to instruct, verify and test.

CIRCLE NO. 406

ELECTRONIC DESIGN 2, January 18, 1978


## Wire-wrapping kit's tool strips and wraps

O.K. Machine & Tool, 3455 Conner St., Bronx, NY 10475. Judy Camen (212) 994-6600.

A wire-wrapping kit, for prototype work, includes a wire-wrapping tool, a 50-ft roll of wrapping wire and pre-stripped wire in four lengths of 1 to 4 in. The kit's combination tool, Model WSU-30, wraps and unwraps #30 wire on 0.025-in. square pins after first stripping the wire with its built-in stripper.

CIRCLE NO. 407

## Thermoplastic replaces rubber in bumpers



Ashland Products, 10910 S. Langley, Chicago, IL 60628. Bill Walter (312) 568-6500.

Made of thermoplastic instead of rubber, the soft and resilient bumpers can dampen vibration and cut noise. The bumpers are corrosion and abrasion resistant and they can be used up to 275 F and stay flexible to -60 F.

CIRCLE NO. 408


## Two conformal coatings meet MIL-I-46058C

Conap, 1405 Buffalo St., Olean, NY 14760. (716) 372-9650.

Two polyurethane conformal coatings for PC boards meet the requirements of MIL-I-46058C for Type UR coatings. Conathane CE-1165 is a two-part system for thin-film use on components and printed circuitry. The coating provides humidity resistance and hydrolytic stability. A tracer dye in the material becomes fluorescent under ultraviolet light as an aid to inspection. Conathane CE-1166 is a single component, moisture-cured polyurethane coating with similar properties.

CIRCLE NO. 409

## Multilayer bus bars have square pins



Methode Electronics, 1700 Hicks Rd.,


Rolling Meadows, IL 60008. (312) 392-3500.

Square-staked and soldered pins are used in multilayer bus bars to increase reliability of wrapped wires. Square 0.025-in. pins, press fitted into round holes and soldered for positive connection, to make the bus bars have passed mechanical and environmental tests for shipboard use. Conductor layers are of electrical-grade copper and the pins can be supplied in phosphor bronze or beryllium copper.

CIRCLE NO. 410

# short Story

## About a 0.4" regulated 6 watt DC-DC Converter



Here's a short story with a happy ending. Tecnetics' new 100 Series low profile DC-DC converter packs 6 watts of power into a very short 0.4" case.

It's a perfect fit for tight places like between rack-mounted PC boards in computers, communications equipment, instruments, or anywhere height space is limited. This new converter is available with single or dual outputs, boasts efficiencies as high as 60%, and offers full isolation and regulation to

eliminate pick-up of noise or feedback.

Tecnetics wrote the book on state-of-the-art converters. We've been producing and improving them since 1959, so that today our catalog contains over 1000 converters, each a tale in itself. So write for our catalog and get the whole story.

And now for the happy ending we promised you: prices for the 100 Series start at \$60.00.

### 100 SERIES DC TO DC REGULATED CONVERTER

Output (VDC): 5-15  
Input (VDC): 5,12,24,28  
Terminals: PC type pins


Dimensions: 2.35"L x 2.125"W x 0.40"H  
Weight: 3.0 ounces Typ.  
Operating Temp.: -25°C to +71°C (Case)

Case: Black glass fiber-filled Diallylphthalate

**tecnetics**® The Power Conversion Specialists P.O. Box 910,  
1625 Range Street, Boulder, Colorado 80302  
(303) 442-3837 TWX 910-940-3246

CIRCLE NUMBER 107

Just  
Published!



# Switching and Linear power supply, power converter Design

Abraham I. Pressman

A "how-to-design" book  
written from a power  
supply designer's  
point of view!

Covers all the circuits, systems,  
magnetics, and thermal design  
skills essential to modern power  
supply design.

#5847-0, cloth, 384 pages, \$19.95

**ORDER YOUR 15-DAY  
EXAMINATION COPY  
NOW!** When billed,  
remit or return book.

**HAYDEN BOOK  
COMPANY INC.**  
50 Essex Street,  
Rochelle Park, N.J.  
07662



## Application notes

### Gauges and sensors

Semiconductor strain gauges, temperature sensors and integrated force/deflection sensors are discussed in a 20-page bulletin. Application notes, a specifications chart, installation instructions and ordering information are included. Kulite Semiconductor Products, Ridgefield, NJ

CIRCLE NO. 411

### Instrumentation amplifiers

The selection and application of high-performance instrumentation amplifiers are covered in a four-page brochure. Key specifications, error budgets, and circuit approaches are described in detail and typical applications are shown for biomedical and strain-gauge amplification. Micro Networks, Worcester, MA

CIRCLE NO. 412

### Voltage regulators

A 198-page softback covers all aspects of power-supply design and helps engineers to select the proper regulator ICs and associated components for higher levels of system performance. Complete data-sheet information on all components and mechanical hardware is a major part of the book. A list of 66 different types of TI regulator circuits, a glossary of voltage-regulator terms and selection guide are also included. Texas Instruments, Dallas, TX

CIRCLE NO. 413

### Memory testing

"Memory Testing with a Difference," 20 pages, discusses a number of factors involved in the selection of memory-test equipment, including timing resolution, automatic calibration, software, and analog performance. Teradyne, Boston, MA

CIRCLE NO. 414

## Bulletin board

Elpac Power Systems'  $\mu$ PS-35 micro-processor power supply now costs less than \$50 (100 qty).

CIRCLE NO. 415

Pro-Log has been granted Underwriters' Laboratory listing on all its **PROM programmers, erase lights and personality modules.**

CIRCLE NO. 416

Gettys Manufacturing has received Underwriters Laboratories' recognition for its N350 servo controller and panel assembly.

CIRCLE NO. 417

VIZ Test Instruments Group has cut prices on its **WD-752A frequency counter** from \$255 to \$200 and **WD751A digital VOM** from \$179 to \$150.

CIRCLE NO. 418

Texas Instruments has received FCC-type acceptance for its **Model 2000 vhf-FM marine radiotelephone.**

CIRCLE NO. 419

National Semiconductor slashes **LM129 and LM199 series voltage reference** prices by more than 40%.

CIRCLE NO. 420

Bendix has introduced a microprocessor-based **interactive drafting and mapping system** for under \$40,000.

CIRCLE NO. 421

Signetics' **digital-to-analog converter IC** prices have been reduced as much as 29%.

CIRCLE NO. 422

Cambridge Memories has reduced prices on its **370/STOR 168 add-on memory system** for large IBM System/370 Model 168 computers by at least 9%.

CIRCLE NO. 423

# OVENAIRE...

...now, more than ever, your best bet for crystal oscillators.

Ovenaire's oscillator capabilities have been enhanced by the acquisition of W.H. Ferwalt, Inc.

- **STATE-OF-THE-ART HIGH STABILITY CRYSTAL OSCILLATORS** with stabilities to  $5 \times 10^{-10}$ /day and  $7 \times 10^{-11}/^{\circ}\text{C}$ .
  - **OVENIZED CRYSTAL OSCILLATORS**  $3 \times 10^{-9}/^{\circ}\text{C}$  at low cost.
  - **TCXO's** with temperature stabilities to  $\pm 1 \times 10^{-7}$  0 to  $50^{\circ}\text{C}$ .
  - **DIP HYBRID CIRCUIT CRYSTAL OSCILLATORS** with temperature stabilities to  $\pm 20$  ppm.
- ...and, as always, your best bet for crystal and component ovens.
- **ELECTRONIC CONTROL MINIATURE OVENS FOR:** HC-18U, HC-25U, HC-42U, HC-43U crystals TO5 & TO8 crystal, transistor or IC 14 Pin & 16 Pin DIP IC.

Plus a complete range of ovens for commercial and military applications.

## OVENAIRE-AUDIO-CARPENTER

Division of Walter Kidde & Company, Inc.  
706 Forrest St., Charlottesville, Va. 22901  
804/977-8050 TWX 510-587-5461 **KIDDE**

CIRCLE NUMBER 108

# Mini BITE\* Indicators Qualified to Mil-I-83287



Widest selection of Bite Indicators for high performance aircraft, computers, communications, ground test equipment, etc. QPL listings to MIL-I-83287/1, /2, /3 or /4. Provide reliable fault detection or circuit condition indication with power drain low as 50 milliwatts. Display positive color contrast with excellent visibility under extreme environments, temperatures  $-65^{\circ}\text{C}$  to  $+125^{\circ}\text{C}$ , vibration to 2000 Hz20G. Available to operate at 1.5, 3, 5, 6, 12 or 28 volts, manual or electrical reset. PROTOTYPES AVAILABLE on phone or letter-head request.

**SUDDEN SERVICE on SMALL QUANTITIES**

\*Built-in-Test-Equipment

**MINELCO**

a **TALLEY INDUSTRIES** Company

135 South Main St., Thomaston, CT 06787  
Phone 203-283-8261

CIRCLE NUMBER 110

## New Low Cost TIME CODE GENERATOR/READER



**Time Code Reader** ..... \$890.  
**Generator/Reader** ..... \$1265.

The new LOW COST Series 9000 Time Code Units generate and read serial IRIG Time Codes used in analog magnetic tape instrumentation, hard wire transmission and telemetry systems. In addition, they provide buffered parallel BCD outputs, TTL compatible, for digital storage devices and computer inputs. Options include Multi-code units, Day-of-Year Calendars and Millisecond BCD outputs.

Write or call Chrono-log Corporation, 2 West Park Road, Havertown, Pa. 19083, (215) 853-1130



CIRCLE NUMBER 109

## ALCOSWITCH

HIGHEST QUALITY  
MINIATURE TOGGLES

Our premium Green Series inherently contain many quality features — all included at no extra cost.

During the past 16 years we've listened to customers. The result is a product that is indisputably the #1 miniature switch line in the industry.

Of importance, our terminals have bonded fine silver contacts which are gold flashed to retard oxidation and facilitate soldering, furthermore, the terminals are Molded-In SE-0 diallyl phthalate cases.

We urge you to call Customer Service at (617) 685-4371. Our sales people would like to tell you why ALCOSWITCH is your best buy.

P.S. Don't forget to ask for our new 76-page catalog and free samples, too!




**ALCO** ELECTRONIC PRODUCTS, INC.  
1551 OSGOOD STREET, NORTH ANDOVER, MA 01845 U.S.A.

Tel: (617) 685-4371 TWX: 71 342-0552

A SUBSIDIARY OF **AUGAT** INC

CIRCLE NUMBER 111

# New literature



## Recorders

"The Recorder Book" illustrates strip chart, multipoint and circular chart instrument lines. Capabilities, prices, options and accessories of each model are listed. Honeywell Process Control Div., Fort Washington, PA

CIRCLE NO. 424

## FET data book

A 260-page FET data book contains an industry-wide cross-reference and substitution guide, Siliconix preferred parts selector guides, complete product specifications, geometry characteristics and mechanical data. Siliconix, Santa Clara, CA

CIRCLE NO. 425

## Switches

Subminiature and microminiature switches are described in a 48-page catalog. The catalog gives complete specifications and includes a 4-page section on mounting information, hardware, and accessories. C&K Components, Watertown, MA

CIRCLE NO. 426

## Connectors

A 180-page standard-line-connector catalog with a special selection guide covers how to order, materials and finishes, electrical data, contact arrangements and tooling accessories. Included are cutaway drawings and photographs. ITT Cannon Electric, Santa Ana, CA

CIRCLE NO. 427

## Switching power supplies

Two brochures describe switching power supplies. The specifications of 12 models in the SMG series, rated from 8 to 2250 W, are detailed in one brochure. The MG switching-power-supplies brochure describes the specifications of products ranging from 50 to 500 W. Gould, Electronic Components Div., El Monte, CA

CIRCLE NO. 428

## Processor storage system

Features of the Multimemory/148 processor storage system are offered in a data sheet. EM&M, Computer Products Div., Hawthorne, CA

CIRCLE NO. 429

## Minicomputers

Four brochures describe a family of minicomputers. Each minicomputer's capabilities are written in understandable, nontechnical terms with color photographs showing each version. Cincinnati Milacron, Electronic Systems Div., Lebanon, OH

CIRCLE NO. 430

## Digital panel meters

Technical specifications and prices for the Slimline Series II panel meters are given in a 12-page catalog. Nationwide Electronic Systems, Streamwood, IL

CIRCLE NO. 431

## Temp sensing devices

Basic temperature-sensing methods using thermocouples, thermistors and resistance-temperature devices (RTDs) are shown in a 40-page catalog. Conax, Buffalo, NY

CIRCLE NO. 432

## Computer systems

A 20-page booklet describes the use of computer systems in large business applications. Included is a section describing five major industrial applications, a catalog of peripherals, an overview of distributed processing, a list of available software and a description of HP's training support and maintenance programs. Hewlett-Packard, Palo Alto, CA

CIRCLE NO. 433

## PM motors

"Permanent Magnet Motors and Integral Motor Tachometers for Servo Applications," 20 pages, offers all motor parameters and size specifications plus complete performance data with curve charts. Indiana General, Motor Products, El Paso, TX

CIRCLE NO. 434

## Oscillators

A 44-page catalog covers frequency controls. Greenray Industries, Mechanicsburg, PA

CIRCLE NO. 435

## Solenoids

A complete range of box frame, tubular, laminated and "c" frame solenoids for ac or dc applications is presented in a 60-page catalog. Dormeyer Mfg. Co., Chicago, IL

CIRCLE NO. 436

## Rectangular connectors

Over 200 components of the MR Series connector family are described with full physical and electrical specifications in a catalog. AMP, Harrisburg, PA

CIRCLE NO. 437

## Silicone products

A 40-page catalog covers hundreds of silicone, organosilicon, and silicon products and their uses in over 25 major industry classifications. Dow Corning, Midland, MI

CIRCLE NO. 438

## Resistors

Positive-temperature-coefficient resistors are covered in an eight-page catalog. Murata, Marietta, GA

CIRCLE NO. 439

## Memories

Six, two-page data sheets describe DEC PDP-11 compatible memories, including planar (add-in) and modular (add-on) memories in capacities from 12 kwords to 4 Mbytes. The bulletins include design features, specifications, and addressing and operating data for PDP-11 users. Monolithic Systems, Englewood, CO

CIRCLE NO. 440

## Breadboards

Microcomputer boards, printed circuit boards and off-the-shelf designer breadboards are covered in a six-page brochure. Artec Electronics, San Carlos, CA

CIRCLE NO. 441

## Display calculator

Important features of the 2102 display calculator, including its full 12-digit capacity, decimal selection for add mode, 0, 2, 3, 4, 6 or floating decimal, and a complete 4-key memory, are outlined in a data sheet. Facit-Addo, Greenwich, CT

CIRCLE NO. 442

## Noise-blanking circuitry

Noise-blanking circuitry available as an option with broadband amplifiers, designed to reduce noise and/or gain on a rapid, repetitive basis, is described in a bulletin. Amplifier Research, Souderton, PA

CIRCLE NO. 443

## Ribbon connectors

Ribbon-contact rack and panel connectors are described in a 20-page catalog. TRW Cinch Connectors, Elk Grove Village, IL

CIRCLE NO. 444

## Foils

High-purity electroformed copper and nickel foils and thin metals are described in a literature package. Gould, Foil Div., Cleveland, OH

CIRCLE NO. 445

## Connectors and cables

A 40-page catalog includes sections on patching, connectors and cable assemblies. Trompeter Electronics, Chatsworth, CA

CIRCLE NO. 446

## Rotary switches

Nine standard, stock configurations of Rotocode rotary switches in a choice of nine output codes from 10 to 60 positions are featured in an eight-page catalog. Application data and dimensional product drawings are provided. Cherry Electrical Products, Waukegan, IL

CIRCLE NO. 447

# This coupon can eliminate the hours of work you hate

Using spec sheets and manufacturer's catalogs to find semiconductor technical information is stealing your valuable time.

But now there's a system that can reduce your reference hours to minutes. Puts technical data on worldwide Microcomputers, Integrated Circuits, Discrete Devices and Optoelectronics components at your fingertips.

The D.A.T.A.BOOKS Electronics Information Series. D.A.T.A. engineers have successfully combined your data needs with standardized values, terms, and definitions. Here are the tens of thousands of semiconductors manufactured in the U.S. and around the world — arranged by key parameters for your quick and easy comparison. Fast information that's accurate, dependable, up to date.

Send us the coupon or circle the reader response number. We'll send you information about eliminating hours of needless searching.

**FREE** 10 Page Brochure  
*Tells how to make your work more  
interesting and less time consuming.*



## D.A.T.A.BOOKS

D.A.T.A., INC. A Cordura Company  
45 U.S. Highway 46, Pine Brook, New Jersey 07058  
Telephone: (201) 227-3740

**Yes, I'd like to eliminate the hours of work I hate.  
Please send me the free brochure on  
D.A.T.A.BOOKS.**

Name \_\_\_\_\_ Title \_\_\_\_\_

Firm \_\_\_\_\_

Street \_\_\_\_\_

City \_\_\_\_\_ State \_\_\_\_\_

Zip \_\_\_\_\_ Phone \_\_\_\_\_

# Across the desk

(continued from page 7)

or elements times the cycle time of the clock. Thus, the MN3005 you describe has only 2048 stages or elements of delay, and 4096 transfers.

The clarification becomes important when comparing different technologies. For example, Reticon Corp. markets a 2000-stage delay element, R5101, with comparable time-delay capability; however, this is a four-phase CCD with 8000 transfers.

Also, you imply—erroneously—that charge-transfer devices cannot be connected in series without intermediate amplifiers and low-pass filters. The devices are sampled devices, with input-aperture times substantially less than one microsecond. Reticon's SAD-1024, for example, has an aperture time of approximately 100 ns. Furthermore, the SAD-1024 permits unity gain, so one can couple the output from one to the input of the next.

Inserting a low-pass filter *degrades* the performance, because a  $(\sin \pi f/f_c)/(\pi f/f_c)$  frequency factor applies any time the stair-step sampled nature of the signal is converted to a smooth analog signal, whether between stages or not. Output filtering is desirable and usually required, but only one such filter should be applied, and that at the output. Interstage filters will compound the frequency roll-off unnecessarily.

*Robert R. Buss*  
Staff Engineer

Reticon Corp.  
910 Benicia Ave.  
Sunnyvale, CA 94086

## Brother of laetrile

I have picked through the bones of contention in your laetrile controversy and my X-ray shows two most important bones have not been dealt with.

The first is public fraud. You may assert that laetrile can't hurt anyone, and so can the seller of snake-oil. For the medicine man knows that the little amount of whiskey he has spiked his concoction with may get you high enough to make you feel good for a little while and get you to come back for some more. But there is no cure for anything, and he says there is and takes your money under false pretenses. That's FRAUD! We have laws that can be invoked to protect the

innocent and the gullible from such lying charlatans, and they apply to laetrile promoters.

The second "bone" has to do with civilian responsibility for keeping government honest. This country has a dread social disease, NIWSST—Nobody Is Watching So Screw Them. No government agency will work properly if not constantly monitored, and likewise no individual will do right unless constantly monitored by friends, family, churches, bosses, the Law, etc. We make government agencies because we know they can be stronger in righting wrongs than individuals. To destroy our bureaucracies is a retrograde step that will make things as bad as they were when we found it necessary to make bureaus. If our "computer design"—in this case, the FDA—has a glitch and won't fulfill a function, don't destroy the computer, deglitch it!

*Nathaniel Cunningham*  
Managing Director

Computronics Engineering  
7225 Hollywood Blvd.  
Los Angeles, CA 90046

## Daughter of laetrile

I am absolutely ashamed that a spokesman for my profession would criticize the American medical profession. Everyone knows how editors will write just anything to get people to read the ads in their publications. The facts would seem to indicate your Editorial in the July 19, 1977, issue of ELECTRONIC DESIGN is such an article.

The wife of a colleague of mine had terminal cancer. Three clinics—one in San Diego, one in Los Angeles, and one in San Francisco—independently reached the same conclusion: She would die within six months, but a heroic attempt to save her life could be made. It was important that the treatment start as soon as possible so that if modern medical research discovered a cure, there would be ample time to save her life. Unfortunately, modern medical research didn't come up with a cure, but my friend's wife went to Mexico, one of 26 countries where laetrile is accepted. She is still alive—six years later.

Clearly, my colleague's wife is an exception. There are probably no more

than 100,000 "exceptions" in the U.S. today. But there are a good many more who choose the treatment provided by modern medical research and generate additional funds for research as a result of their choice.

Come on, George. You know that it is the number one responsibility of a professional to raise money for his profession. Let's hope that laetrile backers fail so that the electronics industry will be able to supply additional equipment for cancer research.

*Steven Rigg*

1316 Palmer Ave.  
Camarillo, CA 93010

## Misplaced Caption Dept.



After you again trace all circuit connections and review the manual, you are ready to apply power to the \$3000 klystron tube.

Sorry. That's Hans Memling's "Portrait of Martin van Nieuwenhove," which hangs in the Hospital of Saint John, Bruges, Belgium.

**Creative Growth Games**—Eugene Raudsepp with George Hough, Jr., Princeton Creative Research, 10 Nassau St., Princeton, NJ 08450. Paper. 224 pg. \$3.95.

*Starting with the premise that we're all born creative, the authors offer 75 unusual games intended to help a reader master creative problem solving.*

CIRCLE NO. 315



# Electronic Design

ELECTRONIC DESIGN's function is:

- To aid progress in the electronics manufacturing industry by promoting good design.
- To give the electronic design engineer concepts and ideas that make his job easier and more productive.
- To provide a central source of timely electronics information.
- To promote communication among members of the electronics engineering community.

**Want a subscription?** ELECTRONIC DESIGN is circulated free of charge to those individuals in the United States and Western Europe who function in design and development engineering in companies that incorporate electronics in their end product and government or military agencies involved in electronics activities. For a free subscription, use the application form bound in the magazine or write for an application form.

If you do not qualify, paid subscription rates are as follows: \$30.00 per year (26 issues) U.S./Canada/Mexico, \$40.00 per year (26 issues) all other countries. Single copies are \$2.50 U.S. and all other countries. The Gold Book (27th issue) may be purchased for \$30.00 U.S./Canada/Mexico, and \$40.00 all other countries.

If you change your address, send us an old mailing label and your new address; there is generally a postcard for this in the magazine. You will have to requalify to continue receiving ELECTRONIC DESIGN free.

**The accuracy policy** of ELECTRONIC DESIGN is:


- To make diligent efforts to ensure the accuracy of editorial matter.
- To publish prompt corrections whenever inaccuracies are brought to our attention. Corrections appear in "Across the Desk."
- To encourage our readers as responsible members of our business community to report to us misleading or fraudulent advertising.
- To refuse any advertisement deemed to be misleading or fraudulent.

Individual article reprints and microfilm copies of complete annual volumes are available. Reprints cost \$6.00 each, prepaid (\$.50 for each additional copy of the same article), no matter how long the article. Microfilmed volumes cost \$23 for 1976 (Vol. 24); \$30 for 1973-75 (Vols. 21-23), varied prices for 1952-72 (Vols. 1-20). Prices may change. For further details and to place orders, contact Customer Services Dept. University Microfilms, 300 N. Zeeb Rd., Ann Arbor, MI 48106. (313) 761-4700.

**Want to contact us?** If you have any comments or wish to submit a manuscript or article outline, address your correspondence to:

Editor  
ELECTRONIC DESIGN  
50 Essex St.  
Rochelle Park, NJ 07662


# PENNY PINCHER FOR OEM PARTS



What it is ...

How to design for it ...

Who design it ...



## FREE DESIGN GUIDE

gives full details on lower tooling costs, lower unit costs, other advantages of Hetero-cavity® molding of nylon/acetal/GR polyester/PPS engineered component parts. Now molding OVER TWO BILLION parts a year, Security can save YOU time and money on your small parts needs. Call or write for free copy of newly-revised full-color brochure today!

**HETERO-CAVITY.**  
Molding of  
Nylon/Acetal/G.R. Polyester  
and PPS  
Engineered  
Component Parts

**security plastics, inc.**  
Largest interchangeable insert molder of engineered component parts in the world.  
14427 N.W. 60th Ave., Miami Lakes, FL 33014 (305) 823-5440

**security plastics, inc.**  
14427 N.W. 60th Avenue,  
Miami Lakes, FL 33014 / (305) 823-5440

Largest interchangeable insert molder of engineered component parts in the world  
CIRCLE NUMBER 113

# ION IMPLANTED Tuning Diodes 2 to 500 pF

Design in Implion® hyperabrupt and abrupt tuning diodes which offer superior capacitance swings, reproducibility and reliability. Tailored for octave or linear tuning in communications and test equipment.

Send for our catalog including selection guide and electrical characteristics as well as information on PIN diodes and low voltage avalanche zener diodes or call 617-273-1730.



**KSW Electronics Corp.**  
SOUTH BEDFORD STREET, BURLINGTON, MA 01803

CIRCLE NUMBER 114

# quick ads


New and current products  
for the electronic designer  
presented by their manufacturers.



**Free Catalog** contains complete line of Power Supplies from Computer Products, Inc. Miniature encapsulated models from 3.6 to 28V, 25mA to 2A. DC/DC Converters, 5 to 12 Watt models, single and dual outputs. High-efficiency supplies, single and dual output, models to 100 Watts. Attractive OEM discounts. Computer Products, Inc. 1400 N. W. 70th Street, Fort Lauderdale, FL. 33309 305/974-5500

POWER SUPPLY CATALOG


181



**DIP Program Header** (patent applied for) Now . . . you can program within the header itself and eliminate costly DIP switches. Available pre-programmed or can be programmed using needle nosed pliers or Aries Program Header tool to remove interconnecting sections between opposing pins or adjacent pins. Protective snap-on cover is provided which can be marked to identify program. Available 8, 14, 16 pin on .300 centers. ARIES Electronics, Inc., B 231, Frenchtown, NJ 08825. (201) 996-4096. TWX 510-235-3391

DIP PROGRAM HEADER


184



**LOW COST QUARTZ CRYSTALS** Use Statek 10 to 300 kHz quartz crystals in TO-5s . . . they eliminate count down for oscillators, filters, tone generators, timers . . . They're rugged, accurate & resistant to high vibration and shock. Prices low as \$1.70 ea. in 1000 qty. Send your written application & we'll send you a sample. Call or write for literature. Details in Gold Book and EEM \* STATEK CORP. \* 512 N. Main, Orange, Ca. 92668 \* (714) 639-7810 \* Telex 67-8394

QUARTZ CRYSTALS


187



**FREQUENCY SYNTHESIZERS.** GenRad offers the best combination of low-phase noise, fast switching speed and price. Frequency range is dc to 500 MHz. Important features: non-harmonic spurs > 80 dB down; a-m, fm and pm capabilities; built-in search sweep; programmable (BCD parallel) frequency control; and optional resolution to 0.1 Hz. GenRad, 300 Baker Ave., Concord, MA 01742, (617) 369-8770.

FREQUENCY SYNTHESIZERS

182



**NEW DESKTOP TAPE READER**—all you do is plug this Smart Box in. Up to 300 cps—RS232C, Current loop, parallel I/O—and quality built. State-of-the-art fiber optics, photo transistor read head, dual-sprocket drive. Outstanding for flexibility and simplicity. Low cost. Decitek, 250 Chandler Street, Worcester, MA 01602 (617) 798-8731.

NEW DESKTOP TAPE READER

185



**Pin 8 output** available on DIP CMOS oscillator operating from any supply voltage from 3V to 15Vdc, supply current 5 ma or less at 12Vdc; square wave output at any fixed frequency from 3MHz to 20-MHz; total frequency tolerance is  $\pm 0.1\%$ ,  $-25^{\circ}\text{C}$  to  $+75^{\circ}\text{C}$ ; dimensions  $0.78'' \text{ L} \times 0.49'' \text{ W} \times 0.3'' \text{ H}$ , model S13R2; also available in model S13R1 which drives 10 TTL gates. The Connor-Winfield Corporation, West Chicago, Illinois 60185 U. S. A. (312) 231-5270 TWX 910-230-3231

OSCILLATOR


188



**MODEL 585: PORTABLE, 250 MHz, 8-DIGIT FREQUENCY COUNTER—ONLY \$345.** 10Hz-250MHz direct measuring counter with 10 millivolts sensitivity. Reads directly in MHz, has excellent sine-wave sensitivity, 0.1Hz Resolution, dual Input Impedance ( $50\Omega/1M\Omega$ ), an Attenuator, 3 gate times, and 0.3" LED display. Includes NiCd module, Charger, and Carrying case. Optional antenna and accessories. DATA PRECISION CORP., Audubon Road, Wakefield, MA. 01880.

FREQUENCY COUNTER


183



**SEIKO's MECHANICAL FILTERS.** 1. Utilizes the precision machining technology of SEIKO, manufacturer of fine time-pieces. 2. Frequency range from 280Hz to 100kHz. 3. Main applications: Pocket pager, Answering phone, Telephone Ringer, Remote control, Omega receiver, Loran C receiver, Measuring Instruments and Oscillators. \*For more detailed information, please contact to: SEIKO INSTRUMENTS, INC., 2990 West Lomita Blvd., Torrance, Ca. 90505 Tel. (213) 530-3400 Telex: 25-910-347-7307

MECHANICAL FILTERS


186



**COMPUTER PROGRAMMABLE MAGNETIC FIELD CONTROLLER.** Model FFC-4DP can interface with most regulated power supplies and virtually any computer with 6 decades of BCD output. Offers 1 part in  $10^6$  full range setting of field amplitude of an electromagnet. Manual input also provided. Features stray field compensation and elimination of hysteresis effects and temperature gradient effects. Many applications. Write: Walker Scientific, Inc., Rockdale Street, Worcester, MA 01606

COMPUTER CONTROLLER


189



**QUIK/STRIP BY ROGERS.** Fast, low-cost system for connecting in-line pins on DIP socket boards and connector arrays. Shock and vibration resistant. 18 gauge current capacity. Can be used on pin densities as high as .100" x .100" and be stacked two or more high. Write or call for details. Rogers Corporation, Chandler, AZ 85224. Phone: (602) 963-4584. (EUROPE: Mektron NV, Gent, Belgium; JAPAN: Nippon Mektron, Tokyo.)


QUIK/STRIP

193



**FIGARO GAS SENSOR TGS** is a gas sensitive semiconductor. When combustible gas is absorbed on the sensor surface, a marked decrease of electrical resistance occurs. Major features of the sensor include high sensitivity, long term reliability and low cost. The applications are: GAS-LEAK ALARM, AUTOMATIC FAN CONTROL, FIRE ALARM, ALCOHOL DETECTOR, etc. Figaro Engineering Inc., North America Office-3303 Harbor Boulevard, Suite D-8, Costa Mesa, Calif. 92626 Tel: (714) 751-4103 Telex: 678396 GAS SENSOR

193



**SOURIAU, INC.** offers a new series designed to enable connectors with a very wide range of custom layouts to be quickly delivered without tooling charge. Modular inserts available with signal, power, coax and high voltage contacts in solder, crimp, PC and wire wrap terminations. Cable to panel and rack to panel types can be made. Request catalog on Series 8140 from SOURIAU, INC., 7740 Lemona Ave., Van Nuys, CA 91405 (213) 787-5341.

MODULAR CONNECTOR SYSTEM


194



**FREE TAKE HOME MICROCOMPUTER** included in tuition. 3-day HANDS ON  $\mu$ P WORKSHOP \$499. 2-day HANDS ON  $\mu$ P INTERFACING WORKSHOP \$299. Free micro has 6800 MPU, RAM, PIA, ACIA, ROM with FANTOM-11 monitor/debug (single step, break points, etc.), expandable to 65K. Spring 78 Tucson, Huntsville, Washington, Lafayette, Los Angeles, Boston, New York. Call Jerilyn 317-742-6802 or write WINTEK Corp., 902 N. 9th St., Lafayette, IN 47904.

$\mu$ P WORKSHOP


194



**New subminiature replaceable-lamp incandescent lights.** 50% cheaper than conventional subminiature flange-base or bi-pin because lamp base formed for bulb's glass and lead wires permits high-speed production. Socket-and-assembly design for one-hole mounting. Flat, dome, seven colors, 2 to 28 V. Samples and specs: Industrial Devices, Inc., Edgewater, N.J. 06020.

TINY MITE

192



**Overcurrent Protector**, manual reset eliminates fuse replacement. Convenient panel mounting. 19 fractional ratings from 0.1 to 5 amp. Other models up to 400 amp. Trip-free and fool-proof, UL and CSA approved. High quality, low cost \$1.49 ea. in 1000 lots. E-T-A Circuit Breakers, 7400 N. Croname Rd., Chicago, Ill. 60648. Tel: (312) 647-8303. Telex: 253780.

CIRCUIT BREAKER

195

# Electronic Design

## Advertising Sales Staff

Susan G. Apolant  
Sales Coordinator

## Rochelle Park, NJ 07662

Robert W. Gascoigne  
Thomas P. Barth  
Stan Tessler  
Constance McKinley  
50 Essex St.  
(201) 843-0550  
TWX: 710-990-5071  
(HAYDENPUB ROPK)

## Philadelphia

Thomas P. Barth  
(201) 843-0550

## Boston 02178

Gene Pritchard  
P.O. Box 379  
Belmont, MA 02178  
(617) 489-2340

## Chicago 60611

Thomas P. Kavooras  
Berry Conner, Jr.  
200 East Ontario  
(312) 337-0588

## Cleveland

Thomas P. Kavooras  
(312) 337-0588

## Los Angeles 90045

Stanley I. Ehrenclou  
Burt Underwood  
8939 Sepulveda Blvd.  
(213) 641-6544

## Texas

Burt Underwood  
(213) 641-6544

## San Francisco

Robert A. Lukas  
465 S. Mathilda, Suite 302  
Sunnyvale, CA 94086  
(408) 736-6667

## England

Constance McKinley  
50 Essex St.  
Rochelle Park, N.J. 07662  
Phone: (201) 843-0550

## Europe

Sanders, W. J. M.  
Raadhuisstraat 24  
Graft-De Ryp, Holland  
Phone: 02997-1303  
Telegrams: Euradteam-Amsterdam  
Telex: 13039-SIPAS

## G. Nebut

Promotion Presse Internationale  
7 ter Cour des Petites Ecuries  
75010 Paris, France  
Telephone: 5231917, 1918, 1919  
Dieter Wollenberg  
Erikastrasse 8  
D-8011 Baldham/Muenchen  
Germany  
Telephone: 0 8106/4541

## Tokyo


Haruki Hirayama  
EMS, Inc.  
5th Floor, Lila Bldg.,  
4-9-8 Roppongi  
Minato-ku, Tokyo, Japan  
Phone: 402-4556  
Cable: EMSINCPERIOD, Tokyo

★ABP

BPA

# quick ads


New and current products  
for the electronic designer  
presented by their manufacturers.



**STAMPED CIRCUITS** look like etched circuits, but they're not. They're stamped—and cost less. One oz., 2 oz., and up to 4 oz. copper available on all conventional PC board materials. Rogers Corporation, Rogers, Conn. 06263 (203) 774-9605. (EUROPE: Mektron NV, Gent, Belgium; JAPAN: Nippon Mektron, Tokyo)

MEKTRON


196



**Free New catalog** contains over 34,500 quality power supplies from the world's largest manufacturer, Power/Mate Corp. Power Supplies for every application including submodulars, open frame, variorated, encapsulated, laboratory & system. All units UL approved and meet most military and commercial specs for industrial and computer uses: Power/Mate Corp., 514 S. River St., Hackensack, NJ 07601 (201) 343-6294

POWER SUPPLIES

199



**THERMISTORS** with leads and coating are highly reliable low cost components in small dimensions more compatible with modern circuit design. R @ 25°C 100Ω to 1 meg Ω ±10% to ±1%. CURVE MATCHED INTERCHANGEABLES to ±.25°C. POINT MATCHED INTERCHANGEABLES to ±.2°C. Call or write for HP97 or TI SR52 THERMISTOR LINEARIZATION PROGRAM. WESTERN THERMISTOR CORPORATION, 354 Via Del Monte, Ocean-side, CA 92054. (714) 433-4484.

THERMISTOR


202



**100MHZ, 7-DIGIT MULTIFUNCTION COUNTER—\$295.** Model 5740 measures Sine-waves, Square Waves, Pulses, Pulse Pairs, Complex Waves. **Frequency:** 5 Hz to 100 MHz; 10ms, 100ms/1 sec./10 sec. gate times, resolution to 0.1 Hz. **Period:** 1/2 ms to 0.2 sec. **Period Average:** 10, 100, 1000 pds. **Total Events:** 0 to 9,999,999. **Elapsed Time:** 0 to 99,999.99 sec. **Sensitivity:** to 10mV. DATA PRECISION, AUDUBON RD., WAKEFIELD, MA 01880. (617) 246-1600.

MULTIFUNCTION COUNTER


197



**METHODE BUS BARS REPLACE MAZE OF COSTLY CABLE HARNESES** in computer, communications, industrial control systems. Ten years custom design experience, plus innovations like extra-strength staked and soldered .025" pins, puts METHODE first in bus bar designs for both military and commercial applications . . . FREE CATALOG. Methode Manufacturing Corp., 1700 Hicks Road, Rolling Meadows, IL. 60008. (312) 392-3500.

BUS BARS


200



**EXTREMELY SHOCK-ABSORBENT CASES.** These polyethylene cases protect your delicate product better than metal or fiberglass cases (and far cheaper). Shock-damping outer shell first absorbs some impact energy, then foam absorbs even more. Result: your product suffers fewer g's. Airtight and waterproof. Meet military/airline/ASTM specs. Unbelievable prices. 64 sizes. Also custom—send dwgs. Thermodyne International Ltd, 12600 Yukon Ave, Hawthorne, CA 90250 (213) 679-0411.

SHOCK-ABSORBENT CASES


203



**PARTS VIALS** Vials for testing, collection and transport of small materials are available at wholesale prices with orders of 1000 or more. Derm-Vial features funnel bottom for easy extraction of small specimens and will hold approximately 3 ml of fluid. Standard unit has flat bottom and holds approximately 4 ml of fluid. Both vials measure 1/2 x 2" are transparent and come with flush inner thread polyethylene caps. Samples on request. MARIN LABORATORY SUPPLY CO., PO. 4019, SAN RAFAEL, CA 94903

PARTS VIALS


198



**New Alden 402SACGL AC receptacle** features snap-in mounting in .025-.060 panels. Injection-molded in a high-impact engineering plastic. Flame retardant, rated 94-VO. Polarized and grounded, will accept all 2 and 3-prong AC plugs. Furnished with 3 pairs of leads only. Leads can be furnished with push-on terminals. Ideal for parallel wiring of bench outlets and power strips. Specify panel thickness. UL approved. ALDEN PRODUCTS CO, 117 N. Main St., Brockton, Ma. 02403 617-583-0160

SNAP-IN AC RECEPTACLE

201



**CARD CAGES & MICROCOMPUTERS.** ECT manufactures S-100 bus products including the ECT-100-F 19" Rack 20 slot Card Cage and Mother Board, 8080 CPU Cards, Power Supplies, Static RAM Cards, Prototyping Boards, Extender Cards, 10 & 20 slot Mother Boards, 10 slot Table Top Microcomputers (shown above), 10 or 20 slot 19" Rack Card Cage Dedicated Controllers or Microcomputers (available wired or kit). ELECTRONIC CONTROL TECHNOLOGY, Box 6, Union, NJ 07083 (201) 686-8080.

TABLE TOP MICROCOMPUTERS

204

# Electronic Design

## recruitment and classified ads

PLACE YOUR AD AT ONLY \$55 PER COLUMN INCH IN

### Electronic Design — GET A REPEAT AD FREE!

With our 2 for 1 plan, your net cost in *Electronic Design* is only \$27.50 per column inch, lowest among all the national newspapers and electronics media. You get a total of 165,418 exposures to OEM engineers and engineering managers (not counting 11,668 more among general or corporate managers) at only 33¢ per thousand! You can't beat the price. You can't beat the coverage and you can't beat the quality.

#### YOU REACH ENGINEERS WITH TITLES LIKE THESE:

- Chief Engineer • Development Engineer • Design Engineer • Project Engineer • Electronic Engineer • Engineer-Supervisor • Section Leader • Staff Engineer • Systems Engineer • Test Engineer • Standards Engineer • Master Engineer

### Electronic Design RECRUITMENT ADVERTISING RATES

15% commission to recognized agencies supplying offset film negatives. 2% 10 days, net 30 days. Four column makeup. Column width 1-3/4" x 10".

SPACE	DIMENSIONS		COST
	Wide	Deep	
One column inch	1-3/4"	x 1"	\$55.
2 col. in.	1-3/4"	x 2"	\$110.
1/16 page (1/4 col.)	1-3/4"	x 2-1/2"	\$130.
1/8 page (1/2 col.)	1-3/4"	x 5"	\$275.
1/4 page (1 col.)	1-3/4"	x 10" Vert.	\$550.
1/2 page (2 cols.)	3-1/2"	x 5" Hor.	
	3-1/2"	x 10" Vert.	\$1100.
	7"	x 5" Hor.	
3/4 page (3 cols.)	5-1/4"	x 10"	\$1650.
1 page	7"	x 10"	\$2200.

NOTE: EACH RECRUITMENT AD YOU PLACE WILL BE REPEATED FREE OF CHARGE!

### LATE CLOSING DATES

*Electronic Design* is mailed every two weeks. Because of its timeliness, personnel recruitment advertising closes only two weeks before each issue's mailing date.

Issue Date	Recruitment Closing Date	Mailing Date
Feb. 1	Jan. 6	Jan. 20
Feb. 15	Jan. 20	Feb. 3
Mar. 1	Feb. 3	Feb. 17
Mar. 15	Feb. 17	Mar. 3
Mar. 29	Mar. 3	Mar. 17
Apr. 12	Mar. 17	Mar. 31
Apr. 26	Mar. 31	Apr. 14



### HOW TO PLACE YOUR AD CALL THE RECRUITMENT HOT LINE 201-843-0550

Camera-ready film (right reading negatives, emulsion side down) or camera-ready mechanicals must be received by deadline. Or, if you wish us to set your ad (typesetting is free) simply pick up the phone and call our RECRUITMENT HOT LINE — (201) 843-0550. Ask for:

Constance McKinley  
RECRUITMENT ADVERTISING MANAGER  
ELECTRONIC DESIGN  
50 Essex Street, Rochelle Park, New Jersey 07662

## ENGINEERING OPPORTUNITIES IN ATLANTA

### • MINICOMPUTERS- PROGRAMMER/ANALYST

BSEE required with minor in Computer Sciences and 3-5 years experience in data acquisition and processing equipment analysis and programming. Specific programming experience on DEC PDP-11 utilizing RT-11 and RSX-11M operating systems is essential.

### • MICROPROCESSORS SYSTEMS ENGINEER

BSEE required with minor in Computer Sciences and 3-5 years experience in microprocessor system development, including software and system architecture. Specific "hands on" experience with INTEL 8080 and MAC 6800 microprocessors is essential. A good knowledge of microprocessor associated input/output devices is also required, together with control logic design capabilities.

\* \* \* \* \*

The above positions represent permanent career opportunities in suburban Atlanta with The Cadre Corporation. Cadre is a multidisciplinary engineering company performing design and turnkey projects for technical and industrial facilities. We offer excellent salaries, pay relocation costs, and have a comprehensive company-paid benefits package which includes an early vesting retirement plan. Qualified candidates may submit a complete resume and salary history in confidence to:

Manager of Engineering  
**THE CADRE CORPORATION**  
P.O. Box 47837  
Atlanta, Georgia 30362  
An Equal Opportunity Employer

## MANAGER OF INDUSTRIAL ENGINEERING

One of our clients, in a central part of the state, needs a manager of Industrial Engineering with a BSIE degree or equivalent and at least 5 years experience in a supervisory capacity. Duties will include: developing standard time data, preparing plant layout, training work measurement analysis, implementing new job standards, and most important of all, revising the companies wage incentive plan.

If you are interested in directing the activities of an Industrial Engineering Department, for an electronics company engaged in commercial products, in a non-union atmosphere, that is offering a starting salary of \$25,000. please send your resume to:

Jean Handman  
Rath & Strong, Inc. — Management Consultants  
21 Worthen Road, Lexington, MA 02173

An Equal Opportunity Employer

### LET'S TALK TURKEY!

Now is the time to make that move. It's a great market and we are on top of it!

A partial listing:

Hi Speed Dig. Logic ..... \$20K  
Mgr. Prod Dev Bus ..... \$33K  
Electrooptics Infrared ..... \$27K  
Sys. simulation Aerospace .. \$28K  
Reliability/Test ..... \$27K  
Dig. Process Control ..... \$29K  
Software Eng's ..... to \$35K  
Eng. Mgr. EW Sys'ts ..... \$40K  
RF Sys'ts ..... \$36K  
Dig. Des. Industrial ..... \$28K  
Analog Des. Non-Mil ..... \$27K  
Telecomm ..... \$30K  
Intel 80/80 PDP 11 ..... \$28K  
ECL Logic Des. .... \$27K  
Components Eng. .... \$25K

These are multiple positions with excellent firms. Send resume with salary and geographic preference and we'll call you at home.

PATHFINDER ENGINEERING AGENCY  
P.O. BOX 34, COMMACK, NY 11725  
Engineers only — nationwide

### ELECTRONIC ENGINEERS

Openings, in Aerospace, Communications, Sonar, RMA, Digital/Analog, RF, Software, Test Engineering fields. BSEE & U.S. citizenship req'd. (firm). Replies kept confidential. EOE Fee Pd. Agcy. To save time, pls. send res. 1st. D. Jones, Tech-Prof Empl., Est. 1967, 3111 St. Paul St., Balto., Md. 21218. (301) 243-1545.

### ENGINEERS SYSTEMS ANALYSTS/ PROGRAMMERS

Nationwide Professional Fee Paid Positions. Salary Range to 35K. Call Collect or send resume to K. Schargus or S. Nemser for immediate attention.

Software/Hardware	Analog/Digital
Weapon Systems	Microprocessors
Sonar/Radar	Instrumentation
Electro optics	Test Engineering
Electronic Design	Mechanical Design

AMERICAN PERSONNEL SERVICE  
240 State Street  
New London, Conn. 06320  
203-442-0395

### STATE OF THE ART

Dunhill is an industrial recruiting organization for electronic engineers offering superior positions.

To offer such an exceptional service to people we must represent excellent to superior positions — positions which offer high promotability and exceptional challenge.

To do this we have over two hundred offices to serve you well — to offer you good opportunities in your backyard and across the country.

We are currently staffing for some outstanding organizations across the country involved in medical electronics, automotive electronics, power electronics and controls and instrumentation.

Your interest in reaching your objectives, in advancing yourself to your goals, is our interest as well. This we respect in strict confidence. You have our trust.

For placement assistance, please call or write Gene Trusky CEC.

DUNHILL  
PENN CENTER  
Pgh., Pa. 15235 (412) 241-8383

### R&D DESIGN QC/QA

Company clients pay all fees, interview & relocation costs. Over 200 openings nationwide.

CALL TOLL FREE 24 HOURS  
1-800-821-2270 X605  
(in Mo. 1-800-892-7655)

Sample Openings  
NC Diagnostic Pgmng ..... \$20-30K  
FL ME-Electronic Pkgs ..... \$18-30K  
FL Cmptr Image Gen ..... \$20-29K  
VA FORTRAN ..... \$17-26K  
MA Mini-computer Arch ..... \$20-30K  
TX A&D Circuit Des ..... \$17-27K  
OH Med Electronics ..... \$18-27K  
CA Microprocessor Apps ..... \$19-29K  
VA NDTE ..... \$16-28K  
TN Comm Sys Des ..... \$18-28K

Ralph Stevenson, VP  
JIM KING

438 Gulf Life Tower  
Jacksonville, Florida 32207

# have a gripe?



# let us know about it!

We'll help you put pressure on any company that makes promises in its ads... then fails to deliver.

*Electronic Design* refuses to run advertisements deemed to be misleading or fraudulent.


ACCURACY is everybody's business. So if you have a gripe about a misstatement or inaccuracy in either editorial or advertising material in *Electronic Design*... tell us about it. We'll do everything we can to find out what happened and see that it's corrected. Notify...

George Rostky

Editor-in-Chief

## Electronic Design

50 Essex Street  
Rochelle Park, New Jersey 07662



## EFFORTLESS ...

If you're ready to move on with your career, it can be a lot easier than you expect.

We are the members of



who work extensively with electronics industry leaders. The companies we service have many openings and pay for us to search you out.

Send your resume to the office nearest you. Then sit back and relax while we do the work.

### SOUTHERN MANAGEMENT REGISTRY

P.O. Box 4036  
Charlotte, North Carolina 28204  
(704) 372-7640

### ALDEN ASSOCIATES, INC.

414 Hungerford Drive  
Rockville, Maryland 20850  
(301) 424-3522

### POWER SERVICES, INC.

Northgate Office Building  
5861 Rivers Avenue  
North Charleston, South Carolina 29405  
(803) 747-0955

### STAFF DYNAMICS, U.E.

26 Sixth Street  
Stamford, Connecticut 06905  
(203) 324-6196

### CAREER SPECIALISTS, INC.

4600 El Camino Real, Suite 206  
Los Altos, California 94022  
(415) 941-3200

### BRENTWOOD PERSONNEL ASSOCIATES

1280 Route 46  
Parsippany, New Jersey 07054  
(201) 335-8700

190 associates internationally



## seeking new career opportunities?

- Circuit Design
- Computer Systems
- Digital Systems
- Systems Simulation
- Signal Processing
- Radar Systems
- ASW Systems
- Pattern Recognition
- Surface Ship Sonar
- Real Time Programmers
- Weapons Systems
- Command/Control
- Electro-Optical
- Reliability/Test
- Avionics Systems
- Electronic Warfare
- Communications
- Mini-Computers
- Submarine Systems
- Microprocessor Systems

We are a Professional Search Firm representing a number of prestigious employers throughout the United States. Our clients include research and development laboratories, defense contractors, government contract research centers, major commercial and industrial corporations and leading management consulting firms. Starting salaries range from \$15,000 to \$40,000 with our fees, and all interview and relocation expenses fully paid by our clients.

If you wish to be considered for current and future opportunities, please send your resume, including current salary and technical strengths, to L. J. Clavelli or R. Beach ... today!



1010 Rockville Pike, P.O. Box 2148  
Rockville, MD 20852 (301) 762-1100

A licensed recruitment organization

## Electronic Design

BRINGS YOU THE HIGHEST  
NUMBER OF QUALIFIED EOEM  
ENGINEERS AND ENGINEERING  
MANAGERS ANYWHERE  
... AT THE LOWEST COST  
ANYWHERE!

**Constance McKinley**  
RECRUITMENT ADVERTISING MANAGER  
ELECTRONIC DESIGN  
50 Essex Street, Rochelle Park, New Jersey 07662  
(201) 843-0550

I'm interested in placing recruitment  
advertising in *Electronic Design*

Issue \_\_\_\_\_ Size of ad \_\_\_\_\_  
 My copy is enclosed  I need more information  
 Name \_\_\_\_\_  
 Title \_\_\_\_\_  
 Company \_\_\_\_\_  
 Address \_\_\_\_\_  
 City \_\_\_\_\_ State \_\_\_\_\_ Zip \_\_\_\_\_  
 Telephone \_\_\_\_\_

## ENGINEERS & EDP

### MEET 26 EMPLOYERS

Interviewing Soon in  
MAJOR MARKETING AREAS

MANY REQUIREMENTS FOR  
AFFIRMATIVE ACTION APPLICANTS  
INCLUDING PROFESSIONAL WOMEN

At an Opportunity Center, you have a unique opportunity to meet representatives of top firms in private interviewing sessions all in a single day or evening. When you apply, your resume minus your name and present employer, is reviewed by representatives of Opportunity Center sponsoring firms. You are notified as to which firms would like to meet you. Your identity is revealed only after you have expressed interest in this corporation. Private interviews are scheduled at your convenience.

### COMPANIES WHO HAVE ATTENDED

Allen Bradley  
Ashland Oil  
Automatic Sprinkler  
American Air Filter  
Bendix  
Borg Warner  
Burroughs  
Carborundum  
Combustion Engineering  
Commonwealth Associates  
Computer Science  
Digital Equipment  
Dravo  
Emerson  
Fairchild  
General Electric  
Gilbert Associates  
Gould, Inc.  
Goodyear  
G.T.E.  
Harris Electric  
Honeywell  
I.T.T.  
Jos. Schlitz  
Koppers Company  
Litton  
Martin Marietta  
3M  
McDonnell Douglas  
Monsanto  
Miles Laboratories  
NCR  
Owens Illinois  
Picker X-Ray  
Simmonds Precision  
Singer  
Stone and Webster  
Sundstrand  
Teledyne  
Texas Instruments  
TRW  
Union Carbide  
Westinghouse  
Xerox

NO FEES OR CHARGES TO APPLICANTS  
SEND RESUME TO:

## OPPORTUNITY CENTER

Akron Savings Bld., Suite 1113  
7 W. Bowery St., Akron, Ohio 44308






# 4-bit, one-chip micro- computers

Brainy enough  
for anything  
from TV games  
to industrial  
controls.



Block diagram of MN1400  
with on-chip, 1024x8-bit ROM.



Now Panasonic offers you a whole family of TTL compatible, one-chip microcomputers. So you can choose the combination of features and capabilities that are most cost-effective for your application. From appliances to gas pumps and electronic scales, to copiers, POS and intelligent terminals, tractor controls and countless others.

### Why pay for costly I/O interfacing when Panasonic puts it all on the chip?

Our MN1400 family is ideally suited for control functions with its extensive array of on-chip I/O facilities. There's an 8-bit presetable counter/timer, a clock generator, an arithmetic logic unit, and several input and output ports. Units are available with a self-contained 1024x8-bit ROM and a 64x4-bit RAM memory.

### Still more flexibility and efficiency from Panasonic.

For flexibility, our instruction set contains up to 75 instructions. To give you TTL compatibility, all our family members operate on +5V. And for extra computing speed, we've utilized N-channel E/D MOS construction.

### Panasonic can help you cut development time and costs.

Our Evaluator, the MN1499, can help you design, evaluate and debug programs quickly. In addition, software is available for a number of applications.

### The Panasonic family of one-chip microcomputers.

Package	MN1400 40-Pin Plastic DIP	MN1402 28-Pin Plastic DIP	MN1498 40-Pin Plastic DIP	MN1499 64-Pin Ceramic DIP
Power Supply	+5V	+5V	+5V	+5V
Instruction Cycle Time	10 $\mu$ s	10 $\mu$ s	10 $\mu$ s	10 $\mu$ s
Instruction Set	75	57	68	75
Instruction Memory	Internal 1024 x 8 bits (8192 bits)	Internal 768 x 8 bits (6144 bits)	External 1024 x 8 bits (8192 bits)	External 2048 x 8 bits (16384 bits)
Total on Chip RAM	64 x 4 bits (256 bits)	32 x 4 bits (128 bits)	64 x 4 bits (256 bits)	64 x 4 bits (256 bits)

### 16-bit microprocessors, too.

They're ideally suited for a wide variety of computer peripheral and business machine applications. Designed with minicomputer architecture LOCOS MOS N-channel construction for optimum speed and thruput efficiency.

For complete information and prices, write to Panasonic Electronic Components, One Panasonic Way, Secaucus, N.J. 07094; or call (201) 348-7269.

**Panasonic**<sup>®</sup>  
just slightly ahead of our time

Share in the success you helped create ...

# ANNOUNCING THE RCA BiMOS BONANZA.

BiMOS is the RCA Linear IC technology that is not only being made by the millions, but used by the millions.

Now we're adding new BiMOS products and new BiMOS prices so you can make even wider use of the highly cost-effective performance of BiMOS op amps.

## **CA3140** 2-for-1 Bonanza

At our new price for the mini-dip 3140, you can buy twice as many as you could at the old. So now, for the same dollar, you can double your use of the most useful op amp since the 741.

## **CA3240** 2-in-1 Bonanza


Our new CA3240E gives you two 3140's in one mini-dip package. At less than twice our new low 3140 price. Your new designs can be achieved with half as many packages.

And the 3240 is available now in prototype quantities. In both mini-dip and 14-lead DIP.

## **CA3140 CA307G** Gold CHIP Bonanza

It's your choice. Two CA3140E's or one 3140 and one CA307G. They both have the same new low price. This BiMOS/Gold CHIP team-up gives you a variety of ways to beat the 741 where you want more performance. Or beat many premium Bifet types where you want lower price or greater availability.

Get your share of the BiMOS Bonanza now. Contact your local RCA Solid State distributor. Or contact RCA Solid State headquarters in Somerville, NJ; Sunbury-on-Thames, Middlesex, England; Quickborn 2085, W. Germany; Ste.-Anne-de-Bellevue, Quebec, Canada; Sao Paulo, Brazil; Tokyo, Japan.



Note: All price references are based on the unit prices in effect November 1, 1977. Prices optional with distributors.

**RCA Linear IC  
experience is  
working for you.**

# RCA