

Reference



Reference

Note

Before using this information and the product it supports, be sure to read the general information in "Notices" on page 751.

Sixth Edition (December 2000)

This edition of *Infoprint Manager: Reference* applies to Infoprint Manager for AIX, Version 3 Release 2 Modification 0, Infoprint Manager for Windows NT and Windows 2000, Version 1 Release 1 Modification 0, and to all subsequent releases and modifications until otherwise indicated in new editions or technical newsletters. Be sure to use the correct edition for the level of the product. Because this is a minor revision, the revision bars from the previous edition are included for retrievability.

Order publications through your IBM representative or the IBM branch office serving your locality. Publications are not stocked at the address given below.

IBM Printing Systems welcomes your comments. For your convenience, a form for reader's comments is provided at the back of this publication. If the form has been removed, you may send your comments to the following address:

INFORMATION DEVELOPMENT IBM PRINTING SYSTEMS DEPARTMENT H7FE BUILDING 003G PO BOX 1900 BOULDER CO 80301-9191

If you prefer to send comments electronically, use one of the following methods:

- Internet/Email: printpub@us.ibm.com
- Fax: 1-800-524-1519 within U.S. or 1-303-924-6873 outside U.S.

Internet

Visit our home page at http://www.ibm.com/printers

When you send information to IBM, you grant IBM a nonexclusive right to use or distribute the information in any way it believes appropriate without incurring any obligation to you.

© Copyright International Business Machines Corporation 1998, 2000. All rights reserved.

US Government Users Restricted Rights – Use, duplication or disclosure restricted by GSA ADP Schedule Contract with IBM Corp.

Contents

Figures xv	Description	17
	Flags	
Tables xvii	Argument	18
	Examples	19
About This Publication xix	pdclean Command: Removes All Jobs from the	
	Specified Object	
Who Should Use This Publication xix	Syntax	
About the Documentation for Infoprint xix	Description	
The Infoprint Publication Library xix	Flags	
Other Publications Related to Infoprint xx	Command Attributes	
Manual (man) Pages for Infoprint Commands,	Arguments	
Utilities, and Transforms	Examples	
Manual (man) pages for Infoprint Attributes xxiii	Suggested Reading	
Infoprint Online Message Catalog xxiii readme Files xxiv	pdcreate Command: Creates Infoprint Objects	
The Organization of This Publication xxv	Syntax	
Conventions Used in This Publication xxvi	Description	
	Flags	
Highlighting xxvi Infoprint Command Notation xxvii	Command Attributes	
mioprini Command Notation xxvii	Arguments	
Chapter 4 Introduction 4	Examples	
Chapter 1. Introduction	Suggested Reading in Hardcopy	
Reference Table for Path Names	Suggested Reading Online	
Objects	pddelete Command: Deletes Infoprint Objects	
Object Classes	Syntax	
Object Name Restrictions	Description	
Object Attributes	Flags	
Commands	Command Attributes	
Flags, Command Attributes, and Arguments 4	Arguments	
Command Output: Headings and Style 5	Examples	30
Tips for Using Commands 6	Suggested Reading	3.
Administrative Utilities	pddisable Command: Stops Destinations from	2.0
Daemon Utilities for Infoprint Manager for AIX 8 Transform Commands	Accepting Jobs and Logs from Logging	
Environment Variables for Infoprint Manager for AIX 9	Syntax	
Windows Services for Infoprint Manager for	Description	
Windows NT and Windows 2000 9	Flags	
Wildows INT and Wildows 2000	Command Attributes	33
Chapter 2 Informint Commands 44	Examples	
Chapter 2. Infoprint Commands 11	Suggested Reading	
lprafp Command: Submits Remote Jobs in Infoprint	pdenable Command: Enables Destinations to Accept	
Manager for AIX	Jobs and Logs to Log	
Syntax	Syntax	3.5
Description	Description	3.5
Flags	Flags	
Arguments	Command Attributes	
Examples	Arguments	
	Examples	
mkfntmap Command: Maps PostScript Fonts 15	Suggested Reading	37
Syntax	pdls Command: Lists Selected Attribute Values	
Description	Syntax	
Arguments	Description	
pdaccount Command: Collect Accounting	Flags	
Information for a Specific Time Period with	Command Attributes	
Information for a specific finite reflow with	Arguments	
Syntax	Examples	
Symmet	Suggested Reading in Hardcopy	

Suggested Reading Online for Infoprint Manager	pdresubmit Command: Resubmits Jobs 79
for AIX	Syntax
pdmod Command: Modifies Attributes of Submitted	Description
Print Jobs	Flags
Syntax	Command Attributes 80
Description	Arguments
Flags	Examples
Command Attributes 51	Suggested Reading 82
Arguments	pdresume Command: Enables Paused Objects to
Examples	Resume Operation
Suggested Reading in Hardcopy 52	Syntax
Suggested Reading Online	Description
pdpause Command: Pauses Jobs, Actual	Flags
Destinations, Servers, or Queues 54	Command Attributes 84
Syntax	Arguments
Description	Examples
Flags	Suggested Reading 85
Command Attributes	pdrm Command: Removes Jobs 86
Arguments	Syntax
Examples	Description
Suggested Reading 60	Flags
pdpr Command: Submits Jobs 61	Command Attributes
Syntax	Arguments
Description 61	Examples
Flags	pdset Command: Defines Attribute Values 89
Command Attributes	Syntax
Job and Document Attributes Used with the	Description
Command	Flags
Arguments	Command Attributes
Examples for Infoprint Manager for AIX 66	Arguments
Examples for Infoprint Manager for AIX and	Examples
Infoprint Manager for Windows NT and	Suggested Reading in Hardcopy
Windows 2000	Suggested Reading Online for Infoprint Manager
Suggested Reading in Hardcopy 69	for AIX
Suggested Reading Online for Infoprint Manager	pdshutdown Command: Stops Servers or Actual
for AIX	Destinations
pdpromote Command: Advances a Job to the Top of	Syntax
a Queue	Description
Syntax	Flags
Description	Command Attributes
Flags	Argument
Command Attributes	Examples
Arguments	Suggested Reading
Example	pdspace Command: Backspaces or Forward Spaces a
Suggested Reading	Printer
pdq Command: Queries Job Status	Syntax
Syntax	Description
Description	Flags
Flags	Command Attributes
Command Attributes	Arguments
Arguments	Examples
Examples	Examples
	Chapter 2. The a Flor for AIV Drint
Suggested Reading in Hardcopy	Chapter 3. The -o Flag for AIX Print
	Commands
pdreorder Command: Reassigns Jobs	Syntax
Syntax	Description
Description	Limitations
Flags	Flag
Command Attributes	Specifying -o Attribute-Value Pairs 104
Arguments	-o Attribute-Value Pairs
Examples	-o Keywords and Values for Specific Data Types 117

Examples	ainurpt5 Utility: Generates Audit Information by
	User
Chapter 4. Infoprint Administrative	Syntax
Utilities	Description
admingui Utility: Opens the Print Administration	Example
Window of the Basic Infoprint Administrator's GUI	Suggested Reading
in Infoprint Manager for AIX	ainurpt6 Utility: Generates Audit Information for a
Syntax	User
Description	Syntax
Flags	Description
Arguments	Example
Examples	Suggested Reading
afpsplit Utility: Extracts Pages from a MO:DCA-P	cfu Utility: Displays and Builds Coded Fonts in
File	Infoprint Manager for AIX
Syntax	Syntax
Description	Description
Flags	Build File Format
Arguments	Arguments
Example	Examples
ainupod1 Utility: Generates Accounting	Suggested Reading
Information by User	cmt Utility: Builds Color Mapping Table Source
Syntax	and Object Files in Infoprint Manager for AIX 144
Description	Syntax
Example	Description
Suggested Reading	Flags
ainupod2 Utility: Generates Accounting	Color Mapping Table Source File 144
Information by Job	ipguiadv, ipguibasic, and ipguidist Utilities: Start
Syntax	the Infoprint Manager Operations GUI 146
Description	Syntax
Example	Description
Suggested Reading	Example
ainupod3 Utility: Generates Accounting Information for a User	ipguiadvadm, ipguibasicadm, and ipguidistadm
Syntax	Utilities: Start the Infoprint Manager
Description	Administration GUI
Example	Syntax
Suggested Reading	Description
ainurpt1 Utility: Generates Accounting Information	Example
by Actual Destination	jsmigr Utility: Migrates PSF for AIX Job Scripts in
Syntax	Infoprint Manager for AIX
Description	Syntax
Example	Description
Suggested Reading	Arguments
ainurpt2 Utility: Generates Accounting Information	Examples
by User	notification client
Syntax	opergui Utility: Opens the Print Management
Description	Window of the Basic Infoprint Administrator's GUI
Example	in Infoprint Manager for AIX
Suggested Reading	Syntax
ainurpt3 Utility: Generates Accounting Information	Description
for a User	Flags
Syntax	Arguments
Description	
Example	pdadmin Utility: Opens the Servers Window of the Advanced Infoprint Administrator's GUI in
Suggested Reading	Infoprint Manager for AIX
ainurpt4 Utility: Generates Audit Information by	Syntax
Destination	Description
Syntax	Examples
Description	pdcrcds Utility: Creates Directories for DCE in
Example	Infoprint Manager for AIX
Suggested Reading	

Syntax	Arguments
Description	Messages and Return Codes 170
Example	Example
pdcrdflt Utility: Creates Default Auxiliary Sheets,	setup Utility: Starts the Infoprint Installer in
Media, and Queue in Infoprint Manager for AIX . 155	Infoprint Manager for AIX
Syntax	Syntax
Description	Description
Flags	Flags
Arguments	Examples
Examples	startppo Utility: Starts the Infoprint SMIT
pdcrmed Utility: Creates Commonly Used Media	Production Print Operations Interface in Infoprint
in Infoprint Manager for AIX	Manager for AIX
Syntax	Syntax
Description	Description
Example	Examples
pdinitports Utility: Initializes Ports	start_server Utility: Starts a Server for a Basic
Syntax	Infoprint Installation in Infoprint Manager for AIX . 177
Description	Syntax
Flags	Description
Arguments	Flags
Examples	Arguments
pdmigpp Utility: Migrates Existing AIX Printers to	Examples
Infoprint in Infoprint Manager for AIX 160	startsry Utility: Starts a Server in Infoprint
Syntax	Manager for AIX
Description	Syntax
Arguments	Description
Example	Flags
pdmincfg Utility: Sets up a Minimum Infoprint	Arguments
Configuration in Infoprint Manager for AIX 162	Examples
Syntax	stop_server Utility: Shuts Down a Server in
Description	Infoprint Manager for AIX
Flags	Syntax
Arguments	Description
Example	Flags
pdmsg Ütility: Displays Information about a	Arguments
Message in Infoprint Manager for AIX 164	Examples
Syntax	tdump Utility: Outputs Tape Contents in
Description	Human-Readable Format in Infoprint Manager for
Flags	AIX
Examples	Syntax
rc.iprsap Utility: Start SAP Callback Daemons for	Description
Infoprint Manager for AIX	Flags
Syntax	Examples
Description	tlist Utility: Lists Files on a Tape in Infoprint
rc.pd Utility: Restarts Servers in Infoprint Manager	Manager for AIX
for AIX	Syntax
Syntax	Description
Description	Flags
sense Utility: Senses Whether a Channel-Attached	Examples
Printer is Attached to Infoprint Manager for AIX . 168	t2file Utility: Reads MVS Partitioned Data Sets
Syntax	from Tape in Infoprint Manager for AIX 185
Description	Syntax
Arguments	Description
Messages and Return Codes 168	Flags
Example	Examples
sense Utility: Senses Whether a Channel-Attached	OL 4 5 B 1999
Printer is Attached to Infoprint Manager for	Chapter 5. Daemon Utilities for
Windows NT and Windows 2000 170	Infoprint Manager for AIX 187
Syntax	mvsprsd Utility: Starts the mvsprsd Daemon 188
Description	Syntax 188

Description	Resource Search Path	217
Flags	Limitations	
Examples	Acknowledgments	
Suggested Reading	Options and Values	
pcl2afpd Utility: Starts the pcl2afpd Daemon 190	jpeg2afp Command: Transforms JPEG Data to AFP	
Syntax	in Infoprint Manager for AIX	226
Description	Syntax	
Flags	Description	
Configuration File Keywords and Values 190	Automatic Invocation	
Examples	Input and Output	
Files	Errors and Error Recovery	
ps2afpd Utility: Starts the ps2afpd Daemon 193	Data Transformations	
Syntax	Parameters	
Description	Resource Search Path	
Flags	Limitations	
Configuration File Keywords and Values 193	Acknowledgments	
Examples	Options and Values	
Files	line2afp Command: Transforms S/370 Line Data	201
startnotd Utility: Starts the notifyd Daemon 197	and ASCII Data to AFP	230
Syntax	Syntax	
Description	Description	
stopnotd Utility: Stops the notifyd Daemon 198	Flags and Values	
Syntax	Examples	
	Files	
Description		
startcbd Utility: Starts the SAP Callback Daemon 199	Messages	
Syntax		
Description	Syntax	
Arguments	Description	
Examples	Limitations	
stopcbd Utility: Stops the SAP Callback Daemon 201	Flags and Values	
Syntax	Transforming PCL Image Data	
Description		276
Arguments	Simple Examples	
Examples	More Complex Examples	2/9
OL	Files	280
Chapter 6. Infoprint Transform	pdf2afp and ps2afp Transforms: Transform PDF or	205
Commands 203	PostScript Data to AFP	
db2afp Command: Transforms DBCS Data to AFP 205	Syntax	
Syntax	Description	
Description	Limitations	
Limitations		289
Flags and Values 205	The ps2afp and ps2afpd Configuration Files	
Examples	Examples	
Files	Files	300
d2afp Command: Transforms ditroff Data to AFP	sap2afp Command: Transforms SAP OTF or ABAP	200
in Infoprint Manager for AIX 209	Data to AFP in Infoprint Manager for AIX	
Syntax	Syntax	
Description	Description	
Limitations	Flags	
Flags and Values	The sap2afp Configuration Files	
Examples	Examples	312
Files	tiff2afp Command: Transforms TIFF Data to AFP in	
gif2afp Command: Transforms GIF Data to AFP in	Infoprint Manager for AIX	
Infoprint Manager for AIX	Syntax	
Syntax	Description	
Description	Automatic Invocation	
Automatic Invocation	Input and Output	
Input and Output	Errors and Error Recovery	
Errors and Error Recovery	Data Transformations	
Data Transformations	Parameters	
Data Hansionnations	Resource Search Path	319

Limitations	. 319	destination-name	364
Acknowledgments		destination-needs-attention-time	
Options and Values			365
options and values	. 017	destination-pass-through	
Chapter 7 Informint Chicat Attributes	220	destination-poll-interval	366
Chapter 7. Infoprint Object Attributes	329	destination-realization	
About Destination Support Systems	. 330	destination-register-threshold	
Infoprint Manager for AIX supports the	220	destination-release-timer	367
following DSSs:	. 330	destination-state	
Infoprint Manager for Windows NT and			
Windows 2000 supports the following DSSs: .	. 331	destination-support-system	
Understanding Attachment Types for PSF		destination-tcpip-internet-address	
Actual Destinations	. 331	destination-tcpip-port-number)/1)71
Attributes Displayed in the Infoprint Manager		destination-timeout-period	
Administration GUI		device-name	372 372
Introducing Object Attributes		device-support-system	
Attributes for Actual Destinations	. 336	document-attributes-supported	
Attributes Not Displayed in the Infoprint		document-finishings-supported	
Administrator's GUI	. 336	document-formats-ripped-at-destination	376 376
Initially Settable Attribute Listing	. 337	document-formats-supported	376
Resettable Attribute Listing	. 337	document-types-supported	
accept-jobs		dss-job-message-disposition	
accounting-exit		dss-job-message-log-size	
ack-interval	. 341	dss-job-message-log-wrap	
add-carriage-returns		ebcdic-character-mapping	
add-line-feeds		enabled	381
ascii-character-map		end-message-supported	381
ascii-font-map		end-sheets-supported	382
associated-queue		font-resolutions-supported	
associated-server	344	force-destination-setup	
attachment-type		force-printer-setup	
attribute-map		form-definition	384
audit-exit		halftones-supported	
automatic-postscript-mode-switch		image-fit-supported	386
auxiliary-sheet-selections-supported	240	image-length	
auxiliary-sneet-selections-supported	. 340	image-out-formats-supported	
booklet-fold		image-width	388
cancel-individual-document-supported		input-data-user-exit	389
carriage-control-types-supported		input-trays-medium	389
character-mappings-supported		input-trays-supported	391
checkpoint-at-stacker	. 350	intervention-timer	301
checkpoint-formats-supported			
color-bits-per-plane		job-attributes-supported	202
color-bits-per-plane-supported			
color-mapping-table		job-finishings-supported	201
color-profile		job-retry-count-limit	
color-profiles-supported		job-retry-interval	
color-rip-servers	. 354	job-rip-actions-supported	
color-toner-saver		job-size-range-ready	
color-toner-saver-supported	. 355	job-size-range-supported	
command	. 356	job-start-wait-supported	
connection-timeout	. 356	list-of-managers	
content-orientations-supported	. 356	locations	
convert-to-ebcdic-supported		log-accounting-data	
data-fidelity-problem-reported-supported		logical-destinations-assigned	
default-font-fidelity-action		managers	
default-font-resolution		maximum-concurrent-jobs	
default-input-tray		maximum-copies-supported	
descriptor		maximum-fonts-to-keep	
destination-command		maximum-overlays-to-keep	402
destination-data-stream		maximum-presentation-object-containers-to-keep	
destination-locations		maximum-segments-to-keep	
destination-model		media-ready	
	. 230	- The state of the	

media-supported	. 404	problem-message	. 430
message	. 405	protected-attributes	. 431
message-font-type	. 405	psf-tray-characteristics	
message-form-definition	. 406	public-context-presentation-object-container .	. 434
model		qualities-supported	. 435
non-process-runout-timer		register-threshold	
notification-profile	. 407	registered-with-spooler	
notify-operator	. 408	remote-queue	. 435
number-up-supported		resource-context	. 436
object-class	410	resource-context-font	
offset-stacking-available		resource-context-form-definition	
operators		resource-context-overlay	
optimize-for-multiple-copies	. 1 11	resource-context-page-definition	
		resource-context-page-definition	
orientations-supported	. 4 11		
other-options		resource-context-presentation-object-container	
output-appearances-supported		reuse-inline-presentation-object-container	
output-bin	. 412	reverse-output	
output-bin-numbers	. 413	rip-ini-file	. 444
output-bins-supported	. 414	rip-server	
output-data-user-exit		scanner-corrections-supported	
output-format-supported		scheduler-sort-primary-order	
overlay		scheduler-sort-secondary-order	
page-select-supported		schedulers-supported	
pcl-server-address	. 417	screen-frequencies-supported	
pcl-server-port	. 417	separator-sheets-supported	. 447
physical-printer	. 418	shared-printer-name	. 448
plex	. 418	sides	. 448
plexes-supported		sides-supported	
postscript-server-address		snmp-active	
postscript-server-port		snmp-community-name	
presentation-fidelity-problem-reported		snmp-retry-count	
presentation-object-container-extraction-mode	421	snmp-timeout	. 451
print-edge-marks		start-message-supported	
print-qualities-supported		start-sheets-supported	
print-quanties-supported		table-reference-characters-supported	
		timeout-period	
print-queue-name	422		
printer		transform-sequence	
printer-command		use-snmp	
printer-data-stream		wait-for-job-completion	
printer-end-sheet	. 423	warning-message	
printer-escape-codes		windows-nt-driver-names	
printer-memory		x-image-shift-range-supported	
printer-locations		y-image-shift-range-supported	
printer-model		Attributes for Auxiliary-Sheet Objects	
printer-name		Initially Settable Attribute Listing	
printer-needs-attention-time		Resettable Attribute Listing	. 458
printer-needs-key-operator-attention-time	. 425	associated-server	. 458
printer-pass-through	. 425	auxiliary-sheet-identifier	. 458
printer-realization	. 425	descriptor	. 459
printer-register-threshold	. 425	object-class	. 459
printer-release-timer		psf-exit-form-definition	
printer-resolutions-ready		psf-exit-page-mark	
printer-resolutions-supported		psf-exit-program-name	
printer-separator-sheet		Attributes for Documents and Default Documents	464
printer-start-sheet		Document	
printer-state		Default Document	
printer-satte		Attributes Not Displayed in the Infoprint	. 107
printer-s370-channel-slot-number			. 464
printer-tcpip-internet-address		Initially Settable Attribute Listing	
printer-tcpip-port-number		Resettable Attribute Listing	
Dinner-IIIIPOHI-DETIOO	. 4.00	гет-госитен Антилте Listing .	. 4n/

account-text	. 469	image-length
address1-text	. 469	image-out-format 50
address2-text	. 470	image-scale
address3-text	. 470	image-width 50
address4-text	. 471	initial-value-document (Document Only) 502
associated-server (Default Document Only) .		initial-value-document-identifier (Default
base-printer		Document Only)
bits-per-spot		input-exit
black-overprint		input-tray-select 50
building-text		jog-between-job-copies 50-
callback-number		list-of-managers (Default Document Only) 500
carriage-control-type		logical-destinations-ready (Default Document
chars		Only)
cms-proclink	175	logical-printers-ready (Default Document Only) 500
cms-product		managers (Default Document Only) 500
color-bits-per-plane		maximum-messages-printed
		maximum-transform-pages-ahead
color-mapping-table		
color-profile	. 4//	message (Default Document Only) 50
		mvs-class
compressed-output		mvs-destination
content-orientation		mvs-forms
control-strip		mvs-segment-id
convert-to-ebcdic		name-text
copies		new-line-option 50
copy-count		node-id-text
data-fidelity-problem-reported		number-up
default-character-mapping		object-class
default-input-tray		octet-count (Document Only) 51
default-medium		offset-stacking-between-job-copies 512
default-printer-resolution	. 484	orientation
department-text		originating-company-text 51
descriptor (Default Document Only)		other-options 51.
destination-company-text	. 485	other-transform-options
destination-initial-value-document (Document		output-appearance
Only)	. 485	output-bin
destination-pass-through	. 486	output-face-up
document-comment	. 486	output-format
document-content (Document Only)		overlay
document-content-list (Document Only)		overlay-back
document-file-name (Document Only)	. 487	overlay-front 51
document-finishing		overprint
document-format	. 488	page-clip
document-number (Document Only)		page-count (Document Only)
document-sequence-number (Document Only)	489	page-definition
document-type (Document Only)		page-media-select
dot-shape		page-select (Document Only)
email-from-address		plex
email-to-address		print-quality
enable-settrap		printer-initial-value-document (Document Only) 52
fax-number		printer-pass-through
fax-to-name		programmer-text
		1 0
file-name (Document Only)		resource-context
font-fidelity-action		resource-context-font
font-processing-messages		resource-context-form-definition
font-resolution		resource-context-overlay
form-definition		resource-context-page-definition
format		resource-context-page-segment
halftone		resource-context-presentation-object-container 52
image-center-x		resource-context-user
image-center-y		resource-exit
imago-fit	108	room-text 530

	521	ich deadline time (Ich Only)	557
scanner-correction		job-deadline-time (Job Only)	
screen-frequency		job-discard-time (Job Only)	
segment-file-size		job-end-message	
sequence-number (Document Only)	. 532	job-finishing	558
shared-formdef		job-hold	
shift-out-shift-in		job-identifier (Job Only)	
sides		job-log (Job Only)	560
start-on-new-sheet		job-media-sheet-count (Job Only)	
subject-text	. 535	job-message-from-administrator (Job Only)	561
table-reference-characters		job-message-to-operator	
title-text		job-name	
transfer-method (Document Only)		job-originator (Job Only)	
transform-message-file-name		job-owner (Job Only)	
transform-output-file-name	. 537	job-page-count (Job Only)	564
type (Document Only)	. 538	job-print-after (Job Only)	
user-id-text		job-priority	
x-image-shift		job-retain-until (Job Only)	
x-image-shift-back		job-retention-period	
y-image-shift	. 540	job-rip-action	
y-image-shift-back	. 540	job-ripped-by-server	567
Attributes for Jobs and Default Jobs		job-size (Job Only)	570
Default Job		job-start-message	
Job	. 342	job-start-wait	
Attributes Not Displayed in the Infoprint		job-state (Job Only)	
Administrator's GUI	. 542	job-state-reasons (Job Only)	
Initially Settable Attribute Listing	. 542	job-submission-complete (Job Only)	573
Resettable Attribute Listing	. 542	job-ticket-content	573
actual-destinations-requested		last-accessor (Job Only)	
associated-server (Default Job Only)			
		last-modifier (Job Only)	
auxiliary-sheet-selection		list-of-managers (Default Job Only)	
comment		locations-requested	
completion-time (Job Only)	. 545	logical-destinations-ready (Default Job Only)	
current-job-state (Job Only)	. 545	logical-printer-requested	574
current-page-printing (Job Only)		logical-printers-ready (Default Job Only)	
d-s-s-requested		managers (Default Job Only)	
deadline-in-jeopardy (Job Only)		media-sheet-count (Job Only)	
delete-segment-list		media-sheets-completed (Job Only)	575
descriptor (Default Job Only)	5/18	massage (Default Joh Only)	575
		message (Default Job Only)	
destination-initial-value-job (Job Only)			
destination-initial-value-job (Job Only)	. 548	message-from-administrator (Job Only)	575
destination-initial-value-job (Job Only) destination-locations-requested	. 548 . 549	message-from-administrator (Job Only)	575 575
destination-initial-value-job (Job Only) destination-locations-requested destination-models-requested	. 548 . 549 . 549	message-from-administrator (Job Only)	575 575 576
destination-initial-value-job (Job Only) destination-locations-requested destination-models-requested destination-name-requested (Job Only)	. 548 . 549 . 549 . 550	message-from-administrator (Job Only)	575 575 576 576
destination-initial-value-job (Job Only) destination-locations-requested destination-models-requested destination-name-requested (Job Only) destinations-assigned (Job Only)	. 548 . 549 . 549 . 550	message-from-administrator (Job Only)	575 575 576 576 576
destination-initial-value-job (Job Only) destination-locations-requested destination-models-requested destination-name-requested (Job Only) destinations-assigned (Job Only) destinations-used (Job Only)	. 548 . 549 . 549 . 550 . 550 . 551	message-from-administrator (Job Only). message-to-operator. models-requested	575 575 576 576 576 576
destination-initial-value-job (Job Only) destination-locations-requested destination-models-requested destination-name-requested (Job Only) destinations-assigned (Job Only)	. 548 . 549 . 549 . 550 . 550 . 551	message-from-administrator (Job Only)	575 575 576 576 576 576
destination-initial-value-job (Job Only) destination-locations-requested destination-models-requested destination-name-requested (Job Only) destinations-assigned (Job Only) destinations-used (Job Only) device-support-system-requested	. 548 . 549 . 549 . 550 . 550 . 551	message-from-administrator (Job Only)	575 576 576 576 576 576 576
destination-initial-value-job (Job Only) destination-locations-requested destination-models-requested destination-name-requested (Job Only) destinations-assigned (Job Only) destinations-used (Job Only) device-support-system-requested discard-time (Job Only)	. 548 . 549 . 549 . 550 . 550 . 551 . 551	message-from-administrator (Job Only) message-to-operator models-requested modification-time (Job Only) name name-of-last-accessor (Job Only) new-job-identifier (Job Only) notification-profile	575 576 576 576 576 576 576
destination-initial-value-job (Job Only) destination-locations-requested destination-models-requested destination-name-requested (Job Only) destinations-assigned (Job Only) destinations-used (Job Only) device-support-system-requested discard-time (Job Only)	. 548 . 549 . 549 . 550 . 550 . 551 . 551 . 551	message-from-administrator (Job Only) message-to-operator models-requested modification-time (Job Only) name name-of-last-accessor (Job Only) new-job-identifier (Job Only) notification-profile number-of-documents (Job Only)	575 576 576 576 576 576 577 579
destination-initial-value-job (Job Only) destination-locations-requested destination-models-requested destination-name-requested (Job Only) destinations-assigned (Job Only) destinations-used (Job Only) device-support-system-requested discard-time (Job Only) dss-requested	. 548 . 549 . 549 . 550 . 550 . 551 . 551 . 551 . 551	message-from-administrator (Job Only) message-to-operator models-requested modification-time (Job Only) name name-of-last-accessor (Job Only) new-job-identifier (Job Only) notification-profile number-of-documents (Job Only)	575 576 576 576 576 576 576 579 579
destination-initial-value-job (Job Only) destination-locations-requested destination-models-requested destination-name-requested (Job Only) destinations-assigned (Job Only) destinations-used (Job Only) device-support-system-requested discard-time (Job Only) dss-requested	. 548 . 549 . 549 . 550 . 550 . 551 . 551 . 551 . 551 . 552 . 552	message-from-administrator (Job Only) message-to-operator models-requested modification-time (Job Only) name name-of-last-accessor (Job Only) notification-profile number-of-documents (Job Only) object-class octets-completed (Job Only)	575 576 576 576 576 576 577 579 580
destination-initial-value-job (Job Only) destination-locations-requested destination-models-requested destination-name-requested (Job Only) destinations-assigned (Job Only) destinations-used (Job Only) destinations-used (Job Only) discard-time (Job Only) discard-time (Job Only)	. 548 . 549 . 549 . 550 . 550 . 551 . 551 . 551 . 551 . 552 . 552 . 553	message-from-administrator (Job Only) message-to-operator models-requested modification-time (Job Only) name name-of-last-accessor (Job Only) new-job-identifier (Job Only) notification-profile number-of-documents (Job Only) object-class octets-completed (Job Only) optimize-for-multiple-copies	575 576 576 576 576 576 577 579 580 580
destination-initial-value-job (Job Only) destination-locations-requested destination-models-requested destination-name-requested (Job Only) destinations-assigned (Job Only) destinations-used (Job Only) device-support-system-requested discard-time (Job Only) dss-requested	. 548 . 549 . 549 . 550 . 550 . 551 . 551 . 551 . 551 . 552 . 552 . 553	message-from-administrator (Job Only) message-to-operator models-requested modification-time (Job Only) name name-of-last-accessor (Job Only) notification-profile number-of-documents (Job Only) object-class octets-completed (Job Only)	575 576 576 576 576 576 577 579 580 580
destination-initial-value-job (Job Only) destination-locations-requested destination-models-requested destination-name-requested (Job Only) destinations-assigned (Job Only) destinations-used (Job Only) destinations-used (Job Only) device-support-system-requested discard-time (Job Only) des-requested end-message.	. 548 . 549 . 549 . 550 . 550 . 551 . 551 . 551 . 551 . 552 . 552 . 553 . 553	message-from-administrator (Job Only) message-to-operator models-requested modification-time (Job Only) name name-of-last-accessor (Job Only) new-job-identifier (Job Only) notification-profile number-of-documents (Job Only) object-class octets-completed (Job Only) optimize-for-multiple-copies originator (Job Only)	575 575 576 576 576 576 579 579 580 580 581
destination-initial-value-job (Job Only) destination-locations-requested destination-models-requested	. 548 . 549 . 549 . 550 . 550 . 551 . 551 . 551 . 552 . 552 . 553 . 553	message-from-administrator (Job Only) message-to-operator models-requested modification-time (Job Only) name name-of-last-accessor (Job Only) new-job-identifier (Job Only) notification-profile number-of-documents (Job Only) object-class octets-completed (Job Only) optimize-for-multiple-copies originator (Job Only) owner (Job Only)	575 576 576 576 576 576 577 579 580 581 581
destination-initial-value-job (Job Only) destination-locations-requested destination-models-requested	. 548 . 549 . 549 . 550 . 550 . 551 . 551 . 551 . 551 . 552 . 552 . 553 . 553 . 553	message-from-administrator (Job Only) message-to-operator models-requested modification-time (Job Only) name name-of-last-accessor (Job Only) new-job-identifier (Job Only) notification-profile number-of-documents (Job Only) object-class octets-completed (Job Only) optimize-for-multiple-copies originator (Job Only) owner (Job Only) pages-completed (Job Only)	575 576 576 576 576 576 577 579 580 581 581
destination-initial-value-job (Job Only) destination-locations-requested destination-models-requested	. 548 . 549 . 549 . 550 . 550 . 551 . 551 . 551 . 552 . 552 . 553 . 553 . 553 . 553	message-from-administrator (Job Only) message-to-operator models-requested modification-time (Job Only) name name-of-last-accessor (Job Only) notification-profile number-of-documents (Job Only) object-class octets-completed (Job Only) optimize-for-multiple-copies originator (Job Only) owner (Job Only) pages-completed (Job Only) physical-printers-requested	575 576 576 576 576 576 576 579 580 581 581 581 582
destination-initial-value-job (Job Only) destination-locations-requested destination-models-requested	. 548 . 549 . 549 . 550 . 550 . 551 . 551 . 551 . 552 . 552 . 553 . 553 . 553 . 553	message-from-administrator (Job Only) message-to-operator models-requested modification-time (Job Only) name name-of-last-accessor (Job Only) new-job-identifier (Job Only) notification-profile number-of-documents (Job Only) object-class octets-completed (Job Only) optimize-for-multiple-copies originator (Job Only) owner (Job Only) pages-completed (Job Only) physical-printers-requested position-in-queue (Job Only)	575 576 576 576 576 576 577 579 580 581 581 581 582 582
destination-initial-value-job (Job Only) destination-locations-requested destination-models-requested destination-name-requested (Job Only) destinations-assigned (Job Only) destinations-used (Job Only) device-support-system-requested discard-time (Job Only) discard-time (Job Only)	. 548 . 549 . 549 . 550 . 550 . 551 . 551 . 551 . 552 . 552 . 553 . 553 . 553 . 553 . 554 . 554	message-from-administrator (Job Only) message-to-operator models-requested modification-time (Job Only) name name-of-last-accessor (Job Only) notification-profile number-of-documents (Job Only) object-class octets-completed (Job Only) optimize-for-multiple-copies originator (Job Only) owner (Job Only) pages-completed (Job Only) physical-printers-requested position-in-queue (Job Only)	575 576 576 576 576 576 577 579 580 581 581 581 582 582 582
destination-initial-value-job (Job Only) destination-locations-requested destination-models-requested destination-name-requested (Job Only) destinations-assigned (Job Only) destinations-used (Job Only) device-support-system-requested discard-time (Job Only) discard-time (Job Only)	. 548 . 549 . 549 . 550 . 550 . 551 . 551 . 551 . 552 . 552 . 553 . 553 . 553 . 553 . 554 . 554 . 554	message-from-administrator (Job Only) message-to-operator models-requested modification-time (Job Only) name name-of-last-accessor (Job Only) notification-profile number-of-documents (Job Only) object-class octets-completed (Job Only) optimize-for-multiple-copies originator (Job Only) owner (Job Only) pages-completed (Job Only) physical-printers-requested position-in-queue (Job Only) previous-job-state (Job Only)	575 576 576 576 576 576 577 579 580 581 581 581 582 582 582
destination-initial-value-job (Job Only) destination-locations-requested destination-models-requested destination-name-requested (Job Only) destinations-assigned (Job Only) destinations-used (Job Only) device-support-system-requested discard-time (Job Only) discard-time (Job Only)	. 548 . 549 . 549 . 550 . 550 . 551 . 551 . 551 . 552 . 552 . 553 . 553 . 553 . 553 . 554 . 554 . 554	message-from-administrator (Job Only) message-to-operator models-requested modification-time (Job Only) name name-of-last-accessor (Job Only) notification-profile number-of-documents (Job Only) object-class octets-completed (Job Only) optimize-for-multiple-copies originator (Job Only) owner (Job Only) pages-completed (Job Only) physical-printers-requested position-in-queue (Job Only)	575 576 576 576 576 576 577 579 580 581 581 581 582 582 582
destination-initial-value-job (Job Only) destination-locations-requested destination-models-requested destination-name-requested (Job Only) destinations-assigned (Job Only) destinations-used (Job Only)	. 548 . 549 . 549 . 550 . 550 . 551 . 551 . 551 . 552 . 552 . 552 . 553 . 553 . 553 . 553 . 554 . 554 . 555 . 555	message-from-administrator (Job Only) message-to-operator models-requested modification-time (Job Only) name name-of-last-accessor (Job Only) notification-profile number-of-documents (Job Only) object-class octets-completed (Job Only) optimize-for-multiple-copies originator (Job Only) owner (Job Only) pages-completed (Job Only) physical-printers-requested position-in-queue (Job Only) previous-job-state (Job Only) previous-state (Job Only) print-after (Job Only)	575 576 576 576 576 576 577 579 580 581 581 582 582 582 583 583
destination-initial-value-job (Job Only) destination-locations-requested destination-models-requested	. 548 . 549 . 549 . 550 . 550 . 551 . 551 . 551 . 552 . 552 . 552 . 553 . 553 . 553 . 553 . 554 . 554 . 555 . 555 . 555	message-from-administrator (Job Only) message-to-operator models-requested modification-time (Job Only) name name-of-last-accessor (Job Only) notification-profile number-of-documents (Job Only) object-class octets-completed (Job Only) optimize-for-multiple-copies originator (Job Only) owner (Job Only) pages-completed (Job Only) pages-completed (Job Only) physical-printers-requested position-in-queue (Job Only) previous-job-state (Job Only) print-after (Job Only) printer-initial-value-job (Job Only)	575 576 576 576 576 576 577 579 580 581 581 582 582 582 582 583 583
destination-initial-value-job (Job Only) destination-locations-requested destination-models-requested destination-name-requested (Job Only) destinations-assigned (Job Only) destinations-used (Job Only)	. 548 . 549 . 549 . 550 . 550 . 551 . 551 . 551 . 551 . 552 . 552 . 552 . 553 . 553 . 553 . 553 . 554 . 554 . 555 . 555 . 555 . 555	message-from-administrator (Job Only) message-to-operator models-requested modification-time (Job Only) name name-of-last-accessor (Job Only) notification-profile number-of-documents (Job Only) object-class octets-completed (Job Only) optimize-for-multiple-copies originator (Job Only) owner (Job Only) pages-completed (Job Only) physical-printers-requested position-in-queue (Job Only) previous-job-state (Job Only) previous-state (Job Only) print-after (Job Only)	575 576 576 576 576 576 577 579 580 581 581 582 582 582 583 583 583

maintan mana manasta d	E02	destination model
printer-name-requested		destination-model
printer-requested		destination-name
printers-assigned (Job Only)		destination-realization
printers-used (Job Only)		destination-support-system
processing-time (Job Only)		destinations-ready 607
queue-assigned (Job Only)		device-support-system 607
queue-position (Job Only)		document-formats-supported 607
reasons (Job Only)		document-types-supported 608
required-resources-not-ready (Job Only)		enabled
required-resources-not-supported (Job Only)		end-message-supported 609
results-profile		image-out-formats-supported 609
retained-time (Job Only)		input-trays-supported 610
retention-period		job-size-range-supported 611
start-message		list-of-managers 611
started-printing-time (Job Only)	587	locations 612
state-reasons (Job Only)	587	logical-printer 612
submission-time (Job Only)	587	managers 612
tape-exit (Job Only)		maximum-copies-supported 612
tape-format (Job Only)		media-supported 612
tape-labeled (Job Only)		message
tape-max-block-size (Job Only)		model 613
tape-rewind-before (Job Only)		notification-profile 613
tape-rewind-unload (Job Only)		nt-drivers
ticket-content (Job Only).		object-class
total-job-octets (Job Only)		orientations-supported 615
user-locale (Job Only).		os2-driver-names
user-name (Job Only).		os2-drivers
Attributes for Logs		page-select-supported
Initially Settable Attribute Listing.		plexes-supported 617
Resettable Attribute Listing		print-qualities-supported 617
associated-server		
		printer
descriptor		printer-associated-printers
enabled		printer-initial-value-document
log-address		printer-initial-value-job
log-identifier	594	printer-locations 618
log-messages		printer-model 618
log-severity		printer-name 618
log-size		printer-realization 618
log-trace-groups		printers-ready 618
log-type		protected-attributes 618
log-wrap		qualities-supported 618
object-class		sides-supported 619
Attributes for Logical Destinations		start-message-supported 619
Attributes Not Displayed in the Infoprint		table-reference-characters-supported 619
Administrator's GUI	598	windows-driver-names 620
Initially Settable Attribute Listing	598	windows-drivers 621
Resettable Attribute Listing	598	windows-nt-driver-names 621
associated-queue		windows-nt-drivers 622
associated-server		x-image-shift-range-supported 622
authorize-jobs		y-image-shift-range-supported 622
auxiliary-sheet-selections-supported		tributes for Media
carriage-control-types-supported		Attributes Not Displayed in the Infoprint
character-mappings-supported		Administrator's GUI 624
content-orientations-supported		Initially Settable Attribute Listing 624
convert-to-ebcdic-supported		Resettable Attribute Listing 624
data-fidelity-problem-reported-supported		associated-server
descriptor		descriptor
destination-associated-destinations		medium-color
destination-initial-value-document		medium-dimensions
destination-initial-value-job		medium-form-parts
destination-locations	003	$medium-holes-count \ . \ . \ . \ . \ . \ . \ . \ . \ . \ $

1		1 .
medium-identifier		hostname
medium-sides		i-p-address
medium-size		ip-address
medium-type	. 628	job-attributes-supported 649
medium-weight	. 629	job-state-reasons-supported 649
message	. 629	job-states-supported 649
object-class		job-submission-timer 650
Attributes for Queues	. 630	list-of-managers 650
Initially Settable Attribute Listing		locale
Resettable Attribute Listing		log-accounting-data
actual-destinations-assigned		logical-destinations-ready
		logical-destinations-supported
actual-destinations-ready		
assign-to-destination	. 631	logical-printers-ready
associated-server		logical-printers-supported
backlog		managers
backlog-lower-bound		maximum-barco-rips
backlog-update-interval	. 632	maximum-non-raster-rips 653
backlog-upper-bound	. 633	maximum-raster-rips 653
backlogged	. 633	message
current-backlog	. 633	modify-individual-document-supported 654
descriptor	. 633	multiple-documents-supported 654
list-of-managers		notification-delivery-methods-supported 654
logical-destinations-assigned		notification-profile 655
logical-destinations-ready	634	npm-server-ip-address 656
logical-printers-assigned	635	npm-server-port-number
logical-printers-ready.		object-class
managers	635	object-classes-supported
message		physical-printers-ready
notification-profile.		physical-printers-supported
		printer-states-supported
notify-operator		printer-states-supported
object-class	. 637	problem-child
operators	. 637	protected-attributes
physical-printers-assigned		queues-supported 659
physical-printers-ready		save-rip-files 659
protected-attributes		security-level 659
queue-backlog	. 638	server-hostname
queue-name	. 638	server-ip-address 660
queue-state	. 638	server-name
requeue-failed-jobs	. 639	server-state
Attributes for Resource Contexts	. 640	smtp-server-host (Windows NT and Windows
Initially Settable Attribute Listing	. 640	2000 Only)
Resettable Attribute Listing		smtp-server-port-number (Windows NT and
associated-server		Windows 2000 Only)
context-address		snmp-aix-printer-models 662
descriptor		snmp-discovery-during-startup 662
object-class		snmp-normal-poll-interval
resource-context-identifier		snmp-problem-poll-interval
Attributes for Servers		snmp-trap-timeout
Initially Settable Attribute Listing		transfer-methods-supported
Resettable Attribute Listing		windows-drivers
		windows-nt-driver-names
accept-unsupported-jobs		
actual-destinations-ready		windows-nt-drivers
actual-destinations-supported		Attributes for Transforms (Windows NT or
auto-create-shared-printers (Windows NT and		Windows 2000 only)
Windows 2000 Only)		Initially Settable Attribute Listing 666
cancel-individual-document-supported		Resettable Attribute Listing 666
descriptor		associated-server
destination-states-supported		descriptor
destination-support-systems-supported	. 646	document-formats-supported 667
document-attributes-supported		object-class
events-supported		other-transform-options

output-document-format 669	Default Form Definitions
terminating-transform 670	General-Purpose Form Definitions
transform-identifier 671	Form Definitions for Printing Envelopes 725
transform-library 671	Form Definitions for 17 by 11 Inch Paper 725
,	Form Definitions Specifying a 0, 0 Offset 726
Chapter 8. Infoprint Environment	Form Definitions Specifying N_UP Page
Variables 673	Positioning
	Form Definitions for Printing on Prepunched
Querying Environment Variables	Paper
Setting Environment Variables 677	Form Definitions for Specific Models of IBM
In a File	Printers
On the Command Line 678	Page Definitions Supplied with Infoprint 730
	Page Definitions for Letter-Sized Paper 730
Chapter 9. Notification Events and	Page Definitions for A4-Sized Paper 730
Event Classes 679	Page Definitions for Letter- and A4-Sized Paper
	with Multiple-Up of 2 and 4
Appendix A. Attribute-to-Object	Page Definitions for Legal-Sized Paper 731
Listing 695	Page Definitions for B4-Sized Paper 732
Listing	
Annandiy P. Migrating DCE for AIV	Glossary
Appendix B. Migrating PSF for AIX	Sources and References
Job Script Keywords to Infoprint	Sources and references
Equivalents 715	Notices
Appendix C. Job Validation and	Licenses
Scheduling 719	Trademarks
ocheduming	
Annandiy D. Farm Definitions and	Index
Appendix D. Form Definitions and	
Page Definitions Supplied with	
Infoprint	

Figures

1.	A PCL Image	9.	Heisei Gothic Portion of a Sample fonts.tab	
2.	A Cropped PCL Image		Configuration File	. 308
3.	A PCL Image Offset from the Top-Left Corner 275	10.	Sample image.tab Configuration File	309
4.	Sample pcl2afp Configuration File 277	11.	Sample pagedef.tab Configuration File	310
5.	Sample ps2afp Configuration File 298	12.	Sample printer.tab Configuration File	311
6.	Sample barcode.tab Configuration File 304	13.	Sample xxxxyyyy.tab Configuration File	
7.	Sample defcp.tab Configuration File 305		(Single-Byte Code Pages)	. 312
8.	Header and Courier Portions of a Sample	14.	Sample xxxxyyyy.tab Configuration File	
	fonts.tab Configuration File		(Double-Byte Code Pages)	. 312

Tables

1.	Infoprint Objects	18.	Notification Event Classes 690
2.	Attribute Operators for Filters 41	19.	PSF for AIX Keywords Used in Job Script
3.	Filter Syntax		Files and Infoprint Equivalents 715
4.	pdmod Operators 49	20.	PSF for AIX Keywords Used in parmdd Files 717
5.	Results of the pdq Command	21.	Document and Destination Attributes Used
6.	pdset Operators		for Validation and Scheduling 720
7.	line2afp Resource Options and Corresponding	22.	Job and Destination Attributes Used for
	Options and Attributes		Validation and Scheduling 721
8.	File Extensions for Resources	23.	Default Form Definition Characteristics 723
9.	PCL Printing and Processing Options 277	24.	General-Purpose Form Definitions 723
10.	PostScript and PDF Printing and Processing	25.	Form Definitions Supplied with Infoprint for
	Options		Printing Envelopes
11.	SAP Code Page Configuration Files 311	26.	Form Definitions Supplied for 17 by 11 Paper 725
12.	Input Tray Names, Job Bin Numbers, and	27.	Form Definitions Supplied with Infoprint
	Tray Numbers on AFP Printer Devices 433		Specifying a 0, 0 Offset
13.	Infoprint Environment Variables Defaulted or	28.	Form Definitions for N_UP Page Positioning 727
	Set for Infoprint Manager for AIX and	29.	Form Definitions for Prepunched Paper 728
	Infoprint Manager for Windows NT and	30.	Form Definitions Supplied for IBM 3831,
	Windows 2000		3835, and 3900 Printers
14.	Infoprint Environment Variables Defaulted or	31.	Form Definition Supplied for IBM 3935 and
	Set in the /etc/environment File in Infoprint		3160 Printers
	Manager for AIX	32.	Page Definitions for Letter-Sized Paper 730
15.	Infoprint Environment Variables Set in the	33.	Page Definitions for A4-Sized Paper 730
	Infoprint SMIT Production Print Operations	34.	Page Definitions for Letter- and A4-Sized
	Interface Environment File for Infoprint		Paper with Multiple-Up of 2 and 4 731
	Manager for AIX	35.	Page Definitions for Legal-Sized Paper 731
16.	AIX Environment Variables 676	36.	Page Definitions for B4-Sized Paper 732
17	Notification Events 670		-

About This Publication

This publication describes the Infoprint Manager (Infoprint):

- Commands
- Flags used with AIX print commands
- Administrative utilities
- · Daemon utilities
- Transform commands
- Object attributes
- Environment variables
- · Notification events and event classes

Who Should Use This Publication

This publication is intended for the person responsible for installing, customizing, operating, or administrating Infoprint.

About the Documentation for Infoprint

Infoprint provides the following types of documentation:

- Infoprint library in portable document format (PDF) or hard copy
- Infoprint documentation on the World Wide Web
- Online help for Infoprint Submit, Infoprint Scan, the Infoprint Administration GUI, the Infoprint Operations GUI, the Infoprint administrator's GUI, the Infoprint SMIT production printing system interface, and the Infoprint SMIT production print operations interface
- Manual (man) pages
- Infoprint online message catalog
- readme files

The Infoprint Publication Library

For the most current information, please go to the IBM Printing System site at http://www.ibm.com/printers.

Infoprint Manager for AIX Publication Library

Infoprint provides the following publications in PDF format on a CD-ROM supplied with the product:

- *Infoprint Manager for AIX: Administrator's Guide*, S544-5595. This publication describes the primary administrator tasks necessary for setting up an Infoprint environment.
- *Infoprint Manager for AIX: User's and Operator's Guide*, S544-5596. This publication describes submitting print jobs from Infoprint Submit, Infoprint Scan, Infoprint Select, and the Infoprint AIX client, scheduling jobs, and managing the print environment.
- *Infoprint Manager: Reference*, S544-5475. For print administrators, operators, and application programmers with the need to perform command-line functions, this publication describes the commands, utilities, transforms, attributes, and attribute values associated with Infoprint.
- *PSF Direct Network Configuration Guide for System/370*, S544-5486. For system administrators or network specialists responsible for configuring a system for Print Services Facility (PSF) Direct. PSF Direct is a function of Infoprint Manager

- that allows another PSF program (PSF/VM, PSF/MVS, or PSF/VSE) to print remotely, using the SNA LU 6.2 protocol, on printers supported by Infoprint. The PSF program sends the print data stream directly to the Infoprint printer.
- IBM PSF for AIX: AFP Upload Configuration Guide Using SNA Server/6000, S544-5422. For system administrators, this publication describes how to configure AFP Upload on both AIX (client) and MVS (server) to send files to the JES spool on the MVS server, using a SNA Server/6000 protocol.
- IBM PSF for AIX: AFP Upload Configuration Guide Using TCP/IP, S544-5423. For system administrators, this publication describes how to configure AFP Upload on both AIX (client) and MVS (server) to send files to the JES spool on the MVS server, using a TCP/IP protocol.

Infoprint Manager for Windows NT and Windows 2000 Publication Library

Infoprint provides the following publications in PDF format on a CD-ROM supplied with the product:

- Infoprint Manager for Windows NT and Windows 2000: Planning Guide, G544–5716. This publication helps you prepare to use Infoprint Manager for Windows NT and Windows 2000. It describes features of this product and compares its functions to those of IBM Print Services Facility for OS/2 (PSF for OS/2). It addresses migration from PSF for OS/2 at a high level. Finally, this publication explains the differences between the AIX and Windows version of Infoprint. You can order a printed copy of this publication from IBM by requesting the form
- Infoprint Manager for Windows NT and Windows 2000: Getting Started, G544–5717. This publication helps you install and configure Infoprint Manager for Windows NT and Windows 2000. It focuses primarily on server and client system software configuration, but it also includes information for the IBM 4159 Model 001 S/390 Parallel Channel Emulator Card. You can order a printed copy of this publication from IBM by requesting the form number.
- Infoprint Manager: Reference, S544-5475. For print administrators, operators, and application programmers with the need to perform command-line functions, this publication describes the commands, utilities, transforms, attributes, and attribute values associated with Infoprint.

Note: This publication is available only in PDF format.

- PSF Direct Network Configuration Guide for System/370, S544-5486. For system administrators or network specialists responsible for configuring a system for Print Services Facility (PSF) Direct. PSF Direct is a function of Infoprint Manager that allows another PSF program (PSF/VM, PSF/MVS, or PSF/VSE) to print remotely, using the SNA LU 6.2 protocol, on printers supported by Infoprint. The PSF program sends the print data stream directly to the Infoprint printer.
- IBM PSF for AIX: AFP Upload Configuration Guide Using SNA Server/6000, S544-5422. For system administrators, this publication describes how to configure AFP Upload on both AIX (client) and MVS (server) to send files to the JES spool on the MVS server, using a SNA Server/6000 protocol.
- IBM PSF for AIX: AFP Upload Configuration Guide Using TCP/IP, S544-5423. For system administrators, this publication describes how to configure AFP Upload on both AIX (client) and MVS (server) to send files to the JES spool on the MVS server, using a TCP/IP protocol.

Other Publications Related to Infoprint

The following publications contain information you might find useful while installing, administrating, and using Infoprint:

 AIX Version 4 Release 1 Commands Reference, SBOF-1851, or AIX Version 4 Release 3 Commands Reference, SBOF-1877. For administrators, operators, and end users, these publications provide complete information about AIX commands.

Note: Infoprint requires AIX Version 4.2.1 or 4.3. Users of AIX Version 4.2.1 should refer to AIX Version 4 Release 1 Commands Reference.

- PSF/MVS MVS Download Guide, G544-5294. For administrators and job submitters, this publication provides instructions for setting up the MVS Download support on PSF/MVS so that data can be transmitted from the Job Entry Subsystem (JES) spool on MVS for printing on an Infoprint system.
- Printing for Fun and Profit under AIX, GG24-3570. For administrators and system engineers, this publication provides instructions for installing printer devices and configuring AIX print queues.
- IBM Page Printer Formatting Aid: User's Guide, S544-5284. For administrators and job submitters, this publication provides instructions for creating form definitions and page definitions with Page Printer Formatting Aid for AIX (PPFA).

Note: This is an optional feature of Infoprint.

- · Advanced Function Presentation: Font Summary, G544-3810. For administrators and job submitters, this publication provides information on IBM fonts.
- Advanced Function Presentation: Printer Information, G544-3290. For administrators and job submitters, this publication provides information on IBM printer devices.
- IBM Data Stream and Object Architectures: Bar Code Object Content Architecture Reference, S544-3766. For administrators, this publication provides information on bar codes.
- IBM Data Stream and Object Architectures: Font Object Content Architecture Reference, S544-3285. For administrators, this publication provides information on coded fonts.
- IBM Data Stream and Object Architectures: Graphics Object Content Architecture Reference, S544-5498. For administrators, this publication provides information on printing graphics.
- IBM Data Stream and Object Architectures: Image Object Content Architecture Reference, SC31-6805. For administrators and job submitters, this publication provides information on the IOCA data stream.
- IBM Data Stream and Object Architectures: Mixed Object Document Content Architecture Reference, SC31-6802. For administrators and job submitters, this publication provides information on the MOD:CA data stream.
- TCP/IP Tutorial and Technical Overview, GG24-3376. For networking specialists, this publication provides an overview of the Transmission Control Protocol/Internet Protocol (TCP/IP) and its uses in heterogeneous networks.

Manual (man) Pages for Infoprint Commands, Utilities, and **Transforms**

Online information, in manual (man) page format, is available for all Infoprint commands and utilities. You can use the AIX man command to view man pages for the following Infoprint commands:

lprafp pdpr pdpromote mkfntmap pdaccount pdq pdclean pdreorder pdcreate pdresubmit pddelete pdresume pddisable pdrm pdset pdenable pdls pdshutdown pdmod pdspace pdpause psfstat

For example, to view online information for the **pdpr** command, enter: man pdpr

You can use the AIX man command to view the following man page for the -o flag, which is used to pass information to Infoprint on AIX print commands:

oflag

You can use the AIX man command to view man pages for the following Infoprint utilities:

admingui afpsplit ainupod1 ainupod2 ainupod3 ainurpt1 ainurpt2 ainurpt3 ainurpt4 ainurpt5 ainurpt6 cfu cmt ipguiadv ipguibasic ipguidist ipguiadvadm $ipguibasicad \\ m$ ipguidistadm jsmigr opergui pdadmin

pdcrcds pdcrdflt pdcrmed

pdinitports pdmigpp pdmincfg pdmsg pdnetifspri rc.iprsap rc.pd

sense for Infoprint Manager for AIX sense for Infoprint Manager for Windows NT and Windows 2000

setup startppo start_server startsrv stop_server tdump tlist t2file

You can use the AIX man command to view man pages for the following Infoprint daemon utilities:

mvsprsd startnotd pcl2afpd stopcbd ps2afpd stopnotd startcbd

You can use the AIX man command to view man pages for the following Infoprint transform commands:

db2afp	pcl2afp
d2afp	pdf2afp
gif2afp	ps2afp
jpeg2afp	sap2afp
line2afp	tiff2afp

For information about the flags that you can use with the man command, refer to the man man page or to the AIX Version 4.2 Commands Reference.

Manual (man) pages for Infoprint Attributes

Note: The Manual Pages for Infoprint Attributes are no longer being revised. For the most current information on Infoprint Attributes, consult "Chapter 7. Infoprint Object Attributes" on page 329 in this manual.

Infoprint provided you with online information about the attributes that each object supports at general availability for Infoprint Manager for AIX, Version 3 Release 2 Modification 0. To view the various attributes, enter the following command:

```
man pd att
```

A list displays containing file names of attribute man pages. You can then display the desired file and view the information about specific attributes.

Use the AIX man command to view the following Infoprint man pages for attributes:

```
pd_att_act_dest
                                           pd_att_medium
pd_att_aux_sheet
                                           pd_att_queue
pd_att_document
                                           pd_att_res_context
pd_att_job
                                           pd_att_server
                                           pd_att_transform
pd_att_log
pd_att_log_dest
```

Infoprint Online Message Catalog

Infoprint supplies a message catalog for the messages that are issued during its operation. For each message, the message catalog includes the text of the message, an explanation, a system action, and a response. You can view all information for a specific Infoprint error message by issuing the Infoprint pdmsg utility followed by the message number.

For example, from the command line enter: pdmsg 5010-096

Messages issued by Infoprint have the following prefixes:

0420	0424
0421	0425
0422	5010
0423	

See the Infoprint pdmsg man page for a complete description of the pdmsg utility.

To view information about an AIX message, issue the AIX info command with the -h flag, followed by the message number. For example, from the command line enter:

info -h MessageNumber

where *MessageNumber* is the number of the AIX message.

readme Files

The readme files on the Infoprint CD-ROM contain last-minute information about Infoprint that the hardcopy publications or the online information do not contain. You can use the AIX more command or a text editor, such as dtpad or vi on AIX, EPM on OS/2, or Notepad on Windows, to view the contents of the readme files.

Viewing PDF Publications

Infoprint provides software publications in PDF files on the publications CD-ROM. To view or print these publications:

- 1. Log in to AIX as **root** or as a member of the **system** group.
- 2. Insert the Infoprint publications CD-ROM into the drive.
- 3. To determine the identifier of your CD-ROM drive, enter on the AIX command line:

1sdev -C -c cdrom

4. Then enter:

mount -v cdrfs -r /dev/cdn /cdrom

where *cdn* is the identifier of your CD-ROM drive, and */cdrom* is the file system that was created to install Infoprint.

- 5. Read the **readme.txt** file in the **/cdrom** directory.
- 6. If your AIX server or Windows system has an internet browser, such as Netscape or Internet Explorer, select the aixindex.html file in the appropriate language directory and click on the descriptions to view the appropriate PDF

For example, if you use English, access the /cdrom/english/aixindex.html file. If your AIX server or Windows system does not have an internet browser, move to the appropriate language directory and slect the appropriate PDF file from the following choices:

Installing Infoprint Manager

Title	PDF file name
Getting up and running in no time with IBM installation services	inscf798.pdf
Installing and Configuring Infoprint Library	library.pdf
Installing Infoprint Manager Control on your AIX Server	aixinsr32.pdf
Installing Optional Features	insoptf32.pdf

Using Infoprint Manager

Title	PDF file name
IPDS Printer Operator Commands	refip798232.pdf

IPDS Error Recovery	ipdserrecov32.pdf
Performing Optional Configuration	optcfg32.pdf
Printing Variable Data	VariData.pdf
Submitting a Job to a DocuTech 135 Printer	prdocu39932.pdf
Using Enhanced Grab and Move to Shift Page Images	prnpgoff39932.pdf
Using Infoprint Scan	g5445722.pdf

Infoprint Publications

Title	PDF file name
Administrator's Guide	iprf1mst.pdf
User's and Operator's Guide	ipro1mst.pdf
Infoprint Manager Reference	iprr2mst.pdf
IBM PSF for AIX: AFP Upload Configuration Guide Using SNA Server/6000	S5445422.pdf
IBM PSF for AIX: AFP Upload Configuration Guide Using TCP/IP	S5445423.pdf
SAP R/3 Support: Configuration and Printing Tasks	sapr332.pdf.pdf

7. To use the Adobe Acrobat Viewer, enter:

cd /usr/lpp/Acrobat3/bin ./acroexch

Click on the **Help** button to learn how to view or print a publication.

8. If you have installed Infoprint Submit or the Adobe Acrobat Viewer on Windows, you can print or view the Infoprint PDF publications from your Windows system. On Windows, the publications directory is called *d*:\cdrom\books\language, where *d*: is the identifier of your CD-ROM drive and *language* is the appropriate language for the books.

The Organization of This Publication

This publication contains the following chapters and appendixes:

Chapter 1. Introduction

This chapter describes the Infoprint object classes and gives some general information about invoking Infoprint commands, utilities, and transforms.

Chapter 2. Infoprint Commands

This chapter describes the syntax, use, flags, attributes, and arguments of the Infoprint commands and shows examples of each command.

Chapter 3. The -o Flag for AIX Print Commands

This chapter describes the **-o** flag, which is used with AIX print commands to pass information to Infoprint.

Chapter 4. Infoprint Administrative Utilities

This chapter describes the syntax, use, flags, and arguments of the Infoprint administrative utilities and shows examples of each utility.

Chapter 5. Daemon Utilities for Infoprint Manager for AIX

This chapter describes the utilities that start Infoprint daemons.

Chapter 6. Infoprint Transform Commands

This chapter describes the transforms used for converting data for printing with Infoprint.

Chapter 7. Infoprint Object Attributes

This chapter describes the use and values of the attributes associated with each Infoprint object class.

Chapter 8. Infoprint Environment Variables

This chapter describes the Infoprint and AIX environment variables that affect the processing of Infoprint commands.

Chapter 9. Notification Events and Event Classes

This chapter describes the Infoprint events for which you can request notification.

Appendix A. Attribute-to-Object Listing

This appendix contains a table listing all the Infoprint attributes in alphabetical order and naming the objects that support each attribute.

Appendix B. Migrating PSF for AIX Job Script Keywords to Infoprint **Equivalents**

This appendix contains a table showing the attribute, or the flag or argument of the pdpr command, that replaces each PSF job script keyword when the job script is migrated to Infoprint.

Appendix C. Job Validation and Scheduling

This appendix describes how Infoprint validates and schedules jobs. It contains tables showing the attributes used for validation and scheduling.

Appendix D. Form Definitions and Page Definitions Supplied with Infoprint

This appendix lists the form definitions and page definitions supplied with Infoprint.

This publication also contains a glossary and an index.

Conventions Used in This Publication

This publication uses conventions for the following:

- Highlighting
- Infoprint command notation

Highlighting

This publication uses four different types of highlighting:

In this publication, bold highlighting identifies commands, attributes, files, Bold directories, and other items whose names the system predefines, such as pdpr and notification-profile.

Italic When used in running text, italic highlighting identifies a variable item whose actual name or value you supply, such as AttributesFileName or Notification. Italics also identify publication titles.

Bold *Italic*

When enclosed in double quotation marks, combined bold and italic highlighting identifies a specific attribute name that you enter exactly as shown and a variable value that you supply with the attribute. For example: "copy-count=number"

Monospace

When used in command examples, information in a monospaced font identifies the exact wording of the command.

Infoprint Command Notation

Command syntax notation uses symbols to show specific conditions. Do not enter the following symbols, unless specifically instructed to do so, when actually issuing a Infoprint command:

```
Bar
Braces {}
```

Note: There are some situations in which you will actually type the brace characters. See "Special Characters That Are Included in Commands" on page xxviii.

```
Brackets
Underlining
Ellipsis
```

These symbols have the following meanings when used in the publications and in the online information:

• A vertical bar, I, between values means that you can only enter one of the values with the command. For example:

```
job-hold:= {true | false}
```

means that when you set the job-hold attribute, you can specify either true or false, but not both.

Braces, { }, around values identify required items that you must supply with the command. For example:

```
job-hold:= {true | false}
```

means that you must enter either true or false.

• Brackets, [], around values indicate that they are optional. For example:

```
resource-context=directory[:directory...]
```

means that you do not have to enter more than one directory, but that you can have two or more directories, each separated by a colon,: .

An ellipsis, ..., means that you can supply more than one occurrence of a keyword or value with the command. For example:

```
resource-context=directory[:directory...]
```

means that you can enter more than directory name.

Underlined text identifies the default fixed value that Infoprint uses if you do not specify a value. For example:

```
default-printer-resolution={240 | 300 | 480 | 600}
```

means that 240 is the default value.

Special Characters That Are Included in Commands

When colons, dashes, the equals sign, double quotation marks, single quotation marks, and braces are shown in command syntax notation, you will include them when you issue the command in most cases. These special characters have the following meanings:

• A colon, :, separates related values. For example: pdpr -f file1 -x "page-select=3:6" file2

```
means that only pages 3 through 6 of file2 are to print.
```

- A dash, -, always precedes a flag, for example, -x.
- The equals sign, =, separates attribute and value pairs. For example: pdmod -x "sides=2" DivSpool12:1011230045

means that 2 is the value assigned to the **sides** attribute.

Double quotation marks, "", surround multiple attribute and value pairs, such

```
-x "sides=2 print-quality=draft"
```

For consistency, this publication also shows double quotation marks around single attribute and value pairs in all command examples, although they are not required. For example:

- -x "document-format=ascii"
- Double quotation marks, "", surround text strings that contain spaces, such as: -m "Down for maintenance"
- Single quotation marks, '', surround a text string that contains spaces inside another string that is enclosed in double quotation marks. An example is:
 - -x "sides=2 job-print-after='08:00:00 10/09/98'"
- Braces, { }, surround a value in a notification profile. An example is:
 - -x "notification-profile={delivery-method=electronic-mail}"

Global Character Used in Examples and Shell Information

The examples using a global character and other examples shown within the Infoprint publications relate to the Korn shell. Depending on the shell you are using, the examples shown may or may not work. The examples may also show control characters that other shells do not require. Adjust the examples as necessary for the shell you are using.

Examples of Commands and Attributes

- This publication shows examples of commands in a format designed for ease of reading. When entering the command, allow the command to wrap characters from one line to the next.
- Many examples in this publication use spacing of attributes and values for ease of reading and formatting considerations. When entering the attributes and their values on the command line or in attributes files, use the correct syntax.

Chapter 1. Introduction

Infoprint Manager for AIX allows you to send a file, as an electronic document, for printing on a printer device or for transmission by fax or electronic mail; and Infoprint Manager for Windows NT and Windows 2000 allows you to send a file, as an electronic document, for printing on a printer device.

This book was originally written for Infoprint Manager for AIX. Because of the commonality between Infoprint Manager for AIX and Infoprint Manager for Windows NT and Windows 2000, this book now documents both products with an admitted slant on the AIX side for such things as examples and path names. (See "Reference Table for Path Names" for a table that lists the NT and 2000 paths with the AIX paths used in this book.) An effort has been made to indicate significant differences between the two platforms, especially in "Chapter 7. Infoprint Object Attributes" on page 329. For example, Infoprint Manager for Windows NT and Windows 2000 does not support tape.

Reference Table for Path Names

AIX Path	NT or 2000 Path
/usr/lpp/psf/ps/psfonts.map	\install_path\ps\fonts.map
/usr/lpp/psf/psf/bin/db2afp	\install_path\bin\db2afp.exe
/usr/lpp/psf/db2afp/afpdfont.rc	\install_path\bin\afpdfont.rc
/usr/lib/nls/loc/iconv/ConverterName	\install_path
/usr/lpp/psf/jpeg2afp/jpeg2afp.cfg	\install_path\
/usr/lpp/psf/reslib	\install_path\reslib
/usr/lpp/afpfonts	\install_path\fontlib
/usr/lpp/psf/fontlib	\install_path\fontlib
inpexit=/usr/lpp/psf/bin/apka2e	inpexit=c:\Program Files\IBM Printing Systems\bin\apka2e, which assumes you installed in the default path
inpexit=/usr/lpp/psf/bin/asciinpe	inpexit=c:\Program Files\IBM Printing Systems\bin\asciinpe, which assumes you installed in the default path
inpexit=/usr/lpp/psf/bin/asciinp	inpexit=c:\Program Files\IBM Printing Systems\bin\asciinp, which assumes you installed in the default path
formdef=memo userlib=/usr/afp/resources	formdef=memo userlib=d:\afp\resources
formdef=memo fdeflib=/usr/lib/formdefns	formdef=memo fdeflib=d:\lib\formdefns
pagedef=memo userlib=/usr/afp/resources	pagedef=memo userlib=d:\afp\resources
pagedef=memo pdeflib=/usr/lib/pagedefns	pagedef=memo pdeflib=d:\lib\pagedefns
/usr/lpp/psf/bin/line2afp	install_path\bin\line2afp.exe
/usr/lpp/psf/bin/acif	install_path\bin\acif.exe
/usr/lpp/psf/acif/apkinp.c, apkind.c, apkres.c, apkout.c, apka2e.c, ascinnp.c	<pre>install_path\exits\acif\apkinp.c, apkind.c, apkres.c, apkout.c, apka2e.c, ascinnp.c</pre>

Introduction

/usr/lpp/psf/bin/apka2e, apkin, apkind,	install_path\bin\apka2e.dll, apkin.dll,
apkres, apkout, apka2e, asciinp, asciinpe	apkind.dll, apkres.dll, apkout.dll, apka2e.dll, asciinp.dll, asciinpe.dll
/usr/lpp/psf/acif/apkexits.h	install_path\exits\acif\apkexits.h
/usr/lpp/psf/bin/Makefile	No NT or 2000 equivalent
No AIX equivalent	install_path\exits\acif\apka2e.dsw, apkinp.dsw, apkind.dsw, apkres.dsw, apkout.dsw, apka2e.dsw, asciinp.dsw, ascinnpe.dsw (Microsoft Visual C++ 6.0 Workspaces for the user exits)
No AIX equivalent	install_path\exits\acif\apka2e.dsp apkinp.dsp apkind.dsp apkres.dsp apkout.dsp apka2e.dsp asciinp.dsp ascinnpe.dsp (Microsoft Visual C++ 6.0 Project files for the user exits)
/usr/lpp/psf/pcl2afp	install_path\pcl2afp
/usr/lpp/psf/pcl2afp/pcl2afp.cfg	install_path\pcl2afp\pcl2afp.cfg
/usr/lpp/psf/pcl2afp/custom.cfg	install_path\pcl2afp\custom.cfg
/usr/lpp/psf/pcl2afp/custom.cfg	install_path\pcl2afp\custom.cfg
/usr/lpp/psf/pcl2afp/pcl2afpd.cfg	install_path\pcl2afp\pcl2afpd.cfg
/usr/lpp/psf/pcl2afp/myfile.cfg	d:\pcl\myfile.cfg
/usr/lpp/psf/pcl2afp/gl_before.pc1 myfile.g1 /usr/lpp/psf/pcl2afp/gl_after.pcl	<pre>install_path\pcl2afp\gl_before.pcl myfile.gl install_path\pcl2afp\gl_after.pcl</pre>
/usr/lpp/psf/pcl2afp/sample.pcl	install_path\pcl2afp\sample.pcl
/usr/lpp/psf/bin/pcl2afp	install_path\bin\pcl2afpd.exe
/usr/lpp/psf/bin/pcl2afpd	install_path\bin\pcl2afpd.exe
/usr/lpp/psf/bin/ppxpcli	install_path\bin\ppxpcli.exe
/usr/lpp/psf/bin/ppxpclis	No equivalent on NT
/usr/lpp/psf/pcl2afp/pcl2afp.cfg	install_path\pcl2afp\pcl2afp.cfg
/usr/lpp/psf/pcl2afp/pcl2afpd.cfg	install_path\pcl2afp\pcl2afpd.cfg
/var/psf/pcl2afp	install_path\var\psf\pcl2afp
/usr/lpp/psf/ps2afp/ps2afp.cfg	install_path\ps2afp\ps2afp.cfg
/usr/lpp/psf/ps2afp/ps2afpd.cfg	install_path\ps2afp\ps2afpd.cfg
/usr/lpp/psf/bin/ps2afp	install_path\bin\ps2afp
/usr/lpp/psf/bin/ps2afpd	install_path\bin\ps2afpd
/usr/lpp/psf/bin/pdf2afp	install_path\bin\pdf2afp
/usr/lpp/psf/bin/ppxps2i	install_path\bin\ppxps2i
/usr/lpp/psf/bin/ps2afpi	install_path\bin\ps2afpi.vm
/usr/lpp/psf/bin/ps2afpi.vm	install_path\bin\ps2afpi
/usr/lpp/psf/bin/ppxps2	install_path\bin\ppxps2
/usr/lpp/psf/bin/ps2afp.ps	install_path\bin\ps2afp.ps
/usr/lpp/psf/bin/ps2afpe.ps	install_path\bin\ps2afpe.ps
/usr/lpp/psf/bin/fontsave	install_path\bin\fontsave
/usr/lpp/psf/psfonts.map	install_path\bin\psfonts.map
/var/psf/psfonts	install_path\var\psfonts

/usr/lpp/psf/tiff2afp/tiff2afp.cfg	install_path\tiff2afp\tiff2afp.cfg
/var/psf/podaccount.log	install_path\var\psf\podaccount.log
/var/psf/audit.log	install_path\var\psf\audit.log

Objects

Infoprint performs the management and printing or transmission of jobs by using Infoprint objects.

Object Classes

Table 1 lists the object classes that Infoprint supports. The destination class is subdivided into logical and actual destinations.

Table 1. Infoprint Objects

Object Name	Purpose
Auxiliary sheet	Represents a sheet of paper, blank or otherwise, that precedes a job, separates copies within a job, or follows a job; or a user exit program that produces output that can be printed on an auxiliary sheet or logged.
Default document	Represents default attribute values for a document within a job. Also called <i>initial value document</i> .
Default job	Represents default attribute values for a job. Also called <i>initial value job</i> .
Destination (actual)	Represents the output device that Infoprint uses to print or transmit the job. It is not the actual output device. It is a software representation of the features and capabilities of the printer or fax hardware device, or of an electronic mailing system.
	A <i>physical printer</i> is an actual destination that represents a printer device. A <i>fax destination</i> represents a fax device. An <i>email destination</i> represents an electronic mailing system.
Destination (logical)	Represents an abstract entity to which users submit jobs for printing or transmission. The logical destination provides restrictions and defaults for the job. It also verifies that associated actual destinations capable of handling the jobs exist. Once the logical destination verifies the job, Infoprint sends it to an associated queue, from which it is routed to an actual destination.
	The term <i>logical printer</i> is used for logical destinations that route jobs to physical printers.
Document	Represents a grouping of data within a job: either a printable file or a resource that is not printable by itself, for example, a font.
Job	Represents one or more documents submitted together in one request.
Log	Represents a collection of messages or message segments added to a file for data collection purposes. Infoprint uses two types of logs: error and trace.
Medium	Represents the physical material on which a job prints.

Introduction

Table 1. Infoprint Objects (continued)

Object Name	Purpose
Queue	Manages a collection of jobs that are waiting to be printed or transmitted and jobs that have been retained after processing. A queue receives jobs from one or more logical destinations and schedules and sends the jobs to actual destinations.
Resource context	Contains directory path information that is used to locate resources needed for processing a job. Resources include fonts, overlays, form definitions, page segments, and page definitions.
Server	Manages and controls the validation, routing, notification, logging, scheduling, and printing or transmission of jobs. The server applies specified defaults to jobs, validates that the destinations on the network can process the jobs, schedules jobs from queues to actual destinations, directs jobs to the actual destination, reports errors, and reports job status.
Transform	Indicates how specific document formats sent to an associated actual destination are to be transformed before printing or storing.

Object Name Restrictions

The following restrictions apply to naming Infoprint objects:

- You can specify object names up to 255 characters in length, except for the names of PSF physical printers, fax destinations, and email destinations, which you must limit to eight characters or less.
- Characters allowed in object names include uppercase A through Z, lowercase a through z, digits 0 through 9, and the special characters hyphen or dash, -, period, . , and underscore, _ . Do not start an object name with a hyphen.
- Names for servers used with SAP systems should restrict their server names to nine characters.

Object Attributes

This section has been moved to "Chapter 7. Infoprint Object Attributes" on page 329 as "Introducing Object Attributes" on page 332.

Commands

Infoprint commands act on objects. They create, modify, and delete objects, and may also return status and other information about the Infoprint objects.

Flags, Command Attributes, and Arguments

The basic Infoprint command syntax is:

command [-flag ...] [argument ...]

The *argument* targets the specific object on which the Infoprint command operates. Most commands must include an *argument*. All commands can include one or more of the following:

Flags Flags consist of a dash, - , followed by a single character. Flags either substitute for command or object attributes or modify the way Infoprint

processes a command. For example, you can use the -c flag instead of the class command attribute. Some flags have values associated with them.

Use the -x and the -X flags to enter command attributes or object attributes on the command line or to read in a file containing those attributes at a specific point in the command.

Command attributes

Use command attributes to modify the action of the command and to define the object class on which the command operates. Most of the command attributes have an associated command flag that causes the same action. You cannot use a command flag in an attributes file. You can use the command attribute in an attributes file or on the command line using the -X flag or the -x flag respectively.

When you enter an attribute and value pair, you must specify the attribute followed by the equals sign, = , followed by the value; do not include spaces between these three items unless you enclose the items in quotation marks. For example, Infoprint accepts both the class=destination and "class = destination" formats.

You must begin and end a string of multiple attribute-value pairs with double quotation marks, for example:

pdls -x "class=job requested-attributes=current-job-state" 10

Object attributes

Use object attributes to apply attribute values to the specified argument. You can use the object attribute in an attributes file or on the command line using the -X flag or the -x flag respectively.

When you enter an attribute and value pair, you must specify the attribute followed by the equals sign, = , followed by the value.

You must begin and end a string of multiple attribute-value pairs with double quotation marks, for example:

pdpr -x "document-format=ascii sides=2 plex=simplex" File1

Arguments

The argument specified in a command is the name of the object the command acts on. For servers, the argument is the name of the server. Servers contain all other objects. For some objects, you must specify the name of its server in the form ServerName:ObjectName. For other objects, the server name is optional. You must look at each command to determine the exact format allowed.

If you specify multiple arguments in one command, they must belong to the same object class.

Command Output: Headings and Style

Some commands allow you to specify whether you want the output displayed in line style, column style, or document column style, and whether you want the output displayed with or without headings. Document column (doccol) style is a variant of column style used only for jobs. It is like column style except that the attributes for the first document in the job are displayed on the same line as the job attributes, rather than on a separate line as in column style.

The following examples show the same information (the current-job-state and destination-name-requested attributes for a job, plus the document-format and copy-count attributes for the first document in the job) in the six possible combinations of headings and style:

Introduction

• Line style, with headings:

```
jw-srv:0524600000: current-job-state = held jw-srv:0524600000: destination-name-requested = jw-lp1 jw-srv:0524600000.1: document-format = ascii jw-srv:0524600000.1: copy-count = 1
```

• Line style, without headings:

• Column style, with headings:

```
        Current
        Destination

        State
        Requested

        -----
        jw-lp1
```

```
Format Copies -----ascii 1
```

· Column style, without headings:

```
held jw-lp1
```

```
ascii 1
```

• Document column style, with headings:

```
 \begin{array}{ccccc} \text{Current} & \text{Destination} \\ \text{State} & \text{Requested} & \text{Format} & \text{Copies} \\ \hline ----- & ----- \\ \text{held} & \text{jw-lp1} & \text{ascii} & 1 \\ \end{array}
```

Document column style, without headings:

```
held jw-lp1 ascii 1
```

Tips for Using Commands

Understanding the following topics can make your use of, and entry of, commands easier.

Wildcards

You can use the global character, an asterisk, * , to simplify broadcasting commands to all servers. For example, STU*: sends the command to all servers whose names begin with the letters STU. When the global character is present in the *ServerName*, Infoprint sends the command to each of the servers that match the specified criterion.

Depending on the shell you are using, you may need to enter control characters to keep the shell from interpreting the asterisk, *, before Infoprint has a chance to operate on it.

Abbreviations

This publication shows attribute names and values in their complete form. Often, you can abbreviate attribute names and values by using the first letter of each word in the name or value. For example, you can use the abbreviation **s-m-s** for the **start-message-supported** attribute, **t** for the **true** value, and specify the attribute and value pair as **s-m-s=t**.

However, sometimes specifying only the first letter in each word is ambiguous, as for the attributes **job-owner** and **job-originator**. Here, specify enough of the name

so that it is unique, as in j-ow and j-or. If the values are ambiguous, Infoprint rejects the command and issues an error message. Use abbreviated attribute names and values as appropriate.

Attributes File

You may want to predefine specific attribute and value pairs in permanent files and access them when you need those specific values within a command. These files can contain command attributes, object attributes, or both.

Creating an Attributes File:

 You can list command attributes and any initially settable or resettable object attributes in an attributes file, including the command attribute attributes. Thus, an attributes file can invoke other attributes files.

Note: If an attributes file calls itself, Infoprint issues an error.

- You can only use a file that contains initially settable attributes with the pdcreate or pdpr commands. If you include an initially settable attribute in an attributes file and use the file with the pdset or pdmod commands, Infoprint rejects the attribute and issues an error message.
- Attributes files must not contain any attributes without values.
- When creating an attributes file, consider spelling out the complete attribute names and attribute values rather than using abbreviations.
- You can use spaces between the attribute name and the equals sign to align the equals sign and values. This makes your files easier to read and maintain.
- · You can use comment lines in attributes files. The comment starts with a number sign, #, and ends at the end of line.

For example, an attributes file used to set two-sided printing and to request a specific printer model contains these lines:

```
# These are my document attributes
sides = 2
destination-models-requested = 4019 # 4019 printer only
```

Note: You can include a number sign, #, as part of an attribute value if you precede it immediately with a backslash, \#.

Using an Attributes File: Infoprint provides both a command attribute and a flag to read an attributes file into a command.

Command Attribute: -x "attributes=AttributesFileName"

You use the -x flag to specify the command attribute attributes. This attribute designates and causes Infoprint to read and use an attributes file, which contains attribute and value pairs (one or more per line), at the current point in the command. Specifying this attribute is equivalent to using the **-X** flag.

Flag: **-X** AttributesFileName

This causes Infoprint to read and use the designated attributes file containing attribute and value pairs at the current point in the command.

```
The following two examples are equivalent:
pdset -X AttrFileAD1.X Serv2-pp
pdset -x "attributes=AttrFileAD1.X" Serv2-pp
```

Introduction

Using the command attribute attributes or the **-X** flag to designate and read an attributes file has the same effect as specifying multiple attribute and value pairs using the **-x** flag. These attributes require the same syntax as those used with the **-x** flag. For example, both of the previous examples reference the following attributes file:

```
# Actual Destination Attributes File
# AttrFileAD1.X
document-formats-supported =ascii ditroff modca-p
maximum-copies-supported =3
document-types-supported =printable overlay page-segment
printer-memory =32
```

It is equivalent to the following command:

```
pdset -x "document-formats-supported=ascii ditroff modca-p
   maximum-copies-supported=3 document-types-supported=printable
   overlay page-segment printer-memory=32" Serv2-pp
```

The -X and -x flags are additive so that Infoprint uses all attributes and values. If you specify the same object attribute more than once in a command with multiple uses of the -x and -X command flags or the attributes command attribute, or a combination of them, the value read last takes precedence.

Locating an Attributes File for Infoprint Manager for AIX: If you do not specify a full path name for the attributes file, Infoprint uses the path name from the environment variable **PDPATH** to locate the attributes file. If you do not define **PDPATH** or it contains a null string, Infoprint looks in your current working directory for the attributes file.

For example, if **PDPATH** contained /usr/user/smith/ the following command: pdpr -X my attributes.X File1

would read the file /usr/smith/my_attributes.X to obtain the attribute and values.

Note: For Infoprint Manager for Windows NT and Windows 2000, you must specify the full path.

Administrative Utilities

Infoprint administrative utilities perform such tasks as setting up a minimum Infoprint configuration, starting servers, and displaying information about Infoprint messages.

Daemon Utilities for Infoprint Manager for AIX

Infoprint has some special utilities for starting daemons. Daemons are often called by the same name as the utility that starts them. For example, the daemon that receives data from MVS Download is called the **mvsprsd** daemon, or simply **mvsprsd**.

Transform Commands

Infoprint transform commands convert another data stream to the AFP data stream. You can allow Infoprint to invoke these transforms automatically, or you can invoke them yourself.

Introduction

Some transforms use options instead of flags. Like flags, options begin with a dash, - , and modify the way Infoprint processes the transform. Unlike flags, options may have more than one character following the dash.

Environment Variables for Infoprint Manager for AIX

Infoprint and AIX environment variables affect the way that Infoprint processes commands and utilities. These environment variables are summarized in "Chapter 8. Infoprint Environment Variables" on page 673.

Windows Services for Infoprint Manager for Windows NT and Windows 2000

Infoprint Manager for Windows NT and Windows 2000 uses Windows Services for many functions, including the Infoprint server, Notification, IPP, and MVS download.

Chapter 2. Infoprint Commands

This chapter describes the following Infoprint commands:

Command Name	AIX	NT and 2000
"lprafp Command: Submits Remote Jobs in Infoprint Manager for AIX" on page 13	AIX	N/A
"mkfntmap Command: Maps PostScript Fonts" on page 15	AIX	NT and 2000
"pdaccount Command: Collect Accounting Information for a Specific Time Period with Infoprint Manager for AIX" on page 17	AIX	N/A
"pdclean Command: Removes All Jobs from the Specified Object" on page 20	AIX	NT and 2000
"pdcreate Command: Creates Infoprint Objects" on page 23	AIX	NT and 2000
"pddelete Command: Deletes Infoprint Objects" on page 28	AIX	NT and 2000
"pddisable Command: Stops Destinations from Accepting Jobs and Logs from Logging" on page 32	AIX	NT and 2000
"pdenable Command: Enables Destinations to Accept Jobs and Logs to Log" on page 35	AIX	NT and 2000
"pdls Command: Lists Selected Attribute Values" on page 38	AIX	NT and 2000
"pdmod Command: Modifies Attributes of Submitted Print Jobs" on page 49	AIX	NT and 2000
"pdpause Command: Pauses Jobs, Actual Destinations, Servers, or Queues" on page 54	AIX	NT and 2000
"pdpr Command: Submits Jobs" on page 61	AIX	NT and 2000
"pdpromote Command: Advances a Job to the Top of a Queue" on page 70	AIX	NT and 2000
"pdq Command: Queries Job Status" on page 72	AIX	NT and 2000
"pdreorder Command: Reassigns Jobs" on page 77	AIX	NT and 2000

Commands

"pdresubmit Command: Resubmits Jobs" on page 79	AIX	NT and 2000
"pdresume Command: Enables Paused Objects to Resume Operation" on page 83	AIX	NT and 2000
"pdrm Command: Removes Jobs" on page 86	AIX	NT and 2000
"pdset Command: Defines Attribute Values" on page 89	AIX	NT and 2000
"pdshutdown Command: Stops Servers or Actual Destinations" on page 94	AIX	NT and 2000
"pdspace Command: Backspaces or Forward Spaces a Printer" on page 99	AIX	NT and 2000

Note: The psfstat command for displaying information about Infoprint destinations and PSF Direct receivers is documented in PSF Direct Network Configuration Guide for System/370 and the psfstat man page.

Iprafp Command: Submits Remote Jobs in Infoprint Manager for AIX

Syntax

lprafp [-n] [-o option] [-r retries] [-q delay] [-p destination] [-s server] FileName ...

Description

The lprafp command, when compiled on a UNIX client system, allows UNIX users operating on AIX 3.2.5 or higher, non-AIX systems, or non-RS/6000 systems to pass -o flag keywords to Infoprint for use in printing or transmitting remote jobs. The **-o** flags that are interpreted by Infoprint can be sent with the remote job.

You can submit a job using a shell script called LPR. When you invoke LPR with the -A flag, LPR invokes the lprafp command. lprafp passes -o keywords to Infoprint. If you invoke the LPR shell script without the -A flag, LPR invokes the operating system's standard print command.

Flags

Indicates that only error messages display when the output is processed. If -n you do not specify this flag, you receive status information on the job sent to the destination system.

-o option

Indicates Infoprint options, for example:

-oformdef=F1SAMPLE

See "Chapter 3. The -o Flag for AIX Print Commands" on page 103 for descriptions of the **-o** options.

-r {**3** | retries}

Indicates how many times the lprafp program attempts to connect with the TCP/IP line printer daemon (lpd) on the destination system. This flag defaults to three retries.

-q {10 | delay}

Indicates the retry delay in seconds. This flag defaults to ten seconds.

-p destination

Indicates the destination name on the server. This flag defaults to the value of the LPR_PRINTER environment variable.

-s server

Specifies the destination server. This flag defaults to the value of the LPR SERVER environment variable.

Arguments

Use the argument value to identify the specific files you want to submit for printing or transmission. If you specify multiple objects, separate the object names with spaces.

You can use the following arguments with the **lprafp** command:

FileName ...

Indicates the files that are to be printed or transmitted. You can specify global file characters in this argument.

Examples

Submitting a Remote Print Job

To submit two copies of /etc/motd to the logical printer named laser on server alexandria, for printing without an end sheet, enter:

LPR -A -ocopies=2 -otrailer=no -s alexandria -p laser /etc/motd

Submitting a Remote Email Job

To send the file memol to the logical destination emailbox on server alexandria, enter:

LPR -A -s alexandria -p emailbox memo1

Note: The default document associated with emailbox must specify the email-to-address attribute.

Setting Environment Variables

To set up the environment so that subsequent print requests are sent to the logical destination named alexe-lp on server alexandria, enter:

export LPR PRINTER=alexe-lp export LPR_SERVER=alexandria

(Note that server can be in dotted address format; for example 9.99.9.99)

To test that your environment variables have been set correctly, enter:

LPR -A /etc/motd

Files

/usr/lpp/psf/utils/lpr/Makefile

Generates the executable program

/usr/lpp/psf/utils/lpr/getopts.c

Source code

/usr/lpp/psf/utils/lpr/getopts.h

Source code header file

/usr/lpp/psf/utils/lpr/LPR

Shell script for print command

/usr/lpp/psf/utils/lpr/lprafp.c

Source code

/usr/lpp/psf/utils/lpr/lprafp.h

Source code header file

mkfntmap Command: Maps PostScript Fonts

Syntax

mkfntmap inputfile ... [> outputfile]

Description

The **mkfntmap** command creates a font mapping file that contains a list of the PostScript Type 1 fonts specified in the inputfiles parameter of the command and their locations.

Infoprint Manager for AIX includes the /usr/lpp/psf/ps/psfonts.map file.

Infoprint Manager for Windows NT and Windows 2000 includes the \install_path\ps\fonts.map file.

The font map file maps the AFP outline fonts to the directory in which they were installed. If you have additional PostScript fonts or you add new PostScript fonts, use the **mkfntmap** command to create a font mapping file for the new fonts after they are installed.

If you will be using the additional fonts frequently, you should add the fonts to the preload.ps file in the /usr/lpp/psf/ps directory for Infoprint Manager for AIX.

If you will be using the additional fonts frequently, you should add the fonts to the preload.ps file in the \install_path\ps directory for Infoprint Manager for Windows NT and Windows 2000.

The fonts you specify in the preload.ps file load before transform processing begins, improving the performance of the PostScript transform.

Note: With Infoprint Manager for AIX, the Courier font must exist in at least one of your font mapping files. It is included in the font mapping file, /usr/lpp/psf/ps/psfonts.map for Infoprint Manager for AIX and the \install_path\ps\fonts.map for Infoprint Manager for Windows NT and Windows 200.

Arguments

The argument value identifies the specific object to which the command applies.

The valid argument values for the **mkfntmap** command are:

inputfile ...

Specifies the name of the file or files that contain PostScript Type 1 fonts. At least one input file is required, although you can list more than one.

outputfile

Specifies the name of the font mapping file that contains the font mapping for the PostScript Type 1 fonts that were specified in the inputfiles. When the output file is created, it can be specified in the ps2afpd daemon and ps2afp command configuration files. You also can specify the outputfile name from the command line with the -F flag of the ps2afp command. If you do not specify an outputfile name, Infoprint writes the results to standard output.

mkfntmap

Examples

• To create a font mapping file of all binary fonts named atm*, which have the extension .pfb, and call it atmfonts.map, enter:

```
mkfntmap atm*.pfb > atmfonts.map
```

• To create a font mapping file of all fonts named cou*, and call it courier.map, enter:

mkfntmap cou* > courier.map

pdaccount Command: Collect Accounting Information for a Specific **Time Period with Infoprint Manager for AIX**

Syntax

```
pdaccount [-c server]
        {-t destination | user | all}
            -s StartTime] [-e EndTime]
            -f] ServerName...
```

Description

Use the pdaccount administrative command to collect summary accounting information for a specified time period in a comma delimited format about jobs processed by actual destinations on one or more servers. This information can be filed and imported into a spread sheet to calculate the cost of consumables, the usage rate of printers, the cost for each user, and so forth. You can request summary information or all available information. The summary information includes the following:

- Total pages printed by a destination or a user for a specified time period
- Total octets printed by a destination or a user for a specified time period

You can also request complete records for a specified time period.

When the **log-accounting-data** actual destination or server attributes are set to true, Infoprint Manager creates an accounting log for each destination and stores the information in the server's accounting logs subdirectory. When the accounting logs are active, Infoprint Manager records the following information:

```
actual destination name (up to 255 characters)
job owner (up to 255 characters)
global job-id without ServerName
submission-time (GMT format)
submission-time (date in server's displayable locale and time zone)
submission-time (time in server's displayable locale and time zone)
completion-time (GMT format)
completion-time (date in server's displayable locale and time zone)
completion-time (time in server's displayable locale and time zone)
pages-completed
octets-completed
data stream (first document only)
job name (up ot 255 characters)
```

For actual destinations that are unable to get pages completed from the printer, the information is obtained from the job-page-count attribute (which can be set by the user), or in some cases, Infoprint Manager determines the information by analyzing the datastream.

Note: Because of the way that Infoprint Manager pauses and cancels jobs, the totals for the pages completed could be inaccurate.

Flags

You can use the following flags with the **pdaccount** command:

pdaccount

-c server

Specifies the object class for the **pdaccount** command. Server is the only class supported for the **pdaccount** command.

-t Specifies the type of account information that you want collected:

destinationSummary information by destinationuserSummary information by job owner

all All records as logged

Attention: Requesting information for **all** accounting records can consume a lot of the server's memory since all the data is read into memory to be sent to you. If you have a lot of data to retrieve, you should consider requesting it for smaller time periods and concatenating the returned data.

For example, if you want to retrieve all the accounting records for a one month period, you could issue four **pdaccount** commands like this:

```
pdaccount -t all -s '00:00:00 03/01/00' -e '00:00:00 03/08/00' Server A >March1.accting.data pdaccount -t all -s '00:00:00 03/08/00' -e '00:00:00 03/15/00' Server A >March2.accting.data pdaccount -t all -s '00:00:00 03/15/00' -e '00:00:00 03/22/00' Server A >March3.accting.data pdaccount -t all -s '00:00:00 03/22/00' -e '00:00:00 03/31/00' Server A >March4.accting.data
```

-s StartTime

Specifies the oldest job-completion time for records to include. If this flag is not specified, defaults to the first record in the accounting log.

-e EndTime

Specifies the latest job-completion time for records to include. If this flag is not specified, defaults to the last record in the accounting log.

-f Places the results in a file in the server's directory. If specified, the results of the **pdaccount** command are filed in the server's directory where the command is processed. The file is named **accounting.summary.timestamp**, where timestamp is the time the request was performed. If -f is not specified, the results are returned to standard out or can be redirected by the user.

Argument

Use the argument value to identify the specific server or servers that you want to collect accounting information for.

You can use the following argument values with the **pdaccount** command:

ServerName

Specifies the server that you want to collect accounting information for.

Examples

Summary Information for Destinations on Server A

To request summary accounting information for the destinations on server A for the period starting at 8 AM on 12/20/99 and ending at 8 AM on 12/24/99, enter the following command:

```
pdaccount -t destination -s '08:00:00 12/20/99' -e '08:00:00 12/24/99' A
```

The information returned is similar to:

Destination, Pages Completed, Octets Completed Printer1,12997,1989787763 Printer2,2455,17676836 Printer3,86673,189808083

Summary Information for Users on All the Servers

To request summary accounting information for users on all the servers for the period starting at 8 AM on 12/20/99 and ending at 8 AM on 12/24/99, enter the following command:

```
pdaccount -t user -s '08:00:00 12/20/99' -e '08:00:00 12/24/99' *:
```

The information returned is similar to:

Owner, Pages Completed, Octets Completed gnelson@info1.penn.boulder.ibm.com, 1347, 1987763 hlava@ips1.penn.boulder.ibm.com,2455,12237676836 root@pumbaa.penn.boulder.ibm.com,86673,189808083

All Accounting Information for Destinations on Servers B and C

To request all the data (or raw data) for the destinations on servers B and C for the period starting at 8 AM on 12/20/99 and ending at 8 AM on 12/24/99, enter the following command:

```
pdaccount -t all -s '08:00:00 12/20/99' -e '08:00:00 12/24/99' B C
```

The command returns the complete accounting log records for the time period collected from all the accounting logs on the requested servers in no particular sorted order.

Attention: Requesting information for all accounting records can consume a lot of the server's memory since all the data is read into memory to be sent to you. If you have a lot of data to retrieve, you should consider requesting it for smaller time periods and concatenating the returned data.

For example, if you want to retrieve all the accounting records for a one month period, you could issue four **pdaccount** commands like this:

```
pdaccount -t all -s '00:00:00 03/01/00' -e '00:00:00 03/08/00' Server A
>March1.accting.data
pdaccount -t all -s '00:00:00 03/08/00' -e '00:00:00 03/15/00' Server A
>March2.accting.data
pdaccount -t all -s '00:00:00 03/15/00' -e '00:00:00 03/22/00' Server A
>March3.accting.data
pdaccount -t all -s '00:00:00 03/22/00' -e '00:00:00 03/31/00' Server A
>March4.accting.data
```

pdclean Command: Removes All Jobs from the Specified Object

Syntax

```
pdclean [-c ObjectClass] [-m "MessageText"]
    [-x "attribute=value ..."] [-X AttributesFileName]
    {ServerName ... | [ServerName:]DestinationName ... |
        [ServerName:]QueueName ...}
```

pdclean -h

Description

Use the **pdclean** administrative command to remove all jobs from the specified servers, logical destinations, queues, or actual destinations. If you are removing jobs from a server, Infoprint ignores any **job-retention-period** or **job-retention-period** or **job-retention-period** or **job-retention-period** or **job-retention-period** or **job-retain-until** value. If you are removing jobs from a logical destination, Infoprint removes all jobs from the queue to which the logical destination submitted the jobs. If you are removing jobs from a queue, Infoprint removes all jobs that the queue contains, regardless of which logical destination or destinations submitted the jobs to the queue.

Infoprint removes processing jobs, if the actual destination supports this.

Infoprint Manager for AIX issues a confirmation message prior to cleaning the object, unless your **PD_CONFIRM_DELETE** environment variable has a value of **no**.

Infoprint Manager for Windows NT and Windows 2000 issues a confirmation message prior to cleaning the object, unless the **Confirm Object Delete** checkbox is unchecked (which is accessed through the Infoprint Manager Management Console with **Edit->Service Configuration**).

Flags

You can use the following flags with the **pdclean** command:

-c {destination | queue | server}

Specifies the object class you want for this command. Within the valid classes, **destination** is a logical or actual destination.

Using this flag is equivalent to specifying the command attribute class.

-h Displays a command-specific help message containing information about command syntax and flags. If you use this flag with any other flag or attribute, Infoprint recognizes only the -h flag.

-m "MessageText"

Specifies the message you want associated with the specified destination, queue, or server. You can use this message to indicate the reason why you are cleaning the destination, queue, or server, or any other appropriate comments.

Using this flag is equivalent to specifying the command attribute message.

You can list this message by specifying **requested-attributes=message** with the **pdls** command.

-x "attribute=value ..."

A single attribute string, consisting of one or more attribute-value pairs.

-X AttributesFileName

Specifies the name of a file containing attribute and value pairs you want Infoprint to insert at the current point in the command.

Using this flag is equivalent to specifying the command attribute attributes.

Command Attributes

You may specify these attributes in a -x "attribute=value ..." string or in an attributes file designated with the -X AttributesFileName flag.

attributes=AttributesFileName

Specifies the designated attributes file that Infoprint reads and inserts at the current point in the command. This file contains attribute and value pairs that Infoprint uses to expand the command.

class={destination | queue | server}

Specifies the destination, queue, or server you want for this command. Within the valid classes, **destination** is a logical or actual destination.

message="MessageText"

Specifies the message you want associated with the destination, queue, or server. You can use this message to indicate the reason why you are cleaning the destination, queue, or server, or any other appropriate comments.

You can list this message by specifying **requested-attributes=message** with the **pdls** command.

Arguments

Use the argument value to specify the destination, queue, or server that you want Infoprint to clean. If you specify multiple objects, all must be of the same object class and you must separate the object names with spaces.

You can use the following arguments with the **pdclean** command:

[ServerName:]DestinationName

Specifies which destinations you want cleaned of jobs.

Cleaning an actual destination removes only those jobs that Infoprint has assigned to that actual destination.

Cleaning a logical destination removes all jobs submitted through that logical destination that Infoprint has not yet completed. Infoprint removes those jobs from the queue associated with that logical destination. Infoprint removes any jobs currently processing if the actual destination supports this.

[ServerName:]QueueName

Specifies which queues you want cleaned of jobs.

Cleaning a queue deletes all jobs that reside in that queue. Infoprint removes any jobs currently processing if the actual destination supports this.

ServerName

Specifies which servers you want cleaned of jobs.

pdclean

Cleaning a server deletes all jobs submitted to any of the logical destinations, or assigned to the actual destinations, residing in that server, including any retained jobs. Infoprint removes any jobs currently processing if the actual destination supports this.

Examples

Clean a Logical Destination

To clean logical destination Mserv-lp of all jobs, enter the command: pdclean Myserv-lp

Clean a Server

To clean server DServ1, enter the command: pdclean -c server DServ1

Clean an Actual Destination

To clean destination Mserv-pp of all jobs and to leave a message, enter the

pdclean -m "Destination Mserv-pp is down for repairs" Super1:PhysPrt2

Suggested Reading

For more information about:

• Attributes file, see "Attributes File" on page 7

pdcreate Command: Creates Infoprint Objects

Syntax

```
pdcreate [-c ObjectClass] [-g] [-m "MessageText"]
        [-r "attribute ..."] [-s StyleName]
        [-x "attribute=value ..."] [-X AttributesFileName]
        {ServerName:AuxiliarySheetName ... |
            ServerName:DefaultDocumentName ... |
            ServerName:DefaultJobName ... |
            ServerName:DestinationName ... |
            ServerName:MediumName ... |
            ServerName:QueueName ... |
            ServerName:ResourceContextName ... |
            ServerName:TransformName ... |
```

pdcreate -h

Description

Use the **pdcreate** administrative command to create Infoprint objects (except servers, logs, documents and jobs) and to set their attributes to specific values.

You can specify any initially settable or resettable attribute for an object with the **pdcreate** command. You can specify an initially settable attribute only when you create an object.

"Appendix A. Attribute-to-Object Listing" on page 695, provides a listing of all attributes by object class and "Chapter 7. Infoprint Object Attributes" on page 329, contains descriptions for each attribute by object.

Note: Infoprint creates servers and logs when the server starts. Infoprint creates documents and jobs when users submit files for printing or transmission with the **pdpr** command.

You can use the **pdcreate** command to create objects for the following object classes:

- destination (logical and actual)
- queue
- initial-value-job
- · initial-value-document
- medium
- auxiliary-sheet
- resource-context
- transform

When you create a destination, it remains in the disabled state and Infoprint cannot accept any jobs for it until you enable the destination. You must issue the **pdenable** command to enable the destinations.

An object you create with the **pdcreate** command still exists even if the server that contains it terminates normally (shutdown) or abnormally. A logical destination or queue returns to its previous state when its server restarts; an actual destination attempts to return to its previous state when its server restarts.

Flags

You can use the following flags with the pdcreate command:

-c {destination | queue | medium | initial-value-job | initial-value-document | auxiliary-sheet | resource-context | transform}

Specifies the object class you want for this command. You can only specify one class per command invocation. Using this flag is equivalent to specifying the command attribute class.

- -g Turns off headings. Using this flag is equivalent to specifying the command attribute headings=false.
- -h Displays a command-specific help message containing information about command syntax and flags. If you use this flag with any other flag or attribute, Infoprint recognizes only the -h flag.

-m "MessageText"

Specifies the message that you want associated with the object you are creating. You may indicate the reason for creating the object or to provide any other comments.

You can list this message by specifying requested-attributes=message with the pdls command. Using this flag is equivalent to specifying the command attribute message.

-r {none | brief | verbose}

Specifies the attribute values you want Infoprint to display for the specified object.

Displays no attributes. none

brief Displays a small subset of important attributes for each object.

verbose

Displays a larger subset of important attributes for each object.

Using this flag is equivalent to specifying the command attribute requested-attributes.

-s {column | doccol | line}

When combined with the -r flag or the requested-attributes command attribute, specifies the format in which you want Infoprint to display attribute information.

column

Attribute values are displayed in tabular format, so that values of the same attribute for multiple objects line up in columns.

doccol For jobs only, job attribute values and the document attribute values for the first document in the job are displayed in column format on the same line.

line Each attribute is displayed on a separate line.

Using this flag is equivalent to specifying the command attribute style.

-x "attribute=value ..."

A single attribute string, consisting of one or more attribute-value pairs.

-X AttributesFileName

Specifies the name of a file containing attribute and value pairs Infoprint inserts at the current point in the command. Using this flag is equivalent to specifying the command attribute attributes.

Command Attributes

You can specify these attributes in a -x "attribute=value ..." string or in an attributes file designated with the -X AttributesFileName flag.

attributes=AttributesFileName

Specifies the designated attributes file that Infoprint reads and inserts at the current point in the command. This file contains attribute and value pairs that Infoprint uses to expand the command.

class={destination | queue | medium | initial-value-job | initial-value-document | auxiliary-sheet | resource-context | transform}

Specifies the object class you want for this command. You can only specify one class per command invocation.

headings={true | false}

Specifies whether you want headings displayed in the output.

message="MessageText"

Specifies the message that you want associated with the object you are creating. You may indicate the reason for creating the object or provide other comments.

You can list this message by specifying **requested-attributes=message** with the **pdls** command.

requested-attributes={none | brief | verbose}

Specifies which output attributes you want Infoprint to display.

none Displays no attributes.

brief Displays a small subset of important attributes for each object.

verbose

Displays a larger subset of important attributes for each object.

style={column | doccol | line}

Specifies the presentation format you want for the displayed output.

column

Attribute values are displayed in tabular format, so that values of the same attribute for multiple objects line up in columns.

doccol For jobs only, job attribute values and the document attribute values for the first document in the job are displayed in column format on the same line.

line Each attribute is displayed on a separate line.

Arguments

Use the argument values to identify the specific object you are creating. If you specify multiple objects, separate the object names with spaces.

Note: Regardless of which object you create, you must use *ServerName*: with the **pdcreate** command.

You can use the following arguments with the pdcreate command:

Server Name: Destination Name

ServerName:QueueName

ServerName:DefaultJobName

ServerName:DefaultDocumentName

ServerName:MediumName

ServerName:AuxiliarySheet ServerName:ResourceContextName ServerName:TransformName

Examples

Create a Queue

To create the queue Serv1-p3-queue, on the server Serv1, enter the command: pdcreate -c queue Serv1:Serv1-p3-queue

Create a Logical Destination

To create the logical destination Destination3-Serv1 in the server Serv1 and specify the queue you want associated with that destination, enter the command: pdcreate -x "associated-queue=Serv1-p3-queue" Serv1:Destination3-Serv1

Create an Actual Destination

To create the PSF TCP/IP-attached actual destination Destination3 in the server Serv1 and specify the queue you want associated with that destination, enter the command:

```
pdcreate -x "destination-realization=actual
   associated-queue=Serv1-p3-queue attachment-type=tcpip
   destination-model=Infoprint4000-ID5-ID6
   destination-tcpip-internet-address=martha.boulder.ibm.com
  destination-tcpip-port-number=5001" Serv1:Destination3
```

Create a Default Document

To create the default document LP3ivd, enter the command:

```
For Infoprint Manager for AIX:
pdcreate -c initial-value-document -m "Created 04/01/1997"
   -x "copy-count=1 document-format=line-data page-definition=MyPageDef
   resource-context-page-definition=/usr/lpp/psf/mypdlib sides=1
   descriptor='IVD for LogPrt3'" Serv1:LP3ivd
```

```
For Infoprint Manager for Windows NT and Windows 2000:
pdcreate -c initial-value-document -m "Created 04/01/1997"
   -x "copy-count=1 document-format=line-data page-definition=MyPageDef
   resource-context-page-definition=\install path\psf\mypdlib sides=1
   descriptor='IVD for LogPrt3'" Serv1:LP3ivd
```

Create a Default Job

To create the default job MyJobTemplate using the attributes specified in the attributes file named MyJobAttributes.X, enter the command:

```
pdcreate -c initial-value-job -X MyJobAttributes.X
server3:MyJobTemplate
```

Create a Medium

To create a medium representing a transparency with the identifier my-clear-medium in the server Serv1, enter the command:

```
pdcreate -c medium -x "descriptor='letter size, common transparency'
  medium-type=transparency medium-color=transparent medium-size=letter
  medium-sides=1 medium-dimensions=215.9:355.6" Serv1:my-clear-medium
```

Create a Medium in All Active Servers

To create the medium A4-blue in all active servers, enter the command: pdcreate -c medium *:A4-blue

Create a Queue and its Notification Profile

To create a notification profile for Serv1-p3-queue in server Serv1, enter the command:

pdcreate -c queue -x "notification-profile={event-identifiers=job-modified queue-state-changed delivery-method=message event-comment='This is a modification of job or status event' delivery-address=dave@cowboy locale=En_US}" Serv1:Serv1-p3-queue

Suggested Reading in Hardcopy

For information about:

- Attributes file, see "Attributes File" on page 7
- Headings and style, see "Command Output: Headings and Style" on page 5
- Attributes for Infoprint objects, see "Chapter 7. Infoprint Object Attributes" on page 329.
- For introductory information about object attributes and their use with commands, see "Introducing Object Attributes" on page 332, which includes information on non-settable, initially settable, and resettable attributes.

Suggested Reading Online

For Infoprint Manager for AIX, to view information about all supported attributes for Infoprint, enter the command:

man pd att

This displays a list of files by object from which you can select the attribute listing you want.

pddelete Command: Deletes Infoprint Objects

Syntax

```
pddelete [-c ObjectClass] [-m "MessageText"]
        [-x "attribute=value ..."] [-X AttributesFileName]
        {ServerName ... | ServerName:AuxiliarySheetName ... |
            ServerName:DefaultDocumentName ... |
            ServerName:DefaultJobName ... |
            ServerName:DefaultJobName ... |
            ServerName:DestinationName ... |
            ServerName:MediumName ... |
            ServerName:MediumName ... |
            ServerName:PostureContextName ... |
            ServerName:TransformName ... |
            ServerName:TransformName:TransformName:TransformName:TransformName:TransformName:TransformName:T
```

Description

Use the pddelete administrative command to delete Infoprint objects.

Infoprint Manager for AIX issues a confirmation message before deleting objects, unless your PD_CONFIRM_DELETE environment variable is set to **no**.

Infoprint Manager for Windows NT and Windows 2000 issues a confirmation message prior to cleaning the object, unless the **Confirm Object Delete** checkbox is unchecked (which is accessed through the Infoprint Manager Management Console with **Edit->Service Configuration**).

Infoprint does not delete jobs with a non-zero value for the **job-retain-until** or **job-retention-period** attribute (either previously set or set with this command) until the retention deadline arrives or the retention period expires.

Flags

You can use the following flags with the **pddelete** command:

```
-c {destination | job | queue | medium | initial-value-job | initial-value-document | auxiliary-sheet | resource-context | transform | server} Specifies the object class you want for this command. Using this flag is equivalent to specifying the command attribute class.
```

-h Displays a command-specific help message containing information about command syntax and flags. If you use this flag with any other flag or attribute, Infoprint recognizes only the **-h** flag.

```
-m "MessageText"
```

Specifies the message you want to associate with the object that you want to delete. You can use this message to indicate the reason for deleting the object or to provide any other comments.

If the command operates on a job with a non-zero value for the **job-retention-period** or **job-retain-until** attribute (either previously set or

set with this command), you can list this message by specifying requested-attributes=job-message-from-administrator with the pdls command. Otherwise, Infoprint deletes this message with the object and you cannot retrieve it. If you do not specify -m, the message already stored with the object remains unchanged and Infoprint deletes it as previously described.

Using this flag is equivalent to specifying the command attribute message.

-r JobRetentionPeriod

You can only use this flag if the object class is **job**. Infoprint rejects the command if you use this flag with any other class.

If the job has a retention period or retention deadline, you must specify this flag with a zero (0) value to delete the job. If not specified, Infoprint uses the present retention period or retention deadline for the job.

Using this flag is equivalent to specifying the object attribute **job-retention-period**.

-x "attribute=value ..."

A single attribute string, consisting of one or more attribute-value pairs.

-X AttributesFileName

Specifies the name of a file containing attribute and value pairs you want Infoprint to insert at the current point in the command.

Using this flag is equivalent to specifying the command attribute attributes.

Command Attributes

You may specify these attributes in a -x "attribute=value ..." string or in an attributes file designated with the -X AttributesFileName flag.

attributes=*AttributesFileName*

Specifies the designated attributes file that Infoprint reads and inserts at the current point in the command. This file contains attribute and value pairs that Infoprint uses to expand the command.

class={destination | job | queue | medium | initial-value-job | initial-value-document | auxiliary-sheet | resource-context | transform | server} Specifies the object class you want for this command.

message="MessageText"

Specifies the message you want to associate with the object you want to delete. You can use this message to indicate the reason for deleting the object or to provide any other comments.

If the command operates on a job with a non-zero value for the **job-retention-period** or **job-retain-until** attribute (either previously set or set with this command), you can list this message by specifying **requested-attributes=job-message-from-administrator** with the **pdls** command. Otherwise, Infoprint deletes this message with the object and you cannot retrieve it.

If you do not specify the **message** attribute, the message stored with the object remains unchanged and Infoprint deletes it as previously described.

Arguments

Use the argument value to identify the specific object you want to delete. If you specify multiple objects, separate the object names with spaces.

pddelete

You can use the following arguments with the **pddelete** command:

ServerName

You must remove all jobs contained within this server before you can delete it.

ServerName: Auxiliary Sheet Name

You cannot delete this auxiliary sheet if any of the actual destinations that reference it are enabled.

ServerName:DefaultDocumentName

You cannot delete this default document if any of the logical destinations that reference it are enabled.

ServerName:DefaultJobName

You cannot delete this default job if any of the logical destinations that reference it are enabled.

LocalJobID or GlobalJobID

Infoprint deletes a job based on the specified value in its **job-retention-period** or **job-retain-until** attribute.

Notes:

- 1. You can identify your own jobs by either the local job ID or the global job ID. You must identify other users' jobs by the global job ID.
- 2. In DCE installations, you do not need permission to delete your own jobs. You must have **write** permission for the server in order to delete other users' jobs. By default, only operators and administrators have this permission.
- 3. In installations without DCE, by default, end users do not have permission to use the **pddelete** command. They cannot delete even their own jobs.

ServerName:MediumName

You cannot delete this medium if any of the actual destinations that reference it are enabled.

[ServerName:]DestinationName

You must remove all the jobs from an actual destination before you can delete it.

[ServerName:]QueueName

You must disable all logical destinations associated with the queue before you can delete the queue. You must remove all jobs (including paused jobs) from the queue before you can delete the queue.

ServerName:ResourceContextName

You cannot delete this resource context if any of the actual destinations that reference it are enabled.

ServerName:TransformName

There is no restriction.

Examples

Delete a Job Using a Local ID

To delete job 5, enter the command:

pddelete -c job 5

Delete Logical Destinations

To delete logical destinations srA-1p11 and srA-1p15, enter the command: pddelete srA-lp11 srA-lp15

Delete a Default Job

To delete the default IVJ_2 from the server DivServ2, enter the command: pddelete -c initial-value-job DivServ2:IVJ_2

Delete a Server

To delete the server Serv1, enter the command: pddelete -c server Serv1

Suggested Reading

For information about:

• Attributes file, see "Attributes File" on page 7

pddisable Command: Stops Destinations from Accepting Jobs and Logs from Logging

Syntax

```
pddisable [-c ObjectClass] [-m "MessageText"]
         [-x "attribute=value ..."] [-X AttributesFileName]
         {ServerName ... | ServerName:LogName ... |
         [ServerName:]DestinationName ... |
        [ServerName:]QueueName ...}
```

pddisable -h

Description

Use the **pddisable** administrative command to stop actual destinations or logical destinations from accepting jobs, or to stop logs from logging data.

When you disable a destination, it does not accept jobs submitted with pdpr or pdresubmit commands. The destination still accepts other commands. All previously submitted jobs and currently processing jobs continue unaffected.

Notes:

- 1. Use the pdenable command to enable a destination to accept jobs again and to enable the logging function of a log again.
- 2. Use the pddisable and pdenable commands to prevent or allow input to the object. Use the **pdpause** and **pdresume** commands to prevent or allow output from the object.

Flags

You can use the following flags with the **pddisable** command:

-c {destination | log | queue | server}

Specifies the object class you want for this command. Within the valid classes, queue disables all associated logical destinations, destination is for a logical or actual destination, and server disables all destinations in the server.

Using this flag is equivalent to specifying the command attribute class.

-h Displays a command-specific help message containing information about command syntax and flags. If you use this flag with any other flag or attribute, Infoprint recognizes only the -h flag.

-m "MessageText"

Specifies the message you want associated with the destination, log, queue, or server. You can use this message to indicate the reason for disabling the object or to provide any other comments.

If you do not specify the -m flag, the message already stored with the object remains unchanged.

When you issue a command against a server, Infoprint propagates the message to the message attribute of the destinations residing in the server. Infoprint does not change the server message attribute. When you issue a command against a queue, Infoprint propagates the message to the message attribute of the logical destinations associated with the queue. Infoprint does not change the queue **message** attribute.

You can list this message by specifying **requested-attributes=message** with the **pdls** command. Using this flag is equivalent to specifying the command attribute **message**.

-x "attribute=value ..."

A single attribute string, consisting of one or more attribute-value pairs.

-X attributes file name

Specifies the name of a file containing attribute and value pairs you want inserted at the current point in the command.

Using this flag is equivalent to specifying the command attribute attributes.

Command Attributes

You may specify these attributes in a -x "attribute=value ..." string or in an attributes file designated with the -X AttributesFileName flag.

attributes=AttributesFileName

Specifies the designated attributes file that Infoprint reads and inserts at the current point in the command. This file contains attribute and value pairs that Infoprint uses to expand the command.

class={destination | log | queue | server}

Specifies the object class you want for this command. Within the valid classes, **queue** disables all associated logical destinations, **destination** is for a logical or actual destination, and **server** disables all destinations in the server.

message="MessageText"

Specifies the message you want to associate with the destination, log, queue, or server. You can use this message to indicate the reason for disabling the object or to provide any other comments.

If you do not specify this attribute, the message already stored with the object remains unchanged.

When you issue a command against a server, Infoprint propagates the message to the **message** attribute of the destinations residing in the server. Infoprint does not change the server **message** attribute.

When you issue a command against a queue, Infoprint propagates the message to the **message** attribute of the logical destinations associated with the queue. Infoprint does not change the queue **message** attribute.

You can list this message by specifying **requested-attributes=message** with the **pdls** command.

Arguments

Use the argument value to identify the specific object you want to disable. If you specify multiple objects, separate the object names with spaces.

You can use the following arguments with the **pddisable** command:

ServerName:LogName

Specifies the log you want to disable. Disabling a log stops it from logging data.

[ServerName:]DestinationName

Specifies the destination you want to disable. Disabling a destination stops

pddisable

it from accepting print or transmission requests. Any jobs currently assigned to an actual destination continue processing.

[ServerName:]QueueName

Specifies the queue you want to disable. Disabling a queue disables all of the logical destinations associated with that queue.

ServerName

Specifies the server you want to disable. Disabling a server disables all destinations residing in the server.

Examples

Disable a Logical Destination

To disable logical destination Serv1-lp on server Serv1, enter: pddisable Serv1-lp

Infoprint does not require the server name.

Disable an Actual Destination

To disable actual destination Serv1-pp on server Serv1, enter: pddisable Serv1-pp

Infoprint does not require the server name.

Disable All Destinations in a Server

To disable the logical and actual destinations contained in the server ServG1 and assign a message to the destinations, enter:

pddisable -c server -m "Unavailable due to testing" ServG1

Disable All Logical Destinations Associated with a Queue

To disable the logical destinations associated with the queue production-q1 on server servera, enter:

pddisable -c queue production-q1

Infoprint does not require the server name.

Suggested Reading

For information about:

Attributes file, see "Attributes File" on page 7

pdenable Command: Enables Destinations to Accept Jobs and Logs to Log

Syntax

```
pdenable [-c ObjectClass] [-m "MessageText"]
    [-x "attribute=value ..."] [-X AttributesFileName]
    {ServerName ... | ServerName:LogName ... |
        [ServerName:]DestinationName ... |
        [ServerName:]QueueName ...}
```

pdenable -h

Description

Use the **pdenable** administrative command to enable the logging function of logs or to enable logical destinations or actual destinations to accept jobs.

Notes:

- 1. Use the **pdenable** and **pddisable** commands to allow or prevent input to an object. Use the **pdresume** and **pdpause** commands to allow or prevent output from the object.
- 2. To stop destinations from accepting jobs, use the **pddisable** command.
- 3. To stop logs from logging data, use the **pddisable** command.

Flags

You can use the following flags with the pdenable command:

-c {destination | log | queue | server}

Specifies the object class you want for this command. Within the valid classes, **queue** enables all associated logical destinations, **destination** is for a logical or actual destination, and **server** enables all destinations in that server.

Using this flag is equivalent to specifying the command attribute class.

-h Displays a command-specific help message containing information about command syntax and flags. If you use this flag with any other flag or attribute, Infoprint recognizes only the **-h** flag.

-m "MessageText"

Specifies the message you want to associate with the destination, log, queue, or server you want to enable. You can use this message to indicate the reason for enabling the object or to provide any other comments. If you do not specify the **-m** flag, the message already stored with the destination, log, queue, or server remains unchanged.

When you issue the command against a server, Infoprint propagates the message to the **message** attribute of the destinations residing in that server. Infoprint does not change the server **message** attribute.

When you issue the command against a queue, Infoprint propagates the message to the **message** attribute of the logical destinations associated with the queue. Infoprint does not change the queue **message** attribute.

You can list this message by specifying **requested-attributes=message** with the **pdls** command.

pdenable

Using this flag is equivalent to specifying the command attribute **message**.

-x "attribute=value ..."

A single attribute string, consisting of one more attribute-value pairs.

-X attributes file name

Specifies the name of a file containing attribute and value pairs you want Infoprint to insert at the current point in the command.

Using this flag is equivalent to specifying the command attribute attributes.

Command Attributes

You can specify these attributes in a -x "attribute=value ..." string or in an attributes file designated with the -X AttributesFileName flag.

attributes=AttributesFileName

Specifies the designated attributes file that Infoprint reads and inserts at the current point in the command. This file contains attribute and value pairs that Infoprint uses to expand the command.

class={destination | log | queue | server}

Specifies the object class you want for this command. Within the valid classes, queue enables all associated logical destinations; destination is for a logical or actual destination; and server enables all destinations in that server.

message="MessageText"

Specifies the message you want to associate with the destination, log, queue, or server that you want to enable. You can use this message to indicate the reason for enabling the object or to provide any other comments. If you do not specify the message attribute, the message already stored with the destination, log, queue, or server remains unchanged.

When you issue the command against a server, Infoprint propagates the message to the **message** attribute of the destinations residing in that server. Infoprint does not change the server **message** attribute.

When you issue the command against a queue, Infoprint propagates the message to the message attribute of the logical destinations associated with the queue. Infoprint does not change the queue **message** attribute.

You can list this message by specifying requested-attributes=message with the **pdls** command.

Arguments

Use the argument value to identify the specific object you want to enable. If you specify multiple objects, separate the object names with spaces.

You can use the following arguments with the **pdenable** command:

ServerName:LogName

Specifies the log you want to enable. Enabling a log allows it to begin accepting input (logging).

[ServerName:]DestinationName

Specifies the destination you want to enable. When first created, destinations are in the disabled state. You cannot enable destinations unless

pdenable

you associate them with an existing queue. Any other objects referenced by the destination must also exist. These are:

- For logical destinations
 - Default jobs
 - Default documents
- For actual destinations
 - Media
 - Auxiliary-sheets
 - Resource-contexts

[ServerName:]QueueName

Specifies the queue you want to enable. When you issue the **pdenable** command against a queue, Infoprint attempts to enable all of its associated logical destinations.

ServerName

Specifies the server you want to enable. When you issue the **pdenable** command against a server, Infoprint attempts to enable all of its destinations.

When a server initializes again after being shut down, whether the destinations are either enabled or disabled depends on:

- The state of the destination when the system was shut down
- · The ability of the server to communicate with its associated queue

Examples

Enable Logical Destinations

To enable logical destinations Serv1-lp and draft-lp on server Serv1, enter: pdenable Serv1-lp draft-lp

Enable All Destinations in a Server

To enable all logical and actual destinations contained in the server ServG1, enter the command:

pdenable -c server ServG1

Suggested Reading

For information about:

• Attributes file, see "Attributes File" on page 7

pdls Command: Lists Selected Attribute Values

Syntax

pdls -h

Description

Use the **pdls** command to request that Infoprint display selected attribute values for one or more jobs or other Infoprint objects.

- By default, Infoprint creates a filter when listing jobs that only allows you to see your jobs. The jobs have a predefined value for the filter that is equal to the job attribute **user-name**; this value is your login identity when you submit a job. You can add to this filter to further restrict the jobs for which Infoprint returns information.
- You must suppress the default filter by using the -U flag or turn off all filtering with the -F flag to see more than your own jobs.
- If you only specify the *ServerName* as the command argument, Infoprint displays the attribute values for all objects belonging to the object class you specify.
- In general, you can only list the attributes of the object class you are requesting. However, you can view attributes of intial-value-jobs (IVJs) and inital-value-documents (IVDs) associated with a logical destination through the logical destination.
- You can list the attribute values for specific jobs by using the local ID or the global ID. You must have submitted the job to use the local ID.

Notes:

- 1. There is a situation when you must use the global ID. If the Infoprint communications daemon responsible for the mapping of local ID-to-global ID values is not available, this can prevent Infoprint from tying the local ID to the global ID. If this situation exists, you must use the global ID, the name of the server, or an argument specification using global characters.
- 2. There is a possible situation that can occur if your administrator has set the **PDIDTABLE** environment variable to a low value, for example 10. You submit a series of jobs during a short time span such that the number of jobs you have in process is larger than the value set, say 14. You will have two jobs with the local IDs of 1, 2, 3, and 4. However, Infoprint no longer associates the first four jobs with a local ID because those local IDs now belong to the 11th, 12th, 13th, and 14th jobs. Therefore, you must use the global ID to take action on any of the first four jobs.

Flags

You can use the following flags with the pdls command:

-c {job | auxiliary-sheet | document | initial-value-document | initial-value-job | log | medium | destination | queue | resource-context | transform | server} Specifies the object class of the object whose attributes you want to list. All object classes are valid.

Using this flag is equivalent to specifying the command attribute class.

-f "FilterCriteria"

Specifies the filter criteria you want to use in selecting from the candidate objects. Among the candidate objects, Infoprint returns only those matching the filter expression. See the command attribute **filter**, for filter expression details.

Using this flag is equivalent to specifying the command attribute filter.

- -F Turns off all filtering, both specified and default. See the -U flag for suppressing only the default.
- **-g** Turns off headings.

Using this flag is equivalent to specifying the command attribute **headings=false**.

- **-h** Displays a command-specific help message containing information about command syntax and flags. If you use this flag with any other flag or attribute, Infoprint recognizes only the **-h** flag.
- -j Use this flag to display only job attributes.

-r {brief | verbose | archive | "attribute ..." | all | none}

Specifies the group of attributes that you want to display for the specified job, auxiliary sheet, document, default document, default job, log, medium, destination, queue, resource-context, or server.

brief Displays a small subset of important attributes for each object.

verbose

Displays a larger subset of important attributes for each object.

archive

Writes only initially settable and resettable attributes to an archive file (see "Create an Archive File" on page 47).

attributes ...

Displays the attributes you specify.

all Displays all attributes.

none Displays no attributes.

If you specify more than one of these values, Infoprint displays all the attributes requested.

Using this flag is equivalent to specifying the command attribute requested-attributes.

-R Displays information for retained jobs only.

Using this flag is equivalent to specifying the command attribute retained-jobs-only.

-s {column | doccol | line}

Specifies the format in which you want Infoprint to display the attributes.

column

Attribute values are displayed in tabular format, so that values of the same attribute for multiple objects line up in columns. This is the default for **-r brief** and **-r verbose**.

doccol For jobs only, job attribute values and the document attribute values for the first document in the job are displayed in column format on the same line.

<u>line</u> Each attribute is displayed on a separate line. This is the default for **-r** all, **-r** "attribute ...:", and **-r** archive.

Using this flag is equivalent to specifying the command attribute **style**.

-U Suppresses the default user-name filter.

-x "attribute=value ..."

Consists of a single attribute string, containing one or more attribute-value pairs.

-X AttributesFileName

Specifies the name of the file containing attribute and value pairs you want Infoprint to insert at the current point in the command.

Using this flag is equivalent to specifying the command attribute attributes.

Command Attributes

You can specify these attributes in a -x "attribute=value ..." string or in an attributes file designated with the -X AttributesFileName flag.

attributes=*AttributesFileName*

Specifies the designated attributes file that Infoprint reads and inserts at the current point in the command. This file contains attribute and value pairs that Infoprint uses to expand the command.

class={job | auxiliary-sheet | document | initial-value-document | initial-value-job | log | medium | destination | queue | resource-context | transform | server}

Specifies the object class of the object whose attributes you want listed. All object classes are valid.

filter="FilterCriteria"

Specifies the selection criteria you want Infoprint to use in order to select a subset from the candidate objects (if you request attribute values for multiple objects). A filter is a logical expression consisting of relations of attributes to attribute values. Among the objects you specify, Infoprint returns only objects whose attribute values match the filter expression.

You can only use attributes for the object class (job, auxiliary-sheet, document, initial-value-document, initial-value-job, log, medium, destination, queue, resource-context, transform, or server) that you specify in the command. The filter may contain an attribute other than one of those you are requesting.

Table 2. Attribute Operators for Filters

Operation	Operator	Strings	Integers	Time Format
Equal	==	Yes	Yes	Yes
Match first part of a value	=*	Yes	Yes	Yes
Match last part of a value	*=	Yes	Yes	Yes
Match any part of a value; such as a sub-string	*=*	Yes	Yes	Yes
Attribute present (any value)	==*	Yes	Yes	Yes

Note: When you test for attribute presence, Infoprint evaluates the filter item as true when the attribute has a **value**, not just when the attribute exists. You may need a false value to satisfy the requirement, as long as the false value conforms to the general syntax.

Match	~=	Yes	No	No
approximately;				
for				
case-insensitive				
sub-string				

Notes:

- 1. An approximate match occurs when at least half of the target string, regardless of starting position, matches the filter value.
- 2. A case-insensitive match occurs when the target string may have a mix of upper- and lower-case characters, but the characters do match.

Match a value greater than that specified	>	No	Yes	Yes
Match a value less than that specified	<	No	Yes	Yes

This list shows the filter syntax:

- 1. A filter item consisting of an attribute name, operator, and value. Table 2 shows the operators and the data formats you can use to separate the attribute and value.
- 2. In Table 2, the attribute-present operation consists of an attribute name followed by the equality operator followed by an * in place of an attribute value. For example:
 - -f "media-ready==*"

If the attribute has no value, Infoprint evaluates the filter item as false. Infoprint evaluates the filter item as true if the attribute has any assigned value.

3. Infoprint can compare each attribute in a filter item to only one attribute value. To compare an attribute to more than one value, or to filter more than one attribute, separate the filter items with one of the following operators:

The AND operator ("&&")

FilterItem && FilterItem

The expression evaluates to true only if both filter items evaluate to true.

The OR operator ("| | ")

FilterItem | | FilterItem

The expression evaluates to true if either of the filter items evaluate to

4. To evaluate a filter item as false, use the NOT operator before the filter item and enclose the filter item in parentheses.

Note: With Infoprint Manager for AIX, depending on the shell you are using, you may need to place quotation marks before and after the parentheses.

The NOT operator! ! (FilterItem)

If the filter item evaluates to true, the expression is false.

If the filter item evaluates to false, the expression is true.

5. When you use multiple logical operators in a filter, Infoprint evaluates them in an order of precedence. You can override the order of precedence by using parentheses, ().

Note: Depending on the shell you are using, you may need to place quotation marks before and after the parentheses. See Table 3 for the order of precedence.

Table 3 summarizes the filter syntax. The table lists the operators in the order of precedence from highest to lowest.

Table 3. Filter Syntax

Operators	Placement
Parentheses: ()	Around filter items
Relational operators: > <	Between attribute and value
Equality operators: ==	Between attribute and value
String matching: =* *= *=* ~=	Between attribute and value
NOT Operator: !	Before (filter-item) only
AND operator: &&	Between two filter items
OR operator: 11	Between two filter items

headings= {true | false}

Specifies whether you want the output displayed with or without headings.

message-count=number

When you request the **log-messages** log attribute, this specifies the number of previous messages you want to see starting from the last message logged. The value you can specify for number can be an integer from 1 through 2147483647.

Use this command attribute in conjunction with the log-messages log attribute to query for error log information. For example:

pdls -c log -r log-messages -x "message-count=4" Serv1:

displays the last four messages contained in the error log for server Serv1.

requested-attributes={brief | verbose | archive | "attribute ...:" all | none} Specifies the group of attributes you want to display for the specified job, auxiliary-sheet, document, default document, default job, log, medium, destination, queue, resource-context, or server object.

brief Displays a small subset of important attributes for each object.

verbose

Displays a larger subset of important attributes for each object.

archive

Writes only initially settable and resettable attributes to an archive file (see "Create an Archive File" on page 47).

attribute ...

Displays the attributes you specify.

all Displays all attributes.

none Displays no attributes.

If you specify more than one of these values, Infoprint displays all the attributes requested.

retained-jobs-only= {true | false}

Displays information for retained jobs only.

style={column | doccol | line}

The format in which you want the attributes displayed.

column

Attribute values are displayed in tabular format, so that values of the same attribute for multiple objects line up in columns. This is the default for **requested-attributes=brief** and **requested-attributes=verbose**.

doccol For jobs only, job attribute values and the document attribute values for the first document in the job are displayed in column format on the same line.

<u>line</u> Each attribute is displayed on a separate line. This is the default for requested-attributes=all, requested-attributes="attribute ...:", and requested-attributes=archive.

when=now

When you specify **when=now** with object class destination, the Infoprint Server returns its current information regarding the destinations instead of performing SNMP queries to get any updates. If you have many SNMP destinations, the use of this command attribute improves the performance of your **pdls** request.

For example, to list the brief attributes of all the destinations in Server1 and request that Server1 does not make SNMP queries to get the latest information but just returns its most current information, use the following command:

pdls -c dest -xwhen=now Server1:

Arguments

Use the argument value to identify the specific object whose attributes you want to display. If you specify multiple objects, separate the object names with spaces.

You can use the following arguments with the **pdls** command:

LocalJobID[.DocNumber]
GlobalJobID[.DocNumber]

ServerName: Auxiliary Sheet Name ServerName:DefaultDocumentName ServerName:DefaultJobName ServerName:LogName ServerName:MediumName [ServerName:]DestinationName [ServerName:]QueueName ServerName:ResourceContextName ServerName:TransformName ServerName:

Note: When you only specify *ServerName*: as the argument of the command (without an object name), Infoprint returns the attribute values for all of the objects within the object class that you specify for that server and that meet the filter criteria.

Examples

List Full Attribute Information for a Document

To display attribute information for the first document in a job with a local ID of 13, enter the command:

```
pdls -c document -r all 13.1
```

List Minimum Information for a Document

To find the minimum information (document number, format, and file name) about the second document in a job with a local ID of 13, enter the command:

```
pdls -c document 13.2
```

List Selected Attributes for a Queue

To list the values of the brief attributes and the backlogged attribute for the queue Charlie-q, enter the command:

```
pdls -c queue -r "brief backlogged" Charlie-q
```

Infoprint displays information similar to the following:

```
Charlie-q: queue-name
                           = Charlie-q
                       = ready
Charlie-q: queue-state
Charlie-q: associated-server = Charlie
Charlie-q: backlogged
                           = false
```

List Document Formats Supported by Destinations

To display the document formats supported by the logical and actual destinations in Serv1, enter the command:

```
pdls -c destination -r document-formats-supported -s line Serv1:
```

Infoprint displays information similar to the following:

```
Serv1-lp: document-formats-supported =
Serv1-pp: document-formats-supported = ascii
                                        dbcs-ascii
                                        ditroff
                                        line-data
                                        modca-p
                                        pdf
                                        postscript
Srv1-pp2: document-formats-supported = ascii
                                        dbcs-ascii
                                        ditroff
                                        line-data
```

List the retention-period Defaulted by a Logical Destination and the Name of the intial-value-job Being Used

To list the retention-period defaulted by a logical destination and the name of the initial value job being used, enter the command:

```
pdls -c destination -r retention-period,destination-initial-value-job Dserv-lp
```

Infoprint displays information similar to the following:

```
Dserv-lp:job-retention-period=1:00
Dserv-lp:destination-initial-value-job=retain
```

Filter Destinations by Attribute with Infoprint Manager for AIX

To determine the logical destinations and actual destinations that support the selected attributes on any server, enter the command:

```
pdls -c destination -f "content-orientation-supported==landscape &&
    plexes-supported==tumble && sides-supported==2"
    -r "destination-realization associated-queue" \*:
```

Note: Including the backslash before the global character prevents the Korn shell from interpreting the * as a filename wildcard. Infoprint displays information similar to the following:

```
Serv3-lp: destination-realization = logical Serv3-lp: associated-queue = Serv3-q Serv4-lp: destination-realization = logical Serv4-lp: associated-queue = Serv4-q Serv3-pp: destination-realization = actual Serv3-pp: associated-queue = Serv3-q Serv4-pp: destination-realization = actual Serv4-pp: associated-queue = Serv4-q
```

Filter Jobs by Attribute with Infoprint Manager for AIX

To list all jobs that have requested more than one copy and that Infoprint has assigned to actual destination mysrv-pp, enter the command:

```
pdls -U -f "copy-count>1 && destination-assigned==mysrv-pp" "*:"
```

Note: Placing the quotation marks before the global character and after the colon prevents the Korn shell from interpreting the * as a filename wildcard.

Filter Jobs by User Name (Include a User)

To list all jobs owned by the user named Smith, enter this command:

```
pdls -f "job-owner==Smith" -U Serv1:
```

Filter Jobs by User Name (Exclude a User)

To list all jobs not owned by the user named Smith, enter the command: pdls -f "!(job-owner==Smith)" -U Serv1:

Filter Jobs by User Name (Substring) with Infoprint Manager for

To list jobs owned by users with a given substring in their names (substring matching) use one of the following filters with the **pdls** command:

• Initial string match:

```
pdls -U -f "job-owner=*Jones" Serv1:
```

Any substring match:

```
pdls -U -f "job-owner*=*one" Serv1:
```

Final string match:

```
pdls -U -f "job-owner*=nes" Serv1:
```

All of these commands return jobs owned by Jones.

Note: These examples use the Korn shell.

Filter Jobs by User Name (Approximate Match) with Infoprint Manager for AIX

To list jobs owned by all users with a name close to Jones (an approximate match), enter the command:

```
pdls -U -f "job-owner = jones" Serv1:
```

Note: This example uses the Korn shell.

Display the Server Associated with a Destination

To query for the name of the server containing logical destination draft-lp, enter the command:

```
pdls -c destination -r associated-server draft-lp
```

Infoprint displays information similar to the following:

```
draft-lp: associated-server=Serv1
```

List the Attributes Specified in a Default Document

To query for the attributes specified in the default document spl7ivd contained in Serv7, enter the command:

```
pdls -c initial-value-document -r all Serv7:spl7ivd
```

Infoprint displays information similar to the following:

```
spl7ivd: carriage-control-type
spl7ivd: chars
spl7ivd: content-orientation
spl7ivd: initial-value-document-identifier = spl7ivd
spl7ivd: associated-server = Serv7
spl7ivd: logical-destination-ready
                                     = Serv7-lp
spl7ivd: copy-count
                                      = 2
                                      = 2
spl7ivd: sides
spl7ivd: document-format
                                      = line-data
```

Note: The list that Infoprint returns contains all possible attributes for a default document (those without values and those with values).

List All Job Attributes

To list all attributes of jobs 10 and 12, enter the command:

```
pdls -r all 10 12
```

List Brief Job Attributes

To list just the brief job attributes of jobs 10 and 12, enter the command: pdls -j 10 12

Display Status of All Jobs

To list the status of all jobs you have submitted to the default logical destination, Dserv-lp, enter the command:

```
pdls -f "destination-name-requested==Dserv-lp" Serv1:
```

Infoprint displays information similar to the following:

Job	ID	Name	Current State	9	Destination Requested	Destinations Assigned
4	Sp1X:1099222204	Wkly-report	processing	0	Dserv-lp	Dserv-pp
5	SplX:1114222205	Test-report	processing	0	Dserv-lp	Laser-pp
6	Sp1X:1224222206	Trip-report	pending	2	Dserv-lp	
1	SplX:0988222201	Dept-memo12	retained		Dserv-lp	

Display Status of All Pending Jobs

To list the job status of all pending jobs submitted to the default logical destination, Dserv-lp, enter the command:

```
pdls -f "destination-name-requested==Dserv-lp &&
    current-job-state==pending" Serv1:
```

Infoprint displays information similar to the following:

Job	ID		Current State	9	Destination Requested	Destinations Assigned
6	SplX:1224222206	Trip-report	pending	2	Dserv-lp	

List the Brief Attributes of a Logical Destination

To list the **brief** attributes of logical destination Dserv-lp, enter the command: pdls -c destination Dserv-lp

Infoprint displays information similar to the following:

```
Destination Realization Enabled Queue
-----
Dserv-lp logical true Dserv-q
```

With Infoprint Manager for AIX, if you do not specify a destination name, Infoprint displays the brief attributes of all the destinations that share the same server with your default logical destination (as defined by your **PDPRINTER** environment variable).

List Document Formats Supported by a Destination

To list the document formats supported by the actual destination srv37-pp in the line style with headings, which is the default style for an attribute list, enter the command:

```
pdls -c destination -r document-formats-supported srv37-pp
```

Infoprint displays information similar to the following:

Create an Archive File

To create an archive file for a server and store it in a file, enter the command: pdls -c server -r archive Serv1 > Serv1.archive

Suggested Reading in Hardcopy

For information about:

- Global character support for server names, see "Wildcards" on page 6
- Attributes file, see "Attributes File" on page 7
- Headings and style, see "Command Output: Headings and Style" on page 5
- Attributes for Infoprint objects, see "Chapter 7. Infoprint Object Attributes" on page 329
- For introductory information about object attributes and their use with commands, see "Introducing Object Attributes" on page 332, which includes information on non-settable, initially settable, and resettable attributes.

Suggested Reading Online for Infoprint Manager for AIX

To view information about all supported attributes for Infoprint, enter the command:

pdls

man pd_att

This displays a list of files by object from which you can select the attribute listing you want.

pdmod Command: Modifies Attributes of Submitted Print Jobs

Syntax

pdmod -h

Description

Use the **pdmod** command to modify the values of job and document attributes of previously submitted jobs.

You may specify any resettable job and document attributes. See "Attributes for Documents and Default Documents" on page 464 and "Attributes for Jobs and Default Jobs" on page 542 for descriptions of all job and document attributes.

You can only modify preprocessing, pending, held, paused, or retained jobs. In general, you cannot modify processing or printing jobs. The only exception is if you modify only **job-hold=true**, the job will be paused, modified, and resumed.

Modifying an existing job may affect the scheduling of the job.

Table 4 lists the four modification operators.

Table 4. pdmod Operators

Operator	Syntax	Description
Replace	attribute=value	Replaces the entire value of the attribute attribute with <i>value</i> or, if not already present, adds the attribute-value pair to the job.
Add values	attribute+=value	Adds the value <i>value</i> to the attribute <i>attribute</i> . You cannot add values to single-valued attributes. An add request that duplicates values on a multi-valued attribute has no effect on the job.
Remove values	attribute-=value	Removes the value <i>value</i> from the attribute <i>attribute</i> . A remove request for a nonexistent value has no effect on the object. A remove request for the last or only value of an attribute is equivalent to a reset-to-default request.
Reset to default	attribute==	Sets the attribute <i>attribute</i> to the default values according to the job-defaulting hierarchy. If you supply values with a reset request, Infoprint ignores them.

If you do not specify a value with a replace, add, or remove request, Infoprint issues an error and rejects the request to change the attribute value for the object.

Note: If Infoprint does not accept a modification, Infoprint rejects the whole request and the job continues as before.

pdmod

Use the global job identifier to identify jobs belonging to another person. If you use DCE, you must have **write** permission for the server to modify other people's jobs.

Flags

You can use the following flags with the **pdmod** command:

-g Turns off headings.

Using this flag is equivalent to specifying the command attribute **headings=false**.

-h Displays a command-specific help message containing information about command syntax and flags. If you use this flag with any other flag or attribute, Infoprint recognizes only the -h flag.

-m "MessageText"

Specifies the message you want to store in the job-message-from-administrator attribute. You can use the message to give the reason why you are modifying the job or to provide any other comments. If you do not specify the -m flag, the message already stored with the job remains unchanged.

You can list this message by specifying requested-attributes=job-message-from-administrator with the pdls command.

Using this flag is equivalent to specifying the command attribute message.

-n CopyCount

Specifies the number of document copies.

Using this flag is equivalent to specifying the object attribute **copy-count**.

-r {none | brief | verbose}

Specifies the attribute values you want to display for the specified object.

none Displays no attributes.

brief Displays a small subset of important attributes for each object.

verbose

Displays a larger subset of important attributes for each object.

Using this flag is equivalent to specifying the command attribute requested-attributes.

-s {column | doccol | line}

When combined with the **-r** flag or the **requested-attributes** command attribute, specifies the format in which you want Infoprint to display the attributes.

column

Attribute values are displayed in tabular format, so that values of the same attribute for multiple objects line up in columns.

doccol For jobs only, job attribute values and the document attribute values for the first document in the job are displayed in column format on the same line.

line Each attribute is displayed on a separate line.

Using this flag is equivalent to specifying the command attribute **style**.

-t JobName

Specifies the new name you want for the job.

Using this flag is equivalent to specifying the object attribute **job-name**.

-x "attribute=value ..."

Consists of an attribute string, containing one or more attribute-value pairs. Prefix the attribute value with the replace operator, =, to replace a value, with the add-values operator, +=, to add a value, or the remove-values operator, -=, to remove a value. Use the reset-to-default operator, ==, with no attribute value to set the attribute to its default value.

-X AttributesFileName

Specifies the name of a file containing attribute and value pairs you want Infoprint to insert at the current point in the command.

Using this flag is equivalent to specifying the command attribute attributes.

Command Attributes

You can specify these attributes in a -x "attribute=value ..." string or in an attributes file designated with the -X AttributesFileName flag.

attributes=AttributesFileName

Specifies the designated attributes file that Infoprint reads and inserts at the current point in the command. This file contains attribute and value pairs that Infoprint uses to expand the command.

headings={true | false}

Specifies if you want Infoprint to display headings on the output.

message="MessageText"

Specifies the message you want to store in the job-message-from-administrator attribute. You can use the message to give the reason why you are modifying the job or to provide any other comments. If you do not specify the message attribute, the message already stored with the job remains unchanged.

You can list this message by specifying requested-attributes=job-message-from-administrator with the pdls command.

requested-attributes={none | brief verbose}

Specifies which attributes you want displayed.

none Displays no attributes.

brief Displays a small subset of important attributes for each object.

verbose

Displays a larger subset of important attributes for each object.

style={column | doccol | line}

Specifies the presentation format that you want for the displayed output.

column

Attribute values are displayed in tabular format, so that values of the same attribute for multiple objects line up in columns.

doccol For jobs only, job attribute values and the document attribute values for the first document in the job are displayed in column format on the same line.

line Each attribute is displayed on a separate line.

Arguments

Use the argument value to identify the specific object that you want to modify. If you specify multiple objects, separate the object names with spaces.

LocalJobID or GlobalJobID

Specifies the local or global job identifier.

Examples

Modify Content Orientation

To modify the job with a local ID of 10 and change the orientation to landscape, enter the command:

pdmod -x "content-orientation=landscape" 10

Modify Job Hold Condition

To modify the job attribute **job-hold** to **false** for job 10 so that Infoprint can schedule the job (previously submitted with job-hold set to true), enter the command:

pdmod -x "job-hold=false" 10

Modify Job Comment

To modify the job attribute job-comment to Test Results 100 for job 10, enter the

pdmod -x "job-comment='Test Results 100'" 10

Modify the Number of Sides that Print

To modify the document attribute sides to specify that all documents in the job with global identifier DivSpool2:1011222243 should print on both sides, enter the command:

pdmod -x "sides=2" DivSpool2:1011222243

Add a Destination Location Request

To add a destination location request to job 10, enter the command:

pdmod -x "destination-locations-requested+='bldg.10 room 1-15'" 10

Remove a Destination Location Request

To remove a destination location request from job 10, enter the command:

pdmod -x "destination-locations-requested-='bldg.25 room 3-22'" 10

Remove All Destination Location Requests

To remove all destination locations requested from job 10, enter the command:

pdmod -x "destination-locations-requested==" 10

Combining Modifications

To modify job 17, by changing the content-orientation and removing the hold on the job, enter the command:

pdmod -x "content-orientation=landscape job-hold=false" 17

Suggested Reading in Hardcopy

For information about:

- Attributes files, see "Attributes File" on page 7
- Headings and style, see "Command Output: Headings and Style" on page 5
- Job defaulting-hierarchy, see "pdpr Command: Submits Jobs" on page 61
- Job attributes, see "Attributes for Jobs and Default Jobs" on page 542
- Document attributes, see "Attributes for Documents and Default Documents" on page 464

pdmod

· For introductory information about object attributes and their use with commands, see "Introducing Object Attributes" on page 332, which includes information on non-settable, initially settable, and resettable attributes.

Suggested Reading Online

To view information about job attributes, enter the command: man pd_att_job

To view information about document attributes, enter the command: man pd_att_document

pdpause Command: Pauses Jobs, Actual Destinations, Servers, or Queues

Syntax

```
pdpause [-c destination] [-m "MessageText"] [-n]
        [-x "attribute=value ..."] [-X AttributesFileName]
        [-w {now | after-current-copy | after-current-job}]
        [ServerName:]DestinationName ...
pdpause -j [-m "MessageText"]
        [-x "attribute=value ..."] [-X AttributesFileName]
        [-w {now | after-current-copy}] [ServerName:]DestinationName ...
pdpause -c job [-m "MessageText"] [-x "attribute=value ..."]
        [-X AttributesFileName] [-w {now | after-current-copy}]
        {LocalJobID ... | GlobalJobID ...}
pdpause -c queue [-m "MessageText"] [-x "attribute=value ..."]
        [-X AttributesFileName] [ServerName:]QueueName ...
pdpause -c server [-m "MessageText"] [-n]
        [-x "attribute=value ..."] [-X AttributesFileName]
        [-w {now | after-current-copy | after-current-job}]
        ServerName ...
pdpause -h
```

Description

Use the **pdpause** administrative command to pause an object that holds jobs or to pause a job.

You can pause these objects:

- Jobs that are
 - pending
 - held
 - ripping
 - imposing
 - processing
 - printing
- Actual destinations

Note: You cannot pause PSF upload-TCP/IP-attached physical printers or PSF upload-SNA-attached physical printers.

- Queues
- Servers (pauses all of the queues and actual destinations contained in a server)

To resume a paused object, use the **pdresume** command.

Note: Use the **pdpause** and **pdresume** commands to prevent or allow output from the object. Use the **pddisable** and **pdenable** commands to prevent or allow input to the object.

Flags

You can use the following flags with the pdpause command:

-c {destination | queue | job | server}

Specifies the object class you want to pause. Within the valid classes, **destination** is an actual destination.

Using this flag is equivalent to specifying the command attribute class.

- -h Displays a command-specific help message containing information about command syntax and flags. This flag and any other flag are mutually exclusive (if you use it with any other flag or attribute, Infoprint recognizes only the -h flag).
- -j This flag is only valid when you use it with object-class **destination**. Use this flag to pause the currently printing job on the specified actual destination. The actual destination must be a physical printer, not a fax destination or an email destination.

-m "MessageText"

Specifies the message you want to associate with the specified destination, queue, job, or server that you are pausing. You can use this message to indicate the reason that you are pausing the object or to provide any other comments.

When pausing a server, Infoprint propagates the message to the **message** attribute of the actual destinations and queues residing in the server.

If the command operates on a destination or a queue, you can list this message by specifying **requested-attributes=message** with the **pdls** command.

When the command operates on a job, the specified text becomes the value of the **job-message-from-administrator** attribute. You can list this message by specifying **requested-attributes=job-message-from-administrator** with the **pdls** command.

If you do not specify the **-m** flag, the message already stored with the destination, queue, job, or server remains unchanged.

Using this flag is equivalent to specifying the command attribute message.

-n Causes the destination to perform an NPRO (move the last printed page to the stacker). Using this flag is equivalent to specifying the command attribute non-process-runout=true.

This flag is valid only with object class **destination** or **server**. It is not valid with the **-j** flag. It is valid only for PSF physical printers and for servers containing them.

-w {now | after-current-copy | after-current-job}

Specifies when to pause the destination, job, or server. If you specify:

now and the paused object is a:

destination

The destination pauses as soon as possible. How long this takes depends on the output device.

job The job pauses as soon as possible. If the job is processing or printing, how long this takes depends on the output device.

pdpause

server The server pauses as soon as possible. How long this takes depends on the output devices represented by the destinations in the server.

after-current-copy

and the paused object is a:

destination

The destination pauses after the current copy of the current job finishes printing.

iob The job pauses after the current copy finishes printing.

server The server pauses after the current copy of the current job on each actual destination in the server finishes printing.

This value is valid only for PSF physical printers, for jobs printing on PSF physical printers, and for servers containing PSF physical printers.

after-current-job

and the paused object is a:

destination

The destination pauses after the current job finishes printing.

server The server pauses after the current job on each actual destination in the server finishes printing.

This value is not valid for jobs, including jobs paused with the -i flag. It is valid only for PSF physical printers and for servers containing PSF physical printers.

Specifying this flag is equivalent to specifying the command attribute when.

-x "attribute=value ..."

A single attribute string, consisting of one or more attribute-value pairs.

-X AttributesFileName

Specifies the name of a file containing attribute and value pairs you want inserted at the current point in the command.

Using this flag is equivalent to specifying the command attribute attributes.

Command Attributes

You can specify these attributes in a -x "attribute=value ..." string or in an attributes file designated with the -X AttributesFileName flag.

attributes=AttributesFileName

Specifies the designated attributes file that Infoprint reads and inserts at the current point in the command. This file contains attribute and value pairs that Infoprint uses to expand the command.

class={destination | queue | job | server}

Specifies the object class that you want to pause. Within the valid classes, destination is an actual destination.

message="MessageText"

Specifies the message that you want to associate with the specified

destination, queue, job, or server that you are pausing. You can use this message to indicate the reason you are pausing the object or to provide any other comments.

When pausing a server, Infoprint propagates the message to the **message** attribute of the actual destinations and queues residing in the server. Infoprint does not change the server **message** attribute.

If the command operates on a destination or a queue, you can list this message by specifying **requested-attributes=message** with the **pdls** command.

When the command operates on a job, the specified text becomes the value of the **job-message-from-administrator** attribute. You can list this message by specifying **requested-attributes=job-message-from-administrator** with the **pdls** command.

If you do not specify the **message** attribute, the message already stored with the destination, queue, job, or server remains unchanged.

non-process-runout={true | false}

Specifies whether the destination should perform an NPRO (move the last printed page to the stacker). This attribute is valid only with object class **destination** or **server**. It is not valid with the **-j** flag. It is valid only for PSF physical printers and for servers containing them.

when={now | after-current-copy | after-current-job}

Specifies when to pause the destination, job, or server. If you specify:

now and the paused object is a:

destination

The destination pauses as soon as possible. How long this takes depends on the output device.

job The job pauses as soon as possible. If the job is processing or printing, how long this takes depends on the output device.

server The server pauses as soon as possible. How long this takes depends on the output devices represented by the destinations in the server.

after-current-copy

and the paused object is a:

destination

The destination pauses after the current copy of the current job finishes printing.

job The job pauses after the current copy finishes printing.

server The server pauses after the current copy of the current job on each actual destination in the server finishes printing.

This value is valid only for PSF physical printers, for jobs printing on PSF physical printers, and for servers containing PSF physical printers.

after-current-job

and the paused object is a:

destination

The destination pauses after the current job finishes printing.

server The server pauses after the current job on each actual destination in the server finishes printing.

This value is not valid for jobs, including jobs paused with the **-j** flag. It is valid only for PSF physical printers and for servers containing PSF physical printers.

Arguments

Use the argument value to identify the specific object that you want to pause. If you specify multiple objects, all of the objects must belong to the same class and you must separate the object names with spaces.

You can use the following arguments with the pdpause command:

LocalJobID... or GlobalJobID...

Specifies the jobs that you want to pause as determined by a local job identifier or global job identifier. If you use DCE, by default, only administrators have the authority to pause jobs. If you do not use DCE, by default, administrators and operators have the authority to pause jobs but end users do not. Therefore, in most cases someone other than the job submitter will pause a job and must identify it by the global job ID. Job submitters who do have authority to pause jobs can identify their own jobs by the local job ID.

The following actions take place when you cause Infoprint to pause:

A ripping or imposing job:

- The job stops. If the first pages of the job have started to print or transmit while the last pages are ripping or imposing, the job is treated like a printing job.
- The job state changes to paused.
- The destination remains available to accept work.
- Infoprint can assign other jobs to the destination.

A processing or printing job:

- The job stops.
 - If you specify -w=after-current-copy, the job stops after the current copy finishes printing.
 - Otherwise, the job stops as soon as possible. How long this takes depends on the type of output device printing or transmitting the job.
- The job state changes to paused.
- The destination remains available to accept work.
- Infoprint can assign other jobs to the destination.

A pending job:

Infoprint prevents scheduling of the job but does not affect any destination.

A held job:

Infoprint prevents the job from becoming pending, even if you or Infoprint removes the reason for the job hold. For example, the specified **job-print-after** time expires.

Paused jobs remain in the queue until someone resumes or cancels them. Infoprint allows modification of a paused job, but you cannot resubmit the job until you issue a **pdresume** command for the job.

Note: If you modify a paused job, it resumes at the beginning, not at the point where it paused.

[ServerName:]DestinationName

Specifies the destinations you want to pause. The action taken depends on whether you include the -i flag in the command.

Without the -j flag:

- The destination stops.
 - If you specify -w=after-current-job, the destination stops after the current job finishes printing.
 - If you specify **-w=after-current-copy**, the destination stops after the current copy finishes printing.
 - Otherwise, the destination stops as soon as possible. How long this takes depends on the type of output device.
- Infoprint changes the destination state to paused.
- Infoprint leaves the job state unchanged; the job is still assigned to the destination.

The actual destination still accepts jobs from its associated queue up to the maximum-concurrent-jobs limit, but does not print them.

With the -j flag:

• The job now printing on the destination stops.

Note: The actual destination must be a physical printer, not a fax destination or an email destination.

- If you specify -w=after-current-copy, the job stops after the current copy finishes printing.
- Otherwise, the job stops as soon as possible. How long this takes depends on the type of printer device.
- Infoprint changes the job state to paused.
- The destination remains available to accept work.
- Infoprint can assign other jobs to the destination.

The actual destination may still accept jobs from its associated queue and process them.

Note: You cannot pause logical destinations because they do not hold jobs.

[ServerName:]QueueName

Specifies the queues you want to pause.

Pausing a queue halts the distribution of jobs from the queue to the actual destinations associated with the queue. Pausing a queue does not prevent it from accepting jobs from its associated logical destinations.

ServerName

Specifies the server on which you want the command to operate. A server does not have a paused state. Issuing the command against a server pauses all queues and actual destinations contained within the server.

Examples

Pause an Actual Destination

To pause actual destination molly-pp and include a message as to why you are pausing the destination, enter the command:

pdpause -m "Toner is low, refilling" molly-pp

Pause a Currently Printing Job

To pause the currently printing job on destination molly-pp, enter the command: pdpause -j molly-pp

Pause a Queue

To pause the queue Div1Q2, enter the command:

pdpause -c queue Div1Q2

Pause All Queues in a Server

To pause all of the queues in server DivServ1, enter the command: pdpause -c server DivServ1

Pause an Actual Destination after the Current Copy with NPRO

To pause actual destination molly-pp after the current copy and move the last printed sheet to the stacker, enter the command:

pdpause -w after-current-copy -n molly-pp

Suggested Reading

For information about:

• Attributes file, see "Attributes File" on page 7

pdpr Command: Submits Jobs

Syntax

Description

Use the **pdpr** command to submit jobs to logical destinations. Each job can contain multiple printable documents and, for jobs sent to PSF physical printers, fax destinations, or email destinations, any number of resources.

With Infoprint Manager for AIX, the target destination name defaults to the value of the **PDPRINTER** environment variable. You can override the default by specifying the name of another logical destination using the **-d** or **-p** flag or the job attribute **destination-name-requested**.

When the server accepts the job request, Infoprint assigns a unique global ID (job identifier) and a local ID to it. Only the job submitter can use the local ID. The job submitter can use either the global ID or the local ID in subsequent commands, such as **pdmod**, **pdrm**, or **pdls**. Anyone else who accesses the job, such as an administrator, must use the global ID.

Infoprint sets the values for job and document attributes from these possibilities:

1. Values specified in the **pdpr** command using the **-x** "attribute=value ..." flag or the **-X** AttributesFile flag.

Note: If multiple values for the same attribute are specified in the **pdpr** command, Infoprint uses the last value read, except for those attributes that can have different values for different documents in the same job.

- 2. The values of a default job specified by the job attribute **initial-value-job** or the values for a default document specified by the document attribute **initial-value-document**.
- 3. The values of a default job specified by the **destination-initial-value-job** attribute or the values of a default document specified by the **destination-initial-value-document** attribute of the logical destination to which the user submitted the job.
- 4. Server defaults for required attribute values not specified through the previous methods.

You must be authorized to submit jobs to the specified destination if the logical destination is protected (the value of its authorize-jobs attribute is true).

If the server cannot locate an actual destination (associated with the requested logical destination) supporting the job and document attributes, Infoprint rejects the job.

Flags

You can use the following flags with the **pdpr** command:

-d *TargetDestinationName*

The target destination can be either the actual destination name if logical-destination-assigned is set on the actual destination or the logical destination name to which you want to submit the job.

With Infoprint Manager for AIX, if you do not specify this flag (or the equivalent -p flag), Infoprint uses the PDPRINTER environment variable to determine the destination.

Using this flag is equivalent to specifying the destination-name-requested attribute.

-f FileName

Specifies files you want included in the job. Use this flag only with file identifiers that are not placed at the end of the command. For example, to print all pages of file1 and pages 3 through 6 of file2, enter:

```
pdpr -f file1 -x page-select=3:6 file2
```

This flag is not valid for tape input.

Turns off headings. -g

> Using this flag is equivalent to specifying the command attribute headings=false.

- -h Displays a command-specific help message containing information about command syntax and flags. If you use this flag with any other flag or attribute, Infoprint recognizes only the -h flag).
- -1 Creates symbolic links to the job files rather than making temporary copies when used with Infoprint Manager for AIX. When Infoprint assigns the job to an actual destination, the server uses the links to the job files to locate the original files and copies them (if needed) at that time. This can be useful when printing large files or jobs.

- 1. Use this flag only for jobs submitted from AIX to an AIX server; you cannot use it when submitting jobs from a workstation client or to a Windows server.
- 2. You must use caution when using this flag because:
 - a. Depending on when you make changes to the files and when the server prints them, the printed output may or may not reflect the changes.
 - b. If you delete the file before the job prints or while the job is printing, the printed output may fail or be incomplete.
 - c. When you are using an AIX client and sending a pdpr command with PDHOST or PD_SOCKET, you cannot specify the -1 flag.

-n {**1** | *CopyCount*}

Specifies the number of document copies that you want to print.

If you do not specify the -n flag, the copy count defaults to one (1).

Using this flag is equivalent to specifying the document attribute **copy-count**=*CopyCount*.

Note: You cannot use the **-n** flag or the document attribute **copy-count** if the job contains inline resources. Use the job attribute **results-profile** instead.

-N {message | email | job-log | none}

Specifies the delivery method that you want to use for notification of job events for this job.

Note: Using this flag and its value causes Infoprint to generate a **notification-profile** attribute value for this job.

-p *TargetDestinationName*

The target destination can be either the actual destination name if **logical-destination-assigned** is set on the actual destination or the logical destination name to which you want to submit the job.

With Infoprint Manager for AIX, if you do not specify this flag (or the equivalent **-d** flag), Infoprint uses the **PDPRINTER** environment variable to determine the destination.

Using this flag is equivalent to specifying the **destination-name-requested** attribute.

-r {none | brief | verbose}

Identifies the job attribute values that you want to display for the job just created.

none Displays no attributes.

brief Displays a small subset of important attributes for the job.

verbose

Displays a larger subset of important attributes for the job.

Using this flag is equivalent to specifying the command attribute requested-attributes.

-s {column | doccol | line}

When combined with the -r flag or the requested-attributes command attribute, specifies the format in which you want the attributes displayed.

column

Attribute values are displayed in tabular format, so that values of the same attribute for multiple objects line up in columns.

doccol For jobs only, job attribute values and the document attribute values for the first document in the job are displayed in column format on the same line.

line Each attribute is displayed on a separate line.

Using this flag is equivalent to specifying the command attribute **style**.

-T TapeDevice

With Infoprint Manager for AIX, specifies the name of the tape device from which **pdpr** reads the input file. Specify the name without prefixing **/dev**, for example, -T rmt0.

-t JobName

Specifies the name you want to assign to the job.

Using this flag is equivalent to specifying the job attribute **job-name**.

-x "attribute=value ..."

Consists of a single attribute string containing one or more attribute-value pairs.

Any document attribute defined with the -x flag affects all files whose names follow that -x flag on the command line, unless you reset that attribute.

To reset an attribute to the default value, specify *AttributeName*==. For example, to reset the **document-type** attribute to its default value, printable, specify

document-type==

-X AttributesFileName

Specifies the name of a file containing attribute and value pairs that you want Infoprint to insert at the current point in the command.

Any document attribute in the file defined with the -X flag affects all files whose names follow that -X flag on the command line, unless you reset that attribute.

To reset an attribute to the default value, specify AttributeName==. For example, to reset the **document-type** attribute to its default value, **printable**, specify

document-type==

Using this flag is equivalent to specifying the command attribute attributes.

-Z InputFileName

Specifies the name of a file containing command flags, command attributes, or the names of files to be printed, that you want Infoprint to insert at the current point in the command. Use this flag when the command is too long to fit on the command line.

Entering a dash (hyphen) causes the command to read from standard input (STDIN). If you use this flag, it must occur at the end of the command after any other flags or command attributes.

Command Attributes

You can specify these attributes in a -x "attribute=value ..." string or in an attributes file designated with the -X AttributesFileName flag.

attributes=AttributesFileName

Specifies the designated attributes file that Infoprint reads and inserts at the current point in the command. This file contains attribute and value pairs that Infoprint uses to expand the command.

Any document attribute in the attributes file affects all files whose names follow that attributes command attribute on the command line, unless you reset that attribute.

To reset an attribute to the default value, specify *AttributeName*==. For example, to reset the **document-type** attribute to its default value, printable, specify

document-type==

headings={true | false}

Specifies whether you want Infoprint to display headings with the attributes.

requested-attributes={none | brief | verbose}

Specifies which job attributes you want Infoprint to display.

none Displays no attributes.

brief Displays a small subset of important attributes for each object.

verbose

Displays a larger subset of important attributes for each object.

style={column | doccol | line}

Specifies the presentation format in which you want Infoprint to display the output.

column

Attribute values are displayed in tabular format, so that values of the same attribute for multiple objects line up in columns.

doccol For jobs only, job attribute values and the document attribute values for the first document in the job are displayed in column format on the same line.

line Each attribute is displayed on a separate line.

Job and Document Attributes Used with the Command

There are two types of object attributes used with the **pdpr** command, per-job and per-document. You can specify these attributes in a **-x** "attribute=value ..." string or in an attributes file designated with the **-X** AttributesFileName flag. You can specify any initially settable or resettable job or document attribute with the **pdpr** command. See"Attributes for Documents and Default Documents" on page 464 and "Attributes for Jobs and Default Jobs" on page 542 for descriptions of job and document attributes.

Per-Job Attributes

Per-job attributes apply to the job as a whole and may occur anywhere in the **pdpr** command.

Per-Document Attributes

If you specify some document attributes before the first document (file) on the command line, those attributes apply to all documents (files) you specify for this job. If you specify a different document attribute between the first and second document (files), that attribute applies to the second document and any following document you specify for this job. This progression of attributes to files continues until the last document (file) specified.

The value for a given attribute must be the same for all the documents in the job except for those listed in "Per-Document Attribute Listing" on page 467. Even for those attributes, the value must be the same for all documents in the job if

- The job is submitted from tape
- · The documents are in ASCII format

Arguments

Use the argument value to identify the name or tape position of a file that you want to print. If you specify multiple file identifiers, separate the file identifiers with spaces. Each file becomes a document within the job. Unless you end the

command with the - flag, indicating that pdpr is to read from standard input, you must place at least one file identifier without the -f flag at the end of the command.

FileName ...

Specifies the document that you want to print. Precede the file name by any per-document attributes.

[\]#FileNumber ...

With Infoprint Manager for AIX, when you submit a file from tape, instead of the file name you can specify the position of the file on the tape. The number sign (#) indicates a file number and the backslash (\) escapes the number sign. If your shell does not have a special meaning for the number sign, you can omit the backslash.

If you specify a multi-document job, and if Infoprint cannot support one or more of the documents within the job, Infoprint rejects the job and issues an error message.

Examples for Infoprint Manager for AIX

Print a Job on the Default Logical Destination

To submit the file File1 to your default logical destination, enter the commands: pdpr File1

Print a Multi-Document Job

To submit the files File1 and File2 to the default logical destination, enter the command:

pdpr File1 File2

Fax a Job

To submit the cover sheet faxcover and the file Memo1 to the logical destination Serv1-faxout for faxing to fax number 1-709-123-4567, enter the command:

```
-x "document-type=printable" Memo1
```

Email a Job

To submit the file report.ps to the logical destination mailbox for electronic mailing to julia@kingston, enter the command:

```
pdpr -d mailbox -x "email-to-address=julia@kingston
   subject-text='Status Report'" report.ps
```

Print Multiple Copies of Each Document in a Job

To submit a job to the default logical destination and to specify two copies of each file in the job, enter one of these commands:

```
pdpr -n 2 Title Contents Body1 Body2 Append
```

```
pdpr -x "copy-count=2" Title Contents Body1 Body2 Append
```

Infoprint prints two copies of Title, followed by two of Contents, and so forth for each file in the job.

Note: You cannot use the -n flag or the document attribute copy-count if the job contains inline resources. Use the job attribute results-profile instead.

Print Multiple Copies of a Job

To submit the job to the default logical destination and to specify two copies of the complete job, enter the command:

```
pdpr -x "results-profile=::2" Title Contents Body1 Body2 Append
```

Infoprint prints a single copy of each file in the job, and then prints a second set in the same manner.

Print Multiple Copies of Documents and Jobs

To submit a job to the default logical destination and to specify two copies of the complete job with each copy of the job containing three copies of each file, enter the command:

```
pdpr -n 3 -x "results-profile=::2" Title Contents Body1 Body2 Append
```

Infoprint prints three copies of Title, followed by three copies of Contents and so until the first copy of the job completes. Then Infoprint prints a second set in the same manner.

Specify Job Name

To submit the file File1 to your default logical destination and to specify the job name, enter the command:

```
pdpr -t CmdRef File1
```

Print a Duplexed Job

To submit the file File1 to the default logical destination and to specify normal-duplexed printing, enter the command:

```
pdpr -x "sides=2 plex=simplex" File1
```

Specify Document Format

To submit the file PSFile2 to the default logical destination and to specify a document format of ASCII, enter the command:

```
pdpr -x "document-format=ascii" PSFile2
```

Request Status

To submit the file File1 to the default logical destination and to receive brief status information, enter the command:

```
pdpr -r brief File1
```

Infoprint displays information similar to the following:

Job	ID	Name	Current State	Destination Requested	Destinations Assigned
8	sp15:0754100002	File1	pending	LogPrt1	

Delay Printing

To submit the file BigJob to the default logical destination and to delay printing until after 6:30 p.m. on May 2, 1997, enter the command:

```
pdpr -x "job-print-after='18:30:00 05/02/97'" BigJob
```

Specify a Symbolic Link

To submit the file BigJob to a logical destination LogPrt4 without copying the file, enter the command:

```
pdpr -p LogPrt4 -1 BigJob
```

Specify Job Discard Time

To submit the file BigJob to the default logical destination and to specify that Infoprint is to discard the job if it has not printed by 5:00 p.m., enter the

pdpr -x "job-discard-time=17:00:00" BigJob

Retain a Job

To submit the file File1 to the default logical destination requesting feedback of job attributes (brief group), and to specifying a retention period of 90 minutes so you can print more copies after you have looked at the first copy, enter the command:

pdpr -r brief -x "job-retention-period=90" File1

Note the job number (local ID) so you can use that number when you want to print more copies within the time allotted.

Specify Default Job and Document

To submit the file File1 to the default logical destination and use the job attribute values specified in the default job ivj23 and the document attribute values specified in the default document ivd44, enter the command:

pdpr -x "initial-value-document=ivd44 initial-value-job=ivj23" File1

Specify Attributes Files for a Job

To submit the file File5 to the default logical destination and to specify the two attributes files default.att and special.att, enter the command:

pdpr -X default.att -X special.att File5

Specify Different Attribute Values for Different Documents

To submit the files File5, File6, and File7 to the default logical destination and to specify that:

- Each document starts on a new sheet of paper
- You want to print pages 11 through 20 of File5, all pages of File6, and all pages of File7
- Each document has a different estimated page count

enter the command:

```
pdpr -x "start-on-new-sheet=true page-select=11:20 page-count=10"
  -f File5 -x "page-select== page-count=3" -f File6
 -x "page-count=19" File7
```

Override an Attribute Value in an Attributes File

To submit the file File1 to the default logical destination and override the value of 2 for the **sides** attribute specified in a given attributes file, enter the command:

```
pdpr -X default.att -x "sides=1" File1
```

Request Feedback Concerning the Job as Each Event Happens

To submit the file File1 to the default logical destination and to have all possible event notifications sent to you by electronic mail, enter the command:

```
pdpr -x "notification-profile={event-identifiers=job-modified
class-job-problem class-job-attention delivery-method=electronic-mail}" File1
```

Print Files from Tape

To print the second and third files on the tape mounted on tape device rmt0, enter: pdpr -T rmt0 \#2 \#3

Examples for Infoprint Manager for AIX and Infoprint Manager for Windows NT and Windows 2000

Print a Job on a Specified Logical Destination

To submit the file File1 to the logical destination fred-lp, enter the command: pdpr -d fred-lp File1

Print a Job on a Specified Actual Destination

To submit the file File5 for printing on actual destination draft-pp, enter the command:

pdpr -p fred-lp -x "actual-destinations-requested=draft-pp" File5

Specify Destination Location

To submit the file File5 for printing on one of the printer devices located in Building 20, Room 17, enter the command:

pdpr -d LogPrt20 -x "destination-locations-requested=bld20.rm17" File5

Specify a Medium

To submit the file MyAddress to logical destination MServ-lp and to specify a default medium of number-10-envelope for the job, enter the command:

pdpr -p MServ-lp -x "default-medium-number-10-envelope" MyAddress

Specify a Command Input File

To submit a job and read the command flags, command attributes, and names of files to be printed from the file pdinput instead of from the command line, enter the command:

pdpr -Z pdinput

Specify a Code Page for ASCII Jobs

To print the files File1 and File2 and to specify the code page IBM-863, enter the commands:

pdpr -d LogPrtPSF -x "default-character-mapping=IBM-863" File1 File2

Print a Range of Pages

To print pages 1 through 10 of the file report.ps, enter the command:

pdpr -p LogPrtPSF -x "document-format=postscript
destination-pass-through=-o-p 1-10" report.ps

Suggested Reading in Hardcopy

For information about:

- Attributes file, see "Attributes File" on page 7
- Headings and style, see "Command Output: Headings and Style" on page 5
- Document attributes, see "Attributes for Documents and Default Documents" on page 464
- Document attributes that can have different values for each document in a job, see "Per-Document Attribute Listing" on page 467
- Job attributes, see "Attributes for Jobs and Default Jobs" on page 542

Suggested Reading Online for Infoprint Manager for AIX

To view information about document attributes, enter the command:

man pd_att_document

To view information about job attributes, enter the command:

man pd_att_job

pdpromote Command: Advances a Job to the Top of a Queue

Syntax

```
pdpromote [-m "MessageText"] [-x "attribute=value ..."]
      [-X AttributesFileName] {LocalJobID | GlobalJobID}
```

pdpromote -h

Description

Use the **pdpromote** administrative command to move a pending job before any currently-queued jobs. The job becomes the first job in the queue. If you then promote another job, it becomes the first job in the queue ahead of the job previously promoted.

A move to the beginning of the queue does not necessarily guarantee that the job is the next job to be printed or transmitted. The jobs currently printing on each of the actual destinations associated with the queue continue printing. The server assigns the promoted job to the first actual destination that:

- · Becomes available
- Uses the job-priority scheduler
- · Is capable of handling the promoted job

If you use DCE, you must have at least **read** and **write** authority for the queue to promote your own jobs as well as the jobs belonging to other people.

You can change the priority level of a job by setting the **job-priority** attribute with the **pdmod** or the **pdset** command. However, Infoprint promotes a job regardless of its priority to the top of the queue when you use the **pdpromote** command.

Flags

You can use the following flags with the **pdpromote** command:

- -h Displays a command-specific help message containing information about command syntax and flags. If you use this flag with any other flag or attribute, Infoprint recognizes only the -h flag.
- -m "MessageText"

Specifies the message you want to store in the **job-message-from-administrator** attribute. You can use this message to indicate why you want to promote the job or to provide any other comments. If you do not specify the **-m** flag, the message already stored with the job remains unchanged.

You can list this message by specifying requested-attributes=job-message-from-administrator with the pdls command.

Using this flag is equivalent to specifying the command attribute message.

-x "attribute=value ..."

A single attribute string, consisting of one or more attribute and value pairs.

-X AttributesFileName

Specifies the name of a file containing attribute and value pairs that you want Infoprint to insert at the current point in the command.

Using this flag is equivalent to specifying the command attribute attributes.

Command Attributes

You may specify these attributes in a -x "attribute=value ..." string or in an attributes file designated with the -X AttributesFileName flag.

attributes=AttributesFileName

Specifies the designated attributes file that Infoprint reads and inserts at the current point in the command. This file contains attribute and value pairs that Infoprint uses to expand the command.

message="MessageText"

Specifies a message you want to store in the **job-message-from-administrator** attribute. You can use this message to indicate why you want to promote this job or to provide any other comments. If you do not specify the **message** attribute, the message already stored with the job remains unchanged.

You can list this message by specifying **requested-attributes=job-message-from-administrator** with the **pdls** command.

Arguments

Use the argument value to identify the specific object that you want Infoprint to promote. You can use the following arguments with the **pdpromote** command:

LocalJobID or GlobalJobID

Specifies the job you want to promote. By default, end users do not have permission to promote jobs. Therefore, in most cases someone other than the job submitter will promote a job and must identify it by the global job ID. Job submitters who do have permission to promote jobs can identify their own jobs by the local job ID.

When you specify a job with the **pdpromote** command, it becomes the first job in the queue. If a another job is then promoted, it becomes the first job in the queue (ahead of the job previously promoted).

Example

To promote job Serv1:1099600001 and add a job message from the administrator, enter the command:

pdpromote -m "This job must be printed in 10 minutes" Serv1:1099600001

Suggested Reading

For information about:

• Attributes file, see "Attributes File" on page 7

pdq Command: Queries Job Status

Syntax

pdq -h

Description

Use the **pdq** command to list the status of some or all jobs submitted to a logical destination or assigned to an actual destination.

With Infoprint Manager for AIX, if you omit both the *LocalJobID* and the *GlobalJobID* and do not name a destination, Infoprint lists all the jobs in the queue associated with the default logical destination, as defined by the **PDPRINTER** environment variable.

If you do not specify a value for the **-r** flag or the command attribute **requested-attributes**, the **pdq** command defaults to the value **brief**. By default, you can list the attribute values only for the jobs you submit.

Infoprint lists the jobs in the order in which the queue considers them for printing.

You can use the filtering option so that Infoprint returns status only for some jobs. The jobs have a predefined value for the filter that is equal to the job attribute **user-name**; Infoprint sets this value to your login identity when you submit a job.

Flags

You can use the following flags with the **pdq** command:

-d DestinationName

Queries all jobs in the queue associated with this destination, or all jobs assigned to this actual destination. The results depend on the destination realization and the value of the queue attribute **assign-to-destination**, as shown in Table 5.

Table 5. Results of the pdq Command

Destination Realization	assign-to-destination	pdq Returns
Logical	true or false	All jobs in the queue associated with the logical destination
Actual	true	All jobs assigned to the actual destination
Actual	false	All jobs in the queue associated with the actual destination

-f "FilterCriteria"

Specifies the filter selection criteria that you want to use for the jobs. Among the jobs, Infoprint returns only those matching the filter expression.

Using this flag is equivalent to specifying the command attribute filter.

- -F Turns off all filtering, both specified and default. See the -U flag for only turning the default filter off.
- **-g** Turns off headings.

Using this flag is equivalent to specifying the command attribute **headings=false**.

- -h Displays a command-specific help message containing information about command syntax and flags. If you use this flag with any other flag or attribute, Infoprint recognizes only the -h flag.
- -j Returns only the job attributes.

-p *DestinationName*

Same as -d DestinationName.

-r {brief | verbose | archive | "attribute ..." | all | none}

Specifies the group of attributes you want to display.

brief Displays a small subset of important attributes for each object.

verbose

Displays a larger subset of important attributes for each object.

archive

Writes only initially settable and resettable attributes to an archive file.

attribute ...

Displays the attributes you specify.

all Displays all attributes.

none Displays no attributes.

If you specify more than one of these values, Infoprint displays all the attributes requested.

Using this flag is equivalent to specifying the command attribute requested-attributes.

-s {column | doccol | line}

Specifies the format in which you want Infoprint to display the attributes.

column

Attribute values are displayed in tabular format, so that values of the same attribute for multiple objects line up in columns.

doccol For jobs only, job attribute values and the document attribute values for the first document in the job are displayed in column format on the same line.

line Each attribute is displayed on a separate line.

Using this flag is equivalent to specifying the command attribute style.

- **-U** Suppresses the default user-name filter.
- -x "attribute=value ..."

Consists of a single attribute string, containing one or more attribute and value pairs.

-X AttributesFileName

Specifies the name of a file containing attribute and value pairs that you want Infoprint to insert at the current point in the command.

Using this flag is equivalent to specifying the command attribute attributes.

Command Attributes

You can specify these attributes in a -x "attribute=value ..." string or in an attributes file designated with the -X AttributesFileName flag.

attributes=AttributesFileName

Specifies the designated attributes file that Infoprint reads and inserts at the current point in the command. This file contains attribute and value pairs that Infoprint uses to expand the command.

filter="FilterCriteria"

Specifies the filter selection criteria you want used if you request attribute values for multiple objects. Infoprint selects only some of the candidate jobs based on the filtering criteria. A filter is a logical expression consisting of relationships between attributes and attribute values. Among the specified jobs, Infoprint only returns those whose attribute values match the filter expression.

The **filter** command attribute functions the same way for the **pdq** command as for the pdls command.

headings={true | false}

Specifies whether you want Infoprint to display headings for the requested

requested-attributes={brief | verbose | archive | "attribute ..." | all | none} Specifies the group of attributes you want to display.

> brief Displays a small subset of important attributes for each object.

verbose

Displays a larger subset of important attributes for each object.

archive

Writes only initially settable and resettable attributes to an archive

attribute ...

Displays the attributes you specify.

all Displays all attributes.

Displays no attributes. none

If you specify more than one of these values, Infoprint displays all the attributes requested.

style={column | doccol | line}

Specifies the presentation format in which you want Infoprint to display the attributes.

column

Attribute values are displayed in tabular format, so that values of the same attribute for multiple objects line up in columns.

doccol For jobs only, job attribute values and the document attribute values for the first document in the job are displayed in column format on the same line.

Each attribute is displayed on a separate line. line

Arguments

Use the argument value to identify the specific object for which you want the status. If you specify multiple objects, separate the object names with spaces.

You can use the following arguments with the **pdq** command:

Local[obID[.DocNumber]

Specifies the job or documents you want Infoprint to list as determined by a local ID or a local ID and document number. If you specify multiple arguments on the command line, separate the arguments with spaces.

Global[obID[.DocNumber]

Specifies the job or documents you want Infoprint to list as determined by a global ID or a global ID and document number. If you specify multiple arguments on the command line, separate the arguments with spaces.

With Infoprint Manager for AIX, if you omit the -d DestinationName or -p DestinationName flag and the LocalJobID or GlobalJobID argument, Infoprint lists all of the jobs in the queue associated with your default logical destination, defined by your PDPRINTER environment variable.

Examples

Query All Jobs on the Default Logical Destination with Infoprint Manager for AIX

To list all your jobs sent to your default logical destination Dsrv-lp, enter the command:

pdq

Infoprint displays information similar to the following:

Job	ID	Name	State	Intervening Jobs	Destination Requested	Destinations Assigned
13	sp14:1104221000	Filo1	processing	Θ.	Dsrv-lp	Dsrv-pp
13	3p14.1104221000	11161	processing	U	D21 4-1h	D21 A-bb
14	sp14:1105226030	JobA	pending	7	Dsrv-lp	
15	sp14:1133000058	MyJob	pending	8	Dsrv-lp	

Note: If you issue the command:

pdq -U

Infoprint displays status information for all jobs in the queue associated with your default logical destination.

Query All Your Jobs on a Logical Destination

To list all jobs that you sent to logical destination dizzy-lp, enter the command: pdq -d dizzy-lp

Query All Users' Jobs on a Logical Destination

To list all jobs that any user sent to logical destination dizzy-lp, enter the command:

pdg -U -d dizzy

Query All Your Jobs Assigned to an Actual Destination

To list all jobs that you submitted and that Infoprint assigned to actual destination proof-pp, enter the command:

pdq -p proof-pp

Note: If the value of assign-to-destination is false for the queue associated with proof-pp, Infoprint lists all your jobs in the queue.

Suggested Reading in Hardcopy

For information about:

- Filters, see the pdls command attribute filter.
- Attributes file, see "Attributes File" on page 7.
- Headings and style, see "Command Output: Headings and Style" on page 5
- Job attributes, see "Attributes for Jobs and Default Jobs" on page 542
- · Document attributes, see "Attributes for Documents and Default Documents" on page 464

Suggested Reading Online

To view information about job attributes, enter the command:

man pd_att_job

To view information about document attributes, enter the command:

man pd_att_document

pdreorder Command: Reassigns Jobs

Syntax

```
pdreorder {-a [TargetServerName:]TargetJobID |
    -b [TargetServerName:]TargetJobID |
    -p [TargetServerName:]TargetDestinationName |
    -s TargetServerName | -u TargetServerName}
    [-m "MessageText"] [-x "attribute=value ..."]
    [-X AttributesFileName] [ServerName:]GlobalJobID ...
```

pdreorder -h

Description

Enter the **pdreorder** command to request Infoprint to reassign a job to a actual destination or to the unassigned jobs area in the same server or another server. You can assign the job to the actual destination where another job is assigned and specify that it should be printed or transmitted before or after the other job. You can reassign the job to a specified actual destination, request the server to reschedule the job, or request the server to make the job an unassigned job.

If a job is reordered to an actual destination that does not support the job's attribute values, the job is held and the **required-resources-not-supported** attribute lists the unsupported values.

Flags

You can use the following flags with the pdreorder command:

-a [TargetServerName:]TargetJobId

Specifies that the reordered job should be assigned to print or transmit after the target job on the same actual destination.

-b [TargetServerName:]TargetJobId

Specifies that the reordered job should be assigned to print or transmit before the target job on the same actual destination.

- **-h** Displays a command-specific help message containing information about command syntax and flags. If you use this flag with any other flag or attribute, Infoprint recognizes only the **-h** flag.
- -m "MessageText"

Specifies the message you want associated with the reordered job. You can use this message to indicate the reason why the job is being reordered or other comments. Using this flag is equivalent to specifying the command attribute **message**.

You can list this message by specifying requested-attributes=job-message-from-administrator with the pdls command.

-p [TargetServerName:]TargetDestinationName

Specifies that the job should be reassigned to the target actual destination.

-s TargetServerName

Specifies that the job should be moved to the target server and that the target server should assign it to an actual destination.

pdreorder

-u TargetServerName

Specifies that the job should be moved to the target server as an unassigned job.

-x "attribute=value ..."

Consists of a single attribute string, containing one or more attribute-value pairs.

-X AttributesFileName

Specifies the name of a file containing attribute and value pairs that you want Infoprint to insert at the current point in the command line. Using this flag is equivalent to specifying the command attribute attributes.

Command Attributes

You can specify these attributes in a -x "attribute=value ..." string or in an attributes file designated with the -X AttributesFileName flag.

attributes=AttributesFileName

Specifies the designated attributes file that Infoprint reads and inserts at the current point in the command. This file contains attribute and value pairs that Infoprint uses to expand the command.

message="MessageText"

Specifies the message you want associated with the reordered job. You can use this message to indicate the reason why the job is being reordered or other comments.

You can list this message by specifying **requested-attributes=job-message-from-administrator** with the **pdls** command.

Arguments

Use the argument value to identify the specific object for which you want the status. If you specify multiple objects, separate the object names with spaces.

You can use the following arguments with the pdreorder command:

[ServerName:]GlobalJobID

The global ID of the job to be reassigned.

Examples

• To reorder job 1099600001 so that it prints after job 1099500047, enter the command:

pdreorder -a 1099500047 1099600001

• To reassign job 2000004341 from server molly to server david and have david assign it to an actual destination, enter the command:

pdreorder -s david molly:2000004341

pdresubmit Command: Resubmits Jobs

Syntax

```
pdresubmit [-c ObjectClass] [-g] [-r "RequestedAttribute ..."]
[-s StyleName]
[-x "attribute=value ..."] [-X AttributesFileName]
[ServerName:]TargetLogicalDestinationName
{LocalJobID ... | GlobalJobID ... |
[ServerName:]QueueName ... |
[ServerName:]DestinationName ...}
```

pdresubmit -h

Description

Use the **pdresubmit** command to resubmit an existing job to a specific logical destination. The logical destination can be in the same server as the logical destination to which the job was first submitted or a different server. You can only resubmit jobs that have the current job state of **held**, **pending**, **retained**, or **unknown**.

If the logical destination specified is in a different server, the old server resubmits the job with all of its current attributes to the new server. Infoprint includes any default attributes associated with the old server so that the new job remains as similar as possible to the old job. If the new server accepts the job, it assigns a new global job identifier and the old global job identifier becomes invalid.

Logical destinations and queues can also be arguments for this command. If a logical destination is the argument, Infoprint resubmits all of the jobs submitted to the old logical destination to the specified new logical destination. If a queue is the argument, Infoprint resubmits all of the jobs in the old queue to the specified logical destination. Infoprint validates all of the resubmitted jobs again. If the newly specified logical destination does does not support them, they remain in the queue that they were in originally.

If the new logical destination cannot accept the job for some reason, Infoprint issues an error message and the job stays where it was.

Notes:

- 1. Infoprint does not change the global job identifier for the job if you resubmit the job to a logical destination on the same server.
- 2. Infoprint changes the global job identifier for the job if you resubmit the job to a logical destination on a different server. However, if you are the job-owner, you can still use the same local job identifier.

Flags

You can use the following flags with the **pdresubmit** command:

```
-c {job | queue | destination}
```

Specifies the object class that you want for this command. Within the valid classes, **destination** only applies to logical destinations.

Using this flag is equivalent to specifying the command attribute class.

-g Turns off headings.

pdresubmit

Using this flag is equivalent to specifying the command attribute headings=false.

-h Displays a command-specific help message containing information about command syntax and flags. if you use this flag with any other flag or attribute, Infoprint recognizes only the **-h** flag.

-r {none | brief verbose}

Specifies the group of attributes you want Infoprint to display for the specified job, queue, or destination.

Displays no attributes. none

brief Displays a small subset of important attributes for each object.

verbose

Displays a larger subset of important attributes for each object.

Using this flag is equivalent to specifying the command attribute requested-attributes.

-s {column | doccol | line}

When combined with the -r flag or the requested-attributes command attribute, this flag specifies the format in which you want the attributes displayed.

column

Attribute values are displayed in tabular format, so that values of the same attribute for multiple objects line up in columns.

doccol For jobs only, job attribute values and the document attribute values for the first document in the job are displayed in column format on the same line.

line Each attribute is displayed on a separate line.

Using this flag is equivalent to specifying the command attribute **style**.

-x "attribute=value ..."

Consists of a single attribute string, containing one or more attribute-value pairs.

-X AttributesFileName

Specifies the name of a file containing attribute and value pairs that you want Infoprint to insert at the current point in the command.

Using this flag is equivalent to specifying the command attribute attributes.

Command Attributes

You may specify these attributes in a -x "attribute=value ..." or in an attributes file designated with the -X AttributesFileName flag.

attributes=AttributesFileName

Specifies the designated attributes file that Infoprint reads and inserts at the current point in the command. This file contains attribute and value pairs that Infoprint uses to expand the command.

class={job | queue | destination}

Specifies the object class you want for this command. Within the valid classes, destination only applies to logical destinations.

headings={true | false}

Specifies whether you want Infoprint to display headings for the requested attributes.

requested-attributes={none | brief verbose}

Specifies the group of attributes you want Infoprint to display for the specified job, queue, or destination.

none Displays no attributes.

brief Displays a small subset of important attributes for each object.

verbose

Displays a larger subset of important attributes for each object.

style={column | doccol | line}

Specifies the format in which you want Infoprint to display the attributes.

column

Attribute values are displayed in tabular format, so that values of the same attribute for multiple objects line up in columns.

doccol For jobs only, job attribute values and the document attribute values for the first document in the job are displayed in column format on the same line.

line Each attribute is displayed on a separate line.

Arguments

Use the argument value to identify the specific object you want to resubmit. If you specify multiple objects, all must belong to the same class and you must separate the object names with spaces.

You must use the following argument:

[ServerName:]TargetLogicalDestinationName

Specifies the name of the new logical destination.

You must use one of the following arguments with the **pdresubmit** command:

LocalJobID or GlobalJobID

Specifies the job you want resubmitted as determined by a local or global job identifier. If you do not use DCE, by default, end users do not have permission to use the **pdresubmit** command. Therefore, in most cases someone other than the job submitter will resubmit a job and must identify it by the global job ID. Job submitters who do have permission to use **pdresubmit**, either because they belong to the **printq** group or because the file permissions have been changed, can identify their own jobs by the local job ID.

If you use DCE, you must have **write** permission for the server to resubmit a job belonging to another user.

[ServerName:]DestinationName

Causes Infoprint to resubmit to the target logical destination all jobs currently submitted to the specified logical destination.

[ServerName:]QueueName

Causes Infoprint to resubmit to the target logical destination all jobs that are currently in the specified queue.

pdresubmit

Examples

Resubmit Jobs

To resubmit jobs 3828:1098223002 and 3828PP:1099223003 to logical destination local-lp, enter the command:

pdresubmit local-lp 3828PP:1098223002 3828PP:1099223003

Resubmit All Jobs from One Logical Destination to Another

To resubmit all jobs submitted to logical destination dept1-1p to logical destination local-lp, enter the command:

pdresubmit local-lp -c destination dept1-lp

Suggested Reading

For information about:

• Attributes file, see "Attributes File" on page 7

pdresume Command: Enables Paused Objects to Resume Operation

Syntax

```
pdresume [-c ObjectClass] [-m "MessageText"]
        [-x "attribute=value ..."] [-X AttributesFileName]
         {LocalJobID ... | GlobalJobID ... |
         ServerName ... | [ServerName:]DestinationName ... |
        [ServerName:]QueueName ...}
```

pdresume -h

Description

Use the **pdresume** administrative command to cause Infoprint to restart paused jobs, actual destinations, queues, or servers.

Note: Use the pdresume and pdpause commands to allow or prevent output from the object, whereas you use the pdenable and pddisable commands to allow or prevent input to the object.

Flags

You can use the following flags with the **pdresume** command:

```
-c {destination | queue | job | server}
```

Specifies the object class you want for this command. Within the valid classes, destination is an actual destination.

Note: You cannot resume PSF upload-TCP/IP-attached physical printers or PSF upload-SNA-attached physical printers.

Using this flag is equivalent to specifying the command attribute class.

-h Displays a command-specific help message containing information about command syntax and flags. If you use this flag with any other flag or attribute, Infoprint recognizes only the -h flag.

```
-m "MessageText"
```

Specifies the message you want associated with the specified destination, queue, job, or server. You can use this message to indicate the reason for resumption or to provide any other comments.

When resuming a server, Infoprint propagates the message to the message attribute of the actual destinations and queues residing in the server. Infoprint does not change the server **message** attribute.

If the command operates on a job, you can list this message by specifying requested-attributes=job-message-from-administrator with the pdls command. If the command operates on a destination, queue, or server you can list this message by specifying requested-attributes=message with the **pdls** command.

If you do not specify the -m flag, the message already stored with the object remains unchanged.

Using this flag is equivalent to specifying the command attribute message.

```
-x "attribute=value ..."
```

A single attribute string, consisting of one or more attribute-value pairs.

pdresume

-X AttributesFileName

Specifies the name of a file containing attribute and value pairs that you want Infoprint to insert at the current point in the command.

Using this flag is equivalent to specifying the command attribute attributes.

Command Attributes

You can specify these attributes in a -x "attribute=value ..." string or in an attributes file designated with the -X AttributesFileName flag.

attributes=AttributesFileName

Specifies the designated attributes file that Infoprint reads and inserts at the current point in the command. This file contains attribute and value pairs that Infoprint uses to expand the command.

class={destination | queue | job | server}

Specifies the object class you want for this command. Within the valid classes, destination is an actual destination.

Note: You cannot resume PSF upload-TCP/IP-attached physical printers or PSF upload-SNA-attached physical printers.

message="MessageText"

Specifies the message you want to associate with the specified destination, queue, job, or server. You can use this message to indicate the reason for resumption or to provide any other comments.

When resuming a server, Infoprint propagates the message to the message attribute of the actual destinations and queues residing in the server. Infoprint does not change the server **message** attribute.

If the command operates on a job, you can list this message by specifying requested-attributes=job-message-from-administrator with the pdls command. If the command operates on a destination, queue, or server, you can list this message by specifying requested-attributes=message with the **pdls** command.

If you do not specify the message attribute, the message already stored with the object remains unchanged.

Arguments

Use the argument value to identify the specific destination, queue, job, or server you want to start processing again (resume operating). If you specify multiple objects, all of the objects must belong to the same class and you must separate the object names with spaces.

You can use the following arguments with the **pdresume** command:

LocalJobID... or GlobalJobID...

Specifies the job you want to resume as determined by a local job identifier or global job identifier. If you use DCE, by default, only an administrator has the authority to resume jobs. If you do not use DCE, by default, administrators and operators have the authority to resume jobs, but end users do not. Therefore, in most cases someone other than the job submitter will resume a job and must identify it by the global job ID. Job submitters who do have authority to resume jobs can identify their own jobs by the local job ID.

A resumed job does not automatically return to its previous state. For example, if the **job-hold** or **print-after** attributes of a paused job were modified, returning to its previous state would cause Infoprint to hold the job even after it was resumed.

Resuming a job that was not previously assigned to an actual destination allows Infoprint to schedule it.

Resuming a job that was processing when it was paused causes Infoprint to restore it to the **pending** state and attempt to schedule it on the original actual destination. If the original destination is not available, Infoprint schedules the job on another actual destination that can support the job checkpoint format and begins processing the job where it stopped. If Infoprint cannot find another actual destination that supports the checkpoint format, Infoprint places the job in the **held** state. You can resubmit the job, which means that Infoprint will start the job from the beginning.

Resuming a job that had any attributes modified while it was paused causes it to restart from the beginning.

[ServerName:]DestinationName

Specifies the destination you want to resume operation.

Resuming an actual destination allows it to start processing jobs that Infoprint has assigned to it.

[ServerName:]Queue

Specifies the queue you want to resume operating.

Resuming a queue resumes the distribution of jobs to actual destinations associated with that queue.

ServerName

Specifies the server on which you want the command to operate. A server does not have a **paused** state. Issuing the command to a server resumes all of the paused queues and actual destinations that reside in that server. The queues can then continue to distribute jobs to actual destinations; and the actual destinations can start processing jobs.

Examples

Resume an Actual Destination

To resume actual destination Csrv-pp and issue a message, enter the command: pdresume -m "Toner refilled" Csrv-pp

Resume a Queue

To resume the queue Div1-q, enter the command: pdresume -c queue Div1-q

Resume All Queues and Actual Destinations in a Server

To resume all of the queues and actual destination in the server Mrk-server3, enter the command:

pdresume -c server Mrk-server3

Suggested Reading

For information about:

Attributes file, see "Attributes File" on page 7

pdrm Command: Removes Jobs

Syntax

pdrm -h

Description

Use the **pdrm** command to remove (delete) previously submitted jobs.

Notes:

- 1. If the job you specify is currently printing or transmitting, Infoprint can only remove it at a pausable point in the job. The pausable point at which the Infoprint can remove the job depends on the type of output device. A pausable point may be immediate or it may be the next page, sheet, document, or job boundary. If there is no such point before the end of job, Infoprint does not remove the job.
- 2. When you request Infoprint to remove a job with a non-zero value for the **job-retention-period** or **job-retain-until** attribute, Infoprint retains the job until the **job-retain-until** deadline or until the **job-retention-period** runs out, then deletes the job.
- 3. You can remove your own jobs by specifying either the local ID or the global ID for the job. You can remove jobs belonging to another person by specifying the global ID for the job.

Note: If you use DCE, you must have **write** permission for the server to remove jobs belonging to another person.

Infoprint issues a confirmation message prior to deleting jobs, unless the environment variable PD_CONFIRM_DELETE for the person requesting the job removal has a value of **no**.

Flags

You can use the following flags with the pdrm command:

-h Displays a command-specific help message containing information about command syntax and flags. If you use this flag with any other flag or attribute, Infoprint recognizes only the **-h** flag.

-m "MessageText"

Specifies the message you that want to associate with the specified job. The specified text becomes the value of the **job-message-from-administrator** attribute. You can use it to provide the reason you are removing the job or to provide any other comments. If you do not specify the **-m** flag, the message already stored with the job remains unchanged.

You can list this message by specifying requested-attributes=job-message-from-administrator with the pdls command.

Using this flag is equivalent to specifying the command attribute **message**.

-r *IobRetentionPeriod*

Specifies the period of time you want the server to retain the job before

Infoprint deletes the job. If specified, this retention period takes precedence over the previous job-retention period set for the job.

Using this flag is equivalent to specifying the job object attribute job-retention-period.

-x "attribute=value ..."

Consists of a single attribute string, containing one or more attribute-value pairs.

-X AttributesFileName

Specifies the name of a file containing attribute and value pairs that you want Infoprint to insert at the current point in the command.

Using this flag is equivalent to specifying the command attribute attributes.

Command Attributes

You can define these attributes in a -x "attribute=value ..." string or in an attributes file designated in the -X AttributesFileName flag.

attributes=AttributesFileName

Specifies the designated attributes file that Infoprint reads and inserts at the current point in the command. This file contains attribute and value pairs that Infoprint uses to expand the command.

message="MessageText"

Specifies the message that you want Infoprint to store in the job-message-from-administrator attribute. You can use it to provide the reason you are removing the job or to provide any other comments. If you do not specify the message attribute, the message already stored with the job remains unchanged.

You can list this message by specifying requested-attributes=job-messagefrom-administrator with the pdls command.

Arguments

Use the argument value to identify the specific job you want to remove. You must use one of the following arguments for the **pdrm** command:

LocalJobID **or** GlobalJobID

Specifies the local ID or global ID of the job that you want Infoprint to

This argument must appear last in the command. If you want to remove more than one job, separate the job identifiers with spaces.

Examples

Remove Your Own Job

To remove your job with the local ID of 15, enter the command:

Remove Another User's Job

To remove the job with global ID Server1:1011223002 on server Server1, enter the command:

pdrm Server1:1011223002

pdrm

Remove Job Regardless of Retention Time
To remove your job with the local ID of 10 as soon as possible, regardless of any previously specified **job-retention-period** attribute value, enter the command: pdrm -r 0 10

pdset Command: Defines Attribute Values

Syntax

pdset -h

Description

Use the **pdset** administrative command to define or modify the values of object attributes. You must disable a destination before you can modify its attributes.

Table 6 lists the four modification operators.

Table 6. pdset Operators

Operator	Syntax	Description
Replace	attribute=value	Replaces the entire value of the attribute attribute with <i>value</i> or adds the attribute to the object, if not already present.
Add values	attribute+=value	Adds the value <i>value</i> to the attribute <i>attribute</i> . You cannot add values to single-valued attributes. Infoprint honors an add request that duplicates values on a multi-valued attribute without warning.
Remove values	attribute-=value	Removes the value <i>value</i> from the attribute <i>attribute</i> . Infoprint ignores a remove request for a nonexistent value, without warning or error. A remove request for the last or only value of an attribute is equivalent to a reset-to-default request.
Reset to default	attribute==	Sets the attribute value <i>attribute</i> to the default. If you supply values with a reset-to-default request, Infoprint ignores them.

If you do not specify a value with a replace, add, or remove request, Infoprint issues an error and rejects the request to change the object.

You can only change values for resettable attributes using the **pdset** command. Using this command for non-settable or initially settable attributes results in an error.

See "Chapter 7. Infoprint Object Attributes" on page 329 for lists of all resettable attributes by object and a description of each attribute.

Changes made to objects are permanent and remain changed even if you shut down and then restart the system (except for logs).

Flags

You can use the following flags with the **pdset** command:

-c {destination | job | server | queue | auxiliary-sheet | document | initial-value-job | initial-value-document | medium | resource-context | transform | log}

> Specifies the object class that you want for this command. Within the valid classes, **destination** is for a logical destination or actual destination.

Using this flag is equivalent to specifying the command attribute class.

Turns off headings. -g

> Using this flag is equivalent to specifying the command attribute headings=false.

-h Displays a command-specific help message containing information about command syntax and flags. If you use this flag with any other flag or attribute, Infoprint recognizes only the -h flag.

-m "MessageText"

Specifies the message that you want to associate with the object that you want to modify. You can use this message to indicate the reason why you are modifying or setting object attributes or to provide any other comments.

If the command operates on a job, you can list this message by specifying requested-attributes=job-message-from-administrator with the pdls command. Otherwise, you can list this message by specifying requested-attributes=message with the pdls command.

If you do not specify the **-m** flag, the message already stored with the object remains unchanged.

Using this flag is equivalent to specifying the command attribute message.

-r {none | brief | verbose}

Specifies the attribute values you want to display for the specified object.

none Displays no attributes.

brief Displays a small subset of important attributes for each object.

verbose

Displays a larger subset of important attributes for each object.

Using this flag is equivalent to specifying the command attribute requested-attributes.

-s {column | doccol | line}

Specifies the format in which you want Infoprint to display the attributes.

column

Attribute values are displayed in tabular format, so that values of the same attribute for multiple objects line up in columns.

doccol For jobs only, job attribute values and the document attribute values for the first document in the job are displayed in column format on the same line.

line Each attribute is displayed on a separate line. Using this flag is equivalent to specifying the command attribute style.

-x "attribute=value ..."

A single attribute string, consisting of one or more attribute-value pairs. Prefix the attribute value with the replace operator, = , to replace a value, the add-value operator, += , to add a value or the remove-value operator, -= , to remove a value. Use the reset-to-default operator, == , with no attribute value to set the value to its default.

-X AttributesFileName

Specifies the name of a file containing attribute and value pairs that you want Infoprint to insert at the current point in the command.

Using this flag is equivalent to specifying the command attribute attributes.

Command Attributes

You can specify these attributes in a -x "attribute=value ..." string or in an attributes file designated with the -X AttributesFileName flag.

attributes=AttributesFileName

Specifies the designated attributes file that Infoprint reads and inserts at the current point in the command. This file contains attribute and value pairs that Infoprint uses to expand the command.

class={destination | job | server | queue | auxiliary-sheet | document | initial-value-job | initial-value-document | medium | resource-context | transform | log}

Specifies the object class you want for this command. Within the valid classes, **destination** is for a logical destination or actual destination.

headings={true | false}

Specifies if you want Infoprint to display headings on the output.

message="MessageText"

Specifies the message that you want to associate with the object you are modifying. You can use this message to indicate the reason that you are modifying the object attributes or to provide any other comments.

If the command operates on a job, you can list this message by specifying requested-attributes=job-message-from-administrator with the pdls command. Otherwise, you can list this message by specifying requested-attributes=message with the pdls command.

If you do not specify the **message** attribute, the message already stored with the object remains unchanged.

requested-attributes={none | verbose | brief}

Specifies the attribute values you want to display for the specified object.

none Displays no attributes.

brief Displays a small subset of important attributes for each object.

verbose

Displays a larger subset of important attributes for each object.

style={column | doccol | line}

Specifies the presentation format in which you want the output displayed.

column

Attribute values are displayed in tabular format, so that values of the same attribute for multiple objects line up in columns. **doccol** For jobs only, job attribute values and the document attribute values for the first document in the job are displayed in column format on the same line.

line Each attribute is displayed on a separate line.

Arguments

Use the argument value to identify the specific object for which you want to set or modify attributes. If you specify multiple objects, separate the object names with spaces.

You can use the following arguments with the **pdset** command:

ServerName: Auxiliary Sheet Name ServerName:DefaultJobName ServerName:DefaultDocumentName ServerName:MediumName ServerName:LogName [ServerName:]DestinationName [ServerName:]QueueName ServerName:ResourceContextName ServerName:TransformName ServerName LocalJobID Global JobID

By default, end users do not have permission to modify jobs. Therefore, in most cases someone other than the job submitter will modify a job and must identify the job by the global job ID. Job submitters who do have permission to modify jobs can identify their own jobs by the local job ID.

Examples

Specify a Descriptor for a Server

To set a description for the server Server1 and identify the processor name containing it and the TCP/IP address for the processor, enter the command:

```
pdset -c server -x "descriptor='Server Server1 is installed on
cowboy. The TCP/IP address for cowboy is 9.99.9.143.'" Server1
```

Change the Operator to Receive Messages

To identify a new person to receive start and stop messages for actual destination Serv4-pp, enter the command:

```
pdset -c destination -x "notify-operator=electronic-mail:ro@cowboy"
Serv4-pp
```

Set the Job Size Range

To set the size of jobs that users can submit to actual destination small-pp, enter the command:

```
pdset -x "job-size-range-supported=0:10000
job-size-range-ready=0:10000" small-pp
```

Specify Media Supported by an Actual Destination

To specify the media supported by a given actual destination and the media currently loaded in the printer device, enter the command:

```
pdset -x "media-supported=letter na-letter-colored
   legal na-legal-colored A4 A4-colored
   psf-tray-characteristics=top:letter
  bottom:A4" Serv4-pp
```

Set a Message

To set the message for server Serv2, enter the command: pdset -c server -m "printing system now ok" Serv2

Suggested Reading in Hardcopy

For information about:

- Attributes for Infoprint objects, see "Chapter 7. Infoprint Object Attributes" on page 329
- Attributes file, see "Attributes File" on page 7
- Headings and style, see "Command Output: Headings and Style" on page 5
- For introductory information about object attributes and their use with commands, see "Introducing Object Attributes" on page 332, which includes information on non-settable, initially settable, and resettable attributes.

Suggested Reading Online for Infoprint Manager for AIX

To view information about all supported attributes for Infoprint, enter the command:

man pd att

This displays a list of files by object from which you can select the attribute listing you want.

pdshutdown Command: Stops Servers or Actual Destinations

Syntax

```
pdshutdown [-c server] [-m "MessageText"] [-w time]
        [-x "attribute=value ..."] [-X AttributesFileName]
        ServerName
pdshutdown [-c destination] [-m "MessageText"]
        [-x "attribute=value ..."] [-X AttributesFileName]
        [-s [-n]] [ServerName:]DestinationName
pdshutdown -h
```

Description

Use the pdshutdown administrative command to terminate a server process or shut down a PSF physical printer, fax destination, or email destination.

You can shut down a server either immediately or after it finishes processing some or all of its current jobs.

Infoprint prevents the server from accepting new jobs while the server is shutting down and after it has shut down. Destinations in the server that were enabled at shutdown time are enabled when the server restarts. Destinations in the server that were disabled at shutdown time are disabled when the server restarts.

Note: To restart a server after shutdown, use the **startsrv** or **start server** utility. See"startsrv Utility: Starts a Server in Infoprint Manager for AIX" on page 179 or "start_server Utility: Starts a Server for a Basic Infoprint Installation in Infoprint Manager for AIX" on page 177.

Shutting down an actual destination:

- Terminates all communication with the output device
- · Pauses the job printing or transmitting on the actual destination
- Terminates all jobs processing on the actual destination and puts these jobs in the **pending** state
- Releases jobs assigned to the actual destination so that you can reschedule them on another actual destination
- · Disables the actual destination

You can shut down a PSF physical printer either immediately or after synchronizing the current job's checkpoint data with the pages that have actually printed.

Notes:

- 1. To restart an actual destination after shutdown, use the **pdenable** command. See"pdenable Command: Enables Destinations to Accept Jobs and Logs to Log"
- 2. Synchronize the checkpoint data for a controlled shutdown, for example, when you want to perform maintenance that will take some time.

- 3. If Infoprint cannot communicate with the output device, shut down the actual destination so that you can reschedule the jobs assigned to it. Do not synchronize the checkpoint data. If you try, the command will hang, waiting for the output device to respond.
 - If you shut down without synchronization, the shutdown will take effect and allow any previously hung commands to complete.
- 4. A job paused by a destination shutdown without synchronization may reprint some pages when printing is resumed.
- 5. If you want to interrupt the actual destination for only a short time, consider pausing it rather than shutting it down. When you pause an actual destination, scheduled jobs remain scheduled. When you shut down an actual destination, scheduled jobs are requeued.

Flags

You can use the following flags with the **pdshutdown** command:

-c {server | destination}

Specifies the object class you want to shut down. Within the valid classes, **destination** is a PSF physical printer, fax destination, or email destination.

Using this flag is equivalent to specifying the command attribute class.

-h Displays a command-specific help message containing information about command syntax and flags. If you use this flag with any other flag or attribute, Infoprint recognizes only the -h flag.

-m "MessageText"

Specifies the message that you want to associate with the server or actual destination being shut down. You can use this message to indicate the reason for the shutdown or to provide any other comments.

You can list this message by specifying **requested-attributes=message** with the **pdls** command. If you do not specify the **-m** flag, the message already stored with the object remains unchanged.

Using this flag is equivalent to specifying the command attribute message.

- -n Causes the PSF physical printer to perform an NPRO (move the last printed page to the stacker). Using this flag is equivalent to specifying the command attribute non-process-runout=true.
 - This flag is valid only with object class **destination**, and only if you also specify **-s**. It is not valid for fax destinations or email destinations.
- -s Synchronizes the checkpoint data for the current job with the pages that have actually printed. This permits the job to resume at the point of synchronization. Using this flag is equivalent to specifying the command attribute **synchronize=true**. Do not use this flag if Infoprint cannot communicate with the printer device.

This flag is valid only with object class **destination**. It is not valid for fax destinations or email destinations.

-w {after-current | now | after-all}

Specifies when you want a server to shut down. When the value is:

now Infoprint cancels and requeues any currently printing jobs, then shuts down the server. You must resubmit the jobs using the **pdresubmit** command when the server restarts.

after-current

The server continues to accept requests other than print requests until the currently-printing jobs finish printing, then the server shuts down.

after-all

The server continues to accept all requests except print requests until all scheduled jobs finish printing, then the server shuts down.

Using this flag is equivalent to specifying the command attribute when.

This flag is valid only with object class **server**.

-x "attribute=value ..."

A single attribute string, consisting of one or more attribute-value pairs.

-X AttributesFileName

Specifies the name of a file containing attribute and value pairs that you want Infoprint to insert at the current point in the command.

Using this flag is equivalent to specifying the command attribute attributes.

Command Attributes

You may specify these attributes in a -x "attribute=value ..." string or in an attributes file designated with the -X AttributesFileName flag.

attributes=AttributesFileName

Specifies the designated attributes file that Infoprint reads and inserts at the current point in the command. This file contains attribute and value pairs that Infoprint uses to expand the command.

class={server | destination}

Specifies the object class you want to shut down. Within the valid classes, destination is a PSF physical printer, fax destination, or email destination.

message="MessageText"

Specifies the message you want associated with the server or actual destination being shut down. You can use this message to indicate the reason for the shutdown or to provide any other comments.

You can list this message by specifying requested-attributes=message with the **pdls** command. If you do not specify the **message** attribute, the message already stored with the object remains unchanged.

non-process-runout={true | false}

Specifies whether the PSF physical printer should perform an NPRO (move the last printed page to the stacker).

This attribute is valid only with object class **destination**, and only if you also specify **synchronize=true**. It is not valid for fax destinations or email destinations.

synchronize={true | false}

Specifies whether to synchronize the checkpoint data for the current job with the pages that have actually printed. A value of true permits the job to resume at the point of synchronization. Do not specify synchronize=true if Infoprint cannot communicate with the printer device.

This attribute is valid only with object class **destination**. It is not valid for fax destinations or email destinations.

when={after-current | now | after-all}

Specifies when you want a server to shut down. When the value is:

now Infoprint cancels and requeues any currently printing jobs, then shuts down the server. You must resubmit the jobs using the **pdresubmit** command when the server restarts.

after-current

The server continues to accept requests other than print requests until the currently-printing jobs finish printing, then the server shuts down.

after-all

The server continues to accept all requests except print requests until all scheduled jobs finish printing, then the server shuts down.

This attribute is valid only with object class **server**.

Argument

Use the argument value to identify the specific server or actual destination that you want to shut down.

You can use the following argument values with the **pdshutdown** command:

ServerName.

Specifies the server that you want to shut down.

[ServerName:]DestinationName

Specifies the actual destination that you want to shut down.

Examples

Shut Down a Server

To shut down server Server1, to abort all jobs that are currently printing, and to set a message, Down for maintenance, enter the command:

pdshutdown -w now -m "Down for maintenance" Server1

Shut Down an Actual Destination

To shut down actual destination Serv9-fax, enter the command: pdshutdown -c destination Serv9-fax

Shut Down a PSF Physical Printer and Update Job Checkpoint Data

To shut down PSF physical printer Serv9-pp after synchronizing the printer with the currently printing job's checkpoint data, enter the command:

pdshutdown -c printer -s Serv9-pp

Note: The PSF physical printer must be able to communicate with the printer device to perform the synchronize function.

Shut Down a PSF Physical Printer, Update Job Checkpoint Data, and Perform NPRO

To shut down PSF physical printer Serv9-pp after synchronizing the currently printing job's checkpoint data and perform an NPRO, enter the command: pdshutdown -c destination -s -n Serv9-pp

pdshutdown

Suggested Reading

For information about:

• Attributes file, see "Attributes File" on page 7.

pdspace Command: Backspaces or Forward Spaces a Printer

Syntax

pdspace -h

Description

Use the **pdspace** command to backspace or forward space the currently printing job on the specified PSF physical printer a given number of sides. If the job is printing on one side of the medium, one side is equivalent to one sheet. If the job is printing on two sides of the medium (duplex), two sides are equivalent to one sheet.

Notes:

- 1. The functions of this command only apply to PSF physical printers. They do not apply to PSF upload-TCP/IP-attached physical printers or PSF upload-SNA-attached physical printers.
- 2. To guarantee accurate backspacing or forward spacing to a specific side, you must install the level of microcode supporting **pdspace** on the printer device.
- 3. You cannot backspace or forward space ASCII print jobs.

You can issue the **pdspace** command while the printer is stopped, paused, or running.

- If the printer has been stopped by pressing the STOP button on the printer device, the printer operator must press the START or READY button before the printer can restart printing. You cannot force a stopped printer to perform an NPRO by specifying the -n flag; but the operator can force an NPRO by pressing the NPRO button.
- If the printer has been paused with the **pdpause** command, you must issue the **pdresume** command before the printer can restart printing.
- If the printer is running, the **pdspace** command takes effect as soon as possible.

The printer backspaces or forward spaces the number of sides you specify, except that:

- The printer will not backspace or forward space to the back side of a duplexed sheet. If a backspace or forward calculation points to the back side of a duplexed sheet, the printer backspaces or forward spaces to the front side of that sheet.
- When backspacing, if you specify a side count of -1, the job restarts printing on page 1 with a new header sheet.
- When backspacing, if you specify more sides than have already printed, the job restarts printing on page 1 without a header sheet.
- When forward spacing, if you specify more sides than there are sides left to print, the job terminates.

Note: Infoprint backspaces or forward spaces from the last printed sheet: any count is one less than you would normally expect. For example, if you backspace ten sides starting at page 39, the job resumes on page 30 because page 39 is counted as one of the pages backspaced.

Flags

You can use the following flags with the pdspace command:

-b SideCount

Specifies the number of sides to backspace before continuing to print. Using this flag is equivalent to specifying the command attribute back-space.

-c destination

Specifies the object class of **destination**, which represents a PSF physical printer. This is the only allowed class. Using this flag is equivalent to specifying the command attribute **class**.

-f SideCount

Specifies the number of sides to forward space before continuing to print. Using this flag is equivalent to specifying the command attribute **forward-space**.

- -h Displays a command-specific help message containing information about command syntax and flags. If you use this flag with any other flag or attribute, Infoprint recognizes only the -h flag.
- -n Causes the printer to perform an NPRO (move the last printed page to the stacker) before restarting printing. An NPRO makes it easier to see exactly where the spacing took place. Using this flag is equivalent to specifying the command attribute non-process-runout=true.

-x "attribute=value ..."

Consists of a single attribute string, containing one or more attribute-value pairs.

-X AttributesFileName

Specifies the name of a file containing attribute and value pairs that you want Infoprint to insert at the current point in the command. Using this flag is equivalent to specifying the command attribute attributes.

Command Attributes

You can define these attributes in a -x "attribute=value ..." string or in an attributes file designated in the -X AttributesFileName flag.

attributes=AttributesFileName

Specifies the designated attributes file that Infoprint reads and inserts at the current point in the command. This file contains attribute and value pairs that Infoprint uses to expand the command.

back-space=SideCount

Specifies the number of sides to backspace before continuing to print.

class=destination

Specifies the object class of **destination**, which represents a PSF physical printer. This is the only allowed class.

forward-space=*SideCount*

Specifies the number of sides to forward space before continuing to print.

non-process-runout={true | false}

Specifies whether the printer should perform an NPRO (move the last printed sheet to the stacker) before restarting printing. An NPRO makes it easier to see exactly where the spacing took place.

Arguments

Use the argument value to identify the specific physical printer on which the job backspaces.

[ServerName:]DestinationName

Examples

Backspacing 22 Sides

To backspace the currently printing job on physical printer jrSrv-pp by 22 sides, enter the command:

pdspace -b22 jrSrv-pp

Forward Spacing 22 Sides

To forward space the currently printing job on physical printer mySrv-pp by 22 sides, enter the command:

pdspace -f22 mySrv-pp

Forward Spacing a Paused Printer 10 Sides with NPRO

To pause physical printer carlo-pp, forward space the job that was printing by 10 sides, move the last printed sheet to the stacker, and resume printing, enter the commands:

```
pdpause carlo-pp
pdspace -f10 -n carlo-pp
pdresume carlo-pp
```

Backspacing to a Specific Side

To backspace exactly to page 62 in the job printing on physical printer mySrv-pp:

- 1. Use *one* of these methods to interrupt printing:
 - Press the **STOP** button to stop the printer device.
 - Enter this command to pause the physical printer: pdpause mySrv-pp
- 2. At the operator viewing point, check to see what page was printing when the job stopped.
- 3. Calculate the number of sides to backspace. For example, if the job stopped at page 97:

```
97 - 62 + 1 = 36
```

You must add one because page 97 is counted as the first side to backspace.

4. Enter the command:

```
pdspace -b36 mySrv-pp
```

- 5. Use *one* of these methods to resume printing:
 - If you pressed STOP, press START to restart the printer device.
 - If you paused the physical printer, enter this command to resume it: pdresume mySrv-pp

pdspace

Chapter 3. The -o Flag for AIX Print Commands

As well as the Infoprint **pdpr** and **lprafp** commands, you can use the AIX print commands, **enq**, **lp**, and **qprt**, to print jobs.

AIX uses the **-o** flag on the AIX print commands and on the Infoprint **lprafp** command to pass information to the backend program. This program handles the details of printing or transmitting your job.

-o flag not valid on pdpr command

You cannot use the **-o** flag on the Infoprint **pdpr** command, nor can you use it to specify Infoprint object attributes. Use the **-o** keywords only on the AIX print commands **enq**, **lp**, and **qprt** and on the Infoprint **lprafp** command.

Similar or equivalent Infoprint object attributes are listed for each **-o** flag keyword. Use these attributes only on the **pdpr** command.

To pass flags or options to a transform command when you submit DBCS ASCII, EUC, GIF, JPEG, line-data, PCL, PDF, PostScript, or TIFF files with the **pdpr** command, use the Infoprint **other-transform-options** document attribute instead of the **-o** flag.

Syntax

You can use any one of the following AIX commands to submit an Infoprint job:

enq [-P DestinationName] [-okeyword=value ...] FileName ...

Ip [-d DestinationName] [-okeyword=value ...] FileName ...

qprt [-**P** DestinationName] [-**o**keyword=value ...] FileName ...

Description

The AIX print commands (**enq**, **lp**, and **qprt**) enqueue requests to a shared system resource. For Infoprint, this resource is a printer device, fax device, or electronic mailing system.

Limitations

If you specify a data type value that causes an Infoprint transform program to be run before the file is printed on a PSF physical printer, the transform program writes the MO:DCA-P output to a temporary file in the directory specified by the PDBASE environment variable or in one of its subdirectories. No single user can create a MO:DCA-P file larger than the amount of free space in the file system containing this directory. If many users are submitting jobs that invoke transform programs, the directory may fill up and prevent all users from successfully running the transform programs.

Flag

The AIX print commands use the following flag to pass information to Infoprint:

-okeyword=value

Is the information to be passed to Infoprint. You can specify as many keyword-value pairs in the AIX print command as you like, provided that each of them starts with the **-o** flag.

Note: You can specify other flags associated with the AIX print commands or with the **lprafp** command, for example, the **-N** flag (number of copies) of the **enq** and **qprt** commands. Some of these flags are equivalent to the **-o** values you can specify with the AIX print commands.

For information about the other flags for the **enq**, **lp**, and **qprt** commands, refer to the appropriate man page or to AIX for RS/6000 Commands Reference.

For information about the other flags for the **lprafp** command, refer to "lprafp Command: Submits Remote Jobs in Infoprint Manager for AIX" on page 13.

Specifying -o Attribute-Value Pairs

In Infoprint, options appear as strings after the **-o** flag in the format *keyword=value*. For example,

enq -P DestinationName -obin=2 -oduplex=no FileName

Consider the following when using **-o** with an AIX print command or with the **lprafp** command:

- The **-o** flag is not valid on the **pdpr** command. Use the similar or equivalent Infoprint attributes listed for each **-o** keyword.
- Do not specify Infoprint attributes with the -o flag.
- All **-o** keywords override the equivalent flags specified with the print commands (such as the **-N** flag of the **enq** and **qprt** commands).
- If you specify the same keyword with the **-o** flag multiple times, Infoprint uses only the value of the last occurrence.
- When using keywords with the -o flag, you can use blanks between the keyword and the -o flag (for example -o bin=1). You cannot, however, use blanks between the keyword and the value (for example, -o bin=1 is valid; -o bin = 1 is not). Values that have blanks must be enclosed with single quotes or double quotes (for example, -odocname="Tim Memo").
- When using another flag with the **-o** flag, you cannot use blanks between the second flag and its value. For example, **-o-w6i** is valid; **-o-w 6i** is not.
- The keywords used with the **-o** flag *are not* case-sensitive. For example, **-o** BIN=1 and **-o** bin=1 are both valid.
- Values for some keywords (such as path names or form definition names), are case-sensitive; for example:

```
and
enq -P3900A -oformdef=F100S /usr/lpp/psf/readme
specify two different files to submit, just as:
enq -P3900A -osfo=/usr/lpp/psf/VMfonts myfile
```

enq -P3900A -oformdef=F100S /usr/lpp/psf/README

```
and
```

```
eng -P3900A -osfo=/usr/lpp/psf/vmfonts myfile
```

specify two different directories to search for fonts.

In addition, the first example below is valid and the second one is not because the **-F** keyword used with the **ps2afp** command must be uppercase.

```
enq -P3900A -odatatype=postscript -o-FFontMapFile
enq -P3900A -odatatype=postscript -o-FFontMapFile
```

 The following flags show the minimum version of the keyword, as well as the complete keyword. For example, you can abbreviate the -obin keyword to two letters: -obi.

-o Attribute-Value Pairs

You can use the following keyword-value pairs with the AIX print commands **enq**, **lp**, or **qprt**, or with the **lprafp** command, to pass information to Infoprint.

{-oac | -oaccount}=account

Specifies the account information that Infoprint prints on start, end, and separator sheets. The account information can also be used for audit and accounting purposes.

This command keyword is equivalent to the Infoprint document attribute account-text.

You must specify a value of **full** for one of the Infoprint actual destination auxiliary sheet attributes (**accounting-exit**, **audit-exit**, **printer-start-sheet**, **printer-end-sheet**, or **printer-separator-sheet**) for Infoprint to use this information.

The value is: *account*

Any 1 to 20 characters of account information.

-oaddress1=address1

Specifies the first line of address information that Infoprint prints on start, end, and separator sheets. The address information can also be used for audit and accounting purposes.

This command keyword is equivalent to the Infoprint document attribute address1-text.

You must specify a value of **full** for one of the Infoprint actual destination auxiliary sheet attributes (**accounting-exit**, **audit-exit**, **printer-start-sheet**, **printer-end-sheet**, or **printer-separator-sheet**) for Infoprint to use this information.

The value is: *address1*

Any 1 to 90 characters of address information.

-oaddress2=address2

Specifies the second line of address information that Infoprint prints on start, end, and separator sheets. Other information is the same as for **-oaddress1.**

This command keyword is equivalent to the Infoprint document attribute address2-text.

-oaddress3=address3

Specifies the third line of address information that Infoprint prints on start, end, and separator sheets. Other information is the same as for **-oaddress1**.

This command keyword is equivalent to the Infoprint document attribute address3-text.

-oaddress4=address4

Specifies the fourth line of address information that Infoprint prints on start, end, and separator sheets. Other information is the same as for **-oaddress1.**

This command keyword is equivalent to the Infoprint document attribute address4-text.

${-obi \mid -obin} = {1 \mid 2 \text{ to } 255 \mid 65 \mid 100}$

Determines the input bin used for the job. This keyword overrides the value specified in the form definition. If you do not specify the **-obin** keyword, Infoprint uses the bin value specified in the form definition you provide for printing the job. If you do not specify the **-obin** keyword and the default form definition is used to print your job, the input bin value in the printer profile or in that form definition is used.

This command keyword is similar to the Infoprint document attribute **default-input-tray**.

Values are:

 $\frac{1}{2}$ Selects the primary bin for the printer device. This is the default.

You can specify bin 2 to bin 255. Refer to your printer documentation for more information about the bins available on the printer device.

65 Selects the envelope bin on certain IBM printer devices.

100 Selects manual feed on certain IBM printer devices.

{-obu | -obuilding}=building

Specifies the building information that Infoprint prints on start, end, and separator sheets. The building information can also be used for audit and accounting purposes.

This command attribute is equivalent to the Infoprint document attribute building-text.

You must specify a value of **full** for one of the Infoprint actual destination auxiliary sheet attributes (**accounting-exit**, **audit-exit**, **printer-start-sheet**, **printer-end-sheet**, or **printer-separator-sheet**) for Infoprint to use this information.

The value is: *building*

Any 1 to 90 characters of building information.

{-ocd | -ocdp | -ocod | -ocodepage}={850 | 437 | 860 | 863 | 865}

Specifies the ASCII input code page used for the job; that is, the "keyboard" code that Infoprint uses to translate the ASCII code points it finds in the job.

This command attribute is similar to the Infoprint document attribute default-character-mapping.

Values are:

850 Defaults to the IBM code page 850.

nnn Other possible input code page values are 437 (a subset of the IBM code page 850), 860 (Portuguese), 863 (French Canadian), or 865 (Nordic); however, none of these IBM code pages are directly supported by AIX. If you are using a different ASCII code page as your keyboard code page, you can select 437, 860, 863, or 865, depending on which code page is the closest match to the one you are currently using.

Notes:

- 1. This parameter is used only for ASCII jobs. If you specify **-odatatype=dbcsascii**, Infoprint ignores the value you specify for the **-ocodepage** keyword and value.
- 2. The Infoprint ASCII data type does not support the non-U.S. code pages supported by AIX (for example, IBM 932 and the variations of ISO8859). Infoprint supports code pages 437, 860, 863, and 865 so that you can select the code page that most closely matches the one you are currently using, if you are located outside the United States and using the ASCII data type.
- 3. If you are printing single-byte ASCII code points that are part of code page 932 (Japan), 938 (Traditional Chinese), or an Extended UNIX Code (EUC) code set for Japan, China, or Korea, you must use the **db2afp** command to print the file, even though the entire file is single-byte ASCII.

{-ocop | -ocopies}={1 to 255}

Specifies the number of copies of the job. If you also specify one of the copy flags for the AIX print command (the -N flag of the enq and qprt commands, or the -n flag of the lp command), the value you specify with the -ocopies keyword overrides the value specified with the -N or -n flag.

This command keyword is equivalent to the Infoprint document attribute **copy-count**.

Values are:

1 The minimum number of copies. This is the default.

255 The maximum number of copies.

{-odatac | -odatack}={block | blkchar | blkpos | unblock}

Determines what type of errors in the job cause Infoprint to issue error messages. The value you assign to this keyword can significantly affect IPDS printer performance as described in the following list.

This command keyword is similar to the Infoprint document attribute data-fidelity-problem-reported.

Values are:

Block print-positioning errors and invalid-character errors; that is, do not report these errors or issue error messages for these types of errors. This value produces the best printer performance.

Print-positioning errors occur when the printer device tries to print outside the valid printable area of the form. Invalid-character errors include attempts to use a code point that is not assigned to a character in an AFP font.

block is the default.

blkchar

Block invalid-character errors; that is, do not report these errors. However, Infoprint reports print-positioning errors and issues error messages for them.

blkpos

Block print-positioning errors; that is, do not report these errors. However, Infoprint reports invalid-character errors and issues error messages for them.

unblock

Report all print-positioning errors and invalid-character errors. If the job has many errors, selecting **unblock** could decrease your IPDS printer device's performance because of the constant communication between the printer device and Infoprint, and because of the repositioning that must occur to continue printing the next page after the page containing the error. You might use this value when diagnosing problems with Infoprint.

{-odatat | -odatatype}={ascii | afpds | dbcsascii | ditroff | gif | jpeg | line | modcap | pcl | pdf | postscript | sap | tiff}

Specifies the type of the input data stream. If you do not specify the **-odatatype** keyword, Infoprint reads the first few lines of the file to determine if the file is an AFP data stream. If Infoprint does not find AFP data stream commands in the file, it assumes a data type of ASCII.

If you are printing PostScript, ditroff, S/370 line data, PCL, double-byte character set (DBCS) ASCII, Extended UNIX Code (EUC) on a PSF physical printer, or if you are printing ASCII data that you want to format with a page definition on a PSF physical printer, specifying the particular data type alerts Infoprint to execute the appropriate transform command (ps2afp, d2afp, line2afp, pcl2afp, or db2afp) before printing the file. In this way, you can specify transform-specific options with the -o flag. See "-o Keywords and Values for Specific Data Types" on page 117 for more information.

This command keyword is equivalent to the Infoprint document attribute document-format.

Values are:

{as | ascii}

The type of data is an ASCII data stream with embedded controls for an IBM 4201-2 Proprinter or 5202 printer. You can also specify **ascii** to print "flat" ASCII (no embedded formatting controls except for newline characters) without using a page definition.

ascii is the default.

{af | afpds}

The type of data is an Advanced Function Presentation data stream.

gif The type of data is Graphical Interchange Format.

jpeg The type of data is Joint Photographic Experts Group.

{db | dbcsascii}

The type of data is double-byte character set (DBCS) ASCII for Japanese or Traditional Chinese, or Extended UNIX Code (EUC) for Japanese, Traditional Chinese, or Korean. DBCS ASCII may contain controls for an IBM 5577 or 5587 printer. When you specify

this value, Infoprint automatically runs the **db2afp** command to transform the DBCS ASCII or EUC into printable AFP data. Infoprint ignores any values specified with the **-ocodepage** flag and keyword.

If you are printing EUC data, you must also specify **-o-e** (the **db2afp -e** flag) along with **-odatatype=dbcsascii**.

{d | ditroff}

The type of data is ditroff, which is a device-independent data stream (troff files that have been formatted for Infoprint using the **troff -Tafp** command). When you specify this value, Infoprint automatically runs **d2afp** to transform the ditroff into printable AFP data.

{1 | line}

The type of data is S/370 line data or is ASCII data that you want to format with a page definition. When you specify this value, Infoprint automatically runs **line2afp** to transform the ASCII or line data into printable AFP data.

Note: If the input file is ASCII, but you want to use fonts that have EBCDIC code points, you must also specify a **line2afp** input exit program to convert the ASCII file to EBCDIC. Infoprint supplies two input exit programs that perform this function:

- /usr/lpp/psf/bin/apka2e, which is appropriate for ASCII files that only contain line feed controls (not carriage returns and form feeds)
- /usr/lpp/psf/bin/asciinpe, which is appropriate for ASCII files that contain line feed, carriage returns, and form feeds.

You specify an exit program using the **-oinpexit** keyword-value pair on the AIX print command.

{mo | modcap}

The type of data is a Mixed Object: Document Content Architecture for Presentation data stream.

{pc | pcl}

The type of data is PCL. When you specify this value, Infoprint automatically runs **pcl2afp** to transform the PCL into printable AFP data.

pdf The type of data is PDF. When you specify this value, Infoprint automatically runs pdf2afp to transform the PDF into printable AFP data.

{ps | postscript}

The type of data is PostScript. When you specify this value, Infoprint automatically runs **ps2afp** to transform the PostScript into printable AFP data.

sap The type of data is an OTF data stream.

You cannot submit ABAP List Format files with the **-odatatype=sap** flag and keyword-value pair. If you submit an ABAP List Format file, Infoprint will convert it to line data, try to print it, and fail.

You must first use **sap2afp** to convert the ABAP List Format file to line data, then submit it with the -odatatype=line flag and keyword-value pair.

tiff The type of data is Tag Image File Format.

{-ode | -odepartment}=department

Specifies the department information that Infoprint prints on start, end, and separator sheets. The department information can also be used for audit and accounting purposes.

This command keyword is equivalent to the Infoprint document attribute department-text.

You must specify a value of full for one of the Infoprint actual destination auxiliary sheet attributes (accounting-exit, audit-exit, printer-start-sheet, printer-end-sheet, or printer-separator-sheet) for Infoprint to use this information.

The value is:

department

Any 1 to 90 characters of department information.

{-odi | -odistribution}=distribution

Specifies the distribution information that Infoprint prints on start, end, and separator sheets.

If you do not specify the **-odistribution** keyword for local jobs, no distribution information prints. For remote jobs, the value defaults to the information provided by AIX (usually the user ID and the name of the host from which the job was submitted; for example, **bob@sys1**).

The value is:

distribution

Any 1 to 90 characters of distribution information. Whether all of these characters print depends on the user exit program.

{-odo | -odocname | -ojobn | -ojobname}=JobName

Identifies the document name or job name associated with this job. If you do not specify the -odocname or -ojobname keyword for ASCII or AFP data stream jobs, Infoprint uses the file name of the first file in the job.

If you do not specify the **-odocname** keyword for other types of data, Infoprint creates a temporary file for the transform output and uses that temporary file name for the job name. If you want to retain the original name of the input file for these types of data, you can specify a job name with this keyword.

The **-odocname** command keyword is equivalent to the Infoprint document attribute **document-file-name**. The **-ojob** command keyword is equivalent to the Infoprint job attribute **job-name**.

The value is:

IobName

You can enter a job name of up to 255 characters in length. Note that the user-exit programs supplied with the start, end, and separator sheets assume a maximum of 50 characters for the job name. If you want to display more than 50 characters, change the user-exit programs to use the number of characters you need. Use single quotes (') or double quotes (") if the document name or job name contains spaces (blanks).

{-odu | -oduplex}={no | yes | tumble}

Specifies whether the job prints on one or both sides of the paper and how successive pages are oriented. This keyword overrides the value specified in the form definition. If you do not specify the **-oduplex** keyword, Infoprint uses the duplex printing value specified in the form definition you provide for printing the job. If you do not specify the **-oduplex** keyword and the default form definition is used to print your job, the duplex printing value in the printer profile or in that form definition is used.

This command keyword is similar to the Infoprint document attributes **plex** and **sides**.

Values are:

 ${n \mid no}$

The job prints on one side of the sheet. This is the default.

 $\{y \mid yes\}$

The job prints on both sides of the sheet, top edge to top edge.

{t | tumble}

The job prints on both sides of the sheet. The top edge of one side is the bottom edge of the other side.

{-of | -oformdef}=*FormDefinitionName*

Specifies the name of the form definition Infoprint uses for the job. The form definition defines the placement of the page of data on the form, the input and output bins to use, duplex printing, and so on.

If you do not specify the **-oformdef** keyword, Infoprint looks in the input file for an inline form definition. If the input file doesn't contain a form definition, Infoprint uses the default form definition for that Infoprint actual destination.

This command keyword is equivalent to the Infoprint document attribute form-definition.

The value is:

FormDefinitionName

Any form definition located in one of the directories defined in the search path.

You can specify a form definition name between 1 and 8 characters in length.

{-oh | -oheader}={yes | no}

Specifies whether Infoprint prints a start sheet before the job.

This command keyword is similar to the Infoprint job attribute auxiliary-sheet-selection.

Values are:

 $\{y \mid yes\}$

Print the start sheet specified by the actual destination attribute **printer-start-sheet** before the job. If there are multiple files in a single job, a start sheet is printed before the first file only. This is the default.

{n | no}

Do not print a start sheet.

{-omsgc | -omsgcount}={9999 | 1 to 9998 | 0}

Specifies the number of messages or groups of related messages that Infoprint prints with the job. A message group consists of one error or warning message, followed by one or more secondary messages.

This command keyword is similar to the Infoprint document attribute maximum-messages-printed.

Values are:

9999 All messages print. This is the default.

1 to 9998

A specified number of messages print.

No messages print.

Note: When Infoprint reaches the message count value, Infoprint processing continues; however, Infoprint prints no additional messages.

{-ona | -oname}=name

Specifies the name information that Infoprint prints on start, end, and separator sheets. The name information can also be used for audit and accounting purposes.

This command keyword is equivalent to the Infoprint document attribute name-text.

You must specify a value of full for one of the Infoprint actual destination auxiliary sheet attributes (accounting-exit, audit-exit, printer-start-sheet, printer-end-sheet, or printer-separator-sheet) for Infoprint to use this information.

The value is:

Any 1 to 90 characters of name information.

{-ono | -onodeid}=NodeID

Specifies the node ID information that Infoprint prints on start, end, and separator sheets. The node ID information can also be used for audit and accounting purposes.

This command keyword is equivalent to the Infoprint document attribute node-id-text.

You must specify a value of full for one of the Infoprint actual destination auxiliary sheet attributes (accounting-exit, audit-exit, printer-start-sheet, printer-end-sheet, or printer-separator-sheet) for Infoprint to use this information.

The value is:

NodeID

Any 1 to 20 characters of nodeid information.

{-oou | -ooutbin}={ 1 | 2 to 65535}

Determines the output bin used for the job. If you do not specify the **-ooutbin** keyword, the output bin value in the printer profile is used.

This command keyword is similar to the Infoprint document attribute output-bin and the Infoprint actual destination attribute output-bin-numbers.

Values are:

<u>1</u> Selects the primary output bin for the printer device. This is the default.

2 to 65535

You can specify bin 2 to bin 65535. Refer to your printer documentation for more information about the bins available on the printer device.

{-oov | -ooverlay}=OverlayName

Specifies the name of an overlay to be printed on every page of the job. An overlay contains predefined data, such as lines, shading, text, boxes, or logos that can be merged with variable data on a printed page. Overlays can also be specified in a form definition. Any overlay you name here is printed in addition to overlays named in the form definition.

This command keyword is equivalent to the Infoprint document attribute **overlay**.

The value is:

OverlayName

Any overlay located in one of the directories defined in the search path.

You can specify an overlay name between 1 and 8 characters in length.

{-opa | -opassthru}=PassthruFlags

Identifies any other information provided when the job is submitted.

You specify this information in the following format:

-opassthru={PassthruFlag=value, [PassthruFlag=value,]...}

The following flags are supported by the user-exit program supplied with Infoprint:

class Identifies the 1-character class keyword provided by TCP/IP for MVS for those jobs submitted to Infoprint from MVS hosts through the Network Print Facility (NPF), PSF Direct, or MVS Download.

destination

Identifies the 1-to 8-character destination keyword provided for those jobs submitted to Infoprint from MVS hosts through the Network Print Facility (NPF), PSF Direct, or MVS Download.

forms Identifies the 1-to 8-character forms keyword provided for those jobs submitted to Infoprint from MVS hosts through the Network Print Facility (NPF), PSF Direct, or MVS Download.

segmentid

Identifies the 1-to 10-character segmentation identifier provided by TCP/IP for MVS for those jobs submitted to Infoprint from MVS hosts through the Network Print Facility (NPF), PSF Direct, or MVS Download.

This command keyword is equivalent to the Infoprint document attributes mvs-class, mvs-destination, mvs-forms, and mvs-segment-id.

{-opr | -oprogrammer}=programmer

Specifies the programmer information that Infoprint prints on start, end, and separator sheets. The programmer information can also be used for audit and accounting purposes.

This command keyword is equivalent to the Infoprint document attribute programmer-text.

You must specify a value of full for one of the Infoprint actual destination auxiliary sheet attributes (accounting-exit, audit-exit, printer-start-sheet, printer-end-sheet, or printer-separator-sheet) for Infoprint to use this information.

The value is:

programmer

Any 1 to 40 characters of programmer information.

{-oresp | -orespath}=PathList

Specifies the search order that Infoprint uses for all Advanced Function Printing (AFP) resources.

This command keyword is equivalent to the Infoprint document attribute resource-context-user.

If you do not specify this keyword, Infoprint uses these search orders:

- · For fonts:
 - 1. The paths named in the **-osrchfontlib** keyword
 - 2. The paths named in the Infoprint default document attribute resource-context-user
 - 3. The paths named in the Infoprint default document attribute resource-context-font
 - 4. The paths named in the Infoprint default document attribute resource-context
 - 5. The paths named in the **PSFPATH** environment variable
 - 6. The paths named in the Infoprint actual destination attribute resource-context-font
 - 7. The directory /usr/lpp/psf/reslib
 - 8. The directory /usr/lpp/afpfonts
 - 9. The directory /usr/lpp/psf/fontlib
- For other resources:
 - 1. The paths named in the Infoprint default document attribute resource-context-user
 - 2. The paths named in the Infoprint default document attributes resource-context-form-definition, resource-context-overlay, resource-context-page-definition, or resource-context-page-segment,
 - 3. The paths named in the Infoprint default document attribute resource-context
 - 4. The paths named in the PSFPATH environment variable
 - 5. The paths named in the Infoprint actual destination attributes resource-context-form-definition, resource-context-overlay, resource-context-page-definition, or resource-context-page-segment,
 - 6. The directory /usr/lpp/psf/reslib

The value is:

PathList

Any valid search path on the system where the job prints. You must use a colon (:) to separate multiple paths.

{-oro | **-oroom**}=*room*

Specifies the room information that Infoprint prints on start, end, and separator sheets. The room information can also be used for audit and accounting purposes.

This command keyword is equivalent to the Infoprint document attribute room-text.

You must specify a value of **full** for one of the Infoprint actual destination auxiliary sheet attributes (**accounting-exit**, **audit-exit**, **printer-start-sheet**, **printer-end-sheet**, or **printer-separator-sheet**) for Infoprint to use this information.

The value is:

room Any 1 to 90 characters of room information.

{-osep | -oseparator}={ yes | no}

Specifies whether Infoprint prints separator sheets between copies of the job.

This command keyword is similar to the Infoprint job attribute auxiliary-sheet-selection.

Values are:

$\{y \mid yes\}$

Print the separator sheet specified by the actual destination attribute **printer-separator-sheet** between copies of the job. This is the default.

 $\{n \mid no\}$

Do not print separator sheets.

{-osfo | -osrchfo | -osrchfontlib}=PathList

Specifies one or more paths Infoprint searches for the fonts required by the job.

This command keyword is equivalent to the Infoprint document attribute resource-context-font.

If you do not specify this keyword, Infoprint uses this search order:

- 1. The paths named in the **-orespath** keyword
- 2. The paths named in the Infoprint default document attribute resource-context-user
- The paths named in the Infoprint default document attribute resource-context-font
- The paths named in the Infoprint default document attribute resource-context
- 5. The paths named in the **PSFPATH** environment variable
- The paths named in the Infoprint actual destination attribute resource-context-font
- 7. The directory /usr/lpp/psf/reslib
- 8. The directory /usr/lpp/afpfonts
- 9. The directory /usr/lpp/psf/fontlib

The value is:

PathList

Any valid search path on the system where the job prints. You must use a colon (:) to separate multiple paths.

{-oti ∣ -otitle}=*title*

Specifies the title information that Infoprint prints on start, end, and separator sheets. The title information can also be used for audit and accounting purposes.

This command keyword is equivalent to the Infoprint document attribute title-text.

You must specify a value of full for one of the Infoprint actual destination auxiliary sheet attributes (accounting-exit, audit-exit, printer-start-sheet, printer-end-sheet, or printer-separator-sheet) for Infoprint to use this information.

The value is:

Any 1 to 90 characters of title information.

{-otr | -otrailer}={yes | no}

Specifies whether an end sheet prints after the job.

This command keyword is similar to the Infoprint job attribute auxiliary-sheet-selection.

Values are:

 $\{y \mid yes\}$

Print the end sheet specified by the actual destination attribute **printer-end-sheet** after the job. This is the default.

 $\{n \mid no\}$

Do not print an end sheet.

{-ous | -ouserid}=*UserID*

Specifies the user ID information that Infoprint prints on start, end, and separator sheets. The user ID information can also be used for audit and accounting purposes.

This command keyword is equivalent to the Infoprint document attribute user-id-text.

You must specify a value of **full** for one of the Infoprint actual destination auxiliary sheet attributes (accounting-exit, audit-exit, printer-start-sheet, printer-end-sheet, or printer-separator-sheet) for Infoprint to use this information.

The value is:

UserID

Any 1 to 20 characters of userid information.

{-oxo | -oxoffset}=nnnn.nnnu

Specifies the X offset of the logical page origin from the physical page origin. This keyword overrides any X offset value in the form definition. If you do not specify the **-oxoffset** keyword, Infoprint uses the X offset value specified in the form definition you provide for printing the job.

This command keyword is equivalent to the Infoprint document attribute x-image-shift.

The value is:

nnnn.nnnu

A numeric value that establishes the X (across) coordinate of the logical page origin, as shown in the figure below. nnnn.nnn is a number that can optionally contain a decimal point, and u is the units in inches (i) or millimeters (m).

If you do not specify a unit (i or m), then Infoprint uses pels as the unit type. You cannot specify fractional values (that is, you cannot use a decimal point) for pels.

Note: If you specify a value that is outside of the printable area, you will get a print-positioning error. To determine the printable area of IBM printer devices, see *Advanced Function Presentation: Printer Information*.

{-oyo | -oyoffset}=nnnn.nnnu

Specifies the Y offset of the logical page origin from the physical page origin. This keyword overrides any Y offset value in the form definition. If you do not specify the **-oyoffset** keyword, Infoprint uses the Y offset value specified in the form definition you provide for printing the job.

This command keyword is equivalent to the Infoprint document attribute **y-image-shift**.

The value is:

nnnn.nnnu

Any numeric value that establishes the Y (down) coordinate of the logical page origin. nnnn.nnn is a number that can optionally contain a decimal point, and u is the units in inches (i) or millimeters (m).

If you do not specify a unit (i or m), then Infoprint uses pels as the unit type. You cannot specify fractional values (that is, you cannot use a decimal point) for pels.

Note: If you specify a value that is outside of the printable area, you will get a print-positioning error. To determine the printable area of IBM printer devices, see *Advanced Function Presentation: Printer Information*.

-o Keywords and Values for Specific Data Types

You can also use **-o** to specify keywords (transform command flags or options) that apply to the following specific data types:

- · Double-byte character set (DBCS) ASCII data
- Extended UNIX code (EUC) data
- Graphical Interchange Format (GIF) data
- Joint Photographic Experts Group (JPEG) data
- · Line data
- PCL data
- Portable Document Format (PDF) data
- PostScript data
- Tag Image Format File (TIFF) data

For example, to specify that the finished width of a PostScript image is 6 inches, enter:

enq -P3825C -odatatype=ps -o-w6i memo1.ps

DBCS ASCII Data and EUC Data

If you are printing DBCS (double-byte) ASCII or Extended UNIX Code (EUC) data:

- Specify -odatatype=dbcsascii for DBCS ASCII or -odatatype=dbcsascii -o-e for EUC with the enq, lp, qprt, or lprafp command; or allow Infoprint to identify the data type.
- Infoprint automatically runs the **db2afp** transform command.
- You can use the following db2afp flags on the command line with enq, lp, qprt or lprafp:

```
-о-е
-o-lja
-o-lch
-o-lko (EUC only)
```

For information about these flags, see "db2afp Command: Transforms DBCS Data to AFP" on page 205.

You cannot use the **db2afp -o** flag to specify an output file.

Note: The db2afp transform must be installed on the workstation where Infoprint is installed.

GIF Data

If you are printing GIF data:

- Specify -odatatype=gif with the enq, lp, qprt, or lprafp command; or allow Infoprint to identify the data type.
- Infoprint automatically runs the **gif2afp** transform command.
- You can use the following gif2afp options on the command line with enq, lp, qprt, or lprafp. For those options that accept a value, do not put a blank between the option and the value.

```
-o-aImageType
-o-algProcessingAlgorithms
-o-calibcalibration
-o-CConfigurationFile
-o-cleancleanup
-o-cmpcompression
-o-cropCropFactors
-o-fit{trim | scale}
-o-gcorrGrayscaleMappingTable
-o-inkcolor
-o-inv
-o-iScanOffsetFileName
-o-lImageLength
-o-MMemoryBound
-o-msspace
-o-msfSpaceFraction
-o-nosniff
-o-noterm
-o-nov
-o-outbitsNumberOfOutputBits
-o-outcolorOutputColorModel
-o-pPageRange
-o-pagetypePageType
-o-paperPaperSize
-o-rresolution
-o-respathResourceSearchPath
```

```
-o-rotrotation
-o-scaleImageSize
-o-sgcorrScannerCorrection
-o-sniff
-o-term
-o-threshHalftoneFile
-o-v
-o-wImageWidth
-o-xLeftMargin
-o-yTopMargin
```

For information about these options, see "gif2afp Command: Transforms GIF Data to AFP in Infoprint Manager for AIX" on page 212.

You cannot use the print command -o flag to pass the gif2afp -o option to specify an output file, or the @, -f, and -z options to specify input files.

Note: The gif2afp transform must be installed on the workstation where Infoprint is installed.

JPEG Data

If you are printing JPEG data:

- Specify -odatatype=jpeg with the enq, lp, qprt, or lprafp command; or allow Infoprint to identify the data type.
- Infoprint automatically runs the **jpeg2afp** transform command.
- You can use the following jpeg2afp options on the command line with enq, lp, qprt, or lprafp. For those options that accept a value, do not put a blank between the option and the value.

```
-o-aImageType
-o-algProcessingAlgorithms
-o-calibcalibration
-o-CConfigurationFile
-o-cmpcompression
-o-cropCropFactors
-o-fit{trim | scale}
-o-force
-o-gcorrGrayscaleMappingTable
-o-iScanOffsetFileName
```

- -o-lImageLength
- -o-MMemoryBound
- -o-msspace
- -o-msfSpaceFraction
- -o-noterm
- -o-nov
- **-o-outbits**NumberOfOutputBits
- -o-outcolorOutputColorModel
- -o-pPageRange
- **-o-pagetype***PageType*
- -o-paperPaperSize
- **-o-r**resolution
- -o-respathResourceSearchPath
- -o-rotrotation
- -o-scaleImageSize
- -o-sgcorrScannerCorrection
- -o-term

```
-o-threshHalftoneFile
-o-v
-o-wImageWidth
-o-wrkdirWorkDirectory
-o-xLeftMargin
-o-yTopMargin
```

For information about these options, see "jpeg2afp Command: Transforms JPEG Data to AFP in Infoprint Manager for AIX" on page 226.

You cannot use the print command **-o** flag to pass the **jpeg2afp -o** option to specify an output file, or the @, **-f**, and **-z** options to specify input files.

Note: The **jpeg2afp** transform must be installed on the workstation where Infoprint is installed.

Line Data

If you are printing S/370 line data, or you are printing ASCII data that you want to format with a page definition:

- Specify **-odatatype=line** with the **enq**, **lp**, **qprt**, or **lprafp** command; or allow Infoprint to identify the data type.
- Infoprint automatically runs the line2afp transform command.
- You can use the following **line2afp** flags on the command line with **enq**, **lp**, **qprt**, or **lprafp**:

```
-occ=value
-occtype=value
-ochars=FontName[, ...]
-ofileformat=value
-oformdef=FormDefinitionName
-oimageout=value
-oinpexit=ProgramName
-omsgdd=FileName
-ooutexit=ProgramName
-opagedef=PageDefinitionName
-oparmdd=FileName
-opdeflib=PathList
-oprmode=value
-oresexit=ProgramName
-otrc=value
-ouserlib=PathList
```

For information about these flags, see "line2afp Command: Transforms S/370 Line Data and ASCII Data to AFP" on page 239.

You cannot use line2afp flags for the input file (inputdd) or the output file (outputdd).

When you are using **line2afp** flags with an AIX print command, you should not use **line2afp** flags that do the same thing as Infoprint-specific **-o** flags. Use the Infoprint-specific **-o** flags instead:

- Use enq -odatatype=line -orespath= instead of enq -odatatype=line -ofdeflib=
- Use enq -odatatype=line -osrchfontlib= instead of enq -odatatype=line -ofontlib=

- Use enq -odatatype=line -orespath= instead of enq -odatatype=line -oovlylib=
- Use enq -odatatype=line -orespath= instead of enq -odatatype=line -opseglib=
- Use enq -odatatype=line -orespath= instead of enq -odatatype=line -oreslib=

Note: The **line2afp** transform and **acif** command must be installed on the workstation where Infoprint is installed.

PCL Data

If you are printing PCL data:

- Specify **-odatatype=pcl** with the **enq**, **lp**, **qprt**, or **lprafp** command; or allow Infoprint to identify the data type.
- Infoprint automatically runs the pcl2afp transform command.
- You can use the following pcl2afp flags on the command line with enq, lp, qprt, or lprafp. For those flags that accept a value, do not put a blank between the flag and the value.

```
-o-aOutputType
```

-o-c

-o-*CConfigurationFile* (the configuration file must be specified as a full path name)

- -o-jnnnn
- -o-lnnnn.nnnu
- -o-Mnnnnn
- -o-pPageRange
- -o-Pnnnnn
- -o-q
- **-o-r**nnn
- -o-SServerName
- **-o-s**nnnn
- -o-wnnnn.nnnu
- -o-xnnnn.nnnu
- -o-ynnnn.nnnu

For information about these flags, see "pcl2afp Command: Transforms PCL Data to AFP" on page 264.

You cannot use the pcl2afp -o flag to specify an output file.

Note: The **pcl2afp** transform must be installed on the workstation where Infoprint is installed.

PostScript and PDF Data

If you are printing PostScript or PDF data:

- Specify -odatatype=ps or -odatatype=pdf with the enq, lp, qprt, or lprafp command; or allow Infoprint to identify the data type.
- Infoprint automatically runs the **ps2afp** transform command. (The **pdf2afp** command is another name for **ps2afp**.)
- You can use the following **ps2afp** flags on the command line with **enq**, **lp**, **qprt**, or **lprafp**. For those flags that accept a value, do not put a blank between the flag and the value.

```
-o-aOutputType
```

-о-с

-o-CConfigurationFile (the configuration file must be specified as a full path **-o-F**FontMapFile[:...] (the font map files must be specified as full path names) -o-gPageRange **-o-j***nnnn* -o-lnnnn.nnnu -o-Mnnnnn -o-pPageRange -o-Pnnnnn -o-q **-o-r**nnn -o-SServerName **-o-s**nnnn -o-wnnnn.nnnu -o-xnnnn.nnnu -o-ynnnn.nnnu

For information about these flags, see "pdf2afp and ps2afp Transforms: Transform PDF or PostScript Data to AFP" on page 287.

You cannot use the **ps2afp -o** flag to specify an output file.

Note: The ps2afp transform must be installed on the workstation where Infoprint is installed.

TIFF Data

If you are printing TIFF data:

- Specify -odatatype=tiff with the enq, lp, qprt, or lprafp command; or allow Infoprint to identify the data type.
- Infoprint automatically runs the **tiff2afp** transform command.
- You can use the following tiff2afp options on the command line with enq, lp, qprt, or lprafp. For those options that accept a value, do not put a blank between the option and the value.

```
-o-aImageType
-o-algProcessingAlgorithms
-o-calibcalibration
-o-choiceImageChoice
-o-CConfigurationFile
-o-cleancleanup
-o-cmpcompression
-o-cropCropFactors
-o-fit{trim | scale}
-o-force
-o-gcorrGrayscaleMappingTable
-o-inkcolor
-o-inv
-o-iScanOffsetFileName
-o-lImageLength
-o-MMemoryBound
-o-mp
-o-msspace
-o-msfSpaceFraction
-o-nomp
-o-nosniff
-o-noterm
```

```
-o-nov
-o-outbitsNumberOfOutputBits
-o-outcolorOutputColorModel
-o-pPageRange
-o-pagetypePageType
-o-paperPaperSize
-o-rresolution
-o-respathResourceSearchPath
-o-rotrotation
-o-scaleImageSize
-o-sgcorrScannerCorrection
-o-sniff
-o-term
-o-threshHalftoneFile
-o-v
-o-wImageWidth
-o-wrkdirWorkDirectory
-o-xLeftMargin
-o-yTopMargin
```

For information about these options, see "tiff2afp Command: Transforms TIFF Data to AFP in Infoprint Manager for AIX" on page 313.

You cannot use the print command **-o** flag to pass the **tiff2afp -o** option to specify an output file, or the @, **-f**, and **-z** options to specify input files.

Note: The **tiff2afp** transform must be installed on the workstation where Infoprint is installed.

Examples

• To submit the ASCII file myfile to the Infoprint logical destination called Xserv-lp with four copies printed on one side of hole-punched paper, which is stored in the secondary bin of the printer device, enter:

```
enq -P Xserv-lp -obin=2 -ocopies=4 -oduplex=n myfile
```

Infoprint includes a form definition that specifies single-sided printouts of hole-punched paper from bin 2. If this form definition (F1H10120) is installed in the default directory, you could alternatively type:

```
enq -P Xserv-lp -ocopies=4 -oformdef=F1H10120 myfile
```

 To submit AFP data stream files file1 and file2 to the Infoprint logical destination called dtsrv-lp, with a search path for fonts of /home/afpfonts, enter:

```
lp -d dtsrv-lp -osrchfontlib=/home/afpfonts file1 file2
```

• To submit the PostScript file myfile to the Infoprint logical destination called servB-lp (which has a resolution of 300 pels), with a form definition of F1PP0120, with no reported invalid-character errors, and with a maximum of 100 printed messages, enter:

```
qprt -P servB-lp -o-r300 -odatac=blkchar -odatat=ps -of=F1PP0120
    -omsqc=100 myfile
```

-o Flag

Chapter 4. Infoprint Administrative Utilities

This chapter describes the following Infoprint administrative utilities:

Utility Name	AIX	NT and 2000
"admingui Utility: Opens the Print Administration Window of the Basic Infoprint Administrator's GUI in Infoprint Manager for AIX" on page 129	AIX	N/A
"afpsplit Utility: Extracts Pages from a MO:DCA-P File" on page 130	AIX	NT and 2000
"ainupod1 Utility: Generates Accounting Information by User" on page 131	AIX	NT and 2000: must be issued from the <i>install_path</i> \bin directory
"ainupod2 Utility: Generates Accounting Information by Job" on page 132	AIX	NT and 2000: must be issued from the <i>install_path</i> \bin directory
"ainupod3 Utility: Generates Accounting Information for a User" on page 133	AIX	NT and 2000: must be issued from the <i>install_path</i> \bin directory
"ainurpt1 Utility: Generates Accounting Information by Actual Destination" on page 135	AIX	NT and 2000: must be issued from the <code>install_path\bin</code> directory
"ainurpt2 Utility: Generates Accounting Information by User" on page 136	AIX	NT and 2000: must be issued from the <code>install_path\bin</code> directory
"ainurpt3 Utility: Generates Accounting Information for a User" on page 137	AIX	NT and 2000: must be issued from the <i>install_path</i> \bin directory
"ainurpt4 Utility: Generates Audit Information by Destination" on page 139	AIX	NT and 2000: must be issued from the <i>install_path</i> \bin directory
"ainurpt5 Utility: Generates Audit Information by User" on page 140	AIX	NT and 2000: must be issued from the <i>install_path</i> \bin directory
"ainurpt6 Utility: Generates Audit Information for a User" on page 141	AIX	NT and 2000: must be issued from the <code>install_path\bin</code> directory
"cfu Utility: Displays and Builds Coded Fonts in Infoprint Manager for AIX" on page 142	AIX	N/A
"cmt Utility: Builds Color Mapping Table Source and Object Files in Infoprint Manager for AIX" on page 144	AIX	N/A

Administrative Utilities

"ipguiadv, ipguibasic, and ipguidist Utilities: Start the Infoprint Manager Operations GUI" on page 146	AIX	NT and 2000: add .bat to command name
"ipguiadvadm, ipguibasicadm, and ipguidistadm Utilities: Start the Infoprint Manager Administration GUI" on page 147	AIX	NT and 2000: add .bat to command name
"jsmigr Utility: Migrates PSF for AIX Job Scripts in Infoprint Manager for AIX" on page 149	AIX	N/A
"notification client" on page 151	AIX	NT and 2000
"opergui Utility: Opens the Print Management Window of the Basic Infoprint Administrator's GUI in Infoprint Manager for AIX" on page 152	AIX	N/A
"pdadmin Utility: Opens the Servers Window of the Advanced Infoprint Administrator's GUI in Infoprint Manager for AIX" on page 153	AIX	N/A
"pdcrcds Utility: Creates Directories for DCE in Infoprint Manager for AIX" on page 154	AIX	N/A
"pdcrdflt Utility: Creates Default Auxiliary Sheets, Media, and Queue in Infoprint Manager for AIX" on page 155	AIX	N/A
"pdcrmed Utility: Creates Commonly Used Media in Infoprint Manager for AIX" on page 157	AIX	N/A
"pdinitports Utility: Initializes Ports" on page 158	AIX	NT and 2000
"pdmigpp Utility: Migrates Existing AIX Printers to Infoprint in Infoprint Manager for AIX" on page 160	AIX	N/A
"pdmincfg Utility: Sets up a Minimum Infoprint Configuration in Infoprint Manager for AIX" on page 162	AIX	N/A

Administrative Utilities

"pdmsg Utility: Displays Information about a Message in Infoprint Manager for AIX" on page 164	AIX	N/A
"rc.iprsap Utility: Start SAP Callback Daemons for Infoprint Manager for AIX" on page 166	AIX	N/A
"rc.pd Utility: Restarts Servers in Infoprint Manager for AIX" on page 167	AIX	N/A
"sense Utility: Senses Whether a Channel-Attached Printer is Attached to Infoprint Manager for AIX" on page 168	AIX	N/A
"sense Utility: Senses Whether a Channel-Attached Printer is Attached to Infoprint Manager for Windows NT and Windows 2000" on page 170	N/A	NT and 2000
"setup Utility: Starts the Infoprint Installer in Infoprint Manager for AIX" on page 173	AIX	NT and 2000
"startppo Utility: Starts the Infoprint SMIT Production Print Operations Interface in Infoprint Manager for AIX" on page 176	AIX	N/A
"start_server Utility: Starts a Server for a Basic Infoprint Installation in Infoprint Manager for AIX" on page 177	AIX	N/A
"startsrv Utility: Starts a Server in Infoprint Manager for AIX" on page 179	AIX	N/A
"stop_server Utility: Shuts Down a Server in Infoprint Manager for AIX" on page 181	AIX	N/A
"tdump Utility: Outputs Tape Contents in Human-Readable Format in Infoprint Manager for AIX" on page 182	AIX	N/A
"tlist Utility: Lists Files on a Tape in Infoprint Manager for AIX" on page 184	AIX	NT and 2000
"t2file Utility: Reads MVS Partitioned Data Sets from Tape in Infoprint Manager for AIX" on page 185	AIX	NT and 2000

Administrative Utilities

admingui Utility: Opens the Print Administration Window of the Basic Infoprint Administrator's GUI in Infoprint Manager for AIX

Syntax

```
admingui [-n | ServerName ...]
admingui -?
```

Description

Use the admingui utility to open the Print Administration window of the basic Infoprint administrator's GUI. The Print Administration window displays the logical destinations, actual destinations, default jobs, default documents, and media that reside in all servers in the namespace.

Flags

The admingui utility uses the following flags:

Prevents Infoprint from starting any server. If you do not specify this flag, Infoprint checks to see if any server is running. If it is not running, Infoprint invokes the **start_server** utility to start an existing server or create a new one.

When you specify **-n**, you cannot specify a *ServerName*.

? Displays help for the admingui utility.

Arguments

The argument value identifies the server to which the utility applies.

Valid argument values for the admingui utility are:

ServerName

Specifies which server to start if no other servers are currently running. ServerName defaults to the hostname. If a server is already running, Infoprint ignores this argument.

When you specify ServerName, you cannot specify the -n flag.

Examples

• To open the Print Administration window of the basic Infoprint administrator's GUI and ensure that the **default** server is started if no other server is running, enter:

admingui

• To open the Print Administration window of the basic Infoprint administrator's GUI and ensure that the **charlie** server is started if no other server is running, enter:

admingui charlie

• To open the Print Administration window of the basic Infoprint administrator's GUI without starting any servers, enter:

```
admingui -n
```

afpsplit Utility: Extracts Pages from a MO:DCA-P File

Syntax

afpsplit [-f page] [-p page] [-o OutputFile] [InputFile]

Description

Issue the **afpsplit** command to extract a page or a range of pages from an AFP MO:DCA-P document and create MO:DCA-P output.

You might use the **afpsplit** command to create a separate file starting at the 25th page and ending at the 50th page of a 200-page document. After you use the **afpsplit** command to create a file, you can view, store, print, or transmit that file.

Notes:

- afpsplit removes structured index fields from MO:DCA-P files. This does not affect the appearance of printed files, but index entries are no longer available for viewing.
- 2. **afpsplit** writes error messages to STDERR.

Flags

-f *page* Specifies the forward space function, where *page* indicates the number of pages (0-99999999) that you can forward space from the beginning of the input file to start extracting the page or range of pages. To start extracting on page *n*, forward space *n*-1 pages.

If you do not specify the **-f** flag, the extraction starts at the beginning of the file. If you specify more than one **-f** flag, the last one you specify is used.

-p page

Specifies the page end function, where *page* indicates the number of pages (0-99999999) to be extracted.

If you do not specify the **-p** flag, all pages from the forward space point to the end of the input file are included in the output file. If you specify more than one **-p** flag, the last one you specify is used.

-o OutputFile

Specifies the name of the file for the page or range of pages produced by afpsplit.

If you do not specify this flag, afpsplit uses standard output (STDOUT).

Arguments

The valid argument value for the **afpsplit** utility is:

InputFile

Specifies the input file.

If you do not specify an input file, afpsplit uses standard input (STDIN).

Example

To extract pages 21-30 from a MO:DCA-P input file called input.afp and use the **pdpr** command to print those 10 pages on printer serv1-lp, enter:

```
afpsplit -f 20 -p 10 input.afp | pdpr -p serv1-lp
```

ainupod1 Utility: Generates Accounting Information by User

Syntax

ainupod1

Description

For Infoprint Manager for AIX, use the ainupod1 utility to generate a report of accounting information for all jobs printed or transmitted on all defined PSF, fax, or email actual destinations, sorted by user ID. This information is derived from the /var/psf/podaccount.log file. By default, basic Infoprint installations set the value of the accounting-exit actual destination attribute to job-ticket, which invokes a user exit program that writes accounting information to this file.

For Infoprint Manager for Windows NT and Windows 2000, use the ainupod1 utility to generate a report of accounting information for all jobs printed or transmitted on all defined PSF actual destinations, sorted by user ID. This information is derived from the \install_path\var\psf\podaccount.log file. By default, basic Infoprint installations set the value of the accounting-exit actual destination attribute to job-ticket, which invokes a user exit program that writes accounting information to this file.

Note: On Windows NT or Windows 2000, this command must be run from the *install_path***bin** directory.

Example

To generate accounting information for all users, enter: ainupod1

ainupod1 returns information similar to the following:

Accounting Report by Customer ID

Customer	Jobs	Pages	Bin1	Bin2
apple	6	8	8	0
donald	18	2297	1511	0

Suggested Reading

- Auxiliary sheets, see "Attributes for Auxiliary-Sheet Objects" on page 458
- Other utilities that generate accounting reports from the podaccount.log file, see "ainupod2 Utility: Generates Accounting Information by Job" on page 132 and "ainupod3 Utility: Generates Accounting Information for a User" on page 133
- Utilities that generate accounting reports from the accounting.log file, see "ainurpt1 Utility: Generates Accounting Information by Actual Destination" on page 135, "ainurpt2 Utility: Generates Accounting Information by User" on page 136, and "ainurpt3 Utility: Generates Accounting Information for a User" on page 137
- Utilities that generate audit reports, see "ainurpt4 Utility: Generates Audit Information by Destination" on page 139, "ainurpt5 Utility: Generates Audit Information by User" on page 140, and "ainurpt6 Utility: Generates Audit Information for a User" on page 141

ainupod2 Utility: Generates Accounting Information by Job

Syntax

ainupod2

Description

For Infoprint Manager for AIX, use the ainupod2 utility to generate a report of accounting information for all jobs printed or transmitted on all defined PSF, fax, and email actual destinations, sorted by job ID. This information is derived from the /var/psf/podaccount.log file. By default, basic Infoprint installations set the value of the the accounting-exit actual destination attribute to job-ticket, which invokes a user exit program that writes accounting information to this file.

For Infoprint Manager for Windows NT and Windows 2000, use the ainupod2 utility to generate a report of accounting information for all jobs printed or transmitted on all defined PSF actual destinations, sorted by job ID. This information is derived from the \install_path\var\psf\podaccount.log file. By default, basic Infoprint installations set the value of the accounting-exit actual destination attribute to job-ticket, which invokes a user exit program that writes accounting information to this file.

Note: On Windows NT or Windows 2000, this command must be run from the *install_path***bin** directory.

Example

To generate accounting information for all jobs, enter: ainupod2

ainupod2 returns information similar to the following:

Accounting Report by Job ID

Job ID	Jobs	lobs Pages		Bin2
E1A0540F.3F8	7	48	48	0
E1B0440B.B0B	10	196	175	0
NONE	53	94	94	0

Suggested Reading

- Auxiliary sheets, see "Attributes for Auxiliary-Sheet Objects" on page 458
- Other utilities that generate accounting reports from the podaccount.log file, see "ainupod1 Utility: Generates Accounting Information by User" on page 131 and "ainupod3 Utility: Generates Accounting Information for a User" on page 133
- Utilities that generate accounting reports from the accounting.log file, see "ainurpt1 Utility: Generates Accounting Information by Actual Destination" on page 135, "ainurpt2 Utility: Generates Accounting Information by User" on page 136, and "ainurpt3 Utility: Generates Accounting Information for a User" on page 137
- Utilities that generate audit reports, see "ainurpt4 Utility: Generates Audit Information by Destination" on page 139, "ainurpt5 Utility: Generates Audit Information by User" on page 140, and "ainurpt6 Utility: Generates Audit Information for a User" on page 141

ainupod3 Utility: Generates Accounting Information for a User

Syntax

ainupod3

Description

For Infoprint Manager for AIX, use the ainupod3 utility to generate a report of accounting information for all jobs printed or transmitted on all defined PSF, fax, and email actual destinations by a given user. This information is derived from the /var/psf/podaccount.log file. By default, basic Infoprint installations set the value of the the accounting-exit actual destination attribute to job-ticket, which invokes a user exit program that writes accounting information to this file.

For Infoprint Manager for Windows NT and Windows 2000, use the ainupod3 utility to generate a report of accounting information for all jobs printed or transmitted on all defined PSF actual destinations by a given user. This information is derived from the \install_path\var\psf\podaccount.log file. By default, basic Infoprint installations set the value of the accounting-exit actual destination attribute to job-ticket, which invokes a user exit program that writes accounting information to this file.

Note: On Windows NT or Windows 2000, this command must be run from the *install_path***bin** directory.

Example

To generate accounting information for user donald, enter: ainupod3

When ainupod3 prompts you for a user ID, enter:

ainupod3 returns information similar to the following:

Print Activity Report for donald

Start Date	Start Time	Destination ID	9	Copies Requested	Job Identification
07/26/1997	15:36:32	e1	45	1	E1B0440B.B0B
07/31/1997	08:24:24	3900-p4	15	1	i1a11908.54d
08/01/1997	08:28:48	e1	131	1	e1a1050c.431

Suggested Reading

- Auxiliary sheets, see "Attributes for Auxiliary-Sheet Objects" on page 458
- Other utilities that generate accounting reports from the podaccount.log file, see "ainupod1 Utility: Generates Accounting Information by User" on page 131 and "ainupod2 Utility: Generates Accounting Information by Job" on page 132
- Utilities that generate accounting reports from the accounting.log file, see "ainurpt1 Utility: Generates Accounting Information by Actual Destination" on page 135, "ainurpt2 Utility: Generates Accounting Information by User" on page 136, and "ainurpt3 Utility: Generates Accounting Information for a User" on page 137

ainupod3

• Utilities that generate audit reports, see "ainurpt4 Utility: Generates Audit Information by Destination" on page 139, "ainurpt5 Utility: Generates Audit Information by User" on page 140, and "ainurpt6 Utility: Generates Audit Information for a User" on page 141

ainurpt1 Utility: Generates Accounting Information by Actual Destination

Syntax

ainurpt1

Description

For Infoprint Manager for AIX, use the **ainurpt1** utility to generate a report of accounting information for all jobs printed or transmitted on all defined PSF, fax, and email actual destinations, sorted by actual destination. This information is derived from the <code>/var/psf/accounting.log</code> file. By default, advanced Infoprint installations set the value of the the **accounting-exit** actual destination attribute to **accounting-log**, which invokes a user exit program that writes accounting information to this file.

For Infoprint Manager for Windows NT and Windows 2000, use the ainurpt1 utility to generate a report of accounting information for all jobs printed or transmitted on all defined PSF actual destinations, sorted by actual destination. This information is derived from the <code>install_path\var\psf\accounting.log</code> file. By default, advanced Infoprint installations set the value of the the accounting-exit actual destination attribute to accounting-log, which invokes a user exit program that writes accounting information to this file.

Note: On Windows NT or Windows 2000, this command must be run from the *install_path*\bin directory.

Example

To generate accounting information for all PSF, fax, and email actual destinations, enter:

ainurpt1

ainurpt1 returns information similar to the following:

Destination	Jobs	Pages	Bin1	Bin2	Fonts	Resident	Overlays	Hard	Soft	D0Rs
ksrv-p1	120	1200	88	32	10	0	0	0	0	15
ksrv-p2	72	981	72	0	4	0	0	0	0	0

Suggested Reading

- Auxiliary sheets, see "Attributes for Auxiliary-Sheet Objects" on page 458
- Other utilities that generate accounting reports from the **accounting.log** file, see "ainurpt2 Utility: Generates Accounting Information by User" on page 136 and "ainurpt3 Utility: Generates Accounting Information for a User" on page 137
- Utilities that generate accounting reports from the **podaccount.log** file, see "ainupod1 Utility: Generates Accounting Information by User" on page 131, "ainupod2 Utility: Generates Accounting Information by Job" on page 132, and "ainupod3 Utility: Generates Accounting Information for a User" on page 133
- Utilities that generate audit reports, see "ainurpt4 Utility: Generates Audit Information by Destination" on page 139, "ainurpt5 Utility: Generates Audit Information by User" on page 140, and "ainurpt6 Utility: Generates Audit Information for a User" on page 141

ainurpt2 Utility: Generates Accounting Information by User

Syntax

ainurpt2

Description

For Infoprint Manager for AIX, use the ainurpt2 utility to generate a report of accounting information for all jobs printed or transmitted on all defined PSF, fax, and email actual destinations, sorted by user. This information is derived from the <code>/var/psf/accounting.log</code> file. By default, advanced Infoprint installations set the value of the the accounting-exit actual destination attribute to accounting-log, which invokes a user exit program that writes accounting information to this file.

For Infoprint Manager for Windows NT and Windows 2000, use the **ainurpt2** utility to generate a report of accounting information for all jobs printed or transmitted on all defined PSF actual destinations, sorted by user. This information is derived from the <code>install_path\var\psf\accounting.log</code> file. By default, advanced Infoprint installations set the value of the the **accounting-exit** actual destination attribute to **accounting-log**, which invokes a user exit program that writes accounting information to this file.

Note: On Windows NT or Windows 2000, this command must be run from the *install_path*\bin directory.

Example

To generate accounting information for all users, enter: ainurpt2

ainurpt2 returns information similar to the following:

Userids	Jobs	Pages	Binl	Bin2	Fonts	Resident	Overlays	Hard	Soft	DORs
billing	120	1200	88	32	10	0	0	0	0	11
repgen	72	981	72	0	4	0	0	0	0	4

Suggested Reading

- Auxiliary sheets, see "Attributes for Auxiliary-Sheet Objects" on page 458
- Other utilities that generate accounting reports from the **accounting.log** file, see "ainurpt1 Utility: Generates Accounting Information by Actual Destination" on page 135 and "ainurpt3 Utility: Generates Accounting Information for a User" on page 137
- Utilities that generate accounting reports from the **podaccount.log** file, see "ainupod1 Utility: Generates Accounting Information by User" on page 131, "ainupod2 Utility: Generates Accounting Information by Job" on page 132, and "ainupod3 Utility: Generates Accounting Information for a User" on page 133
- Utilities that generate audit reports, see "ainurpt4 Utility: Generates Audit Information by Destination" on page 139, "ainurpt5 Utility: Generates Audit Information by User" on page 140, and "ainurpt6 Utility: Generates Audit Information for a User" on page 141

ainurpt3 Utility: Generates Accounting Information for a User

Syntax

ainurpt3

Description

For Infoprint Manager for AIX, use the ainurpt3 utility to generate a report of accounting information for all jobs printed or transmitted on all defined PSF, fax, and email actual destinations by a given user. This information is derived from the /var/psf/accounting.log file. By default, advanced Infoprint installations set the value of the the accounting-exit actual destination attribute to accounting-log, which invokes a user exit program that writes accounting information to this file.

For Infoprint Manager for Windows NT and Windows 2000, use the ainurpt3 utility to generate a report of accounting information for all jobs printed or transmitted on all defined PSF actual destinations by a given user. This information is derived from the *install_path*\var\psf\accounting.log file. By default, advanced Infoprint installations set the value of the the accounting-exit actual destination attribute to accounting-log, which invokes a user exit program that writes accounting information to this file.

Note: On Windows NT or Windows 2000, this command must be run from the *install_path***bin** directory.

Example

To generate accounting information for user kathy, enter: ainurpt3

When ainurpt3 prompts you for a user ID, enter:

ainurpt3 returns information similar to the following:

Report for kathy

Start Date	Start Time	Destination ID	Pages Printed	Job Name
06/02/1997	12:53:47	ksrv-p1	1190	/net/home/kathy/May.billing
06/03/1997	15:42:31	hsrv-p1	944	/net/home/kathy/May.reports

Suggested Reading

- Auxiliary sheets, see "Attributes for Auxiliary-Sheet Objects" on page 458
- Other utilities that generate accounting reports from the accounting.log file, see "ainurpt1 Utility: Generates Accounting Information by Actual Destination" on page 135 and "ainurpt2 Utility: Generates Accounting Information by User" on page 136
- Utilities that generate accounting reports from the podaccount.log file, see "ainupod1 Utility: Generates Accounting Information by User" on page 131, "ainupod2 Utility: Generates Accounting Information by Job" on page 132, and "ainupod3 Utility: Generates Accounting Information for a User" on page 133

ainurpt3

• Utilities that generate audit reports, see "ainurpt4 Utility: Generates Audit Information by Destination" on page 139, "ainurpt5 Utility: Generates Audit Information by User" on page 140, and "ainurpt6 Utility: Generates Audit Information for a User" on page 141

ainurpt4 Utility: Generates Audit Information by Destination

Syntax

ainurpt4

Description

For Infoprint Manager for AIX, use the ainurpt4 utility to generate a report of audit information for all jobs printed or transmitted on all defined PSF, fax, and email actual destinations, sorted by actual destination. This information is derived from the /var/psf/audit.log file. To write information to this file, specify accounting-log as the value of the audit-exit actual destination attribute.

For Infoprint Manager for Windows NT and Windows 2000, use the ainurpt4 utility to generate a report of audit information for all jobs printed or transmitted on all defined PSF actual destinations, sorted by actual destination. This information is derived from the *install_path*\var\psf\audit.log file. To write information to this file, specify accounting-log as the value of the audit-exit actual destination attribute

Note: On Windows NT or Windows 2000, this command must be run from the *install_path***bin** directory.

Example

To generate audit information for all PSF, fax, and email actual destinations, enter: ainurpt4

ainurpt4 returns information similar to the following:

Destination	Jobs	Pages	Bin1	Bin2	Fonts	Resident	Overlays	Hard	Soft	D0Rs
ksrv-p1	120	1200	88	32	10	0	0	0	0	15
ksrv-p2	72	981	72	0	4	0	0	0	0	0

Suggested Reading

- Auxiliary sheets, see "Attributes for Auxiliary-Sheet Objects" on page 458
- · Other utilities that generate audit reports, see "ainurpt5 Utility: Generates Audit Information by User" on page 140 and "ainurpt6 Utility: Generates Audit Information for a User" on page 141
- Utilities that generate accounting reports from the accounting.log file, see "ainurpt1 Utility: Generates Accounting Information by Actual Destination" on page 135, "ainurpt2 Utility: Generates Accounting Information by User" on page 136, and "ainurpt3 Utility: Generates Accounting Information for a User" on page 137
- Utilities that generate accounting reports from the podaccount.log file, see "ainupod1 Utility: Generates Accounting Information by User" on page 131, "ainupod2 Utility: Generates Accounting Information by Job" on page 132, and "ainupod3 Utility: Generates Accounting Information for a User" on page 133

ainurpt5 Utility: Generates Audit Information by User

Syntax

ainurpt5

Description

For Infoprint Manager for AIX, use the **ainurpt5** utility to generate a report of audit information for all jobs printed or transmitted on all defined PSF, fax, and email actual destinations, sorted by user. This information is derived from the <code>/var/psf/audit.log</code> file. To write information to this file, specify **accounting-log** as the value of the **audit-exit** actual destination attribute.

For Infoprint Manager for Windows NT and Windows 2000, use the **ainurpt5** utility to generate a report of audit information for all jobs printed or transmitted on all defined PSF actual destinations, sorted by user. This information is derived from the <code>install_path\var\psf\audit.log</code> file. To write information to this file, specify **accounting-log** as the value of the **audit-exit** actual destination attribute.

Note: On Windows NT or Windows 2000, this command must be run from the *install_path*\bin directory.

Example

To generate audit information for all users, enter: ainurpt5

ainurpt5 returns information similar to the following:

Userids	Jobs	Pages	Bin1	Bin2	Fonts	Resident	Overlays	Hard	Soft	D0Rs
billing	120	1200	88	32	10	0	0	0	0	11
repgen	72	981	72	0	4	0	0	0	0	4

Suggested Reading

- Auxiliary sheets, see "Attributes for Auxiliary-Sheet Objects" on page 458
- Other utilities that generate audit reports, see "ainurpt4 Utility: Generates Audit Information by Destination" on page 139 and "ainurpt6 Utility: Generates Audit Information for a User" on page 141
- Utilities that generate accounting reports from the **accounting.log** file, see "ainurpt1 Utility: Generates Accounting Information by Actual Destination" on page 135, "ainurpt2 Utility: Generates Accounting Information by User" on page 136, and "ainurpt3 Utility: Generates Accounting Information for a User" on page 137
- Utilities that generate accounting reports from the **podaccount.log** file, see "ainupod1 Utility: Generates Accounting Information by User" on page 131, "ainupod2 Utility: Generates Accounting Information by Job" on page 132, and "ainupod3 Utility: Generates Accounting Information for a User" on page 133

ainurpt6 Utility: Generates Audit Information for a User

Syntax

ainurpt6

Description

For Infoprint Manager for AIX, use the ainurpt6 utility to generate a report of audit information for all jobs printed or transmitted on all defined PSF, fax, and email actual destinations by a given user. This information is derived from the /var/psf/audit.log file. To write information to this file, specify accounting-log as the value of the audit-exit actual destination attribute.

For Infoprint Manager for Windows NT and Windows 2000, use the ainurpt6 utility to generate a report of audit information for all jobs printed or transmitted on all defined PSF actual destinations by a given user. This information is derived from the *install_path*\var\psf\audit.log file. To write information to this file, specify accounting-log as the value of the audit-exit actual destination attribute.

Note: For Windows NT or Windows 2000, this command must be run from the *install path***bin** directory.

Example

To generate audit information for user kathy, enter: ainurpt6

When ainurpt6 prompts you for a user ID, enter: kathy

ainurpt6 returns information similar to the following:

Report for kathy

Start Date	Start Time	Destination ID	Pages Printed	Job Name
06/02/1997 06/03/1997			1190 944	<pre>/net/home/kathy/May.billing /net/home/kathy/May.reports</pre>

Suggested Reading

- Auxiliary sheets, see "Attributes for Auxiliary-Sheet Objects" on page 458
- Other utilities that generate audit reports, see "ainurpt4 Utility: Generates Audit Information by Destination" on page 139 and "ainurpt5 Utility: Generates Audit Information by User" on page 140
- Utilities that generate accounting reports from the accounting.log file, see "ainurpt1 Utility: Generates Accounting Information by Actual Destination" on page 135, "ainurpt2 Utility: Generates Accounting Information by User" on page 136, and "ainurpt3 Utility: Generates Accounting Information for a User" on page 137
- Utilities that generate accounting reports from the podaccount.log file, see "ainupod1 Utility: Generates Accounting Information by User" on page 131, "ainupod2 Utility: Generates Accounting Information by Job" on page 132, and "ainupod3 Utility: Generates Accounting Information for a User" on page 133

cfu Utility: Displays and Builds Coded Fonts in Infoprint Manager for AIX

Syntax

cfu [-**d** | -**b**] CodedFontName [BuildFileName]

Description

cfu, the Coded Font Utility, displays and builds coded fonts for use with IBM Infoprint Control. The main purpose of the **cfu** utility is to allow users of double-byte raster fonts to indicate which font sections in the coded font should be downloaded to the printer and which font sections can be found resident in the printer. This is useful when:

- You have added user-defined characters to a font section
- The printer-resident version of a font differs from the system-resident version of a font, and you want to ensure that IBM Infoprint Control downloads the system version.

You can also add and delete sections from the coded font and change which character sets and code pages are referenced in the coded font.

You can also use the **cfu** utility to build single-byte coded fonts by specifying a font character set name and a code page name.

You can use the **cfu** utility in two ways:

- In the display mode of the cfu utility, you provide a coded font name as input. The **cfu** utility generates a build file that can be used as input to the build mode of the **cfu** utility.
- In the build mode of the **cfu** utility, you provide a build file name as input. The **cfu** utility generates a coded font.

Flags

The **cfu** utility uses the following flags:

- Display mode displays the contents of a coded font. Output is written to -d standard output. This is the default mode if no flag is entered.
- -b Build mode builds a new coded font using the build file name, or standard input if the build file name is omitted.

Build File Format

Each non-commented line in the build file defines one repeating group within the Coded Font Index structured field. Repeating group definitions may not span more than one line and fields within each line must be delimited with blanks. A pound sign (#) at the beginning of a line indicates a comment.

A repeating group definition has the following format:

- Field 1 is the section identifier of the repeating group. The format is X'hh', where *hh* is the hexadecimal section identifier. Both the **X** character and the single quotation marks are required.
- Field 2 is the character set name. Only the first 8 characters are used.
- Field 3 is the code page name. Only the first 8 characters are used.
- Field 4 is the section resident indicator:

- 1 Use the printer-resident section if possible.
- Download the section.

Note: This field is only meaningful for double-byte raster fonts.

This is an example of a repeating group:

```
# SectId CharSet CodePage Resident
# ----- -----
 X'41' C0Z24F41 T1Z24F41 0
```

Arguments

The valid argument values for the **cfu** utility are:

CodedFontName

The name of the coded font for display mode or the new coded font name in build mode. cfu will not overwrite existing coded fonts in build mode.

Note: In build mode, the *coded font name* is also the internal coded font name in the Begin Coded Font structured field.

BuildFileName

The input file used to build a new coded font. If build file name is omitted, cfu reads from standard input.

Examples

 To display the contents of the coded font X0Z24F, enter either of the following commands:

```
cfu X0Z24F
cfu -d X0Z24F
```

To build a new coded font with the name X0Z24F using build file X0Z24F.bld,

```
cfu -b X0Z24F X0Z24F.bld
```

Suggested Reading

Refer to Data Stream and Object Architectures: Font Object Content Architecture Reference for more information on coded font structured fields.

cmt Utility: Builds Color Mapping Table Source and Object Files in Infoprint Manager for AIX

Syntax

cmt -i input file [-o output file] [-n internal CMT name] [-t]

Description

cmt, the Color Mapping Table Utility, generates color mapping table source and object files. If the input file is an object color mapping table, cmt generates a source output file; and if the input file is a source file, cmt generates an object file. Object color mapping tables are used to map OCA (Object Content Architecture) colors and fills to printer specific colors.

Flags

The **cmt** utility uses the following flags:

- -i The file name of the input file. The input file can be a source or object file. When you use the **cmt** utility, you must specify this flag.
- **-o** The file name of the output file. If this flag is not specified, **stdout** is used. This is a optional flag.
- -n The name that appears on the MO:DCA Begin Object Container (BOC) structured field. This is a optional flag.
- -t Use this flag to turn on trace. This is a optional flag.

Color Mapping Table Source File

The source file describes the contents of the color mapping table object file.

Each mapping definition of one source color or fill to a target color is bracketed by the keywords **BeginMappingDef:** and **EndMappingDef:**. The **cmt** utility requires one mapping definition for each source target mapping.

Each source definition within a mapping definition is bracketed by the keywords **BeginSourceDef:** and **EndSourceDef:**. The **cmt** utility requires one source definition for each mapping definition.

Valid keywords and values for a source definition follow:

ColorSpace

You must specify **OCA**, **Highlight**, or **GOCA**.

ColorValue

You must specify a value that depends upon the value specified for **ColorSpace**:

 When ColorSpace=OCA, ColorValue is a one string component of the following:

Default

Blue

Red

Pink

Green

Cyan

Yellow

Black Brown Medium

Note: The binary representation for all **OCA** colors are supported by the **cmt** utility.

• When ColorSpace=Highlight, the ColorValue has one component, integer 0 through 3, for example:

ColorValue: 2

• When ColorSpace=GOCA, the ColorValue has one component, integer 0 through 16 or 64, for example:

ColorValue: 13

Each target definition within a mapping definition is bracketed by the keywords BeginTargetDef and EndTargetDef The cmt utility requires one target definition within each mapping definition. Valid keywords and values for a target definition follow:

ColorSpace

You must specify RGB, CMYK, Highlight, or CIELAB.

ColorValue

You must specify a value determined by the value specified by ColorSpace as follows:

- When ColorSpace=RGB, the ColorValue has three components from 0 through 255. For example, 33 167 247.
- When ColorSpace=CMYK, the ColorValue has four components from 0 through 255. For example, 135 26 37 255.
- When ColorSpace=CIELAB, the ColorValue has three components with the first integer from 0 through 100, and the second and third integers from -127 through 127. For example 65 -120 111.

PercentShading

Valid values are integers 0 through 100. This optional value defaults to 100.

PercentCoverage

Value values are integers 0 through 100. This optional value defaults to

ipguiadv, ipguibasic, and ipguidist Utilities: Start the Infoprint Manager Operations GUI

Syntax

For Infoprint Manager for AIX:

ipguiadv

ipguibasic

ipguidist

For Infoprint Manager for Windows NT and Windows 2000:

ipguiadv.bat

Description

Issue the **ipguiadv**, **ipguibasic**, or **ipguidist** utility to start the Infoprint Manager Operations GUI on Infoprint Manager for AIX.

Issue the **ipguiadv** utility to start the Infoprint Manager Operations GUI on Infoprint Manager for Windows NT and Windows 2000.

Each view is designed to be most useful in a specific environment, but you can open any view in any environment.

For Infoprint Manager for AIX:

ipguiadv

Starts the view for an advanced Infoprint Manager Operations GUI.

ipguibasic

Starts the view for a basic Infoprint Manager Operations GUI.

ipguidist

Starts the view for a distributed Infoprint Manager Operations GUI.

For Infoprint Manager for Windows NT and Windows 2000:

ipguiadv

Starts the view for an advanced Infoprint Manager Operations GUI.

Note: On Windows NT or Windows 2000, **ipquiadv** is installed into *install_path***ipqui**, which is not the PATH.

Example

With Infoprint Manager for AIX, to start the Infoprint Manager Operations GUI, displaying the view for a basic Infoprint installation, enter: ipguibasic

With Infoprint Manager for Windows NT and Windows 2000, to start the Infoprint Manager Operations GUI, displaying the view for an advanced Infoprint installation, enter:

ipguiadv.bat

ipguiadvadm, ipguibasicadm, and ipguidistadm Utilities: Start the **Infoprint Manager Administration GUI**

Syntax

For Infoprint Manager for AIX:

ipguiadvadm

ipguibasicadm

ipguidistadm

For Infoprint Manager for Windows NT and Windows 2000:

ipguiadvadm.bat

ipguibasicadm.bat

ipguidistadm.bat

Description

Issue the ipguiadvadm, ipguibasicadm, or ipguidistadm utility to start the Infoprint Manager Administration GUI on Infoprint Manager for AIX.

Issue the ipguiadvadm utility to start the Infoprint Manager Administration GUI on Infoprint Manager for Windows NT and Windows 2000.

For Infoprint Manager for AIX:

ipguiadvadm

Starts the view for an advanced Infoprint Manager Administration GUI.

ipguibasicadm

Starts the view for a basic Infoprint Manager Administration GUI.

ipguidistadm

Starts the view for a distributed Infoprint Manager Administration GUI.

For Infoprint Manager for Windows NT and Windows 2000:

ipguiadvadm

Starts the view for an advanced Infoprint Manager Administration GUI.

Note: On Windows NT or Windows 2000, **ipquiadvadm.bat** is installed into *install_path***ipquiadm**, which is not the PATH.

Each view is designed to be most useful in a specific environment, but you can open any view in any environment.

Example

With Infoprint Manager for AIX, to start the Infoprint Manager Administration GUI, displaying the view for a basic Infoprint installation, enter: ipguibasicadm

ipguiadvadm, ipguibasicadm, and ipguidistadm

With Infoprint Manager for Windows NT and Windows 2000, to start the Infoprint Manager Administration GUI, displaying the view for an advanced Infoprint installation, enter:

ipguiadvadm.bat

jsmigr Utility: Migrates PSF for AIX Job Scripts in Infoprint Manager for AIX

Syntax

jsmigr JobScript ...

Description

Issue the jsmigr utility to migrate PSF for AIX job scripts to Infoprint command scripts and attributes files. The **jsmigr** utility creates the following files:

JobScript.ksh

Infoprint command script containing

- The pdpr command
- One or more **-X** flags invoking attributes files
- If the job script includes the corresponding keywords, other flags and arguments of the pdpr command (for example, the -T flag for tape input or the names of files to be printed)

This file is created in the same directory as the migrated job script and has the same file name with .ksh appended.

JobScript.X

Attributes file used by JobScript.ksh, containing attributes migrated from the job script keywords. This file is created in the same directory as the migrated job script and has the same file name with .X appended.

FileName.X

Attributes files used by JobScript.ksh. These files are migrated from job scripts named as values for the a_Parmdd, i_Filenames, p_Config, and **e_Filemsg** keywords. Each file is created in the same directory as the original file and has the same file name with X appended.

Notes:

- 1. This utility normally executes as part of the Infoprint installation.
- 2. "Appendix B. Migrating PSF for AIX Job Script Keywords to Infoprint Equivalents" on page 715 shows the attributes to which job script keywords are migrated.
- 3. If multiple job scripts refer to the same file, **ismigr** migrates the file only once.
- 4. Job scripts named as values for the a_Parmdd, p_Config, and e_Filemsg keywords must be specified with absolute path names.
- 5. Infoprint searches for job scripts named as values for the i_Filenames keyword in these directories:
 - a. Current directory
 - b. \$HOME/js
 - c. /var/psf/js
- 6. If a data type is specified with the JsFileType keyword, keywords that are not valid for that data type are commented out in the attributes file resulting from conversion. For example, if JsFileType has any value other than line, all a_ keywords are commented out. If you edit the attributes file and change the value of the **document-format** attribute to **line-data**, you must remove the comment characters before using the attributes file to submit line-data jobs.

jsmigr

- 7. If the input device is not **rmt***x*, tape-related job script keywords are commented out in the attributes file resulting from conversion. You must edit the attributes file and remove the comment characters before using it to submit jobs read from tape.
- 8. Job scripts containing both a_ and p_ keywords may convert to an attributes file that causes transforms to fail, especially if any of the keywords convert to the **other-transform-options** attribute. This happens because PSF for AIX ignores job script keywords that do not apply to the job, but Infoprint processes all attributes.
- 9. If **jsmigr** encounters a job script keyword that it cannot map to an Infoprint attribute, it issues an error message, erases the attributes file it is writing, ends migrating the job script, and continues with the next job script.
- 10. If jsmigr encounters a job script keyword that it can map to an Infoprint attribute, with a value that has no Infoprint equivalent, it converts the keyword and continues writing the attributes file. When you use the attributes file to submit a job, Infoprint issues an error message and does not print or transmit the job.

Arguments

The argument value identifies the job script to be migrated.

Valid argument values for the **jsmigr** utility are:

JobScript

Specifies the job script to be migrated. The job script file must have a .js extension, which you do not have to specify.

You can specify multiple job script names. You can use an asterisk (*) to specify all job scripts in a directory.

Examples

- To migrate the job scripts bigjob.js and smalljob.js, enter: jsmigr bigjob smalljob
- To migrate all the job scripts in the directory /var/psf/js, enter: jsmigr /var/psf/js/*

notification client

Used to start a notification window to retreive notifications delivered by *message* from the notification server.

opergui Utility: Opens the Print Management Window of the Basic Infoprint Administrator's GUI in Infoprint Manager for AIX

Syntax

opergui [-n | ServerName]

Description

Use the opergui utility to open the Print Management window of the basic Infoprint administrator's GUI. The Print Management window displays the actual destinations, unassigned jobs, and retained jobs that reside in all servers in the namespace.

Flags

The **opergui** utility uses the following flag:

- Prevents Infoprint from starting any servers. If you do not specify this flag, Infoprint checks to see if any servers are running. If no servers are running, Infoprint invokes the start_server utility to start the specified server if it exists or create it if it does not.
 - If you specify the **-n** flag, you cannot specify a server name.
- -? Displays help for the **opergui** utility.

Arguments

The argument value identifies the server to which the utility applies.

Valid argument values for the **opergui** utility are:

ServerName

Specifies the name of the server you want to start if no other servers are currently running. ServerName defaults to the hostname. If any servers are running, Infoprint ignores this argument.

If you specify a server name, you cannot specify the **-n** flag.

Examples

- To open the Print Management window of the basic Infoprint administrator's GUI, starting the default server if no other servers are running, enter:
- To open the Print Management window of the basic Infoprint administrator's GUI, starting the server charlie if no other servers are running, enter: opergui charlie
- To open the Print Management window of the basic Infoprint administrator's GUI, without starting any servers, enter:

```
opergui -n
```

pdadmin Utility: Opens the Servers Window of the Advanced Infoprint **Administrator's GUI in Infoprint Manager for AIX**

Syntax

pdadmin

Description

Use the **pdadmin** utility to open the Servers window of the advanced Infoprint administrator's GUI. The Servers window displays the queues and actual destinations default jobs, default documents, and media that reside in the servers you select in a dialog.

Examples

- To monitor all the servers in the namespace:
 - 1. Enter: pdadmin
 - 2. In the Select Servers dialog, click **OK**.
- To monitor the servers julia and henry:
 - 1. Enter: pdadmin
 - 2. In the Select Servers dialog, select julia.
 - 3. Hold down the CTRL key and select henry.
 - 4. Click OK.

pdcrcds Utility: Creates Directories for DCE in Infoprint Manager for AIX

Syntax

pdcrcds

Description

Issue the pdcrcds utility to create the directories and soft links needed for Infoprint within the DCE namespace. You should only run the pdcrcds utility once in each DCE cell in which Infoprint servers will run regardless of the number of servers. This utility also establishes the initial ACL structure used by the Infoprint security service.

Note: This utility normally executes as part of the Infoprint installation.

Example

To create directories needed for Infoprint in the DCE namespace, enter: pdcrcds

Infoprint displays the following:

Creating Infoprint directories in the DCE namespace...

pdcrdflt Utility: Creates Default Auxiliary Sheets, Media, and Queue in **Infoprint Manager for AIX**

Syntax

```
pdcrdflt [-c] ServerName
```

Description

Issue the **pdcrdflt** utility to perform the following server configuration tasks:

- Create the default auxiliary sheets and media in a server.
- For a basic installation only, create the default queue.
- For a basic installation only, set server and queue attributes.

The default auxiliary sheets that this utility creates are:

```
accounting-log
blank
brief
full
job-ticket
none
64xx
```

The default media that this utility creates are:

A3 A4 **B4 B5** ledger

legal letter

tabloid

You only need to run the pdcrdflt utility if the startsrv utility failed to create all the default objects.

If you specify the -c flag, pcrdflt

• Sets the following server attributes to **true**:

```
accept-unsupported-jobs
save-rip-files
```

- Creates the default queue
- Sets the following queue attributes to **true**:

```
assign-to-printer
requeue-failed-jobs
```

If you have a server that has been configured for an advanced Infoprint installation and want to reconfigure it for a basic installation, do not use pdcrdflt. You must create the default queue and reset the attributes manually.

Flags

The **pdcrdflt** utility uses the following flags:

Configures the server for a basic installation. If you do not specify this flag, -c Infoprint configures the server for an advanced installation.

pdcrdflt

Arguments

The argument value identifies the server to which the utility applies.

Valid argument values for the **pdcrdflt** utility are:

ServerName

Specifies the name of the server to configure. You must specify the name.

Examples

• To create the default objects for a server with the name srv1 in an advanced installation, enter:

pdcrdflt srv1

• To configure the server charlie for a basic installation and create the default objects, enter:

pdcrdflt -c charlie

pdcrmed Utility: Creates Commonly Used Media in Infoprint Manager for AIX

Syntax

pdcrmed ServerName

Description

Issue the **pdcrmed** utility to create the large number of predefined medium objects. Use this utility after starting the server.

The utility creates these predefined medium objects:

A0	B7	jis-b6-white
A1	B8	jis-b7-white
A2	B9	jis-b8-white
A3-colored	B10	jis-b9-white
A4-colored	C4-envelope	jis-b10-white
A4-transparent	C5-envelope	letter-tab
A4-tab	a	manual
A5	b	monarch-envelope
A5-colored	c	na-legal-colored
A6	d	na-letter-colored
A7	designated-long-envelope	na-letter-transparent
A8	e	na-number-9-envelope
A9	executive	na-number-10-envelope
A10	folio	na-6x9-envelope
B0	invoice	na-7x9-envelope
B1	jis-b0-white	na-9x11-envelope
B2	jis-b1-white	na-9x12-envelope
B3	jis-b2-white	na-10x13-envelope
B4-colored	jis-b3-white	na-10x14-envelope
B4-envelope	jis-b4-colored	na-10x15-envelope
B5-colored	jis-b4-white	quarto
B5-envelope	jis-b5-colored	8x10.5
B6	jis-b5-white	8.5x12.4
		9x11
		12x18

Arguments

The argument value identifies the server to which the utility applies.

Valid argument values for the **pdcrmed** utility are:

ServerName

Specifies the name of the server on which to create the medium objects. You must specify the name.

Example

To create the commonly used medium objects on a server with the name srv1, enter:

pdcrmed srv1

pdinitports Utility: Initializes Ports

Syntax

pdinitports [-n NumberOfPorts | MinimumPortNumber MaximumPortNumber]
pdinitports {-h | -?}

Description

For Infoprint Manager for AIX, use the **pdinitports** utility to set up Infoprint to use a specific range or number of port numbers on this system for interprocess communication. By initializing a specific range of port numbers, you can avoid using port numbers that are used by or reserved for other programs.

Notes:

- 1. See the /etc/services file for reserved port numbers. Because Infoprint does not use the port numbers in /etc/services, you do not have to run this utility if all reserved port numbers are listed there.
- 2. Because Infoprint automatically initializes port numbers when it is started, you should not normally have to run this utility.
- 3. Before using this utility, you must shut down all the servers on this system.

For Infoprint Manager for Windows NT and Windows 2000, use the **pdinitports** utility to set up Infoprint to use a specific range or number of port numbers on this system for interprocess communication. By initializing a specific range of port numbers, you can avoid using port numbers that are used by or reserved for other programs.

Notes:

- 1. See the /etc/services file for reserved port numbers. Because Infoprint does not use the port numbers in /etc/services, you do not have to run this utility if all reserved port numbers are listed there.
- 2. Because Infoprint automatically initializes port numbers when it is started, you should not normally have to run this utility.
- 3. Before using this utility, you must shut down all the servers on this system.

Flags

The **pdinitports** utility uses the following flags:

-n NumberOfPorts

Specifies that Infoprint is to find the first available block of *num-ports* port numbers and use them. If you do not specify either this flag or a range of port numbers, **pdinitports** finds and uses the first available block of 10 port numbers.

- **-h** Displays help for the **pdinitports** utility.
- -? Displays help for the **pdinitports** utility.

Arguments

Valid argument values for the **pdinitports** utility are:

MinimumPortNumber

The minimum port number that the Infoprint will use on this system.

MaximumPortNumber

The maximum port number that the Infoprint will use on this system.

If you do not specify either a range of port numbers or the -n flag, pdinitports finds and uses the first available block of 10 port numbers.

Examples

- To initialize Infoprint to use the first available range of 12 ports, enter: pdinitports -n 12
- To initialize Infoprint to use ports 6001 through 6010, enter: pdinitports 6001 6010

pdmigpp Utility: Migrates Existing AIX Printers to Infoprint in Infoprint Manager for AIX

Syntax

pdmigpp AIXPrintQueue ServerName DestinationName QueueName

Description

Issue the **pdmigpp** utility to migrate an existing AIX print queue to an actual destination within Infoprint.

You can migrate printer devices currently configured for the AIX print system, for PSF for AIX, and for AIX remote queues that send jobs to another AIX processor or to any remote host connected to the network with TCP/IP.

This utility automatically selects the appropriate DSS, which the **device-support-system** actual destination attribute reflects. If the AIX print queue is a remote queue, Infoprint selects the BSD DSS. For PSF physical printers, the utility selects the appropriate attachment type, reflected by the **attachment-type** actual destination attribute. The corresponding Infoprint actual destination attributes, if they exist, reflect any values for the existing printer device.

After this utility has run successfully, an Infoprint actual destination that is equivalent to the AIX print queue exists in the specified server.

To run this utility ensure that:

- If you use DCE, you are logged into DCE with administrator authority
- You are logged onto the AIX processor on which the AIX print queue resides
- The Infoprint server whose name you specify is up and running

Arguments

The argument value identifies the existing AIX virtual printer that the utility migrates to Infoprint as an actual destination within the specified server and its associated queue.

Valid argument values for the **pdmigpp** utility are:

AIXPrintQueue

The name of an existing AIX print queue that the utility migrates to Infoprint.

ServerName

Specifies the name of the server that will contain the actual destination the utility creates.

DestinationName

The name of the Infoprint actual destination that the utility creates.

QueueName

The name of the Infoprint queue that will provide jobs to the created actual destination.

pdmigpp

Example

To migrate the PSF for AIX print queue 1pd8 to actual destination PhyPtr3 on server Server2 with an associated queue of queue1, enter: pdmigpp 1pd8 Server2 PhyPtr3 queue1

pdmincfg Utility: Sets up a Minimum Infoprint Configuration in **Infoprint Manager for AIX**

Syntax

pdmincfg [-s] [ServerName]

Description

Issue the **pdmincfg** utility to create a minimum Infoprint configuration.

This minimum configuration consists of one server, one logical destination, one queue, and one actual destination. You can use this minimum configuration to verify that Infoprint is properly installed and is operational. The pdmincfg utility creates a minimal configuration appropriate for a small Infoprint installation.

Flags

The **pdmincfg** utility uses the following flag:

Causes **pdmincfg** to start the specified server. If you do not specify this flag, but do specify the ServerName, Infoprint does not start the server. If you do not request Infoprint to start the server, Infoprint assumes it is already up and running.

Arguments

The argument value identifies the specific object to which the utility applies.

Valid argument values for the **pdmincfg** utility are:

ServerName

Specifies the name of the server that runs in the minimum configuration. ServerName defaults to the hostname.

Example

To set up a minimum configuration on a system with the server name of serv1, follow these steps:

1. Enter:

```
pdmincfg -s serv1
```

Infoprint displays the following:

Your server print database will be stored in /var/pd/serv1. Press enter to continue or press CTRL-C to cancel the request.

Note: Your **PDBASE** environment variable setting determines the directories where Infoprint stores your server print database.

2. Press Enter and the following displays:

Note: If the server does not exist, Infoprint prompts you after message 5010-467. Type y and press Enter to create the server.

```
5010-467 Starting server serv1.
5010-406 Creating default objects. Please wait.
5010-405 Successfully started server serv1.
5010-470 Creating logical destination serv1-lp.
5010-471 Creating queue serv1-q.
5010-472 Enabling logical destination serv1-lp.
```

Enter 1 or 2 for the type of actual destination to be created:

- 1 = Test actual destination that does not actually print to a printer device
- 2 = Actual destination that uses your attributes file
- 3. You now have a choice of responses:
 - To create a test actual destination to verify that Infoprint is properly installed, enter 1.
 - To create an actual destination that represents a real printer device, follow these steps:
 - a. Enter 2.

Infoprint displays the following:

Enter the name of your destination attributes file:

b. Enter the name of a file containing attributes that describe the destination you want to create. For example:

```
/usr/fred/attfiles/pp tcpip.X
```

This example shows the full pathname of the file. If /usr/fred/attfiles is defined in your PDPATH environment variable, you can specify just the file name.

The file pp_tcpip.X contains information like this:

```
# TCP/IP-attached actual destination
destination-realization
                                 =actual
attachment-type
                                 =tcpip
                               =Infoprint4000
destination-model
destination-tcpip-internet-address=martha.boulder.ibm.com
destination-tcpip-port-number
                                =5001
```

4. Infoprint displays the following:

```
5010-476 Creating actual destination serv1-pp.
5010-477 Enabling actual destination serv1-pp.
5010-462 Your minimum configuration is now active:
        Logical Destination: serv1-lp
        Queue: serv1-q
        Actual Destination: serv1-pp
```

5. To print a file named test on the actual destination you just created, enter: pdpr -p serv1-lp test

pdmsg Utility: Displays Information about a Message in Infoprint Manager for AIX

Syntax

pdmsg [-d] [-t] MessageNumber

Description

The pdmsg utility displays the text and description of an Infoprint message at the command line. The pdmsg utility extracts the text and description from the appropriate message catalogs. If you do not specify the -d or -t flag with the utility, Infoprint displays both the text and the message description.

Flags

The **pdmsg** utility uses the following flags:

- Displays only the description of a message, which consists of a 7-digit message number, an explanation of the message, the system action, and the
- -t Displays only the text of a message, which consists of a 7-digit message number along with the actual words of the message itself. Underlined blanks in the text identify variable fields in the message text (also called message inserts). When Infoprint actually issues messages, Infoprint replaces the blanks with the appropriate variable information.

MessageNumber

The number of the Infoprint message you want displayed. Valid message numbers range from 0420-001 through 0423-999 and 5010-001 through 5010-999; however, not every number in these ranges has an associated message.

Examples

To view the text and description for Infoprint message 5010-096, enter: pdmsg 5010-096
Infoprint displays the following: 5010-096 The value is not supported for attribute 5010-096 EXPLANATION: The server or destination does not support this value. SYSTEM ACTION: Infoprint could not process the request. RESPONSE: Enter the command again and specify a value that is supported by the server and destination, or specify a destination that supports (by association) the value. To view only the text for Infoprint message 5010-096, enter: pdmsg -t 5010-096
Infoprint displays the following: 5010-096 The value is not valid not supported for attribute To view only the description for Infoprint message 5010-096, enter: pdmsg -d 5010-096
Infoprint displays the following:

pdmsg

5010-096

EXPLANATION: The server or destination does not support this value.

SYSTEM ACTION: Infoprint could not process the request. RESPONSE: Enter the command again and specify a value that is supported by the server and destination, or specify a destination that supports (by association) the value.

rc.iprsap Utility: Start SAP Callback Daemons for Infoprint Manager for AIX

Syntax

rc.iprsap

Description

Use this utility to start the Infoprint Manager SAP callback daemons for each SAP system defined to use Infoprint Manager as an OMS (Output Management System). /etc/inittab invokes the rc.iprsap utility to automatically restart the Infoprint Manager SAP callback daemons listed in this file during reboot if you activate it through SMIT as follows:

Infoprint Printing System
Utilities
SAP Callback Daemon

Note: For specific information about a menu choice, press the **F1** key for help.

As the administrator, you can edit the <code>/etc/rc.iprsap</code> file using a text editor, such as vi. Edit this file to include a startcbd line for each SAP System setup to receive callback notifications. See "startcbd Utility: Starts the SAP Callback Daemon" on page 199 for more information.

rc.pd Utility: Restarts Servers in Infoprint Manager for AIX

Syntax

rc.pd

Description

/etc/inittab (or a program called from /etc/inittab) invokes the rc.pd utility to automatically restart the Infoprint servers listed in /etc/rc.pd.servers during a reboot. As the administrator, you can edit the rc.pd.servers file using a text editor, such as vi. Edit this file to include a startsrv line for each server you want to start automatically.

sense Utility: Senses Whether a Channel-Attached Printer is Attached to Infoprint Manager for AIX

Syntax

sense SlotControlUnitAddress

Description

The **sense** command senses whether a channel-attached printer device is attached to the RS/6000. If it is, the command returns a code of 81 in the sense bytes information, indicating that a connection exists.

Note: You must shut down the actual destination representing the printer device before issuing the **sense** command. If the actual destination is enabled, the results of the **sense** command will not be accurate.

Arguments

Slot Control Unit Address

The slot number (first one or two digits) and control unit address (last two digits, in hexadecimal) of the printer device you want to check. Enter any alphabetic hexadecimal characters in lowercase only.

Messages and Return Codes

The **sense** utility returns the following messages and return codes:

• If you receive this message and return code:

the printer device is ready and correctly attached. You can print jobs on it.

• If you receive this message and return code:

the printer device is correctly attached, but it is not ready to receive print jobs. Follow the instructions in the printer documentation to make the printer device ready at the printer's operator panel or console.

If you receive this message:

```
printer not connected at address 3AF
```

the printer device is not attached correctly; or the printer device is not powered on. Check the printer and ensure that it is powered on and ready to accept print jobs. Verify that you entered the correct slot number and control unit address with the **sense** command. If the printer is powered on and you entered the correct information with the command, contact your IBM Printing Systems Company service representative.

• If you receive this message:

```
printer not defined at address 3AF
```

any of these things may be wrong:

- The printer is either not configured or not configured correctly.

- You did not shut down the actual destination before entering the sense command.
- The device driver for the printer at this address is missing or has not been loaded onto the S/370 Channel Emulator/A adapter. To load the driver, use the SMIT Miscellaneous Configuration panel.

Example

To check the connection on a channel-attached printer attached to an S/370 Channel Emulator/A adapter in slot 3, with a hexadecimal control unit address of af, enter:

sense 3af

sense Utility: Senses Whether a Channel-Attached Printer is Attached to Infoprint Manager for Windows NT and Windows 2000

Syntax

sense [-f] [-s] *slot_number control_unit_address*

Description

The **sense** command queries a channel-attached printer attached to the PC through the IBM 4159 S/390 Parallel Channel Emulator Card. The sense byte information is displayed.

Note: You must shut down the actual destination representing the printer device before issuing the **sense** command. If the actual destination is enabled, the results of the **sense** command will not be accurate.

Arguments

- -f All forms of channel sense data should be retrieved. The printer must be made ready for this to complete successfully.
- -s Only basic channel sense data should be retrieved.

slot number

The PC slot that the channel card is installed in. The number is a value between 1 and 8. If you only have one channel card installed, the channel slot number is always 1.

control_unit_address

The channel control unit address as it is configured on the target channel-attached printer. The address is a hexadecimal value between 00 and FF.

Note: The **sense** command can only be issued using eight unique control unit addresses per channel card installed in the PC. Subsequent invocations of the **sense** command or activation of channel attached actual destinations with control unit addresses beyond the eighth unique address will result in an error. The system must be re-booted to allow a new set of eight control unit addresses. For example, if the one actual destination is active to a printer at channel address 34, then the **sense** command is issued seven times to control unit addresses 11 through 17. If the **sense** command is then issued to control unit address B1 or an actual destination is enabled to a printer at channel address B1, it will fail since the eight unique control unit addresses have been exhausted.

Messages and Return Codes

The **sense** utility returns the following messages and return codes:

• If you receive this message:

the printer device is ready and correctly attached. You can print jobs on it.

• If you receive this message and return code:

the printer device is correctly attached, but it is not ready to receive print jobs. Follow the instructions in the printer documentation to make the printer device ready at the printer's operator panel or console.

If you receive this message:

There is no channel card in the specified slot

there is no S/390 Parallel channel card installed in the slot specified.

• If you receive this message:

No device is responding at Control Unit address 91

the channel cabling and termination are correctly attached, but no device is resonding at the specified control unit address. Any of the following things may be wrong:

- The specified control unit address does not match the control unit address specified in the printer's configuration. Consult your printer documentation to identify the control unit address configured in your printer.
- The channel attachment has not been enabled on the printer or the wrong channel attachment has been enabled on the printer.
- If multiple channel cards are present in the Windows PC, the slot number does not match the channel card containing the printer at the specified control unit address.
- If you receive this message:

The specified control unit is being used by another program

the actual destination for this printer was not shutdown before entering the sense command.

If you receive this message:

A Channel Program Check occurred while issuing the senseid

or

An Interface Control Check occurred while issuing the senseid

it is likely that there is a channel cabling problem between the 4159 S/390 Parallel Channel Emulator Card and the printer.

Note: The term *senseid* in this message may be one of several nouns indicating that any of the following things may be wrong:

- The channel cable connectors have bent or broken pins.
- The channel cables aer not properly terminated.
- The channel cables are not properly seated in the printer tailgate.
- The channel cables are oriented backwards.
- The channel cable configuration exceeds specifications.

Example

To check the connection on a channel-attached printer attached to the 4159 S/390 Parallel Channel Emulator Card in slot 1, with a hexadecimal control unit address of af, enter:

c:\>sense 1 af

The message you receive is:

sense for NT/2000

The device type is: 3835-02 c:\>

To obtain full sense information for the same device, enter:

c:\>sense -f 1 af

The message you receive is:

The device type is: 3835-02

The sense extended response is:

c:\>

setup Utility: Starts the Infoprint Installer in Infoprint Manager for AIX

Syntax

```
setup -c [-e] [-R] [-s FileSystem]
setup -C [-e] [-L locale] -n ServerName -p PortNumber
        [-P DestinationName] [-R] [-s FileSystem]
setup -m [-a ResponseFile] [-e] [-q] [-R] [-s Filesystem]
setup -M [-a ResponseFile] [-e] [-q] [-R] [-s Filesystem] [-S]
```

Description

Issue the **setup** utility to start the Infoprint Installer. The Infoprint Installer installs either the entire Infoprint Control component of Infoprint Manager, including an Infoprint server and an Infoprint AIX client, or the Infoprint AIX client alone.

The AIX client allows users to enter Infoprint commands on the command line for transmission to the Infoprint server, which may be on another AIX system. The AIX client has no graphical user interface.

Notes:

1. You can install the Infoprint server or Infoprint AIX client in any of the following languages:

English

French

German

Italian

Japanese

Spanish

If the Infoprint AIX client and server do not use the same language, the Infoprint server must run in English.

2. If you use Infoprint Manager DCE, and if the Infoprint AIX client and server are not in the same DCE namespace, the client can issue only the pdpr, pdls, and **pdq** commands.

Flags

The **setup** utility uses the following flags:

- -a Specifies a response file for use with an unattended installation. By default, unattended installations do not display any Installer screens. Further, when the -a flag is used, the default mount point is /ip remote. All unattended installations must be performed using an Infoprint Manager Software Server, not the Infoprint Manager CD-ROMs.
- Invokes the Infoprint Installer graphical user interface (GUI) to install only -c the Infoprint AIX client.
 - Note: The -L, -n, -p, and -P flags are not valid with this flag. The Infoprint Installer GUI will prompt you to specify the locale, server name, port number, and optional default logical destination.
- -C Invokes the Infoprint Installer to install only the Infoprint AIX client using the command line, without invoking the Installer GUI.

Note: If you use this flag, you must specify the -n and -p flags.

-e Echos the Installer log updates to **stdout** as they occur.

-L locale

Specifies the locale of the AIX client. The default is **en_US** (U.S. English).

Note: This flag is not valid with the **-c** flag. It is optional with the **-C** flag.

- Performs unattended installations on one or more remote systems. Before you can you this flag, you must create an Infoprint Manager Software Server on the local machine. After the software server is in place, you must copy response files to its /ip_remote/auto subdirectory to specify the which installations to complete. The default mount point for unattended installation is /ip_remote. The -m flag performs the specified installations concurrently.
- -M Performs unattended installations like the -m flag, but the installations are performed serially. That is, an installation on the first system will complete before the installation on the second system begins.

-n ServerName

Specifies the name of the Infoprint server.

Note: This flag is not valid with the **-c** flag. It is required with the **-C** flag.

-p PortNumber

Specifies the port number that the remote Infoprint server is using for communications.

Note: This flag is not valid with the **-c** flag. It is required with the **-C** flag.

-P DestinationName

Specifies the default logical destination to which the Infoprint AIX client submits jobs.

Note: This flag is not valid with the -c flag. It is optional with the -C flag.

- -q Displays the Installer screens during an unattended install.
- -R Replaces any currently installed version of the Infoprint Installer on your AIX system with the Installer code from the Infoprint CD-ROMs.

-s FileSystem

Specifies the file system where the installable software images may be accessed. For example, you could specify the file system that you defined for installing Infoprint, or the drive where you mounted the Infoprint server CD-ROM. The default mount point for all installations that use the Installer GUI is/cdrom. The default mount point for all unattended installations is /ip remote.

Note: The **/cdrom** file system may be predefined.

- -S Saves the .wlog files from any prior installation. This flag is usually used with the -M flag to maintain a record of all installations performed on a machine as part of a serial sequence of unattended remote installations.
- **-h** Displays help for the **setup** utility.

Examples

- To install Infoprint in the file system /cdrom, follow these steps:
 - 1. Log onto AIX as **root**.
 - 2. If available, insert the latest Infoprint Manager server APAR Service CD-ROM into the drive. Otherwise, insert the gold Infoprint Manager Server 1 CD-ROM into the drive.
 - 3. If this is the first time you are running the Infoprint Installer on this system, create the /cdrom file system. Enter:

smit cdrfs

- 4. Select Add a CDROM File System.
- 5. Complete the Add a CDROM File System panel.
 - a. In the **DEVICE Name** field, enter the identifier of your CD-ROM drive. If you do not know the identifier, select List in the AIXwindows version of SMIT, or press PF4 in the ASCII version of SMIT, to see a list of CD-ROM drives. Select one.
 - b. In the MOUNT POINT field, enter /cdrom.
 - c. Select **OK** (AIXwindows version) or press **Enter** (ASCII version).
 - d. Press F10 to exit from SMIT.
- 6. To mount the CD-ROM, enter the following command on the AIX command line:

mount /cdrom

7. To read the /readme.txt file, enter:

dtpad /cdrom/readme.txt

8. Enter:

/cdrom/setup

- You want to install only a German-language Infoprint AIX client in the previously defined file system /cdrom, and to replace the previous version of the Infoprint Installer. The client will communicate with the English-language server martha, running on port number 6874. Because your AIX console does not support graphics, you cannot invoke the Infoprint Installer GUI. Follow these steps:
 - 1. Log onto AIX as **root**.
 - 2. Insert the gold Infoprint Manager Server 1 CD-ROM into the drive.
 - 3. To mount the CD-ROM, enter:

mount /cdrom

4. Enter:

/cdrom/setup -C -L de DE -n martha -p 6874 -R

startppo Utility: Starts the Infoprint SMIT Production Print Operations Interface in Infoprint Manager for AIX

Syntax

```
startppo [-t | -g width×depth+XOffset+YOffset]
startppo {-h | -?}
```

Description

Issue the **startppo** utility to start the Infoprint SMIT production print operations interface

Flags

The **startppo** utility uses the following flags:

-t Starts the ASCII (tty) version of the Infoprint SMIT production print operations interface. The ASCII version of the Infoprint SMIT production print operations interface has no graphics and is controlled with the keyboard.

If you do not specify the **-t** flag, **startppo** starts the AIXWindows version of the Infoprint SMIT production print operations interface. The AIXWindows version displays a graphic of a running man to indicate task progress and can be controlled either with the mouse or with the keyboard.

-g width×depth+XOffset+YOffset

Overrides the default size and position of the window for the AIXWindows version of the Infoprint SMIT production print operations interface.

- **-h** Displays help for the **startppo** utility.
- -? Displays help for the **startppo** utility.

Examples

 To start the ASCII version of the Infoprint SMIT production print operations interface, enter:

```
startppo -t
```

• To start the AIXWindows version of the Infoprint SMIT production print operations interface in an 800 by 500 window, enter:

```
startppo -g 800×500+100+100
```

start_server Utility: Starts a Server for a Basic Infoprint Installation in Infoprint Manager for AIX

Syntax

start_server [-1] locale [-p] port [ServerName] start_server -?

Description

Issue the **start_server** utility to create or restart a server configured for a basic Infoprint installation. A server:

- Manages the validation, routing, and scheduling of jobs
- Manages the printing or transmission process
- Contains logical destinations, queues, and actual destinations

Three possible conditions can exist when you issue this utility:

- If the server name you specify with the utility (or the default server name) does not exist, Infoprint creates the server on the AIX processor from which you issue the utility and then starts the new server.
- If the server name does exist but is not currently running, Infoprint displays status information and issues a message when it has successfully restarted the server.
- If the server name does exist and it is currently running, Infoprint displays a message that shows the server is already operational.

Note: Use **start_server** instead of **startsrv** when both these conditions are true:

- You want to configure the server for a basic Infoprint installation. start_server always configures a new server for a basic installation, while startsrv defaults to an advanced installation.
- You do not want to be prompted for confirmation if the server does not already exist. start_server never prompts, while startsrv prompts by default.

Flags

The **start_server** utility uses the following flags:

-1 locale

Allows you to specify the locale for Infoprint messages in a specific language. If you do not specify this flag, the default is your current locale.

-p port Allows you to specify the port number when starting a server in a locale other than the default locale. The port number you assign must not conflict with port numbers in use by other processes. The file /etc/services lists the port numbers reserved by other processes.

If you do not specify this flag, the port defaults to the value of the PD_SOCKET environment variable, if any, then to 6874.

Note: When selecting your own port number, always increment the choice by two because the Infoprint server uses two numbers: the one you specify and the next one, for example, 6874 and 6875.

-? Displays help for the **start_server** utility.

Arguments

The argument value identifies the specific object to which the utility applies.

The valid argument value for the start_server utility is:

ServerName

Assigns a name to a new server or specifies the name of the server to restart. *ServerName* defaults to the hostname.

Examples

• To create a server with the same name as the host and configure it for a basic installation, enter:

start_server

• To restart serv1, enter:

start_server serv1

startsrv Utility: Starts a Server in Infoprint Manager for AIX

Syntax

startsrv [-c] [-F] [-1] locale [-p] port [ServerName] startsrv -?

Description

Issue the **startsrv** utility to create or restart a server. A server:

- Manages the validation, routing, and scheduling of jobs
- · Manages the printing or transmission process
- Contains logical destinations, queues, and actual destinations

The following conditions can exist when you issue this utility:

- If the server name you specify with the utility (or the default server name), does not exist, and if you do not specify the -F flag, Infoprint displays a confirmation message asking if you want to create a new server. If your response is yes, Infoprint creates the server on the AIX processor from which you issue the utility and then starts the new server.
- If the server name does not exist, and if you specify the -F flag, Infoprint creates the server on the AIX processor from which you issue the utility without asking for confirmation and then starts the new server.
- If the server name does exist but is not currently running, Infoprint displays status information and issues a message when it has successfully restarted the
- If the server name does exist and it is currently running, Infoprint displays a message that shows the server is already operational.

Note: Use **startsrv** instead of **start_server** when either of these conditions is true:

- You want to configure the server for an advanced Infoprint installation. startsrv configures a new server for an advanced installation by default, while start_server always configures a new server for a basic installation.
- You want to be prompted for confirmation if the server does not already exist. **startsrv** prompts by default, while **start_server** never prompts.

Flags

The **startsrv** utility uses the following flags:

- -c Configures a new server for a basic Infoprint installation. If you do not specify this flag, Infoprint configures the server for an advanced installation. This flag has no effect on an existing server.
- -F Forces creation of the server if it does not already exist. Infoprint does not display confirmation prompts (if any).
 - If you do not specify this flag and if the server does not already exist, Infoprint prompts you to confirm whether to create the server.
- -1 locale
 - Allows you to specify the locale for Infoprint messages in a specific language. If you do not specify this flag, the default is your current locale.
- -p port Allows you to specify the port number when starting a server in a locale other than the default locale. The port number you assign must not conflict

with port numbers in use by other processes. The file /etc/services lists the port numbers reserved by other processes.

If you do not specify this flag, the port defaults to the value of the PD_SOCKET environment variable, if any, then to 6874.

Note: When selecting your own port number, always increment the choice by two because the Infoprint server uses two numbers: the one you specify and the next one, for example, 6874 and 6875.

-? Displays help for the **startsrv** utility.

Arguments

The argument value identifies the specific object to which the utility applies.

The valid argument value for the startsrv utility is:

ServerName

Assigns a name to a new server or specifies the name of the server to restart. *ServerName* defaults to the hostname.

Examples

• To create a server with the name serv1 and configure it for an advanced installation, enter:

startsrv -F serv1

• To create a server with the same name as the host and configure it for a basic installation, enter:

startsrv -c -F

• To restart serv1, enter:

startsrv serv1

stop_server Utility: Shuts Down a Server in Infoprint Manager for AIX

Syntax

```
stop_server [-F] [ServerName]
stop_server -?
```

Description

Issue the **stop_server** utility to shut down a server.

Flags

The **stop_server** utility uses the following flags:

- -F Forces the server to shut down as soon as possible. If you do not specify this flag, the server shuts down when all currently printing jobs have finished printing.
- -? Displays help for the **stop_server** utility.

Arguments

The argument value identifies the specific object to which the utility applies.

The valid argument value for the **stop_server** utility is:

ServerName

Specifies the name of the server to shut down. *ServerName* defaults to the hostname.

Examples

• To shut down a server with the same name as the host as soon as possible, enter:

```
stop server -F
```

- To shut down serv1 after all currently printing jobs have finished printing, enter: stop server serv1
- To shut down the server DeServ, which is running in the locale De DE, enter:

```
export LC_ALL=De_DE
stop_server DeServ
export LC ALL=
```

tdump Utility: Outputs Tape Contents in Human-Readable Format in **Infoprint Manager for AIX**

Syntax

```
tdump [-a] [-b] [-c] [-n number] [-o OutputFile] [-s {b | f}]
           -t \{ \mathbf{rmt}m \mid \mathbf{rmt}m.n \}
```

Description

Use the **tdump** utility to output the contents of a tape in a human-readable format. You can format the output to display in hexadecimal or octal (with a readable character above each byte), dump by file or block, determine the size of a file on tape, or determine the largest block in a file.

You can examine the output from this utility to determine such information as:

- The format of the tape
- What type of data is on the tape
- The maximum block size
- Label information for IBM standard labeled and nonstandard labeled tapes
- Error diagnosis for damaged or incorrectly created tapes

tdump works from the place where the tape is positioned. If you need to dump the third file on a tape, you must position the tape with the AIX tctl command or the Infoprint SMIT production printing system interface Position A Tape panel to the beginning of the third file and then invoke **tdump**.

Flags

The **tdump** utility uses the following flags:

- Input is in ASCII. If this flag is not specified, EBCDIC is used. -a
- -h Dump by block. If this flag is not specified, file is used.
- Dump bytes in octal format. If this flag is not specified, hexadecimal is -C used.
- **-n** number

Number of files or blocks to dump. If this flag is not specified, 1 is used.

-o OutputFile

Output file. If this flag is not specified, **stdout** is used.

 $-s \{b \mid f\}$

Reports largest block size in the file (b) or the number of bytes in the file (f). Suppresses dump.

-t tdrive

Name of the tape drive containing the tape, of the form **rmt***m* or **rmt***m*.*n*, where m is a non-negative integer and n is from 1 to 7, inclusive

Examples

 To dump two files in hexadecimal to stdout from the current position of the tape in drive rmt0, enter:

```
tdump -t rmt0 -n 2
```

 To display the largest block in the file from the current position of the tape in drive rmt2, enter:

tdump -s b -t rmt2

• To instruct tdump to interpret the tape as ASCII and write the bytes in octal for the next three blocks on the tape in drive rmt0 into outfile, enter:

tdump - t rmt0 - n 3 - b - a - c - o outfile

tlist Utility: Lists Files on a Tape in Infoprint Manager for AIX

Syntax

tlist -t {rmtm | rmtm.n}

Description

For IBM standard labeled tapes, use the **tlist** utility to display the name and file characteristics (record format, record length, and block size) of each file on a tape. For nonstandard or unlabeled tapes, the **tlist** utility displays the number of files on a tape.

You can use the **tlist** utility to create a list of file names to use as arguments for the **pdpr** command.

Flags

The tlist utility uses the following flags:

-t tdrive

Name of the tape drive containing the tape, of the form rmtm or rmtm.n, where m is a non-negative integer and n is from 1 to 7, inclusive

Examples

• To display the names of all files on an IBM standard labeled tape for the tape in tape drive rmt2, enter:

tlist -t rmt2

• To count the number of files on a non-standard or unlabeled tape for the tape in tape drive rmt0, enter:

tlist -t rmt0

t2file Utility: Reads MVS Partitioned Data Sets from Tape in Infoprint Manager for AIX

Syntax

t2file [-d directory] [-m member ...] -t {rmtm | rmtm.n} [-s]

Description

Use the t2file utility to read MVS partitioned data sets from IBM standard labeled tapes created with the MVS IEBCOPY program and to break them apart into individual files on AIX.

The typical application for this program is to break apart host resource libraries that have been dumped to tape into individual files, as IBM Infoprint Control requires.

Flags

The **t2file** utility uses the following flags:

-d directory

Directory where files should be written. If this flag is not specified, the files are written to the current directory.

-m member ...

Specific members to read from the MVS partitioned data set. If this flag is not specified, all members are read.

Note: You must specify all the file names with one use of the **-m** option. To specify one name, use **t2file** -m *memname*. To specify multiple names, use t2file -m 'mem1 mem2 mem3'. If you have multiple -m options, t2file does not concatenate them together. It uses the last occurrence of -m on the command line.

-t tdrive

Name of the tape drive containing the tape, of the form **rmt***m* or **rmt***m*.*n*, where m is a non-negative integer and n is from 1 to 7, inclusive.

Unload only one MVS partitioned data set. If this flag is not specified, all -s partitioned data sets are read.

Examples

- To designate specific members to read from the MVS partitioned data set, enter: t2file -m 'mem1 mem2 mem3' -t rmt3
- To unload only one MVS partitioned data set from tape drive rmt2 into the current directory and then end the program, position the tape at the beginning of the header label before the partitioned data set with the AIX tctl command on the Infoprint SMIT production printing system interface Position A Tape panel and enter:

t2file -t rmt2 -s

• To unload all the members from all the partitioned data sets on the tape in the drive rmt0 into /home/custom/resources, enter:

t2file -t rmt0 -d /home/custom/resources

t2file

Chapter 5. Daemon Utilities for Infoprint Manager for AIX

This chapter describes the following Infoprint daemon utilities:

- "mvsprsd Utility: Starts the mvsprsd Daemon" on page 188
- "pcl2afpd Utility: Starts the pcl2afpd Daemon" on page 190
- "ps2afpd Utility: Starts the ps2afpd Daemon" on page 193
- "startnotd Utility: Starts the notifyd Daemon" on page 197
- "stopnotd Utility: Stops the notifyd Daemon" on page 198
- "startcbd Utility: Starts the SAP Callback Daemon" on page 199
- "stopcbd Utility: Stops the SAP Callback Daemon" on page 201

mvsprsd Utility: Starts the mvsprsd Daemon

Syntax

mvsprsd -**p**PortNumber -**d** FileSystem [-**d** FileSystem ...] [-**x** ShellScript] [-**q** destination] [-**k**]

Description

Use the **mvsprsd** daemon to start the **mvsprsd** daemon. This daemon receives the data that MVS Download transmits from the Job Entry Subsystem (JES) spool on an MVS system for printing.

You can specify that the **mvsprsd** daemon starts whenever the system starts by including the **mvsprsd** command in one of the files that are executed when the AIX operating system is initialized. The two types of files that are read during AIX initialization are /etc/rc files and the /etc/inittab file.

If the **mvsprsd** daemon stops running for some reason, you can restart it by issuing the following command:

```
/usr/lpp/psf/bin/mvsprsd -p PortNumber -d FileSystem -x ShellScript -q destination -k
```

If your job does not print on IBM Infoprint Control, you might be able to restart the shell script process with the downloaded file and downloaded print-options string. If you specified the -k flag on the print command, you can use the following command to restart the shell script with its required parameter list: /usr/lpp/pd/bin/mvsprpsm.sh FileName.PRD "\$(cat string.JCL)" destination

where FileName.PRD represents the file successfully downloaded to IBM Infoprint Control as

MVS_system_name.jobname.dataset_name.forms_name.yyyyddd.hhmmsstABCD.PRD; and where string.JCL represents the MVS print options string that is saved to a file named in the following format:

MVS_system_name.jobname.dataset_name.forms_name.yyyyddd.hhmmsstABCD.JCL.

Note that the string /usr/lpp/pd/bin/mvsprpsm.sh... refers to the shell script that is provided with this command. Check to see that your installation has not modified this shell script or added another shell script before specifying this value.

Flags

The **mvsprsd** daemon utility uses the following flags:

-p PortNumber

Specifies the socket port number for the daemon in the valid range (5001-64000). Do not use 8251 and 8253, which are used by Infoprint for the PCL and PostScript data transforms. The port number must be the same as the port number specified in the routing-control data set used by MVS Download.

-d FileSystem

Specifies a file system where Infoprint stores the received file until the shell script you specify in the -x flag processes and deletes the file. The **mvsprsd** daemon must have write permission for the file system.

You must specify at least one file system. You can specify up to ten file systems. If you specify more than one file system, the file system having the most available space is used. To specify more than one file system, specify the entire flag again:

-d FileSystem1 -d FileSystem2 ...

-x ShellScript

Specifies the complete path name and file name for the shell script that the daemon executes to process the files sent by MVS Download. You can specify the the file name of the shell script without the path name and it will default to the /usr/lpp/pd/bin path.

The daemon forks a child process to execute the shell script after each successfully received file. If you do not specify the path name of a shell script, the received files are not printed and remain on the file system.

Infoprint provides a shell script, mvsprpsm.sh, which submits a file to the pdpr command for printing and deletes the file if the file prints successfully. This shell script is installed in the /usr/lpp/pd/bin directory.

-q destinationname

Specifies the name of the logical destination to which the shell script can submit the file. If you specify a logical destination, you should also specify the name of a shell script on the -x flag that the program uses to submit files to the logical destination.

If you specify this shell script on the -x flag, you must specify the -q flag or **mvsprsd** displays its command syntax and exits.

If you do not specify a logical destination name, the received files are not printed and remain on the file system.

-k Specifies that the MVS print-options string is kept on the file system and can be used later for error recovery. If a file is transferred from MVS to AIX successfully, but does not print because of a problem, IBM recommends that you specify this option so that the job can be resubmitted for printing from the AIX operating system.

Examples

- 1. To start an MVS Download daemon that stores files received from the JES spool on the /files1 or /files2 file system and executes the **mvsprpsm.sh** shell script, which submits the files to the serv2-1p logical destination, enter:
- 2. To have the same MVS Download daemon keep the MVS print-options string file(s), enter:

mvsprsd -p5400 -d/files1 -d/files2 -qserv2-lp -k

Note: Anyone can start the **mvsprsd** daemon, but only someone with **root** authority can stop it.

mvsprsd -p 5400 -d /files1 -d /files2 -x mvsprpsm.sh -q serv2-lp

Suggested Reading

- PSF/MVS: MVS Download Guide
- The man pages for the rc command and the inittab file

pcl2afpd Utility: Starts the pcl2afpd Daemon

Syntax

pcl2afpd [-C ConfigurationFile]

Description

Use the pcl2afpd utility to start the pcl2afpd daemon. The pcl2afpd daemon manages the PCL interpreter portion of the Infoprint PCL transform program. You must start the pcl2afpd daemon somewhere on the network before you can use the pcl2afp transform command to transform PCL data streams for printing or transmission with Infoprint.

The **startsrv** or **start_server** utility automatically starts the **pcl2afpd** daemon if it is installed and not running.

If the pcl2afpd daemon stops running, you can restart it by issuing the following command:

/usr/lpp/psf/bin/pcl2afpd

Infoprint uses the <code>pcl2afpd</code> daemon configuration file to determine the default parameters of the <code>pcl2afpd</code> daemon. The <code>/usr/lpp/psf/pcl2afp/pcl2afpd.cfg</code> file is installed with Infoprint, and Infoprint uses it as the default configuration file. You can, however, copy the configuration file, use an AIX editor to edit the copy of the file, and rename it so that you can customize the <code>pcl2afpd</code> daemon for your applications. After you make the modifications, you specify the new configuration file with the <code>-C</code> flag of the <code>pcl2afpd</code> daemon utility.

Note: If you create your own configuration file, you must specify it with the **-C** flag of the **pcl2afp** transform command when you transform PCL files.

Flags

The pcl2afpd daemon utility uses the following flag:

-C ConfigurationFile

Specifies the configuration file Infoprint uses with the transform. The value is:

ConfigurationFile

A valid PCL configuration file name. If you do not specify a file, Infoprint uses the file /usr/lpp/psf/pcl2afp/pcl2afpd.cfg.

Configuration File Keywords and Values

The pcl2afpd.cfg file contains the same keywords as the pcl2afp.cfg file except that the transform daemon configuration file does not have the server keyword. The pcl2afpd.cfg contains several additional keywords.

For the keywords common to both configuration files, see "The pcl2afp and pcl2afpd Configuration Files" on page 276.

The PCL transform daemon configuration file can also contain the following keywords:

device_controls=[plex,][input*n*=(pcl_bin=*m*)][input*n*=...)]

Specifies whether to recognize the plex command in the PCL datastream,

and optionally, how to associate the AFP input tray (**input***n*, where *n* is between 1 and 255) with the pcl bin (pcl_bin=m, where m is between 0 and 59). When you do not specify **input***n*=(**pcl_bin**=*m*) with **plex**, Infoprint recognizes the plex command with no tray mappings. If you do not specify plex and tray mapping is not supplied, Infoprint uses the settings in the default formdef (which is duplex).

Note: You can specify **input***n***=**(**pcl_bin=***m*) up to twenty times.

log_file={WorkDirectory/pcl2afpd.log | PathName}

Specifies the file in which the transform daemon logs errors and messages when it converts a data stream from PCL to an AFP data stream.

Valid keyword values are:

WorkDirectory/pcl2afpd.log

This is the default log file, where WorkDirectory is the value of the work_directory keyword. The default work directory is /var/psf/pcl2afp.

PathName

The full path name of a log file

mail command={/usr/bin/mail | PathName}

Specifies the executable file that the pcl2afp command uses to send transform status notifications.

Valid keyword values are:

/usr/bin/mail

The AIX mail command

PathName

The full path name of a communication program

notify={root | UserID}

Identifies the user to receive notification about problems encountered during transformation of the PCL file into an AFP data stream file. If a particular user runs most of the PCL transform jobs, you might want to send notifications to that person using this keyword.

Valid keyword values are:

The user at the server console root

UserID

An AIX user ID

pcl_program={/usr/lpp/psf/bin/ppxpcli | PathName}

Specifies which PCL-to-AFP transform program (the PCL interpreter) to run. Generally, you will not change this value.

Valid keyword values are:

/usr/lpp/psf/bin/ppxpcli

The default PCL interpreter

PathName

The full path name of a PCL interpreter file

pcl_support_prog={/usr/lpp/psf/bin/ppxpclis | PathName}

Specifies which PCL-to-AFP transform support program to run. Generally, you will not change this value. Values are:

/usr/lpp/psf/bin/ppxpclis

The default PCL support program

PathName

The full path name of a PCL support program.

work_directory={/var/psf/pcl2afp | PathName}

Specifies the path to the directory where the transform daemon puts its work files. The transform daemon must have read, write, and execute permissions to this directory. The transform daemon is owned by the root user, but runs as daemon, and is in the printq group.

Values are:

/var/psf/pcl2afp

The default work directory

PathName

A directory path

Examples

• To restart the pcl2afpd daemon with the default configuration file, enter: pc12afpd

Notes:

- 1. If you have not set the PATH environment variable to include /usr/lpp/psf/bin, you must enter the path name with the pcl2afpd daemon.
- 2. Anyone can start the pcl2afpd daemon, but only a person with root user authority can stop it.
- To restart the pcl2afpd daemon with the configuration file myfile.cfg, which resides in the directory /usr/lpp/psf/pcl2afp, enter: pcl2afpd -C /usr/lpp/psf/pcl2afp/myfile.cfg

Files

/usr/lpp/psf/bin/pcl2afpd

Transform daemon

/usr/lpp/psf/pcl2afp/pcl2afpd.cfg

pcl2afpd daemon configuration file

/usr/lpp/psf/bin/ppxpcli

PCL interpreter program

/usr/lpp/psf/bin/ppxpclis

PCL interpreter support program

ps2afpd Utility: Starts the ps2afpd Daemon

Syntax

ps2afpd [-C ConfigurationFile]

Description

Use the ps2afpd utility to start the ps2afpd daemon. The ps2afpd daemon manages the interpreter portion of the Infoprint PostScript and PDF transform programs. You must start the ps2afpd daemon somewhere on the network before you can use the ps2afp or pdf2afp transform command to transform PostScript or PDF data streams for printing with Infoprint on IPDS printers.

The startsrv or start_server utility automatically starts the ps2afpd daemon if it is installed and not running.

If the ps2afpd daemon stops running, you can restart it by issuing the following command:

/usr/lpp/psf/bin/ps2afpd

Infoprint uses the ps2afpd daemon configuration file to determine the default parameters of the ps2afpd daemon. The /usr/lpp/psf/ps2afpd.cfg file is installed with Infoprint, and Infoprint uses it as the default configuration file. You can, however, copy the configuration file, use an AIX editor to edit the copy of the file, and rename it so that you can customize the ps2afpd daemon for your applications. After you make the modifications, you specify the new configuration file with the -C: flag of the ps2afpd daemon utility.

Note: If you create your own configuration file, you must specify it with the -C flag of the ps2afp transform command when you transform PostScript or PDF files.

Flags

The **ps2afpd** daemon utility uses the following flag:

-C ConfigurationFile

Specifies the configuration file Infoprint uses with the transform. The value

ConfigurationFile

A valid PostScript configuration file name. If you do not specify a file, Infoprint uses the file /usr/lpp/psf/ps2afp/ps2afpd.cfg.

Configuration File Keywords and Values

The ps2afpd.cfg file contains the same keywords as the ps2afp.cfg file except that the transform daemon configuration file does not have the server keyword. The ps2afpd.cfg contains several additional keywords.

For the keywords common to both configuration files, see "The ps2afp and ps2afpd Configuration Files" on page 297.

The PostScript transform daemon configuration file can also contain the following keywords:

device_controls=[plex,][inputw=(size[,type=x,color=y,weight=z)][inputn=...)]

Specifies whether to recognize the plex command, and optionally, how to associate the AFP input tray (inputw) with the contents of the output bin. When you specify inputw, you must specify size, where size is a text string like letter, legal, a3, a4, b4, b5, ledger, or a dimension like 8.5ix11i. Dimensions can be specified as inches (i), millimeters (m), or points (p). The other three input descriptors (type, color, and weight) are optional, but when you specify them, you must separate them with a comma and no spaces.

When you do not specify **input***w*=*size*... with **plex**, Infoprint recognizes plex mappings with no additional information for the tray contents.

Note: You can specify [**input***w*=(*size* ...)] as many times as you need to.

log_file={WorkDirectory/pcl2afpd.log | PathName}

Specifies the file in which the transform daemon logs errors and messages when it converts a data stream from PostScript or PDF to an AFP data stream.

Valid keyword values are:

WorkDirectory/ps2afpd.log

This is the default log file, where *WorkDirectory* is the value of the **work_directory** keyword. The default work directory is **/var/psf/ps2afp**.

PathName

The full path name of a log file

mail_command={/usr/bin/mail | PathName}

Specifies the executable file that the **pcl2afp** command uses to send transform status notifications.

Valid keyword values are:

/usr/bin/mail

The AIX mail command

PathName

The full path name of a communication program

notify={root | UserID}

Identifies the user to receive notification about problems encountered during transformation of the PostScript or PDF file into an AFP data stream file. If a particular user runs most of the PostScript and PDF transform jobs, you might want to send notifications to that person using this keyword.

Valid keyword values are:

root The user at the server console

UserID

An AIX user ID

ps_program={/usr/lpp/psf/bin/ppxps2i | PathName}

Specifies which Postscript-or-PDF-to-AFP transform program (the PostScript interpreter) to run. Generally, you will not change this value. If you do change it, you must change the value of the <code>ps_init_file</code> keyword to specify an initialization file at the same level.

Valid keyword values are:

/usr/lpp/psf/bin/ppxps2i

The PostScript Level 2 transform

PathName

The full path name of a PostScript interpreter file

ps_init_file={/usr/lpp/psf/ps2afp/ppxps2.ps | PathName}

Specifies the PostScript initialization program to use with the PostScript interpreter. This file specifies the types of messages that the PostScript interpreter reports. Generally, you will not change this value. If you do change it, you must change the value of the ps_program keyword to specify a PostScript interpreter at the same level.

Valid keyword values are:

/usr/lpp/psf/ps2afp/ppxps2.ps

The PostScript Level 2 initialization file

PathName

The full path name of an initialization file

work_directory={/var/psf/ps2afp | PathName}

Specifies the path to the directory where the transform daemon puts its work files. The transform daemon must have read, write, and execute permissions to this directory. The transform daemon is owned by the root user, but runs as daemon, and is in the printq group.

Values are:

/var/psf/ps2afp

The default work directory

PathName 1 8 1

A directory path

Examples

 To restart the ps2afpd daemon with the default configuration file, enter: ps2afpd

Notes:

- 1. If you have not set the **PATH** environment variable to include /usr/lpp/psf/bin, you must enter the path name with the ps2afpd daemon.
- 2. Anyone can start the **ps2afpd** daemon, but only a person with **root** user authority can stop it.
- To restart the ps2afpd daemon with the configuration file myfile.cfg, which resides in the directory /usr/lpp/psf/ps2afp, enter:

ps2afpd -C /usr/lpp/psf/ps2afp/myfile.cfg

Files

/usr/lpp/psf/bin/ps2afpd

PostScript daemon

/usr/lpp/psf/bin/ps2afp

PostScript transform executable

/usr/lpp/psf/bin/pdf2afp

PDF transform executable (linked to /usr/lpp/psf/bin/ps2afp)

/usr/lpp/psf/ps2afp/ps2afpd.cfg

ps2afpd daemon configuration file

/usr/lpp/psf/ps2afp/ps2afp.cfg

ps2afp command configuration file

ps2afpd

/usr/lpp/psf/bin/ppxps2i

PostScript level 2 interpreter program

/usr/lpp/psf/bin/ps2afpi

PostScript Level 1 interpreter program

/usr/lpp/psf/bin/ps2afpi.vm

PostScript interpreter program initial virtual memory

/usr/lpp/psf/ps2afp/ppxps2.ps

PostScript level 2 initialization file

/usr/lpp/psf/ps2afp/ps2afp.ps

PostScript Level 1 initialization file

/usr/lpp/psf/ps2afp/ps2afpe.ps

PostScript Level 1 initialization file for extended error reporting

/usr/lpp/psf/bin/fontsave

PostScript executable for saving fonts

/usr/lpp/psf/ps2afp/psfonts.map

Default PostScript font mapping file

/var/psf/psfonts

User-defined PostScript fonts file

startnotd Utility: Starts the notifyd Daemon

Syntax

startnotd

Description

Use the startnotd utility to start the notifyd daemon. The notifyd daemon receives and stores notification messages for all users requesting notification by deliver-method message. Only one notification daemon needs to be running for each Infoprint Manager cell or domain; one notification daemon receives notifications from and services all Infoprint Manager servers sharing the same name space.

With Infoprint Manager for AIX, you can specify that the **notifyd** daemon starts whenever the system starts or is rebooted by using the Infoprint Manager SMIT panels on AIX.

The **notifyd** daemon has a monitor that will restart it if it ever stops running. If you want to stop it, to move it to another machine for example, use the "stopnotd Utility: Stops the notifyd Daemon" on page 198.

stopnotd Utility: Stops the notifyd Daemon

Syntax

stopnotd

Description

Use the **stopnotd** utility to stop the **notifyd** daemon and its monitor.

If you want to start the **notifyd**, see "startnotd Utility: Starts the notifyd Daemon" on page 197.

startcbd Utility: Starts the SAP Callback Daemon

Syntax

startcbd SystemName HostName InstanceID User Client Password Language[31h]

Description

Use the **startcbd** utility to start a **sapbcd** daemon. The **sapbcd** or SAP Callback daemon logs onto an SAP system and delivers notifications from Infoprint Manager servers to the SAP system. You should start only one sapbcd for each SAP system for which you have configured Infoprint Manager as an Output Management System (OMS). All SAP instances sharing the same database form one SAP system.

See "rc.iprsap Utility: Start SAP Callback Daemons for Infoprint Manager for AIX" on page 166 for information on having SAP Callback daemons start on system reboot.

Each sapbcd daemon has a monitor that will restart if it stops for some reason. If you want to stop it, to move it to another machine for example, use the "stopcbd Utility: Stops the SAP Callback Daemon" on page 201.

Arguments

The **startcbd** utility uses the following arguments:

SystemName

Specifies the three character SAP system name.

HostName

Specifies the name of the host where you want the SAP Callback daemon to log onto the SAP system.

InstanceID

Specifies the SAP Instance ID you want the SAP Callback daemon to log

User Specifies the userid defined for the SAP Callback daemon to log on with. This needs to be a userid of CPIC type with XOMI permissions.

Client Specifies the SAP client for the SAP Callback daemon to log onto.

Password

Specifies the password for the SAP Callback daemon to log on with.

Language

Specifies the language for the SAP Callback daemon to log on with.

31h An extra argument to specify that the SAP Callback daemon is for a 3.1h or 3.1i system.

Examples

- To start the **startcbd** daemon to support SAP Release 4 System TST after you
 - Configured Infoprint Manager as an OMS in TST
 - Created a CPIC user for the **sapcbd** daemon
 - Identified which instance and client you want the **startcbd** to log onto

Then you would enter:

startcbd

startcbd TST ibmbtt15 15 ibm 030 ipmpass EN

- To start the **startcbd** daemon to support SAP Release 3.1 System TST after you have:
 - Configured Infoprint Manager as an OMS in TST
 - Created a CPIC user for the sapcbd daemon
 - Identified which instance and client you want the startcbd to log onto

Then you would enter:

startcbd TST ibmbtt15 15 ibm 030 ipmpass EN 31h

stopcbd Utility: Stops the SAP Callback Daemon

Syntax

stopcbd SAPSystemName

Description

Use the **stopcbd** utility to stop the **sapcbd** daemon or SAP Callback daemon for an SAP system and stop its monitor.

Arguments

The **stopcbd** utility uses the following argument:

SAPSystemName

Specifies the three character ID of the SAP system that the sapcbd daemon is supporting. This is the specific **sapcbd** daemon to stop.

Examples

To stop or shutdown the **sapcbd** daemon for SAP System PRD, enter: stopcbd PRD

stopcbd

Chapter 6. Infoprint Transform Commands

This chapter describes the following Infoprint transform commands:

Transform Name	AIX	NT and 2000
"db2afp Command: Transforms DBCS Data to AFP" on page 205	AIX	NT and 2000
"d2afp Command: Transforms ditroff Data to AFP in Infoprint Manager for AIX" on page 209	AIX	N/A
"gif2afp Command: Transforms GIF Data to AFP in Infoprint Manager for AIX" on page 212	AIX	N/A
"jpeg2afp Command: Transforms JPEG Data to AFP in Infoprint Manager for AIX" on page 226	AIX	N/A
"line2afp Command: Transforms S/370 Line Data and ASCII Data to AFP" on page 239	AIX	NT and 2000
"pcl2afp Command: Transforms PCL Data to AFP" on page 264	AIX	NT and 2000
"pdf2afp and ps2afp Transforms: Transform PDF or PostScript Data to AFP" on page 287	AIX	NT and 2000
"sap2afp Command: Transforms SAP OTF or ABAP Data to AFP in Infoprint Manager for AIX" on page 302	AIX	N/A
"tiff2afp Command: Transforms TIFF Data to AFP in Infoprint Manager for AIX" on page 313	AIX	N/A

Note: Infoprint invokes the appropriate transform automatically whenever you print a DBCS ASCII, DBCS EUC, ditroff, GIF, JPEG, line data, PCL, PDF, PostScript, SAP, or TIFF job on a PSF physical printer. You can pass options to these transforms using the **other-transform-options** document attribute on the Infoprint **pdpr** command or the **-o** flag of the AIX print commands (**enq**, **lp**, and **qprt**) and the Infoprint **lprafp** command.

For more information, see "Attributes for Documents and Default Documents" on page 464, "pdpr Command: Submits Jobs" on page 61, "lprafp Command: Submits Remote Jobs in Infoprint Manager for AIX" on page 13, or "Chapter 3. The -o Flag

Transforms

for AIX Print Commands" on page 103.

db2afp Command: Transforms DBCS Data to AFP

Syntax

db2afp [-o -OutputFile] [-l {ja | ch | ko}] [-e] [InputFile]

Description

Use the **db2afp** command to transform either a DBCS ASCII or an EUC file into an AFP data stream file so that you can print the file on an Infoprint printer.

The db2afp command can transform input files that use the following code pages:

- Japanese PC (code page number 932)
- Japanese EUC
- Traditional Chinese PC (code page number 938 and 950 for AIX)
- Traditional Chinese PC (code page number 950 for NT)
- Traditional Chinese EUC
- Korean EUC

You can run **db2afp** manually if you want to transform a DBCS ASCII or EUC file into an AFP data stream file without printing it immediately.

The PSF DSS automatically runs the db2afp command whenever:

- Infoprint identifies the format of a document in a print job as DBCS ASCII or EUC.
- You specify **document-format=dbcs-ascii** with the **-x** flag or in an attributes file on the **pdpr** command.

Note: For EUC format, specify **document-format=dbcs-ascii** and an EUC code page as the value of the **default-character-mapping** attribute.

- You submit a DBCS ASCII or EUC print job and request -odatatype=dbcsascii
 with one of the AIX print commands (enq, lp, and qprt) or with the lprafp
 command
- You select an attributes file that shows **dbcs-ascii** in the Type of Data in the Print File field, using the Infoprint SMIT panels.

If you do not specify an input file, the **db2afp** command defaults to standard input. If no output file is specified, the **db2afp** command defaults to standard output.

Limitations

The **db2afp** command generates an AFP data stream file with double-byte character set (DBCS) font references. These DBCS fonts (for Japanese, Traditional Chinese, and Korean) are not part of Infoprint and are sold separately.

Flags and Values

You can specify these flags and values

- With the db2afp command
- With the enq -o, lp -o, qprt -o, or lprafp commands
- With the **pdpr** command, using the **other-transform-options** attribute or equivalent attributes on the command line or in an attributes file

Note: If you are migrating from PSF for AIX, see "Appendix B. Migrating PSF for AIX Job Script Keywords to Infoprint Equivalents" on page 715 for a table of attributes equivalent to the job script keywords that you used to use to specify flags and values for transforms.

-o OutputFile

Specifies the name of the AFP data stream output file generated by the transform. If you do not specify the **-o** flag, Infoprint writes the result to standard output.

You cannot use **-o**OutputFile on the command line with the **enq**, **lp**, **qprt**, or **lprafp** commands. You can only use **-o**OutputFile with the **db2afp** command, or with the **other-transform-options** attribute on the **pdpr** command.

This flag is equivalent to the **transform-output-file-name** document attribute on the **pdpr** command.

-1 {japanese | chinese | korean}

Specifies the language to be used for the transform. The values are: **ja** | **japanese**

The input file is in Japanese.

ch | chinese

The input file is in Traditional Chinese for AIX (code page 938).

c2 The input file is in Traditional Chinese for NT/2000 (code page 950).

ko | korean

The input file is in Korean.

Note: If you specify **-l ko**, you must also specify the **-e** flag. The **db2afp** command supports only Korean EUC, not Korean DBCS ASCII.

If you do not specify -l or -e on the command line, the db2afp command uses the value that has previously been set and exported with the PSFDBLANG environment variable. The PSFDBLANG environment variable can be set to one of the following:

- j Japanese (code page 932)
- je Japanese EUC
- c Traditional Chinese (code page 938)
- t Traditional Chinese (code page 950)
- ce Traditional Chinese EUC
- ke Korean EUC

With Infoprint Manager for AIX, if you are unsure about the value to use with the **PSFDBLANG** environment variable, enter the following command:

echo \$LANG

The command displays one of the following output values:

Ja_JP Japanese DBCS ASCII

ja_JP Japanese EUC

zh_TW

Traditional Chinese EUC

ko_KR

Korean EUC

With Infoprint Manager for Windows NT and Windows 2000, if you are unsure about the value to use with the **PSFDBLANG** environment variable, enter the following at a Windows command prompt: chcp

The command displays the following information: Active code page: nnn

where nnn is the code page number 932, 938, 950.

Notes:

- A Traditional Chinese DBCS ASCII locale does not exist.
 If you specify either -l or -e on the command line, the db2afp command ignores the value set in the PSFDBLANG environment variable. If the PSFDBLANG value has not been set and you do not specify -l (and -e for EUC files), the transform will not work.
- 2. The value set in the **PSFDBLANG** environment variable is used when you submit a DBCS ASCII or EUC print job with the AIX print commands (**enq**, **lp**, or **qprt**), with the **pdpr** or **lprafp** command, or in the SMIT Submit an Infoprint Job panel.
- 3. This flag and the **-e** flag, used together, are equivalent to the **default-character-mapping** document attribute on the **pdpr** command.
- -e Tells the db2afp command to use the EUC code page when converting the input file into an AFP data stream. If the input file is in the Korean language, you should always use -e. If the input file is in Traditional Chinese or Japanese, you should use -e if your input data is in EUC format.

This flag and the -l flag, used together, are equivalent to the **default-character-mapping** document attribute on the **pdpr** command.

InputFile

Specifies the DBCS ASCII or EUC file that will be transformed into AFP. If you do not specify an input file, the **db2afp** command uses standard input.

Examples

• To transform the Japanese DBCS ASCII file dbfile into an AFP data stream file called dbfile.afp, enter:

```
db2afp -o dbfile.afp -l ja dbfile
```

The file is transformed, but not printed.

Note: You could also use the following command to perform a similar task, except that the output is sent to the printer:

```
pdpr -p servC-lp -x "default-character-mapping=ibm-932" dbfile
```

 To transform the Korean EUC file korefile into an AFP data stream file called korefile.afp, enter:

```
db2afp -o korefile.afp -l ko -e korefile
```

The file is transformed, but not printed.

Note: You could also use the following command to transform the file, then print it:

```
pdpr -p servC-lp -x "other-transform-options='-e -l ko'" korefile
```

or

pdpr -p servC-lp -x "default-character-mapping=ibm-euckr" korefile

 With Infoprint Manager for AIX, to transform a Traditional Chinese DBCS ASCII file named memo.tc into an AFP file and print it on an Infoprint printer named servC-1p, enter:

```
pdpr -X chinese.X -p servC-lp memo.tc
```

In this example, the attributes file named chinese.X contains the following settings:

```
document-format=dbcs-ascii
default-character-mapping=ibm-938
```

With Infoprint Manager for AIX, to set the db2afp command to default to Korean EUC, enter the following lines in the .profile file (Bourne shell or Korn shell) or the .cshrc file (C shell) in your home directory:

```
export PSFDBLANG=ke
```

The db2afp command now uses Korean EUC as long as the PSFDBLANG environment variable is set and exported, and -l or -e are not specified on the command line. So, to transform the Korean EUC file korefile into an AFP data stream file called korefile.afp, you now can enter:

```
db2afp -o korefile.afp korefile
```

Similarly, you could now use the following command to transform the Korean EUC file, then print it:

```
enq -PservC-lp -o datatype=dbcsascii korefile
```

Files

For Infoprint Manager for AIX, use the following locations:

/usr/lpp/psf/bin/db2afp

Transform program

/usr/lpp/psf/db2afp/afpdfont.rc

AFP font mapping file used by the db2afp command

/usr/lib/nls/loc/iconv/ConverterName

Code page translation files (which contains mappings from the input code page to the output code page)

For Infoprint Manager for Windows NT and Windows 2000, use the following locations:

install_path\bin\db2afp.exe

Transform program

install_path\bin\afpdfont.rc

AFP font mapping file used by the db2afp command

install_path\iconv\ConverterName

Code page translation files (which contains mappings from the input code page to the output code page)

d2afp Command: Transforms ditroff Data to AFP in Infoprint Manager for AIX

Syntax

d2afp [-o OutputFile] [InputFile]

Description

The **d2afp** command transforms a ditroff data stream file preformatted for an AFP device into an AFP data stream file so that you can print the file on an Infoprint printer.

The process to transform troff files into AFP data stream files has two steps:

1. The troff file is first formatted by specifying the **troff -Tafp** command. This formatting step produces a device-independent troff (ditroff) file.

Notes:

- a. Use the -Tafp flag and value; otherwise, you cannot transform the ditroff file with the d2afp command. If you do not want to specify the -Tafp flag and value each time you use the troff command, you can set the TYPESETTER environment variable to afp. To do this, enter the following at the AIX command-line prompt or add this line to your .profile file (Bourne shell or Korn shell) or the .cshrc file (C shell) in your home directory:
 - export TYPESETTER=afp
- b. Although you cannot use the **d2afp** command to transform ditroff files formatted with **troff** -**Tpsc** or **troff** -**Thplj**, you can print them. Use the **psc** or **hplj** command to convert the file to PostScript or PCL format. Then use **ps2afp** or **pcl2afp** to transform it.
- 2. The ditroff file is then transformed into an AFP data stream file with the d2afp command.

The PSF DSS automatically runs the **d2afp** command whenever:

- Infoprint identifies the format of a document in a print job as ditroff.
- You specify **document-format=ditroff** with the **-x** flag or in an attributes file submitted with the **pdpr** command.
- You submit a ditroff print job and include the -odatatype=ditroff flag and keyword-value pair with one of the AIX print commands (enq, lp, and qprt) or with the lprafp command.
- You select an attributes file that has **ditroff** in the Type of Data in Print File field when using the Infoprint SMIT panels to submit a print job.

Limitations

The **d2afp** command limits the number of fonts that a ditroff file can load, change, or map. The following shows the maximum number of fonts for specific conditions:

ditroff Fonts

Condition

- 40 Loaded at one time
- 127 Point size or font changes on one page
- 200 ditroff fonts mapped to AFP fonts

If your troff file has graphics, you might use a different method to print ditroff files. If one of the following conditions applies:

- Your PPDS or PCL printer does not support the PCL5 or PCL5C data streams.
- Your channel-attached printer does not have the Advanced Function Image and Graphics feature installed.

Note: TCP/IP-attached IPDS printers print troff files with graphics; therefore, you do not need to use other procedures.

use this procedure to print troff files containing graphics:

- 1. Convert the troff file to ditroff format using the **troff** -**Thplj** command.
- 2. Convert the ditroff file to PCL format using the **hplj** command.
- 3. Submit the PCL file to print. Infoprint automatically invokes the pcl2afp command to convert the PCL file to AFP format.

Flags and Values

You can specify the *InputFile* and the **-o** *OutputFile* values in any order.

InputFile

Specifies the name of the input file to transform. This input file must be a ditroff file; that is, a troff file formatted for an AFP printer device using the **troff** -Tafp command.

If you do not specify an input file, the command uses standard input. The value for the input file is any valid AIX file name.

-o OutputFile

Specifies the name of the AFP data stream output file generated by the transform. If you do not specify the **-o** flag, the output generated goes to standard output. The value for the output file is any valid AIX file name.

Examples

• To transform the ditroff file myfile into an AFP data stream file called myfile.afp, enter:

```
d2afp myfile -o myfile.afp
```

 To create an AFP data stream output file from the troff file doc.trf and print the output file using the Infoprint logical printer servC-lp, enter:

```
troff -Tafp doc.trf | d2afp | pdpr -p servC-lp
```

In this example, the troff command searches the /usr/lib/font/devafp directory for the troff font and printer description files. The d2afp command also uses files in this directory.

In the preceding example, the d2afp transform runs on the local AIX system whether the printer, servC-lp is a local or remote printer.

Note: You could also use the following command to perform the same function: troff -Tafp doc.trf | pdpr -p servC-lp -odatatype=ditroff

In this case, if the printer, servC-lp, is local, the **d2afp** transform runs on the local AIX system; however, if the printer is remote, the d2afp transform runs on the remote AIX system.

• To print the ditroff file report on an Infoprint printer named servD-lp, enter: pdpr -X ditroff.X report

In this example, the attributes file named ditroff.X contains the following settings:

document-format=ditroff printer-name-requested=servD-lp

Files

/usr/lpp/psf/bin/d2afp

Transform program

/usr/lib/font/devafp/devafp.fontmap

AFP font mapping file used by the d2afp command to map troff fonts to AFP code pages and AFP character sets

/usr/lib/font/devafp/*.d2afp

Binary versions of the troff font and description files used by the d2afp command

/usr/lpp/psf/fontlib

AFP font resource directory, which includes AFP character sets and AFP code pages for ditroff

/usr/lib/font/devafp/README.d2afp

File that has useful information about AFP characters for troff and ditroff files

Other files associated with the troff command are described in AIX for RS/6000 Commands Reference.

gif2afp Command: Transforms GIF Data to AFP in Infoprint Manager for AIX

Syntax

```
gif2afp [-a ImageType] [-alg ProcessingAlgorithms]
         [-calib calibration] [-C ConfigurationFile]
         [-clean cleanup] [-cmp compression]
         [-crop CropFactors] [-fit {trim | scale}]
         [-gcorr GrayscaleMappingTable] [-ink color] [-inv]
         [-i ScanOffsetFileName] [-1 ImageLength]
         [-M MemoryBound] [-ms space] [-msf SpaceFraction]
         [-o OutputFile] [-outbits NumberOfOutputBits]
         [-outcolor OutputColorModel] [-p PageRange]
         [-pagetype PageType] [-paper PaperSize]
         [-r resolution] [-respath ResourceSearchPath]
         [-rot rotation] [-scale ImageSize]
         [-sgcorr ScannerCorrection]
         [-sniff | -nosniff] [-term | -noterm]
         [-thresh HalftoneFile] [-v | -nov] [-w ImageWidth]
         [-x LeftMargin] [-y TopMargin] [-z]
         [[file | directory | -f FileList | @FileList]...]
```

Description

The gif2afp command transforms a GIF (Graphical Interchange Format) data stream into an AFP (MO:DCA-P) or PostScript Level 2 data stream file.

The transform can process GIF images, including bilevel, grayscale and color images. The output can be bilevel (IM1 or IOCA FS10), 4-bit or 8-bit grayscale, or 24-bit YCbCr color (IOCA FS11). The transform automatically uses halftoning to convert the grayscale and color images to bilevel.

Automatic Invocation

The PSF DSS automatically invokes the gif2afp transform command whenever you submit a GIF file for printing. You can pass options to gif2afp using the other-transform-options attribute on the pdpr command or the -o flag of the AIX print commands and the lprafp command.

Input and Output

gif2afp can process either standard input, or multiple files specified on the command line. If no input file is specified, stdin is assumed. Only a single GIF file should be submitted via stdin. If multiple GIF files are concatenated via standard input, all except the first one are ignored.

If an input file is specified on the command line, it can be either a GIF file, a directory, or a file list (-f and @ prefixes). Multiple input file specifications are allowed. The transform processes each file in the order in which it was specified on the command line. If the -z option is specified, a list of file names to be processed is also submitted via standard input. The files on the list are processed as if the list were given via the -f option on the same place on the command line as **-z**.

If the file name points to a directory, **gif2afp** processes every file in that directory. The files are processed in the order they would be shown using the **ls -a** command. Directory search is not recursive, that is, the subdirectories are not searched.

If the file name is preceded by the **-f** option or the at sign (@), **gif2afp** assumes that the file contains the list of GIF files to be processed. Each of the files in the list is processed in the order it was listed.

If a GIF file has the extension .gif or .GIF, this extension need not be given explicitly. gif2afp first tries to open the file as specified and, if unsuccessful, tries to append the extensions .gif and .GIF in turn.

For example, suppose that:

- The directory tFiles contains the files file1.gif, file2.gif, file3.gif, and file4.gif and nothing else.
- The file flist in the current directory contains the two file names tFiles/file2.gif and tFiles/file3.gif. The names listed in the file list may have their extensions omitted.
- The file flist2 contains the file name tFiles/file4. Again, the names listed in the file list may have their extensions omitted.

In order to process files file1.gif, file2.gif, file3.gif, and file4.gif, any of the following invocations of **gif2afp** would work:

```
gif2afp tFiles/file1.gif tFiles/file2.gif tFiles/file3.gif tFiles/file4.gif gif2afp tFiles/file1 tFiles/file2 tFiles/file3 tFiles/file4 gif2afp tFiles/file*.gif gif2afp tFiles gif2afp tFiles gif2afp tFiles/file1 -fflist tFiles/file4 gif2afp tFiles/file1 -f flist tFiles/file4 gif2afp tFiles/file1 -f flist -f flist2 gif2afp tFiles/file1 @flist @flist2
```

The file list files allow the display text to be added for each file. A display text is any text starting with the pound character (#) and extending to the end of the line. The display text should follow the file name, and can extend over several lines, up to 2048 characters long. The initial # character on each line is discarded. If a display text is present for a file name, that text is displayed in the status and error messages instead of the file name. This is useful if the <code>gif2afp</code> is invoked using temporary files whose names are meaningless to the user. Any display text before the first file name is treated as comment and discarded. Display text is allowed also if the <code>-z</code> option is used to submit the file list via standard input.

GIF files may contain multiple images. The **gif2afp** transform can process and output all the images in the file, subject to the values given in the **-p** option.

The output file name can be either specified explicitly via the **-o** option, or derived from the input file name. If multiple input files have been specified, the default output file is standard output. If a single input file is given and the output file is not specified explicitly, the transform strips the **.gif** or **.gif** extension from the input file name (if one is present), and appends the **.afp** extension for AFP output, or the **.ps** extension for PostScript output, to get the output file name.

To disable automatic output file name generation and force the default output stream to be the standard output in all cases, set the environment variable GIF2AFP_o to - or stdout, or, alternatively, put the line o=- or o=stdout into the configuration file and invoke that configuration file using the -C option or the GIF2AFP_C environment variable.

For example, all the following commands:

```
gif2afp myfile
gif2afp myfile.gif
gif2afp myfile -o myfile.afp
```

have myfile.afp as the output file. Note that there is no requirement for the explicitly specified input and output files to have .gif and .afp extensions. To process GIF file foo.bar into an AFP file foo.bar2, invoke the transform using gif2afp foo.bar -o foo.bar2

The output data stream is MODCA-P IS/1, MODCAP-P IS/2, or PostScript Level 2. IS/1 images are bilevel and are encoded as IOCA Function Set 10 or IM1. IM1 images are uncompressed. IOCA FS10 output images can be either uncompressed, or compressed via one of the four available compression algorithms (see the **-cmp** option). The default is ITU-T T.6 Group 4 compression. IM1 images are always uncompressed. IS/2 images can be either bilevel, 4-bit or 8-bit grayscale, or 24 bit YCbCr color. Multibit images are encoded as IOCA Function Set 11. Be aware that the only product that supports IOCA FS11 images is the AFP Workbench, that is, grayscale and color AFP images are not currently supported by any printer.

PostScript Level 2 images can be uncompressed or ITU-T T.6 Group 4 bilevel, uncompressed 8-bit grayscale or uncompressed 24-bit RGB color. By default, the transform leaves scaling and halftoning to the printer (that is, color GIF images are output as 24-bit RGB color images).

Errors and Error Recovery

gif2afp divides errors into fatal and non-fatal. The fatal error categories are the following:

- Errors in the user-specified parameters, either in the environment variables, the configuration file, or the command line arguments. These errors include unrecognized options, invalid values for parameters, or inability to open the configuration file or the output file.
- Out of memory errors. The requested memory is larger than the memory specified using the -M option or the dynamic memory allocation has failed.
- Disk space errors. The transform guards against trying to write to a full file system. See the -ms and -msf options for setting the minimum free disk space requirements. If the file system is full, the transform deletes the partial output file before terminating.
- Internal errors.

In the case of a fatal error, the last output page might not be complete.

Errors encountered in the GIF files are non-fatal and gif2afp attempts to recover from them. These errors include not being able to open an input file, an input file not being a GIF file, or an input file containing features that cannot be processed. If the transform fails to open 15 or more input files, it assumes an error in the parameter list (for example, -f was used with a file that does not contain a file list) and terminates.

If an error is encountered in a file, the transform attempts to recover with the next image in the file. If such recovery is not possible, **gif2afp** attempts to recover with the next input file. In both cases, a warning message is issued. Errors and warnings are output to standard error.

For example, let a directory tFiles contain files file1.gif, file1.txt, file2.gif and file3.gif, where file1.txt is an ASCII file. Invoking the transform via gif2afp tFiles

processes the bilevel images in all three GIF files correctly. A warning is issued that file1.txt is not a GIF file.

Non-fatal errors can be made fatal by using the option **-term**, or the corresponding environment variable or configuration file entry. If **-term** is set, the transform terminates in error if it encounters an error in the GIF data stream.

Data Transformations

If the input image is grayscale or color, and the output image type is bilevel (IOCA FS10 or IM1), the transform internally scales the image to the desired size, then uses a halftoning algorithm (ordered dither, the default, or Floyd-Steinberg) to convert it to bilevel. In converting the image to bilevel, the characteristics of the output device such as dot shape and dot gain must be taken into consideration. The **-gcorr** option can be used to specify a different mapping of gray levels.

For very light or very dark images, the halftoning algorithms can be automatically recalibrated to preserve details that would be lost using the default calibration. See the **-alg** option for more information.

To maintain the image quality, scaling must be done prior to halftoning. Halftoning algorithm is very computation-intensive. Unless the images are small, **gif2afp** cannot process the color images fast enough to feed even a slow printer.

The size and position of the output image depend on several factors:

- The size specified to the transform
- The form map specified at print time
- · The forms and options loaded in the printer

If the image is too large to to fit on the page, it is trimmed to size by default. Use the **-fit scale** option to instruct the printer to scale the image to the paper size. If the paper size is not specified explicitly via the **-paper** option, the paper size defaults to US letter size (8.5 by 11 inches). If the image is larger than this, the paper dimensions are increased as necessary. If the paper size is specified explicitly, it is not increased if the image does not fit on paper. The options **-1** and **-w** have the same effect as **-paper**.

The size of the actual image (as opposed to the paper size) is controlled by the **-scale** option. You can either specify a value of **orig** for the **-scale** option or give an actual size. If you specify **orig**, the output image is the same size as the input image. If you specify **-scale** with an actual size, the output image is scaled to the desired size. You can also specify a percentage for enlargement or reduction.

Even if you specify **-scale orig**, the image may still have to be scaled if the input file specifies non-square pixels. By default, the transform leaves scaling to the printer. The exceptions are:

- Images that are being halftoned, which are always scaled in the transform,
- Images that have different resolutions in X and Y directions (non-square pixels)

Note: Because GIF files do not specify resolutions, the image is assumed to have the resolution of the output device.

You can use the -alg option to instruct the transform to perform internal image scaling. Options -alg, -clean, and -ink choose and configure various scaling algorithms.

GIF images are compressed using the LZW algorithm. Because LZW compression is not part of any current IOCA function set, gif2afp always reads and decompresses the image.

Parameters

gif2afp behavior is governed by many parameters. The parameters are set by the following hierarchy (least significant first):

- · Internal defaults
- Environment variables
- Configuration file
- Command-line arguments

Command Line Arguments

Note the following points regarding the command line arguments for the gif2afp transform:

- Options and input file names can appear on the command line in any order.
- When you run gif2afp as a standalone transform, the blank between option and value is optional (for example, both -inkblack and -ink black are valid).
- When you use the **-o** flag of the **enq**, **lp**, **qprt**, or **lprafp** commands to pass options to gif2afp, no blank is permitted between option and value is optional (for example, -o-inkblack is valid, but -o -ink black is not).
- When you use the **other-transform-options** attribute on the **pdpr** command to pass options to gif2afp, any string containing a blank must be surrounded by single quotes (for example, both other-transform-options=-inkblack and other-transform-options='-ink black' are valid).
- All values except file names are case-insensitive.
- If an option is specified multiple times, the last specification remains in force.
- If multiple configuration file names are given, they are processed in order.

Configuration File

The configuration file has entries of the form option=value, where each pair must reside on a separate line. Options and other syntax are the same as for the command line arguments and the option names are the same. Input files and configuration files cannot be specified in the configuration file (that is, nested configuration files are not supported). In the case of options without values (for example, -inv), the equals sign must be present.

Some command line options, for example, -calib, cannot be used in the configuration file or as environment variables. Options available only on the command line are noted as such in their descriptions.

If you do not specify a configuration file on the command line with the **-C** option, the transform checks for the existence of the default configuration file, **/usr/lpp/psf/gif2afp/gif2afp.cfg**. If this file exists, the transform uses it as the configuration file.

The following is an example of a valid configuration file:

```
scale = letter
r= 300
o = -
inv=
alg=afp
```

Note that the spaces around the equals sign (=) are optional. In this example, the option-value pair o = - means that the default output file is the standard output. Output file name computation has been disabled.

Environment Variables

Environment variables have the form **GIF2AFP**_option, where option is the same as on the command line and the configuration file.

Some command line options, for example, **-calib**, cannot be used in the configuration file or as environment variables. Options available only on the command line are noted as such in their descriptions.

For example, to achieve the same effect as the configuration file in the last example, the following statements have to be executed in the calling shell:

```
export GIF2AFP_scale=letter
export GIF2AFP_r=300
export GIF2AFP_o=-
export GIF2AFP_inv=" "
export GIF2AFP_alg=afp
```

There must be some value set for each desired option. For options that do not take a value, specify a blank surrounded by double quotes, for example:

```
export GIF2AFP_inv=" " correct
export GIF2AFP inv= has no effect
```

Resource Search Path

For resource files, such as scan offset files and grayscale correction files, the transform searches the current directory by default. You can use the **-respath** option to specify a list of directories to be searched for such files. This resource path does not apply to the configuration file.

Limitations

- Timing data from GIF animation sequences is ignored.
- · Animation sequences are processed as unrelated images.

Acknowledgments

This software is partially based on the Independent JPEG Group's JPEG compression and decompression code.

Options and Values

@FileList

Specifies a name of a file that contains a list of files to be processed by the transform. If the @ option is present, the output file defaults to standard

output, even if the list of files contains only a single entry. Multiple @ options are allowed. Also see the **-f** and **-z** options. The @ is not preceded by the dash, and is implemented to maintain compatibility with the **ps2afp** transform.

-a {ioca | ioca10 | ioca11 | im1 | PS.2}

-a {IO1_G4 | IM1 | IO1 | IO1_MMR | PSEG_IO1_G4 | PSEG_IM1 | PSEG_IO1 | PSEG_IO1_MMR | OVLY_IO1_G4 | OVLY_IM1 | OVLY_IO1 | OVLY_IO1_MMR}

Choice of the output image type. The first syntax chooses between the IOCA FS 10 (ioca, ioca10), IOCA FS11 (ioca11), IM1, and PostScript Level 2 (PS.2) output. IOCA FS10 and IM1 yield bilevel images, while IOCA FS11 results in 4-bit or 8-bit gray or 24-bit color output (see option -outbits). Note that presently the only product that supports IOCA FS11 is the AFP Workbench. The output compression algorithm is set via the option -cmp. To set the page type (page, overlay, page segment or object), use the -pagetype option.

The second syntax is to maintain compatibility with the ps2afp transform, and sets the image type (IO1 for IOCA FS10 or IM1 for IM1 output), compression (G4 for Group 4 or MMR for Group 3), and page type (PSEG for page segment or OVLY for overlay). If PSEG or OVLY is not specified, the output is a printable page. If no compression algorithm is specified, the output is not compressed. The second syntax cannot be used for IOCA FS11 output.

Some older printers do not support IOCA images. In such cases, the IM1 output type should be chosen. IM1 images are uncompressed and thus use more space. The processing might also take longer since the IM1 image cannot be scaled by the printer and so internal scaling algorithms must be used. See option -alg.

The default is **ioca** for IOCA FS10 output compressed via Group 4 algorithm.

This option is similar to the **image-out-format** document attribute on the **pdpr** command.

-alg {afp | alg1 | alg2 | alg3}

-alg {htod1 | htfs}

-alg htcal1

Choice of the scaling and halftoning algorithms. You can specify multiple choices, separated by commas, for one **-alg** option. The effect is the same as specifying multiple **-alg** options. For example, **-alg** htfs,htcal is equivalent to **-alg** htfs **-alg** htcal.

The scaling algorithms are:

- If **afp** is chosen, the scaling is done using the default algorithm in the printer. This makes the transform much faster. If the image must be reduced, however, this algorithm may drop some information from the image, such as thin lines.
- **alg1** activates the internal scaling algorithm to scale the image explicitly to the specified size. This algorithm is guaranteed not to discard any ink. "White space" in the image, however, may be lost (that is, features close

to one another might merge). This algorithm makes the transform run longer, and might occasionally make for a "dirty" image, since the occasional "noise pixels" in the scanned images tend to be amplified.

- alg2 activates the more flexible version of alg1. If this algorithm is selected, option -clean can be used to specify the amount of ink "cleanup" to be performed. Option -clean 0.0 makes the algorithm alg2 perform like alg1 (albeit more slowly). Increasing the value specified in -clean discards more and more ink, until -clean 1.0 results in a blank page.
- alg3 activates a scaling algorithm that works by deleting or duplicating rows and columns in the image. This is a fast general-purpose algorithm.

For bilevel images, the default is **afp** if the output image type is IOCA and **alg3** if the output image type is IM1. For color images with bilevel output, the scaling is always done prior to the halftoning algorithm. If a grayscale or color output is chosen (**-a ioca11**), this option is ignored and the algorithm is set to **afp**.

The halftoning algorithms are:

- **htod1** uses an ordered dither with a screen derived from the value of the **-thresh** option. The default is an 85 line per inch screen.
- htfs uses the Floyd-Steinberg algorithm.
- htcal1 recalibrates the halftoning algorithm for each image. htcal1 forces
 the transform to read the whole image into memory and requires an
 additional pass through the image. It should be used only for very light
 or very dark images.

The default is **htod1**. Each halftoning algorithm uses a different internal default calibration curve. If the automatic calibration is turned on, a still different set of calibration curves are used.

See options -clean, -gcorr, -ink, -paper, -scale, -thresh, -l, -w, -x, and -y.

-calib scanner

-calib {scanner | printer | patch | patchr},name1...

Transform calibration for the scanner or printer. If **scanner** is specified, **-sgcorr** must be present. If **printer** is specified, **-sgcorr** may or may not be present. If **patch** or **patchr** is specified, **-sgcorr** (if present) is ignored. Detailed explanation of the calibration process is beyond the scope of this entry.

You cannot specify **-calib** in the configuration file or as an environment variable.

-C *ConfigurationFileName*

The name of a configuration file containing option-value pairs. If multiple -C options are given on the command line, they are processed in order. Specifying the configuration file on the command line overrides any specification done via the GIF2AFP_C environment variable.

The default configuration file is /usr/lpp/psf/gif2afp/gif2afp.cfg.

-clean $\{0.5 \mid x.xxx\}$

The internal scaling algorithm alg2 allows for variable thresholding. The scaled pixel is declared painted if the fraction of its area greater than the

threshold is painted in the original image. The value x.xxx is a real number between zero and 1 inclusive and gives this threshold.

If the option **-clean 0.0** is issued, **alg2** behaves like **alg1** and turns on a pixel as long as any part of the pixel has been painted in the original image. **-clean 1.0** results in a blank image because the output pixels are never painted.

Note that setting **-clean 0.95** and **0.9999999** turns on the pixels that had essentially all the area painted in the original picture. Depending on the data, most of the image will probably be preserved. Increasing **-clean** by a small amount to **1.0** erases the image. If the scaling algorithm is not **alg2**, this option is ignored. The default is **-clean 0.5**.

-cmp {none | mh | mmr | g3 | g4 | jpeg}

Choice of the output image compression algorithm:

none Uncompressed output

mh ITU-T T.4 G3 Modified Huffman

mmr IBM Modified Modified Read

g3 ITU-T T.4 G3 Modified Read

g4 ITU-T T.6 G4

jpeg JPEG non-differential Huffman coding with baseline DCT. The output image data should be compressed to reduce the file sizes and increase the printing speed.

The default compression is ITU-T T.6 Group 4 for bilevel images and no compression for grayscale or color images. Note that some printers may not support Group 4 compression algorithm and require using the **-cmp** option to choose a different one. The JPEG algorithm can compress only 8-bit grayscale and 24-bit color images. 4-bit grayscale images cannot be compressed.

-crop $t,b,l,r[i \mid m \mid p \mid d]$

Image cropping. *t,b,l,r* specify how much should be cropped from the image top, bottom, left edge, and right edge. The numbers are floating point and can be either positive or negative. Negative numbers indicate that a blank space should be inserted. The units are inches, millimeters, points, and dots (pels), with the default being dots. The cropping is specified in the context of the output page, to that "top" means the top of the output page and so on, regardless of the **-rot** option. To crop, the transform will enlarge the image by the amount to be cropped, then crop the specified amount by manipulating the actual bitmap. The resulting image has the size as specified by the explicit (or implicit) **-scale** option. See also option **-j**.

If **-fit trim** is specified, the right and the bottom edge of the image are not cropped. Instead, the image grows as necessary. Because **-fit trim** causes the output data stream to contain the "position and trim" specification, the printer discards any extra image.

-f FileList

Specifies the name of a file that contains a list of files to be processed by the transform. If the **-f** option is present, the output file defaults to standard output, even if the list of files contains only a single entry. Multiple **-f** options are allowed. See also options @ and **-z**.

-fit {trim | scale}

Determines whether the printer behavior will be position-and-trim or scale-to-fit if the image is too large to fit on the paper. The default is **trim**.

This option is equivalent to the **image-fit** document attribute on the **pdpr** command.

-gcorr FileName

Specifies a file with grayscale mapping table for halftoning of the grayscale and color images to bilevel for output. The mapping table must be provided to compensate for the printing characteristics of the particular output device and paper type, such as dot gain. This file must contain either:

- 256 real numbers, one for each level of gray in the 8-bit grayscale image
- The PostScript **settransfer** operator

The algorithm converts every image to 8-bit grayscale before applying the halftoning algorithm. The default internal mapping table has been optimized for the 600-pel IBM Infoprint 4000 laser printer. You shouldn't change this unless you know what you are doing. See also options -alg and -thresh. PostScript code submitted via the -thresh option can have the same effect as -gcorr.

-ink {black | white}

This option is used only with scaling algorithm alg1 or alg2. The GIF images can be either black on white or white on black. The internal scaling algorithm must know which, because "ink" is preserved at the expense of "non-ink" The default value, "black", indicates that the image is black on white.

If the option **-inv** is used to print the reversed image, the inversion is done as the data is read by the transform, before any processing is done. The black or white must thus be specified in the terms of the printed image, not in the terms of the input GIF image.

-inv Reverses the image. Areas that are black in the original image become white and vice versa. Note that the reversed image may be either black on white or white on black, depending on the original image.

-j ScanOffsetFileName

Sometimes input images must be shifted to get the desired positioning on the page. The scan offset file contains the directions for shifting. The file has the format of

```
[attribute]
values
:
values
[attribute]
values
:
values
:
values
```

Currently, the recognized attributes are [Units] (values millimeters, mm, inches, in, points, dots, pels) [Page_Offset_Type] (values crop or grow) and [Page_Offsets]. The values for page offsets are in the format FileName,Hhoriz,Vvert Each entry refers to a file. The file names must be specified (or at least the leading comma must), but are currently ignored and the offset factors are applied to each file in turn. Note that the same factors are applied to each image in the file. The horiz and vert values are the amount that the image is to be shifted, in the horizontal and vertical

direction. The positive directions are down and right (that is, the origin is in the left upper corner of the page). The default units are millimeters. Like the values for the **-crop** option, the shifts are specified in the output space context.

Extra spaces and blank lines are allowed. Unrecognized attributes and their values are ignored. See the sample file **shift.sample**.

If the image is moved left or up, part of the bitmap is removed. If the image is moved down or right, removal is governed by the value of the [Page_Offset_Type] attribute. If crop is chosen, the transform removes the requisite amount from the right and bottom edges of the bitmap. If grow is chosen, the transform does not remove any space. The bitmap grows and the trimming, if any, is left to the printer. If the -fit trim option (the default) is specified, [Page_Offset_Type] defaults to grow. For -fit scale, [Page_Offset_Type] defaults to crop.

- $l \{11i \mid yyy.yy[d \mid m \mid i \mid p]\}$

Specifies the paper length. The optional units are dots (pels), millimeters, inches, or points. The default unit is dots. If the unit is dots, decimals (if any) are ignored. The default paper length is 11 inches. See options -w to set the paper width or **-paper** to set both dimensions at the same time.

-M {0 | nnn}

Limits the amount of memory available to gif2afp. nnn is the maximum amount of memory in kilobytes. A value of 0 means there is no memory limit. nnn can be set from 0 to the maximum value that AIX allows. The default is **0**.

-ms {10 | nnn}

Requires that at least *nnn* kilobytes of disk space be available on the file system that contains the output file. This limit is enforced every time data is written to the output file. If the output is standard output, this option is ignored. The default is 10. See option -msf.

-msf $\{0.1 \mid x.xxx\}$

The number x.xxx is a real number between 0 and 1. It denotes the minimum space that must be left unused on the file system containing the output file. The space is given as a fraction of the total space in the file system. This limit is enforced every time data is written to the output file. If the output is standard output, this option is ignored. The default is **0.1**. See option **-ms**.

-nosniff

See [-sniff | -nosniff].

-noterm

See [-term | -noterm].

-nov See $[-v \mid -nov]$.

-o FileName

Optional output file name. Specify - for standard output.

-outbits NumberOfOutputBits

Sets the number of bits per pel in output. This value must be 1, 4, 8, or 24. If the output image type is IOCA FS10 or IM1, the number of output bits is set to 1 and this option is ignored. For IOCA FS11 output, the default is 24. Note that this number represents the maximum number of bits used per pel. Thus, even if the number of bits is set to **24**, a 4-bit grayscale image is still displayed in 4-bit format.

-outcolor {rgb | ycbcr | ycrcb}

Sets the output color model to RGB, YCbCr, or YCrCb if the image type is IOCA FS11 and the number of output bits is 24. Otherwise, this option is ignored. The default is **ycbcr**.

-p {**even** | **odd** | *nn* | *nn-mm* | *nn-*}

Specifies that the output should only contain the specified pages. If no **-p** option is given, all the pages are output. Multiple **-p** options may be specified. Their effect is cumulative. Regardless of the order in which the pages are specified, they are always printed in ascending order. The recognized values are:

even Print all even pagesodd Print all odd pagesnn Print page nnnn-mm Print pages nn to mm, inclusive.

nn- Print all pages starting with page *nn*

Pages are numbered starting with 1.

-pagetype {page | overlay | ovly | pseg | object}

Sets the output page type to be page, overlay, page segment or object. The same page type is set for every page in the output. Thus, unless option -p is used to select a single page, multiple overlays, page segments or overlays are stored in the output file. The default is page. See option -a.

-paper {a5 | a4 | a3 | letter | folio | legal | ledger | xxx.xx,yyy.yy[d | m | i | p]} Specifies the output paper size. The supported values are:

a3 A3 format (297 by 420 mm or 11.69 by 16.54 inches)

a4 A4 format (210 by 297 mm or 8.27 by 11.69 inches)

a5 A5 format (148 by 210 mm or 5.83 by 8.27 inches)

letter 8.5 by 11 inches (216 by 279 mm)

folio 8.5 by 13.0 inches (216 by 330 mm)

legal 8.5 by 14.0 inches (216 by 356 mm)

ledger 11.0 by 17.0 inches (279 by 432 mm)

$xx.xx,yy.yy[\mathbf{d} \mid \mathbf{m} \mid \mathbf{i} \mid \mathbf{p}]$

Horizontal and vertical page dimensions. The optional units are dots (pels), millimeters, inches, or points.

The default paper size is letter. If **-paper** is not used, the paper size is increased, if necessary, to contain the output image.

See options -1, -w, and -scale.

-r {300 | *nnn*}

The output device resolution, specified in dots per inch. The default is 300.

This option is equivalent to the **default-printer-resolution** document attribute on the **pdpr** command.

-respath directory[:directory...]

Sets the search path for resource files, such as the scan offset files and

grayscale calibration curve files. If a resource file name is specified as a relative name (does not start with a /), the transform searches every directory in the path, in the order specified in the path, until it finds the file (or fails). See options -j and -gcorr for scan offsets and grayscale calibration curve. The default is the current directory.

-rot $\{0 \mid 90 \mid 180 \mid 270[p \mid i]\}$

The image is rotated in the clockwise direction by the amount specified. The default is zero, that is, no rotation.

If \mathbf{p} is specified, the transform sets the output datastream in such a way that the printer performs the actual image rotation. If \mathbf{i} is specified, the transform rotates the output bitmap. When \mathbf{i} is chosen, the transform takes much longer to run and uses much more memory. If no letter is specified, the default or any previous value (such as the value specified in the configuration file) remains in force. The default is \mathbf{p} .

-scale {orig | a5 | a4 | a3 | letter | folio | legal | ledger | $xxx.xx,yyy.yy[\underline{d} \mid m \mid i \mid p] \mid xxx\%$ }

Specifies the output image size. The image is scaled to this size and centered in the area defined by the paper size and margin options. The supported values are:

orig	Preserve the input image size, regardless of the printable paper
	area

a3 A3 format (297 by 420 mm or 11.69 by 16.54 inches)

a4 A4 format (210 by 297 mm or 8.27 by 11.69 inches)

a5 A5 format (148 by 210 mm or 5.83 by 8.27 inches)

letter 8.5 by 11 inches (216 by 279 mm)

folio 8.5 by 13.0 inches (216 by 330 mm)

legal 8.5 by 14.0 inches (216 by 356 mm)

ledger 11.0 by 17.0 inches (279 by 432 mm)

$xx.xx,yy.yy[\mathbf{d} \mid \mathbf{m} \mid \mathbf{i} \mid \mathbf{p}]$

Horizontal and vertical image dimensions. The optional units are dots (pels), millimeters, inches, or points.

xxx% Magnification relative to the original image size. Numbers below 100% mean reduction, while Numbers above 100% mean enlargement. For example, **-scale 200%** causes the output image to be twice as long and twice as wide as the input image.

The default image size is **orig**.

-sgcorr FileName

Specifies the name of the scanner-related calibration file. If **-calib** is absent, this option is ignored.

A detailed discussion of **-sgcorr** is beyond the scope of this document.

[-sniff | -nosniff]

Turns automatic conversion to black on white for bilevel images on (-sniff) or off (-nosniff). The automatic conversion algorithm counts the number of 0 and 1 bits in the image. If there are fewer zeros, it assumes the printed features are represented by zeros (white on black), and inverts the image to

be black on white. The detection and conversion are done after the conversion specified by the Photometric Interpretation tag is applied (if any).

This option is ignored if the image is not bilevel. The default is **-nosniff**.

[-term | -noterm]

Disables (-term) or enables (-noterm) error recovery.

- When error recovery is disabled, on encountering an error in a GIF file, the transform terminates with an error message and a nonzero return code.
- When error recovery is enabled, the errors in GIF files are treated as non-fatal. The transform attempts to recover with the next image in the file, or with the next file. The return code is zero.

The default is **-noterm**.

-thresh FileName

Specifies a file that contains a PostScript Type 1 or Type 3 halftone dictionary. Alternatively, the PostScript code can specify the **setscreen** operator instead of a Type 1 dictionary. The halftone cell in the dictionary is used to overwrite the default ordered dither clustered dot halftone cell. If the PostScript code contains a transfer function, either in the halftone dictionary or specified by the **settransfer** operator, the current grayscale correction curve is overwritten as if **-gcorr** were used.

[-v | -nov]

Turns verbose mode on (-v) or off (-nov).

- When verbose mode is on, the transform prints a message as it opens each resource file, then echoes the command line, then prints a message for each file name as it is processed.
- When verbose mode is off, the transform prints only error messages.

The default is **-nov**.

-w $\{8.5i \mid yyy.yy[d \mid m \mid i \mid p]\}$

Specifies the paper width. The optional units are dots (pels), millimeters, inches, or points. The default unit is dots. The default page width is 8.5 inches. See options -1 to set the paper length or -paper to set both dimensions at the same time.

$-x \{0 \mid nnn.nn[d \mid m \mid i \mid p]\}$

Specifies the left margin. The optional units are dots (pels), millimeters, inches, or points. The default unit is dots. The default is zero (no margin).

$-y \{0 \mid nnn.nn[d \mid m \mid i \mid p]\}$

Specifies the top margin. The optional units are dots (pels), millimeters, inches, or points. The default unit is dots. The default is zero (no margin).

-z Signifies that a list of files to be processed is submitted from standard input. See also options -f and @.

jpeg2afp Command: Transforms JPEG Data to AFP in Infoprint Manager for AIX

Syntax

```
jpeg2afp [-a ImageType] [-alg ProcessingAlgorithms]
         [-calib calibration] [-C ConfigurationFile]
         [-cmp compression] [-crop CropFactors]
         [-fit {trim | scale}] [-force]
         [-gcorr GrayscaleMappingTable]
         [-i ScanOffsetFileName] [-1 ImageLength]
         [-M MemoryBound] [-ms space] [-msf SpaceFraction]
         [-o OutputFile] [-outbits NumberOfOutputBits]
         [-outcolor OutputColorModel] [-p PageRange]
         [-pagetype PageType] [-paper PaperSize]
         [-r resolution] [-respath ResourceSearchPath]
         [-rot rotation] [-scale ImageSize]
         [-sgcorr ScannerCorrection] [-term | -noterm]
         [-thresh HalftoneFile] [-v | -nov]
         [-w ImageWidth] [-wrkdir WorkDirectory]
         [-x LeftMargin] [-y TopMargin] [-z]
         [[file | directory | -f FileList | @FileList]...]
```

Description

The **jpeg2afp** command transforms a JPEG (Joint Photographic Experts Group) data stream into an AFP (MO:DCA-P) or PostScript Level 2 data stream file.

The transform can process images compressed using baseline lossy JPEG compression. Only 8 bits per channel and Huffman coding are supported. The output can be bilevel (IM1 or IOCA FS10), 4-bit or 8-bit grayscale, or 24-bit YCbCr color (IOCA FS11). The transform automatically uses halftoning to convert the grayscale and color images to bilevel.

Automatic Invocation

The PSF DSS automatically invokes the <code>jpeg2afp</code> transform command whenever you submit a JPEG file for printing. You can pass options to <code>jpeg2afp</code> using the <code>other-transform-options</code> attribute on the <code>pdpr</code> command or the <code>-o</code> flag of the AIX print commands and the <code>lprafp</code> command.

Input and Output

jpeg2afp can process either standard input, or multiple files specified on the command line. If no input file is specified, **stdin** is assumed. Standard input is cached to a file (see the **-wrkdir** option) and then processed. Only a single JPEG file should be submitted via **stdin**. If multiple JPEG files are concatenated via standard input, all except the first one are ignored.

If an input file is specified on the command line, it can be either a JPEG file, a directory, or a file list (-f and @ prefixes). Multiple input file specifications are allowed. The transform processes each file in the order in which it was specified on the command line. If the -z option is specified, a list of file names to be processed is also submitted via standard input. The files on the list are processed as if the list were given via the -f option on the same place on the command line as -z.

If the file name points to a directory, **jpeg2afp** processes every file in that directory. The files are processed in the order they would be shown using the **ls -a** command. Directory search is not recursive, that is, the subdirectories are not searched.

If the file name is preceded by the **-f** option or the at sign (@), **jpeg2afp** assumes that the file contains the list of JPEG files to be processed. Each of the files in the list is processed in the order it was listed.

If a JPEG file has the extension .jpg, .jpeg, .JPG, or .JPEG, this extension need not be given explicitly. jpeg2afp first tries to open the file as specified and, if unsuccessful, tries to append the extensions .jpg .jpeg, .JPG, and .JPEG in turn.

For example, suppose that:

- The directory tFiles contains the files file1.jpg, file2.jpg, file3.jpg, and file4.jpg and nothing else.
- The file flist in the current directory contains the two file names tFiles/file2.jpg and tFiles/file3.jpg. The names listed in the file list may have their extensions omitted.
- The file flist2 contains the file name tFiles/file4. Again, the names listed in the file list may have their extensions omitted.

In order to process files file1.jpg, file2.jpg, file3.jpg, and file4.jpg, any of the following invocations of **jpeg2afp** would work:

```
jpeg2afp tFiles/file1.jpg tFiles/file2.jpg tFiles/file3.jpg tFiles/file4.jpg
jpeg2afp tFiles/file1 tFiles/file2 tFiles/file3 tFiles/file4
jpeg2afp tFiles/file*.jpg
jpeg2afp tFiles
jpeg2afp tFiles/file1 -fflist tFiles/file4
jpeg2afp tFiles/file1 -f flist tFiles/file4
jpeg2afp tFiles/file1 -f flist tFiles/file4
jpeg2afp tFiles/file1 -f flist -f flist2
jpeg2afp tFiles/file1 @flist @flist2
```

The file list files allow the display text to be added for each file. A display text is any text starting with the pound character (#) and extending to the end of the line. The display text should follow the file name, and can extend over several lines, up to 2048 characters long. The initial # character on each line is discarded. If a display text is present for a file name, that text is displayed in the status and error messages instead of the file name. This is useful if the <code>jpeg2afp</code> is invoked using temporary files whose names are meaningless to the user. Any display text before the first file name is treated as comment and discarded. Display text is allowed also if the <code>-z</code> option is used to submit the file list via standard input.

The output file name can be either specified explicitly via the -o option, or derived from the input file name. If multiple input files have been specified, the default output file is standard output. If a single input file is given and the output file is not specified explicitly, the transform strips the .jpg or .jpeg extension from the input file name (if one is present), and appends the .afp extension for AFP output, or the .ps extension for PostScript output, to get the output file name.

To disable automatic output file name generation and force the default output stream to be the standard output in all cases, set the environment variable <code>JPEG2AFP_o</code> to - or <code>stdout</code>, or, alternatively, put the line <code>o=-</code> or <code>o=stdout</code> into the configuration file and invoke that configuration file using the -C option or the <code>JPEG2AFP_C</code> environment variable.

jpeg2afp

For example, all the following commands:

```
jpeg2afp myfile
jpeg2afp myfile.jpg
jpeg2afp myfile -o myfile.afp
```

have myfile.afp as the output file. Note that there is no requirement for the explicitly specified input and output files to have .jpg and .afp extensions. To process JPEG file foo.bar into an AFP file foo.bar2, invoke the transform using jpeg2afp foo.bar -o foo.bar2

The output data stream is MODCA-P IS/1, MODCAP-P IS/2, or PostScript Level 2. IS/1 images are bilevel and are encoded as IOCA Function Set 10 or IM1. IM1 images are uncompressed. IOCA FS10 output images can be either uncompressed, or compressed via one of the four available compression algorithms (see the **-cmp** option). The default is ITU-T T.6 Group 4 compression. IM1 images are always uncompressed. IS/2 images can be either bilevel, 4-bit or 8-bit grayscale, or 24 bit YCbCr color. Multibit images are encoded as IOCA Function Set 11. Be aware that the only product that supports IOCA FS11 images is the AFP Workbench, that is, grayscale and color AFP images are not currently supported by any printer.

PostScript Level 2 images can be uncompressed or ITU-T T.6 Group 4 bilevel, uncompressed 8-bit grayscale or uncompressed 24-bit RGB color. By default, the transform leaves scaling and halftoning to the printer (that is, color JPEG images are output as 24-bit RGB color images).

Errors and Error Recovery

jpeg2afp divides errors into fatal and non-fatal. The fatal error categories are the following:

- Errors in the user-specified parameters, either in the environment variables, the
 configuration file, or the command line arguments. These errors include
 unrecognized options, invalid values for parameters, or inability to open the
 configuration file or the output file.
- Out of memory errors. The requested memory is larger than the memory specified using the **-M** option or the dynamic memory allocation has failed.
- Disk space errors. The transform guards against trying to write to a full file system. See the -ms and -msf options for setting the minimum free disk space requirements. If the file system is full, the transform deletes the partial output file before terminating.
- · Internal errors.

In the case of a fatal error, the last output page might not be complete.

Errors encountered in the JPEG files are non-fatal and <code>jpeg2afp</code> attempts to recover from them. These errors include not being able to open an input file, an input file not being a JPEG file, or an input file containing features that cannot be processed. If the transform fails to open 15 or more input files, it assumes an error in the parameter list (for example, <code>-f</code> was used with a file that does not contain a file list) and terminates.

If an error is encountered in a file, the transform attempts to recover with the next input file. A warning message is issued. Errors and warnings are output to standard error.

For example, let a directory tFiles contain files file1.jpg, file1.txt, file2.jpg and file3.jpg, where file1.txt is an ASCII file. Invoking the transform via

jpeg2afp tFiles

processes the bilevel images in all three JPEG files correctly. A warning is issued that file1.txt is not a JPEG file.

Non-fatal errors can be made fatal by using the option **-term**, or the corresponding environment variable or configuration file entry. If **-term** is set, the transform terminates in error if it encounters an error in the JPEG data stream.

Data Transformations

If the input image is grayscale or color, and the output image type is bilevel (IOCA FS10 or IM1), the transform internally scales the image to the desired size, then uses a halftoning algorithm (ordered dither, the default, or Floyd-Steinberg) to convert it to bilevel. In converting the image to bilevel, the characteristics of the output device such as dot shape and dot gain must be taken into consideration. The **-gcorr** option can be used to specify a different mapping of gray levels.

For very light or very dark images, the halftoning algorithms can be automatically recalibrated to preserve details that would be lost using the default calibration. See the **-alg** option for more information.

To maintain the image quality, scaling must be done prior to halftoning. Halftoning algorithm is very computation-intensive. Unless the images are small, **jpeg2afp** cannot process the color images fast enough to feed even a slow printer.

The size and position of the output image depend on several factors:

- The size specified to the transform
- The form map specified at print time
- The forms and options loaded in the printer

If the image is too large to to fit on the page, it is trimmed to size by default. Use the **-fit scale** option to instruct the printer to scale the image to the paper size. If the paper size is not specified explicitly via the **-paper** option, the paper size defaults to US letter size (8.5 by 11 inches). If the image is larger than this, the paper dimensions are increased as necessary. If the paper size is been specified explicitly, it is not increased if the image does not fit on paper. The options **-1** and **-w** have the same effect as **-paper**.

The size of the actual image (as opposed to the paper size) is controlled by the **-scale** option. You can either specify a value of **orig** for the **-scale** option or give an actual size. If you specify **orig**, the output image is the same size as the input image. If you specify **-scale** with an actual size, the output image is scaled to the desired size. You can also specify a percentage for enlargement or reduction.

By default, the transform leaves scaling to the printer. The exceptions are images that are being halftoned, which are always scaled in the transform.

Note: Because JPEG files do not specify resolutions, the image is assumed to have the resolution of the output device.

If possible, jpeg2afp rewraps the JPEG raster data in MODCA-P headers.

For 8-bit grayscale and 24-bit color images, both JPEG and IOCA FS11 support JPEG compression algorithms. However, the JPEG standard has different

jpeg2afp

subsampling defaults than IOCA FS11. Thus, most 24-bit color images are not suitable for rewrapping, even if they use a JPEG compression algorithm and a color model supported by IOCA FS11.

Note also that JPEG is a lossy compression algorithm. Decompressing a JPEG image and then recompressing it for output might result in reduced image quality. For that reason, the default is to use no compression for the gray or color output.

Be aware that not all the printers support all the recognized IOCA compression standards. If the output image is IM1, the image is always decompressed and scaled in the transform.

Parameters

jpeg2afp behavior is governed by many parameters. The parameters are set by the following hierarchy (least significant first):

- Internal defaults
- Environment variables
- Configuration file
- · Command-line arguments

Command Line Arguments

Note the following points regarding the command line arguments for the **jpeg2afp** transform:

- Options and input file names can appear on the command line in any order.
- When you run **jpeg2afp** as a standalone transform, the blank between option and value is optional (for example, both -fittrim and -fit trim are valid).
- When you use the **-o** flag of the **enq**, **lp**, **qprt**, or **lprafp** commands to pass options to **jpeg2afp**, no blank is permitted between option and value is optional (for example, **-o-fittrim** is valid, but **-o-fittrim** is not).
- When you use the **other-transform-options** attribute on the **pdpr** command to pass options to **jpeg2afp**, any string containing a blank must be surrounded by single quotes (for example, both other-transform-options=-fittrim and other-transform-options='-fit trim' are valid).
- All values except file names are case-insensitive.
- If an option is specified multiple times, the last specification remains in force.
- If multiple configuration file names are given, they are processed in order.

Configuration File

The configuration file has entries of the form *option=value*, where each pair must reside on a separate line. Options and other syntax are the same as for the command line arguments and the option names are the same. Input files and configuration files cannot be specified in the configuration file (that is, nested configuration files are not supported). In the case of options without values (for example, -v), the equals sign must be present.

Some command line options, for example, **-calib**, cannot be used in the configuration file or as environment variables. Options available only on the command line are noted as such in their descriptions.

If you do not specify a configuration file on the command line with the **-C** option, the transform checks for the existence of the default configuration file, <code>/usr/lpp/psf/jpeg2afp/jpeg2afp.cfg</code>. If this file exists, the transform uses it as the configuration file.

The following is an example of a valid configuration file:

```
scale = letter
r= 300
o = -
v=
```

Note that the spaces around the equals sign (=) are optional. In this example, the option-value pair o = - means that the default output file is the standard output. Output file name computation has been disabled.

Environment Variables

Environment variables have the form **JPEG2AFP_***option*, where *option* is the same as on the command line and the configuration file.

Some command line options, for example, **-calib**, cannot be used in the configuration file or as environment variables. Options available only on the command line are noted as such in their descriptions.

For example, to achieve the same effect as the configuration file in the last example, the following statements have to be executed in the calling shell:

```
export JPEG2AFP_scale=letter
export JPEG2AFP_r=300
export JPEG2AFP_o=-
export JPEG2AFP_v=" "
```

There must be some value set for each desired option. For options that do not take a value, specify a blank surrounded by double quotes, for example:

```
export JPEG2AFP_v=" " correct export JPEG2AFP_v= has no effect
```

Resource Search Path

For resource files, such as scan offset files and grayscale correction files, the transform searches the current directory by default. You can use the **-respath** option to specify a list of directories to be searched for such files. This resource path does not apply to the configuration file.

Limitations

- Only Huffman coding with baseline DCT JPEG algorithm is supported.
- At most 8-bit grayscale and 24-bit color are supported.

Acknowledgments

This software is partially based on the Independent JPEG Group's JPEG compression and decompression code.

Options and Values

```
@FileList
```

Specifies a name of a file that contains a list of files to be processed by the transform. If the @ option is present, the output file defaults to standard output, even if the list of files contains only a single entry. Multiple @ options are allowed. Also see the -f and -z options. The @ is not preceded by the dash, and is implemented to maintain compatibility with the ps2afp transform.

```
-a {ioca | ioca10 | ioca11 | im1 | PS.2}
```

-a {IO1_G4 | IM1 | IO1 | IO1_MMR | PSEG_IO1_G4 | PSEG_IM1 | PSEG_IO1 | PSEG_IO1_MMR | OVLY_IO1_G4 | OVLY_IM1 | OVLY_IO1 | OVLY_IO1_MMR}

Choice of the output image type. The first syntax chooses between the IOCA FS 10 (ioca, ioca10), IOCA FS11 (ioca11), IM1, and PostScript Level 2 (PS.2) output. IOCA FS10 and IM1 yield bilevel images, while IOCA FS11 results in 4-bit or 8-bit gray or 24-bit color output (see option **-outbits**). Note that presently the only product that supports IOCA FS11 is the AFP Workbench. The output compression algorithm is set via the option **-cmp**. To set the page type (page, overlay, page segment or object), use the **-pagetype** option.

The second syntax is to maintain compatibility with the ps2afp transform, and sets the image type (IO1 for IOCA FS10 or IM1 for IM1 output), compression (G4 for Group 4 or MMR for Group 3), and page type (PSEG for page segment or OVLY for overlay). If PSEG or OVLY is not specified, the output is a printable page. If no compression algorithm is specified, the output is not compressed. The second syntax cannot be used for IOCA FS11 output.

Some older printers do not support IOCA images. In such cases, the IM1 output type should be chosen. IM1 images are uncompressed and thus use more space. The processing might also take longer since the IM1 image cannot be scaled by the printer and so internal scaling algorithms must be used. See option -alg.

The default is ioca for IOCA FS10 output compressed via Group 4 algorithm.

This option is similar to the **image-out-format** document attribute on the pdpr command.

-alg afp

-alg {htod1 | htfs}

-alg htcal1

Choice of the scaling and halftoning algorithms. You can specify multiple choices, separated by commas, for one -alg option. The effect is the same as specifying multiple -alg options. For example, -alg htfs, htcal is equivalent to -alg htfs -alg htcal.

The scaling algorithms are:

• If **afp** is chosen, the scaling is done using the default algorithm in the printer. This makes the transform much faster. If the image must be reduced, however, this algorithm may drop some information from the image, such as thin lines.

For color images with bilevel output, the scaling is always done prior to the halftoning algorithm. If a grayscale or color output is chosen (-a **ioca11**), this option is ignored and the algorithm is set to **afp**.

The halftoning algorithms are:

- htod1 uses an ordered dither with a screen derived from the value of the **-thresh** option. The default is an 85 line per inch screen.
- htfs uses the Floyd-Steinberg algorithm.

htcal1 recalibrates the halftoning algorithm for each image. htcal1 forces
the transform to read the whole image into memory and requires an
additional pass through the image. It should be used only for very light
or very dark images.

The default is **htod1**. Each halftoning algorithm uses a different internal default calibration curve. If the automatic calibration is turned on, a still different set of calibration curves are used.

See options -gcorr, -paper, -scale, -thresh, -l, -w, -x, and -y.

-calib scanner

-calib {scanner | printer | patch | patchr},name1...

Transform calibration for the scanner or printer. If **scanner** is specified, **-sgcorr** must be present. If **printer** is specified, **-sgcorr** may or may not be present. If **patch** or **patchr** is specified, **-sgcorr** (if present) is ignored. Detailed explanation of the calibration process is beyond the scope of this entry.

You cannot specify **-calib** in the configuration file or as an environment variable.

-C *ConfigurationFileName*

The name of a configuration file containing option-value pairs. If multiple -C options are given on the command line, they are processed in order. Specifying the configuration file on the command line overrides any specification done via the <code>JPEG2AFP_C</code> environment variable.

The default configuration file is /usr/lpp/psf/jpeg2afp/jpeg2afp.cfg.

-cmp {none | mh | mmr | g3 | g4 | jpeg}

Choice of the output image compression algorithm:

none Uncompressed output

mh ITU-T T.4 G3 Modified Huffman

mmr IBM Modified Modified Read

g3 ITU-T T.4 G3 Modified Read

g4 ITU-T T.6 G4

jpeg JPEG non-differential Huffman coding with baseline DCT. The output image data should be compressed to reduce the file sizes and increase the printing speed.

The default compression is ITU-T T.6 Group 4 for bilevel images and no compression for grayscale or color images. Note that some printers may not support Group 4 compression algorithm and require using the **-cmp** option to choose a different one. The JPEG algorithm can compress only 8-bit grayscale and 24-bit color images. 4-bit grayscale images cannot be compressed.

-crop $t,b,l,r[i \mid m \mid p \mid d]$

Image cropping. *t*,*b*,*l*,*r* specify how much should be cropped from the image top, bottom, left edge, and right edge. The numbers are floating point and can be either positive or negative. Negative numbers indicate that a blank space should be inserted. The units are inches, millimeters, points, and dots (pels), with the default being dots. The cropping is

specified in the context of the output page, to that "top" means the top of the output page and so on, regardless of the **-rot** option. To crop, the transform will enlarge the image by the amount to be cropped, then crop the specified amount by manipulating the actual bitmap. The resulting image has the size as specified by the explicit (or implicit) **-scale** option. See also option **-j**.

If **-fit trim** is specified, the right and the bottom edge of the image are not cropped. Instead, the image grows as necessary. Because **-fit trim** causes the output data stream to contain the "position and trim" specification, the printer discards any extra image.

-f FileList

Specifies the name of a file that contains a list of files to be processed by the transform. If the **-f** option is present, the output file defaults to standard output, even if the list of files contains only a single entry. Multiple **-f** options are allowed. See also options @ and **-z**.

-fit {trim | scale}

Determines whether the printer behavior will be position-and-trim or scale-to-fit if the image is too large to fit on the paper. The default is **trim**.

This option is equivalent to the **image-fit** document attribute on the **pdpr** command.

-force If present, this option forces **jpeg2afp** to decompress and recompress the image, regardless of other factors.

-gcorr FileName

Specifies a file with grayscale mapping table for halftoning of the grayscale and color images to bilevel for output. The mapping table must be provided to compensate for the printing characteristics of the particular output device and paper type, such as dot gain. This file must contain either:

- 256 real numbers, one for each level of gray in the 8-bit grayscale image
- The PostScript **settransfer** operator

The algorithm converts every image to 8-bit grayscale before applying the halftoning algorithm. The default internal mapping table has been optimized for the 600-pel IBM Infoprint 4000 laser printer. You shouldn't change this unless you know what you are doing. See also options **-alg** and **-thresh**. PostScript code submitted via the **-thresh** option can have the same effect as **-gcorr**.

-j ScanOffsetFileName

Sometimes input images must be shifted to get the desired positioning on the page. The scan offset file contains the directions for shifting. The file has the format of

```
[attribute]
values
:
values
[attribute]
values
:
values
:
values
```

Currently, the recognized attributes are [Units] (values millimeters, mm, inches, in, points, dots, pels) [Page_Offset_Type] (values crop or grow) and [Page_Offsets]. The values for page offsets are in the format

FileName, Hhoriz, Vvert Each entry refers to a file. The file names must be specified (or at least the leading comma must), but are currently ignored and the offset factors are applied to each file in turn. The horiz and vert values are the amount that the image is to be shifted, in the horizontal and vertical direction. The positive directions are down and right (that is, the origin is in the left upper corner of the page). The default units are millimeters. Like the values for the **-crop** option, the shifts are specified in the output space context.

Extra spaces and blank lines are allowed. Unrecognized attributes and their values are ignored. See the sample file **shift.sample**.

If the image is moved left or up, part of the bitmap is removed. If the image is moved down or right, removal is governed by the value of the <code>[Page_Offset_Type]</code> attribute. If <code>crop</code> is chosen, the transform removes the requisite amount from the right and bottom edges of the bitmap. If <code>grow</code> is chosen, the transform does not remove any space. The bitmap grows and the trimming, if any, is left to the printer. If the <code>-fit trim</code> option (the default) is specified, <code>[Page_Offset_Type]</code> defaults to <code>grow</code>. For <code>-fit scale</code>, <code>[Page_Offset_Type]</code> defaults to <code>crop</code>.

-1 $\{11i \mid yyy.yy[d \mid m \mid i \mid p]\}$

Specifies the paper length. The optional units are dots (pels), millimeters, inches, or points. The default unit is dots. If the unit is dots, decimals (if any) are ignored. The default paper length is 11 inches. See options -w to set the paper width or -paper to set both dimensions at the same time.

-M {0 | nnn}

Limits the amount of memory available to **jpeg2afp**. *nnn* is the maximum amount of memory in kilobytes. A value of **0** means there is no memory limit. *nnn* can be set from **0** to the maximum value that AIX allows. The default is **0**.

-ms {10 | nnn}

Requires that at least *nnn* kilobytes of disk space be available on the file system that contains the output file. This limit is enforced every time data is written to the output file. If the output is standard output, this option is ignored. The default is **10**. See option **-msf**.

-msf $\{0.1 \mid x.xxx\}$

The number *x.xxx* is a real number between 0 and 1. It denotes the minimum space that must be left unused on the file system containing the output file. The space is given as a fraction of the total space in the file system. This limit is enforced every time data is written to the output file. If the output is standard output, this option is ignored. The default is **0.1**. See option **-ms**.

-noterm

See [-term | -noterm].

<u>-nov</u> See [-v | <u>-nov</u>].

-o FileName

Optional output file name. Specify - for standard output.

-outbits NumberOfOutputBits

Sets the number of bits per pel in output. This value must be 1, 4, 8, or 24. If the output image type is IOCA FS10 or IM1, the number of output bits is set to 1 and this option is ignored. For IOCA FS11 output, the default is 24.

Note that this number represents the maximum number of bits used per pel. Thus, even if the number of bits is set to **24**, a 4-bit grayscale image is still displayed in 4-bit format.

-outcolor {rgb | ycbcr | ycrcb}

Sets the output color model to RGB, YCbCr, or YCrCb if the image type is IOCA FS11 and the number of output bits is 24. Otherwise, this option is ignored. The default is **ycbcr**.

-p {**even** | **odd** | *nn* | *nn-mm* | *nn-*}

Specifies that the output should only contain the specified pages. If no **-p** option is given, all the pages are output. Multiple **-p** options may be specified. Their effect is cumulative. Regardless of the order in which the pages are specified, they are always printed in ascending order. The recognized values are:

even Print all even pages
odd Print all odd pages
nn Print page nn
nn-mm Print pages nn to mm, inclusive.
nnPrint all pages starting with page nn

Pages are numbered starting with 1.

-pagetype {page | overlay | ovly | pseg | object}

Sets the output page type to be page, overlay, page segment or object. The same page type is set for every page in the output. Thus, unless option -p is used to select a single page, multiple overlays, page segments or overlays are stored in the output file. The default is page. See option -a.

-paper {a5 | a4 | a3 | letter | folio | legal | ledger | xxx.xx,yyy.yy[d | m | i | p]} Specifies the output paper size. The supported values are:

```
a3 A3 format (297 by 420 mm or 11.69 by 16.54 inches)
```

a4 A4 format (210 by 297 mm or 8.27 by 11.69 inches)

a5 A5 format (148 by 210 mm or 5.83 by 8.27 inches)

letter 8.5 by 11 inches (216 by 279 mm)

folio 8.5 by 13.0 inches (216 by 330 mm)

legal 8.5 by 14.0 inches (216 by 356 mm)

ledger 11.0 by 17.0 inches (279 by 432 mm)

$xx.xx,yy.yy[\mathbf{d} \mid \mathbf{m} \mid \mathbf{i} \mid \mathbf{p}]$

Horizontal and vertical page dimensions. The optional units are dots (pels), millimeters, inches, or points.

The default paper size is letter. If **-paper** is not used, the paper size is increased, if necessary, to contain the output image.

See options -1, -w, and -scale.

-r {300 | nnn}

The output device resolution, specified in dots per inch. The default is 300.

This option is equivalent to the **default-printer-resolution** document attribute on the **pdpr** command.

-respath directory[:directory...]

Sets the search path for resource files, such as the scan offset files and

grayscale calibration curve files. If a resource file name is specified as a relative name (does not start with a /), the transform searches every directory in the path, in the order specified in the path, until it finds the file (or fails). See options -j and -gcorr for scan offsets and grayscale calibration curve. The default is the current directory.

-rot {0 | 90 | 180 | 270[p | i]}

The image is rotated in the clockwise direction by the amount specified. The default is zero, that is, no rotation.

If \mathbf{p} is specified, the transform sets the output datastream in such a way that the printer performs the actual image rotation. If \mathbf{i} is specified, the transform rotates the output bitmap. When \mathbf{i} is chosen, the transform takes much longer to run and uses much more memory. If no letter is specified, the default or any previous value (such as the value specified in the configuration file) remains in force. The default is \mathbf{p} .

-scale {orig | a5 | a4 | a3 | letter | folio | legal | ledger | $xxx.xx,yyy.yy[\underline{d} \mid m \mid i \mid p] \mid xxx\%$ }

Specifies the output image size. The image is scaled to this size and centered in the area defined by the paper size and margin options. The supported values are:

<u>orig</u> Preserve the input image size, regardless of the printable paper

a3 A3 format (297 by 420 mm or 11.69 by 16.54 inches)

a4 A4 format (210 by 297 mm or 8.27 by 11.69 inches)

a5 A5 format (148 by 210 mm or 5.83 by 8.27 inches)

letter 8.5 by 11 inches (216 by 279 mm)

folio 8.5 by 13.0 inches (216 by 330 mm)

legal 8.5 by 14.0 inches (216 by 356 mm)

ledger 11.0 by 17.0 inches (279 by 432 mm)

$xx.xx,yy.yy[\mathbf{d} \mid \mathbf{m} \mid \mathbf{i} \mid \mathbf{p}]$

Horizontal and vertical image dimensions. The optional units are dots (pels), millimeters, inches, or points.

xxx% Magnification relative to the original image size. Numbers below 100% mean reduction, while Numbers above 100% mean enlargement. For example, **-scale 200%** causes the output image to be twice as long and twice as wide as the input image.

The default image size is **orig**.

-sgcorr FileName

Specifies the name of the scanner-related calibration file. To use this option in the calibration process (with the option **-calib**) you must specify a single file name. If **-calib** is absent, this option is ignored.

A detailed discussion of **-sgcorr** is beyond the scope of this document.

[-term | -noterm]

Disables (-term) or enables (-noterm) error recovery.

 When error recovery is disabled, on encountering an error in a JPEG file, the transform terminates with an error message and a nonzero return code.

ipeg2afp

• When error recovery is enabled, the errors in JPEG files are treated as non-fatal. The transform attempts to recover with the next file. The return code is zero.

The default is **-noterm**.

-thresh FileName

Specifies a file that contains a PostScript Type 1 or Type 3 halftone dictionary. Alternatively, the PostScript code can specify the **setscreen** operator instead of a Type 1 dictionary. The halftone cell in the dictionary is used to overwrite the default ordered dither clustered dot halftone cell. If the PostScript code contains a transfer function, either in the halftone dictionary or specified by the **settransfer** operator, the current grayscale correction curve is overwritten as if **-gcorr** were used.

[-v | -nov]

Turns verbose mode on (-v) or off (-nov).

- When verbose mode is on, the transform prints a message as it opens each resource file, then echoes the command line, then prints a message for each file name as it is processed.
- When verbose mode is off, the transform prints only error messages.

The default is **-nov**.

-w $\{8.5i \mid yyy.yy[d \mid m \mid i \mid p]\}$

Specifies the paper width. The optional units are dots (pels), millimeters, inches, or points. The default unit is dots. The default page width is 8.5 inches. See options -1 to set the paper length or -paper to set both dimensions at the same time.

-wrkdir WorkDirectoryName

Input to <code>jpeg2afp</code> from <code>stdin</code> must be cached on disk before it can be processed. This option specifies which directory to use for the caching of the standard input. If this option is absent or the directory cannot be opened, the transform first tries to use <code>/var/psf/jpeg2afp</code> as the working directory and, if <code>/var/psf/jpeg2afp</code> is absent, uses <code>/tmp</code>.

The **stdin** cache file is never visible to the user because it is immediately unlinked after creation. Thus, the cache file is always deleted when **jpeg2afp** finishes execution, even if **jpeg2afp** is killed or otherwise terminates in error.

$-x \{0 \mid nnn.nn[d \mid m \mid i \mid p]\}$

Specifies the left margin. The optional units are dots (pels), millimeters, inches, or points. The default unit is dots. The default is zero (no margin).

$-y \{0 \mid nnn.nn[d \mid m \mid i \mid p]\}$

Specifies the top margin. The optional units are dots (pels), millimeters, inches, or points. The default unit is dots. The default is zero (no margin).

-z Signifies that a list of files to be processed is submitted from standard input. See also options -f and @.

line2afp Command: Transforms S/370 Line Data and ASCII Data to AFP Syntax

line2afp [cc=value] [cctype=value]
 [chars=FontName[, ...]] [fdeflib=PathList] [fileformat=value]
 [fontlib=PathList] formdef=FormDefinitionName [imageout=value]
 [inpexit=ProgramName] [inputdd=FileName] [msgdd=FileName]
 [outexit=ProgramName] [outputdd=FileName]
 [ovlylib=PathList] pagedef=PageDefinitionName
 [parmdd=FileName] [pdeflib=PathList]
 [prmode=value] [pseglib=PathList] [resexit=ProgramName]
 [reslib=PathList] [trc=value] [userlib=PathList]

With Infoprint Manager for AIX, if you need guidance in passing the line2afp command option syntax through the shell, refer to the documentation for the shell you are using in the AIX for RS/6000 Commands Reference.

Table 7 shows the **line2afp** command options that specify resource names or resource directories, and the corresponding AIX print command options and Infoprint attributes:

Table 7. line2afp Resource	Options and	Corresponding	Options and Attributes
----------------------------	-------------	---------------	------------------------

line2afp option	AIX -o flag option	Document attribute	Physical printer attribute
chars	-ochars	chars	
fdeflib	-orespath	resource-context-form-definition	resource-context-form-definition
fontlib	-osrchfontlib	resource-context-font	resource-context-font
formdef	-oformdef	form-definition	form-definition
ovlylib	-orespath	resource-context-overlay	resource-context-overlay
pagedef	-opagedef	page-definition	
pdeflib	-opdeflib	resource-context-page-definition	resource-context-page-definition
pseglib	-orespath	resource-context-page-segment	resource-context-page-segment
reslib	-orespath	resource-context	
userlib	-ouserlib	resource-context-user	

For these options, you should specify the same value with the **line2afp** command as you specify to Infoprint when you submit the print job or predefine for the physical printer where the job prints. In this way, the search paths and resources used at transform time are identical to the search paths and resources used at print time.

In addition to the usual command notational conventions, the <code>line2afp</code> command follows these additional rules. These rules apply to options you type at the command line. See also the <code>parmdd</code> option for the syntax of options contained in the <code>line2afp</code> option file.

• When the **line2afp** command processes any unrecognized or unsupported option, **line2afp** issues a message, ignores the option, and continues processing any remaining options. The **line2afp** command then stops processing.

line2afp

• With Infoprint Manager for AIX, though the options themselves are not case-sensitive, associated values, such as file names, attribute names, and directory names *are* case-sensitive. For example,

formdef=F1MINE

is *not* the same as formdef=f1mine

Be sure to specify these values in the case in which they exist in the file system (for external resources) or in the print file (for inline resources).

• If the same option is specified more than one time, the line2afp command uses the last value specified. For example, if you specify the following: pagedef=P1MINE pagedef=P1YOURS

the line2afp command uses page definition P1YOURS only.

Description

The **line2afp** command transforms S/370 line data, mixed-mode data, and ASCII files into the AFP (MO:DCA-P) data stream, so that you can print the file on an Infoprint printer.

When you use the **line2afp** command to convert S/370 line data or ASCII data, you must specify a page definition (**pagedef** option). If the page definition names fonts, Infoprint uses those fonts. If the page definition does not name any fonts, and if you want the file to print with more than one font, then the input file must contain table reference characters (TRCs), and you must:

- Specify trc=yes.
- Use **chars** to indicate the fonts to be associated with each TRC.

If the page definition does not specify fonts, and you have not specified any TRCs, your job will print, although the output may not be formatted correctly.

If the page definition does not name any fonts, and you want the whole file to print with one font, then you must:

- Specify trc=no.
- Use chars to indicate the single fonts in which the file should be printed.

If the page definition does not specify fonts, and you have not specified any TRCs, your job will print, although the output may not be formatted correctly.

If the page definition does not name any fonts, and you want the whole file to print with one font, then you must:

The line2afp command searches for resources in the following order:

- 1. Paths specified by the **userlib** option for miscellaneous user resources. If **line2afp** is invoked as part of submitting a print job, the paths you specified with the **resource-context-user** attribute on the **pdpr** command, in an attributes file, or in a default document, are also searched.
- 2. Paths specified by the **fdeflib**, **fontlib**, **ovlylib**, **pdeflib**, and **pseglib** options for specific types of resources.
- 3. Paths specified by the **reslib** option. If **line2afp** is invoked as part of submitting a print job, the paths you specified with the **-orespath** flag on an AIX print

- command, or with the **resource-context** attribute on the **pdpr** command, in an attributes file, or in a default document, are also searched.
- 4. Paths specified by the **PSFPATH** environment variable.
- 5. If line2afp is invoked as part of submitting a print job, the paths specified with the resource-context-font, resource-context-form-definition, resource-context-overlay, resource-context-page-definition, and resource-context-page-segment physical printer attributes for specific types of resources.
- 6. With AIX:
 - a. /usr/lpp/psf/reslib
 - b. /usr/lpp/afpfonts
 - c. /usr/lpp/psf/fontlib
- 7. With Windows NT or Windows 2000, where *install_path* indicates the path where you installed Infoprint Manager:
 - a. \install_path\reslib
 - b. \install_path\afpfonts
 - c. \install_path\fontlib

When the **line2afp** command finds more than one resource with the same name in the same directory, it selects the resource to be used depending on the file extension. Table 8 shows the order in which resources with the same name but different file extensions are used by **line2afp**.

Note: If a file name includes a period (.), the file extension is that part of the file name that follows the period. For example, the file extension of the file name **ARTWORK.PSEG3820** is **PSEG3820**.

Table 8. File Extensions for Resources

Type of Resource	File Extensions Searched (see note)	
BCOCA (bar code) objects	1. No file extension	
Code pages	 No file extension FONT3820 FONT38PP CDP 	
Coded fonts	 No file extension FONT3820 FONT38PP CFT 	
Font character sets, 240-pel resolution	 No file extension 240 FONT3820 FONT38PP 	
Font character sets, 300-pel resolution	 300 FONT300 No file extension 	
Fonts, outline	1. OLN 2. FONTOLN	
Form definitions	 No file extension FDEF3820 FDEF38PP FDE 	
GOCA (graphics) objects	1. No file extension	

Table 8. File Extensions for Resources (continued)

File Extensions Searched (see note)
1. No file extension
 No file extension OVLY3820 OVLY38PP OVL
 No file extension PDEF3820 PDEF38PP PDE
 No file extension PSEG3820 PSEG38PP PSG PSE
 No file extension SETUP SET COMSETUP

The PSF DSS automatically invokes line2afp whenever you submit a line-data or unformatted ASCII job. You can specify document-format=line-data or document-format=ascii on the pdpr command, or -odatatype=line or -odatatype=ascii on an AIX print command or the lprafp command, or you can allow Infoprint to identify the data type.

Flags and Values

You can specify many of these flags and values with the other-transform-options attribute on the pdpr command or with the enq -o, lp -o, qprt -o, or lprafp -o command.

See "pdpr Command: Submits Jobs" on page 61 and "Attributes for Documents and Default Documents" on page 464 or "Chapter 3. The -o Flag for AIX Print Commands" on page 103 for more information.

cc={yes | no}

Specifies whether the input file has carriage-control characters.

Values are:

The file contains carriage-control characters. **yes** is the default. yes The file does not contain carriage-control characters. no

Carriage-control characters, if present, are located in the first byte (column) of each line in a document. They are used to control how the line will be formatted (single space, double space, triple space, and so forth). In addition, other carriage-controls can be used to position the line anywhere on the page. If there are no carriage-controls, single spacing is assumed.

This option and the **cctype** option, used together, are equivalent to the document attribute carriage-control-type on the pdpr command.

$cctype=\{z \mid a \mid m\}$

Specifies the type of carriage-control characters in the input file. The

line2afp command supports ANSI carriage-control characters in either ASCII or EBCDIC encoding, as well as machine carriage-control characters. The **line2afp** command does not allow a mixture of ANSI and machine carriage-control characters within a file. Values are:

<u>z</u> The file contains ANSI carriage-control characters that are encoded in ASCII. **z** is the default.

The carriage-control characters are the ASCII hexadecimal values that directly relate to ANSI carriage-controls, which cause the action of the carriage-control character to occur *before* the line is printed. For example, if the carriage-control character is zero (X'30'), which represents double spacing, double spacing will occur *before* the line is printed.

a The file contains ANSI carriage-control characters that are encoded in EBCDIC.

The use of ANSI carriage-control characters cause the action of the carriage-control character to occur *before* the line of data is printed. For example, if the carriage-control character is a zero (X'F0'), which represents double spacing, the double spacing will occur *before* the line is printed.

m The file contains machine code carriage-control characters that are encoded in hexadecimal format.

The use of machine code carriage-control characters cause the action of the carriage-control character to occur *after* the line of data is printed. For example, if the carriage-control character is a X'11', which represents double spacing, the line will be printed and the double spacing will occur *after* the line is printed. In addition, machine code carriage-control has a set of carriage-control characters that perform the action, but do not print the associated line.

If you specify **cc=yes** but you do not specify **cctype**, the **line2afp** command assumes that the file contains ANSI carriage-control characters encoded in ASCII.

If you are not sure which type of carriage-control characters are in your input file, consult your system support group.

This option and the **cc** option, used together, are equivalent to the document attribute **carriage-control-type** on the **pdpr** command.

chars=FontName1, FontName2, FontName3, FontName4

Specifies the file name of from one to four coded fonts to be used in processing the print file. A coded font specifies a character set and code page pair.

The value is:

FontName

The name of the desired coded font. The font name is limited to 4 alphanumeric or national characters, and should not include the 2-character prefix of the coded-font name (**X0** through **XG**). With Infoprint Manager for AIX, the font name is case-sensitive.

line2afp

With Infoprint Manager for AIX, if you use the ASCII fonts that are supplied with Infoprint, use the 4-character names. If you use your own coded font that has a file name with more than 6 characters (including the X*n* prefix), then do one of the following:

- Rename the font file to a shorter name. For example, mv X0423002 X04202
- Copy the font file to a file that has a shorter name. For example, cp X0423002 X04202
- Link the original font file to a shorter name. For example, ln -s X0423002 X04202

With Infoprint Manager for Windows NT and Windows 2000, if you use the ASCII fonts that are supplied with Infoprint, use the 4-character names. If you use your own coded font that has a file name with more than 6 characters (including the Xn prefix), then do one of the following:

- · Rename the font file to a shorter name. For example, rename X0423002 X04202
- Copy the font file to a file that has a shorter name. For example, copy X0423002 X04202

When you use the line2afp command to convert S/370 line-mode data or unformatted ASCII data, you must specify a page definition (pagedef option). If the page definition names some fonts, the line2afp command uses those fonts, and ignores the chars option. If the page definition does not name any fonts (like the sample page definitions supplied with Infoprint), and if you want the file to print with more than one font, then the input file must contain table reference characters, and you must:

- Specify trc=yes.
- Use chars to indicate the fonts to be associated with each table reference character (TRC). Fontname1 is associated with TRC 0, FontName2 is associated with TRC 1, and so on.

If the page definition does not name any fonts, and you want the whole file to print with only one font, then the input file must not contain table reference characters and you must:

- Specify trc=no.
- Use **chars** to indicate the single font in which the file should be printed.

Consider the following when specifying fonts with the **chars** option:

- If your input file is unformatted ASCII, you can do one of the following:
 - Specify a font that has the appropriate ASCII code points. To specify a font search path, either use the **fontlib** option to specify it explicitly, or set the **PSFPATH** environment variable to search the appropriate directories. See "IBM AFP Fonts for ASCII Data" in AFP Conversion and Indexing Facility: User's Guide for a list of suggested ASCII fonts.
 - Use the apka2e or asciinpe input record exit programs to convert the ASCII code points in the input file into EBCDIC, and use EBCDIC fonts. To do this, use the **inpexit** option, specifying:

For AIX

inpexit=/usr/lpp/psf/bin/apka2e

For NT/2000

inpexit=c:\Program Files\IBM Printing Systems\bin\apka2e
where this path assumes you installed into the default path.

If the ASCII input file contains form feeds or carriage returns, specify:

For AIX

inpexit=/usr/lpp/psf/bin/asciinpe

For NT/2000

inpexit=c:\Program Files\IBM Printing
Systems\bin\asciinpe where this path assumes you installed
into the default path.

- You can specify fonts with the **chars** option only if you want the entire file printed in a single printing direction. The **line2afp** command uses the fonts that have 0-degree character rotation for the specified direction. When a file requires fonts with more than one print direction or character rotation, you must specify the fonts in the page definition.
- You can specify from one to four fonts with the **chars** option. If you specify more than one font with the **chars** option, then the input file must contain table reference characters, and you must specify **trc=yes**.
- If you use **chars** to specify fonts, but you also use the **pagedef** option to specify a page definition that names fonts, the **chars** option is ignored. Therefore, if your page definition names fonts, you should not use **chars**.
- If you do not specify a **chars** option, and if no fonts are contained in the page definition you specified, the **line2afp** command uses the default font that is set in the printer's hardware.

This option is equivalent to the document attribute **chars** on the **pdpr** command.

fdeflib=PathList

Specifies the directories in which form definitions are stored. The value is: *PathList*

Any valid search path. The **line2afp** command searches the paths in the order in which they are specified.

With AIX, you must use a colon (:) to separate multiple paths.

With NT/2000, you must use a semi-colon (;) to separate multiple paths.

The **line2afp** command searches for the form definition in the following order:

- 1. The paths you specified with **userlib**, if any. If **line2afp** is invoked as part of submitting a print job, the paths you specified with the **resource-context-user** attribute on the **pdpr** command, in an attributes file, or in a default document, are also searched.
- 2. The paths you specified with **fdeflib**, if any. If **line2afp** is invoked as part of submitting a print job, the paths you specified with the **resource-form-definition** attribute on the **pdpr** command, in an attributes file, or in a default document, are also searched.
- 3. The paths you specified with **reslib**, if any. If **line2afp** is invoked as part of submitting a print job, the paths you specified with the

line2afp

- **-orespath** flag on an AIX print command, or with the **resource-context** attribute on the **pdpr** command, in an attributes file, or in a default document, are also searched.
- 4. The paths specified by the **PSFPATH** environment variable.
- 5. If **line2afp** is invoked as part of submitting a print job, the paths specified with the **resource-context-form-definition** physical printer attribute.
- 6. With AIX:
 - a. /usr/lpp/psf/reslib
 - b. /usr/lpp/afpfonts
 - c. /usr/lpp/psf/fontlib
- 7. With Windows NT or Windows 2000, where *install_path* indicates the path where you installed Infoprint Manager:
 - a. \install_path\reslib
 - b. \install_path\afpfonts
 - c. \install_path\fontlib

For S/370 line data and for ASCII data that you want to format with a page definition, if you are transforming and printing a file by piping line2afp's output to an AIX print command or the pdpr command, you should specify the same form definition search path on both sides of the pipe, unless you are sure that the same form definition will be found by line2afp and Infoprint using each program's default search path.

With Infoprint Manager for AIX, for S/370 line data and for ASCII data that you want to format with a page definition, if you are transforming and printing a file by specifying **-odatatype=line** with an AIX print command, you must specify the form definition search path with **-orespath** instead of **fdeflib**. For example:

enq -odatatype=line -oformdef=myfd -opagedef=mypdef
-orespath=/home/greg/resources -Pprinter myfile

This option is equivalent to the document attribute **resource-context-form-definition** on the **pdpr** command.

fileformat={record | record,n | stream | stream,(newline=X'nn')}

Specifies the format of the input file. If you do not specify **fileformat**, the **line2afp** command uses **stream** as the default.

The **fileformat** option does not apply to input files that are resources. Resource files are in MO:DCA-P or AFP data stream format, and the **line2afp** command automatically determines that the file is a resource.

Values are:

record The input file is formatted in S/370 record format, where the first two bytes of each line specify the length of the line. Files with **record** format typically are MVS or VM files that have a variable record format and are downloaded to AIX or Windows.

record,n

The input file is formatted in such a way that each record (including AFP data stream and MO:DCA-P records) is a fixed length, *n* bytes long. The value of *n* is a number from 1 to 32767. The encapsulated size of the AFP structured field must be less than

the size of *n*. Files with **record**, *n* format typically are MVS or VM files that have a fixed record format and are downloaded to AIX or Windows.

stream

The input file has no length information; it is a stream of data separated by a newline character. The AFP portion (if any) of the input file has its length information encapsulated in the structured field. Files with stream format typically come from a workstation operating system like AIX, Windows, OS/2, or DOS.

The line2afp command examines the first six bytes of the first line data record of the input file, to determine whether the input file is ASCII or EBCDIC. If line2afp determines that the input file is ASCII, line2afp looks for ASCII newline characters (X'0A') to delimit the end of a record. If line2afp determines that the input file is EBCDIC, line2afp looks for EBCDIC newline characters (X'25') to delimit the end of a record. The line2afp command does not include newline characters in the MO:DCA-P data stream that line2afp produces.

stream is the default.

stream,(newline=X'nn')

Use **newline** to specify a hexadecimal value for the newline character in the input data file.

You can use **newline** when **line2afp**'s algorithm cannot determine the correct newline character (if blanks are at the beginning of the file, for instance). Or you can use newline if you want to specify a newline character that is not the standard default. For example, you could use **newline** as follows:

fileformat=stream, (newline=X'0D')

If **newline** is not specified, **line2afp** uses the algorithm specified under fileformat=stream.

This option is equivalent to the document attribute **new-line-options** on the **pdpr** command.

fontlib=*PathList*

Specifies the directories in which fonts are stored.

The value is:

PathList

Any valid search path. The **line2afp** command searches the paths in the order in which they are specified.

With AIX, you must use a colon (:) to separate multiple paths.

With NT/2000, you must use a semi-colon (;) to separate multiple paths.

The **line2afp** command searches for the fonts in the following order:

1. The paths you specified with **userlib**, if any. If **line2afp** is invoked as part of submitting a print job, the paths you specified with the resource-context-user attribute on the pdpr command, in an attributes file, or in a default document, are also searched.

line2afp

- 2. The paths you specified with fontlib, if any. If line2afp is invoked as part of submitting a print job, the paths you specified with the -osrchfontlib flag on an AIX print command, or with the resource-context-font attribute on the pdpr command, in an attributes file, or in a default document, are also searched.
- 3. The paths you specified with **reslib**, if any. If **line2afp** is invoked as part of submitting a print job, the paths you specified with the **resource-context** attribute on the **pdpr** command, in an attributes file, or in a default document, are also searched.
- 4. If **line2afp** is invoked as part of submitting a print job, the paths specified with the **resource-context-font** physical printer attribute.
- 5. The paths specified by the **PSFPATH** environment variable.
- 6. With AIX:
 - a. /usr/lpp/psf/reslib
 - b. /usr/lpp/afpfonts
 - c. /usr/lpp/psf/fontlib
- 7. With Windows NT or Windows 2000, where *install_path* indicates the path where you installed Infoprint Manager:
 - a. \install_path\reslib
 - b. \install_path\afpfonts
 - c. \install_path\fontlib

For S/370 line data and for ASCII data that you want to format with a page definition, if you are transforming and printing a file by piping line2afp's output to an AIX print command or the pdpr command, you should specify the same font search path on both sides of the pipe, unless you are sure that the same fonts will be found by line2afp and Infoprint using each program's default search path.

With Infoprint Manager for AIX, for S/370 line data and for ASCII data that you want to format with a page definition, if you are transforming and printing a file by specifying **-odatatype=line** with an AIX print command, you must specify the font search path (if any) with **-osrchfontlib** instead of **fontlib**, as shown in the following example:

```
enq -odatatype=line -osrchfontlib=/home/greg/resources
-oformdef=myfdef -opagedef=mypdef -Pprinter myfile
```

Note: If the input file is ASCII data that you want to format with a page definition, you can do one of the following:

- Specify a font that has the appropriate ASCII code points. To specify a font search path, either use the **fontlib** option to specify it explicitly, or set the **PSFPATH** environment variable to search the appropriate directories.
- Use the apka2e or asciinpe input record exit to convert the ASCII code points in the input file into EBCDIC, and use EBCDIC fonts.
 To do this, use the inpexit option, specifying:

For AIX

inpexit=/usr/lpp/psf/bin/apka2e

For NT/2000

inpexit=c:\Program Files\IBM Printing
Systems\bin\apka2e where this path assumes you
installed into the default path.

or

For AIX

inpexit=/usr/lpp/psf/bin/asciinpe

For NT/2000

inpexit=c:\Program Files\IBM Printing
Systems\bin\asciinpe where this path assumes you
installed into the default path.

This option is equivalent to the document attribute **resource-context-font** on the **pdpr** command.

formdef=FormDefinitionName

Specifies the file name of the form definition. A form definition defines how a page of data is placed on a form, the number of copies of a page, any modifications to that group of copies, the paper source, and duplexing. The form definition is actually used at print time, not at transform time.

The value is:

FormDefinitionName

Any valid form definition file name. The *FormDefinitionName* can be 1 to 8 alphanumeric or national characters, including the two-character prefix, if there is one. For AIX, the *FormDefinitionName* is case-sensitive.

Note: If the file name of the form definition includes a file extension, do not use the file extension when specifying the form definition. For example, to use a form definition named **memo.FDEF38PP**, specify **formdef=memo**.

The <code>line2afp</code> command requires a form definition in order to process the input file (even though the form definition actually gets used at print time). If you do not specify <code>formdef=</code>, or if you specify <code>formdef=</code> without a form definition file name, the <code>line2afp</code> command will not work.

For S/370 line data and for ASCII data that you want to format with a page definition, if you are transforming and printing a file by piping line2afp's output to an AIX print command or the pdpr command, you should specify the same form definition on both sides of the pipe. If you are using the default form definition for the target printer, you do not need to specify a form definition with the AIX print command or pdpr command.

The form definition you use may be located:

- In a directory
- Inline in the file (that is, within the file itself)

If the form definition file is in a directory, use the **userlib** option or **fdeflib** option to specify the path to the file. For example:

For AIX

formdef=memo userlib=/usr/afp/resources

For NT/2000

formdef=memo userlib=d:\afp\resources

or

For AIX

formdef=memo fdeflib=/usr/lib/formdefns

For NT/2000

formdef=memo fdeflib=d:\lib\formdefns

If the form definition is an inline resource, you must do the following:

- Specify cc=yes to indicate that the file contains carriage-control characters.
- Specify **formdef**=*FormDefinitionName*, where *FormDefinitionName* is the name of the inline form definition; or specify **formdef**=**dummy**.

If you specify **formdef=dummy** but the file does not include an inline form definition, the **line2afp** command looks for the form definition named **dummy**.

If you use **formdef** to specify an inline form definition that is different than the actual form definition used inline, the **line2afp** command looks for the **formdef** value instead of the inline form definition.

An input file can contain multiple form definitions, but only one form definition can be used for printing. If a file contains more than one inline form definition, and you specify <code>formdef=FormDefinitionName</code>, <code>line2afp</code> uses the first inline form definition named <code>FormDefinitionName</code>. If a file contains more than one inline form definition, and you specify <code>formdef=dummy</code>, <code>line2afp</code> uses the first inline form definition in the input file.

This option is equivalent to the document attribute **form-definition** on the **pdpr** command.

imageout={asis | ioca}

Specifies the format of the image data produced by the **line2afp** command in the output document.

Values are:

asis The line2afp command produces all image data in the same format that it was in the input file.

<u>ioca</u> The <u>line2afp</u> command produces all image data in the Image Object Content Architecture uncompressed format. **ioca** is the default.

This option is similar to the document attribute **image-out-format** on the **pdpr** command.

inpexit=*ProgramName*

Specifies the name or the full path name of the input record exit program. The **line2afp** command calls this program for every record (every line) it reads from the input file (**inputdd**). If you specify the file name without a path, the **line2afp** command searches for the exit program in the paths specified by the **PATH** environment variable. If you do not specify this option, the **line2afp** command will not use an input record exit program.

The value is:

ProgramName

Any valid input record exit program name. With Infoprint Manager for AIX, the exit program name is case-sensitive.

If the input file is unformatted ASCII, but the fonts you are using contain EBCDIC, not ASCII, code points (for example, you specify **chars=GT15**), you can specify:

With AIX:

/usr/lpp/psf/bin/apka2e

Converts ASCII stream data to EBCDIC stream data.

/usr/lpp/psf/bin/asciinpe

Converts unformatted ASCII data into a record format that contains an American National Standards Institute (ANSI) carriage control character in byte 0 of every record, and then converts the ASCII stream data to EBCDIC stream data.

With NT/2000:

c:\Program Files\IBM Printitng Systems\bin\apka2e

Converts ASCII stream data to EBCDIC stream data. This path assumes you installed into the default directory.

c:\Program Files\IBM Printitng Systems\bin\asciinpe

Converts unformatted ASCII data into a record format that contains an American National Standards Institute (ANSI) carriage control character in byte 0 of every record, and then converts the ASCII stream data to EBCDIC stream data. This path assumes you installed into the default directory.

If your input file uses fonts that have ASCII code points (for example, you specify **chars=H292**, or any of the fonts listed in "IBM AFP Fonts for ASCII Data" in *AFP Conversion and Indexing Facility: User's Guide*) you should *not* use the **apka2e** or **asciinpe** exit programs. However, if your unformatted ASCII file contains carriage returns and form feeds, you may want to specify the following exit program supplied with Infoprint:

For AIX: /usr/lpp/psf/bin/asciinp

Converts unformatted ASCII data that contains carriage returns and form feeds into a record format that contains an American National Standards Institute (ANSI) carriage control character. This exit encodes the ANSI carriage control character in byte 0 of every record.

For NT/2000: c:\Program Files\IBM Printing Systems\bin\asciinp

Converts unformatted ASCII data that contains carriage returns and form feeds into a record format that contains an American National Standards Institute (ANSI) carriage control character. This exit encodes the ANSI carriage control character in byte 0 of every record.

This option is equivalent to the document attribute **input-exit** on the **pdpr** command.

inputdd=FileName

Specifies the full path name of the input file that the line2afp command will process. If you do not specify inputdd, the line2afp command uses standard input.

You cannot use **inputdd=***FileName* on the command line with the **enq**, **lp**, qprt, or lprafp. commands, or with the other-transform-options attribute on the pdpr command. You can only use inputdd=FileName with the line2afp command.

msgdd=FileName

Specifies the name or the full path name of the file where the line2afp command writes error messages. If you specify the file name without a path, the line2afp command puts the error file into your current directory. If you do not specify msgdd, the line2afp command uses standard error for its message output.

This option is equivalent to the document attribute transform-message**file-name** on the **pdpr** command.

outexit=ProgramName

Specifies the name or the full path name of the output record exit program. The line2afp command calls this program for every output record (every line) it writes to the output document file (outputdd). If you specify the file name without a path, the line2afp command searches for the file name in the paths specified by the PATH environment variable. If you do not specify this option, the line2afp command will not use an output record exit program.

The value is:

ProgramName

Any valid output record exit program name. With Infoprint Manager for AIX, the exit program name is case-sensitive.

This option is equivalent to the document attribute **output-exit** on the **pdpr** command.

outputdd=FileName

Specifies the name or the full path name of the output document file. If you specify the file name without a path, the line2afp command puts the output file into your current directory. If you do not specify outputdd, the line2afp command writes the output to standard output.

You cannot use **outputdd=***FileName* on the command line with the **enq**, **lp**, or qprt commands, or with the other-transform-options attribute on the pdpr command. You can only use outputdd=FileName with the line2afp command.

This option is equivalent to the document attribute transform-output-file**name** on the **pdpr** command.

ovlylib=PathList

Specifies the directories in which overlays are stored. The value is:

PathList.

Any valid search path. The line2afp command searches the paths in the order in which they are specified.

With AIX, you must use a colon (:) to separate multiple paths.

With NT/2000, you must use a semi-colon (;) to separate multiple paths.

The line2afp command searches for an overlay in the following order:

1. The paths you specified with **userlib**, if any. If **line2afp** is invoked as part of submitting a print job, the paths you specified with the

- **resource-context-user** attribute on the **pdpr** command, in an attributes file, or in a default document, are also searched.
- 2. The paths you specified with **ovlylib**, if any. If **line2afp** is invoked as part of submitting a print job, the paths you specified with the **resource-context-overlay** attribute on the **pdpr** command, in an attributes file, or in a default document, are also searched.
- 3. The paths specified in **reslib**, if any. If **line2afp** is invoked as part of submitting a print job, the paths you specified with the **-orespath** flag on an AIX print command, or with the **resource-context** attribute on the **pdpr** command, in an attributes file, or in a default document, are also searched.
- 4. If **line2afp** is invoked as part of submitting a print job, the paths specified with the **resource-context-overlay** physical printer attribute.
- 5. The paths specified by the **PSFPATH** environment variable.
- 6. With AIX:
 - a. /usr/lpp/psf/reslib
 - b. /usr/lpp/afpfonts
 - c. /usr/lpp/psf/fontlib
- 7. With Windows NT or Windows 2000, where *install_path* indicates the path where you installed Infoprint Manager:
 - a. \install_path\reslib
 - b. \install_path\afpfonts
 - c. \install_path\fontlib

For S/370 line data and for ASCII data that you want to format with a page definition, if you are transforming and printing a file by piping line2afp's output to an AIX print command or the pdpr command, you should specify the same overlay search path on both sides of the pipe, unless you are sure that the same overlays will be found by line2afp and Infoprint using each program's default search path.

Infoprint Manager for AIX, for S/370 line data and for ASCII data that you want to format with a page definition, if you are transforming and printing a file by specifying **-odatatype=line** with an AIX print command, you must specify the overlay search path with **-orespath** instead of **ovlylib**. For example:

```
enq -odatatype=line -oformdef=myfd -opagedef=mypd
-orespath=/home/greg/resources -Pprinter myfile
```

This option is equivalent to the document attribute **resource-context-overlay** on the **pdpr** command.

pagedef=PageDefinitionName

Specifies the file name of the page definition. A page definition defines the page format that the **line2afp** command uses to compose the input file into pages. The page definition is actually used at transform time, not at print time.

The value is:

PageDefinitionName

Any valid page definition file name. The PageDefinitionName can be

1 to 8 alphanumeric or national characters, including the two-character prefix, if there is one. With AIX, the **pdefname** is case-sensitive.

Note: If the file name of the page definition includes a file extension, do not use the file extension when specifying the page definition. For example, to use a page definition named memo.PDEF38PP, specify pagedef=memo.

The line2afp command requires a page definition in order to process the input file. If you do not specify pagedef=, or if you specify pagedef= without a page definition file name, the line2afp command will not work.

The page definition you use may be located:

- In a directory
- Inline in the file (that is, within the file itself)

If the page definition file is in a directory, use the userlib option or pdeflib option to specify the path to the file. For example:

For AIX

pagedef=memo userlib=/usr/afp/resource

For NT/2000

pagedef=memo userlib=d:\afp\resource

or

For AIX

pagedef=memo pdeflib=/usr/lib/pagedefns

For NT/2000

named dummy.

pagedef=memo pdeflib=d:\lib\pagedefns

If the page definition is an inline resource, you must do the following:

- Specify cc=yes to indicate that the file contains carriage-control characters.
- Specify **pagedef=**PageDefinitionName, where PageDefinitionName is the name of the inline page definition; or specify **pagedef=dummy**. If you specify pagedef=dummy but the file does not include an inline page definition, the line2afp command looks for the page definition

If you use pagedef to specify an inline page definition that is different than the actual page definition used inline, the line2afp command looks for the **pagedef** value instead of the inline page definition.

An input file can contain multiple page definitions, but only one page definition can be used by the line2afp command. If a file contains more than one inline page definition, and you specify pagedef=PageDefinitionName, line2afp uses the first inline page definition named PageDefinitionName. If a file contains more than one inline page definition, and you specify pagedef=dummy, the line2afp command uses the first inline page definition in the input file.

This option is equivalent to the document attribute page-definition on the pdpr command.

parmdd=FileName

Specifies the name or the full path name of a file that contains the **line2afp** options and their values. If you specify the file name without a path, the **line2afp** command searches for the file name in your current directory.

You may find it convenient to put the <code>line2afp</code> options and values into a file, so that you do not have to type all of them on the command line whenever you use <code>line2afp</code>.

Values are:

FileName

The name of the file containing line2afp command options and values.

Notes:

1. The beginning delimiter for comments is "/*". For example:

```
formdef=F1TEMP /* Temporary formdef
formdef=F1PROD /* Production-level formdef
```

Comments can appear anywhere, but the **line2afp** command ignores all information in the line following the "/*" character string.

- 2. Each option must be on a separate line. For example: chars=GT10 cctype=a /* This is NOT allowed.
- 3. If the option file contains the name of the input file (inputdd=FileName), you cannot specify the option file with an AIX print command's -o flag or with the other-transform-options attribute on the pdpr command. For example, these commands are not valid:

```
enq -odatatype=line -oparmdd=myparms
pdpr -x "document-format=line-data
   other-transform-options='parmdd=myparms'"
```

```
However, these are valid:
```

```
line2afp parmdd=myparms | enq
line2afp parmdd=myparms | pdpr -d my-printer
```

pdeflib=PathList

Specifies the directories in which page definitions are stored.

The value is:

PathList

Any valid search path. The **line2afp** command searches the paths in the order in which they are specified.

With AIX, you must use a colon (:) to separate multiple paths.

With NT/2000, you must use a semi-colon (;) to separate multiple paths.

The line2afp command searches for a page definition in the following order:

- The paths you specified with userlib, if any. If line2afp is invoked as part of submitting a print job, the paths you specified with the resource-context-user attribute on the pdpr command, in an attributes file, or in a default document, are also searched.
- 2. The paths you specified with **pdeflib**, if any. If **line2afp** is invoked as part of submitting a print job, the paths you specified with the

- **resource-context-page-definition** attribute on the **pdpr** command, in an attributes file, or in a default document, are also searched.
- 3. The paths specified in reslib, if any. If line2afp is invoked as part of submitting a print job, the paths you specified with the -orespath flag on an AIX print command, or with the resource-context attribute on the pdpr command, in an attributes file, or in a default document, are also searched.
- 4. If **line2afp** is invoked as part of submitting a print job, the paths specified with the **resource-context-page-definition** physical printer attribute
- 5. The paths specified by the **PSFPATH** environment variable.
- 6. With AIX:
 - a. /usr/lpp/psf/reslib
 - b. /usr/lpp/afpfonts
 - c. /usr/lpp/psf/fontlib
- 7. With Windows NT or Windows 2000, where *install_path* indicates the path where you installed Infoprint Manager:
 - a. \install_path\reslib
 - b. \install_path\afpfonts
 - c. \install_path\fontlib

This option is equivalent to the document attribute **resource-context-page-definition** on the **pdpr** command.

prmode={SOSI1 | SOSI2 | aaaaaaaa}

Specifies the type of data in the input file and whether the line2afp command must perform optional processing of that data.

Values are:

- **SOSI1** Specifies that each shift-out, shift-in code be converted to a blank and a Set Coded Font Local text control.
- **SOSI2** Specifies that each shift-out, shift-in code be converted to a Set Coded Font Local text control.

аааааааа

Any 8-byte alphanumeric string. This value is supplied to all of the ACIF user exits. (Refer to *AFP Conversion and Indexing Facility: User's Guide* for information about ACIF user exits.)

For the **SOSI** process modes to work correctly, the first font specified in the **chars** option (or in a font list in a page definition) must be a single-byte font, and the second font must be a double-byte font.

This option is equivalent to the document attribute **shift-out-shift-in** on the **pdpr** command.

pseglib=PathList

Specifies the directories in which page segments and BCOCA, GOCA, and IOCA objects are stored.

The value is:

PathList.

Any valid search path. The **line2afp** command searches the paths in the order in which they are specified.

With AIX, you must use a colon (:) to separate multiple paths. With NT/2000, you must use a semi-colon (;) to separate multiple paths.

The line2afp command searches for page segments in the following order:

- The paths you specified with userlib, if any. If line2afp is invoked as part of submitting a print job, the paths you specified with the resource-context-user attribute on the pdpr command, in an attributes file, or in a default document, are also searched.
- 2. The paths you specified with **pseglib**, if any. If **line2afp** is invoked as part of submitting a print job, the paths you specified with the **resource-context-page-segment** attribute on the **pdpr** command, in an attributes file, or in a default document, are also searched.
- 3. The paths specified in **reslib**, if any. If the **line2afp** command is invoked as part of submitting a print job, the paths you specified with the **-orespath** flag on an AIX print command, or with the **resource-context** attribute on the **pdpr** command, in an attributes file, or in a default document, are also searched.
- If line2afp is invoked as part of submitting a print job, the paths specified with the resource-context-page-segment physical printer attribute.
- 5. The paths specified by the **PSFPATH** environment variable.
- 6. With AIX:
 - a. /usr/lpp/psf/reslib
 - b. /usr/lpp/afpfonts
 - c. /usr/lpp/psf/fontlib
- 7. With Windows NT or Windows 2000, where *install_path* indicates the path where you installed Infoprint Manager:
 - a. \install_path\reslib
 - b. \install_path\afpfonts
 - c. \install_path\fontlib

For S/370 line data and for ASCII data that you want to format with a page definition, if you are transforming and printing a file by piping line2afp's output to an AIX print command or the pdpr command, you should specify the same page segment search path on both sides of the pipe, unless you are sure that the same page segments will be found by line2afp and Infoprint using each program's default search path.

For S/370 line data and for ASCII data that you want to format with a page definition, if you are transforming and printing a file by specifying **-odatatype=line** with an AIX print command, you must specify the page segment search path with **-orespath** instead of **pseglib**. For example:

```
enq -odatatype=line -oformdef=myfd -opagedef=mypd
-orespath=/home/greg/resources -Pprinter myfile
```

This option is equivalent to the document attribute **resource-context-page-segment** on the **pdpr** command.

resexit=ProgramName

Specifies the name or the full path name of the resource exit program. This is the program the **line2afp** command calls each time it attempts to retrieve a requested resource from a directory. If you specify the file name

line2afp

without a path, the **line2afp** command searches for the file name in the paths specified by the **PATH** environment variable. If you do not specify this option, the **line2afp** command does not use a resource exit program. The exit program name is case-sensitive.

The value is:

ProgramName

Any valid resource exit program name.

This option is equivalent to the document attribute **resource-exit** on the **pdpr** command.

reslib=PathList

Specifies the paths for the system resource directories. System resource directories typically contain resources that are shared by many users. The directories can contain any AFP resources (fonts, page segments, overlays, page definitions, or form definitions).

For S/370 line data and for ASCII data that you want to format with a page definition, if you are transforming and printing a file by piping line2afp's output to an AIX print command or the pdpr command, you should specify the same resource search path on both sides of the pipe, unless you are sure that the same resources will be found by line2afp and Infoprint using each program's default search path.

For S/370 line data and for ASCII data that you want to format with a page definition, if you are transforming and printing a file by specifying **-odatatype=line** with an AIX print command, you must specify the search path for AFP resources with **-orespath** instead of **reslib**. For example:

```
enq -odatatype=line -oformdef=myfd -opagedef=mypd
-orespath=/home/greg/resources -Pprinter myfile
```

The value is:

PathList

Any valid search path. The **line2afp** command searches the paths in the order in which they are specified.

With AIX, you must use a colon (:) to separate multiple paths.

With NT/2000, you must use a semi-colon (;) to separate multiple paths.

The line2afp command searches for resources in the following order:

- 1. Paths specified by the **userlib** option for miscellaneous user resources, or the **resource-context-user** attribute on the **pdpr** command if **line2afp** was invoked as part of submitting a print job.
- 2. Paths specified by the **fdeflib**, **fontlib**, **ovlylib**, **pdeflib**, and **pseglib** options for specific types of resources or the equivalent options of an AIX print command or equivalent document attributes on the **pdpr** command if **line2afp** was invoked as part of submitting a print job.
- 3. Paths specified by the **reslib** option, or the **-orespath** flag of an AIX print command or the **resource-context** attribute on the **pdpr** command if **line2afp** was invoked as part of submitting a print job.
- 4. Paths specified by the **PSFPATH** environment variable.
- 5. If **line2afp** is invoked as part of submitting a print job, the paths specified with the **resource-context-font**, **resource-context-form-**

definition, **resource-context-overlay**, **resource-context-page-definition**, and **resource-context-page-segment** physical printer attributes for specific types of resources.

- 6. With AIX:
 - a. /usr/lpp/psf/reslib
 - b. /usr/lpp/afpfonts
 - c. /usr/lpp/psf/fontlib
- 7. With Windows NT or Windows 2000, where *install_path* indicates the path where you installed Infoprint Manager:
 - a. \install_path\reslib
 - b. \install_path\afpfonts
 - c. \install_path\fontlib

This option is equivalent to the document attribute **resource-context** on the **pdpr** command.

trc={yes | no}

Specifies whether the input file contains table reference characters (TRCs). Some applications may produce output that uses different fonts on different lines of a file by specifying TRCs at the beginning of each line after the carriage-control character, if one is present.

Values are:

yes The input file contains table reference characters.

 $\underline{\mathbf{no}}$ The input file does not contain table reference characters. \mathbf{no} is the default.

Consider the following when you use TRCs:

- The order in which the fonts are specified in the **chars** option establishes which number is assigned to each associated TRC. For example, the first font specified is assigned 0, the second font 1, and so on.
- If you specify trc=yes but TRCs are not contained in the file, the line2afp command interprets the first character (or second, if carriage-control characters are used) of each line as the font identifier. Consequently, the font used to process each line of the file may not be the one you expect, and one byte of data will be lost from each line.
- If you specify trc=no or you do not specify trc at all, but your data contains a TRC as the first character (or second if carriage-control characters are used) of each line, the line2afp command interprets the TRC as a text character in the processed output, rather than using it as a font identifier.

This option is equivalent to the document attribute **table-reference-characters** on the **pdpr** command.

userlib=PathList

Specifies the names of user directories containing AFP resources for processing the input file. The directories can contain any AFP resources (fonts, page segments, overlays, page definitions, or form definitions).

By convention, these resources are typically used by one user, as opposed to the system resources (specified with the **reslib** option) that are shared

by many users. Therefore, you should use the **userlib** option to specify resources that are not retrieved with the **fdeflib**, **fontlib**, **ovlylib**, **pdeflib**, or **pseglib** options.

The value is:

PathList

Any valid search path. The **line2afp** command searches the paths in the order in which they are specified.

With AIX, you must use a colon (:) to separate multiple paths.

With NT/2000, you must use a semi-colon (;) to separate multiple paths. $\,$

The line2afp command searches for resources in the following order:

- 1. Paths specified by the **userlib** option, or the **resource-context-user** attribute on the **pdpr** command if **line2afp** was invoked as part of submitting a print job.
- 2. Paths specified by the **fdeflib**, **fontlib**, **pdeflib**, **pseglib**, **ovlylib**, options for specific types of resources or the equivalent options of an AIX print command or equivalent document attributes on the **pdpr** command if **line2afp** was invoked as part of submitting a print job.
- 3. Paths specified by the **reslib** option, or the **-orespath** flag of an AIX print command or the **resource-context** attribute on the **pdpr** command if **line2afp** was invoked as part of submitting a print job.
- 4. Paths specified by the **PSFPATH** environment variable.
- 5. If line2afp is invoked as part of submitting a print job, the paths specified with the resource-context-font, resource-context-form-definition, resource-context-overlay, resource-context-page-definition, and resource-context-page-segment physical printer attributes for specific types of resources.
- 6. With AIX:
 - a. /usr/lpp/psf/reslib
 - b. /usr/lpp/afpfonts
 - c. /usr/lpp/psf/fontlib
- 7. With Windows NT or Windows 2000, where *install_path* indicates the path where you installed Infoprint Manager:
 - a. \install_path\reslib
 - b. \install_path\afpfonts
 - c. \install_path\fontlib

Examples

• To print a "flat" ASCII file called timesheet that does not contain carriage controls, on the Infoprint printer named servC-lp, enter:

```
pdpr -p servC-lp -x "document-format=line-data
  form-definition=FDEF1 page-definition=PDEF3 input-exit=apka2e
  carriage-control-type=none" timesheet
```

Because you specified document-format=line data, Infoprint invokes the **line2afp** command. Because you specified form-definition=FDEF1, the **line2afp** command uses the FDEF1 form definition. Because you specified page-definition=PDEF3, the **line2afp** command uses the PDEF3 page definition.

If the PDEF3 page definition specifies 2-up printing, then the timesheet file prints 2-up — that is, with two "pages" printed side by side on the same physical page.

• On AIX, assume that you want to print a S/370 line data file called statements. Assume that the file contains ANSI carriage-control characters.

To print this file on the Infoprint printer named servA-lp; use form definition FDEF6 in your current directory (/usr/liz/fdefs) and use page definition P1USER10 which might be in the directory /usr/res/pdefs1 or in the directory /usr/res/pdefs2, enter:

```
pdpr -p servA-lp -x "document-format=line-data form-definition=FDEF6
  resource-context=/usr/liz/fdefs page-definition=P1USER10
  resource-context-page-definition=/usr/res/pdefs1:/usr/res/pdefs2
  carriage-control-type=ansi-ebcdic
  new-line-options=counted-4-octet-aligned"
  /usr/370/statements
```

- Because you specified document-format=line data, Infoprint invokes the line2afp command.
- Because you specified page-definition=P1USER10, the pdpr command tells the line2afp command to use the page definition named P1USER10.
- Because you specified resource-context-page-definition, the pdpr command tells the line2afp command to search the two directories you specified for the page definition.
- Because you specified form-definition=FDEF6, the pdpr command tells the line2afp command to use the form definition named FDEF6.
- Because you specified carriage-control-type=ansi-ebcdic, and new-line-options=record, the pdpr command gives line2afp information about the data stream format of statements.
- Suppose you downloaded a file called myfile from a S/370 host to the Windows NT/2000 PC. The file transfer process converted the file's EBCDIC encoding to ASCII; the file still retains table reference characters and carriage controls. The file also retains the line length it had on the host (100 characters long). Also suppose that your current directory is d:\Host.Files.

To print this file on the Infoprint printer BServ-lp; use the coded fonts Courier 12-pitch (X042B2) and Times New Roman 14-pitch (X0N2D2) for the output; use the form definition called F1USER10 in your current directory; and use the page definition called MYP1 (which does not name any fonts) in your current directory, enter:

```
pdpr -X 370files.X myfile
```

where the attributes file named 370files.X contains the following settings:

```
document-format=line-data
chars=42B2,N202
form-definition=F1USER10
resource-context=d:\Host.Files
page-definition=MYP1
resource-context-page-definition=d:\Host.Files
new-line-options=record,100
table-reference-characters=yes
carriage-control-type=ansi-ascii
printer-name-requested=BServ-lp
```

- Because you specified document-format=line-data, Infoprint invokes the line2afp command.
- The page definition you specified with page-definition does not name any fonts, but the input file contained table reference characters that indicate

when fonts should be changed. You specified table-referencecharacters=yes and chars=42B2,N2D2, and pdpr passes these values to line2afp.

You had to use resource-context-page-definition to specify the path to the page definition; line2afp does not automatically look in your current directory.

- Because you specified chars=42B2, N2D2, pdpr tells line2afp to associate font 42B2 with the first table reference character, and font N2D2 with the second table reference character. Any lines in the input file that begin with table reference character 0 will now print using font 42B2; lines beginning with table reference character 1 will print using font N2D2.
- Because you specified form-definition=F1USER10, pdpr tells line2afp to use form definition F1USER10. You had to use resource-context to specify the path to the form definition; pdpr and line2afp do not automatically look in your current directory.
- Suppose you downloaded a file called myfile from a S/370 host to the RS/6000. The file transfer process converted the file's EBCDIC encoding to ASCII; the file still retains table reference characters, plus ANSI carriage controls. You want to print this file on the Infoprint printer servC-1p, but you do not have any ASCII fonts; you only have the EBCDIC coded fonts Gothic 10-pitch (X0GT10) and Gothic 12-pitch (X0GT12).

To print this file using the form definition called F1USER10 and the page definition called MYPDEF2, which does not name any fonts, enter:

```
pdpr -p servC-lp -x "document-format=line-data
   chars=GT10,GT12 input-exit=apka2e
   form-definition=F1USER10 page-definition=MYPDEF2
   table-reference-characters=yes
   carriage-control-type=ansi-ebcdic
   resource-context=/usr/mydir" myfile
```

- Because you specified document-format=line-data, Infoprint invokes the line2afp command.
- The page definition you specified with **page-definition** does not name any fonts, but the input file contains table reference characters that specify when fonts are to be changed. You specified table-reference-characters=yes and chars=GT10,GT12, and pdpr passes these values to line2afp.
- Because you specified chars=GT10,GT12, pdpr tells line2afp to associate font GT10 with the first table reference character, and font GT12 with the second table reference character. Any lines in the input file that begin with table reference character 0 will now print using font GT10; lines beginning with table reference character 1 will print using font GT12.
- Because you specified input-exit-apka2e, pdpr tells line2afp to convert the ASCII input file into EBCDIC so you can use your EBCDIC coded fonts (GT10 and GT12). Your carriage controls are also in EBCDIC now, so you have to specify carriage-control-type-ansi-ebcdic. This example assumes you have /usr/lpp/psf/bin in your PATH environment variable.
- Because you specified form-definition=F1USER10, pdpr tells line2afp to use form definition F1USER10. You had to use resource-context to specify the path to the form definition; pdpr and line2afp do not automatically look in your current directory.

Files

For AIX:

/usr/lpp/psf/bin/line2afp

Symbolic link to the acif command

/usr/lpp/psf/bin/acif

The acif command

/usr/lpp/psf/acif/apkinp.c, apkind.c, apkres.c, apkout.c, apka2e.c, asciinp.c asciinpe.c

acif user exits (see AFP Conversion and Indexing Facility: User's Guide for more information)

/usr/lpp/psf/bin/apka2e, apkinp, apkind, apkres, apkout, apka2e, asciinp, asciinpe

User exit executables (see AFP Conversion and Indexing Facility: User's Guide for more information)

/usr/lpp/psf/bin/Makefile

The build rules for the ACIF user exits

/usr/lpp/psf/acif/apkexits.h

C language header file for the ACIF user exits

For NT/2000:

install_path\bin\line2afp.exe

The acif executable

install path\bin\acif.exe

The acif command

install_path\exits\acif\apkinp.c, apkind.c, apkres.c, apkout.c, apka2e.c, asciinp.c asciinpe.c

acif user exits (see AFP Conversion and Indexing Facility: User's Guide for more information)

install_path\bin\apka2e.dll, apkinp.dll, apkind.dll, apkres.dll, apkout.dll, apka2e.dll, asciinp.dll, asciinpe.dll

User exit executables (see AFP Conversion and Indexing Facility: User's Guide for more information)

install_path\exits\acif\apkexits.h

C language header file for the ACIF user exits

install_path\exits\acif\apka2e.dsw, apkinp.dsw, apkind.dsw, apkres.dsw, apkout.dsw, apka2e.dsw, asciinp.dsw, asciinpe.dsw

Microsoft Visual C++ 6.0 Workspaces for the user exists

install_path\exits\acif\apka2e.dsp, apkinp.dsp, apkind.dsp, apkres.dsp, apkout.dsp, apka2e.dsp, asciinp.dsp, asciinpe.dsp

Microsoft Visual C++ 6.0 Project files for the user exits.

Messages

For AIX, message files for the **line2afp** transform can be found in **/usr/lib/nls/msg/**LANG/**acif.cat**, where LANG is the name of a locale, for example, en US.

pcl2afp Command: Transforms PCL Data to AFP

Syntax

```
pcl2afp [-aOutputType] [-C ConfigurationFile] [-c] [-i nnnn]
        [-device ['plex,] [inputn=(pcl_bin=m)][inputn=(pcl_bin=m)']...]
        [-I nnnn.nnnu] [-M nnnnn] [-o OutputFile] [-P nnnnn]
        [-p PageRange] [-q] [-r nnn] [-S ServerName] [-s nnnn]
        [-w nnnn.nnnu] [-x nnnn.nnnu] [-y nnnn.nnnu] [InputFile ...]
```

Description

The pcl2afp command transforms a PCL data stream file into an AFP data stream file.

The PSF DSS runs the pcl2afp command automatically whenever:

- Infoprint identifies the format of a document in a print job as PCL.
- You use the pdpr command to specify document-format=pcl with the -x flag or in an attributes file.
- You specify a data type of -odatatype=pcl with an AIX print command (enq, lp, or **qprt**) or with the **lprafp** command.

If you specify multiple values of the same flag, pcl2afp uses the last value specified, with the exception of the -p flag. Multiple values of the -p flag are accumulated and the pages identified for printing are printed in normal numerical sequence, regardless of the order you specify.

When using the pcl2afp command, you can specify an optional input file name. If you do not specify an input file name, pcl2afp uses standard input. The output file name is also optional; if you do not specify one, the pcl2afp command writes the results to standard output.

Note the following about the flags you can specify with the pcl2afp command:

- 1. You can pass flags to pcl2afp using the other-transform-options document attribute on the Infoprint pdpr command or the -o flag of the AIX print commands (enq, lp, and qprt) and the Infoprint lprafp command.
- 2. When you run pcl2afp as a standalone transform, flags can appear anywhere on the command line with or without a blank in the flag and value pair. When you specify pcl2afp transform flags with the other-transform-options attribute, any string containing a blank must be surrounded by single quotes. Do not use a blank between the flag and the value when you specify pcl2afp transform flags with an AIX print command or with the lprafp command.
- 3. When you specify flags with the pcl2afp command, pcl2afp echoes them back to your display along with the settings for the flags. To suppress the command echoing, enter the -q (quiet) flag along with the pcl2afp command.
- 4. The order in which Infoprint uses PCL options is as follows:
 - a. Any options you specify on the command line with the pcl2afp command (for example, -r300), including values contained in the customized configuration file you specify with the pcl2afp -C command. If you specify the same option more than once, Infoprint uses the last value.
 - b. Values contained in the configuration file, pcl2afp.cfg, in the current directory, if you invoked pcl2afp directly. If you invoked pcl2afp indirectly

- by submitting a print job with a data type of PCL, **pcl2afp** ignores any configuration files in the current directory, and proceeds to step 4c.
- c. Values contained in the pcl2afp.cfg file in the user's home directory.
- d. Values contained in the default **pcl2afp** command configuration file:

For AIX

/usr/lpp/psf/pcl2afp/pcl2afp.cfg

For NT/2000

install_path\pcl2afp\pcl2afp.cfg

- e. Values contained in the customized configuration file you specify with the pcl2afpd -C command.
- f. Values contained in the default pcl2afpd daemon configuration file:

For AIX

/usr/lpp/psf/pcl2afp/pcl2afpd.cfg

For NT/2000

install_path\pcl2afp\pcl2afpd.cfg

- g. Values contained in the pcl2afpd.cfg file when pcl2afpd was started.
- h. The defaults that are built into **pcl2afpd**. These defaults are the same as the defaults for the **pcl2afp** flags.
- 5. The position of PCL data on the page depends on the interaction of the -1 and -w flags, the -x and -y flags, and the form definition you use. In general, to position data on the page:
 - Use -1 and -w to set the physical page dimensions.
 - Use a form definition that specifies zero vertical offset and zero horizontal offset (for example, F100S, F100D, or F100T) or specify X and Y offsets of 0 when you submit the print job. For more information, see page 275.
 - Use -x and -y to avoid any areas that your printer cannot print.
- 6. You can specify the pcl2afp flags and values with the pcl2afp command, with the pdpr -x "other-transform-options" command, or with enq -o, lp -o, qprt -o, or lprafp -o command. You can also specify equivalent attributes with the -x flag or in an attributes file with the pdpr command.

Note: If you are migrating from PSF for AIX, see "Appendix B. Migrating PSF for AIX Job Script Keywords to Infoprint Equivalents" on page 715 for a table of attributes equivalent to the job script keywords that you use to specify flags and values for transforms.

Limitations

- The **pcl2afp** transform must be installed, and the **pcl2afpd** daemon must be running.
- PCL data can contain device commands (for example, to begin or end duplexing
 or to change the input bin). Because the AFP architecture defines those device
 functions in a form definition resource instead of the print data, the pcl2afp
 transform ignores the device commands in the print data. To access those device
 functions (such as duplexing and bin selection), you must specify them in the
 form definition or attributes file, or on a print command, when you print the
 job.
- Resolution conversion algorithms may yield degraded appearance when used to reduce the resolution of a data stream. For this reason, pcl2afp may degrade the

- appearance of higher-resolution data streams when used with 240-pel printers. You should verify that print fidelity is satisfactory.
- There are subtle differences between PCL4 and PCL5e when it comes to handling fonts. While many PCL4 files will work with pcl2afp, some may not produce the expected output.

Flags and Values

-a {IO1_G4 | IM1 | IO1 | IO1_MMR | PSEG_IO1_G4 | PSEG_IM1 | PSEG_IO1 | PSEG_IO1_MMR | OVLY_IO1_G4 | OVLY_IM1 | OVLY_IO1 | OVLY_IO1 MMR}

Determines the type of AFP data stream image to generate for each page in the PCL file.

Values are:

IO1 G4

Compressed Image Object Content Architecture (IOCA) image in Modified TSS (formerly CCITT) T.6 G4 Facsimile Coding Scheme (G4 MMR) format. This is the recommended output type because it takes up less space on the fixed disk, and it prints faster. It is the default specified in the **pcl2afpd** daemon and **pcl2afp** command configuration files.

Note: The IBM 3812 and 3816 printers do not support printing with an image type of **IO1_G4**. For these printers, specify an image type of **IO1_MMR** because it is the compressed image type supported by these printers, and it will result in faster printing than uncompressed image types.

PPDS, PCL, and TCP/IP-attached IPDS printers can print IOCA images; however, only channel-attached printers that have the Advanced Function Image and Graphics (AFIG) feature installed can print IOCA images. Therefore, if you are printing images on channel-attached printers without the AFIG feature, select the **IM1** value.

IM1 IM1 image. This type of image is not compressed.

IO1 IOCA image. This type of image is not compressed.

IO1_MMR

Compressed IOCA image in Modified Modified Read (MMR) format.

PSEG_IO1_G4 | PSEG_IM1 | PSEG_IO1 | PSEG_IO1_MMR Page segment of the specified image type.

Note: When generating page segments from multiple-page documents, you may want to use the **-p** flag to select which page is to be made into a page segment; otherwise, multiple page segments will be created, one for each page of PCL.

OVLY_IO1_G4 | OVLY_IM1 | OVLY_IO1 | OVLY_IO1_MMR Overlay of the specified image type.

Note: When generating overlays from multiple-page documents, you may want to use the **-p** flag to select which page is to

be made into an overlay; otherwise, multiple overlays will be created, one for each page of PCL.

This flag is similar to the **image-out-format** document attribute on the **pdpr** command.

-C ConfigurationFile

Specifies the path and file name of the customized configuration file **pcl2afp** uses with the transform. If you specify the **-C** flag with an AIX print command (**enq**, **lp**, or **qprt**), or with the **lprafp** command. specify the fully qualified name of the file, including its path; for example:

For AIX

/usr/lpp/psf/pcl2afp/myfile.cfg

For NT/2000

d:\pcl\myfile.cfg

-c Concatenates multiple input files without putting a Esc-E (end of job) characters between the files. The pcl2afp command interprets the input files as a continuous data stream, and processes them as if they were one PCL job. This flag can be useful when processing PCL files with inline resources.

Note: Do not use this flag when you perform the PCL-to-AFP data stream transform by submitting a print job with the **pdpr** command.

InputFile ...

Specifies one or more input files to be transformed. If you specify more than one input file name, the **pcl2afp** command concatenates the files and separates them with the Esc-E (end of job) characters. The results of the transform are written to a single output file (if one is specified) or to standard output.

In addition, you can specify PCL inline resource files as input files to the <code>pcl2afp</code> command. The file name of the inline resource file must precede the file name of the PCL print file so that <code>pcl2afp</code> concatenates the files in the correct order. The <code>pcl2afp</code> command concatenates the resources in front of the print file when the <code>-c</code> flag is specified.

If you do not specify an input file, **pcl2afp** uses standard input. If the **pcl2afp** command cannot read from standard input, the command issues a message.

-device '[plex,] [inputn=(pcl_bin=m)][inputn=(pcl_bin=m)][inputn=...]'

Specifies whether to recognize the plex command, and optionally, how to associate the AFP input tray (inputn, where n is a value between 1 to 255) with the pcl bin (pcl_bin=m, where m is a value between 0 to 59). When you do not specify inputn=(pcl_bin=n) with plex, Infoprint recognizes the plex command with no tray mappings.

Note: You can specify **input***n*=(**pcl_bin**=*m*) up to twenty times.

-j {20 | 1 to 9998 | 9999}

Specifies the maximum amount of time, in minutes, to spend processing the job.

Values are:

20 20 minutes, the default

1 to 9998

The timer ranges from 1 to 9998 minutes, in one-minute increments

9999 No time limit

-l nnnn.nnnu

Specifies the length of the generated image; nnnn.nnn is a number that can optionally contain a decimal point, and u is the units in inches (i) or millimeters (m). If you do not specify a unit (i or m), then pcl2afp uses pels as the unit type. You cannot specify fractional values (that is, you cannot use a decimal point) for pels.

Note: If a text margin is already built into the file, try **-l11i** to set the length to 11 inches.

For 240-pel resolution printers, values are:

11i 11 inches, the default

16 to 5280

The length can be from 16 pels to 5280 pels, 0.067i to 22.002i, or 1.701m to 558.852m. For example, the following are all valid:

- -1 40m
- -1 200.5m
- -1 13i
- -1 4000

For 300-pel resolution printers, values are:

11i 11 inches, the default

16 to 6600

The length can be from 16 pels to 6600 pels, 0.053i to 22.001i, or 1.346m to 558.842m. For example, the following are all valid:

- -1 40m
- -1 200.5m
- -1 13i
- -1 5000

For 480-pel resolution printers, values are:

11i 11 inches, the default

16 to 10560

The length can be from 16 pels to 10560 pels, 0.033i to 22.002i, or 0.838m to 558.852m. For example, the following are all valid:

- -1 40m
- -1 200.5m
- -1 13i
- -1 8000

For 600-pel resolution printers, values are:

11i 11 inches, the default

16 to 20400

The length can be from 16 pels to 20400 pels, 0.0267i to 34.001i, or 0.678m to 863m. For example, the following are all valid:

- -1 40m
- -1 200.5m
- -1 13i
- -1 10000

This flag is equivalent to the **image-length** document attribute on the **pdpr** command.

-M {6000 | 2000 to nnnnn}

Determines the maximum amount of memory, in KB, that the transform can use. This flag may be useful if you are processing large PCL jobs that require a lot of memory.

Values are:

6000 6000KB (6MB), the default

2000 to nnnnn

The maximum memory ranges from 2000 to *nnnnn* (where *nnnnn* is the maximum upper limit allowed by AIX or Windows) up to 64MB.

-o OutputFile

Specifies the output path and file into which the transformed PCL files are to be written. If more than one output file is specified, the last specified file name and path is the one used. If no output file is specified, the result is written to standard output.

You cannot use **-o** *OutputFile* on the command line with the **enq**, **lp**, **qprt**, or **lprafp** commands. You can only use **-o** *OutputFile* with the **pcl2afp** command, or with the **other-transform-options** attribute on the **pdpr** command.

This option is equivalent to the **transform-output-file-name** document attribute on the **pdpr** command.

-P {8253 | 924 to nnnnn}

Specifies the TCP/IP port number pcl2afp uses to make a connection with the workstation on which the pcl2afpd daemon is running (set by the -S flag). If your Infoprint installation uses more than one PCL daemon, use this flag to select the daemon.

This port should not be the same port used by the TCP/IP-attached IPDS printer or by the PostScript transform. On AIX, to find out which ports are already being used on your system (although they may or may not be active), look in the /etc/services file.

Values are:

8253 The default port number.

924 to nnnnn

Any valid port number greater than or equal to 924. With AIX, the maximum value, *nnnnn*, depends on AIX, but it must be equal to or less than 65535.

Note: You can only access secure ports, 924 to 1023, with **root** user authority.

-p PageRange

Specifies that the output should only contain selected pages. When you specify multiple **-p** flags, the **pcl2afp** command accumulates them and prints the identified pages in normal numerical order, regardless of the order you specify. Examples of values include:

-p even

Output even pages.

-p odd

Output odd pages.

-р 1-10

Output pages 1 through 10.

-p 10- Output pages from page 10 until the end of the job.

-p 1 -p 3 -p 6

Output pages 1, 3, and 6, in that order.

-p1 -p6 -p3

Output pages 1, 3, and 6, in that order.

This flag is equivalent to the **page-select** document attribute on the **pdpr** command.

-q Quiets (suppresses) the echoing of the pcl2afp command to the display.

-r {240 | 300 | 480 | 600}

Specifies the resolution of the output image. Select the resolution based on the printer on which you will be printing the image.

Values are:

240 pels-per-inch (for example, IBM 3812, 3825, 3827, 3835, and 3900 printers), the default

300 gels-per-inch (for example, IBM 3112, 3116, 4019, 4028, 4029, and 4039 printers and Hewlett-Packard printers)

480 480 pels-per-inch

600 600 pels-per-inch (for example, IBM 3900 printers)

Note: If you specify a resolution that the printer does not support, Infoprint will print the image under most conditions, but with degraded results. Specify the correct resolution for the printer on which you will print the PCL job.

This flag is equivalent to the **default-printer-resolution** document attribute on the **pdpr** command.

-S ServerName

Specifies the name of the AIX system on which the **pcl2afpd** daemon is running. If you do not specify this flag, the *ServerName* defaults to the effective name of the workstation on which you issued the **pcl2afp** command. The value is:

ServerName

Any valid AIX workstation name on which the **pcl2afpd** daemon is installed and running. The name is defined in the **/etc/hosts** file or by a name server, and may be a nickname like **molly**, or a dotted decimal address like **9.99.9.23**.

-s {20 | 1 to 9998 | 9999}

Specifies the maximum amount of time, in minutes, that the PCL interpreter remains idle between jobs before it goes down. When the PCL interpreter is running, it uses some of the workstation memory. If the PCL interpreter goes down, you do not need to bring it back up; the interpreter automatically starts when you submit another PCL job as long as the pcl2afpd daemon is running.

Values are:

The default time is 20 minutes.

1 to 9998

The time is the number of minutes specified in one-minute increments.

9999 There is no time limit.

-w nnnn.nnnu

Specifies the width of the generated image; nnnn.nnn is a number that can optionally contain a decimal point, and u is the units in inches (i) or millimeters (m). If you do not specify a unit (i or m), then pcl2afp uses pels as the unit type. You cannot specify fractional values (that is, you cannot use a decimal point) for pels.

Note: If a text margin is already built into the file, try **-w8.5i** to set the width to 8.5 inches.

For 240-pel resolution printers, values are:

8.5i 8.5 inches, the default

16 to 4080

The width can be from 16 pels to 4080 pels, 0.065i to 17.002i, or 1.641m to 431.852m. For example, the following are all valid:

- -w 40m
- -w 200.5m
- -w 13i
- -w 3300

For 300-pel resolution printers, values are:

8.5i 8.5 inches, the default

16 to 5100

The width can be from 16 pels to 5100 pels, 0.052i to 17.001i, or 1.313m to 431.842m. For example, the following are all valid:

- -w 40m
- -w 200.5m
- -w 13i
- -w 5000

For 480-pel resolution printers, values are:

8.5i 8.5 inches, the default

16 to 8160

The width can be from 16 pels to 8160 pels, 0.065i to 17.002i, or 1.641m to 431.852m. For example, the following are all valid:

- -w 40m
- -w 200.5m
- -w 13i
- -w 6600

For 600-pel resolution printers, values are:

8.5i 8.5 inches, the default

16 to 10200

The width can be from 16 pels to 10200 pels, 0.052i to 17.001i, or 1.313m to 431.842m. For example, the following are all valid:

- -w 40m
- -w 200.5m
- -w 13i
- -w 10000

This flag is equivalent to the **image-width** document attribute on the **pdpr** command.

-x nnnn.nnnu

Specifies an X offset (horizontal offset) of the generated image; nnnn.nnn is a number that can optionally contain a decimal point, and *u* is the units in inches (i) or millimeters (m). If you do not specify a unit (i or m), then pcl2afp uses pels as the unit type. You cannot specify fractional values (that is, you cannot use a decimal point) for pels.

An offset value specifies a border or margin around the generated image to avoid the non-printable areas of some printers. An X-offset value specifies the left and right margins of the generated image.

For all printers, values are:

0.167i 0.167 inches, the default

0 to 8.5i

The X offset can be no more than half of the width (-w) of the generated image. For example, if you specify a width of 13i, then the X offset can be no larger than 6.5i.

This flag is equivalent to the **x-image-shift** document attribute on the **pdpr** command.

Notes:

- 1. The X offset specified with -x must be less than the width specified with -w. If the -x value is greater than or equal to the -w value, a blank page is printed.
- 2. The X-offset value specifies margins on *both* the left and right sides of the page. If you have a width of 8.5 inches and specify an X offset of 5 inches, a blank page will also result because the margins on the left and right sides of the paper exceed the width of the paper.
- 3. PCL processing is slower when you use the -x flag, because the pcl2afpd daemon must stop and re-start the PCL interpreter. You may improve performance by changing the pcl_x_offset value in the pcl2afpd daemon configuration file rather than using -x on a regular basis.

-y nnnn.nnnu

Specifies a Y offset (vertical offset) of the generated image; nnnn.nnn is a number that can optionally contain a decimal point, and u is the units in inches (i) or millimeters (m). If you do not specify a unit (i or m), then pcl2afp uses pels as the unit type. You cannot specify fractional values (that is, you cannot use a decimal point) for pels.

An offset value specifies a border or margin around the generated image to avoid the non-printable areas of some printers. A Y-offset value specifies the top and bottom margins of the generated image.

For all printers, values are:

0.167i 0.167 inches, the default

0 to 8.5i

The Y offset can be no more than half of the width (-w) of the generated image. For example, if you specify a width of 14i, then the X offset can be no larger than 7.0i.

This flag is equivalent to the **y-image-shift** document attribute on the **pdpr** command.

Notes:

- 1. The Y offset specified with -y must be less than the length specified with -l. If the -y value is greater than or equal to the -l value, a blank page is printed.
- 2. The Y-offset value specifies margins on *both* the top and bottom edges of the page. If you have a length of 11 inches and specify an Y offset of 6 inches, a blank page will also result because the margins on the top and bottom of the paper exceed the length of the paper.
- 3. PCL processing is slower when you use the **-y** flag, because the **pcl2afpd** daemon must stop and re-start the PCL interpreter. You may improve performance by changing the **pcl_y_offset** value in the **pcl2afpd** daemon configuration file rather than using **-y** on a regular basis.

Transforming PCL Image Data

The output of the PCL transform (the pcl2afp command) is AFP image data for any type of PCL input, whether it be text or images. The image created by the pcl2afp command minimizes white space within an image block by defining the image block size to be exactly the right size to contain all of the black pels of the image. A PCL image may not print if any part of the image lies outside of the valid printable area. In addition, be aware that using form definitions that specify a non-zero logical page origin may move a valid PCL image out of the printable area; thus, the image won't print.

The pcl2afp command, the pcl2afp.cfg configuration file, and the pcl2afpd.cfg configuration file all let you specify the length and the width of PCL images. Before you use the -l and -w flags of the pcl2afp command or modify the pcl_length and pcl_width options in the configuration file, it's helpful to understand how Infoprint places PCL images on the page.

Figure 1 on page 274 shows an example of a PCL image. This image is 8.5 inches high and 11 inches wide, measured from the lower-left corner of the image.

If you want to print the entire image, specify a length of 11i and a width of 8.5i. When Infoprint prints the image, the upper-left corner of the image is placed at the point on the page called the logical page origin, which is specified in the form definition. The logical page origin is the point on the form where the page of data is positioned, and it is specified as an offset from the top-left corner of the sheet. Therefore, if the form definition has a logical page origin of 0.165 inches from both the left and top sides of the sheet, then the top-left corner of the image is placed 0.165 inches down and to the left of the upper left corner of the sheet.

pcl2afp




Figure 1. A PCL Image

All this gets more complicated if you don't specify the entire image. For example, if you want to crop the image so that you only use the lower left corner, you would specify a width of 7i and a length of 7i with the **pcl2afp** command. The upper left corner of the resulting image is then placed at the logical page origin (Figure 2).




Figure 2. A Cropped PCL Image

In this final example, specify a PCL image that is 8.5 inches wide and 11 inches high. Again, the upper-left corner of the transformed image is placed at the logical page origin. Unless you specify a form definition with the print job that has a zero logical page origin (for example, **F100S**, **F100D**, or **F100T**), the page will not print because part of the image is outside the valid printable area (Figure 3).




Figure 3. A PCL Image Offset from the Top-Left Corner

As you can see from Figure 3, specifying the correct form definition is extremely important, particularly when you are printing a full-page image.

The default length and width values specified in the PCL configuration files, pcl2afp.cfg and pcl2afpd.cfg work with the default form definitions that Infoprint provides for each type of Infoprint printers.

However, if you want to specify exact placement of your PCL output on the page using a zero vertical and horizontal offset from the top-left corner of the page, do one of the following:

- Specify one of the following form definitions:
 - F100S F100D
 - F100T
- Specify an X- and Y-offset value of **0** to override the values set in the form definition, using one of the following:
 - The **-oxoffset** and **-oyoffset** flags on the AIX print commands
 - The X offset and Y offset fields on the SMIT Submit an Infoprint Job panel
 - The **x-image-shift** and **y-image-shift** attributes with the **-x** flag or in an attributes submitted with the **pdpr** command

If you specify a 0 horizontal and vertical offset in the form definition, with an AIX print command, or in an attributes file, the image produced by the **pcl2afp** transform might be printed in the unprintable area of the printer. To avoid printing in the unprintable area, you can specify the -x (X offset) and -y (Y offset) flags on the **pcl2afp** command. These flags add white space to the top and left side of the image produced by the transform, ensuring that no data will print in the unprintable area. For more information about the unprintable area of your printer, refer to *Advanced Function Presentation: Printer Information*.

The pcl2afp and pcl2afpd Configuration Files

Instead of typing flags on the command line with the <code>pcl2afp</code> command, you can use the <code>-C</code> flag to specify a configuration file that contains the flags. In this way, you can simply specify a configuration file name, rather than typing many flags. You may find it convenient to use a configuration file if you repeatedly use the same flags with the <code>pcl2afp</code> command, or if you are using different PCL processing values than the defaults defined by your system support group.

When your system support group installed the pcl2afp transform, a default pcl2afp command configuration file, pcl2afp.cfg, was installed as follows:

For AIX

/usr/lpp/psf/pcl2afp

For NT/2000

install_path\pcl2afp

If you want to create your own files, copy the **pcl2afp.cfg** file and then use a system editor to modify the options in this ASCII file to suit your needs.

A default **pcl2afpd** daemon configuration file, **pcl2afpd.cfg**, was also installed as follows:

For AIX

/usr/lpp/psf/pcl2afp

For NT/2000

install_path\pcl2afp

The **pcl2afpd** daemon configuration file can contain most of the same keywords as the **pcl2afp** command configuration file, plus some keywords that control the operation of the **pcl2afpd** daemon. Values in the command configuration file override values in the daemon configuration file.

Figure 4 on page 277 shows an example of a configuration file.

```
# KEYWORD
                           EQUIVALENT
                                                              PURPOSE
                           pcl2afp FLAG
 port = 8253
                           # -P
                                             which TCP/IP port to use
                           # -S
 server = 127.0.0.1
                                         which server to connect with
 pcl max memory = 6000K
                           # -M
                                        maximum amount of memory that
                                         PCL uses; the 'K' is ignored
 pcl job timeout = 20
                                            maximum number of minutes
                           # -j
                                                   to process PCL job
 pcl server timeout = 20
                                          maximum number of minutes
                                            server waits between jobs
# -w
pcl_length = 11i  # -l
pcl_x_offset = 0.167i  # -x
pcl_y_offset = 0.167i  # -y
pcl_resolution = 240  # -r
pcl_output_type = I01 G4 #
                                             width of generated image
                                            length of generated image
                                               left and right margins
                                               top and bottom margins
                                                resolution of printer
                                        type of AFP image to generate
```

Figure 4. Sample pcl2afp Configuration File

Table 9 shows the **pcl2afp** flags and their equivalent configuration file keywords. To override the values in the default configuration file, **pcl2afp.cfg**, you can do one of the following:

- Specify flags with the pcl2afp command at transform time.
- Specify a configuration file with pcl2afp -C at transform time.
- Specify **pcl2afp** flags with **-o** flags on an AIX print command, or with equivalent attributes with the **-x** flag or in an attributes file on the **pdpr** command, to transform a file and print it at the same time.

Note: If you are migrating from PSF for AIX, see "Appendix B. Migrating PSF for AIX Job Script Keywords to Infoprint Equivalents" on page 715 for a table of attributes equivalent to the job script keywords that you use to specify flags and values for transforms.

Table 9. PCL Printing and Processing Options

pcl2afp Flag	Keyword in pcl2afp Configuration File	Keyword in pcl2afpd Configuration File	
Note: The valid values for configuration file keywords are the same as for the corresponding pcl2afp command flag. For keywords used only in the pcl2afpd daemon configuration file, which have no corresponding command flag, see"pcl2afpd Utility: Starts the pcl2afpd Daemon" on page 190.			
-a OutputType	pcl_output_type=value	pcl_output_type=value	
-C ConfigurationFile	None	None	
-с	None	None	
-device	<pre>device_controls=[plex], [inputn=(pcl_bin=m)] [inputn=(pcl_bin=m) [inputn=]]</pre>	<pre>device_controls=[plex], [inputn=(pcl_bin=m)] [inputn=(pcl_bin=m)[inputn=]]</pre>	
InputFile	None	None	
-j nnnn	pcl_job_timeout=nnnn	pcl_job_timeout=nnnn	

pcl2afp

Table 9. PCL Printing and Processing Options (continued)

pcl2afp Flag	Keyword in pcl2afp Configuration File	Keyword in pcl2afpd Configuration File
-1 nnnn.nnnu	pcl_length=nnnn.nnnu	pcl_length=nnnn.nnnu
-M nnnnn	pcl_max_memory=nnnnn	pcl_max_memory=nnnnn
-o OutputFile	None	None
-Р ппппп	port=PortNumber	port=PortNumber
-p PageRange	None	None
-q	None	None
-r nnn	pcl_resolution=nnn	pcl_resolution=nnn
-S ServerName	server=ServerName	None
-s nnnn	pcl_server_timeout=nnnn	pcl_server_timeout=nnnn
-w nnnn.nnnu	pcl_width=nnnn.nnnu	pcl_width=nnnn.nnnu
-x nnnn.nnnu	pcl_x_offset=nnnn.nnnu	pcl_x_offset=nnnn.nnnu
-у пппп.пппи	pcl_y_offset=nnnn.nnnu	pcl_y_offset=nnnn.nnnu
None	None	log_file=PathName
None	None	mail_command=PathName
None	None	notify=UserID
None	None	pcl_program=PathName
None	None	pcl_support_program=PathName
None	None	work_directory=PathName

Simple Examples

This section shows some simple examples of using **pcl2afp**. For more detailed examples, see "More Complex Examples" on page 279.

• To submit the sample PCL file sample.pcl supplied with Infoprint Manager for AIX to the logical printer named Pserv-lp, enter:

```
enq -PPserv-lp -odatat=pcl /usr/lpp/psf/pcl2afp/sample.pcl
```

• To transform the PCL file myfile into an AFP data stream, and then submit it to the Infoprint logical printer called Pserv-lp, enter:

```
pdpr -p Pserv-lp -x "default-printer-resolution=300" myfile
```

```
or
pcl2afp -r300 myfile | pdpr -p Pserv-lp
```

Note: You need to specify a resolution of 300 pels (default-printer-resolution=300) because the Pserv-lp printer routes jobs to a 4019 printer device. The 4019 is a 300-pel resolution printer and the default resolution for the pcl2afp command is 240 pels.

• To transform the PCL file myfile into an AFP data stream, with an image that is 8 inches high and 5 inches wide, and write the result to a file called myfile.afp, enter:

```
pcl2afp -1 8i -w 5i -o myfile.afp myfile
or
pcl2afp -1 8i -w 5i myfile > myfile.afp
```

 To transform the PCL myfile file into an AFP data stream in 300-pel resolution, as an IO1_MMR image, and send the result to the printer with the pdpr command, enter:

```
pcl2afp -aIO1_MMR -r300 myfile | pdpr -X myafp.X -p lserv-lp
or
pdpr -X mypcl.X myfile -p Pserv-lp
```

where the attributes file named myafp.X contains the following settings:

```
document-format=modca-p
printer-name-requested=robin-lp
```

and the attributes file named mypcl.X contains the following settings:

```
document-format=pcl
printer-name-requested=robin-lp
image-output-format=io1_mmr
default-printer-resolution=300
```

• Assume that the PCL file myfile uses the BarKode.pcl font that is a PCL resource on a system named molly. Also assume that the pcl2afpd daemon is running on robin, but you are logged in to the AIX system named molly. To transform myfile into an AFP data stream, but not print it:

```
pcl2afp -S robin -c -o myfile.afp BarKode.pcl myfile
```

The -c flag concatenates the two input files, with the file BarKode.pcl first, so that the two files are processed together. In this way, myfile uses BarKode.pcl as an inline resource.

• Because the **pcl2afp** transform does not accept HP-GL/2 directly as input, you can use the **-c** flag to concatenate some sample PCL files that allow the HP-GL/2 file to be processed. To transform the HP-GL/2 file myfile.gl into a MO:DCA-P data stream file myfile.afp, enter:

For AIX

```
pcl2afp -o myfile.afp -c /usr/lpp/psf/pcl2afp/gl_before.pcl
  myfile.gl /usr/lpp/psf/pcl2afp/gl_after.pcl
```

For NT/2000

```
pcl2afp -o myfile.afp -c install_path\pcl2afp\gl_before.pcl
myfile.gl install_path\pcl2afp\gl_after.pcl
```

The **-c** flag concatenates the three input files, making myfile.gl appear as a PCL file that includes HP-GL/2 commands.

More Complex Examples

This section shows the following examples of transforming and printing PCL files:

- "Printing a PCL File"
- "Printing a PCL File with a Defined Image Size" on page 280
- "Printing a PCL File at 300-Pel Resolution" on page 282
- "Printing a PCL File with a Custom Configuration File" on page 283
- "Transforming Three PCL Files at the Same Time" on page 285
- "Transforming an HP-GL/2 File" on page 285

Printing a PCL File

In this example, you will submit a PCL file called PCLFile1 for printing on an Infoprint printer called molly-lp.

Configuration Assumptions: This example assumes the following tasks have been performed by your system support group:

- Infoprint, including the **pcl2afp** transform, has been installed on the workstation on which the **pcl2afp** command is executed.
- The **pcl2afpd** daemon has been started on the workstation on which the **pcl2afp** command is executed.
- A 3825 printer device has been installed and defined to Infoprint. A logical printer called molly-lp routes jobs to the physical printer representing that device.

Using the AIX SMIT Submit an Infoprint Job Panel: To print this example, do the following steps:

1. On the AIX command line, enter:

smit ipsub

SMIT displays a list of attributes files to select from.

Note: The attributes file must contain the **document-format** attribute. Although Infoprint can determine the document format without being told, SMIT cannot.

Select template_PCL.X.

SMIT displays the Submit an Infoprint Job panel.

- 3. Enter PCLFile1 in the NAMES of files to be submitted in the job field.
- 4. Select molly-lp from the list for the Logical PRINTER field.
- 5. Press Enter (ASCII interface) or select **Do** (AIXwindows interface).

Using the Command Line Options: To print this example, enter the following on the command line: or

```
pdpr -p molly-lp PCLFile1
```

or on AIX

enq -P molly-lp PCLFile1

Using an Attributes File with the pdpr Command: To print this example, enter the following on the command line:

```
pdpr -X pclex1.X -p molly-lp PCLFile1
```

where the attributes file named pclex1.X contains the following settings:

document-format=pcl

A data type of PCL

Printing a PCL File with a Defined Image Size

In this example, you will submit a PCL file called PCLFile2.pcl for printing on an Infoprint printer called Dserv-lp. In addition, you will specify the form definition F100S and an image size of 9 inches in length and 6 inches in width, measured from the upper-left corner of the image.

Configuration Assumptions: This example assumes the following tasks have been performed by your system support group:

- Infoprint, including the **pcl2afp** transform, has been installed on the workstation on which the **pcl2afp** command is executed.
- The pcl2afpd daemon has been started on the workstation on which the pcl2afp command is executed.

 A 3900 printer device has been installed and defined to Infoprint. A logical printer called Dserv-lp routes jobs to the physical printer representing that device.

Using the AIX SMIT Submit an Infoprint Job Panel: To print this example, do the following steps:

1. On the AIX command line, enter:

```
smit ipsub
```

SMIT displays a list of attributes files to select from.

Note: The attributes file must contain the **document-format** attribute. Although Infoprint can determine the document format without being told, SMIT cannot.

2. Select template PCL.X.

SMIT displays the Submit an Infoprint Job panel.

- 3. Enter PCLFile2.pcl in the NAMES of files to be submitted in the job field.
- 4. Select Dserv-lp from the list for the Logical PRINTER field.
- 5. Enter F100S in the FORM DEFINITION name field.
- 6. Enter 9i in the Image LENGTH field.
- 7. Enter 6i in the Image WIDTH field.
- 8. Press Enter (ASCII interface) or select Do (AIXwindows interface).

Using the Command Line Options: To print this example, enter the following on the command line:

```
pdpr -p Dserv-lp -x "form-definition=F100S
   image-length=19i image-width=6i" PCLFile2.pcl

or on AIX
eng -P Dserv-lp -oformdef=F100S -o-l9i -o-w6i PCLFile2.pcl
```

Infoprint identifies the input data type as PCL without being told. Infoprint automatically runs **pcl2afp**, and passes -19i and -w6i from the **enq** command to **pcl2afp**.

You can get the same result by piping the output of the **pcl2afp** command to the input of the **enq** command:

```
pcl2afp PCLFile2.pcl -19i -w 6i | enq -P Dserv-lp -oformdef=F100S
```

Using an Attributes File with the pdpr Command: To print this example, enter the following on the command line:

```
pdpr -X pclex2.X -p Dserv-lp PCLFile2.pcl
```

where the attributes file named pclex2.X contains the following settings:

image-length=9i

Image length is nine inches

image-width=6i

Image width is six inches

form-definition=F100S

Use the F100S formdef for printing the job

Printing a PCL File at 300-Pel Resolution

In this example, you will submit a PCL file called PCLFile3.pcl for printing on an Infoprint printer called G4019-Serv1. In addition, you will specify a resolution of 300 pels.

Configuration Assumptions: This example assumes the following tasks have been performed by your system support group:

- Infoprint, including the pcl2afp transform, has been installed on the workstation on which the pcl2afp command is executed.
- The pcl2afpd daemon has been started on the workstation on which the pcl2afp command is executed.
- The 4019 printer has been installed and defined to AIX. A logical printer, named G4019-Serv1, has been configured to route jobs to the physical printer representing the 4019.

Using the AIX SMIT Submit an Infoprint Job Panel: To print this example, do the following steps:

1. On the AIX command line, enter:

```
smit ipsub
```

SMIT displays a list of attributes files to select from.

Note: The attributes file must contain the document-format attribute. Although Infoprint can determine the document format without being told, SMIT cannot.

2. Select template PCL.X.

SMIT displays the Submit an Infoprint Job panel.

- 3. Enter PCLFile3.pcl in the NAMES of files to be submitted in the job field.
- 4. Select G4019-Serv1 from the list for the Logical PRINTER field.
- 5. Select 300 from the list for the Printer RESOLUTION field.
- 6. Press Enter (ASCII interface) or select Do (AIXwindows interface).

Using the Command Line Options: To print this example, enter the following on the command line:

```
pdpr -o G4019-Serv1 -x "default-printer-resolution=300" PCLFile3.pcl
```

```
or on AIX
```

```
enq -P G4019-Serv1 -o-r300 PCLFile3.pcl
```

Infoprint determines that the input data type is PCL and automatically runs pcl2afp, passing -r300 from the enq command to pcl2afp.

You can get the same result by piping the output of the pcl2afp command to the input of the **enq** command:

```
pcl2afp PCLFile3.pcl -r 300 | enq -P G4019-Serv1
```

Using an Attributes File with the pdpr Command: To print this example, enter the following on the command line:

```
pdpr -X pclex3.X PCLFile3.pcl
```

where the attributes file named pclex3.X contains the following settings:

document-format=pcl

A data type of PCL

default-printer-resolution=300

Image resolution is 300 pels

printer-name-requested=G4019-Serv1

Submit the job to the G4019-Serv1 logical printer

Printing a PCL File with a Custom Configuration File

In this example, you will submit a PCL file called PCLFile4.pcl for printing on an Infoprint printer called molly-lp. In addition, you will specify the form definition F100D, as well as a customized PCL configuration file called custom.cfg, which is located in the directory

For AIX

/usr/lpp/psf/pcl2afp

For NT/2000

install_path\pc12afp

The output file name is PCLFile4.afp.

Configuration Assumptions: This example assumes the following items have been done by your system support group:

- Infoprint, including the **pcl2afp** transform, has been installed on the workstation on which the **pcl2afp** command is executed.
- The pcl2afpd daemon has been started on the workstation on which the pcl2afp command is executed.
- A 3825 printer device has been installed and defined to Infoprint. A logical printer called molly-lp routes jobs to the physical printer representing that device.
- The customized configuration file is custom.cfg, located in the pcl2afpdirectory; and you have permission to read this file.

Using the AIX SMIT Submit an Infoprint Job Panel: To print this example, do the following steps:

1. On the AIX command line, enter:

smit ipsub

SMIT displays a list of attributes files to select from.

Note: The attributes file must contain the **document-format** attribute. Although Infoprint can determine the document format without being told, SMIT cannot.

Select template_PCL.X.

SMIT displays the Submit an Infoprint Job.

- 3. Enter PCLFile4.pcl in the NAMES of files to be submitted in the job field.
- 4. Select molly-lp from the list for the Logical PRINTER field.
- 5. Enter F100D in the FORM DEFINITION name field.
- Enter /usr/lpp/psf/pcl2afp/custom.cfg in the PCL transform OPTIONS file field
- 7. Press Enter (ASCII interface) or select Do (AIXwindows interface).

Using the Command Line Options: To print this example, enter the following on the command line:

For AIX

```
pdpr -p molly-lp -x "form-definition=F100D
   other-transform-options='-o-C/usr/lpp/psf/pcl2afp/custom.cfg'"
   PCLFile4.pcl

or
enq -P molly-lp -oformdef=F100D
   -o-C/usr/lpp/psf/pcl2afp/custom.cfg PCLFile4.pcl
```

For NT/2000

install_path\pcl2afp\custom.cfg

Infoprint determines the data type, automatically runs pcl2afp, and passes:

For AIX

-C/usr/lpp/psf/pcl2afp/custom.cfg to pcl2afp (When you use the -C flag with an AIX print command, no spaces are allowed between the -C flag and the configuration file name, and the configuration file name must be fully qualified).

For NT/2000

-C install_path\custom.cfg

(

On AIX, you can get the same result by invoking **pcl2afp** first, then using **enq** to process the output of **pcl2afp**:

```
pcl2afp PCLFile4.pcl -o PCLFile4.afp -C /usr/lpp/psf/pcl2afp/custom.cfg enq -P molly-lp -oformdef=F100D PCLFile4.afp
```

Using an Attributes File with the pdpr Command: To print this example, enter the following on the command line:

```
pdpr -X pclex4.X PCLFile4.pcl
```

where the attributes file named pclex4.X contains the following settings:

For AIX:

document-format=pcl

A data type of PCL

other-transform-options='-C /usr/lpp/psf/pcl2afp/custom.cfg'

Use the /usr/lpp/psf/pcl2afp/custom.cfg pcl2afp configuration file

form-definition=F100D

Use the F100D form definition for printing the job

printer-name-requested=molly-lp

Submit the job to the molly-lp logical printer

For NT/2000:

document-format=pcl

A data type of PCL

$other-transform-options='-C \ install_path \\ \ \ pcl2afp \\ \ \ \ custom.cfg'$

Use the *install_path***pcl2afp\custom.cfg** configuration file

form-definition=F100D

Use the F100D form definition for printing the job

printer-name-requested=molly-lp

Submit the job to the molly-lp logical printer

Transforming Three PCL Files at the Same Time

In this example, you will transform three PCL files to create one AFP data stream file. The PCL files are called PCLFile5.pcl, PCLFile6.pcl, and PCLFile7.pcl. You write the output of the transform to the file called PCLFile0.afp. Other options you want to specify are an image type of **IM1**.

Configuration Assumptions: This example assumes the following tasks have been performed by your system support group:

- Infoprint, including the **pcl2afp** transform, has been installed on the workstation on which the **pcl2afp** command is executed.
- The **pcl2afpd** daemon has been started on the workstation on which the **pcl2afp** command is executed.

Using the AIX SMIT Submit an Infoprint Job Panel: You cannot perform the PCL to AFP data stream transform using the Submit an Infoprint Job panel without also submitting the output file as a print job.

Using the Command Line Options: To transform this example, enter the following on the command line:

pcl2afp -aim1 PCLFile5.pcl PCLFile6.pcl PCLFile7.pcl -oPCLFile0.afp

Transforming an HP-GL/2 File

Because the <code>pcl2afp</code> transform does not accept HP-GL/2 directly as input, you can use the <code>-c</code> flag to concatenate some sample PCL files that allow the HP-GL/2 file to be processed. To transform the HP-GL/2 file <code>myfile.gl</code> into a MO:DCA-P data stream file <code>myfile.afp</code>, enter:

For AIX

```
pcl2afp -o myfile.afp -c /usr/llp/psf/pcl2afp/gl_before.pcl
   myfile.gl /usr/lpp/psf/pcl2afp/gl_after.pcl
```

For NT/2000

```
pcl2afp -o myfile.afp -c install\_path \pcl2afp/gl\_before.pcl myfile.gl install\_path \pcl2afp \gl\_after.pcl
```

The **-c** flag concatenates the three input files, making myfile.gl appear as a PCL file that includes HP-GL/2 commands.

Files

For AIX:

/usr/lpp/psf/pcl2afp/sample.pcl

PCL sample program

/usr/lpp/psf/bin/pcl2afp

Transform program

/usr/lpp/psf/bin/pcl2afpd

PCL daemon

/usr/lpp/psf/bin/ppxpcli

PCL interpreter program

/usr/lpp/psf/bin/ppxpclis

PCL interpreter support program

pcl2afp

/usr/lpp/psf/pcl2afp/pcl2afp.cfg
PCL pcl2afp command configuration file
/usr/lpp/psf/pcl2afp/pcl2afpd.cfg
PCL pcl2afpd daemon configuration file
/var/psf/pcl2afp
Work directory for PCL transform

For NT/2000:

install_path\pcl2afp\sample.pcl
PCL sample program
install_path\bin\pcl2afp.exe
Transform program
install_path\bin\pcl2afpd.exe

PCL daemon

install_path\bin\ppxpcli.exe

PCL interpreter program /usr/lpp/psf/pcl2afp/pcl2afp.cfg

PCL pcl2afp command configuration file *install_path*\pcl2afp\pcl2afpd.cfg

PCL pcl2afpd daemon configuration file

install_path\var\psf\pcl2afp
 Work directory for PCL transform

pdf2afp and ps2afp Transforms: Transform PDF or PostScript Data to AFP

Syntax

```
{pdf2afp | ps2afp}
        [-a OutputType] [-C ConfigurationFile] [-c]
        [-device '[plex],[inputw=(size,[type=x,color=y,weight=z][inputw=(...]']
        [-F FontMapFile[:FontMapFile...]] [-g PageRange] [-j nnnn]
        [-1 nnnn.nnnu] [-M nnnnn] [-o OutputFile]
        [-P nnnnn] [-p PageRange] [-q] [-r nnn]
        [-S ServerName] [-s nnnn] [-w nnnn.nnnu]
        [-x nnnn.nnnu] [-y nnnn.nnnu] [InputFile ...]
```

Description

The **ps2afp** command and its alias, the **pdf2afp** command, transform a PostScript or Portable Document Format (PDF) data stream file into an AFP data stream file.

The PSF DSS runs the ps2afp command automatically whenever:

- Infoprint identifies the format of a document in a print job as PostScript or PDF.
- You use the **pdpr** command to specify **document-format=postscript** or **document-format=pdf** with the **-**x flag or in an attributes file.
- You specify a data type of **-odatatype=ps** or **-odatatype=pdf** with an AIX print command (**enq**, **lp**, or **qprt**) or with the **lprafp** command.

If you specify multiple values of the same flag, ps2afp uses the last value specified, with the exception of the -F, -g, and -p, flags. ps2afp concatenates multiple values of the -F flag from left-to-right (first entered to last entered). Multiple values of the -g and -p flags are accumulated and the pages identified for printing are printed in normal numerical sequence, regardless of the order you specify.

When using the **ps2afp** or **pdf2afp** command, you can specify an optional input file name. If you do not specify an input file name, **ps2afp** reads standard input. The output file name is also optional; if you do not specify one, the **ps2afp** command writes the results to standard output.

Note the following about the flags you can specify with the <code>ps2afp</code> or <code>pdf2afp</code> command:

- 1. When you run **ps2afp** or **pdf2afp** as a standalone transform, flags can appear anywhere on the command line with or without a blank in the flag and value pair.
 - When you specify **ps2afp** transform flags with the **other-transform-options** attribute, any string containing a blank must be surrounded by single quotes. Do not use a blank between the flag and the value when you specify **ps2afp** transform flags with an AIX print command or with the **lprafp** command.
- 2. When you specify flags with the **ps2afp** or **pdf2afp** command, the command echoes them back to your display along with the settings for the flags. To suppress the command echoing, enter the **-q** (quiet) flag along with the **ps2afp** or **pdf2afp** command.
- 3. Finally, be aware that the PostScript or PDF file may contain the commands **letter** and **legal**. If these commands are present in the PostScript or PDF file,

you may not get what you expect due to the interaction of the **letter** and **legal** commands with the **-l** and **-w** flags of the **ps2afp** or **pdf2afp** command. The order in which **ps2afp** uses PostScript and PDF options is as follows:

- a. The PostScript program commands letter and legal, if they are present.
- b. Any options you specify on the command line with the ps2afp or pdf2afp command (for example, -r300), including values contained in the customized configuration file you specify with the ps2afp -C or pdf2afp command. If you specify the same option more than once, Infoprint uses the last value.
- c. Values contained in the configuration file, ps2afp.cfg, in the current directory, if you invoked ps2afp or pdf2afp directly. If you invoked ps2afp indirectly by requesting enq -odatatype=ps, or enq -odatatype=pdf, ps2afp ignores any configuration files in the current directory, and proceeds to step 3d.
- d. Values contained in the **ps2afp.cfg** file in the user's home directory.
- e. Values contained in the default **ps2afp** command configuration file:

For AIX

/usr/lpp/psf/ps2afp/ps2afp.cfg

For NT/2000

install_path\ps2afp\ps2afpd.cfg

- f. Values contained in the customized configuration file you specify with the ps2afpd -C command.
- g. Values contained in the default **ps2afpd** daemon configuration file:

For AIX

/usr/lpp/psf/ps2afp/ps2afpd.cfg

For NT/2000

install_path\ps2afp\ps2afpd.cfg

- h. Values contained in the ps2afpd.cfg file when ps2afpd was started.
- i. The defaults that are built into **ps2afpd**. These defaults are the same as the defaults for the **ps2afp** flags, except that the default output type (-a flag) is an IM1 uncompressed image.
- 4. The position of PostScript or PDF data on the page depends on the interaction of the -l and -w flags, the -x and -y flags, and the form definition you use. In general, to position data on the page,
 - Use -l and -w to set the physical page dimensions.
 - Use a form definition that specifies zero vertical offset and zero horizontal offset (for example, **F100S**, **F100D**, or **F100T**) or specify X and Y offsets of 0 when you submit the print job.
 - Use -x and -y to avoid any areas that your printer cannot print.
- 5. You can specify the ps2afp flags and values with the ps2afp or pdf2afp command, or with enq -o, lp -o, qprt -o, or or lprafp. You can also specify equivalent attribute values with the -x flag or in an attributes file with the pdpr command.

Note: If you are migrating from PSF for AIX, see "Appendix B. Migrating PSF for AIX Job Script Keywords to Infoprint Equivalents" on page 715 for a table of attributes equivalent to the job script keywords that you use to specify flags and values for transforms.

Limitations

- Infoprint, including the **psf2afp** transform, must be installed, and the **ps2afpd** daemon must be running.
- PostScript data can contain device commands (for example, to begin or end duplexing or to change the input bin). Because the AFP architecture defines those device functions in a form definition resource instead of the print data, the ps2afp transform ignores the device commands in the print data. To access those device functions (such as duplexing and bin selection), you must specify them in the form definition or attributes file, or on a print command, when you print the job.
- Resolution conversion algorithms may yield degraded appearance when used to reduce the resolution of a datastream. For this reason, ps2afp may degrade the appearance of higher-resolution datastreams when used with 240-pel printers. You should verify that print fidelity is satisfactory.

Flags and Values

-a {IO1_G4 | IM1 | IO1 | IO1_MMR | PSEG_IO1_G4 | PSEG_IM1 | PSEG_IO1 | PSEG_IO1_MMR | OVLY_IO1_G4 | OVLY_IM1 | OVLY_IO1 | OVLY_IO1_MMR | FS45}

Determines the type of AFP data stream image to generate for each page in the PostScript or PDF file.

Values are:

IO1 G4

Compressed Image Object Content Architecture (IOCA) image in Modified TSS (formerly CCITT) T.6 G4 Facsimile Coding Scheme (G4 MMR) format. This is the recommended output type because it takes up less space on the fixed disk, and it prints faster. It is the default specified in the **ps2afpd** daemon and **ps2afp** command configuration files.

Note: The IBM 3812 and 3816 printers do not support printing with an image type of **IO1_G4**. For these printers, specify an image type of **IO1_MMR** because it is the compressed image type supported by these printers. This will result in faster printing than uncompressed image types.

PPDS, PCL, and TCP/IP-attached IPDS printers can print IOCA images; however, only channel-attached printers that have the Advanced Function Image and Graphics (AFIG) feature installed can print IOCA images. Therefore, if you are printing images on channel-attached printers without the AFIG feature, select the **IM1** value.

IM1 IM1 image. This type of image is not compressed.

IO1 IOCA image. This type of image is not compressed.

IO1_MMR

Compressed IOCA image in Modified Modified Read (MMR) format.

PSEG_IO1_G4 | PSEG_IM1 | PSEG_IO1 | PSEG_IO1_MMR Page segment of the specified image type.

Note: When generating page segments from multiple-page documents, you may want to use the **-p** flag to select which page is to be made into a page segment; otherwise, multiple page segments will be created, one for each page of PostScript or PDF.

OVLY_IO1_G4 | OVLY_IM1 | OVLY_IO1 | OVLY_IO1_MMR

Overlay of the specified image type.

Note: When generating overlays from multiple-page documents, you may want to use the **-p** flag to select which page is to be made into an overlay; otherwise, multiple overlays will be created, one for each page of PostScript or PDF.

FS45 IOCA color format.

This flag is similar to the **image-out-format** document attribute on the **pdpr** command.

-C ConfigurationFile

Specifies the path and file name of the customized configuration file Infoprint uses with the transform. If you specify the **-C** flag with an AIX print command (**enq**, **lp**, or **qprt**), or with the **lprafp** command, specify the fully qualified name of the file, including its path; for example:

With AIX

/usr/lpp/ps2afp/myfile.cfg

With NT/2000

install_path\ps2afp\myfile.cfg

-c Concatenates multiple input files without putting a Ctrl-D (end of job) character between the files. The **ps2afp** command interprets the input files as a continuous data stream, and processes them as if they were one PostScript or PDF job. This flag can be useful when processing PostScript or PDF files with inline resources. (See "Examples" on page 299).

Note: Do not use this flag when you perform the data stream transform by submitting a print job with the **pdpr** command.

-device '[plex], [inputw=(size[,type=x,color=y,weight=z]) inputw=...]'

Specifies whether to recognize plex mapping, and optionally, how to associate the AFP input tray (inputw) with the contents of the output bin. When you specify inputw, you must specify size, where size is a text string like letter, legal, a3, a4, b4, b5, ledger, or a dimension like 8.5ix11i. Dimensions can be specified as inches (i), millimeters (m), or points (p). The other three input descriptors (type, color, and weight) are optional, but when you specify them, you must separate them with a comma and no spaces.

When you do not specify **input***w***=...)** with **plex**, Infoprint recognizes plex mappings with no additional information for the tray contents.

Note: You can specify [inputw=... as many times as you need to.

-F FontMapFile[:FontMapFile...]

Specifies the path and file name **ps2afp** uses for the font mapping file. This file correlates PostScript font names with their file locations. A font mapping file must exist on the AIX system where the **ps2afpd** daemon is running (specified by the **-S** flag).

You can include multiple values in the **-F** flag by separating each value with a colon (:). The files will be concatenated. When you specify multiple **-F** flags, **ps2afp** concatenates them from left-to-right (first entered to last entered) in that order.

The -F value overrides the ps_font_map_files value in the ps2afp configuration file and the ps2afpd configuration file. If you do not specify -F, ps2afp uses the font mapping file specified in the ps2afp command or ps2afpd daemon configuration file. (By default, the ps2afpd daemon configuration file specifies the font mapping file as follows:

For AIX

/usr/lpp/psf/ps/psfonts.map

For NT/2000

install_path\ps\fonts.map

If you specify **-F** without a file name, or if the file does not exist, the **ps2afp** command does not work.

Notes:

- PostScript or PDF processing is slower when you use the -F flag, because the ps2afpd daemon must stop and re-start the PostScript interpreter. You may improve performance by changing the ps_font_map_files value in the ps2afpd daemon configuration file rather than using -F on a regular basis.
- 2. Specify the fully qualified name of the file if you specify the **-F** flag with an AIX print command.

-g PageRange

Specifies that the output should only contain selected pages. When you specify multiple **-g** flags, the **ps2afp** command transforms only the specified pages in the PostScript or PDF input data stream, then prints the transformed pages in normal numerical order, regardless of the order you specify. Examples of values include:

-g even

Output even pages.

-g odd Output odd pages.

-g 1-10

Output pages 1 through 10.

-g 10- Output pages from page 10 until the end of the job.

-g 1 -g 3 -g 6

Output pages 1, 3, and 6, in that order.

-g1 -g6 -g3

Output pages 1, 3, and 6, in that order.

This flag is equivalent to the **page-select** document attribute on the **pdpr** command.

Note: You should only specify the **-g** flag when the input data conforms to Adobe Document Structuring Conventions (DSC). If you have any doubt about the input data, use the **-p** flag.

You cannot specify both the **-g** flag and the **-p** flag.

InputFile ...

Specifies one or more input files to be transformed. If you specify more than one input file name, the **ps2afp** command concatenates the files and

separates them with the Ctrl-D (end of job) character. The results of the transform are written to a single output file (if one is specified) or to standard output.

In addition, you can specify PostScript inline resource files as input files to the **ps2afp** command. The file name of the inline resource file must precede the file name of the PostScript or PDF print file so that ps2afp concatenates the files in the correct order.

If you do not specify an input file, ps2afp uses standard input. If the ps2afp command cannot read from standard input, ps2afp issues a message.

-j {20 | 1 to 9998 | 9999}

Specifies the maximum amount of time, in minutes, to spend processing the job.

Values are:

20 minutes, the default 20

1 to 9998

The timer ranges from 1 to 9998 minutes, in one-minute increments

9999 No time limit

-l nnnn.nnnu

Specifies the length of the generated image; nnnn.nnn is a number that can optionally contain a decimal point, and u is the units in inches (i) or millimeters (m). If you do not specify a unit (i or m), then ps2afp uses pels as the unit type. You cannot specify fractional values (that is, you cannot use a decimal point) for pels.

Note: If a text margin is already built into the file, try -l11i to set the length to 11 inches.

For 240-pel resolution printers, values are:

11i 11 inches, the default

16 to 8160

The length can be from 16 pels to 8160 pels, 0.065i to 34i, or 1.641m to 863.628m. For example, the following are all valid:

- -1 40m
- -1 200.5m
- -1 13i
- -1 4000

For 300-pel resolution printers, values are:

11i 11 inches, the default

16 to 10200

The length can be from 16 pels to 10200 pels, 0.052i to 34i, or 1.313m to 863.628m. For example, the following are all valid:

- -1 40m
- -1 200.5m
- -1 13i
- -1 5000

For 480-pel resolution printers, values are:

11 inches, the default 11i

16 to 16320

The length can be from 16 pels to 16320 pels, 0.065i to 34i, or 1.641m to 863.628m. For example, the following are all valid:

- -1 40m
- -1 200.5m
- -l 13i
- -1 8000

For 600-pel resolution printers, values are:

11i 11 inches, the default

16 to 20400

The length can be from 16 pels to 20400 pels, 0.052i to 34i, or 1.313m to 863.628m. For example, the following are all valid:

- -1 40n
- -1 200.5m
- -1 13i
- -1 10000

This flag is equivalent to the **image-length** document attribute on the **pdpr** command.

-M {15000 | 11000 to nnnnn}

Determines the maximum amount of memory, in KB, that the transform can use. This flag may be useful if you are processing large PostScript or PDF jobs that require a lot of memory.

Values are:

15000 15000KB (15MB)

11000 to *nnnnn*

The maximum memory ranges from 11000 to *nnnnn* (where *nnnnn* is the maximum upper limit allowed by AIX) up to 64MB. 15000 is the default.

-o OutputFile

Specifies the output path and file into which the transformed files are to be written. If more than one output file is specified, the last specified file name and path is the one used. If no output file is specified, the result is written to standard output.

You cannot use **-o** *OutputFile* on the command line with the **enq**, **lp**, **qprt**, or **lprafp** commands. You can only use **-o** *OutputFile* with the **ps2afp** command. You can also specify the **transform-output-file-name** document attribute on the **pdpr** command.

-P {8251 | 924 to nnnnn}

Specifies the TCP/IP port number ps2afp uses to make a connection with the workstation on which the ps2afpd daemon is running (set by the -S flag). If your Infoprint installation uses more than one PostScript daemon, use this flag to select the daemon.

This port should not be the same port used by the TCP/IP-attached IPDS printer or the PCL transform. To find out which ports are already being used on your system (although they may or may not be active), look in the /etc/services file.

Values are:

8251 The default port number.

924 to nnnnn

Any valid port number greater than or equal to 924. The maximum value, *nnnnn*, depends on AIX, but it must be equal to or less than 65535.

Note: You can only access secure ports, 924 to 1023, with **root** user authority.

-p PageRange

Specifies that the output should only contain selected pages. When you specify multiple **-p** flags, the **ps2afp** command transforms all the pages in the input, then extracts the specified MO:DCA-P pages and prints them in normal numerical order, regardless of the order you specify.

You cannot specify both the **-g** flag and the **-p** flag.

Examples of values include:

-p even

Output even pages.

-p odd

Output odd pages.

-p 1-10

Output pages 1 through 10.

-p 10- Output pages from page 10 until the end of the job.

-p 1 -p 3 -p 6

Output pages 1, 3, and 6, in that order.

-p1 -p6 -p3

Output pages 1, 3, and 6, in that order.

This flag is equivalent to the **page-select** document attribute on the **pdpr** command.

-q Quiets (suppresses) the echoing of the **ps2afp** command to the display.

-r {240 | 300 | 480 | 600}

Specifies the resolution of the output image. Select the resolution based on the printer on which you will be printing the image.

Values are:

240 pels-per-inch (for example, IBM 3812, 3825, 3827, 3835, and 3900 printers).

300 gels-per-inch (for example, IBM 4019, 4028, 4029, and 4039 printers and Hewlett-Packard printers)

480 pels-per-inch

600 pels-per-inch (for example, IBM 3900 printers), the default

This flag is equivalent to the **default-printer-resoulution** document attribute on the **pdpr** command.

Note: If you specify a resolution that the printer does not support, Infoprint will print the image under most conditions, but with degraded results. Specify the correct resolution for the printer on which you will print the job.

-S ServerName

Specifies the name of the AIX system on which the ps2afpd daemon is

running. If you do not specify this flag, the *ServerName* defaults to the effective name of the workstation on which you issued the **ps2afp** command. The value is:

ServerName

Any valid AIX workstation name on which the **ps2afpd** daemon is installed and running. The name is defined in the **/etc/hosts** file or by a name server, and may be a nickname like **molly**, or a dotted decimal address like **9.99.9.23**.

-s {20 | 1 to 9998 | 9999}

Specifies the maximum amount of time, in minutes, that the PostScript interpreter remains idle between jobs before it goes down. When the PostScript interpreter is running, it uses some of the workstation memory. If the PostScript interpreter goes down, you do not need to bring it back up; the interpreter automatically starts when you submit another PostScript or PDF job as long as the **ps2afpd** daemon is running.

Values are:

The default time is 20 minutes.

1 to 9998

The time is the number of minutes specified in one-minute increments.

9999 There is no time limit.

-w nnnn.nnnu

Specifies the width of the generated image; nnnn.nnn is a number that can optionally contain a decimal point, and u is the units in inches (i) or millimeters (m). If you do not specify a unit (i or m), then ps2afp uses pels as the unit type. You cannot specify fractional values (that is, you cannot use a decimal point) for pels.

Note: If a text margin is already built into the file, try **-w8.5i** to set the width to 8.5 inches.

For 240-pel resolution printers, values are:

8.5i 8.5 inches, the default

16 to 8160

The width can be from 16 pels to 8160 pels, 0.065i to 34i, or 1.641m to 863.628m. For example, the following are all valid:

- -w 40m
- -w 200.5m
- -w 13i
- -w 3300

For 300-pel resolution printers, values are:

8.5i 8.5 inches, the default

16 to 10200

The width can be from 16 pels to 10200 pels, 0.052i to 34i, or 1.313m to 863.628m. For example, the following are all valid:

- -w 40m
- -w 200.5m
- -w 13i
- -w 5000

For 600-pel resolution printers, values are:

8.5i 8.5 inches, the default

16 to 20400

The width can be from 16 pels to 20400 pels, 0.052i to 34i, or 1.313m to 863.628m. For example, the following are all valid:

-w 40m -w 200.5m -w 13i -w 5000

This flag is equivalent to the **image-width** document attribute on the **pdpr** command.

-x nnnn.nnnu

Specifies an X offset (horizontal offset) of the generated image; nnnn.nnn is a number that can optionally contain a decimal point, and u is the units in inches (i) or millimeters (m). If you do not specify a unit (i or m), then ps2afp uses pels as the unit type. You cannot specify fractional values (that is, you cannot use a decimal point) for pels.

An offset value specifies a border or margin around the generated image to avoid the non-printable areas of some printers. An X-offset value specifies the left and right margins of the generated image.

Values are:

0 No border is specified. This is the default.

0 to 17i

The value specified here can be no greater than half of the value specified on the **-w** flag. For example, if you specified -w=12i, this value can be no greater than 6i.

This flag is equivalent to the **x-image-shift** document attribute on the **pdpr** command.

Notes:

- 1. The X offset specified with -x must be less than the width specified with -w. If the -x value is greater than or equal to the -w value, a blank page is printed.
- 2. The X-offset value specifies margins on both the left and right sides of the page. If you have a width of 8.5 inches and specify an X offset of 5 inches, a blank page will also result because the margins on the left and right sides of the paper exceed the width of the paper.
- 3. PostScript or PDF processing is slower when you use the -x flag, because the ps2afpd daemon must stop and re-start the PostScript interpreter. You may improve performance by changing the ps_x_offset value in the ps2afpd daemon configuration file rather than using -x on a regular basis.

-y nnnn.nnnu

Specifies a Y offset (vertical offset) of the generated image; nnnn.nnn is a number that can optionally contain a decimal point, and u is the units in inches (i) or millimeters (m). If you do not specify a unit (i or m), then ps2afp uses pels as the unit type. You cannot specify fractional values (that is, you cannot use a decimal point) for pels.

An offset value specifies a border or margin around the generated image to avoid the non-printable areas of some printers. A Y-offset value specifies the top and bottom margins of the generated image.

Values are:

No border is specified. This is the default.

0 to 17i

The value specified here can be no greater than half of the value specified on the -l flag. For example, if you specified -l=16i, this value can be no greater than 8i.

This flag is equivalent to the **y-image-shift** document attribute on the **pdpr** command.

Notes:

- 1. The Y offset specified with -y must be less than the length specified with -l. If the -y value is greater than or equal to the -l value, a blank page is printed.
- 2. The Y offset value specifies margins on *both* the top and bottom edges of the page. If you have a length of 11 inches and specify an Y offset of 6 inches, a blank page will also result because the margins on the top and bottom of the paper exceed the length of the paper.
- 3. PostScript or PDF processing is slower when you use the -y flag, because the ps2afpd daemon must stop and re-start the PostScript interpreter. You may improve performance by changing the ps_y_offset value in the ps2afpd daemon configuration file rather than using -y on a regular basis.

The ps2afp and ps2afpd Configuration Files

Instead of typing flags on the command line with the <code>ps2afp</code> or <code>pdf2afp</code> command, you can use the <code>-C</code> flag to specify a configuration file that contains the flags. In this way, you can simply specify a configuration file name, rather than typing many flags. You may find it convenient to use a configuration file if you repeatedly use the same flags with the <code>ps2afp</code> or <code>pdf2afp</code> command, or if you are using different PostScript or PDF processing values than the defaults defined by your system support group.

When your system support group installed the **ps2afp** transform and its alias, **pdf2afp**, a default **ps2afp** command configuration file, **ps2afp.cfg**, was installed in the following directory:

With AIX

/usr/lpp/psf/ps2afp

With NT/2000

*install_path***ps2afp**

If you want to create your own files, copy the **ps2afp.cfg** file and then use a system editor to modify the options in this ASCII file to suit your needs.

A default **ps2afpd** daemon configuration file, **ps2afpd.cfg**, was also installed in the following directory:

With AIX

/usr/lpp/psf/ps2afp

With NT/2000

install_path\ps2afp

The **ps2afpd** daemon configuration file can contain most of the same keywords as the **ps2afp** command configuration file, plus some keywords that control the operation of the **ps2afpd** daemon. Values in the command configuration file override values in the daemon configuration file.

Figure 5 shows an example of a configuration file.

```
# ps2afp configuration file
```

		ps2afp FLAG PURPOSE ####################################
port = 8251 server = 127.0.0.1	# -P # -S	which TCP/IP port to use which server to connect with
ps_max_memory = 14000K	# -M #	maximum amount of memory that PostScript uses; the 'K' is ignored
<pre>ps_job_timeout = 20 ps_server_timeout = 20</pre>	# -j # # -s #	maximum number of minutes to process PostScript job maximum number of minutes server waits between jobs
<pre>ps_width = 8.5i ps_length = 11i ps_x_offset = 0i ps_y_offset = 0i ps_resolution = 600 ps_output_type = I01_G4</pre>	# -w # -l # -x # -y # -r # -a	width of generated image length of generated image left and right margins top and bottom margins resolution of printer type of AFP image to generate

Figure 5. Sample ps2afp Configuration File

Table 10 shows the **ps2afp** flags and their equivalent configuration file keywords. To override the values in the default configuration file, **ps2afp.cfg**, you can do one of the following:

- Specify flags with the **ps2afp** or **pdf2afp** command at transform time.
- Specify a configuration file with **ps2afp** -C at transform time.
- Specify **ps2afp** flags with **-o** flags on an AIX print command, or with equivalent attributes with the **-x** flag or in an attributes file on the **pdpr** command, to transform a file and print it at the same time.

Note: If you are migrating from PSF for AIX, see "Appendix B. Migrating PSF for AIX Job Script Keywords to Infoprint Equivalents" on page 715 for a table of attributes equivalent to the job script keywords that you use to specify flags and values for transforms.

Table 10. PostScript and PDF Printing and Processing Options

ps2afp or pdf2afp Flag	Keyword in ps2afp Configuration File	Keyword in ps2afpd Configuration File					
Note: The valid values for configuration file keywords are the same as for the corresponding ps2afp or pdf2afp command flag. For keywords used only in theps2afpd daemon configuration file, which have no corresponding command flag, see"ps2afpd Utility: Starts the ps2afpd Daemon" on page 193.							
-a OutputType	ps_output_type=value	ps_output_type=value					
-C ConfigurationFile	None	None					
-c	None	None					

Table 10. PostScript and PDF Printing and Processing Options (continued)

ps2afp or pdf2afp Flag	Keyword in ps2afp Configuration File	Keyword in ps2afpd Configuration File	
-device	device_control=[plex],[inputw= (size,[type=x,color=y, weight=z])][inputw= (size,[type=x,color=y, weight=z])][inputw= (])	device_control=[plex],[inputw= (size,[type=x,color=y, weight=z])][inputw= (size,[type=x,color=y, weight=z])][inputw= (])	
-F FontMapFile[:]	ps_font_map_file=PathName	ps_font_map_file=PathName	
-g PageRange	None	None	
InputFile	None	None	
-j nnnn	ps_job_timeout=nnnn	ps_job_timeout=nnnn	
-l nnnn.nnnu	ps_length=nnnn.nnnu	ps_length=nnnn.nnnu	
-M nnnnn	ps_max_memory=nnnnn	ps_max_memory=nnnnn	
-o OutputFile	None	None	
-P nnnnn	port=PortNumber	port=PortNumber	
-p PageRange	None	None	
-q	None	None	
-r nnn	ps_resolution=nnn	ps_resolution=nnn	
-S ServerName	server=ServerName	None	
-s nnnn	ps_server_timeout=nnnn	ps_server_timeout=nnnn	
-w nnnn.nnnu	ps_width=nnnn.nnnu	ps_width=nnnn.nnnu	
-x nnnn.nnnu	ps_x_offset=nnnn.nnnu	ps_x_offset=nnnn.nnnu	
-у пппп.пппи	ps_y_offset=nnnn.nnnu	ps_y_offset=nnnn.nnnu	
None	None	log_file=PathName	
None	None	mail_command=PathName	
None	None	notify=UserID	
None	None	ps_init_file=PathName	
None	None	ps_program=PathName	
None	None	ps_support_program=PathName	
None	None	work_directory=PathName	

Examples

• To submit the PostScript file sample.ps to the logical printer named molly-lp, enter the follwoing:

For AIX

enq -Pmolly-lp -odatat=ps /usr/lpp/psf/ps2afp/sample.ps

For NT/2000

pdpr -pmolly-lp install_path\ps\sample.ps

• To transform the PDF file myfile1 into an AFP data stream, and then submit it to the Infoprint logical printer called robin-lp, enter:

or

pdpr -p robin-lp -x "default-printer-resolution=300" myfile1

or

```
pdf2afp -r300 myfile1 | pdpr -p robin-lp
```

Note: You need to specify a resolution of 300 pels (default-printer-resolution=300 or -r300) because robin-lp routes jobs to a 4019 printer device. The 4019 printer is a 300-pel resolution printer and the default resolution for the **pdf2afp** command is 600 pels.

• To transform the PostScript file myfile2 into an AFP data stream, with an image that is 8 inches high and 5 inches wide, and write the result to a file called myfile2.afp, enter:

```
ps2afp -1 8i -w 5i -o myfile2.afp myfile2
or
ps2afp -1 8i -w 5i myfile2 > myfile2.afp
```

• To transform the PostScript file myfile2 into an AFP data stream, creating a compressed IO (IOCA) image (the default image type for the **ps2afp** command), and piping the result to the **pdpr** command to submit the file to the Infoprint logical printer called molly-lp, enter:

```
ps2afp myfile2 | pdpr -p molly-lp
```

You can get the same result without piping (that is, using **pdpr** directly) by entering:

```
pdpr -p molly-lp myfile2
```

 To transform the PDF myfile1 file into an AFP data stream in 300-pel resolution, as an IO1_MMR image, and send the result to the printer with the pdpr command, enter:

```
pdf2afp -aIO1_MMR -r300 myfile1 | pdpr -X myafp.X
or
pdpr -X myps.X myfile1
```

where the attributes file named myafp.X contains the following settings:

```
document-format=modca-p
printer-name-requested=david-lp
```

and the attributes file named myps.X contains the following settings:

```
document-format=pdf
printer-name-requested=david-lp
image-out-format=io1_mmr
default-printer-resolution=300
```

Assume that the PostScript file myfile2 uses the BarKode.pfa font that is a
PostScript resource not installed for use by the ps2afpd on an AIX system
named robin. Also assume that the ps2afpd daemon is running on robin, but
you are logged into the AIX system named molly. To transform myfile2 into an
AFP data stream, but not print it:

```
ps2afp -S robin -c -o myfile2.afp BarKode.pfa myfile2
```

The -c flag concatenates the two input files, with the file BarKode.pfa first, so that the two files are processed together. In this way, myfile2 uses BarKode.pfa as an inline resource.

Files

```
For AIX: /usr/lpp/psf/bin/ps2afpd
PostScript daemon
```

/usr/lpp/psf/bin/ps2afp

PostScript transform executable

/usr/lpp/psf/bin/pdf2afp

PDF transform executable (linked to /usr/lpp/psf/bin/ps2afp)

/usr/lpp/psf/ps2afp/ps2afpd.cfg

ps2afpd daemon configuration file

/usr/lpp/psf/ps2afp/ps2afp.cfg

ps2afp command configuration file

/usr/lpp/psf/bin/ppxps2i

PostScript level 2 interpreter program

/usr/lpp/psf/bin/ps2afpi

PostScript Level 1 interpreter program

/usr/lpp/psf/bin/ps2afpi.vm

PostScript interpreter program initial virtual memory

/usr/lpp/psf/ps2afp/ppxps2.ps

PostScript level 2 initialization file

/usr/lpp/psf/ps2afp/ps2afp.ps

PostScript Level 1 initialization file

/usr/lpp/psf/ps2afp/ps2afpe.ps

PostScript Level 1 initialization file for extended error reporting

/usr/lpp/psf/bin/fontsave

PostScript executable for saving fonts

/usr/lpp/psf/psfonts.map

Default PostScript font mapping file

/var/psf/psfonts

User-defined PostScript fonts file

For NT/2000:

install_path\bin\ps2afpd.exe

PostScript daemon

install_path\bin\ps2afp.exe

PostScript transform executable

install_path\bin\pdf2afp.exe

PDF transform executable

install_path\ps2afp\ps2afpd.cfg

ps2afpd daemon configuration file

install_path\ps2afp\ps2afp.cfg

ps2afp command configuration file

install_path\bin\ps2afpi.exe

PostScript Level 1 interpreter program

install_path\bin\ps2afpi.vm

PostScript interpreter program initial virtual memory

install_path\ps2afp\ps2afp.ps

PostScript Level 1 initialization file

install_path\ps\fonts.map

Default PostScript font mapping file

install_path\var\psf\psfonts

User-defined PostScript fonts file

sap2afp Command: Transforms SAP OTF or ABAP Data to AFP in **Infoprint Manager for AIX**

Syntax

```
sap2afp -d DeviceName {-f FileName | -i | -q} [-g]
        [-r { 240 | 300 | 480 | 600}] [-t]
```

Description

Use the sap2afp command to transform an SAP Output Text Format (OTF) or Advanced Business Application Programming (ABAP) file into an AFP data stream file and to submit it to an Infoprint destination.

Flags

-d DeviceName

Specifies the name of the R/3 output device. This name is converted to the name of an Infoprint logical destination as specified in the printer.tab configuration file.

-f FileName

Specifies the input file to be converted. This file is erased after successful

- -g Invokes the Graphics Object Content Architecture (GOCA) feature of the printer device. The GOCA feature allows you to print boxes with four different levels of shading, as well as clear and solid boxes.
- Specifies that input comes from standard input (stdin). A temporary file -i (sap2afp.tmp) is created, processed as with the -f parameter, then erased.
- -q Invokes the **lpq** command to display the queue.

-r { 240 | 300 | 480 | 600}

Specifies the printer resolution used to print image data in the job. If you do not specify the -r flag, the DEFRES value in the image.tab file is used. In the **image.tab** file shipped with Infoprint, the **DEFRES** value is **600**.

-t Traces program execution.

The sap2afp Configuration Files

This section consists of examples for the following configuration files that are required for the **sap2afp** transform:

```
barcode.tab
defcp.tab
fonts.tab
image.tab
pagedef.tab
printer.tab
xxxxyyyy.tab
```

- 1. All tables can contain comments (starting with // in column 1) and empty lines. These lines are ignored by the **sap2afp** transform.
- 2. All table entries are case-sensitive.

barcode.tab Configuration File

This table describes the bar code mappings. SAP calls bar codes by names that must be mapped into the matching bar codes available with Bar Code Object Content Architecture (BCOCA).

barcode.tab uses the following keyword-value pairs:

BarCode

Specifies the OTF bar code names (**SAPBARCODE** parameter of the **BC** OTF command). The maximum length of this field is 8 bytes. It can contain any value.

- Type Specifies the AFP bar code type as defined in *IBM Data Stream and Object Architectures: Bar Code Object Content Architecture Reference* for the **Barcode Type** parameter of the **Barcode Data Descriptor** Structured Field. The content can be any decimal value between 0 and 999. The **sap2afp** transform does not verify that this value maps to a valid hexadecimal barcode type.
- **Mode** Specifies the modifier byte within the **Barcode Modifier** parameter of the **Barcode Data Descriptor** Structured Field. Any numeric value between 0 and 999 is accepted and not verified.
- **Flag** Controls the printing of the Human Readable Interface (**HRI**) character. Specify one of the following values:
 - O Causes the HRI character to be printed
 - 128 Causes the HRI character not to be printed

ModWidth=n

This optional keyword specifies the width of the smallest defined bar code element, using mils (thousandths of an inch). For bar code types that explicitly specify the module width, such as POSTNET or RM4SCC, this field is ignored. The range of values allowed is 1–254. If **ModWidth** is not specified, the printer default ModWidth is used.

n specifies the width of each module, using thousandths of an inch (1/1000) as the unit of measurement.

Ratio=n

This optional keyword specifies the ratio between the width of the wide and the narrow bar code elements. The range of values allowed is 100–500, but you must specify a value appropriate for your printer and bar code type. If the values you specify are not appropriate for your printer, error messages are issued at printing time. If **Ratio** is not specified, the printer default Ratio is used.

nspecifies the **Ratio** as a percent value. The ratio value should between 200 and 300 in the formnnn. For example, 200 represents a ratio of 2 to 1; 250 represents a ratio of 2.5 to 1. For bar code types that explicitly specify the module width (for example, POSTNET and RM4SCC, this field is ignored. If RATIO is not specified, the default ratio for the bar code symbol is used.

Note: Many barcode types do not support Ratio values or if they do, the Ratio values are within certain ranges that are type-specific.

The following example uses both the **Ratio** and **ModWidth** optional keywords:

BarCode=BC CD39 Type=001 Mode=001 Flag=128 Ratio=200 ModWidth=10

Notes:

- 1. The system administrator is responsible for the values entered in the table. Invalid values are not verified and may result in errors.
- 2. The second group of bar codes in the **barcode.tab** file (following the blank line) is supported from R/3 Release 3.0A only.

Figure 6 shows a sample **barcode.tab** configuration file.

```
// Barcode table
// Format : Barcode=ARTNR Type=017 Mode=002
//BarCode = 30F9
                       Type = 001 \text{ Mode} = 001 \text{ Flag} = 000
//BarCode = 30F91
                       Type = 001 \text{ Mode} = 002 \text{ Flag} = 000
//BarCode = MSI
                       Type = 002 \text{ Mode} = 002 \text{ Flag} = 000
//BarCode = UPCA
                       Type = 003 \text{ Mode} = 000 \text{ Flag} = 000
//BarCode = UPCE
                       Type = 005 \text{ Mode} = 000 \text{ Flag} = 000
                       Type = 006 Mode = 000 Flag = 000
//BarCode = UPC2
//BarCode = UPC5
                       Type = 007 Mode = 000 Flag = 000
//BarCode = EAN8
                       Type = 008 \text{ Mode} = 000 \text{ Flag} = 000
//BarCode = EAN13
                       Type = 009 Mode = 000 Flag = 000
//BarCode = IND25
                       Type = 010 Mode = 002 Flag = 000
//BarCode = MAT25
                       Type = 011 \text{ Mode} = 002 \text{ Flag} = 000
//BarCode = INTER
                       Type = 012 \text{ Mode} = 002 \text{ Flag} = 000
//BarCode = CODA
                       Type = 013 \text{ Mode} = 002 \text{ Flag} = 000
//BarCode = C128
                       Type = 017 \text{ Mode} = 002 \text{ Flag} = 000
//BarCode = EAN2
                       Type = 022 \text{ Mode} = 000 \text{ Flag} = 000
//BarCode = EAN5
                       Type = 023 \text{ Mode} = 000 \text{ Flag} = 000
//BarCode = POST
                       Type = 024 \text{ Mode} = 002 \text{ Flag} = 000
                       Type = 001 Mode = 001 Flag = 128
//BarCode = AUFNR
BarCode = ARTNR
                     Type = 017 \text{ Mode} = 002 \text{ Flag} = 000
                     Type = 017 \text{ Mode} = 002 \text{ Flag} = 000
BarCode = AUFNR
BarCode = BARCLVS Type = 001 Mode = 001 Flag = 000
BarCode = BC C128B Type = 017 Mode = 002 Flag = 128
BarCode = BC CD39C Type = 001 Mode = 002 Flag = 128
BarCode = BC EAN13 Type = 009 Mode = 000 Flag = 128
BarCode = BC EAN8 Type = 008 Mode = 000 Flag = 128
BarCode = BC_I25
                    Type = 012 Mode = 001 Flag = 128
BarCode = BC MSI
                     Type = 002 \text{ Mode} = 001 \text{ Flag} = 128
BarCode = BC MSIC Type = 002 Mode = 002 Flag = 128
BarCode = BC MSIC1 Type = 002 Mode = 003 Flag = 128
BarCode = BC MSIC2 Type = 002 Mode = 005 Flag = 128
BarCode = KUNAUNR Type = 017 Mode = 002 Flag = 000
BarCode = KUNAUPS Type = 017 Mode = 002 Flag = 000
BarCode = MBBARC
                     Type = 017 \text{ Mode} = 002 \text{ Flag} = 000
BarCode = MBBARC1
                    Type = 008 \text{ Mode} = 000 \text{ Flag} = 000
BarCode = RSNUM
                     Type = 017 \text{ Mode} = 002 \text{ Flag} = 000
BarCode = RSPOS
                     Type = 017 \text{ Mode} = 002 \text{ Flag} = 000
BarCode = RUECKNR Type = 017 Mode = 002 Flag = 000
```

Figure 6. Sample barcode.tab Configuration File

defcp.tab Configuration File

Figure 7 shows the default conversion table for the conversion of ASCII characters into EBCDIC. The **sap2afp** transform uses this table for ABAP data conversion.

The left column consists of the ASCII code, while the right column contains the corresponding EBCDIC value. The values are checked for a numeric value between 0 and 255.

```
// Linedata CodePage
//------
// This file is used internally by sap2afp, as well as
// to convert ABAP data to linedata.

// Format : Ascii=Ebcdic

// T1000819 + box characters -> T1DABASE

000 = 064
001 = 064
002 = 064
...
253 = 064
254 = 062
255 = 223
```

Figure 7. Sample defcp.tab Configuration File

fonts.tab Configuration File

This table maps the fonts used in the OTF data stream to AFP fonts.

The following font families are predefined with R/3:

FONTFAMILY
COURIER
Courier
HELVE
Helvetica
LETGOTH
LETTE Gothic
LNPRINT
Line Print

TIMES Times New Roman

OCRA Optical Character Recognition A
OCRB Optical Character Recognition B

JPMINCHO Heisei Mincho
DBMINCHO Heisei Mincho
DBGOTHIC Heisei Gothic

Note: JPMINCHO and DBMINCHO are different names for the same font.

A font named BARCODE must be defined for the HRI character of a bar code.

The following parameters in the **fonts.tab** configuration file set the format of the fonts you use to print with R/3:

DefCodePage

Specifies the default SBCS code page used if no FC OTF command is given or if the requested font is not found in the **fonts.tab** table.

DefCharSet

Specifies the default SBCS character set used if no FC OTF command is given or if the requested font is not found in the fonts.tab table.

DBDefCodePage

Specifies the default DBCS code page used if no FC OTF command is given or if the requested font is not found in the **fonts.tab** table.

DBDefCharSet

Specifies the default DBCS character set used if no FC OTF command is given or if the requested font is not found in the **fonts.tab** table.

SBDefCodePage

Specifies the default SBCS code page used for half-width characters in DBCS fonts if no FC OTF command is given or if the requested font is not found in the **fonts.tab** table.

SBDefCharSet

Specifies the default SBCS character set used for half-width characters in DBCS fonts if no FC OTF command is given or if the requested font is not found in the **fonts.tab** table.

- **Font** Describes the font family (**FONTFAMILY** parameter of the **FC** OTF command). The maximum size is 8 bytes and content is not verified.
- Size Specifies the font size in 1/10 of a point (FONT SIZE parameter of the FC OTF command). The value must be numeric and is not verified.
- Type Defines the font type (BOLD and ITALIC parameter of the FC OTF command). Type=0 is normal, Type=1 is italic, Type=2 is bold, and Type=3 is italic bold. Any other value is invalid.

CodePage

Specifies the code page and requires a valid AFP code page name (8 bytes). The value is not verified. An invalid name can result in an error message.

CharSet

Specifies the AFP font character set. The content is not verified.

CodedFont

Specifies the AFP coded font. The content is not verified.

DB Specifies whether the font is an SBCS font (DB=0) or a DBCS font (DB=1).

SBCodePage

Specifies the single-byte code page used for half-width characters in DBCS fonts. The value is not verified. An invalid name can result in an error message.

SBCharSet

Specifies the AFP single-byte font character set used for half-width characters in DBCS fonts. The content is not verified.

SBCodedFont

Specifies the AFP single-byte coded font used for half-width characters in DBCS fonts. The content is not verified.

If an SBCS font that matches the **Font**, **Size** and **Type** values is not found, the code page and font character set from the **DefCodePage** and **DefCharSet** keywords are used and a warning message is displayed. If a DBCS font that matches the **Font**, **Size** and **Type** values is not found, the code pages and font character sets from the **DBDefCodePage**, **SBDefCodePage**, **DBDefCharSet**, and **SBDefCharSet** keywords are used and a warning message is displayed.

The device types **IBMAFP** and **IBMAFP3** support the predefined font families. These font families are also supported as IBM Expanded Core Fonts, or IBM Chinese, Japanese, and Korean (CJK) Fonts.

ISO 8859-1 (Latin-1) is the default code page that maps to the **1148** code page in the **fonts.tab** configuration table. This ISO code page maps to the German **T1V10273** code page and must be modified for non-Latin-1 R/3 installations. You can make this change on the *xxxxyyyy*.**tab** configuration file that is used to convert data from ASCII data to EBCDIC data so that these characters are mapped correctly. If you have installed a SAP R/3 Release 2.2 or earlier, use the **S9148.CPA** file to determine the modifications you need to make.

Use the font Letter Gothic Latin1 of the coordinated font family for ABAP listings. If you do not want to install the coordinated font family and plan to use the traditional Gothic text fonts found within the IBM Compatibility Fonts, you can adjust the font names in the **pagedef.tab** configuration file.

If you wish to use fonts that are not supported, take the following steps:

- 1. Obtain the font as Adobe Type 1.
- 2. Convert the font into a raster using the Type Transformer in the IBM AFP Font Collection (program number 5648-113).
- 3. Contact your IBM representative for further details.

Figure 8 on page 308 and Figure 9 on page 308 show examples of sections of the **fonts.tab** configuration file.

sap2afp

```
// Fonts table
   Format: Font=COURIER Size=070 Type=0 CodePage=T1V10273 CharSet=C0420070 DB=0
//
             Font=COURIER Size=090 Type=0 CodedFont=X0GT2A DB=0
             Font=JPMINCHO Size=060 Type=0 CodePage=T10300 CharSet=CZJHMN DB=1 SBCodePage=T1H01027 SBCharSet=CZJHMN
//
             Font=JPMINCHO Size=060 Type=0 CodedFont=XZJHMN DB=1 SBCodedFont=XZN16J
DefCodePage = T1V10273
DefCharSet = C0420000
DBDefCodePage = T10300
DBDefCharSet = CZJHMN
SBDefCodePage = T1H01027
SBDefCharSet = CZJHMN
// Courier
Font=COURIER Size=070 Type=0 CodePage=T1V10273 CharSet=C0420070 DB=0 Font=COURIER Size=070 Type=1 CodePage=T1V10273 CharSet=C0430070 DB=0
               Size=070 Type=2 CodePage=T1V10273 CharSet=C0440070 DB=0
Font=COURIER
               Size=070 Type=3 CodePage=T1V10273 CharSet=C0450070 DB=0
Font=COURIER
Font=COURIER
               Size=080 Type=0 CodePage=T1V10273 CharSet=C0420080 DB=0
               Size=080 Type=1 CodePage=T1V10273 CharSet=C0430080 DB=0
Font=COURIER
Font=COURIER
               Size=080 Type=2 CodePage=T1V10273 CharSet=C0440080 DB=0
               Size=080 Type=3 CodePage=T1V10273 CharSet=C0450080 DB=0
Font=COURIER
               Size=100 Type=0 CodePage=T1V10273 CharSet=C0420000 DB=0 Size=100 Type=1 CodePage=T1V10273 CharSet=C0430000 DB=0
Font=COURIER
Font=COURIER
               Size=100 Type=2 CodePage=T1V10273 CharSet=C0440000 DB=0
Font=COURIER
Font=COURIER
               Size=100 Type=3 CodePage=T1V10273 CharSet=C0450000 DB=0
Font=COURIER
               Size=120 Type=0 CodePage=T1V10273 CharSet=C04200B0 DB=0
               Size=120 Type=1 CodePage=T1V10273 CharSet=C04300B0 DB=0
Font=COURIER
               Size=120 Type=2 CodePage=T1V10273 CharSet=C04400B0 DB=0
Font=COURIER
               Size=120 Type=3 CodePage=T1V10273 CharSet=C04500B0 DB=0
Font=COURIER
Font=COURIER
               Size=140 Type=0 CodePage=T1V10273 CharSet=C04200D0 DB=0
Font=COURIER
               Size=140 Type=1 CodePage=T1V10273 CharSet=C04300D0 DB=0
               Size=140 Type=2 CodePage=T1V10273 CharSet=C04400D0 DB=0
Size=140 Type=3 CodePage=T1V10273 CharSet=C04500D0 DB=0
Font=COURIER
Font=COURIER
Font=COURIER
               Size=200 Type=0 CodePage=T1V10273 CharSet=C04200J0 DB=0
Font=COURIER
               Size=200 Type=1 CodePage=T1V10273 CharSet=C04300J0 DB=0
               Size=200 Type=2 CodePage=T1V10273 CharSet=C04400J0 DB=0
Font=COURIER
Font=COURIER Size=200 Type=3 CodePage=T1V10273 CharSet=C04500J0 DB=0
```

Figure 8. Header and Courier Portions of a Sample fonts.tab Configuration File

```
// Japanese Gothic

Font=DBGOTHIC Size=060 Type=0 CodePage=T10300 CharSet=CZJHKG DB=1 SBCodePage=T1H01027 SBCharSet=CZJHKG Font=DBGOTHIC Size=100 Type=0 CodePage=T10300 CharSet=CZJHKG DB=1 SBCodePage=T1H01027 SBCharSet=CZJHKG Font=DBGOTHIC Size=100 Type=0 CodePage=T10300 CharSet=CZJHKG DB=1 SBCodePage=T1H01027 SBCharSet=CZJHKG Font=DBGOTHIC Size=100 Type=1 CodePage=T10300 CharSet=CZJHKG DB=1 SBCodePage=T1H01027 SBCharSet=CZJHKG Font=DBGOTHIC Size=120 Type=0 CodePage=T10300 CharSet=CZJHKG DB=1 SBCodePage=T1H01027 SBCharSet=CZJHKG Font=DBGOTHIC Size=140 Type=0 CodePage=T10300 CharSet=CZJHKG DB=1 SBCodePage=T1H01027 SBCharSet=CZJHKG Font=DBGOTHIC Size=160 Type=0 CodePage=T10300 CharSet=CZJHKG DB=1 SBCodePage=T1H01027 SBCharSet=CZJHKG Font=DBGOTHIC Size=180 Type=0 CodePage=T10300 CharSet=CZJHKG DB=1 SBCodePage=T1H01027 SBCharSet=CZJHKG DB=1 SBCOdePage=T1H01027 SBCharSet=CZJHKG
```

Figure 9. Heisei Gothic Portion of a Sample fonts.tab Configuration File

image.tab Configuration File

This table defines values used to print image data. It contains the following parameters:

DEFRES

Specifies the default resolution used for printing image data if you do not specify a value for the -r flag of the sap2afp command. Valid values are 240, 300, 480, and 600.

Width Specifies the width of the dither matrix.

Height

Specifies the height of the dither matrix.

Cell Specifies the values for the dither matrix.

Transform

Specifies 256 grayscale correction values.

Figure 10 shows an example of the **image.tab** configuration file.

```
// image.tab
// from image.tab.851r
//
// This file is used to determine the dither matrix and the
// grayscale correction values.
// Define the default output resolution
DEFRES = 600
// Define the dither matrix
Width = 78
Height = 78
Cell =
15 63 184 219 249 240 158 109 98 54 82 118 133 113 75 64
87 104 166 215 234 229 179 62 38 4 15 59 186 220 246 240
166 123 87 61 65 108 133 118 78 64 100 105 167 219 234 230
28 73 193 223 253 247 199 76 31 8 20 93 148 156 203 178
136 126 144 186 201 155 151 90 43 24 28 75 199 222 254 251
196 79 31
// Grayscale correction values
//
Transform =
Θ
1
248
252
255
```

Figure 10. Sample image.tab Configuration File

pagedef.tab Configuration File

The pagedef table provides the PAGEDEF and FORMDEF values used from the value of the *PJPAPER parameter that is passed to the sap2afp transform with the Z access method. It also provides the fonts used for ABAP data.

The name of a **PAGEDEF** for line data is restricted to five digits instead of the usual six characters. The reason for this restriction is that the **PJPAPER** field is twelve bytes long and **must** begin with a **Z**. This restriction applies to ABAP reports (line data) with user-specific formatting only.

Paper Specifies the value of the OTF print option parameter **PJPAPER**. The value is not verified.

FormDef

Specifies the name of the form definition to be used for printing both OTF and ABAP reports. This value is not verified. An error results if the form definition is not found on the print server system.

sap2afp

PageDef

Specifies the name of the page definition to be used for printing ABAP reports. This value is not verified. An error results if the page definition is not found on the print server system.

FontNorm

Specifies the normal coded font used for line data printing. The value is not verified.

FontBold

Specifies the bold coded font used for line data printing. The value is not verified.

Figure 11 shows a sample pagedef.tab configuration file:

```
// PageDef table
// Format : Paper=X_65_132 FormDef=F1A10111 PageDef=P1H01SP1
// FontNorm = 50D0 FontBold = 50F0
// Notes:
// =====
// 1) The pagedefs apply to letter size paper.
     A4 paper size may require modifying the PageDef field.
// 2) Z INCH12 is a sample for a user specification
Paper=X 65 132 FormDef=F1A10111 PageDef=P1V06683 FontNorm = GB2A FontBold = GB2A
Paper=X 44 120 FormDef=F1A10111 PageDef=P1V06683 FontNorm = GB2A FontBold = GB2A
Paper=X 58 170 FormDef=F1A10111 PageDef=P1V06683 FontNorm = GT8A FontBold = GT8A
Paper=X 65 255 FormDef=F1A10111 PageDef=P1V06683 FontNorm = GT24 FontBold = GT24
Paper=X 65 80 FormDef=F1A10111 PageDef=P1C09182 FontNorm = GT2A FontBold = GB2A
Paper=X 90 120 FormDef=F1A10111 PageDef=P1C09182 FontNorm = GT5A FontBold = GT5A
Paper=X PAPER FormDef=F1A10111 PageDef=P1C09182 FontNorm = GT2A FontBold = GB2A
// Sample of an added user-defined pagedef entry:
// Paper=Z INCH12 FormDef=F1SAPFD PageDef=P1SAPPD FontNorm = GT2A FontBold = GB2A
```

Figure 11. Sample pagedef.tab Configuration File

printer.tab Configuration File

Before you can use the R/3 output device, you must map it to an Infoprint logical printer. This is done in the **printer.tab** configuration file that comes with the **sap2afp** transform. **printer.tab** is located in the **/usr/lpp/psf/sap2afp** directory. Because SAP R/3 restricts the names of output devices to four characters, the **printer.tab** configuration file allows you to map these names to longer and more meaningful names.

Note: You must update the **printer.tab** file every time you add or delete an R/3 AFP printer.

printer.tab uses the following keyword-value pairs:

Dest Specifies the four-character name of the R/3 output device. Specify this value for the -d flag of the sap2afp command.

System

Specifies the operating system from which the sap2afp output is printed.

Queue

Specifies the name of the Infoprint logical destination.

Node Specifies the IP address of the target operating system. The content (a maximum of 15 bytes) is not verified.

Node is required for all values of the **System** keyword, but the value is used only when **System=OS/2**.

Figure 12 shows a sample **printer.tab** configuration file. Note that you can include comments in lines preceded by two slashes (//).

```
// Printer table
// Format : Dest=SPRT System=AIX Queue=pc14039 Node=192.9.200.220
// Note: The Node parameter is not used for entries where the
// System field is AIX or MVS, but you must still enter a value.
Dest=MVSP System=MVS Queue=pc14039 Node=192.9.200.220
Dest=AIX1 System=AIX Queue=pc14029 Node=192.9.200.116
Dest=AIX2 System=AIX Queue=PSF4039 Node=192.9.200.220
Dest=OS2P System=OS2 Queue=OS2AFP Node=192.9.201.66
Dest=OS2 System=OS2 Queue=OS2AFP Node=192.9.201.66
```

Figure 12. Sample printer.tab Configuration File

For example, suppose that you have defined an R/3 AFP printer called **AFPT**. To map **AFPT** to the Infoprint logical destination **psf3116**, add the following line to **printer.tab**:

Dest=AFPT System=AIX Queue=psf3116 Node=0.0.0.0

xxxxyyyy.tab Configuration File

These tables are used for the mapping of characters of an individual SAP ASCII code page into an EBCDIC codepage. SAP uses two kinds of code pages: input code pages and output code pages.

SAP provides the the code page configuration files listed in Table 11.

Table 11. SAP Code Page Configuration Files

File Name	Input Code Page	Description	Output Code Page	Description
00000000.tab	T1000819	Latin-1 ISO ANSI 8-bit	T1V10273	Germany F.R./Austria-CECP
11000000.tab	T1000819	Latin-1 ISO ANSI 8-bit	T1V10273	Germany F.R./Austria-CECP
40010000.tab	T1000876 ¹	OCR-A ASCII	T1000892	OCR-A
40040000.tab	T1000877 ¹	OCR-B ASCII	T1000893	OCR-B
80000000.tab	IBM-932	Japanese	IBM-1031-SAP2AFP	Japanese

^{1.} Both the OCR-A and the OCR-B code pages are equivalent to ISO-8859/1 with the special characters hook, fork, and chair.

The file names correspond to the 4-digit value of the **INPUTCODEPAGE** plus the 4-digit value **OUTPUTCODEPAGE** parameter of the **CP** OTF command.

sap2afp

```
// Codepage table
// Inp CodePage 0000
// Out CodePage 0000
// Format : Ascii=Ebcdic
000 = 000
001 = 001
002 = 002
003 = 003
253 = 064
254 = 062
255 = 223
Figure 13. Sample xxxxyyyy.tab Configuration File (Single-Byte Code Pages)
// Japanese
// SAP2AFP is configured to use IBM-932-SAP2AFP as the iconv
// "From" value.
// This table sets the "To" value to IBM-1031-SAP2AFP.
```

Figure 14. Sample xxxxyyyy.tab Configuration File (Double-Byte Code Pages)

Examples

Transforming and Printing a File

This command converts the file FONTSHP.OTF and queues the AFP datastream for the destination called 3825. After conversion, SAP R/3 erases the input file FONTSHP.OTF.

```
sap2afp -d 3825 -f FONTSHP.OTF
```

CONVERT FOR=8000

CONVERT TO=IBM-1031-SAP2AFP

Transforming and Printing from Standard Input

This command redirects the spooled file SP11041 to stdin, which is read by the sap2afp transform. The input from stdin is placed in the sap2afp.tmp file, which is processed and then erased. AFP data stream output is sent to destination LPRT.

```
sap2afp -d LPRT -i < /usr/sap/DEV/DVEBMGS00/SP11041</pre>
```

Tracing the Transform

This command converts the file ANYFILE.OTF and sends output to destination 3825. A trace of the execution can be found in the file sap2afp.trc, which is placed in the current directory.

```
sap2afp -d 3825 -f ANYFILE.OTF -t
```

tiff2afp Command: Transforms TIFF Data to AFP in Infoprint Manager for AIX

Syntax

```
tiff2afp [-a ImageType] [-alg ProcessingAlgorithms]
         [-calib calibration] [-choice ImageChoice]
         [-C ConfigurationFile] [-clean cleanup]
         [-cmp compression] [-crop CropFactors]
         [-fit {trim | scale}] [-force]
         [-gcorr GrayscaleMappingTable] [-ink color] [-inv]
        [-i ScanOffsetFileName] [-1 ImageLength]
        [-M MemoryBound] [-mp | -nomp]
         [-ms space] [-msf SpaceFraction]
         [-o OutputFile] [-outbits NumberOfOutputBits]
         [-outcolor OutputColorModel] [-p PageRange]
         [-pagetype PageType] [-paper PaperSize]
         [-r resolution] [-respath ResourceSearchPath]
         [-rot rotation] [-scale ImageSize]
         [-sgcorr ScannerCorrection]
        [-sniff | -nosniff] [-term | -noterm]
         [-thresh HalftoneFile] [-v | -nov]
        [-w ImageWidth] [-wrkdir WorkDirectory]
        [-x LeftMargin] [-y TopMargin] [-z]
        [[file | directory | -f FileList | @FileList]...]
```

Description

The **tiff2afp** command transforms a TIFF (Tag Image Format File) data stream into an AFP (MO:DCA-P) or PostScript Level 2 data stream file.

The transform can process extended TIFF Revision 6.0 images, including bilevel, grayscale and color images. The output can be bilevel (IM1 or IOCA FS10), 4-bit or 8-bit grayscale, or 24-bit YCbCr color (IOCA FS11). The transform automatically uses halftoning to convert the grayscale and color images to bilevel.

Automatic Invocation

The PSF DSS automatically invokes the **tiff2afp** transform command whenever you submit a TIFF file for printing. You can pass options to **tiff2afp** using the **other-transform-options** attribute on the **pdpr** command or the **-o** flag of the AIX print commands and the **lprafp** command.

Input and Output

tiff2afp can process either standard input, or multiple files specified on the command line. If no input file is specified, stdin is assumed. Standard input is cached to a file (see the -wrkdir option) and then processed. Only a single TIFF file should be submitted via stdin. If multiple TIFF files are concatenated via standard input, all except the first one are ignored.

If an input file is specified on the command line, it can be either a TIFF file, a directory, or a file list (-f and @ prefixes). Multiple input file specifications are allowed. The transform processes each file in the order in which it was specified on the command line. If the -z option is specified, a list of file names to be

processed is also submitted via standard input. The files on the list are processed as if the list were given via the -f option on the same place on the command line as **-z**.

If the file name points to a directory, tiff2afp processes every file in that directory. The files are processed in the order they would be shown using the ls -a command. Directory search is not recursive, that is, the subdirectories are not searched.

If the file name is preceded by the -f option or the at sign (@), tiff2afp assumes that the file contains the list of TIFF files to be processed. Each of the files in the list is processed in the order it was listed.

If a TIFF file has the extension .tif, .tiff, .TIF, or .TIFF, this extension need not be given explicitly. tiff2afp first tries to open the file as specified and, if unsuccessful, tries to append the extensions .tif .tiff, .TIF, and .TIFF in turn.

For example, suppose that:

- The directory tFiles contains the files file1.tif, file2.tif, file3.tif, and file4.tif and nothing else.
- The file flist in the current directory contains the two file names tFiles/file2.tif and tFiles/file3.tif. The names listed in the file list may have their extensions omitted.
- The file flist2 contains the file name tFiles/file4. Again, the names listed in the file list may have their extensions omitted.

In order to process files file1.tif, file2.tif, file3.tif, and file4.tif, any of the following invocations of tiff2afp would work:

```
tiff2afp tFiles/file1.tif tFiles/file2.tif tFiles/file3.tif tFiles/file4.tif
tiff2afp tFiles/file1 tFiles/file2 tFiles/file3 tFiles/file4
tiff2afp tFiles/file*.tif
tiff2afp tFiles
tiff2afp tFiles/file1 -fflist tFiles/file4
tiff2afp tFiles/file1 -f flist tFiles/file4
tiff2afp tFiles/file1 -f flist -f flist2
tiff2afp tFiles/file1 @flist @flist2
```

The file list files allow the display text to be added for each file. A display text is any text starting with the pound character (#) and extending to the end of the line. The display text should follow the file name, and can extend over several lines, up to 2048 characters long. The initial # character on each line is discarded. If a display text is present for a file name, that text is displayed in the status and error messages instead of the file name. This is useful if the tiff2afp is invoked using temporary files whose names are meaningless to the user. Any display text before the first file name is treated as comment and discarded. Display text is allowed also if the -z option is used to submit the file list via standard input.

TIFF files may contain multiple images. The tiff2afp transform can process and output all the images in the file, both full and reduced resolutions, subject to the values given in the **-choice** and **-p** options. Transparency maps are ignored. If the page numbers are available in the TIFF data, the pages are sorted on output. The pages are not sorted across file boundaries.

The output file name can be either specified explicitly via the **-o** option, or derived from the input file name. If multiple input files have been specified, the default output file is standard output. If a single input file is given and the output file is

not specified explicitly, the transform strips the .tif or .tiff extension from the input file name (if one is present), and appends the .afp extension for AFP output, or the .ps extension for PostScript output, to get the output file name.

To disable automatic output file name generation and force the default output stream to be the standard output in all cases, set the environment variable TIFF2AFP_o to - or stdout, or, alternatively, put the line o=- or o=stdout into the configuration file and invoke that configuration file using the -C option or the TIFF2AFP_C environment variable.

For example, all the following commands:

```
tiff2afp myfile
tiff2afp myfile.tif
tiff2afp myfile -o myfile.afp
```

have myfile.afp as the output file. Note that there is no requirement for the explicitly specified input and output files to have .tif and .afp extensions. To process TIFF file foo.bar into an AFP file foo.bar2, invoke the transform using tiff2afp foo.bar -o foo.bar2

The output data stream is MODCA-P IS/1, MODCAP-P IS/2, or PostScript Level 2. IS/1 images are bilevel and are encoded as IOCA Function Set 10 or IM1. IM1 images are uncompressed. IOCA FS10 output images can be either uncompressed, or compressed via one of the four available compression algorithms (see the **-cmp** option). The default is ITU-T T.6 Group 4 compression. IM1 images are always uncompressed. IS/2 images can be either bilevel, 4-bit or 8-bit grayscale, or 24 bit YCbCr color. Multibit images are encoded as IOCA Function Set 11. Be aware that the only product that supports IOCA FS11 images is the AFP Workbench, that is, grayscale and color AFP images are not currently supported by any printer.

PostScript Level 2 images can be uncompressed or ITU-T T.6 Group 4 bilevel, uncompressed 8-bit grayscale or uncompressed 24-bit RGB color. By default, the transform leaves scaling and halftoning to the printer (that is, color TIFF images are output as 24-bit RGB color images).

Errors and Error Recovery

tiff2afp divides errors into fatal and non-fatal. The fatal error categories are the following:

- Errors in the user-specified parameters, either in the environment variables, the configuration file, or the command line arguments. These errors include unrecognized options, invalid values for parameters, or inability to open the configuration file or the output file.
- Out of memory errors. The requested memory is larger than the memory specified using the **-M** option or the dynamic memory allocation has failed.
- Disk space errors. The transform guards against trying to write to a full file system. See the **-ms** and **-msf** options for setting the minimum free disk space requirements. If the file system is full, the transform deletes the partial output file before terminating.
- Internal errors.

In the case of a fatal error, the last output page might not be complete.

Errors encountered in the TIFF files are non-fatal and **tiff2afp** attempts to recover from them. These errors include not being able to open an input file, an input file not being a TIFF file, or an input file containing features that cannot be processed.

tiff2afp

If the transform fails to open 15 or more input files, it assumes an error in the parameter list (for example, -f was used with a file that does not contain a file list) and terminates.

If an error is encountered in a file, the transform attempts to recover with the next image in the file. If such recovery is not possible, tiff2afp attempts to recover with the next input file. In both cases, a warning message is issued. Errors and warnings are output to standard error.

For example, let a directory tFiles contain files file1.tif, file1.txt, file2.tif and file3.tif, where file1.txt is an ASCII file. Invoking the transform via tiff2afp tFiles

processes the bilevel images in all three TIFF files correctly. A warning is issued that file1.txt is not a TIFF file.

Non-fatal errors can be made fatal by using the option **-term**, or the corresponding environment variable or configuration file entry. If -term is set, the transform terminates in error if it encounters an error in the TIFF data stream.

Data Transformations

If the input image is grayscale or color, and the output image type is bilevel (IOCA FS10 or IM1), the transform internally scales the image to the desired size, then uses a halftoning algorithm (ordered dither, the default, or Floyd-Steinberg) to convert it to bilevel. In converting the image to bilevel, the characteristics of the output device such as dot shape and dot gain must be taken into consideration. The **-gcorr** option can be used to specify a different mapping of gray levels.

For very light or very dark images, the halftoning algorithms can be automatically recalibrated to preserve details that would be lost using the default calibration. See the **-alg** option for more information.

To maintain the image quality, scaling must be done prior to halftoning. Halftoning algorithm is very computation-intensive. Unless the images are small, tiff2afp cannot process the color images fast enough to feed even a slow printer.

The size and position of the output image depend on several factors:

- The size specified to the transform
- The form map specified at print time
- The forms and options loaded in the printer

If the image is too large to to fit on the page, it is trimmed to size by default. Use the **-fit scale** option to instruct the printer to scale the image to the paper size. If the paper size is not specified explicitly via the **-paper** option, the paper size defaults to US letter size (8.5 by 11 inches). If the image is larger than this, the paper dimensions are increased as necessary. If the paper size is been specified explicitly, it is not increased if the image does not fit on paper. The options -1 and **-w** have the same effect as **-paper**.

The size of the actual image (as opposed to the paper size) is controlled by the -scale option. You can either specify a value of orig for the -scale option or give an actual size. If you specify orig, the output image is the same size as the input image. If you specify -scale with an actual size, the output image is scaled to the desired size. You can also specify a percentage for enlargement or reduction.

Even if you specify **-scale orig**, the image may still have to be scaled if the input resolution is different from the output resolution. By default, the transform leaves scaling to the printer. The exceptions are:

- Images that are being halftoned, which are always scaled in the transform
- Images that have different resolutions in X and Y directions

You can use the **-alg** option to instruct the transform to perform internal image scaling. Options **-alg**, **-clean**, and **-ink** choose and configure various scaling algorithms.

If possible, tiff2afp rewraps the TIFF raster data in MODCA-P headers. This does not change the compression algorithm used in the data, even though it might be different from the output compression algorithm specified on the command line. The data is rewrapped only if no changes are to be made in the image and if the compression algorithm is supported by the IOCA standard. Besides uncompressed data, the bilevel compression algorithms supported by both TIFF and IOCA are ITU-T Group 3 and Group 4 algorithms.

For 8-bit grayscale and 24-bit color images, both TIFF and IOCA FS11 support JPEG compression algorithms. However, TIFF and JPEG standards have different subsampling defaults than IOCA FS11. Thus, most 24-bit color images are not suitable for rewrapping, even if they use a JPEG compression algorithm and a color model supported by IOCA FS11.

Note also that JPEG is a lossy compression algorithm. Decompressing a JPEG image and then recompressing it for output might result in reduced image quality. For that reason, the default is to use no compression for the gray or color output.

Be aware that not all the printers support all the recognized IOCA compression standards. To make sure that the transform decompresses the data and recompresses it using the specified algorithm, use the option **-force**. If the output image is IM1, the image is always decompressed and scaled in the transform.

The TIFF images are often divided into many segments for efficient memory handling. Some printers terminate the printing in error if the page is too complex. For that reason, **tiff2afp** decompresses, repartitions, and compresses the data if it deems there are too many segments in the picture.

Parameters

tiff2afp behavior is governed by many parameters. The parameters are set by the following hierarchy (least significant first):

- Internal defaults
- Environment variables
- Configuration file
- Command-line arguments

Command Line Arguments

Note the following points regarding the command line arguments for the tiff2afp transform:

- Options and input file names can appear on the command line in any order.
- When you run **tiff2afp** as a standalone transform, the blank between option and value is optional (for example, both -inkblack and -ink black are valid).

- When you use the **-o** flag of the **enq**, **lp**, **qprt**, or **lprafp** commands to pass options to tiff2afp, no blank is permitted between option and value is optional (for example, -o-inkblack is valid, but -o -ink black is not).
- When you use the **other-transform-options** attribute on the **pdpr** command to pass options to tiff2afp, any string containing a blank must be surrounded by single quotes (for example, both other-transform-options=-inkblack and other-transform-options='-ink black' are valid).
- All values except file names are case-insensitive.
- If an option is specified multiple times, the last specification remains in force.
- If multiple configuration file names are given, they are processed in order.

Configuration File

The configuration file has entries of the form option=value, where each pair must reside on a separate line. Options and other syntax are the same as for the command line arguments and the option names are the same. Input files and configuration files cannot be specified in the configuration file (that is, nested configuration files are not supported). In the case of options without values (for example, -inv), the equals sign must be present.

Some command line options, for example, -calib, cannot be used in the configuration file or as environment variables. Options available only on the command line are noted as such in their descriptions.

If you do not specify a configuration file on the command line with the -C option, the transform checks for the existence of the default configuration file, /usr/lpp/psf/tiff2afp/tiff2afp.cfg. If this file exists, the transform uses it as the configuration file.

The following is an example of a valid configuration file:

```
scale = letter
r = 300
0 = -
inv=
alg=afp
```

Note that the spaces around the equals sign (=) are optional. In this example, the option-value pair $\mathbf{o} = -$ means that the default output file is the standard output. Output file name computation has been disabled.

Environment Variables

Environment variables have the form TIFF2AFP_option, where option is the same as on the command line and the configuration file.

Some command line options, for example, -calib, cannot be used in the configuration file or as environment variables. Options available only on the command line are noted as such in their descriptions.

For example, to achieve the same effect as the configuration file in the last example, the following statements have to be executed in the calling shell:

```
export TIFF2AFP scale=letter
export TIFF2AFP r=300
export TIFF2AFP o=-
export TIFF2AFP inv=" "
export TIFF2AFP alg=afp
```

There must be some value set for each desired option. For options that do not take a value, specify a blank surrounded by double quotes, for example:

```
export TIFF2AFP_inv=" " correct
export TIFF2AFP inv= has no effect
```

Resource Search Path

For resource files, such as scan offset files and grayscale correction files, the transform searches the current directory by default. You can use the **-respath** option to specify a list of directories to be searched for such files. This resource path does not apply to the configuration file.

Limitations

- · Only Huffman coding with baseline DCT JPEG algorithm is supported.
- Old style JPEG specification (Photometric Interpretation 6) is not supported. Photometric Interpretation 6 is obsolete and will be removed from the TIFF specification. Use the Photometric Interpretation 7 to incorporate the JPEG compressed images in TIFF files.
- Additional color information, such as alpha data, is disregarded.
- · Transparency maps are ignored.
- At most 8-bit grayscale and 24-bit color are supported.

Acknowledgments

This software is partially based on the Independent JPEG Group's JPEG compression and decompression code.

Options and Values

@FileList

Specifies a name of a file that contains a list of files to be processed by the transform. If the @ option is present, the output file defaults to standard output, even if the list of files contains only a single entry. Multiple @ options are allowed. Also see the -f and -z options. The @ is not preceded by the dash, and is implemented to maintain compatibility with the ps2afp transform.

```
-a {ioca | ioca10 | ioca11 | im1 | PS.2}
```

-a {IO1_G4 | IM1 | IO1 | IO1_MMR | PSEG_IO1_G4 | PSEG_IM1 | PSEG_IO1 | PSEG_IO1_MMR | OVLY_IO1_G4 | OVLY_IM1 | OVLY_IO1 | OVLY_IO1_MMR}

Choice of the output image type. The first syntax chooses between the IOCA FS 10 (ioca, ioca10), IOCA FS11 (ioca11), IM1, and PostScript Level 2 (PS.2) output. IOCA FS10 and IM1 yield bilevel images, while IOCA FS11 results in 4-bit or 8-bit gray or 24-bit color output (see option -outbits). Note that presently the only product that supports IOCA FS11 is the AFP Workbench. The output compression algorithm is set via the option -cmp. To set the page type (page, overlay, page segment or object), use the -pagetype option.

The second syntax is to maintain compatibility with the **ps2afp** transform, and sets the image type (**IO1** for IOCA FS10 or **IM1** for IM1 output), compression (**G4** for Group 4 or **MMR** for Group 3), and page type (**PSEG** for page segment or **OVLY** for overlay). If **PSEG** or **OVLY** is not specified,

the output is a printable page. If no compression algorithm is specified, the output is not compressed. The second syntax cannot be used for IOCA FS11 output.

Some older printers do not support IOCA images. In such cases, the IM1 output type should be chosen. IM1 images are uncompressed and thus use more space. The processing might also take longer since the IM1 image cannot be scaled by the printer and so internal scaling algorithms must be used. See option -alg.

The default is **ioca** for IOCA FS10 output compressed via Group 4 algorithm.

This option is similar to the **image-out-format** document attribute on the **pdpr** command.

```
-alg \{afp \mid alg1 \mid alg2 \mid alg3\}
```

-alg {htod1 | htfs}

-alg htcal1

Choice of the scaling and halftoning algorithms. You can specify multiple choices, separated by commas, for one **-alg** option. The effect is the same as specifying multiple **-alg** options. For example, -alg htfs,htcal is equivalent to -alg htfs -alg htcal.

The scaling algorithms are:

- If **afp** is chosen, the scaling is done using the default algorithm in the printer. This makes the transform much faster. If the image must be reduced, however, this algorithm may drop some information from the image, such as thin lines.
- alg1 activates the internal scaling algorithm to scale the image explicitly to the specified size. This algorithm is guaranteed not to discard any ink. "White space" in the image, however, may be lost (that is, features close to one another might merge). This algorithm makes the transform run longer, and might occasionally make for a "dirty" image, since the occasional "noise pixels" in the scanned images tend to be amplified.
- alg2 activates the more flexible version of alg1. If this algorithm is selected, option -clean can be used to specify the amount of ink "cleanup" to be performed. Option -clean 0.0 makes the algorithm alg2 perform like alg1 (albeit more slowly). Increasing the value specified in -clean discards more and more ink, until -clean 1.0 results in a blank page.
- alg3 activates a scaling algorithm that works by deleting or duplicating rows and columns in the image. This is a fast general-purpose algorithm.

For bilevel images, the default is **afp** if the output image type is IOCA and **alg3** if the output image type is IM1. For color images with bilevel output, the scaling is always done prior to the halftoning algorithm. If a grayscale or color output is chosen (**-a ioca11**), this option is ignored and the algorithm is set to **afp**.

The halftoning algorithms are:

- **htod1** uses an ordered dither with a screen derived from the value of the **-thresh** option. The default is an 85 line per inch screen.
- htfs uses the Floyd-Steinberg algorithm.

htcal1 recalibrates the halftoning algorithm for each image. htcal1 forces
the transform to read the whole image into memory and requires an
additional pass through the image. It should be used only for very light
or very dark images.

The default is **htod1**. Each halftoning algorithm uses a different internal default calibration curve. If the automatic calibration is turned on, a still different set of calibration curves are used.

See options -clean, -gcorr, -ink, -paper, -scale, -thresh, -l, -w, -x, and -y.

-calib scanner

-calib {scanner | printer | patch | patchr},name1...

Transform calibration for the scanner or printer. If **scanner** is specified, **-sgcorr** must be present. If **printer** is specified, **-sgcorr** may or may not be present. If **patch** or **patchr** is specified, **-sgcorr** (if present) is ignored. Detailed explanation of the calibration process is beyond the scope of this entry.

You cannot specify **-calib** in the configuration file or as an environment variable.

-choice {full | reduced | both}

TIFF image files may contain both full and reduced resolution versions of each image. The transform can output both versions, or full resolution only, or reduced resolution only, depending on the value for this option. The default is to output the full resolution images only.

See the **-mp** and **-nomp** options.

-C ConfigurationFileName

The name of a configuration file containing option-value pairs. If multiple -C options are given on the command line, they are processed in order. Specifying the configuration file on the command line overrides any specification done via the TIFF2AFP_C environment variable.

The default configuration file is /usr/lpp/psf/tiff2afp/tiff2afp.cfg.

-clean $\{0.5 \mid x.xxx\}$

The internal scaling algorithm **alg2** allows for variable thresholding. The scaled pixel is declared painted if the fraction of its area greater than the threshold is painted in the original image. The value *x.xxx* is a real number between zero and 1 inclusive and gives this threshold.

If the option **-clean 0.0** is issued, **alg2** behaves like **alg1** and turns on a pixel as long as any part of the pixel has been painted in the original image. **-clean 1.0** results in a blank image because the output pixels are never painted.

Note that setting **-clean 0.95** and **0.9999999** turns on the pixels that had essentially all the area painted in the original picture. Depending on the data, most of the image will probably be preserved. Increasing **-clean** by a small amount to **1.0** erases the image. If the scaling algorithm is not **alg2**, this option is ignored. The default is **-clean 0.5**.

-cmp {none | mh | mmr | g3 | g4 | jpeg}

Choice of the output image compression algorithm:

none Uncompressed output

ITU-T T.4 G3 Modified Huffman mh

IBM Modified Modified Read mmr

g3 ITU-T T.4 G3 Modified Read

ITU-T T.6 G4 g4

jpeg JPEG non-differential Huffman coding with baseline DCT. The output image data should be compressed to reduce the file sizes

and increase the printing speed.

The default compression is ITU-T T.6 Group 4 for bilevel images and no compression for grayscale or color images. Note that some printers may not support Group 4 compression algorithm and require using the **-cmp** option to choose a different one. The JPEG algorithm can compress only 8-bit grayscale and 24-bit color images. 4-bit grayscale images cannot be compressed.

-crop $t,b,l,r[i \mid m \mid p \mid d]$

Image cropping. *t,b,l,r* specify how much should be cropped from the image top, bottom, left edge, and right edge. The numbers are floating point and can be either positive or negative. Negative numbers indicate that a blank space should be inserted. The units are inches, millimeters, points, and dots (pels), with the default being dots. The cropping is specified in the context of the output page, to that "top" means the top of the output page and so on, regardless of the -rot option. To crop, the transform will enlarge the image by the amount to be cropped, then crop the specified amount by manipulating the actual bitmap. The resulting image has the size as specified by the explicit (or implicit) -scale option. See also option -j.

If **-fit trim** is specified, the right and the bottom edge of the image are not cropped. Instead, the image grows as necessary. Because -fit trim causes the output data stream to contain the "position and trim" specification, the printer discards any extra image.

-f FileList

Specifies the name of a file that contains a list of files to be processed by the transform. If the -f option is present, the output file defaults to standard output, even if the list of files contains only a single entry. Multiple -f options are allowed. See also options @ and -z.

-fit {trim | scale}

Determines whether the printer behavior will be position-and-trim or scale-to-fit if the image is too large to fit on the paper. The default is **trim**.

This option is equivalent to the **image-fit** document attribute on the **pdpr** command.

-force If present, this option forces **tiff2afp** to decompress and recompress the image, regardless of other factors.

-gcorr FileName

Specifies a file with grayscale mapping table for halftoning of the grayscale and color images to bilevel for output. The mapping table must be provided to compensate for the printing characteristics of the particular output device and paper type, such as dot gain. This file must contain either:

- 256 real numbers, one for each level of gray in the 8-bit grayscale image
- The PostScript settransfer operator

The algorithm converts every image to 8-bit grayscale before applying the halftoning algorithm. The default internal mapping table has been optimized for the 600-pel IBM Infoprint 4000 laser printer. You shouldn't change this unless you know what you are doing. See also options **-alg** and **-thresh**. PostScript code submitted via the **-thresh** option can have the same effect as **-gcorr**.

-ink {black | white}

This option is used only with scaling algorithm alg1 or alg2. The TIFF images can be either black on white or white on black. The internal scaling algorithm must know which, because "ink" is preserved at the expense of "non-ink" The default value, "black", indicates that the image is black on white.

If the option **-inv** is used to print the reversed image, the inversion is done as the data is read by the transform, before any processing is done. The black or white must thus be specified in the terms of the printed image, not in the terms of the input TIFF image.

-inv Reverses the image. Areas that are black in the original image become white and vice versa. Note that the reversed image may be either black on white or white on black, depending on the original image.

-i ScanOffsetFileName

Sometimes input images must be shifted to get the desired positioning on the page. The scan offset file contains the directions for shifting. The file has the format of

```
[attribute]
values
:
values
[attribute]
values
:
values
values
```

Currently, the recognized attributes are [Units] (values millimeters, mm, inches, in, points, dots, pels) [Page_Offset_Type] (values crop or grow) and [Page_Offsets]. The values for page offsets are in the format FileName,Hhoriz,Vvert Each entry refers to a file. The file names must be specified (or at least the leading comma must), but are currently ignored and the offset factors are applied to each file in turn. Note that the same factors are applied to each image in the file. The horiz and vert values are the amount that the image is to be shifted, in the horizontal and vertical direction. The positive directions are down and right (that is, the origin is in the left upper corner of the page). The default units are millimeters. Like the values for the -crop option, the shifts are specified in the output space context.

Extra spaces and blank lines are allowed. Unrecognized attributes and their values are ignored. See the sample file **shift.sample**.

If the image is moved left or up, part of the bitmap is removed. If the image is moved down or right, removal is governed by the value of the **[Page_Offset_Type]** attribute. If **crop** is chosen, the transform removes the requisite amount from the right and bottom edges of the bitmap. If **grow** is chosen, the transform does not remove any space. The bitmap grows and

the trimming, if any, is left to the printer. If the **-fit trim** option (the default) is specified, [Page_Offset_Type] defaults to grow. For -fit scale, [Page_Offset_Type] defaults to crop.

-1 {11i | yyy.yy[d | m | i | p]}

Specifies the paper length. The optional units are dots (pels), millimeters, inches, or points. The default unit is dots. If the unit is dots, decimals (if any) are ignored. The default paper length is 11 inches. See options -w to set the paper width or **-paper** to set both dimensions at the same time.

-M {0 | nnn}

Limits the amount of memory available to tiff2afp. nnn is the maximum amount of memory in kilobytes. A value of 0 means there is no memory limit. nnn can be set from 0 to the maximum value that AIX allows. The default is 0.

[-mp | -nomp]

Each TIFF image is supposed to have a marker bit set if there are multiple TIFF images in the file. This marker is sometimes missing, even if there are multiple images present in the file. The **-mp** option instructs the transform to behave as if the multipage marker bit were set. The transform then processes all the images in the file, subject to the **-p** and **-choice** options. The default is to leave the marker bit unset (**-nomp**).

-ms {10 | nnn}

Requires that at least *nnn* kilobytes of disk space be available on the file system that contains the output file. This limit is enforced every time data is written to the output file. If the output is standard output, this option is ignored. The default is 10. See option -msf.

-msf $\{0.1 \mid x.xxx\}$

The number x.xxx is a real number between 0 and 1. It denotes the minimum space that must be left unused on the file system containing the output file. The space is given as a fraction of the total space in the file system. This limit is enforced every time data is written to the output file. If the output is standard output, this option is ignored. The default is **0.1**. See option **-ms**.

```
-nomp See [-mp | -nomp].
```

-nosniff

See [-sniff | -nosniff].

-noterm

See [-term | -noterm].

See [-v | -nov]. -nov

-o FileName

Optional output file name. Specify - for standard output.

-outbits NumberOfOutputBits

Sets the number of bits per pel in output. This value must be 1, 4, 8, or 24. If the output image type is IOCA FS10 or IM1, the number of output bits is set to 1 and this option is ignored. For IOCA FS11 output, the default is 24. Note that this number represents the maximum number of bits used per pel. Thus, even if the number of bits is set to 24, a 4-bit grayscale image is still displayed in 4-bit format.

-outcolor {rgb | ycbcr | ycrcb}

Sets the output color model to RGB, YCbCr, or YCrCb if the image type is IOCA FS11 and the number of output bits is 24. Otherwise, this option is ignored. The default is **ycbcr**.

-p {**even** | **odd** | *nn* | *nn-mm* | *nn-*}

Specifies that the output should only contain the specified pages. If no -p option is given, all the pages are output (but see the -choice option for printing full or reduced resolution images of each page). Multiple -p options may be specified. Their effect is cumulative. Regardless of the order in which the pages are specified, they are always printed in ascending order. The recognized values are:

Print all even pages Print all odd pages odd Print page nn nnnn-mm Print pages nn to mm, inclusive. Print all pages starting with page nn nn-

Pages are numbered starting with 1.

-pagetype {page | overlay | ovly | pseg | object}

Sets the output page type to be page, overlay, page segment or object. The same page type is set for every page in the output. Thus, unless option -p is used to select a single page, multiple overlays, page segments or overlays are stored in the output file. The default is page. See option -a.

-paper {a5 | a4 | a3 | letter | folio | legal | ledger | xxx.xx,yyy.yy[d | m | i | Specifies the output paper size. The supported values are: **p**]}

a3 A3 format (297 by 420 mm or 11.69 by 16.54 inches)

a4 A4 format (210 by 297 mm or 8.27 by 11.69 inches)

A5 format (148 by 210 mm or 5.83 by 8.27 inches) a5

8.5 by 11 inches (216 by 279 mm) letter

folio 8.5 by 13.0 inches (216 by 330 mm)

legal 8.5 by 14.0 inches (216 by 356 mm)

ledger 11.0 by 17.0 inches (279 by 432 mm)

$xx.xx,yy.yy[\mathbf{d} \mid \mathbf{m} \mid \mathbf{i} \mid \mathbf{p}]$

Horizontal and vertical page dimensions. The optional units are dots (pels), millimeters, inches, or points.

The default paper size is letter. If **-paper** is not used, the paper size is increased, if necessary, to contain the output image.

See options -1, -w, and -scale.

-r {300 | nnn}

The output device resolution, specified in dots per inch. The default is 300.

This option is equivalent to the **default-printer-resolution** document attribute on the pdpr command.

-respath *directory*[:*directory*...]

Sets the search path for resource files, such as the scan offset files and grayscale calibration curve files. If a resource file name is specified as a relative name (does not start with a /), the transform searches every directory in the path, in the order specified in the path, until it finds the file (or fails). See options **-j** and **-gcorr** for scan offsets and grayscale calibration curve. The default is the current directory.

-rot {0 | 90 | 180 | 270[p | i]}

The image is rotated in the clockwise direction by the amount specified. The default is zero, that is, no rotation.

If \mathbf{p} is specified, the transform sets the output datastream in such a way that the printer performs the actual image rotation. If \mathbf{i} is specified, the transform rotates the output bitmap. When \mathbf{i} is chosen, the transform takes much longer to run and uses much more memory. If no letter is specified, the default or any previous value (such as the value specified in the configuration file) remains in force. The default is \mathbf{p} .

-scale {orig | a5 | a4 | a3 | letter | folio | legal | ledger | $xxx.xx,yyy.yy[\underline{d} \mid m \mid i \mid p] \mid xxx\%$ }

Specifies the output image size. The image is scaled to this size and centered in the area defined by the paper size and margin options. The supported values are:

<u>orig</u> Preserve the input image size, regardless of the printable paper area.

a3 A3 format (297 by 420 mm or 11.69 by 16.54 inches)

a4 A4 format (210 by 297 mm or 8.27 by 11.69 inches)

a5 A5 format (148 by 210 mm or 5.83 by 8.27 inches)

letter 8.5 by 11 inches (216 by 279 mm)

folio 8.5 by 13.0 inches (216 by 330 mm)

legal 8.5 by 14.0 inches (216 by 356 mm)

ledger 11.0 by 17.0 inches (279 by 432 mm)

$xx.xx,yy.yy[\mathbf{d} \mid \mathbf{m} \mid \mathbf{i} \mid \mathbf{p}]$

Horizontal and vertical image dimensions. The optional units are dots (pels), millimeters, inches, or points.

xxx% Magnification relative to the original image size. Numbers below 100% mean reduction, while Numbers above 100% mean enlargement. For example, **-scale 200**% causes the output image to be twice as long and twice as wide as the input image.

The default image size is **orig**.

-sgcorr FileName

Specifies the name of the scanner-related calibration file. To use this option in the calibration process (with the option **-calib**) you must specify a single file name. If **-calib** is absent, this option is ignored.

A detailed discussion of **-sgcorr** is beyond the scope of this document.

[-sniff | -nosniff]

Turns automatic conversion to black on white for bilevel images on (-sniff) or off (-nosniff). The automatic conversion algorithm counts the number of 0 and 1 bits in the image. If there are fewer zeros, it assumes the printed features are represented by zeros (white on black), and inverts the image to be black on white. The detection and conversion are done after the conversion specified by the Photometric Interpretation tag is applied (if any).

This option is ignored if the image is not bilevel. The default is **-nosniff**.

[-term | -noterm]

Disables (-term) or enables (-noterm) error recovery.

- When error recovery is disabled, on encountering an error in a TIFF file, the transform terminates with an error message and a nonzero return code.
- · When error recovery is enabled, the errors in TIFF files are treated as non-fatal. The transform attempts to recover with the next image in the file, or with the next file. The return code is zero.

The default is **-noterm**.

-thresh FileName

Specifies a file that contains a PostScript Type 1 or Type 3 halftone dictionary. Alternatively, the PostScript code can specify the setscreen operator instead of a Type 1 dictionary. The halftone cell in the dictionary is used to overwrite the default ordered dither clustered dot halftone cell. If the PostScript code contains a transfer function, either in the halftone dictionary or specified by the settransfer operator, the current grayscale correction curve is overwritten as if **-gcorr** were used.

[-v | -nov]

Turns verbose mode on (-v) or off (-nov).

- When verbose mode is on, the transform prints a message as it opens each resource file, then echoes the command line, then prints a message for each file name as it is processed.
- When verbose mode is off, the transform prints only error messages.

The default is **-nov**.

-w $\{8.5i \mid yyy.yy[d \mid m \mid i \mid p]\}$

Specifies the paper width. The optional units are dots (pels), millimeters, inches, or points. The default unit is dots. The default page width is 8.5 inches. See options -1 to set the paper length or -paper to set both dimensions at the same time.

-wrkdir WorkDirectoryName

The TIFF data stream is by definition non-sequential. Thus, input from **stdin** must be cached on disk before it can be processed. This option specifies which directory to use for the caching of the standard input. If this option is absent or the directory cannot be opened, the transform first tries to use /var/psf/tiff2afp as the working directory and, if /var/psf/tiff2afp is absent, uses /tmp.

The **stdin** cache file is never visible to the user because it is immediately unlinked after creation. Thus, the cache file is always deleted when tiff2afp finishes execution, even if **tiff2afp** is killed or otherwise terminates in error.

$-x \{0 \mid nnn.nn[d \mid m \mid i \mid p]\}$

Specifies the left margin. The optional units are dots (pels), millimeters, inches, or points. The default unit is dots. The default is zero (no margin).

$-y \{0 \mid nnn.nn[d \mid m \mid i \mid p]\}$

Specifies the top margin. The optional units are dots (pels), millimeters, inches, or points. The default unit is dots. The default is zero (no margin).

Signifies that a list of files to be processed is submitted from standard -Z input. See also options -f and @.

tiff2afp

Chapter 7. Infoprint Object Attributes

This chapter lists the attributes for these Infoprint print objects:

- "Attributes for Actual Destinations" on page 336
- "Attributes for Auxiliary-Sheet Objects" on page 458
- "Attributes for Documents and Default Documents" on page 464
- "Attributes for Jobs and Default Jobs" on page 542
- "Attributes for Logs" on page 593
- "Attributes for Logical Destinations" on page 598
- "Attributes for Media" on page 624
- "Attributes for Queues" on page 630
- "Attributes for Resource Contexts" on page 640
- "Attributes for Servers" on page 643
- "Attributes for Transforms (Windows NT or Windows 2000 only)" on page 666

Attribute Disclaimer

There are attributes and attribute values identified in the *ISO 10175-1 Information Technology - Text and Office Systems - Document Printing Application (DPA) Part 1: Abstract-Service Definition and Procedures* standard that Infoprint does not support. If you use any of these non-supported attributes or values, Infoprint may accept them. However, the results may be different than you expect. Sometimes, Infoprint may issue a message indicating that it does not support the attribute or value.

About Destination Support Systems

The programs that the actual destination uses to send jobs to the output device are called the destination support system (DSS).

Infoprint Manager for AIX supports the following DSSs:

AIX DSS

The AIX DSS permits Infoprint Manager to bridge to the AIX print-spooling subsystem. In standard AIX printing, users submit jobs to an AIX print queue. The AIX print-spooling subsystem schedules the jobs and passes them to a printer device by means of a backend program, usually **piobe**, or if the queue is a remote queue, **rembak**.

In the AIX DSS, users submit jobs to a destination from which an Infoprint queue receives them. The Infoprint physical printer submits jobs to the printer device using an AIX backend program.

You should attach this type of printer device as specified by its documentation before creating its associated Infoprint actual destination.

BSD DSS

The BSD DSS permits Infoprint Manager to bridge to existing UNIX/BSD printing subsystems. Infoprint Manager sends jobs submitted to BSD physical printers as separate print requests to a local or remote print queue.

For local printer devices, Infoprint Manager can use the **piobe** backend program. More typically, Infoprint Manager uses the **rembak** program to send jobs to a printer device connected to another processor. This processor can run AIX or any other operating system that supports the **lpd** protocol and that connects to the network using TCP/IP.

For remote printer devices, you must set up a remote queue and configure the remote system. Refer to the printer configuration documentation of the remote system.

PSF DSS

The PSF DSS permits Infoprint Manager to bridge to the IBM Print Services Facility (PSF) printing subsystem. This DSS allows communication with output devices that have Intelligent Printer Data Stream (IPDS) functionality. The PSF DSS is the most flexible DSS. It provides a single point of control and tracking for print jobs. Infoprint Manager transforms jobs submitted to PSF destinations to IPDS or PCL before sending them to the output device.

The way in which Infoprint Manager communicates with the output device depends on the type of actual destination. For PSF DSS actual destinations, it also depends on the attachment type.

3170 DSS

Infoprint Manager uses the 3170 DSS to communicate with IBM InfoColor 70 printer devices. Before creating the actual destination, you must determine the Internet Protocol (IP) address of the printer device.

Infoprint 2000 DSS

Infoprint Manager uses the Infoprint 2000 DSS to communicate with TCP/IP-attached IBM Infoprint 2000 printer devices that do not use the AFCCU Channel Driver. Before creating the actual destination, you must determine the Internet Protocol (IP) address of the printer device.

Email DSS

Infoprint Manager uses the email DSS to communicate with electronic mailing systems.

Fax DSS

Infoprint Manager uses the fax DSS to communicate with fax devices.

Infoprint Manager for Windows NT and Windows 2000 supports the following DSSs:

BSD DSS

The BSD DSS permits Infoprint Manager to bridge to remote printers or printing subsystems. Infoprint Manager sends jobs submitted to BSD physical printers as separate print requests to a remote print queue.

Infoprint Manager typically uses the **lpr** command to send jobs to a printer device or to another system. This can be any device or system that supports the **lpd** protocol and that connects to the network using TCP/IP. Refer to the printer configuration documentation of the remote device or system for details on how to set up a remote queue.

PSF DSS

The PSF DSS permits Infoprint Manager to bridge to the IBM Print Services Facility printing subsystem. This DSS allows communication with output devices that have Intelligent Printer Data Stream (IPDS) functionality or that have PCL functionality. The PSF DSS is the most flexible DSS. It provides a single point of control and tracking for print jobs. Infoprint Manager transforms jobs submitted to PSF destinations to the IPDS or PCL data stream before sending them to the output device.

The way in which Infoprint Manager communicates with the output device depends on the type of actual destination. For PSF DSS actual destinations, it also depends on the attachment type. (See "Understanding Attachment Types for PSF Actual Destinations".)

Passthrough DSS

The Passthrough DSS permits Infoprint Manager to bridge to the Windows print-spooling subsystem. This DSS supports mono-IPDS (PostScript or PCL) printers by using standard Windows NT/Windows 2000 ports and port monitors.

You must attach this type of printer device as specified by its documentation before creating its associated Infoprint Manager destination.

IPP DSS

Infoprint Manager uses the IPP DSS to communicate with destinations through the Internet Print Protocol (IPP). This DSS allows Infoprint Manager to access a printer using a Uniform Resource Locator (URL) string.

Understanding Attachment Types for PSF Actual Destinations

The attachment type for an actual destination defines how the printer device attaches to the server and communications with Infoprint Manager. Based on the printer device, the attachment type is one of the following:

• TCP/IP. The printer device communicates using the Intelligent Printer Data Stream (IPDS) and attaches to the server through the TCP/IP network. To create the actual destination, you must specify the Internet Protocol (IP) address of the printer device and the port number through which Infoprint Manager communicates with the device. The port number for TCP/IP-attached printers is

Attributes

- an integer from 5001 to 65535. For printers attached using the i-data 7913 IPDS Printer LAN Attachment, you must use 5001 as the port number.
- Channel. The IPDS printer device attaches to the server through a S/370 Channel Emulator/A adapter for Infoprint Manager for AIX and an IBM 4159 Model 001 S/390 Parallel Channel Emulator Card (using S/390 bus/tag cabling) for Infoprint Manager for Windows NT and Windows 2000. Before creating the actual destination, you must identify the slot number in the server that contains the card and the hexadecimal control unit address of the printer device.
- Other-driver. The PCL, PostScript, or PPDS printer device communicates using TCP/IP or attaches directly to the server through a parallel/serial port (or through a hardware alternative to such direct attachment). When you want to create the actual destination with Infoprint Manager for Windows NT and Windows 2000, you must specify the port associated with a port monitor needed to operate the printer.
- Command. You must attach this type of printer as specified by its documentation and configure it in AIX before creating its associated actual destination for Infoprint Manager for AIX or configure it to function as a Windows printer (using the standard Windows Add Printer Wizard) before creating its associated actual destination for Infoprint Manager for Windows NT and Windows 2000.
- **Upload-SNA**. With Infoprint Manager for AIX, the printer device is attached to a host system. Infoprint Manager communicates with PSF for OS/390 or PSF for MVS through the SNA network. Before creating the actual destination, you must determine the code pages used on both the AIX and host systems.
- **Upload-TCP/IP.** With Infoprint Manager for AIX, the printer device is attached to a host system. Infoprint Manager communicates with PSF for OS/390 or PSF for MVS through the TCP/IP network. Before creating the actual destination, you must determine the Internet Protocol (IP) address of the printer device and the port number through which Infoprint Manager communicates with the device. The port number for TCP/IP-attached printers is an integer from 5001 to 65535. You must also determine the code pages used on both the AIX and host systems.

Attributes Displayed in the Infoprint Manager Administration GUI

Attributes that include **GUI Label** are shown in the corresponding properties notebooks in the Infoprint Manager Administration GUI. The following objects have properties notebooks:

- Actual Destination
- Documents and Default Documents
- Jobs and Default Jobs
- Logical Destinations
- Servers
- Transforms

Introducing Object Attributes

All Infoprint objects have associated attributes. Attributes provide information about the objects and determine what you can do with objects.

Attribute Disclaimer

There are attributes and attribute values identified in the ISO 10175-1 Information Technology Text and Office Systems - Document Printing Application (DPA) - Part 1: Abstract-Service Definition and Procedures standard that Infoprint does not support. If you use any of these non-supported attributes or values, Infoprint may accept them. However, the results may be different than you expect. At times you may receive a message stating that Infoprint does not support the attribute or value.

Initially Settable, Resettable Attributes, and Non-Settable Infoprint attributes fall into three categories:

Initially settable

For some attributes, you can set a value when you create the object with the **pdcreate** or the **pdpr** command. You cannot change these attributes afterwards.

For example, the following command:

```
pdpr -x "job-originator='Anne Brown'" -d Sevv1-ld bigbook
```

creates a job containing a file called bigbook and identifies the person who submitted the job by name. The attribute job-originator is initially settable and you cannot change it.

Resettable

For some attributes, you can set or modify the value using the pdmod command (for jobs and documents) or the pdset command (for all objects, including jobs and documents), after you create the object.

For example, this command:

```
pdmod -x "job-end-message='Please call 5-9999 for pickup'" 37
```

sets a new value for the **job-end-message** attribute for the existing job whose local ID is 37.

Non-settable

You cannot set a value for some attributes at any time.

For example, in the following command:

```
pdcreate -c queue Serv1:Queue3
```

Infoprint uses the command arguments to assign the queue attribute queue-name the value Queue3, and the associated-server attribute the value Serv1. You cannot set different values for these arguments using the -x flag of the **pdcreate** command and you cannot change them later.

Resetting Attributes to the Default Value

"Chapter 7. Infoprint Object Attributes" on page 329 shows default values for all attributes. For some attributes, the default value is "no value".

- When you create an object, Infoprint assigns a default value (or values, for some multi-valued attributes) to each attribute. You can override these default values by specifying a different value using the -x and -X flags of the pdmod or pdset commands.
- You can change values back to their default values by using the pdmod or pdset commands and specifying the attribute name followed by two equals signs, ==, without any attribute value.

Attributes

```
For example, the following command:
pdset -x "printer-end-sheet==" Serv3-pp
```

sets the value assigned to printer-end-sheet for the actual destination Serv3-pp back to its default value.

 Deleting all the values from a multi-valued attribute or deleting the value of a single-valued attribute sets the attribute value to the default values.

Attribute Syntax

This section describes the syntax to use when you set values for three types of attributes on the command line or in an attributes file. Most attributes are either single-valued (they can have only one value at a time) or multi-valued (they can have multiple values). Infoprint also has some complex attributes.

Examples of these types of attributes follow.

Single-Valued Attributes: For single-valued attributes, the syntax is:

```
"attribute=value"
"attribute='value with spaces'"
```

Enclose the value in single quotation marks if it includes spaces, for example: -x "message='Down for maintenance until 7AM'"

Note: The Infoprint administrator's GUI does not require quotation marks.

Multi-Valued Attributes: For multi-valued attributes, the syntax is:

"attribute=value1 value2 value3"

where value1 value2 value3 are multiple values of the attribute. Separate the values with spaces and enclose the attribute name and values in double quotation marks. For example:

-x "content-orientations-supported=portrait landscape"

assigns two values, portrait and landscape, to the content-orientations-supported attribute.

Note: In the Infoprint administrator's GUI, most multi-valued attributes require you to specify each value on a separate line of a list box. When you must enter multiple values in a single field, separate the values by commas. For example, enter multiple values for the **chars** attribute like this:

```
GT10,GT12
Fonts
```

Complex Attributes: Complex attributes can have multiple values, but each value itself has multiple components. Each component of a value has its own values. Two types of complex attributes are those that require braces, { } , enclosing each value, and those that have the components of each value separated by a colon, : .

Note: In the Infoprint administrator's GUI, you enter each component in a separate field. No braces or colons are required.

Complex Attributes that Require Braces: The only complex attribute that requires braces is **notification-profile**

- Each value for this complex attribute begins and ends with braces, { } .
- · Each value has several components
- · Each component has a name and associated values
- The sequence in which you enter the components is not important
- The component event-identifiers is the only component that can have multiple values

An example of creating a **notification profile** with one value for a queue follows:

```
pdset -c queue
   -x "notification-profile={event-identifiers=job-modified
   queue-state-changed delivery-method=message
   event-comment='This is a job modification or status event'
   delivery-address=dave@cowboy locale=En_US.IBM-850}" Queue1
```

If you change one component within the notification profile, Infoprint sets all the rest of the components of that value to their default values. For example, the following command sets the **delivery-address**, but Infoprint sets the other components to their defaults:

```
pdset -c queue
-x "notification-profile={delivery-address=tom@hope}" Queue1
```

If you want to maintain the existing values, you must specify them. You cannot use the add, +=, or delete, -=, operators of the **pdset** or **pdmod** commands when changing the component values within a **notification-profile** value. However, you can add or delete all components of a value from the **notification-profile** by using the add, +=, or delete, -=, operators. For example, the following command:

```
pdset -c queue
-x "notification-profile+={delivery-address=mary@cowboy} Queue1
```

delivery-method=message delivery-address=mary@cowboy

adds another value to the previous one. Now the **notification-profile** has two values.

```
notification-profile=
{event-identifiers=job-modified queue-state-changed delivery-method=message
event-comment='This is a job modification or status event'
delivery-address=dave@cowboy locale=En_US.IBM-850}
{event-identifiers=object-deleted object-cleaned queue-backlogged
```

The second value contains default values for each component except the delivery address. If you want values other than defaults, you must specify them.

Complex Attributes that Require Colons: All other complex attributes require colons between components.

Do not enter the component name.

locale=En US.IBM-850}

- Separate the values for the components with a colon, : , and no spaces
- Enter a colon even if you do not enter a value for a given component. Infoprint sets the default value or no value for that component.
- If you use the default value for the last value, Infoprint does not require the colon for that component.
- Separate each attribute value within a multi-valued attribute with spaces (see the following example)

An example of setting the **notify-operator** attribute for a queue is:

```
pdset -c queue -x "notify-operator=
  message:White@Caddy.xyz.com email:Jones@Chevy.xyz.com"
  Queue2
```

Attributes

```
Examples of setting the results-profile attribute for a job are:

pdset -c job -x "results-profile='dave@cowboy:pickup:2:Please staple'" 2

pdset -c job -x "results-profile='dave@cowboy::2:Please staple'" 2
```

The result of these two commands is the same because the default for the second component is **pickup**.

Using Windows NT or Windows 2000 Shell Commands

When you use Infoprint Manager with Windows NT or Windows 2000 Shell commands, you need to be aware that the Windows NT or Windows 2000 Shell commands interpret certain characters differently. For example, when you need to specify two double quotation marks, you may need to use a back slash to tell the Shell to recognize the double quotation mark as a double quotation mark and not as a command (\"). In a command file, similarly, you may need to specify two percent signs (%%) to tell the Shell to recognize one of the percent signs as a percent sign and not as a command file variable. For more information on the use of Shell commands, consult documentation on Windows Shell Commands.

Attributes for Actual Destinations

- Infoprint uses actual destinations for job validation and scheduling. See
 "Appendix C. Job Validation and Scheduling" on page 719 for an explanation of
 job validation and scheduling and for tables showing the attributes used for
 these tasks.
- Infoprint uses the actual destination *xxx*-**supported** attributes for job validation. Infoprint uses both the *xxx*-**ready** and the *xxx*-**supported** attributes for job scheduling.
- Infoprint issues an error if you update an *xxx*-ready attribute with a value not currently assigned to the corresponding *xxx*-supported attribute.
- Actual destinations have different attribute sets based on the DSS that supports the destination.
- Infoprint supplies some files containing attributes that have the values for some of the actual destination attributes already set, based on the output device model or destination attachment type. You will find these files containing attributes in the /usr/lpp/pd/attr directory for Infoprint Manager for AIX and in the \install_path\attr directory for Infoprint Manager for Windows NT and Windows 2000.

Attributes Not Displayed in the Infoprint Administrator's GUI

While all actual destination attributes and attribute values are supported for both basic and advanced Infoprint installations, neither Infoprint administrator's GUI displays a complete set.

- The basic Infoprint administrator's GUI displays only the attributes of greatest interest to Print on Demand (Commercial Printing) Infoprint administrators.
- The advanced Infoprint administrator's GUI displays most attributes and attribute values of greatest interest to Data Center (Production Printing) Infoprint administrators, but omits a few that are used primarily in basic Infoprint installations.

You can list the values of attributes not displayed in the Infoprint administrator's GUI using the **pdls** command. You can set the values of initially settable and resettable attributes using the **pdcreate** command. You can change the values of resettable attributes using the **pdset** command.

Initially Settable Attribute Listing

You can set these attributes with the pdcreate command when you create an actual destination.

attachment-type destination-data-stream destination-realization destination-support-system device-name print-queue-name

Resettable Attribute Listing

You can set these attributes with the pdcreate command when you create an actual destination or modify them with the pdset command after you create the actual destination.

accept-jobs accounting-exit ack-interval add-carriage-returns add-line-feeds ascii-character-mapping ascii-font-map associated-queue attribute-map audit-exit automatic-postscript-mode-switch auxiliary-sheet-selections-supported booklet-fold carriage-control-types-supported character-mappings-supported checkpoint-at-stacker color-bits-per-plane color-bits-per-plane-supported color-mapping-table color-profile color-profiles-supported color-toner-saver color-toner-saver-supported color-rip-servers connection-timeout content-orientations-supported convert-to-ebcdic-supported data-fidelity-problem-reported-supported default-font-fidelity-action default-font-resolution default-input-tray descriptor destination-command destination-locations destination-model destination-pass-through destination-poll-interval destination-register-threshold destination-release-timer

destination-tcpip-internet-address destination-tcpip-port-number

destination-timeout-period document-finishings-supported document-formats-ripped-at-destination document-formats-supported document-types-supported dss-job-message-disposition dss-job-message-log-size dss-job-message-log-wrap ebcdic-character-mapping end-message-supported end-sheets-supported font-resolutions-supported force-destination-setup form-definition halftones-supported image-fit-supported image-length image-out-formats-supported image-width input-data-user-exit input-trays-medium **input-trays-supported** (BSD only; otherwise non-settable) intervention-timer job-batches-ready job-finishings-supported job-retry-count-limit job-retry-interval job-rip-actions-supported job-size-range-ready job-size-range-supported job-start-wait-supported list-of-managers log-accounting-data logical-destinations-assigned maximum-concurrent-jobs maximum-copies-supported maximum-fonts-to-keep maximum-overlays-to-keep maximum-presentation-object-containers-to-keep maximum-segments-to-keep media-ready (BSD only; otherwise non-settable) media-supported message message-font-type message-form-definition non-process-runout-timer notification-profile notify-operator number-up-supported offset-stacking-available optimize-for-multiple-copies output-appearances-supported output-bin output-bin-numbers output-bins-supported output-data-user-exit

output-format-supported overlay page-select-supported pcl-server-address pcl-server-port plex plexes-supported postscript-server-address postscript-server-port presentation-fidelity-problem-reported presentation-object-container-extraction-mode print-edge-marks print-qualities-supported printer-end-sheet printer-escape-codes printer-memory printer-resolutions-ready printer-resolutions-supported printer-separator-sheet printer-start-sheet printer-s370-channel-device-address printer-s370-channel-slot-number protected-attributes psf-tray-characteristics public-context-presentation-object-container remote-queue resource-context resource-context-font resource-context-form-definition resource-context-overlay resource-context-page-definition resource-context-page-segment resource-context-presentation-object-container reuse-inline-presentation-object-container reverse-output rip-ini-file scanner-corrections-supported scheduler-sort-primary-order scheduler-sort-secondary-order screen-frequencies-supported separator-sheets-supported shared-printer-name sides sides-supported snmp-community-name snmp-retry-count snmp-timeout start-message-supported start-sheets-supported table-reference-characters-supported transform-sequence use-snmp wait-for-job-completion windows-nt-driver-names x-image-shift-range-supported y-image-shift-range-supported

accept-jobs

Indicates whether Infoprint can assign newly submitted or resubmitted jobs to this actual destination.

GUI Label

Accept jobs

DSS

All

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

true

Usage Guidelines

- A value of **false** does not prevent you from using the basic Infoprint administrator's GUI to reassign jobs that have been assigned to another actual destination to this actual destination.
- When this value is **false** and the queue attribute **assign-to-destination** is true, Infoprint rejects jobs sent to this actual destination.
- Infoprint can assign jobs to this actual destination even if it is disabled. Of course, the jobs will not be printed or transmitted until the destination is enabled.
- The accept-unsupported-jobs server attribute overrides the accept-jobs attributes.

accounting-exit

Specifies the name of an auxiliary-sheet object that sets accounting exit parameters.

GUI Label

Accounting exit

DSS

PSF, Infoprint 2000

Type

Resettable, single-valued

Allowed Values

You can enter the name of an auxiliary sheet or any of these fixed values: **accounting-log**

Accounting information is written to the:

- /var/psf/accounting.log file for AIX
- \install_ path\var\psf\accounting.log file Windows NT and Windows 2000, where install_path indicates the path where you installed Infoprint Manager.

blank This value is technically valid, but should not be used.

brief A sheet with brief accounting information is printed after the job.
 full A sheet with full accounting information is printed after the job.
 job-ticket

Accounting information is written to:

- /var/psf/podaccounting.log file for AIX
- \install_path\var\psf\podaccounting.log file Windows NT and Windows 2000, where install_path is the path where you installed Infoprint Manager for Windows NT and Windows 2000.

none No accounting information is produced.

Default Value

• For Infoprint Manager for AIX:

Basic Infoprint administrator's GUI job-ticket

Advanced Infoprint administrator's GUI and command line accounting-log

• For Infoprint Manager for Windows NT and Windows 2000: accounting-log

Usage Guidelines

For fax and email destinations, you can use **accounting-log**; however, while the name of entries is valid, the content of the entries may be inaccurate.

ack-interval

Determines how often Infoprint sends acknowledgement requests to the destination.

GUI Label

Acknowledgement interval (pages)

DSS

PSF, Fax, Email

Type

Resettable, single-valued

Allowed Values

You can enter a value of 1 through 9999. This value represents pages.

Default Value

100

Usage Guidelines

The unit for this attribute is pages. If you change this attribute value, the change can affect performance. You can control how often Infoprint updates the job attribute **pages-completed** by decreasing or increasing this value:

- Decreasing the value (number of pages) increases the number of acknowledgement requests during normal printing activities. This decreases the destination throughput and reduces the complexity of the exception recovery activities that Infoprint performs.
- Increasing the value (number of pages) decreases the number of acknowledgement requests. This provides less accurate information about the destination and exception conditions.

Note: This attribute is only used for IPDS printers.

add-carriage-returns

Indicates whether Infoprint should add carriage return characters when transforming ASCII documents for printing on this actual destination.

GUI Label

Add ASCII carriage returns

DSS

PSF

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true false no

Default Value

No default value

add-line-feeds

Indicates whether Infoprint should add line feed characters when transforming ASCII documents for printing on this actual destination.

GUI Label

Add ASCII line feeds

DSS

PSF

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

No default value

ascii-character-map

Indicates the ASCII code page that AIX uses to map the attributes of this PSF upload-TCP/IP-attached or PSF upload-SNA-attached actual destination.

GUI Label

ASCII code page to use

DSS

PSF (AIX Only)

Type

Resettable, single-valued

Allowed Values

You can enter the name of an ASCII code page, such as ISO8859–1.

Default Value

No default value

Usage Guidelines

Infoprint requires this attribute for PSF upload-SNA-attached and upload-TCP/IP-attached actual destinations and ignores it for other attachment types.

ascii-font-map

Defines how the destination maps the ASCII font escape sequences to AFP character sets that Infoprint uses for ASCII fonts. Infoprint uses this attribute to map each font-change escape to an AFP font character set.

GUI Label

ASCII fonts mappings

DSS

PSF

Type

Resettable, multi-valued, complex

Syntax

font-escape:font-name

Separate each pair of values with a colon, for example:

10cpi:C02055D0

Components

font-escape: Specifies the name of an ASCII font-escape sequence.

Type: Single-valued

Allowed Values: You can enter a text string containing the sequence name.

font-name: Specifies the name of an AFP font character set.

Type: Single-valued

Allowed Values: You can enter a text string containing the font character set name.

Default Values

font-escape Value	font-name Value
10cpi	C02055D0
10cpi-emphasized	C02075D0
10cpi-subscript	C02055P0
10cpi-subscript-emphasized	C02075P0
10cpi-2wide	C02059A0
10cpi-2wide-emphasized	C02079A0
10cpi-2wide-2high	C02059L0
10cpi-2wide-2high-emphasized	C02079L0
10cpi-2wide-subscript	C02055J0

font-escape Value	font-name Value
10cpi-2wide-subscript-emphasized	C02075J0
10cpi-2high	C02051K0
10cpi-2high-emphasized	C02071K0
10cpi-condensed	C02055F0
10cpi-condensed-subscript	C02051R0
10cpi-condensed-2wide	C02059C0
10cpi-condensed-2wide-subscript	C02056N0
12cpi	C02055E0
12cpi-emphasized	C02075E0
12cpi-subscript	C02054Q0
12cpi-subscript-emphasized	C02074Q0
12cpi-2wide	C02059B0
12cpi-2wide-emphasized	C02079B0
12cpi-2wide-subscript	C02058M0
12cpi-2wide-subscript-emphasized	C02078M0
proportional	C02055G0
proportional-emphasized	C02075G0
proportional-subscript	C02055S0
proportional-subscript-emphasized	C02075S0
proportional-2wide	C02059G0
proportional-2wide-emphasized	C02079G0
proportional-2wide-subscript	C02051H0
proportional-2wide-subscript-emphasized	C02071H0
proportional-2high	C02055H0
proportional-2high-emphasized	C02075H0

associated-queue

Identifies the queue from which this actual destination receives jobs.

GUI Label

Queue fed by

DSS

All

Type

Resettable, single-valued

Allowed Values

You can enter a text string up to 255 characters long that contains the ID of the queue. The ID cannot contain the cell name.

Default Value

No default value

Usage Guidelines

The value for this attribute is the name of a queue. The associated queue must exist and be in communication with the destination before you can enable the actual destination.

associated-server

Identifies the name of the server in which this actual destination resides.

GUI Label

Server

DSS

All

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value to the value of the *ServerName* portion of the argument from the **pdcreate** command used to create this actual destination.

Default Value

No default value

attachment-type

Identifies how the output device that this actual destination represents attaches to the PSF DSS and how Infoprint communicates with the output device.

DSS

PSF

Type

Initially settable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value Explanation

command Infoprint communicates with this printer device by forwarding

print requests to the remote print system or printer with a command. You may need to create a queue on the remote print

system.

channel Infoprint communicates with this S/370 channel-attached printer

device through the channel.

other-driver Infoprint communicates directly with the printer device through an

AIX printer backend program or a Windows NT or Windows 2000

printer port.

tcpip Infoprint communicates with this TCP/IP LAN-attached printer

device directly through the TCP/IP network.

upload-sna This printer device is attached to an MVS system. Infoprint

communicates with PSF/MVS through the SNA LU 6.2 network.

Note: This value is only supported by the PSF DSS for AIX.

upload-tcpip This printer device is attached to an MVS system. Infoprint

communicates with PSF/MVS through the TCP/IP network.

Note: This value is only supported by the PSF DSS for AIX.

Default Value

No default value

Usage Guidelines

- You need to specify a value for this attribute when you create a PSF actual destination.
- Some actual destination attributes apply only to certain attachment types.

attribute-map

Provides a list of Infoprint attributes and their associated generated command flags.

GUI Label

Map attributes to flags

DSS

BSD

Type

Resettable, multi-valued, complex

Syntax

attribute:flag

Separate each pair of values with a colon, for example: destination-pass-through:-0

Components

attribute: The name of an Infoprint document or job attribute that corresponds to a flag of the generated print command.

GUI Label: Infoprint attribute

Type: Single-valued

Allowed Values: You can enter a text string containing an attribute name.

flag: The name of a flag of the generated print command.

GUI Label: Output command option

Type: Single-valued

Allowed Values: You can enter a text string containing a flag.

Default Values

destination-pass-through:-o

Usage Guidelines

- With AIX by default, BSD assumes the generated command is a rembak command.
- With Windows NT or Windows 2000 by default, BSD assumes the generated command is an **lpr** command.
- Some printer devices, for example, the IBM 4317 Network Printer 17, IBM Infoprint 20 Printer, and IBM Infoprint 32 Printer, do not support the BSD -Z flag. If you receive the following error message when you try to print on one of these printers:

```
0782-597 The value of \_Z attribute is not in the ring list specified in the limits field
```

delete the job-name:-o-Z value from the attribute-map attribute.

audit-exit

Specifies the name of the auxiliary-sheet object that sets audit exit parameters.

GUI Label

Audit exit

DSS

PSF, Email, Fax, Infoprint 2000

Type

Resettable, single-valued

Allowed Values

You can enter the name of an auxiliary sheet or any of these fixed values: accounting-log

Audit information is written to the:

- /var/psf/audit.log file for AIX
- \install_path\var\psf\audit.log file for Windows NT and Windows 2000, where *install_path* indicates the path where you installed Infoprint Manager.

blank This value is technically valid, but should not be used.

A sheet with brief audit information is printed after the job. brief

full A sheet with full audit information is printed after the job.

job-ticket

A sheet with full audit information from the job ticket is printed after the

No audit information is produced. none

Default Value

No default value

Usage Guidelines

If you do not set a value, Infoprint produces no audit information at the end of a job submitted to this actual destination.

automatic-postscript-mode-switch

Indicates whether this actual destination supports switching into PostScript mode using controls placed in the data stream.

GUI Label

Switch to PostScript automatically

DSS

AIX

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

false

Usage Guidelines

- If this actual destination has this feature, it can print PostScript documents among non-PostScript documents.
- The value for this attribute does not change if you delete the document-formats-supported value of postscript.

auxiliary-sheet-selections-supported

Identifies the combination of start, separator, and end sheets selection that this actual destination supports for jobs.

GUI Label

Auxiliary sheets allowed

DSS

AIX, PSF, Infoprint 2000, IPP, Passthrough

Type

Resettable, multi-valued

Allowed Values

For AIX, PSF, and Infoprint 2000, you can enter any of these fixed values:

end

none

sep

sep-end

start

start-end

start-sep

start-sep-end

For IPP and Passthrough, you can enter any of these fixed values:

none

start

Default Values

AIX, PSF, and Infoprint 2000 defaults: end, none, sep, sep-end, start, start-end, start-sep, start-sep-end.

Internet Printing Protocol (IPP) and Passthrough defaults: none, start.

Usage Guidelines

- Infoprint compares the job attribute **auxiliary-sheet-selection** to this attribute for validation and scheduling.
- You can use this attribute to restrict how much control users have over auxiliary-sheet-selection on this actual destination.
- If you remove all values that specify a particular auxiliary sheet (such as **start**), the job submitter cannot "turn off" the corresponding actual destination attribute (such as **printer-start-sheet**).

booklet-fold

Specifies how booklets are ordered and folded on this output device.

GUI Label

Fold booklet

DSS

PSF, Infoprint 2000

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

up down

Default Value

up

Usage Guidelines

- The Infoprint 60 Finisher folds booklets **up**; that is, the cover (if any) is inserted at the beginning of the booklet, and after the booklet prints, the cover is saddle-stitched from the bottom and folded upward.
- The Infoprint 2000 (without the IPDS feature) and inline booklet makers attached to the Infoprint 4000s fold booklets **down**; that is, the cover (if any) is inserted at the end of the booklet, and after the booklet prints, it is saddle-stitched from the top and folded downward.

Note: The Infoprint 2000 DSS sets the booklet-fold to **down**, so that Infoprint 2000 (without the IPDS feature) customers don't have to specify the **booklet-fold** attribute. However, customers using the Infoprint 4000s need to specify the **down** value for the **booklet-fold** attribute.

cancel-individual-document-supported

Indicates whether this actual destination is capable of cancelling a single document within a multi-document job.

DSS

All

туре

Non-settable, single-valued

Allowed Values

Infoprint sets this value to false.

Default Value

false

carriage-control-types-supported

Identifies the types of carriage controls that this actual destination supports.

GUI Label

Carriage control types allowed

DSS

PSF, Email, Fax, Infoprint 2000

Type

Resettable, multi-valued

Allowed Values

```
You can enter any of these fixed values:
    ansi-ascii
    ansi-ebcdic
    machine
    none
```

Default Values

ansi-ascii, ansi-ebcdic, machine, none

Usage Guidelines

- Infoprint compares the document attribute **carriage-control-type** to this attribute for validation and scheduling.
- You can use this attribute to restrict use of this actual destination.

character-mappings-supported

Identifies the character mappings (code pages) that this actual destination supports.

GUI Label

Character mappings allowed

DSS

AIX, PSF, Email, Fax, Infoprint 2000

Type

Resettable, multi-valued

Allowed Values

You can enter any of these fixed values:

ibm-437

ibm-850

ibm-860

ibm-863

ibm-865

ibm-932

ibm-938 with Infoprint Manager for AIX only

ibm-euccn

ibm-eucjp

ibm-euckr

ibm-euctw

Default Values

AIX The value of the **destination-model** attribute for the actual destination determines the default value.

PSF, Email, Fax, Infoprint 2000

ibm-437, ibm-850, ibm-860, ibm-863, ibm-865, ibm-eucjp, ibm-euckr, ibm-euctw

Usage Guidelines

Infoprint compares the document attribute **default-character-mapping** to this attribute for scheduling.

checkpoint-at-stacker

Indicates where to pause jobs printing on this actual destination.

GUI Label

Checkpoint at stacker

DSS

PSF

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

false

Usage Guidelines

When this attribute is set to **false** (the default), the checkpoint for paused jobs occurs at the operator viewing point on the printer device (the printhead). This means that when a paused job resumes, printing begins where it stopped, without reprinting any pages.

Set this attribute to **yes** if you want the checkpoint to occur at the stacker. This means that when a paused job resumes, all pages not stacked will be reprinted. This guarantees that, even if there is a paper jam between the printhead and the stacker, you will have at least one copy of each printed page.

checkpoint-formats-supported

Infoprint sets this attribute to identify the checkpoints supported for paused jobs for this actual destination.

GUI Label

Checkpoint formats allowed

DSS

AIX, PSF, Email, Fax, 3170, Infoprint 2000

Type

Non-settable, multi-valued

Allowed Values

Infoprint sets this value to any of these fixed values:

dsf-document-number dsf-job-copy dsf-results-profile no-context-info psf-interrupt

Default Values

AIX dsf-document-number, dsf-job-copy, dsf-results-profile dsf-results-profile, psf-interrupt

Email, Fax, Infoprint 2000 dsf-results-profile

Usage Guidelines

Infoprint uses this information to reschedule paused jobs.

Actual Destination color-bits-per-plane Specifies whether the transform is to produce monochrome (fs10) or color images (fs42 or fs45). **GUI Label** Color bits per plane **DSS PSF** Type Resettable, single-valued **Allowed Values** You can enter one of these fixed values: • **0-bits** (monochrome FS10) • **1-bit** (color FS42) • **8-bits** (color FS45) **Default Value** For Infoprint Color 130 Plus, the default is 8-bits. For all other actual destinations, the default is **0-bits**. **Usage Guidelines** • This attribute only applies to attachment types of TCP/IP, Upload TCP/IP, Upload SNA, and Channel. color-bits-per-plane-supported Specifies the types of images supported on the actual destination when printing a document. **GUI Label** Color bits per plane allowed **DSS PSF Type** Resettable, multi-valued **Allowed Values** You can enter one of these fixed values: • **0-bits** (monochrome FS10) • **1-bit** (color FS42) • **8-bits** (color FS45) **Default Value**

For Infoprint Color 130 Plus, the following defaults apply:

- **0-bits** (monochrome FS10)
- 1-bit (color FS42)
- **8-bits** (color FS45)

For all other actual destinations, the default is **0-bits** (monochrome FS10).

Usage Guidelines

- This attribute only applies to attachment types of TCP/IP, Upload TCP/IP, Upload SNA, and Channel.
- Black and white printers or black and white printers with spot-color attachments support **0-bits**.
- Infoprint Color 100 AFP printers support 0-bits and 1-bit
- Infoprint Color 130 Plus printers support 0-bits, 1-bit, and 8-bits.

color-mapping-table

Identifies the default color mapping table (CMT) that the output device uses when printing a document.

GUI Label

Color mapping table

DSS

PSF

Type

Resettable, single-valued

Allowed Values

You can enter a text string of up to 8 characters that contains the identification of the color mapping table.

Default Value

No default value

Usage Guidelines

- Be aware that setting **color-toner-saver** to **True** or **Yes** results in less vibrant process colors.
- Refer to "Appendix A" in *IBM Data Stream and Object Architectures: Mixed Object Document Content Architecture Reference* for more detailed information on the use of color mapping tables.

color-profile

Specifies the color profile, if any, to be used by the PostScript transform.

GUI Label

Color profile

DSS

PSF

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

- SWOP
- Euroscale
- none

Default Value

none

Usage Guidelines

• This attribute only applies to attachment types of TCP/IP, Upload TCP/IP, Upload SNA, and Channel.

color-profiles-supported

Identifies which color profiles can be used by the actual destination when printing a document.

GUI Label

Color profiles allowed

DSS

PSF

Type

Resettable, multi-valued

Allowed Values

You can enter one of these fixed values:

- SWOP
- Euroscale
- none

Default Value

For Infoprint Color 130 Plus, the following defaults apply:

- SWOP
- Euroscale
- none

For all other actual destinations, the default is **none**.

Usage Guidelines

- This attribute only applies to attachment types of TCP/IP, Upload TCP/IP, Upload SNA, and Channel.
- You can use this attribute to restrict the use of **color-profile**.

color-rip-servers

Identifies the Internet Protocol address (IP Address parameter) and port number of hosts capable of RIPping documents for this actual destination.

GUI Label

Color RIP servers

DSS

3170

Type

Resettable, multi-valued

Allowed Values

You can enter a text string up to 4095 characters long that contains either of these types of address:

Dotted decimal address

A series of integers within the range of 0 to 255, each separated by a period, . (decimal address). For example:

9.99.12.85:11126

Hostname

For example:

leo.boulder.IBM.com:11126

Default Value

The value of the **destination-tcpip-internet-address** attribute with a port number of 11126

color-toner-saver

When cyan, magenta, and yellow (cmyk) are combined in a certain proportion, the result approximates black. When the **color-toner-saver** attribute is used, the proportion of cyan, magenta, and yellow are reduced and substituted with black toner, which reduces the amount of color toner used. This option only applies to non-cmyk PostScript (for example, RGB) for which a color rendering dictionary (CRD) is used to determine the cmyk values to use.

GUI Label

Color toner saver

DSS

PSF

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

With the **color-toner-saver** attribute, a value of **true** or **yes** substitutes black for common cyan, magenta, and yellow components to reduce consumption of toner and to reduce the cost per page; while a value of **false** or **no** uses the cmyk proportions specified.

Default Value

false

Usage Guidelines

- This attribute only applies to attachment types of TCP/IP, Upload TCP/IP, Upload SNA, and Channel.
- Setting color-toner-saver to True or Yes results in less vibrant process colors.
- For information on the use of **color-mapping-table** with relation to **color-toner-saver**, see "color-mapping-table" on page 353.

color-toner-saver-supported

Identifies the values that can be specified for **color-toner-saver**. When cyan, magenta, and yellow (cmyk) are combined in a certain proportion, the result approximates black. When the **color-toner-saver** attribute is used, the proportion of cyan, magenta, and yellow are reduced and substituted with black toner, which reduces the amount of color toner used. This option only applies to non-cmyk PostScript (for example, RGB) for which a color rendering dictionary (CRD) is used to determine the cmyk values to use.

GUI Label

Color toner saver allowed

DSS

PSF

Type

Resettable, multi-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

- true or yes
- · false or no

Usage Guidelines

- This attribute only applies to attachment types of TCP/IP, Upload TCP/IP, Upload SNA, and Channel.
- You can use this attribute to restrict the use of **color-toner-saver**.

command

See destination-command.

connection-timeout

Sets the connection timeout parameter for TCP/IP-attached actual destinations. This time period is the amount of time that Infoprint waits before it stops trying to communicate with the output device when it cannot make a connection.

GUI Label

Connection time out (sec)

DSS

PSF, Email, Fax

Type

Resettable, single-valued

Allowed Values

You can enter a value of 0 through 9999. The unit is seconds.

Default Value

30

Usage Guidelines

- A value of **0** prevents any time out.
- Infoprint uses this attribute with TCP/IP-attached actual destinations and ignores it for other attachment types.

content-orientations-supported

Identifies the page presentations that this actual destination supports.

GUI Label

Orientations allowed

DSS

AIX, 3170

Type

Resettable, multi-valued

Input Synonym

You can use the synonym **orientations-supported**.

Allowed Values

You can enter any of these fixed values:

landscape portrait reverse-landscape reverse-portrait

Default Values

portrait

Usage Guidelines

- Infoprint compares the document attribute content-orientation to this attribute for validation and scheduling.
- You can use this attribute to restrict use of this actual destination.

convert-to-ebcdic-supported

Indicates whether this actual destination supports converting document data from ASCII to EBCDIC.

GUI Label

Convert to EBCDIC allowed

PSF, Email, Fax, Infoprint 2000

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value **Input Synonym**

true yes false no

Default Value

true

Usage Guidelines

- Infoprint compares the value of the document attribute **convert-to-ebcdic** to this attribute for job validation and scheduling.
- Infoprint uses the document attribute convert-to-ebcdic when printing line-data documents.
- You can use this attribute to restrict use of this actual destination.

data-fidelity-problem-reported-supported

Identifies which types of data fidelity errors this actual destination reports.

GUI Label

Data fidelity problems allowed

DSS

PSF, Infoprint 2000

Type

Resettable, multi-valued

Allowed Values

```
You can enter any of these fixed values:
all
character
none
position
```

Default Values

all, character, none, position

Usage Guidelines

- Infoprint compares the document attribute **data-fidelity-problem-reported** to this attribute for scheduling.
- Use this attribute to specify whether Infoprint issues error messages for print-positioning and invalid-character errors that occur for channel-attached, TCP/IP-attached, upload-SNA-attached, and upload-TCP/IP-attached printer devices.

Print positioning errors occur when the print position for the data is beyond the valid printable areas as defined by the intersection of the physical and logical pages. (A logical page identifies the printing boundaries of a physical page.) Invalid-character errors occur when the code point does not map to a character in a font.

default-font-fidelity-action

Indicates what Infoprint should do if a font required to print a document is not available in the resolution specified by the data stream, the document **font-resolution** attribute, or the actual destination **default-font-resolution** attribute.

GUI Label

Default font fidelity action

DSS

PSF, Email, Fax

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value Explanation

stop Stop printing the job.

continue Attempt to substitute a similar font at a different

resolution.

Default Value

continue

Usage Guidelines

The value of the document attribute **font-fidelity-action** and the value specified in the data stream override the value of this attribute.

default-font-resolution

Specifies the font resolution used for documents printed on this actual destination when no value is specified in the data stream or by the document **font-resolution** attribute.

GUI Label

Default font resolution

DSS

PSF

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

240

300

outline

Default Value

outline

Usage Guidelines

- The value of this attribute must be one of the values of the **font-resolutions-supported** attribute.
- Usually the font resolution and the printer resolution match, but there are two cases when they do not:
 - Some printer devices, for example, the Infoprint 60 and Infoprint 4000s, can print fonts of any resolution, although the print head is always 600 pels.
 - It is possible to print a document created with fonts of one resolution on a
 printer device with a different resolution by substituting fonts. Depending on
 the document, the output may or may not be acceptable.

default-input-tray

Specifies the name of the default input tray for a PSF actual destination.

GUI Label

Default input tray

DSS

PSF

Type

Resettable, single-valued

Allowed Values

You can enter any value as long as the value maps to one of the actual destination **input-trays-supported** or **psf-tray-characteristics** attribute values.

Default Value

No default value

Usage Guidelines

- The value you specify must be one of the values specified for the **input-trays-supported** or **psf-tray-characteristics** actual destination attribute.
- Infoprint only uses the value you supply for this attribute if:
 - The user does not specify a medium or input tray.
 - The form definition Infoprint uses for the job does not specify an input tray.

descriptor

Provides a textual description of this actual destination.

GUI Label

Description

DSS

All

Type

Resettable, single-valued

Allowed Values

You can enter a text string up to 4095 characters long that describes this actual destination. You may want to include such things as the type and location of the output device that this actual destination represents and any usage information, such as restrictions for this actual destination.

Default Value

No default value

Usage Guidelines

The use of this attribute is optional. However, a detailed description is useful to users who want to specify a given destination or to determine which destination can handle their jobs. A description is also helpful when you create a new logical destination and want to determine which actual destinations you should associate with the new logical destination.

destination-command

Specifies the command-line entry to print the job data.

GUI Label

Printer command

DSS

AIX, BSD, PSF

Type

Resettable, single-valued

Input Synonyms

You can use the synonym **printer-command** or **command**.

Allowed Values

You can enter a text string up to 4095 characters long that contains the command.

Default Value

AIX /usr/lib/lpd/piobe

BSD for Infoprint Manager for AIX /usr/lpd/rembak

BSD for Infoprint Manager for Windows NT and Windows 2000 No Default

PSF other-driver attached actual destinations for Infoprint Manager for AIX only /usr/lib/lpd/piobe

PSF command-attached actual destinations for Infoprint Manager for AIX qprt -Pxxx -dp -Z!

where xxx is the value of the **print-queue-name** attribute. If there is no value for the **print-queue-name** attribute, xxx is

asc If the destination-data-stream=ppds

pcl If the destination-data-stream=pcl4, pcl5, or pcl5c

PSF command-attached actual destinations for Infoprint Manager for Windows NT and Windows 2000

No Default

Usage Guidelines

- For AIX actual destinations:
 - Infoprint uses the value as the command that the AIX actual destination executes for each document printed. It should include the full path name for the print driver you are using for your printer device.

With the addition of the **wait-for-job-completion** actual destination attribute, there is a new backend program called pioinfo that can be used in place of the piojetd backend program. For example, **destination-command=/usr/lpd/pio/etc/pioinfo** *ip_address*, where *ip_address* is the ip address of the printer.

See "wait-for-job-completion" on page 454 for more information.

If the printer backend program is a variation of, or front end to, rembak, specify true on the remote-queue actual destination attribute. Examples of rembak-based backend programs include piorflb and piocolor.

For more information on **rembak**, see "remote-queue" on page 435.

- For PSF actual destinations:
 - Infoprint uses the value as the command string to print a job on the command-attached printer and to send the job to the correct remote queue.
 - With the PSF DSS for AIX:
 - Infoprint uses the command string to invoke the printer backend program for other-driver attached actual destinations.
 - If you do not specify this attribute for command-attached actual destinations, Infoprint fills in the value of *XXX* (shown under Default Value) with the value of the **print-queue-name** attribute.
 - With a PSF-other-driver attached printer, **destination-command** is supported for an AIX server; however, it is not supported for an NT server.

destination-data-stream

Identifies the data stream format that is output to the printer device.

GUI Label

Data Stream

DSS

PSF

Type

Initially settable, single-valued

Allowed Values

You can enter one of these fixed values:

pcl4 pcl5 pcl5c

ppds

ipds

Note: ipds is not an allowed value for command-attached and other-driver attached printers.

afpds

Note: afpds is only allowed with an attachment type of Upload-SNA or Upload-TCPIP.

For more information on attachment types, see "Understanding Attachment Types for PSF Actual Destinations" on page 331.

Input Synonym

You can use the synonym printer-data-stream.

Default Value

Other-driver attached actual destinations

pcl4

Command-attached actual destinations

pcl4

Other attachment types

ipds

destination-locations

Identifies the location of the output device.

GUI Label

Locations

DSS

All

Type

Resettable, multi-valued

Input Synonyms

You can use the synonym printer-locations or locations.

Allowed Values

You can enter a text string up to 4095 characters long, for each value, that describes the physical location of the output device. Each value is a different description for the same location.

Default Values

No default values

Usage Guidelines

Infoprint compares the job attribute **destination-locations-requested** to this attribute for scheduling. The user can specify the **destination-locations-requested** job attribute to request that Infoprint use the output device at this specific location to process the job.

destination-model

Identifies the make and model number defined by the manufacturer of the output device.

GUI Label

Model

DSS

AIX, PSF, BSD, 3170, Infoprint 2000, Email, Fax, Passthrough, IPP

Type

Non-settable with AIX and PSF other-driver attached actual destinations; resettable, single-valued with other listed DSSs

Input Synonyms

You can use the synonym **printer-model** or **model**.

Allowed Values

You can enter a text string up to 4095 characters long that contains the make and model number of the output device.

Default Value

If SNMP communication is active, Infoprint queries the printer device and sets the values according to the response; otherwise no default value.

With Internet Printing Protocol (IPP) printers when SNMP communication is not active, the default comes from IPP.

Usage Guidelines

- You must set this value when you create an AIX or PSF actual destination, unless Infoprint can determine the value by means of SNMP.
- If you specify a value for the **destination-model** attribute, you deactivate the default provided by SNMP.
- If you allow SNMP to determine this value for an AIX actual destination or a PSF other-driver attached actual destination, it must be one of the values of the server **snmp-aix-printer-models** attribute.
- For AIX actual destinations and PSF other-driver attached actual destinations on an AIX server, this value must match the file prefix of a file in the /usr/lib/lpd/pio/predef directory on the AIX processor on which the actual destination was created unless the destination-model is an Infoprint model and then the external name (for example, an Infoprint 20) is mapped to the predefined name for you.
- For AIX actual destinations, Infoprint uses the value you specify here to determine the values to set for the **document-formats-supported** attribute.
- For PSF TCP/IP-attached actual destinations capable of printing halftones, and for any PSF actual destination that represents a printer device with a finisher

attached, specify the model name in the format **Infoprint**xxxx. where xxxx is the model number, for example, Infoprint4000-IR3-IR4. Do not put a space between **Infoprint** and the model number.

Note: If you configure these printer models as PSF other-driver attached actual destinations or as AIX actual destinations on an AIX server, specify the model name as the file prefix of a file in the /usr/lib/lpd/pio/predef directory unless the destination-model is an Infoprint model and then the external name (for example, an Infoprint 60) is mapped to the predefined name for you.

- Infoprint compares the job attribute destination-models-requested to this attribute for scheduling.
- For IPP printers, Infoprint uses the destination-model information for validation and scheduling.

destination-name

Identifies the name of this actual destination.

DSS

All

Type

Non-settable, single-valued

Input Synonyms

You can use the synonym printer-name, printer, or physical-printer.

Allowed Values

Infoprint set this value to the DestinationName portion of the argument used with the pdcreate command or with the pdmigpp utility when this actual destination was created.

Default Value

No default value

Usage Guidelines

- Infoprint compares the job attribute actual-destination-requested to this attribute for validation and scheduling.
- The name must be unique within the namespace.

destination-needs-attention-time

Reports the amount of time the output device has been waiting for simple intervention, such as loading paper.

GUI Label

Attention needed

DSS

All

Type

Non-settable, single-valued

Input Synonym

You can use the synonym **printer-needs-attention-time**.

Allowed Values

Infoprint sets this value to [HH:]MM. The unit is minutes or hours and minutes, separated by a colon.

Default Value

No default value

destination-needs-key-operator-attention-time

Reports the amount of time the output device has been waiting for the attention of a key (or skilled) operator.

GUI Label

Operator needed

DSS

All

Type

Non-settable, single-valued

Input Synonym

You can use the synonym **printer-needs-key-operator-attention-time**.

Allowed Values

Infoprint sets this value to [HH:]MM. The unit is minutes or hours and minutes, separated by a colon.

Default Value

No default value

destination-pass-through

Allows you to pass information to the DSS (destination driver). Infoprint does not process the information, but passes it directly to the DSS. With the AIX DSS, the information is used to update the actual destinations's colon file.

For information on the use of **destination-pass-through** with **other-transform-options**, see 669.

GUI Label

Other options

DSS

AIX, BSD, PSF, 3170, Infoprint 2000

Type

Resettable, single-valued

Input Synonyms

You can use the synonym printer-pass-through or other-options.

Allowed Values

You can enter a text string up to 4095 characters long containing update information.

Syntax 1

With AIX DSS:

'colon-file-attribute=value ...'

For example, to set the datastream filter attribute (\underline{d}) in the printer colon file to "passthrough" (p), enter:

destination-pass-through=' d=p'

Default Value

No default value

Note: If you use the destination-pass-through attribute when submitting a job to a PSF direct-attached actual destination, you can either direct the options to the PSF DSS or to the backend specified in the value of the destination-command attribute. When you specify -BE in the value for the destination-pass-through attribute, Infoprint passes all values preceding -BE to the PSF DSS. Infoprint passes any values following -BE to the backend program.

destination-poll-interval

Specifies the amount of time in seconds between job status polls of a Internet Printing Protocol (IPP) printer or a Passthrough printer.

GUI Label

Poll interval (sec)

DSS

IPP, Passthrough

Type

Resettable, single-valued

Allowed Values

You can enter a value from 0 through 2147483647.

Default Value

2

destination-realization

Indicates whether the destination is an actual destination or a logical destination.

DSS

All

Type

Initially settable, single-valued

Input Synonym

You can use the synonym printer-realization.

Allowed Values

You can enter one of these fixed values: actual

logical

Default Value

logical

destination-register-threshold

Specifies the amount of time that this actual destination will wait between attempts to communicate (register) with the server.

GUI Label

Attempt to register with server

DSS

All

Type

Resettable, single-valued

Input Synonyms

You can use the synonym printer-register-threshold or register-threshold.

Allowed Values

You can enter a value of [HH:]MM. The unit is minutes or hours and minutes, separated by a colon.

Default Value

10

Usage Guidelines

The **destination-register-threshold** value applies when the actual destination and the queue are in separate Infoprint servers. If the Infoprint server containing the queue is not running, the printer in the running server keeps trying to establish contact with the server that contains the queue. This attempt is made every n minutes with the following effect:

- If you lower the **destination-register-threshold** value, network traffic increases when the server is down, but the actual destination registers more quickly when you bring up the server.
- If you raise the destination-register-threshold value, network traffic decreases
 when the server is down, but the actual destination registers more slowly when
 you bring up the server.

destination-release-timer

Specifies the maximum amount of time between jobs, in seconds, before Infoprint gives up control of a PSF actual destination.

GUI Label

Release time (sec)

DSS

PSF

Type

Resettable, single-valued

Input Synonym

You can use the synonym printer-release-timer.

Allowed Values

You can enter an integer from 0 through 9999. The unit value is seconds.

Default Value

9999

Usage Guidelines

• The **destination-release-timer** allows Infoprint to share an output device with a print manager, such as PSF Direct. Specify a value of 9999 if the output device is not shared.

- The **destination-release-timer** allows time for all processes to stop running gracefully as Infoprint gives up control of the attached PSF actual destination.
- If the non-process-runout-timer attribute has a greater value than the
 destination-release-timer attribute, Infoprint issues an automatic NPRO.
 However, IBM recommends that you set non-process-runout-timer to a lower
 value than destination-release-timer.

destination-state

Identifies the current state of the actual destination.

GUI Label

State

DSS

All

Type

Non-settable, single-valued

Input Synonym

You can use the synonym printer-state.

Allowed Values

Infoprint sets and updates the value to one of these fixed values:

Fixed Value Explanation

connecting-to-printer The actual destination has received a job and is

trying to connect to its printer device. After it connects to the device, the actual destination locks the printer device until it finishes processing the job so that another print system cannot use the

device.

Note: This state applies only to AIX actual

destinations and PSF other-driver attached actual destinations on Infoprint Manager for

AIX.

idle The actual destination is waiting for a job. An

actual destination can be idle even if its output device is printing a job from some other AIX process or from the AIX print-spooling subsystem; or from some other Windows application or the

Windows spooler.

needs-attention The actual destination can connect to the output

device, but for some reason the output device

cannot print.

needs-key-operator This state occurs when there is a serious problem

with the output device. Either the actual

destination cannot connect to the output device or there is some other problem. For example, a printer device may be out of toner. Infoprint automatically disables the actual destination when the actual destination enters this state. If the actual

destination uses SNMP, Infoprint automatically

re-enables it when the problem is corrected. To prevent automatic re-enabling, manually disable

the actual destination.

paused The actual destination was paused with the

pdpause command or by a job with

job-start-wait=true.

printing The actual destination is processing a job.

shutdown The actual destination was shut down with the

pdshutdown command.

Note: This state applies only to PSF actual

destinations.

timed-out The actual destination received a job, but the actual

destination could not connect to the printer device in the time specified by the **printer-timeout-period**

actual destination attribute.

Note: This state applies only to AIX actual

destinations and PSF other-driver attached

actual destinations.

Default Value

No default value

destination-support-system

Identifies the type of destination support system for this actual destination.

DSS

All

Type

Initially settable, single-valued

Input Synonym

You can use the synonym **device-support-system**.

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

aix piobe

psf 3170 email fax IP2000 IPP

windows passthrough

Default Value

psf

Usage Guidelines

- Infoprint compares the job attribute **dss-requested** to this attribute for scheduling.
- You must enter a value for this attribute when you create an actual destination unless it will use the PSF DSS.

destination-tcpip-internet-address

Identifies the Internet Protocol address (IP Address parameter) of this actual destination. This is the Internet Protocol address assigned to the output device.

GUI Label

TCP/IP address

DSS

AIX, BSD, PSF, 3170, Infoprint 2000, IPP, Passthrough

Type

Resettable, single-valued

Input Synonym

You can use the synonym printer-tcpip-internet-address.

Allowed Values

You can enter a text string up to 4095 characters long that is either of these types of address:

Dotted decimal address

A series of integers within the range of 0 to 255, each separated by a period, . (decimal address). For example:

9.99.12.85

Hostname

For example:

leo.boulder.ibm.com

Note: When you create an SNMP printer, you must specify either the fully-qualified printer name or the internet address. If you create an SNMP printer with an abbreviated printer name, Infoprint issues the SNMP connection lost message when you attempt to enable the printer.

Default Value

No default value

- You must enter a value for destinations to use SNMP. When you use NPM, the value for destinations to use SNMP must be a decimal address.
- You must enter a value for PSF TCP/IP-attached actual destinations, for PSF upload-TCP/IP-attached actual destinations, for 3170 actual destinations, and for Infoprint 2000 actual destinations.
- Infoprint ignores this attribute for PSF channel-attached and upload-SNA-attached actual destinations.
- For printers attached using the i-data 7913 IPDS Printer LAN Attachment, use the IP address of the 7913.

destination-tcpip-port-number

Identifies the Port Number parameter for PSF TCP/IP-attached and upload-TCP/IP-attached actual destinations. This is the TCP/IP port number configured at the output device.

GUI Label

TCP/IP port number

DSS

PSF

Type

Resettable, single-valued

Input Synonym

You can use the synonym **printer-tcpip-port-number**.

Allowed Values

You can enter an integer from 1 through 2147483647, but you typically enter an integer from 5001 to 65535. For devices whose port is configurable, the port you specify must match the port configured at the output device. For printers attached using the i-data 7913 IPDS Printer LAN attachment, you must use the value of 5001.

Default Value

No default value

Usage Guidelines

You must enter a value for PSF TCP/IP-attached and upload-TCP/IP-attached actual destinations. Infoprint ignores this attribute for other attachment types.

destination-timeout-period

Specifies the amount of time, in seconds, that Infoprint allows for the server to try to connect to a shared network printer (printer device) after the actual destination receives a new job request.

DSS

AIX, PSF

Resettable, single-valued

Input Synonym

You can use the synonym timeout-period or printer-timeout-period.

Allowed Values

You can enter an integer from 0 through 2147483647. The unit is seconds.

Default Value

60

- For PSF actual destinations, this attribute applies only to actual destinations with an attachment type of **other**.
- While the server is attempting to connect to the printer device, this actual destination is in the **timed-out** state, but it can still accept jobs.

- If the server cannot connect to the printer device within the specified time, the following happens:
 - The printer state becomes **timed-out**.
 - This actual destination will not accept new jobs.
 - Infoprint may issue a warning message, depending on the notification profile of this actual destination.
 - The server continues to try to connect to the printer device until successful, or until this actual destination is disabled.
 - Infoprint sends a warning message at the end of each timeout period (if specified by the notification profile).

device-name

Identifies the output device that this actual destination represents.

GUI Label

Windows port name (Passthrough) Device (all other DSSs) URL (IPP)

DSS

AIX, PSF, Email, Fax, Infoprint 2000, IPP, Passthrough

Type

Initially settable, single-valued

Allowed Values

You can enter a text string up to 255 characters long that contains the name (ID) of the output device that prints jobs assigned to this actual destination. The value usually identifies the path to the device name, commonly located in a /dev directory.

For Internet Printing Protocol (IPP) printers, enter the URL for the IPP printer.

For Passthrough printers, enter the Windows NT or Windows 2000 Port Name.

Default Value

No default value

- · You must enter a value for this attribute when you create a PSF command-attached actual destination on an AIX server; however, it is not supported for an NT server.
- You must enter a value for this attribute when you create a PSF other-driver-attached actual destination on Windows NT or Windows 2000; however, it is not supported on an AIX Server.
- On Windows NT and Windows 2000, the device name must be the name of a Windows NT or Windows 2000 port that has already been created.
- You must configure the device name you specify in AIX. You can determine which device names exist by using the SMIT fastpath smit pdp and then listing all defined printers and plotters. If you need to create the output device within AIX, use the SMIT fastpath **smit makprt**.
- If an AIX print queue has been configured for this actual destination, the device name appears in the /etc/qconfig file.

- Do not specify a value for PSF TCP/IP-attached, upload-TCP/IP-attached, upload-SNA-attached, or channel-attached destinations.
- · When you are working with AIX DSS actual destinations, see "Creating and Managing Actual Destinations" in the Infoprint Manager for AIX: Administrator's Guide for information on correcting the configuration of remote-queue printers that have **device-name** set to /dev/null.

device-support-system

See destination-support-system.

document-attributes-supported

Identifies the document attributes that this actual destination supports. Infoprint checks this attribute during validation to allow jobs whose documents have these attributes to continue on to this actual destination.

DSS

A11

Type

Non-settable, multi-valued

Allowed Values

Infoprint sets a text string that contains a list of document attributes that this actual destination supports.

Note: This list includes only document attributes that directly affect the actual destination. Documents with attributes that affect the server, for example, initial-value-document, can be printed even though those attributes are not on this list.

Default Value

AIX content-orientation, copy-count, default-input-tray, default-medium, destination-pass-through, document-comment, document-content, document-content-list, document-format, document-type, maximum-messages-printed, plex, print-quality, sides

BSD copy-count, destination-pass-through, document-comment, document-content, document-content-list, document-format, document-type, maximum-messages-printed, plex, print-quality, sides

PSF DSS for AIX

account-text, address1-text, address2-text, address3-text, address4-text, base-printer, building-text, carriage-control-type, chars, color-bits-per-plane, color-profile, color-toner-saver, convert-to-ebcdic, copy-count, data-fidelity-problem-reported, default-character-mapping, default-input-tray, default-medium, default-printer-resolution, department-text, destination-pass-through, document-comment, document-content, document-content-list, document-finishing, document-format, document-type, font-fidelity-action, font-resolution, form-definition, image-fit, image-length, image-out-format, image-width, input-exit, input-tray-select, maximum-messages-printed, maximum-transform-pages-ahead, mvs-class, mvs-destination, mvs-forms, mvs-segment-id, name-text, new-line-option, node-id-text, number-up, other-transform-options, output-appearance, output-bin, output-format, overlay, page-definition, page-media-select, page-select, plex, programmer-text, resource-context, resource-context-font,

resource-context-form-definition, resource-context-overlay, resource-context-page-definition, resource-context-page-segment, resource-context-presentation-object-container, resource-context-user, resource-exit, room-text, scanner-correction, screen-frequency, segment-file-size, shared-formdef, shift-out-shift-in, sides, start-on-new-sheet, table-reference-characters, title-text, transform-message-file-name, transform-output-file-name, user-id-text, x-image-shift, x-image-shift-back, y-image-shift, y-image-shift-back

PSF DSS for Windows NT and Windows 2000

account-text, address1-text, address2-text, address3-text, address4-text, base-printer, building-text, carriage-control-type, chars, color-bits-per-plane, color-profile, color-toner-saver, convert-to-ebcdic, copy-count, data-fidelity-problem-reported, default-character-mapping, default-input-tray, default-medium, default-printer-resolution, department-text, destination-pass-through, document-comment, document-content, document-content-list, document-finishing, document-format, document-type, font-fidelity-action, font-resolution, form-definition, image-fit, image-length, image-out-format, image-width, input-exit, input-tray-select, maximum-messages-printed, maximum-transform-pages-ahead, mvs-class, mvs-destination, mvs-forms, mys-segment-id, name-text, new-line-option, node-id-text, number-up, other-transform-options, output-bin, output-format, overlay, page-definition, page-media-select, page-select, plex, programmer-text, resource-context, resource-context-font, resource-context-form-definition, resource-context-overlay, resource-context-page-definition, resource-context-page-segment, resource-context-presentation-objectcontainer, resource-context-user, resource-exit, room-text, segment-file-size, shared-formdef, shift-out-shift-in, sides, start-on-new-sheet, table-reference-characters, title-text, transform-message-file-name, transform-output-file-name, user-id-text, x-image-shift, x-image-shift-back, y-image-shift, y-image-shift-back

3170 bits-per-spot, black-overprint, cms-proclink, cms-product, compressed-output, content-orientation, control-strip, copy-count, default-medium, default-printer-resolution, destination-pass-through, document-content, document-content-list, document-format, document-type, dot-shape, enable-settrap, image-center-x, image-center-y, image-length, image-scale, image-width, maximum-messages-printed, output-bin, output-face-up, overprint, page-clip, plex, sides, x-image-shift, y-image-shift

Email account-text, address1-text, address2-text, address3-text, address4-text, carriage-control-type, chars, convert-to-ebcdic, copy-count, default-character-mapping, document-comment, document-content, document-format, document-type, email-from-address, email-to-address, form-definition, image-fit, image-length, image-width, input-exit, maximum-messages-printed, new-line-option, number-up, other-transform-options, output-format, overlay, page-definition, page-select, resource-context, resource-context-font, resource-contextform-definition, resource-context-overlay, resource-context-pagedefinition, resource-context-page-segment, resource-context-user, resource-exit, shared-formdef, shift-out-shift-in, subject-text, table-reference-characters, title-text, transform-message-file-name, transform-output-file-name, x-image-shift, y-image-shift

Fax account-text, address1-text, address2-text, address3-text, address4-text, callback-number, carriage-control-type, chars, convert-to-ebcdic,

copy-count, default-character-mapping, destination-company-text, document-comment, document-content, document-format, document-type, fax-number, fax-to-name, form-definition, image-fit, image-length, image-width, input-exit, maximum-messages-printed, new-line-option, number-up, originating-company-text, other-transform-options, output-format, overlay, page-definition, page-select, resource-context, resource-context-font, resource-contextform-definition, resource-context-overlay, resource-context-pagedefinition, resource-context-page-segment, resource-context-user, resource-exit, shared-formdef, shift-out-shift-in, subject-text, table-reference-characters, title-text, transform-message-file-name, transform-output-file-name, x-image-shift, y-image-shift

Infoprint 2000

account-text, base-printer, carriage-control-type, chars, copy-count, convert-to-ebcdic, default-character-mapping, default-medium, default-print-resolution, document-comment, document-content, document-format, document-type, form-definition, halftone, image-fit, image-length, image-out-format, image-width, input-exit, new-line-option, number-up, other-transform-options, output-bin, output-format, overlay, page-definition, page-select, plex, printer-pass-through, resource-context, resource-context-font, resource-context-form-definition, resource-context-page-definition, resource-context-page-segment, resource-context-overlay, resource-context-user, resource-exit, shift-out-shift-in, sides, start-on-new-sheet, table-reference-characters, transform-message-filename, transform-output-file-name, x-image-shift, x-image-shift-back y-image-shift, y-image-shift-back

Passthrough

copy-count, default-medium, destination-pass-through, document-content, document-type

IPP copy-count, default-medium, destination-pass-through, document-content, document-type

document-finishings-supported

Identifies the document finishing options that this actual destination supports.

GUI Label

Finishing options allowed

DSS

PSF

Type

Resettable, multi-valued

Allowed Values

You can enter any of these fixed values: z-fold

Default Values

z-fold

Usage Guidelines

• Infoprint compares the document attribute **document-finishing** to this attribute for validation and scheduling.

• You can use this attribute to restrict use of this actual destination.

document-formats-ripped-at-destination

Identifies the document formats that can be ripped at this actual destination.

GUI Label

Formats to RIP at destination

DSS

Email, Infoprint 2000

Type

Resettable, multi-valued

Allowed Values

You can enter any of these fixed values:

Fixed Value	Input Synonym	DSS
ascii		Infoprint 2000
kgl		Infoprint 2000
pcl	hppcl, hp-pcl	Infoprint 2000
postscript	ps	Email, Infoprint 2000
tiff		Email

Default Values

No default values

document-formats-supported

Identifies the document formats that this actual destination supports. Infoprint sets this value dynamically based on the DSS and the document formats for which transforms are available.

GUI Label

Formats allowed

DSS

All

Type

Resettable, multi-valued

Allowed Values

You can enter any of these fixed values based on DSS for Infoprint Manager for AIX. There are no DSS restrictions for these values with Infoprint Manager for Windows NT and Windows 2000; however, you must ensure that the actual destination supports the document-format, or that a transform object is available that transforms the datastream into something that the PSF DSS supports.

Fixed Value	Input Synonym	DSS
ascii		AIX, BSD, PSF (except upload printers), Passthrough, IPP
dbcs-ascii		AIX, BSD, PSF, Infoprint 2000
ditroff		BSD, PSF DSS for AIX, email, fax, Infoprint 2000
d630		AIX, BSD
gif		BSD, PSF DSS for AIX, email, fax, Infoprint 2000
hpgl	hp-gl	AIX, BSD

Fixed Value	Input Synonym	DSS
iso-6429		AIX, BSD, Passthrough, IPP
jpeg		BSD, PSF DSS for AIX, email, fax, Infoprint 2000
kgl		BSD, Infoprint 2000
lcds		BSD
line-data		BSD, PSF, email, fax, Infoprint 2000
metacode		BSD
modca-p	afpds	BSD, PSF, email, fax, Infoprint 2000
passthru		AIX, BSD
pcl	hppcl, hp-pcl	AIX, BSD, PSF, email, fax, Infoprint 2000, Passthrough, IPP
pdf		BSD, PSF, email, fax, Infoprint 2000
postscript	ps	All
ppds		BSD
sap		BSD, PSF DSS for AIX, email, fax, Infoprint 2000,
		Passthrough
sap-abap		BSD, PSF DSS for AIX, email, fax, Infoprint 2000,
		Passthrough
simple-text	text	BSD, Passthrough, IPP
tiff		BSD, PSF DSS for AIX, email, fax, Infoprint 2000

Default Values

AIX ascii, hpgl, iso-6429, passthru, pcl, pdf, and postscript.

> Based on the value of the destination-model attribute and how the /usr/lpd/pio/predef directory defines the printer model.

ascii, iso-6429, pcl, ppds, postscript, simple-text.

PSF upload-SNA-attached and upload-TCP/IP-attached actual destinations If all transforms are available, dbcs-ascii, ditroff, gif, jpeg, line-data, modca-p, pcl, postscript, sap, sap-abap, tiff

Other PSF actual destinations with PSF DSS for AIX

If all transforms are available, ascii, dbcs-ascii, ditroff, gif, jpeg, line-data, modca-p, pcl, pdf, postscript, sap, sap-abap, tiff

Other PSF actual destinations with PSF DSS for Windows NT and Windows

If all transforms are available, ascii, dbcs-ascii, line-data, modca-p, pcl, pdf, postscript

3170 postscript

Infoprint 2000

If all transforms are available, dbcs-ascii, ditroff, gif, jpeg, kgl, line-data, modca-p, pcl, pdf, postscript, sap, sap-abap, sap-otf, tiff

Fax, Email

If all transforms are available, dbcs-ascii, ditroff, gif, jpeg, line-data, modca-p, pcl, pdf, postscript, sap, sap-abap, sap-otf, tiff

Passthrough

ascii, iso-6429, pcl, ppds, postscript, simple-text.

IPP ascii, iso-6429, pcl, ppds, postscript, simple-text.

Usage Guidelines

• When you create a PSF, email, fax, or Infoprint 2000 actual destination, Infoprint sets these values to the document formats for which transforms are available.

When the server is shut down and restarted, Infoprint updates the values to reflect transforms that have been added or deleted. You can also modify these values.

- Infoprint compares the document attribute document-format to this attribute for validation and scheduling.
- Delete attribute values to restrict use of this actual destination.

document-types-supported

Identifies the types of documents that this actual destination supports.

GUI Label

Types allowed

DSS

All

Type

Resettable, multi-valued

Allowed Values

You can enter any of these fixed values:

Fixed Value DSS color-mapping-table PSF cover-sheet Fax

document-definition PSF DSS for AIX, 3170, email, fax, Infoprint 2000

email-body Email email-signature Email file-reference All

font PSF, email, fax, Infoprint 2000 form-definition PSF, email, fax. Infoprint 2000 formatted-job-ticket PSF, 3170, email, fax, Infoprint 2000 insert-sheet PSF, email, fax, Infoprint 2000 job-ticket PSF, 3170, email, fax. Infoprint 2000 overlay PSF, email, fax, Infoprint 2000 page-definition PSF, email, fax, Infoprint 2000 page-segment PSF, email, fax, Infoprint 2000 page-shift-file PSF, email, fax, Infoprint 2000

printable All

resource PSF DSS for AIX, 3170, email, fax, Infoprint 2000 **variable-data** PSF DSS for AIX, 3170, email, fax, Infoprint 2000

Default Values

AIX file-reference, printable

BSD file-reference, printable

PSF DSS for AIX

color-mapping-table, document-definition, file-reference, font, form-definition, formatted-job-ticket, insert-sheet, job-ticket, overlay, page-definition, page-segment, page-shift-file, printable, resource, variable-data

PSF DSS for Windows NT and Windows 2000

color-mapping-table, file-reference, font, form-definition, formatted-job-ticket, insert-sheet, job-ticket, overlay, page-definition, page-segment, page-shift-file, printable

- 3170 document-definition, file-reference, formatted-job-ticket, job-ticket printable, resource, variable-data
- Email document-definition, email-body, email-signature, file-reference, font, form-definition, formatted-job-ticket, insert-sheet, job-ticket, overlay, page-definition, page-segment, page-shift-file, printable, resource, variable-data
- Fax cover-sheet, document-definition, file-reference, font, form-definition, formatted-job-ticket, insert-sheet, job-ticket, overlay, page-definition, page-segment, page-shift-file, printable, resource, variable-data

Infoprint 2000

document-definition, file-reference, font, form-definition, formatted-job-ticket, form-definition, insert-sheet, job-ticket, overlay, page-definition, page-shift-file, printable resource, variable-data

Passthrough

file-reference, printable

IPP file-reference, printable

Usage Guidelines

- Infoprint compares the document attribute **document-type** to this attribute for scheduling.
- You can use this attribute to restrict use of this actual destination.

dss-job-message-disposition

Indicates how job messages about errors detected by the device support system (DSS), such as data stream errors, are recorded.

GUI Label

Record job messages

DSS

PSF

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

log print

Default Value

print

Usage Guidelines

If you specify **log**, messages are written to the

- /var/psf/DestinationName/jobmessage.log file for AIX, where DestinationName is the name of this actual destination.
- \install_ path\var\psf\DestinationName\jobmessage.log file Windows NT and Windows 2000, where DestinationName is the name of this actual destination and install_path indicates the path where you installed Infoprint Manager.

dss-job-message-log-size

Indicates the size, in kilobytes, the DSS job message log can grow to.

GUI Label

Job message log size (KBytes)

DSS

PSF

Type

Resettable, single-valued

Allowed Values

You can enter an integer from 1 to 2000000. The unit is kilobytes.

Default Value

8192

Usage Guidelines

This attribute is used only when the value of the **dss-job-message-disposition** attribute is **log**.

dss-job-message-log-wrap

Indicates whether Infoprint should start overwriting messages at the beginning of the DSS job message log when the log is full.

GUI Label

Wrap job message log

DSS

PSF

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

true

Usage Guidelines

This attribute is used only when the value of the **dss-job-message-disposition** attribute is **log**.

ebcdic-character-mapping

Indicates the EBCDIC code page that PSF/MVS uses to map the attributes of this PSF upload-TCP/IP-attached or PSF upload-SNA-attached actual destination.

GUI Label

EBCDIC code page to use

DSS

PSF

Type

Resettable, single-valued

Allowed Values

You can enter the name of an EBCDIC code page.

Default Value

ibm-037

Usage Guidelines

Infoprint requires this attribute for PSF upload-SNA-attached and upload-TCP/IP-attached actual destinations and ignores it for other attachment types.

enabled

Indicates whether this actual destination is enabled and can accept jobs.

GUI Label

Enabled

DSS

All

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value to:

- **true** when an Infoprint administrator has issued the **pdenable** command, and the queue associated with the destination exists and is in communication with this actual destination.
- false when an Infoprint administrator has disabled this actual destination with the pddisable command, or when some printer error has been detected.

Default Value

false

end-message-supported

Indicates whether this actual destination supports the job attribute **job-end-message**.

GUI Label

Send job completed message

DSS

All

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

true

Usage Guidelines

- · Use this attribute to allow operators to receive messages that users specify with the job-end-message job attribute when they submit the job. When the value of this attribute is true, Infoprint sends the message to the operators specified by the notify-operator attribute for this actual destination when the job finishes printing.
- Infoprint compares the job attribute job-end-message to this attribute for validation and scheduling.
- You can use this attribute to restrict use of this actual destination.

end-sheets-supported

Identifies the types of end sheets that this actual destination supports.

GUI Label

End sheets allowed

DSS

AIX, PSF

Type

Resettable, multi-valued

Allowed Values

You can enter any of the following fixed values. For PSF only, you can enter a string up to 255 characters long that contains identifiers of auxiliary-sheet objects.

Fixed Value	DSS	Explanation
accounting-log	PSF	This value is technically valid, but should not be used for end sheets.
blank	PSF	The end sheet is blank.
brief	AIX, PSF	The end sheet style is brief.
full	AIX, PSF	The end sheet style is full.
job-ticket	PSF	The job ticket is printed on the end sheet.
none	AIX, PSF	No end sheet prints.

Default Values

AIX brief, full, none

PSF accounting-log, blank, brief, full, job-ticket, none, and the names of other defined auxiliary sheets which have legal PSF auxiliary sheet attributes.

- PSF actual destinations can use auxiliary-sheet objects if they have valid psf-exit-xxx values. AIX actual destinations print start and end sheets, but they do not use auxiliary-sheet objects.
- Infoprint verifies that the value of the **printer-end-sheet** attribute is a value of this attribute.
- You cannot delete a value from this attribute if the value you want to delete is the value of the **printer-end-sheet** attribute.
- · For PSF actual destinations, Infoprint sets this value dynamically to the names of all defined auxiliary sheets with legal attributes. You should never have to reset this value.

font-resolutions-supported

Indicates the values of the document attribute **font-resolution** that this actual destination accepts.

GUI Label

Font resolutions allowed

DSS

PSF

Type

Resettable, multi-valued

Allowed Values

You can enter any of these fixed values:

240 300 outline

Default Values

240, 300, outline

Usage Guidelines

- Usually the font resolution and the printer resolution match, but there are two cases when they do not:
 - Some printer devices, for example, the Infoprint 60 and Infoprint 4000s, can print fonts of any resolution, although the print head is always 600 pels.
 - It is possible to print a document created with fonts of one resolution on a
 printer device with a different resolution by substituting fonts. Depending on
 the document, the output may or may not be acceptable.
- Infoprint compares the document attribute **font-resolution** to this attribute for validation and scheduling.
- You can use this attribute to restrict use of this actual destination.

force-destination-setup

Indicates whether jobs requiring resources that this actual destination does not have ready or does not support should be held or scheduled to print.

GUI Label

Disable on job mismatch

DSS

All

Type

Resettable, single-valued

Input Synonym

You can use the synonym **force-printer-setup**.

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

false

Usage Guidelines

- When the value of **force-destination-setup** is **false**, Infoprint checks that the actual destination can process each job in the queue before scheduling the job to print. If the job requires any resources that are not ready or not supported, the job is RIPped if appropriate, then held. The **required-resources-not-ready** job attribute indicates what resources are not ready. The **required-resources-not-supported** job attribute indicates what resources are not supported.
- When the value of force-destination-setup is true, Infoprint does not check
 whether the actual destination can process the job until the job is sent to the
 actual destination. At that time, if any required resources are not ready or not
 supported, Infoprint disables the actual destination and sends a message to the
 operator to change the destination setup. When the operator enables the actual
 destination, the job is printed or transmitted.

force-printer-setup

See force-destination-setup.

form-definition

Identifies the default form definition that the output device uses when printing or transmitting a document.

GUI Label

Form definition

DSS

PSF, Email, Fax, Infoprint 2000

Type

Resettable, single-valued

Allowed Values

You can enter a text string up to 8 characters long that contains the form-definition ID.

Default Value

Basic Infoprint administrator's GUI F100D

Advanced Infoprint administrator's GUI and command line F1A10111

Usage Guidelines

- The form definition controls positioning of the output image on the page.
- A form definition can specify overlays, a paper source for cut-sheet printers (input bin selection), duplex printing, and text suppression on a page.

halftones-supported

Identifies the values for the document attribute **halftone** that this actual destination supports.

GUI Label

Halftones allowed

DSS

PSF

Type

Resettable, multi-valued

Allowed Values

The value of a halftone attribute is a combination of screen-name and output-appearance in the format: screen-name:output-appearance.

For custom halftones, the value can also be a combination of screen-name, output-appearance, and saved-calibration in the format: screen-name:outputappearance:saved-calibration.

You can enter a customized value or one of these fixed values:

ibm71lpi:standard

ibm71lpi:highlight-midtones

ibm71lpi:dark

ibm85lpi:standard

ibm85lpi:highlight-midtones

ibm85lpi:dark

ibm106lpi:standard

ibm106lpi:highlight-midtones

ibm106lpi:dark

ibm141lpi:standard

ibm141lpi:highlight-midtones

ibm141lpi:dark

Note: With the Infoprint 21, you can select the following halftone values in addition to the fixed values listed above:

ibm150lpi:standard

ibm150lpi:highlight-midtones

ibm150lpi:dark

ibm200lpi:standard

ibm200lpi:highlight-midtones

ibm200lpi:dark

You can enter one of the following fixed values if you are using enhanced toner on the Infoprint4000 or Infoprint4000-IR3-IR4 printer:

ibm71lpi:standard.enhtoner

ibm71lpi:highlight-midtones.enhtoner

ibm71lpi:dark.enhtoner

ibm85lpi:standard.enhtoner

ibm85lpi:highlight-midtones.enhtoner

ibm85lpi:dark.enhtoner

ibm106lpi:standard.enhtoner

ibm106lpi:highlight-midtones.enhtoner

ibm106lpi:dark.enhtoner

ibm141lpi:standard.enhtoner

ibm141lpi:highlight-midtones.enhtoner

ibm141lpi:dark.enhtoner

Default Value

ibm71lpi:standard

ibm71lpi:highlight-midtones

ibm71lpi:dark

ibm85lpi:standard

ibm85lpi:highlight-midtones ibm85lpi:dark ibm106lpi:standard ibm106lpi:highlight-midtones ibm106lpi:dark ibm141lpi:standard ibm141lpi:highlight-midtones ibm141lpi:dark

For the Infoprint4000 and Infoprint4000-IR3-IR4 printers, the following are also defaults:

ibm71lpi:standard.enhtoner

ibm71lpi:highlight-midtones.enhtoner

ibm71lpi:dark.enhtoner

ibm85lpi:standard.enhtoner

ibm85lpi:highlight-midtones.enhtoner

ibm85lpi:dark.enhtoner

ibm106lpi:standard.enhtoner

ibm106lpi:highlight-midtones.enhtoner

ibm106lpi:dark.enhtoner

ibm141lpi:standard.enhtoner

ibm141lpi:highlight-midtones.enhtoner

ibm141lpi:dark.enhtoner

Usage Guidelines

- Infoprint compares the document attribute halftone to this attribute for validation and scheduling.
- You can use this attribute to restrict the use of this actual destination.

image-fit-supported

Specifies the methods of adjusting TIFF, GIF, and JPEG images to fit on the printed page that this actual destination supports.

GUI Label

Image fit allowed

DSS

PSF, Email, Fax, Infoprint 2000

Type

Resettable, multi-valued

Allowed Values

You can enter any of these fixed values: position-and-trim scale-to-fit

Default Value

No default value

Usage Guidelines

Infoprint compares the document attribute **image-fit** to this attribute for validation and scheduling.

image-length

Specifies the default length of a page of PostScript, PCL, TIFF, GIF, JPEG, or PDF data after it has been transformed for Infoprint printing or transmission.

GUI Label

Finished page length (inches) or (mm)

DSS

PSF, Email, Fax, Infoprint 2000

Type

Resettable, single-valued

Allowed Values

The value you specify is in the form nnnn.nnnu

nnnn.nnn

is a number that can optionally contain a decimal point.

u is the units in inches (i) or millimeters (m). If you do not specify a unit, the default unit is pels. You cannot use a decimal point when the unit is pels.

For 240-pel resolution printers, valid values are:

 16 - 8160
 pels

 0.065 - 34
 inches

 1.641 - 863.628
 millimeters

For 300-pel resolution printers, valid values are:

 16 - 10200
 pels

 0.052 - 34
 inches

 1.313 - 863.628
 millimeters

For 480-pel resolution printers, valid values are:

 16 - 16320
 pels

 0.065 - 34
 inches

 1.641 - 863.628
 millimeters

For 600-pel resolution printers, valid values are:

 16 - 20400
 pels

 0.052 - 34
 inches

 1.313 - 863.628
 millimeters

Default Value

No default value

Usage Guidelines

- This attribute is valid only for GIF, JPEG, PCL, PDF, PostScript, and TIFF documents.
- This attribute is not valid for ASCII documents.
- If a text margin is already built into the file, try **image-length=11i** to set the length to 11 inches.
- This attribute is used if you do not specify a value for the **image-length** document attribute or in the file specified by the **rip-ini-file** attribute.

image-out-formats-supported

Specifies the formats of image data, produced by the program that transforms line data to AFP data, that this actual destination supports.

GUI Label

Image out formats allowed

DSS

PSF, Infoprint 2000

Type

Resettable, multi-valued

Allowed Values

You can enter any of these fixed values:

```
ioca-uncompressed
im1
io1
io1-g4
io1-mmr
asis
```

Default Values

ioca-uncompressed, im1, io1, io1-g4, io1-mmr, asis

Usage Guidelines

Infoprint compares the document attribute **image-out-format** to this attribute for validation and scheduling. You should use the document attribute when you print line-data documents.

image-width

Specifies the default width of a page of PostScript, PCL, TIFF, GIF, JPEG, or PDF data after it has been transformed for Infoprint printing or transmission.

GUI Label

Finished page width (inches) or (mm)

DSS

PSF, Fax, Email, Infoprint 2000

Type

Resettable, single-valued

Allowed Values

The value you specify is in the form nnnn.nnnu

nnnn.nnn

is a number that can optionally contain a decimal point.

is the units in inches (i) or millimeters (m). If you do not specify a unit, the default unit is pels. You cannot use a decimal point when the unit is pels.

For 240-pel resolution printers, valid values are:

 16 - 8160
 pels

 0.065 - 34
 inches

 1.641 - 863.628
 millimeters

For 300-pel resolution printers, valid values are:

 16 - 10200
 pels

 0.052 - 34
 inches

 1.313 - 863.628
 millimeters

For 480-pel resolution printers, valid values are:

16 - 16320 pels 0.065 - 34 inches **1.641 - 863.628** millimeters

For 600-pel resolution printers, valid values are:

 16 - 20400
 pels

 0.052 - 34
 inches

 1.313 - 863.628
 millimeters

Default Value

No default value

Usage Guidelines

- This attribute is valid only for GIF, JPEG, PCL, PDF, PostScript, and TIFF documents.
- If a text margin is already built into the file, try **image-width=8.5i** to set the length to 8.5 inches.
- This attribute is used if you do not specify a value for the **image-width** document attribute or in the file specified by the **rip-ini-file** attribute.

input-data-user-exit

Specifies the name of a program that monitors input data to this actual destination. For example, if a certain document format is printed on special media, the input data exit program can issue a message requesting the operator to change the paper whenever a job in that format is submitted.

GUI Label

Input data exit

DSS

PSF, Email, Fax, Infoprint 2000

Type

Resettable, single-valued

Allowed Values

You can enter a text string of up to 255 characters.

Default Value

No default value

Usage Guidelines

You can use the sample input data exit program supplied:

- With Infoprint:
 - For AIX, /usr/lpp/psf/bin/ainuxind (source /usr/lpp/psf/exits/ainuxind.c)
 - For Windows NT and Windows 2000, \install_path\bin\ainuxind (source \install_path\exits\ainuxind.c), where install_path indicates the path where you installed Infoprint Manager
- Write your own

For more information on user-exit programs for Infoprint Manager, visit the appropriate site from the IBM Printing Systems web site: http://www.ibm.com/printers.

input-trays-medium

Identifies which input medium is in which printer tray.

GUI Label

Media ready

DSS

AIX

Type

Resettable, multi-valued, complex

Syntax

tray-identification:medium-identifier

Separate each pair of values with a colon, for example:

tray-1:A4-colored

Components

tray-identification: Identifies the type of input tray.

GUI Label: Input tray

Type: Single-valued

Allowed Values: You can enter one of these fixed values:

auto-envelope-feed manual-envelope-feed automatic-tray middle auxiliary-envelope top auxiliary-paper tray-1 bottom tray-2 continuous-form-feed tray-3 current-selected-tray tray-4 envelope tray-5 large-capacity capacity-2000-sheet

manual

Default Value: If Simple Network Management Protocol (SNMP) communication is active, Infoprint queries the printer device and sets the value according to the response; otherwise **tray-1**. However, if you specify a value for **input-tray**, you deactivate the SNMP default.

medium-name: Identifies the medium in the input tray.

GUI Label: Media ready

Type: Single-valued

Allowed Values: You can enter a text string up to 255 characters long that contains the name of the medium or one of the fixed values of the **medium-identifier** attributes of the default media. See the medium attribute **medium-identifier** for a list of these values.

Default Value: If Simple Network Management Protocol (SNMP) communication is active, Infoprint queries the printer device and sets the values according to the response; otherwise letter. However, if you specify a value for medium-identifier, you deactivate the SNMP default.

Usage Guidelines

- Infoprint automatically sets the values for the **input-trays-supported** and **media-ready** attributes from the values of this attribute.
- Infoprint verifies that the values of the *medium-name* component of this attribute are values of the **media-supported** attribute.

input-trays-supported

Identifies the types of input trays, such as top or envelope, supported on the printer device.

GUI Label

Input trays allowed

DSS

AIX, BSD, PSF, Fax, Email, 3170

Type

Non-settable (AIX and PSF) or resettable (BSD), multi-valued

Allowed Values

- AIX Infoprint sets the values for this attribute based on the values of the input-trays-medium attribute.
- **BSD** You can enter any names that describe input trays.
- **PSF** Infoprint sets the values for this attribute based on the values of the **psf-tray-characteristics** attribute.

Default Values

- **AIX** The value of the **input-trays-medium** attribute
- **BSD** No default value
- **PSF** The value of the **psf-tray-characteristics** attribute

Usage Guidelines

- Infoprint uses this attribute for job validation and scheduling:
 - AIX Infoprint compares the document attribute **default-input-tray** to this attribute.
 - **BSD** This attribute is for information only.
 - **PSF** Infoprint compares the document attribute **default-input-tray** or **input-tray-select** to this attribute.
- You can use this attribute to restrict use of this actual destination.

intervention-timer

Specifies the maximum amount of time, in seconds, that Infoprint waits before it treats an intervention-required condition at the output device as a permanent error.

GUI Label

Intervention timer (sec)

DSS

PSF

Type

Resettable, single-valued

Allowed Values

You can enter a value of 1 through 9999. The unit is seconds.

Default Value

9999

Usage Guidelines

A value of 9999 specifies that a permanent error condition can never occur.

job-attributes-supported

Identifies the job attributes that this actual destination supports.

DSS

A11

Type

Non-settable, multi-valued

Allowed Values

Infoprint sets a text string that contains a list of job attributes that this actual destination supports.

Note: This list includes only job attributes that directly affect the actual destination. Jobs with attributes that affect the server, for example, job-retention-period, can be printed even though those attributes are not on this list.

Default Values

AIX auxiliary-sheet-selection, job-batch, job-start-wait

BSD job-batch, job-start-wait

PSF auxiliary-sheet-selection, current-page-printing, delete-segment-list, formatted-job-ticket-content, job-batch, job-finishing, job-rip-action, job-start-wait, media-sheets-completed, optimize-for-multiple-copies, segment-list-file-name

3170 formatted-job-ticket-content

delete-segment-list, formatted-job-ticket-content, job-batch, job-rip-action, job-ripped-by-server, job-start-wait, media-sheetscompleted, segment-list-file-name

Fax delete-segment-list, formatted-job-ticket-content, job-rip-action, job-start-wait, media-sheets-completed, segment-list-file-name

Infoprint 2000

auxiliary-sheet-selection, delete-segment-list, formatted-job-ticketcontent, job-finishings, job-rip-action, job-ripped-by-server, media-sheets-completed, segment-list-file-name

Passthrough

auxiliary-sheet-selection, job-batch, job-start-wait

IPP auxiliary-sheet-selection, job-batch, job-start-wait

iob-batches-ready

Specifies which job-batch values can currently print to this actual destination.

GUI Label

Job batches ready

DSS

All

Type

Resettable, multi-valued

Allowed Values

You can enter a text string up to 4095 characters long, for each value, that contains the job-batch name.

Default Values

No default values

Usage Guidelines

Infoprint compares the value of the job attribute **job-batch** to this attribute during job scheduling.

job-finishings-supported

Identifies the job finishing options that this actual destination supports.

GUI Label

Finishing options allowed

DSS

PSF, Infoprint 2000

Type

Resettable, multi-valued

Allowed Values

You can enter any of these fixed values for PSF-supported printers, that is printers that use the PSF DSS:

```
edge-stitch
edge-stitch-2
edge-stitch-3
edge-stitch-bottom
edge-stitch-left
edge-stitch-right
edge-stitch-top
saddle-stitch
staple-bottom-left
staple-bottom-right
staple-top-left
staple-top-right
```

You can enter any of these fixed values for printers that use the Infoprint 2000 DSS:

```
booklet-stitch-and-fold
booklet-stitch-fold-and-trim
edge-stitch-2
staple-bottom-left
staple-top-left
```

Default Values

3170 staple-top-left, staple-bottom-left, and edge-stitch

Infoprint 70

staple-top-left, staple-bottom-left, staple-top-right, and edge-stitch

Usage Guidelines

- Infoprint compares the job attribute **job-finishing** to this attribute for validation and scheduling.
- You can use this attribute to restrict the use of finishing options for an actual destination.

job-retry-count-limit

Indicates the number of times that Infoprint should attempt to submit a job to this actual destination after an initial failure.

GUI Label

Number of times to retry jobs

DSS

AIX, BSD, PSF, Fax, Passthrough, IPP

Type

Resettable, single-valued

Allowed Values

You can enter an integer from 0 through 2147483647.

Default Value

0

Usage Guidelines

- Values greater than 0 are useful when poor network line quality causes temporary loss of communication between this actual destination and the backend program. A second or subsequent attempt to submit the job may succeed if communication can be reestablished.
- If the job cannot be submitted within the specified number of attempts, Infoprint
 disables the destination and places it in the needs-key-operator state.
- The **job-retry-interval** actual destination attribute indicates the number of seconds between attempts.
- If the value of this attribute is **0**, the **job-retry-interval** attribute is ignored.
- If the value of the **job-retry-interval** attribute is **0**, this attribute is ignored.

job-retry-interval

Indicates the number of seconds that Infoprint should wait between attempts to submit a job to this actual destination.

GUI Label

Interval to retry jobs (sec)

DSS

AIX, BSD, PSF, Passthrough, IPP

Type

Resettable, single-valued

Allowed Values

You can enter an integer from 0 through 2147483647.

Default Value

0

Usage Guidelines

- If the job cannot be submitted within the specified number of attempts, Infoprint disables the destination and places it in the **needs-key-operator** state.
- The **job-retry-count-limit** actual destination attribute indicates the number of attempts after an initial failure.
- If the value of this attribute is **0**, the **job-retry-count-limit** attribute is ignored.
- If the value of the **job-retry-count-limit** attribute is **0**, this attribute is ignored.

job-rip-actions-supported

Indicates whether this actual destination supports converting a PostScript job to raster image patterns and holding the job, printing the job, or neither.

GUI Label

RIP options allowed

DSS

PSF, Email, Fax, Infoprint 2000

Type

Resettable, multi-valued

Allowed Values

You can enter any of these fixed values:
rip-and-hold
rip-and-print
rip-and-print-ignore-ready
rip-only
rip-only-ignore-ready

Default Value

rip-and-hold, rip-and-hold-ignore-ready, rip-and-print, rip-and-print-ignore-ready, rip-only, rip-only-ignore-ready

Usage Guidelines

Infoprint compares the job attribute **job-rip-action** to this attribute for validation and scheduling.

job-size-range-ready

Defines the range of job sizes in bytes (octets) that this actual destination can accept and print.

GUI Label

Size ready (Bytes)

DSS

All

Type

Resettable, single-valued, complex

Syntax

lower-limit:upper-limit

Separate the values with a colon, for example:

1025:1000000

You can omit either value, for example:

1025:

:1000000

Components

lower-limit: Identifies the lower limit value of the job size. The unit value is octets (bytes).

GUI Label: Lower limit

Type: Single-valued

Allowed Values: You can enter an integer from 0 to 9223372036854775800. The lower limit must be less than or equal to the upper limit.

Default Value: 0

upper-limit: Identifies the upper limit value of the job size. The unit value is octets (bytes).

GUI Label: Upper limit

Type: Single-valued

Allowed Values: You can enter an integer from 0 to 9223372036854775800. The upper limit must be greater than or equal to the lower limit.

Default Value: 9223372036854775800

Usage Guidelines

- You can use this attribute to restrict jobs sent to this actual destination according to the capacity of the output device or your policy for output device use.
- You must set the range for this attribute within the range of the job-size-range-supported value.
- Infoprint compares the job attribute total-job-octets to this attribute for scheduling.

job-size-range-supported

Defines the range of job sizes in bytes (octets) that this actual destination can accept.

GUI Label

Size allowed (Bytes)

DSS

All

Type

Resettable, single-valued, complex

Syntax

lower-limit:upper-limit

Separate the values with a colon, for example:

1025:1000000

You can omit either value, for example:

1025: :1000000

Components

lower-limit: Identifies the lower limit value of the job size. The unit value is octets (bytes).

GUI Label: Lower limit

Type: Single-valued

Allowed Values: You can enter an integer from 0 to 9223372036854775800. The lower limit must be less than or equal to the upper limit.

Default Value: 0

upper-limit: Identifies the upper limit value of the job size. The unit value is octets (bytes).

GUI Label: Upper limit

Type: Single-valued

Allowed Values: You can enter an integer from 0 to 9223372036854775800. The upper limit must be greater than or equal to the lower limit.

Default Value: 9223372036854775800

Usage Guidelines

- You can use this attribute to restrict jobs sent to this actual destination according to the capacity of the output device or your policy for output device use.
- You must set the range for this attribute equal to or greater than the range you specify for the **job-size-range-ready** attribute value.
- Infoprint compares the job attribute **total-job-octets** to this attribute for validation and scheduling.

job-start-wait-supported

Indicates whether job submitters are allowed to set the **job-start-wait** job attribute to pause the actual destination just before the job prints.

GUI Label

Wait to start job allowed

DSS

All

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

false

Usage Guidelines

Infoprint compares the job attribute **job-start-wait** to this attribute for validation and scheduling.

list-of-managers

Identifies the people responsible for the configuration of this actual destination and maintenance of the output device associated with this actual destination.

GUI Label

Managers

DSS

All

Type

Resettable, multi-valued

Input Synonym

You can use the synonym managers.

Allowed Values

You can enter a text string up to 255 characters long, for each value, that contains such things as the name, user ID, office number, or telephone number of the person responsible for this actual destination and the output device associated with it.

Default Values

No default values

Usage Guidelines

This attribute is useful if a user needs to contact someone to report a problem or to request a change.

locations

See destination-locations.

log-accounting-data

Defines whether the accounting log is active for this actual destination. If you set the value to the default by using the == operator, the value of the server attribute **log-accounting-data** is used.

GUI Label

Log accounting data

DSS

All

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Note: The accounting logs are stored in an Infoprint Server directory called **accounting.logs**.

Default Value

No default value

Usage Guidelines

You can use this attribute to activate or deactivate the accounting log for this actual destination.

Note: The accounting log contains the following job attributes and values for each job processed for this actual destination:

actual destination name (up to 255 characters)

job owner (up to 255 characters) **global job-id** without *ServerName* **submission-time** (GMT format)

submission-time (date in server's displayable locale and time zone)
submission-time (time in server's displayable locale and time zone)

completion-time (GMT format)

completion-time (date in server's displayable locale and time zone) **completion-time** (time in server's displayable locale and time zone)

pages-completed
octets-completed
data stream (first document only)

job name (up to 255 characters)

logical-destinations-assigned

Indicates the logical destination through which submissions to this actual destination are forwarded.

GUI Label

Route submitted jobs to

DSS

All

Type

Resettable, single-valued

Allowed Values

You can enter a text string of up to 255 characters that contains the name of the logical destination.

Default Value

No default value

Usage Guidelines

The named logical destination must exist in the same Infoprint server as the actual destination.

When a job submission is received at an actual destination object with the **logical-destinations-assigned** set, the **actual-destinations-requested** attribute is set to the name of the actual destination that received the request, and then the job is submitted through the specified **logical-destinations-assigned**.

If **logical-destinations-assigned** is **not** set in the actual destination, the actual destination does not accept direct job submission requests, which are rejected with an unsupported error message.

managers

See list-of-managers.

maximum-concurrent-jobs

Defines an upper limit for the number of jobs that this actual destination can process at a time.

GUI Label

Maximum concurrent jobs

DSS

All

Type

Resettable, single-valued

Allowed Values

AIX You can enter an integer from 1 through 9.

BSD You can enter an integer from 1 through 9.

Infoprint 2000

You can enter an integer from 1 through 99.

PSF You can enter an integer from 1 through 99.

Note: When you are using a PSF other-driver attached actual destination, the maximum value is 9.

3170 You can enter an integer from 1 through 99.

Email You can enter an integer from 1 through 99.

Fax You can enter an integer from 1 through 99.

Passthrough

You can enter an integer from 1 through 9.

IPP You can enter an integer from 1 through 9.

Default Value

AIX 2

BSD 1

Infoprint 2000

12

PSF other-driver attached actual destinations

2

PSF command-attached actual destinations

1

Other PSF actual destinations

4

3170 4 Email 12 Fax 12 Passthrough 1 IPP 1

Usage Guidelines

You can use this attribute to tune your Infoprint system to efficiently use your destination resources.

maximum-copies-supported

Indicates the number of document copies, in a single job, that this actual destination allows.

GUI Label

Maximum copies allowed

DSS

All

Type

Resettable, single-valued

Allowed Values

You can enter an integer from 1 through 2147483647.

Default Value

2147483647

Usage Guidelines

- You can use this attribute to restrict jobs sent to this actual destination according to the capacity of the output device or your policy for output device use.
- Infoprint compares the document attribute **copy-count** to this attribute for scheduling.

maximum-fonts-to-keep

Specifies the maximum number of fonts to keep in the memory of the printer device between jobs.

GUI Label

Maximum fonts to keep

DSS

PSF

Type

Resettable, single-valued

Allowed Values

You can enter an integer from 0 through 999.

Default Value

10

Usage Guidelines

- Fonts are a single size and typeface in a particular type family, including letters, numerals, punctuation marks, special characters, and ligatures.
- If you specify that the printer device can store fonts in its memory between jobs, the printer will not have to download the same fonts for the next job. However, this requires additional printer memory.

maximum-overlays-to-keep

Specifies the maximum number of overlays to keep in the memory of the printer device between jobs.

GUI Label

Maximum overlays to keep

DSS

PSF

Type

Resettable, single-valued

Allowed Values

You can enter an integer from 0 through 999.

Default Value

Usage Guidelines

- Overlays are collections of predefined data such as lines, shading, test boxes, and logos that the printer device can merge with variable data on a page or a
- If you specify that the printer device can store overlays in its memory between jobs, the printer will not have to download the same overlays for the next job. However, this requires additional printer memory.

maximum-presentation-object-containers-to-keep

Specifies the maximum number of presentation object containers (called data object resources in the IPDS Reference) to keep in the memory of the printer device between jobs.

GUI Label

Maximum presentation object containers to keep

DSS

PSF

Type

Resettable, single-valued

Allowed Values

You can enter an integer from 0 through 32511.

Default Value

100

maximum-segments-to-keep

Specifies the maximum number of page segments to keep in the memory of the printer device between jobs.

GUI Label

Maximum segments to keep

DSS

PSF

Type

Resettable, single-valued

Allowed Values

You can enter an integer from 0 through 999.

Default Value

0

Usage Guidelines

- Page segments contain text and images that the printer device can include at any addressable point on a page or an electronic overlay.
- If you specify that the printer device can store page segments in its memory between jobs, the printer will not have to download the same page segments for the next job. However, this requires additional printer memory.

media-ready

Identifies the media now loaded in the printer device.

GUI Label

Media ready

DSS

AIX, BSD, PSF, 3170, Infoprint 2000, IPP, Passthrough

Type

Non-settable (AIX and PSF) or resettable (BSD, 3170, IPP, and Passthrough), multi-valued

Allowed Values

- AIX Infoprint sets the values for this attribute based on the values of the input-trays-medium attribute.
- **BSD** You can enter any values of the **media-supported** attribute.

PSF, Infoprint 2000

Infoprint sets the values for this attribute based on the values of the psf-tray-characteristics attribute.

3170 Infoprint sets the values for this attribute based on the values of the media-supported attribute.

IPP and Passthrough

You can enter any values of the **media-supported** attribute.

Default Values

For AIX, BSD, PSF actual destinations, Passthrough, and IPP, if SNMP communication is active, Infoprint queries the printer device and sets the values according to the response; otherwise:

AIX The default comes from the values of the input-trays-medium attribute.

BSD No default value

PSF, Infoprint 2000

The default comes from the values of the **psf-tray-characteristics** attribute.

3170 The values of the **media-supported** attribute.

IPP The default value comes from IPP.

Passthrough

There is no default.

Usage Guidelines

- Infoprint restricts the possible values for this attribute to the values currently specified for the **media-supported** attribute.
- Infoprint compares the document attribute **default-medium** to this attribute for job scheduling.
- If you specify a value for the **media-ready** attribute, you deactivate the default provided by SNMP.

media-supported

Identifies the types of media that the actual destination supports.

GUI Label

Media allowed

DSS

AIX, BSD, PSF, 3170, Infoprint 2000, IPP, Passthrough

Type

Resettable, multi-valued

Allowed Values

You can enter a text string up to 255 characters long that contains the names of the media. These can be:

- The medium identifiers of medium objects created by the **pdcrmed** utility. For these fixed values, see the medium **medium-identifier** attribute.
- The medium identifiers of medium objects you created yourself
- For PSF actual destinations, IPP printers, Passthrough printers, and BSD actual destinations, any names that describe the media, even if no medium objects with those names exist
- For Infoprint 2000 actual destinations, IPP printers, and Passthrough printers, medium objects must exist for all the names that you created for the Infoprint 2000 printers.

Default Values

For AIX, BSD, PSF, IPP, and Passthrough actual destinations, if SNMP communication is active, Infoprint queries the printer device and sets the values according to the response; otherwise:

AIX letter

BSD No default values

PSF, Infoprint 2000 (basic Infoprint administrator's GUI)

All allowed fixed values

PSF, Infoprint 2000 (advanced Infoprint administrator's GUI and command line) Command-attached actual destinations

letter

other-driver attached actual destinations letter

Other actual destinations

No default values

3170 The names of all default medium objects

IPP With Internet Printing Protocol (IPP) printers, the default comes from IPP. **Passthrough**

There is no default.

Usage Guidelines

- Infoprint uses this attribute for job validation:
 - AIX Infoprint compares the document attribute **default-medium** to this attribute for job validation and scheduling.
 - **BSD** This attribute is for information only.
 - **PSF** Infoprint compares the document attribute **default-medium** or **page-media-select** to this attribute for job validation and scheduling.
 - 3170 Infoprint compares the document attribute **default-medium** to this attribute for job validation and scheduling.
- For AIX actual destinations, Infoprint verifies that the values of the *medium-identifier* component of the **input-trays-medium** attribute are values of this attribute.
- For PSF and Infoprint 2000 actual destinations, Infoprint verifies that the values
 of the *medium-loaded* component of the **psf-tray-characteristics** attribute are
 values of this attribute.
- The actual destination does not automatically update this attribute. When you create a medium object, you must add its medium identifier to each actual destination that supports it.
- You can use this attribute to restrict use of this actual destination.
- If you specify a value for the **media-supported** attribute, you deactivate the default provided by SNMP.

message

Provides information associated with this actual destination.

GUI Label

Message

DSS

All

Type

Resettable, single-valued

Allowed Values

You can enter a text string up to 4095 characters long that contains information about this actual destination.

Default Value

No default value

Usage Guidelines

Use of this descriptive attribute is optional.

message-font-type

Identifies the font type that the printer device uses to print the message page.

GUI Label

Message page font type

DSS

PSF

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

normal condensed

Default Value

normal

message-form-definition

Identifies the AFP form definition that the printer device uses to process the message page.

GUI Label

Message page form definition

DSS

PSF

Type

Resettable, single-valued

Allowed Values

A text string up to 255 characters long that contains the form definition ID.

Default Value

F1MG0110

model

See destination-model.

non-process-runout-timer

Designates the amount of time, in seconds, that a continuous-forms printer device waits for the next job before it runs the forms from the print transfer station to the stacker after the last page of a job prints.

GUI Label

Non-process runout timer (sec)

DSS

PSF

Type

Resettable, single-valued

Allowed Values

You can enter an integer from 0 through 9999. The unit is seconds.

Default Value

60

Usage Guidelines

If you enter a value of 0, Infoprint does not allow the timer to expire.

notification-profile

Designates which users Infoprint notifies of specified events related to this actual destination, and how Infoprint notifies them.

GUI Label

Notification profile

DSS

A11

Type

Resettable, multi-valued, complex

Syntax

-x "notification-profile={event-identifiers=event ... delivery-address=name@node delivery-method=value event-comment='some text' locale=locale}"

You can omit any of these components, for example:

-x "notification-profile={event-identifiers=class-actual-destination-status class-warning delivery-address=jeff@ttank event-comment='Its still going' locale=En US.IBM-850}"

Components

event-identifiers: Specifies the events for which the user receives messages.

GUI Label: Events

Type: Multi-valued

Allowed Values: You can enter any of the values listed for the server attribute events-supported.

Default Values: object-deleted, object-cleaned, printer-needs-administrator, printer-needs-attention, printer-needs-operator, printer-timed-out

delivery-address: Provides the address of the person who receives the event messages or the directory location and file name where Infoprint stores the message.

GUI Label: Address

Type: Single-valued

Allowed Values: You can enter a text string up to 255 characters long that contains the user name and node or the directory and file name.

Default Value: The login ID of the user who created this actual destination.

delivery-method: Specifies how the user or file receives event messages.

GUI Label: Method

Type: Single-valued

Allowed Values: You can enter one of these fixed values:

Fixed Value Input Synonym electronic-mail e-mail, email

file file-add-to message none

Default Value: message

Usage Guidelines:

- If you specify a value of **file** or **file-add-to**, you must specify a value for the **delivery-address** component.
- When you specify a value of **file**, the file is used for the life of the object. If you create another object with the same file name, the file gets replaced.
- When you specify a value of **file-add-to**, several objects write notifications to the same file, and it is never erased or recreated.

event-comment: Supplies textual information that Infoprint prepends to the event message.

GUI Label: Comment

Type: Single-valued

Allowed Values: You can enter a text string up to 4095 characters long that contains the comment.

Default Value: No default value

locale: Defines the language and code page of notification messages.

Type: Single-valued

Allowed Values: You can enter the name of any locale for which the Infoprint messages in the corresponding language are installed.

Default Value: The locale of the person who created this actual destination.

notify-operator

Identifies people who are to receive the messages specified by the job attributes **job-start-message** and **job-end-message**.

GUI Label

Operators to notify

DSS

All

Type

Resettable, multi-valued, complex

Input Synonym

You can use the synonym **operators**.

Syntax

delivery-method:delivery-address

Separate each pair of values with a colon, for example: message:op20phyptr1

Components

delivery-method: Specifies how the person receives the messages.

GUI Label: Method

Type: Single-valued

Allowed Values: You can enter one of these fixed values:

electronic-mail message none

Default Value: message

delivery-address: Provides the address of the person to receive the messages.

GUI Label: Address

Type: Single-valued

Allowed Values: Enter a login ID and node.

Default Value: The login ID of the person who created this actual destination.

number-up-supported

Specifies the number of pages that this actual destination can print on a single side of the paper.

GUI Label

Number up allowed

DSS

PSF, Email, Fax, Infoprint 2000

Type

Resettable, multi-valued

Allowed Values

You can enter any of these fixed values:

Fixed Value Input Synonym imposition-simple-1-up 1up imposition-simple-2-up 2up imposition-simple-3-up 3up

imposition-simple-4-up 4up

generic-none

Default Values

imposition-simple-1-up, imposition-simple-2-up, imposition-simple-3-up, imposition-simple-4-up, generic-none

Usage Guidelines

- The value **generic-none** applies only to the actual destination. You cannot request this value with the document attribute **number-up**.
 - When the values for **number-up-supported** include **generic-none**, the actual destination accepts documents without a value for the **number-up** attribute. The actual destination also accepts documents without a value for the **number-up** attribute when there are no values for **number-up-supported**.
- Infoprint compares the document attribute **number-up** to this attribute for validation and scheduling.
- You can use this attribute to restrict use of this actual destination.

object-class

Identifies the object class to which this object belongs.

DSS

All

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value to destination.

Default Value

destination

offset-stacking-available

Indicates whether PSF command-attached or other-driver attached actual destinations support offsetting jobs in the output stack.

GUI Label

Allow offset stacking

DSS

PSF

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

false

Usage Guidelines

- This attribute applies only to PSF command-attached and other-driver attached actual destinations. Other actual destinations ignore this attribute.
- Offset stacking occurs only if the form definition for the job specifies offset stacking.
- PPDS and PCL4 data streams do not support the offset stacking option; therefore, this attribute has no effect on destinations using those data streams.

This attribute is not used for job validation or scheduling.

operators

See notify-operator.

optimize-for-multiple-copies

Used with the optimize-for-multiple-copies job attribute to indicate whether the printer device should save pages in order to print multiple copies of the job faster.

GUI Label

Optimize for copies

DSS

PSF

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

actual destinations representing Infoprint 4000 printer devices (destination-model=Infoprint4000, destination-model=Infoprint4000-ID5-ID6, or destination-model=Infoprint4000-IR3-IR4) that are migrated from PSF for AIX or created using the Infoprint administrator's GUI

false All other actual destinations

Usage Guidelines

• This attribute is used in combination with the optimize-for-multiple-copies job attribute:

Job Attribute	Destination Attribute	Results
true	true	Pages are saved
true	false	Pages are not saved
false	true	Pages are not saved
false	false	Pages are not saved
No value	true	Pages are saved
No value	false	Pages are not saved

• If the printer device cannot save pages, the job is printed and this attribute is ignored.

orientations-supported

See content-orientations-supported.

other-options

See destination-pass-through.

output-appearances-supported

Use the halftones-supported attribute to specify the output-appearancessupported attribute values. (See "halftones-supported" on page 384 for more information.) The **ouptput-appearances-supported** attribute is supported to maintain downward compatibility, but it is not the recommended attribute for specifying the output-appearance values that this actual destination supports.

Identifies the values for the document attribute output-appearance that this actual destination supports.

DSS

PSF (AIX Only)

Type

Resettable, multi-valued

Allowed Values

You can enter a customized value or any of these fixed values: highlight-midtones dark

Default Values

standard, highlight-midtones, dark

Usage Guidelines

- Infoprint compares the document attribute output-appearance to this attribute for validation and scheduling.
- You can use this attribute to restrict use of this actual destination.

output-bin

Specifies the name of the output bin to which you want Infoprint to direct output.

GUI Label

Default output bin

DSS

PSF, Infoprint 2000

Type

Resettable, single-valued

Allowed Values

You can enter a text string up to 255 characters long that contains the output bin name.

Default Value

PSF No default values

3170 main, test

Infoprint 2000 stapler

Usage Guidelines

• The name you specify must match the name in one of the values for the following attribute:

PSF output-bin-numbers

Infoprint 2000

output-bins-supported

- Infoprint only uses the value you specify for the **output-bin** actual destination attribute if the user does not specify a value for the output-bin document attribute and if the form definition Infoprint uses for the job does not specify an output bin.
- This attribute is valid for ASCII documents within a job only if it is not changed between documents in the job.
- With Infoprint 2000:
 - If a job requests stapling or some other finishing, the job goes to the appropriate finishing output bin regardless of what output bin is specified with the **output-bin** attribute.
 - If a job specifies a finishing output bin and no finishing is specified, the job is printed and sent to the top bin.

output-bin-numbers

Specifies a bin name followed by a bin number. Infoprint uses this attribute to map names of output bins, such as top, to bin numbers that the printer device understands.

GUI Label

Map output bin to number

DSS

PSF

Type

Resettable, multi-valued, complex

Syntax

bin-name:bin-number

Separate each pair of values with a colon, for example:

top:1 staple:2

Components

bin-name: The name of an output bin.

GUI Label: Bin name

Type: Single-valued

Allowed Values: You can enter a text string containing a bin name.

bin-number: The number that the printer device has assigned to the output bin.

GUI Label: Bin number

Type: Single-valued

Allowed Values: You can enter a numeric value.

Default Values

If SNMP communication is active, Infoprint queries the printer device and sets the values according to the response; otherwise no default value.

Usage Guidelines

- Infoprint automatically updates the **output-bins-supported** actual destination attribute from the value or values that you set for this attribute.
- If you set the **output-bins-numbers** attribute, you deactivate the default provided by SNMP.

output-bins-supported

Identifies the supported output bins on the printer device.

GUI Label

Output bins allowed

DSS

PSF, 3170, Infoprint 2000

Type

Resettable, multi-valued

Allowed Values

PSF Infoprint sets this value from the values you supply for the output-bin-numbers actual destination attribute. If you add or delete a value from the **output-bin-numbers** attribute, Infoprint modifies this attribute to match your change.

3170 Infoprint sets this value to the names of the output bins on the InfoColor 70 printer device.

Infoprint 2000

top, stapler, stacker, bookletmaker

Default Values

PSF No default values

3170 main, test

Infoprint 2000

top, stapler

Usage Guidelines

- Infoprint compares the value of the output-bin document attribute to this attribute during job validation and scheduling.
- You can use this attribute to restrict the use of this actual destination.

output-data-user-exit

Specifies the name of a program that monitors output data from this actual destination. For example, the output data exit program can print a report at the end of a job listing the start and end time and the number of fonts, page segments, and overlays in the job so that you can track output device performance.

GUI Label

Output data exit

DSS

PSF, Email, Fax, Infoprint 2000

Type

Resettable, single-valued

Allowed Values

You can enter a text string of up to 255 characters.

Default Value

No default value

Usage Guidelines

You can use the sample output data exit program supplied:

- With Infoprint:
 - With AIX, /usr/lpp/psf/bin/ainuxout (source /usr/lpp/psf/exits/ainuxout.c)
 - With Windows NT or Windows 2000, \install_path\bin\ainuxout (source \install_path\usr\lpp\psf\exits\ainuxout.c), where install_path indicates the path where you installed Infoprint Manager
- Write your own

For more information on user-exit programs for Infoprint Manager, visit the appropriate site from the IBM Printing Systems web site: http://www.ibm.com/printers.

output-format-supported

Used with the **number-up-supported** attribute to identify the ways of imposing pages on a sheet that this actual destination supports.

GUI Label

Output formats allowed

DSS

PSF, Email, Fax, Infoprint 2000

Type

Resettable, multi-valued

Allowed Values

You can specify any of these fixed values:

side-by-side-copies simple-n-up booklet-print slit-and-merge

Note: You can only specify **simple-n-up** with the PSF DSS for Windows NT and Windows 2000.

Default Value

side-by-side-copies simple-n-up booklet-print slit-and-merge

Note: simple-n-up is the only default with the PSF DSS for Windows NT and Windows 2000.

Usage Guidelines

- See the document attribute output-format for explanations of the attribute values.
- Infoprint compares the document attribute output-format to this attribute for validation and scheduling.
- You can use this attribute to restrict use of this actual destination.

overlay

Specifies an overlay that Infoprint uses for each sheet-side for all jobs printed on this actual destination.

GUI Label

Medium overlay

DSS

PSF, Email, Fax, Infoprint 2000

Type

Resettable, single-valued

Allowed Values

You can enter a text string up to eight characters long that contains the name of the overlay.

Default Value

No default value

Usage Guidelines

- This attribute is valid for ASCII documents within a job only if it is not changed between documents in the job.
- When you specify **overlay, overlay-front**, and **overlay-back** on the command line, Infoprint honors all of them as long as the **form-definition** document attribute is **not** specified.

page-select-supported

Specifies the type of page numbering that this actual destination supports.

GUI Label

Range of pages allowed

DSS

PSF, Email, Fax, Infoprint 2000

Type

Resettable, multi-valued

Allowed Values

You can enter a fixed value of numeric.

Default Value

numeric

Usage Guidelines

Infoprint compares the document attribute page-select to this attribute for validation and scheduling.

pcl-server-address

Identifies the Internet Protocol address (IP Address parameter) of the host where the daemon that transforms PCL data imbedded in an AFP data file resides.

GUI Label

PCL server address

DSS

PSF, Email, Fax, Infoprint 2000

Type

Resettable, single-valued

Allowed Values

You can enter a text string up to 4095 characters long that is either of these types of address:

Dotted decimal address

A series of integers within the range of 0 to 255, each separated by a period, . (decimal address). For example:

9.99.12.85

Hostname

For example:

leo.boulder.ibm.com

Default Value

127.0.0.1 (the local host)

Usage Guidelines

This attribute is not used in transforming PCL data that is not imbedded in AFP data files.

pcl-server-port

Identifies the Port Number parameter of the host where the daemon that transforms PCL data imbedded in an AFP data file resides.

GUI Label

PCL server port

PSF, Email, Fax, Infoprint 2000

Type

Resettable, single-valued

Allowed Values

You can enter an integer from 1 through 2147483647, but you typically enter an integer from 5001 to 65535.

Default Value

8253

Usage Guidelines

This attribute is not used in transforming PCL data that is not imbedded in AFP data files.

physical-printer

See destination-name.

plex

Identifies the plexes that this printer prints. Plex indicates whether the page images of the output document are conditioned for eventual one-sided or two-sided printing, and the relative orientation of consecutive pages.

GUI Label

Plex to print

DSS

PSF, Infoprint 2000

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values: simplex tumble

Default Values

AIX simplex Infoprint 2000 simplex PSF simplex

Usage Guidelines

- The value of the **plex** attribute must be one of the values of the **plexes-supported** attribute.
- This attribute is valid for ASCII documents within a job only if it is not changed between documents in the job.
- · Infoprint uses plex specifications in this order:
 - The plex document attribute unless you specify different values for this attribute for each document in a job and also specify a value for the document form-definition attribute. In this case, Infoprint ignores the plex document attribute.
 - 2. The plex specification in the document or default document form definition.
 - 3. The **plex** actual destination attribute.

Note: Because all IBM-supplied form definitions contain a plex specification, the **plex** actual destination attribute is used only with custom form definitions that do not contain a plex specification.

plexes-supported

Identifies the plexes that this actual destination supports. Plex indicates whether the page images of the output document are conditioned for eventual one-sided or two-sided printing, and the relative orientation of consecutive pages.

GUI Label

Plexes allowed

DSS

AIX, BSD, PSF, 3170, Infoprint 2000

Type

Resettable, multi-valued

Allowed Values

You can enter any of these fixed values: simplex tumble

Default Values

AIX simplex

BSD No default value

PSF (basic Infoprint administrator's GUI)

If SNMP communication is active, Infoprint queries the printer device and sets the values according to the response; otherwise **simplex**, **tumble**.

PSF (advanced Infoprint administrator's GUI and command line)

If SNMP communication is active, Infoprint queries the printer device and sets the values according to the response; otherwise **simplex**.

3170 simplex, tumble

Usage Guidelines

- Infoprint compares the document attribute plex to this attribute for scheduling.
- If you specify a value for the **plexes-supported** attribute, you deactivate the default provided by SNMP.

postscript-server-address

Identifies the Internet Protocol address (IP Address parameter) of the host where the daemon that transforms PostScript data imbedded in an AFP data file resides.

GUI Label

PostScript server address

DSS

PSF, Email, Fax, Infoprint 2000

Type

Resettable, single-valued

Allowed Values

You can enter a text string up to 4095 characters long that is either of these types of address:

Dotted decimal address

A series of integers within the range of 0 to 255, each separated by a period, . (decimal address). For example: 9.99.12.85

Hostname

For example: leo.boulder.ibm.com

Default Value

127.0.0.1 (the local host)

Usage Guidelines

This attribute is not used in transforming PostScript data that is not imbedded in AFP data files.

postscript-server-port

Identifies the Port Number parameter of the host where the daemon that transforms PostScript data imbedded in an AFP data file resides.

GUI Label

PostScript server port

DSS

PSF, Email, Fax, Infoprint 2000

Type

Resettable, single-valued

Allowed Values

You can enter an integer from 1 through 2147483647, but you typically enter an integer from 5001 to 65535.

Default Value

8251

Usage Guidelines

This attribute is not used in transforming PostScript data that is not imbedded in AFP data files.

presentation-fidelity-problem-reported

Identifies the types of errors that cause this actual destination to stop printing when Infoprint detects them.

GUI Label

Presentation fidelity problem reported

DSS

PSF

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value	Explanation
barcode	Infoprint stops printing the file when it detects an error in bar code data in the Bar Code Object Content Architecture (BCOCA) data stream, or if the printer device does not support BCOCA.
image	Infoprint stops printing the file when it detects an error in image or graphics data in the Image Object Content Architecture (IOCA) or Graphics Object Content Architecture (GOCA) data streams, or if the printer device does not support IOCA or GOCA.
all	Infoprint stops printing the file if it detects either barcode or image data problems.
none	Infoprint prints the file without reporting barcode or image errors.

Default Value

none

presentation-object-container-extraction-mode

Specifies the degree of optimization attempted by transforms.

GUI Label

Presentation object container extraction mode

DSS

PSF

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

ignore All data is ripped.

inline Resources are identified and extracted for reuse within a document, and the resources are kept as part of the file.

Default Value

ignore

print-edge-marks

Specifies whether this actual destination prints edge marks on the output.

GUI Label

Print edge marks

DSS

PSF

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

false

print-qualities-supported

Identifies the levels of print quality available on this actual destination.

GUI Label

Print qualities allowed

DSS

AIX, BSD

Type

Resettable, multi-valued

Input Synonym

You can use the synonym qualities-supported.

Allowed Values

You can enter any of these fixed values:

draft high normal

Default Values

AIX normal

BSD No default value

Usage Guidelines

- Infoprint compares the document attribute print-quality to this attribute for validation and scheduling.
- You can use this attribute to restrict use of this actual destination.

print-queue

See print-queue-name.

print-queue-name

Specifies which AIX print queue is the default value for the destination-command attribute.

GUI Label

AIX print queue (AIX DSS) Windows print queue (Passthrough DSS)

DSS

PSF

Type

Initially settable, single-valued

Input Synonym

You can use the synonym **print-queue**.

Allowed Values

You can enter a text string up to 255 characters long that contains the name of the AIX print queue.

Default Value

No default value

Usage Guidelines

- Do not confuse this attribute with the associated-queue attribute, which specifies the Infoprint queue that sends jobs to this actual destination.
- If the attachment-type is aix, Infoprint uses this attribute to determine the default value following the **-P** flag in the **destination-command** attribute.
- If the attachment type is not aix, Infoprint does not use the print-queue-name attribute.

printer

See destination-name.

printer-command

See destination-command.

printer-data-stream

See destination-data-stream.

printer-end-sheet

Identifies the style of end sheet that the printer device uses.

GUI Label

End sheet

DSS

AIX, PSF

Type

Resettable, single-valued

Allowed Values

You can enter one of the following fixed values. For PSF only, you can enter an identifier of an auxiliary-sheet object.

Fixed Value	DSS	Explanation
accounting-log	PSF	This value is technically valid, but should not be used for end sheets.
blank	PSF	The end sheet is blank.
brief	AIX, PSF	The end sheet style is brief.
full	AIX, PSF	The end sheet style is full.
job-ticket	PSF	The job ticket is printed on the end sheet.
none	AIX, PSF	No end sheet prints.

Default Value

AIX full **PSF** none

Usage Guidelines

- · PSF actual destinations can use auxiliary-sheet objects if they have valid psf-exit-xxx values. AIX actual destinations print auxiliary sheets, but they do not use auxiliary-sheet objects.
- Infoprint verifies that the value of this attribute is a value of the end-sheets-supported attribute.

printer-escape-codes

Specifies the printer escape codes that this actual destination uses to print line-data jobs.

GUI Label

Escape codes

DSS

PSF

Type

Resettable, single-valued

Allowed Values

You can enter a string up to 255 characters long containing the printer escape codes.

Syntax

Escape codes must be in lowercase format and cannot include spaces. You must enter unprintable characters, and may enter printable characters, in this format:

\xnn

where *nn* is a two-character (one-byte) hexadecimal code. For example:

represents ESC

Default Value

No default value

Usage Guidelines

Use printer escape codes to control fonts, line spacing, and the size of the output page, enabling more than 80 characters to print on a line.

For example, this hex string:

\x1b\x5b\x53\x0c\x00\x01\x20\x01\x20\x00\x00\x4b\x60\x38\x40\x4e\xc0

translates to the following values:

1b ESC

5b Left square bracket

53 S

0c00 Length of command

0120 Top margin (0.2 inches)

0120 Bottom margin (0.2 inches)

0000 Left margin (0 inches)

4b60 Right margin (13.4 inches)

3840 Page length (10 inches)

4ec0 Page width (14 inches)

The first four values (ESC, [, S, command length) are always the same in a string of escape codes specifying page dimensions. The values representing the margins and page length and width are hex values in 1440ths of an inch and can be changed to meet your specifications. All dimensions are measured as if the page were printed in portrait.

printer-memory

Defines the amount of printer memory (in kilobytes) for this PSF command-attached or other-driver attached printer.

GUI Label

Memory (KBytes)

DSS

PSF

Type

Resettable, single-valued

Allowed Values

You can enter an integer from 512 to 65535. The unit is kilobytes.

Default Value

Other-driver attached actual destinations

1024

Command-attached actual destinations

1024

Other-driver attached types

No default value

Usage Guidelines

- Infoprint uses this attribute with PSF command-attached actual destinations and other-driver attached actual destinations and ignores it for other attachment types.
- If the printer device reports an out-of-memory condition, you can add more memory to the printer device or decrease the value for this attribute.

printer-locations

See destination-location.

printer-model

See destination-model.

printer-name

See destination-name.

printer-needs-attention-time

See destination-needs-attention-time.

printer-needs-key-operator-attention-time

See destination-needs-key-operator-attention-time.

printer-pass-through

See destination-pass-through.

printer-realization

See destination-realization.

printer-register-threshold

See destination-register-threshold.

printer-release-timer

See destination-release-timer.

printer-resolutions-ready

Specifies which of the values specified for the printer-resolutions-supported attribute this actual destination is ready to use.

GUI Label

Resolutions ready

DSS

PSF, 3170

Type

Resettable, multi-valued

Allowed Values

You can enter any of these fixed values:

Fixed Value	DSS
240	PSF
300	PSF
480	PSF
600	PSF, 3170

The unit is pels.

Default Values

No default values

Usage Guidelines

- This attribute applies only for printing image data. It has no effect on font resolutions.
- Refer to the printer device documentation for information on the resolution you should specify.
- If you specify a resolution that the printer device does not support, jobs will still print under most conditions. However, you may see poor printed results.
- The values of the **printer-resolutions-ready** attribute must be a subset of the values of the **printer-resolutions-supported** attribute.
- Infoprint compares the document attribute **default-printer-resolution** to this attribute for scheduling.

printer-resolutions-supported

Specifies the resolution, in pels, at which the printer device can print PostScript and PCL jobs.

GUI Label

Resolutions allowed

DSS

PSF, 3170, Infoprint 2000

Type

Resettable, multi-valued

Allowed Values

You can enter any of these fixed values:

Fixed Value	DSS
240	PSF
300	PSF
480	PSF

600 PSF, 3170, Infoprint 2000

The unit is pels.

Default Values

PSF (basic Infoprint administrator's GUI)

240, 300, 480, 600

PSF (advanced Infoprint administrator's GUI and command line)

3170, Infoprint 2000

600

Usage Guidelines

- This attribute applies only for printing image data. It has no effect on font resolutions.
- · Refer to the printer device documentation for information on the resolution you should specify.
- If you specify a resolution that the printer device does not support, jobs will still print under most conditions. However, you may see poor printed results.
- Infoprint compares the document attribute default-printer-resolution to this attribute for validation and scheduling.
- You can use this attribute to restrict use of this actual destination.

printer-separator-sheet

Identifies the style of separator sheet that the printer device uses.

GUI Label

Slip/Separator sheet

DSS

AIX, PSF

Type

Resettable, single-valued

Allowed Values

You can enter one of the following fixed values. For PSF only, you can enter an identifier of an auxiliary-sheet object.

Fixed Value accounting-log	<i>DSS</i> PSF	Explanation This value is technically valid, but should not be used for separator sheets.
blank	PSF	The separator sheet is blank.
brief	PSF	The separator sheet style is brief.
full	PSF	The separator sheet style is full.
job-ticket	PSF	The job ticket is printed on the separator sheet.
none	AIX, PSF	No separator sheet prints.

Default Value

AIX none **PSF** none

Usage Guidelines

· PSF actual destinations can use auxiliary-sheet objects if they have valid psf-exit-xxx values. AIX actual destinations print start and end sheets, but they do not use auxiliary-sheet objects.

- Because AIX actual destinations do not print separator sheets, the only valid value for them is **none**.
- Infoprint verifies that the value of this attribute is a value of the **separator-sheets-supported** attribute.

printer-start-sheet

Identifies the type of start sheet that this printer device uses.

GUI Label

Start sheet

DSS

AIX, PSF, 3170, IPP, Passthrough

Type

Resettable, single-valued

Allowed Values

You can enter one of the following fixed values. For PSF only, you can enter an identifier of an auxiliary-sheet object.

Fixed Value	DSS	Explanation
accounting-log	PSF	This value is technically valid, but should not be used for start sheets.
blank	PSF	The start sheet is blank.
brief	AIX, PSF, IPP,	The start sheet style is brief.
	Passthrough	
full	AIX, PSF, 3170, IPP,	The start sheet style is full.
	Passthrough	
job-ticket	PSF	The job ticket is printed on the start sheet.
none	AIX, PSF, 3170, IPP,	No start sheet prints.
	Passthrough	•
filename	IPP, Passthrough	The location of a customized auxiliary sheet template.

Default Value

AIX, 3170, IPP, Passthrough

full

PSF (basic Infoprint administrator's GUI)

job-ticket

PSF (advanced Infoprint administrator's GUI and command line) brief

Usage Guidelines

- PSF actual destinations can use auxiliary-sheet objects if they have valid **psf-exit-***xxx* values. AIX actual destinations print start and end sheets, and 3170 actual destinations print start sheets; but they do not use auxiliary-sheet objects.
- Infoprint verifies that the value of this attribute is a value of the **start-sheets-supported** attribute.
- For IPP and Passthrough printers, the auxiliary sheets specified with *filename* can be customized by copying and modifying one of the following template files shipped with Infoprint Manager for Windows NT and Windows 2000:

\install-path\bin\brief.ps

Template for "brief" format, Postscript output format

\install-path\bin\full.ps

Template for "full" format, Postscript output format

\install-path\bin\brief.txt

Template for "brief" format, PCL/ASCII output format

\install-path\bin\full.txt

Template for "full" format, PCL/ASCII output format

The template files contain special *insert formatting* characters that are used to indicate where the Passthrough DSS inserts certain information about the print job:

%B Large *banner style* job-owner/job-original/user-name (whichever is found first)

%t, %T

job-name heading, job-name contents

%p, %P

time printed heading, time printed contents

%q, %Q

job-submission-time heading, job-submission-time contents

%h, %H

actual-destination and server heading, actual-destination and server contents

%s, %S

job-owner/job-original/user-name heading, job-owner/job-originator/user-name contents

%d, %D

results-profile delivery-address, %s heading, results-profile delivery-address, or %S contents

%c, %C

job-comment heading, job-comment contents

printer-state

See destination-state.

printer-s370-channel-device-address

Identifies the control unit address parameter for channel-attached actual destinations. This is the device address of the control unit for the printer device.

GUI Label

S/370 channel address

DSS

PSF

Type

Resettable, single-valued

Allowed Values

You can enter a hexadecimal address expressed as a series of characters in the range: integer (0..9), alpha (a..f, A..F); legal values are 00–FF.

Default Value

No default value

Usage Guidelines

You must enter a value for PSF channel-attached actual destinations. Infoprint ignores this attribute for other attachment types.

printer-s370-channel-slot-number

Identifies the slot number parameter for channel-attached actual destinations. This is the slot number in which the S/390 Parallel Channel Emulator is installed.

GUI Label

S/370 slot number

DSS

PSF

Type

Resettable, single-valued

Allowed Values

You can enter an integer from 1 through 8.

Default Value

No default value

Usage Guidelines

- You must enter a value for PSF channel-attached actual destinations. Infoprint ignores this attribute for other attachment types.
- If a single IBM 4159 Model 001 Channel Card is installed in the computer, specify 1 for the slot address. If multiple channel cards are installed in the computer, see the 4159 procedures in the *Infoprint Manager for Windows NT and Windows 2000: Getting Started*.

printer-tcpip-internet-address

See destination-tcpip-internet-address.

printer-tcpip-port-number

See destination-tcpip-port-number.

printer-timeout-period

See destination-timeout-period.

problem-message

Provides information on the cause of a problem with a actual destination.

GUI Label

Problem message

DSS

All

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value to a text string that contains the message information.

Default Value

No default value

Usage Guidelines

- This attribute may contain problem information whenever the actual destination state is not idle, connecting-to-printer, or printing.
- If the actual destination state is **needs-key-operator**, Infoprint disables the actual destination. If the actual destination uses SNMP, Infoprint automatically re-enables it when the problem is corrected. To prevent automatic re-enabling, manually disable the actual destination.

protected-attributes

Specifies one or more actual destination attributes that DCE prevents Infoprint operators from setting or changing.

GUI Label

Protected attributes

DSS

All

Type

Resettable, multi-valued

Allowed Values

You can enter one or more actual destination attributes.

Default Values

This attribute always specifies itself, **protected-attributes**, as a value.

Usage Guidelines

With DCE security

Normally, anyone with DCE write permission for actual destinations can set values for actual destination attributes. By default, the pd_admin and pd_operator DCE groups both have write permission. Once you define an actual destination attribute as a protected attribute, you must have DCE **delete** permission to modify the attribute. Members of the **pd_operator** DCE group do not have **delete** permission unless the DCE administrator modifies the default permissions for that group.

With Non-DCE security

Normally, anyone with write permission for actual destinations can set values for actual destination attributes. By default, the admin and oper groups both have write permission. Once you define an actual destination attribute as a protected attribute, you must have actual-destination delete permission to modify the attribute. Members of the oper group do not have actual-destination delete permission unless the administrator modifies the default permissions for that group.

psf-tray-characteristics

Defines the current characteristics of the input trays on this output device.

GUI Label

Media ready

DSS

PSF, Infoprint 2000

Type

Resettable, multi-valued, complex

Syntax

input-tray:medium-loaded:job-bin-number:tray-number:duplex-supported

Separate values with colons, for example:

top:letter:1:1:false

Components

input-tray: Specifies which input tray this value defines.

GUI Label: Input tray

Type: Single-valued

Allowed Values: You can enter any name you want, for example:

alternate bottom envelope insert

Note: The **insert** input tray is on the finisher, not the printer device itself. This means that you cannot print inserts with the rest of the job. If you want printed inserts, preprint them and load the printed sheets into the insert input tray.

large-capacity main manual side top

Default Value: The default value for PSF command-attached and other-driver attached actual destinations is top. For other actual destinations, there is no default value.

media-loaded: Specifies the medium that is now in the input tray. Infoprint adds the value you specify for this component automatically to the media-ready actual destination attribute.

GUI Label: Media ready

Type: Single-valued

Allowed Values: The value you specify does not have to match one of the values specified by the medium-identifier medium attributes. However, it must be one of the values specified by the media-supported attribute for this actual destination.

Default Value: The default value for PSF command-attached and other-driver attached actual destinations is letter. For other actual destinations, there is no default value.

Usage Guidelines: If you want to change the value of this component, make sure you add the value to the **media-supported** attribute first.

job-bin-number: Specifies a bin number that the data stream can specify to select this input tray.

GUI Label: Bin number

Type: Single-valued

Allowed Values: You can enter an integer from 1 to 255.

Default Value: If SNMP communication is active, Infoprint queries the printer device and sets the values according to the response; otherwise:

- The default value for PSF command-attached and other-driver attached actual destinations is 1. For other actual destinations, there is no default value.
- If you specify any of the values for the **input-tray** name shown in Table 12, and no values for this component and the **tray-number** component, the values for both of these components default to the values shown in the explanation of this component. You can specify values for all three components if those values are not appropriate for a particular printer device.

Usage Guidelines: Each AFP printer device model has its own configuration of paper input trays, known as bins, each with a specific number. This component maps the value specified for the input tray and loaded media to a bin number that Infoprint understands and uses. Some values have special meanings:

Table 12. Input Tray Names, Job Bin Numbers, and Tray Numbers on AFP Printer Devices

Input Tray Name	Job Bin Number	Tray Number
alternate	1	5
bottom	2	4
envelope	65	6
manual	100	2
top	1	1

tray-number: Identifies the tray number of the input tray, depending on the printer model, associated with the job bin number.

GUI Label: Tray number

Type: Single-valued

Allowed Values: You can enter an integer value of 1 or 2.

Default Value: The default value for PSF command-attached and other-driver attached actual destinations is 1. This component does not apply to other attachment types.

For command-attached actual destinations and other-driver attached actual destinations, if you specify any of the values for the **input-tray** name shown in the table under **job-bin-number** and no value for this component, the value for this component defaults to the value shown in the explanation of the **job-bin-number** component.

Usage Guidelines: See the documentation for the printer device for further information on which types of input trays this printer supports.

duplex-supported: Specifies whether two-sided printing is possible from this input tray.

GUI Label: Duplex

Type: Single-valued

Allowed Values: You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value: The default value for PSF command-attached and other-driver attached actual destinations is **false**. This component does not apply to other attachment types.

Default Values

If SNMP communication is active, Infoprint queries the printer device and sets the values according to the response; otherwise, the default values are as described for each component.

Usage Guidelines

- With PSF command-attached or PSF other-driver attached printers, you can specify a maximum of 15 values, one for each input tray of the printer device.
- With PSF TCP/IP attached printers, there is no limit on the number of values you can specify for **psf-tray-characteristics**.
- Infoprint automatically sets the **media-ready** and **input-trays-supported** actual destination attributes from the value you set here.
- Infoprint verifies that the values of the **media-loaded** component of this attribute are values of the **media-supported** attribute.

public-context-presentation-object-container

Identifies which presentation object containers (or called data object resources in the IPDS Reference) are public. Any uniquely identified resource found in a directory that is listed in this directory path is a candidate for reuse across jobs.

GUI Label

Public presentation object containers

DSS

PSF

Type

Resettable, single-valued

Allowed Values

You can enter the name of a public-context-presentation object or a text string up to 255 characters long that defines the directory path to the public-context-presentation object. You can specify one or more paths for one public context. You can specify paths for file systems mounted to AIX, such as MVS data sets and VM minidisks.

Syntax

path:path for AIX path;path for Windows NT or Windows 2000

Separate path names with colons on AIX, for example:

/dor:/dept123/presentation-object-container

Separate path names with semicolons on Windows NT or Windows 2000, for example:

d:\dor;d:\dept123\presentation-object-container

Default Value

With AIX, no default values.

With Windows NT or Windows 2000, no default values.

qualities-supported

See print-qualities-supported.

register-threshold

See destination-register-threshold.

registered-with-spooler

Indicates whether this actual destination and the server containing the actual destination's queue have established communication.

GUI Label

Registered with spooler

DSS

All

Type

Non-settable, single-valued

Allowed Values

Infoprint sets one of these fixed values:

true

false

Default Value

false

remote-queue

Indicates whether the backend program sends data to a remote print queue rather than controlling this AIX actual destination directly.

GUI Label

Use remote print queue

AIX, PSF (AIX only with other-driver attachment type)

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

false

Usage Guidelines

- If the printer backend program is a variation of, or front end to, rembak, specify true. Examples of rembak-based backend programs include piorflb and piocolor.
- When you are working with AIX DSS actual destinations, see "Creating and Managing Actual Destinations" in the *Infoprint Manager for AIX: Administrator's Guide* for information on correcting the configuration of **remote-queue** printers that have **device-name** set to /dev/null.

resource-context

Defines the default directory paths that Infoprint searches for AFP resources, including fonts, form definitions, overlays, page definitions, page segments, and color mapping table.

GUI Label

Location of resources

DSS

PSF, Email, Fax, Infoprint 2000

Type

Resettable, single-valued

Allowed Values

You can enter the name of a resource-context object or a text string up to 255 characters long that defines the directory path to fonts. You can specify one or more paths for one resource context. You can specify paths for file systems mounted to AIX, such as MVS data sets and VM minidisks.

Syntax

```
path:path for AIX path;path for Windows NT or Windows 2000
```

Separate multiple paths with a colon on AIX or a semicolon on Windows NT or Windows 2000, for example:

• In AIX,

/fonts:/dept123/fonts

 In Windows NT or Windows 2000, d:\fontlib;d:\dept123\fonts

Default Value

With AIX, no default values, but Infoprint always searches:

- 1. /usr/lpp/psf/reslib
- 2. /usr/lpp/afpfonts
- 3. /usr/lpp/psf/fontlib

With Windows NT or Windows 2000, no default values, but Infoprint always searches:

1. \install_path\reslib

- 2. \install_path\afpfonts
- 3. \install_path\fontlib

Usage Guidelines

- You can use this attribute to locate default resources or color mapping tables.
- Infoprint searches resource paths in this order:
 - 1. resource-context-user document attribute
 - 2. resource-context-font, resource-context-form-definition, resource-context-overlay, resource-context-page-definition, or resource-context-page-segment document attribute, as appropriate for the type of resource.
 - 3. **resource-context** document attribute
 - 4. PSFPATH environment variable
 - 5. resource-context-font, resource-context-form-definition, resource-context-overlay, resource-context-page-definition, or resource-context-page-segment actual destination attribute, as appropriate for the type of resource
 - 6. resource--context actual destination attribute
 - 7. With AIX:
 - a. /usr/lpp/psf/reslib
 - b. /usr/lpp/afpfonts
 - c. /usr/lpp/psf/fontlib
 - 8. With Windows NT or Windows 2000, where install path indicates the path where you installed Infoprint Manager:
 - a. \install_path\reslib
 - b. \install_path\afpfonts
 - c. \install_path\fontlib

If Infoprint cannot find the resource because none of the paths contain the resource, it still processes the job and prints error messages at the end of the job. Infoprint reports the job as completed.

resource-context-font

Defines the directory paths that Infoprint searches for fonts for the job.

GUI Label

Location of fonts

PSF, Email, Fax, Infoprint 2000

Type

Resettable, single-valued

Allowed Values

You can enter the name of a resource-context object or a text string up to 255 characters long that defines the directory path to the AFP resources. You can specify one or more paths for one resource context.

Syntax 1 4 1

path:path for AIX path;path for Windows NT or Windows 2000

Separate multiple paths with a colon on AIX or a semicolon on Windows NT or Windows 2000.

Default Value

With AIX, no default values, but Infoprint always searches /usr/lpp/psf/reslib.

With Windows NT or Windows 2000, no default values, but Infoprint always searches \install_path\reslib.

Usage Guidelines

You can use this attribute to locate default resources or color mapping tables.

Infoprint searches resource paths in this order:

- 1. resource-context-user document attribute
- 2. resource-context-font, resource-context-form-definition, resource-contextoverlay, resource-context-page-definition, or resource-context-page-segment document attribute, as appropriate for the type of resource
- 3. resource-context document attribute
- 4. PSFPATH environment variable
- 5. resource-context-font, resource-context-form-definition, resource-contextoverlay, resource-context-page-definition, or resource-context-page-segment actual destination attribute, as appropriate for the type of resource
- 6. resource-context actual destination attribute
- 7. With AIX:
 - a. /usr/lpp/psf/reslib
 - b. /usr/lpp/afpfonts for fonts
 - c. /usr/lpp/psf/fontlib for fonts
- 8. With Windows NT or Windows 2000:
 - a. \install_path\reslib
 - b. \install_path\afpfonts for fonts
 - c. \install_path\fontlib for fonts

If Infoprint cannot find the resource because none of the paths contain the resource, it still processes the job and prints error messages at the end of the job. Infoprint reports the job as completed.

resource-context-form-definition

Defines the directory paths that Infoprint searches for the form definition for the job.

GUI Label

Location of form definitions

DSS

PSF, Email, Fax, Infoprint 2000

Type

Resettable, single-valued

Allowed Values

You can enter the name of a resource-context object or a text string up to 255 characters long that defines the directory path to form definitions. You can specify one or more paths for one resource context. In AIX, you can specify paths for file systems mounted to AIX, such as MVS data sets and VM minidisks.

Syntax

path:path for AIX path;path for Windows NT or Windows 2000

Separate path names with colons on AIX and semicolons on Windows NT or Windows 2000, for example:

• For AIX:

/formdef:/dept123/form

 For Windows NT or Windows 2000: \reslib\formdef;d:\dept123\form

Default Value

With AIX, no default values, but Infoprint always searches /usr/lpp/psf/reslib.

With Windows NT or Windows 2000, no default values, but Infoprint always searches \install_path\reslib.

Usage Guidelines

- You can use either the document or the actual destination form-definition attribute to specify the form definition.
- Infoprint searches paths in this order:
 - 1. resource-context-user document attribute
 - 2. resource-context-form-definition document attribute
 - 3. **resource-context** document attribute
 - 4. **PSFPATH** environment variable
 - 5. resource-context-form-definition actual destination attribute
 - 6. With AIX, /usr/lpp/psf/reslib
 - 7. With Windows NT or Windows 2000, \install_path\reslib
- If Infoprint cannot find the resource because none of the paths contain the resource, it still processes the job and prints error messages at the end of the job. Infoprint reports the job as completed.

resource-context-overlay

Defines the directory paths that Infoprint searches for an overlay for the job.

GUI Label

Location of overlays

DSS

PSF, Email, Fax, Infoprint 2000

Type

Resettable, single-valued

Allowed Values

You can enter the name of a resource-context object or a text string up to 255 characters long that defines the directory path to overlays. You can specify one or more paths for one resource context. You can specify paths for file systems mounted to AIX, such as MVS data sets and VM minidisks.

Syntax

path:path for AIX path;path for Windows NT or Windows 2000

Separate path names with colons on AIX, for example:

/overlay:/dept123/overlay

Separate path names with semicolons on Windows NT or Windows 2000, for example:

\overlay;d:\dept123\overlay

Default Value

With AIX, no default values, but Infoprint always searches /usr/lpp/psf/reslib.

With Windows NT or Windows 2000, no default values, but Infoprint always searches \install_path\reslib.

Usage Guidelines

- You use a form definition for the job to specify the overlay.
- Infoprint searches paths in this order:
 - 1. resource-context-user document attribute
 - 2. resource-context-overlay document attribute
 - 3. resource-context document attribute
 - 4. **PSFPATH** environment variable
 - 5. resource-context-overlay actual destination attribute
 - 6. With AIX, /usr/lpp/psf/reslib
 - 7. With Windows NT or Windows 2000, \install_path\reslib
- If Infoprint cannot find the resource because none of the paths contain the
 resource, it still processes the job and prints an error messages at the end of the
 job. Infoprint reports the job as completed.

resource-context-page-definition

Defines the directory paths that Infoprint searches for a page definition for the job.

GUI Label

Location of page definitions

DSS

PSF, Email, Fax, Infoprint 2000

Type

Resettable, single-valued

Allowed Values

You can enter the name of a resource-context object or a text string up to 255 characters long that defines the directory path to page definitions. You can specify one or more paths for one resource context. You can specify paths for file systems mounted to AIX, such as MVS data sets and VM minidisks.

Syntax

path:path for AIX path;path Windows NT or Windows 2000

Separate path names with colons on AIX, for example:

/pagedef:/dept123/page-definition

Separate path names with semicolons on Windows NT or Windows 2000, for example:

\pagedef;d:\dept123\page-definition

Default Value

With AIX, no default values, but Infoprint always searches /usr/lpp/psf/reslib.

With Windows NT or Windows 2000, no default values, but Infoprint always searches \install_path\reslib.

Usage Guidelines

- You use the **page-definition** document attribute to specify the page definition for the job.
- Infoprint searches paths in this order:
 - 1. **resource-context-user** document attribute
 - 2. resource-context-page-definition document attribute
 - 3. resource-context document attribute
 - 4. **PSFPATH** environment variable
 - 5. resource-context-page-definition actual destination attribute
 - 6. With AIX, /usr/lpp/psf/reslib
 - 7. With Windows NT or Windows 2000, \install_path\reslib
- If Infoprint cannot find the resource because none of the paths contain the resource, it still processes the job and prints error messages at the end of the job. Infoprint reports the job as completed.

resource-context-page-segment

Defines the directory paths that Infoprint searches for page segments for the job.

GUI Label

Location of page segments

DSS

PSF, Email, Fax, Infoprint 2000

Type

Resettable, single-valued

Allowed Values

You can enter the name of a resource-context object or a text string up to 255 characters long that defines the directory path to page segments. You can specify one or more paths for one resource context. You can specify paths for file systems mounted to AIX, such as MVS data sets and VM minidisks.

Syntax

path:path for AIX path;path for Windows NT or Windows 2000

Separate path names with colons on AIX, for example:

/pageseg:/dept123/page-segment

Separate path names with semicolons on Windows NT or Windows 2000, for example:

d:\pageseg;d:\dept123\page-segment

Default Value

With AIX, no default values, but Infoprint always searches /usr/lpp/psf/reslib.

With Windows NT or Windows 2000, no default values, but Infoprint always searches \install_path\reslib.

Usage Guidelines

- Page segments are identified within the document. If the document refers to a page segment that resides external to the document, its location must be specified in at least one of the components of the search path as described below.
- Infoprint searches paths in this order:
 - 1. resource-context-user document attribute
 - 2. resource-context-page-segment document attribute
 - 3. resource-context document attribute
 - 4. **PSFPATH** environment variable
 - 5. **resource-context-page-segment** actual destination attribute
 - 6. For AIX, /usr/lpp/psf/reslib
 - 7. For Windows NT or Windows 2000, \install_path\reslib
- If Infoprint cannot find the resource because none of the paths contain the resource, it still processes the job and prints error messages at the end of the job. Infoprint reports the job as completed.

resource-context-presentation-object-container

Adds to the directory paths that Infoprint searches for presentation object containers (or called data object resources in the IPDS Reference), such as EPS, IOCA images, or PDF pages, for the actual destination.

GUI Label

Location of presentation object containers

DSS

PSF

Type

Resettable, single-valued

Allowed Values

You can enter the name of a resource-context-presentation object or a text string up to 255 characters long that defines the directory path to the resource-contextpresentation object. You can specify one or more paths for one resource context. You can specify paths for file systems mounted to AIX, such as MVS data sets and VM minidisks.

Syntax

path:path for AIX path;path for Windows NT or Windows 2000

Separate path names with colons on AIX, for example:

/dor:/dept123/presentation-object-container

Separate path names with semicolons on Windows NT or Windows 2000, for example:

d:\dor;d:\dept123\presentation-object-container

Default Value

With AIX, no default values, but Infoprint always searches /usr/lpp/psf/reslib.

With Windows NT or Windows 2000, no default values, but Infoprint always searches \install_path\reslib.

Usage Guidelines

- Presentation objects are identified within the document. If the document refers to an object that resides external to the document, its location must be specified in at least one of the components of the search path as described below.
- Infoprint searches paths in this order:
 - 1. resource-context-user document attribute
 - 2. resource-context-presentation-object-container document attribute
 - 3. resource-context document attribute
 - 4. **PSFPATH** environment variable
 - 5. resource-context-presentation-object-container actual destination attribute
 - 6. For AIX, /usr/lpp/psf/reslib
 - 7. For Windows NT or Windows 2000, \install_path\reslib
- If Infoprint cannot find the resource because none of the paths contain the resource, it still processes the job and prints error messages at the end of the job. Infoprint reports the job as completed.

reuse-inline-presentation-object-container

Specifies whether uniquely identified resources discovered inline are candidates for reuse across jobs. For printers that support the capture of presentation-object containers, resources can be reused across invocations of PSF or in shared environments with PSF/MVS.

GUI Label

Reuse inline presentation object containers

DSS

PSF

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

false

reverse-output

Indicates whether this actual destination should print jobs in reverse (last page first).

GUI Label

Print last page first

DSS

3170

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

false

Usage Guidelines

If you specify true, you may also wish to specify true for the document attribute output-face-up so that pages will be collated in the right order.

rip-ini-file

Identifies the default .ini file for this actual destination. This file contains default page setup values used to RIP files.

GUI Label

RIP ini file

DSS

3170

Type

Resettable, single-valued

Allowed Values

You can enter a text string up to 255 characters long that contains the full path name of the file.

Default Value

/usr/lpp/pd/bin/default.ini

rip-server

See color-rip-servers.

scanner-corrections-supported

Identifies the scanner calibration methods for which this actual destination supports correction.

GUI Label

Scanner corrections allowed

DSS

PSF (AIX Only)

Resettable, multi-valued

Allowed Values

You can enter any of these fixed values:

Ricoh420

XeroxDocuimage620S

none

Default Values

Ricoh420, XeroxDocuimage620S, none

Usage Guidelines

Infoprint compares the document attribute scanner-correction to this attribute for validation and scheduling.

scheduler-sort-primary-order

Identifies which of the schedulers specified by the schedulers-supported attribute Infoprint uses to determine how to schedule jobs.

GUI Label

Primary scheduler

DSS

All

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value

Explanation

deadline

Infoprint schedules jobs with the earliest deadline first.

fifo Infoprint schedules jobs in the order they are submitted.

job-priority

Infoprint schedules jobs in order of priority.

longest-job-first

Infoprint schedules jobs in order of size, longest first.

shortest-job-first

Infoprint schedules jobs in order of size, shortest first.

Default Value

job-priority

scheduler-sort-secondary-order

Identifies which of the schedulers specified by the schedulers-supported attribute Infoprint uses to determine how to break ties produced by the scheduler specified by the scheduler-sort-primary-order attribute. For example, if you normally schedule jobs by priority, you can specify that when two jobs have the same priority, Infoprint should schedule the shorter one first.

GUI Label

Secondary scheduler

DSS

All

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value

Definition

deadline

Infoprint schedules jobs with the earliest deadline first.

fifo Infoprint schedules jobs in the order they are submitted. **job-priority**

Infoprint schedules jobs in order of priority.

longest-job-first

Infoprint schedules jobs in order of size, longest first.

shortest-job-first

Infoprint schedules jobs in order of size, shortest first.

Default Value

fifo

schedulers-supported

Identifies the scheduling algorithms that this actual destination supports.

GUI Label

Schedulers allowed

DSS

All

Type

Non-settable, multi-valued

Allowed Values

Infoprint sets this value to these fixed values:

Fixed Value

Definition

deadline

Infoprint schedules jobs with the earliest deadline first.

fifo Infoprint schedules jobs in the order they are submitted.

job-priority

Infoprint schedules jobs in order of priority.

longest-job-first

Infoprint schedules jobs in order of size, longest first.

shortest-job-first

Infoprint schedules jobs in order of size, shortest first.

Default Values

deadline, fifo, job-priority, longest-job-first, shortest-job-first

screen-frequencies-supported

Use the **halftones-supported** attribute to specify the **screen-frequencies-supported** attribute values. (See "halftones-supported" on page 384 for more information.) The **screen-frequencies-supported** attribute is supported to maintain downward compatibility, but it is not the recommended attribute for specifying screen frequencies for printing halftones.

Identifies the screen frequencies used for printing halftones that this actual destination supports.

DSS

PSF (AIX Only)

Type

Resettable, multi-valued

Allowed Values

You can enter any of these fixed values:

85

106

141

Default Values

71, 85, 106, 141

Usage Guidelines

Infoprint compares the document attribute screen-frequency to this attribute for validation and scheduling.

separator-sheets-supported

Identifies the separator sheets that this actual destination supports.

GUI Label

Slip/Separator sheets allowed

DSS

AIX, PSF

Type

Resettable, multi-valued

Allowed Values

You can enter any of the following fixed values. For PSF only, you can enter a string up to 255 characters long that contains identifiers of auxiliary-sheet objects.

Fixed Value	DSS	Explanation
accounting-log	PSF	This value is technically valid, but should not be used for separator sheets.
blank	PSF	The separator sheet is blank.
brief	PSF	The separator sheet style is brief.
full	PSF	The separator sheet style is full.
job-ticket	PSF	The job ticket is printed on the separator sheet.
none	AIX, PSF	No separator sheet prints.

Default Values

AIX

PSF accounting-log, blank, brief, full, job-ticket, none, and the names of other defined auxiliary sheets which have legal PSF auxiliary sheet attributes.

Usage Guidelines

- PSF actual destinations can use auxiliary-sheet objects if they have valid psf-exit-xxx values. AIX actual destinations print start and end sheets, but they do not use auxiliary-sheet objects.
- · Because AIX actual destinations do not print separator sheets, the only valid value for them is **none**.
- Infoprint verifies that the value of the **printer-separator-sheet** attribute is a value of this attribute.

- You cannot delete a value from this attribute if the value you want to delete is the value of the **printer-separator-sheet** attribute.
- For PSF actual destinations, Infoprint sets this value dynamically to the names of all defined auxiliary sheets with legal attributes. You should never have to reset this value.

shared-printer-name

Specifies the names of the Infoprint gateway shared printer, if any, that forwards jobs to this destination.

GUI Label

Shared gateway printer

DSS

All with NT/2000 servers

Type

Resettable, single-valued

Allowed Values

Text name of a gateway shared printer.

Default Values

Derived from the actual destination name if the server's **auto-create-shared-printers** attribute is **true**; otherwise, no default.

Usage Guidelines

The **shared-printer-name** is automatically set by IBM when the gateway printers are automatically created.

sides

Indicates whether the printer device prints on one or two sides of the media.

GUI Label

Sides to print

DSS

PSF, Infoprint 2000, Passthrough

Type

Resettable, single-valued

Allowed Values

You can enter an integer value of 1 or 2.

Default Values

If SNMP communication is active, Infoprint queries the printer device and sets the values according to the response; otherwise:

PSF

Infoprint 2000

2

Passthrough

1

Usage Guidelines

• The value of the **sides** attribute must be one of the values of the **sides-supported** attribute.

- This attribute is valid for ASCII documents within a job only if it is not changed between documents in the job.
- Infoprint uses sides specifications in this order:
 - The sides document attribute unless you specify different values for this attribute for each document in a job and also specify a value for the form-definition document attribute. In that case, Infoprint ignores the sides document attribute.
 - 2. The sides specification in the document or default document form definition.
 - 3. The sides specification in the actual destination form definition.
 - 4. The **sides** actual destination attribute.

Note: Because all IBM-supplied form definitions contain a sides specification, the **sides** actual destination attribute is used only with custom form definitions that do not contain a sides specification.

sides-supported

Indicates whether this actual destination supports printing on one or two sides of the media.

GUI Label

Sides allowed

DSS

AIX, BSD, PSF, 3170, Infoprint 2000, Passthrough

Type

Resettable, multi-valued

Allowed Values

You can enter an integer of 1 or 2.

Default Values

With AIX, PSF, and BSD, if SNMP communication is active, Infoprint queries the printer device and sets the values according to the response; otherwise, the default follows:

AIX 1

BSD No default value

PSF (basic Infoprint administrator's GUI)

1, 2

PSF (advanced Infoprint administrator's GUI and command line)

1

3170 2

Passthrough

1

Usage Guidelines

- You can use this attribute to restrict jobs sent to this actual destination according to the capacity of the output device or your policy for output device use.
- Infoprint compares the document attribute **sides** to this attribute for scheduling.
- If you specify a value for the **sides-supported** attribute, you deactivate the default that SMNP provides.

snmp-active

Indicates whether Infoprint has established Simple Network Management Protocol (SNMP) communications with the output device that this actual destination represents.

GUI Label

SNMP is active

DSS

AIX, BSD, PSF, IPP, Passthrough

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value to one of these fixed values:

true

false

Default Value

If you have defined a value for the **destination-tcpip-internet-address** attribute and Infoprint has established SNMP communication with the printer device, **true**; otherwise **false**.

snmp-community-name

Specifies the name of the SNMP community to which the printer device that this actual destination represents belongs.

GUI Label

Community name

DSS

AIX, BSD, PSF, IPP, Passthrough

Type

Resettable, single-valued

Allowed Values

You can enter a text string up to 255 characters long that contains the SNMP community name.

Default Value

public

Usage Guidelines

If the value of the **use-snmp** attribute is **false**, this attribute is ignored.

snmp-retry-count

Specifies the number of times, after an initial failure, that Infoprint should attempt to establish SNMP communication with the printer device that this actual destination represents.

GUI Label

Number of times to retry

DSS

AIX, BSD, PSF, IPP, Passthrough

Type

Resettable, single-valued

Allowed Values

You can enter an integer from 0 through 2147483647.

Default Value

2

Usage Guidelines

- If the value of the **use-snmp** attribute is **true**, and if you have defined a value for the **destination-tcpip-internet-address** attribute, Infoprint attempts to establish SNMP communication with the printer device when:
 - The actual destination is created.
 - Any of the SNMP attributes of the actual destination are changed,
 - The actual destination is enabled and the value of the snmp-active attribute is false.
 - The server is started.
- If the value of the **use-snmp** attribute is **false**, this attribute is ignored.

snmp-timeout

Specifies the number of seconds that Infoprint should wait for SNMP operations on the printer device that this actual destination represents to complete.

GUI Label

Timeout (sec)

DSS

AIX, BSD, PSF, IPP, Passthrough

Type

Resettable, single-valued

Allowed Values

You can enter an integer from 0 through 2147483647.

Default Value

5

Usage Guidelines

- Set a value of 0 to use the SNMP default timeout period.
- If the value of the **use-snmp** attribute is **false**, this attribute is ignored.

start-message-supported

Indicates whether the actual destination supports the job attribute **job-start-message**.

GUI Label

Send job start message

DSS

All

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

true

Usage Guidelines

- When you set this attribute value to true, operators can receive messages that users specify with the job-start-message job attribute when they submit the job. Infoprint sends the message to the operators specified by the notify-operator attribute for this actual destination when the job starts printing. Sending a start message does not stop the job from printing; normally the job prints without operator intervention.
- Infoprint compares the job attribute job-start-message to this attribute for validation and scheduling.
- You can use this attribute to restrict use of this actual destination.

start-sheets-supported

Identifies the start sheets that this actual destination supports.

GUI Label

Start sheets allowed

DSS

AIX, PSF, 3170, IPP, Passthrough

Type

Resettable, multi-valued

Allowed Values

You can enter any of the following fixed values. For PSF only, you can enter a string up to 255 characters long that contains identifiers of auxiliary-sheet objects.

Fixed Value	DSS	Explanation
accounting-log	PSF	This value is technically valid, but should not be used for start sheets.
blank	PSF	The start sheet is blank.
brief	AIX, PSF, IPP,	The start sheet style is brief.
	Passthrough	
full	AIX, PSF, 3170, IPP,	The start sheet style is full.
	Passthrough	
job-ticket	PSF	The job ticket is printed on the start sheet.
none	AIX, PSF, 3170, IPP,	No start sheet prints.
	Passthrough	

Default Values

AIX, IPP, Passthrough brief, full, none

PSF accounting-log, blank, brief, full, job-ticket, none, and the names of other defined auxiliary sheets which have legal PSF auxiliary sheet attributes.

3170 full, none

Usage Guidelines

- PSF actual destinations can use auxiliary-sheet objects if they have valid psf-exit-xxx values. AIX actual destinations print start and end sheets, and 3170 actual destinations print start sheets; but they do not use auxiliary-sheet objects.
- Infoprint verifies that the value of the **printer-start-sheet** attribute is a value of this attribute.
- You cannot delete a value from this attribute if the value you want to delete is the value of the **printer-start-sheet** attribute.
- For PSF actual destinations, Infoprint sets this value dynamically to the names of all defined auxiliary sheets with legal attributes. You should never have to reset this value.

table-reference-characters-supported

Indicates whether this actual destination supports table reference characters. Some line-data applications produce table reference characters to specify font changes.

GUI Label

Table reference characters allowed

PSF, Email, Fax, Infoprint 2000

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

true

Usage Guidelines

- Infoprint compares the document attribute table-reference-characters to this attribute for scheduling.
- You can use this attribute to restrict use of this actual destination.

timeout-period

See printer-timeout-period.

transform-sequence

Specifies a list of names of transform objects that make up the transform sequence for this actual destination. The order of the values in this attribute determines the order that the transforms are run.

GUI Label

Transforms to use

All with NT/2000 servers

Type

Resettable, multi-valued

Allowed Values

Names of the transform objects.

Default Values

None.

use-snmp

Indicates whether Infoprint should attempt SNMP communication with the output device that this actual destination represents.

GUI Label

Use SNMP

DSS

AlX, BSD, PSF, IPP, Passthrough

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true ves false no

Default Value

true

Usage Guidelines

If Infoprint fails to establish SNMP contact with an output device, it uses the ping command to test whether it is possible to communicate with the device in other ways. If the ping command succeeds, Infoprint concludes that the device is not an SNMP device and resets this attribute to false.

wait-for-job-completion

Indicates whether Infoprint Manager waits for the job to print completely before reporting the job as completed or reports the job as completed as soon as all the data has been sent to the printer.

DSS

AlX

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

true when the printer and backend support PJL USTATUS; or false when the printer or the backend do not support PJL USTATUS.

Usage Guidelines

• This attribute can be used to activate or deactivate reporting of job completion.

Note: There is a new backend program called pioinfo for use with printers that can be used in place of the piojetd backend program. For example, destination-command=/usr/lpd/pio/etc/pioinfo ip_address, where *ip_address* is the ip address of the printer.

• There is a performance trade-off when you use this attribute: if you choose true, your printer performance may be reduced slightly; and when you choose false, the job completion messages are not accurate.

warning-message

Provides information about printer device conditions that require attention but allow printing to continue, such as low paper or low toner.

GUI Label

Warning message

AIX, BSD, PSF, IPP, Passthrough

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value to a text string that contains the message information.

Default Value

No default value

Usage Guidelines

Infoprint uses this attribute only when SNMP communication is active with the printer device.

windows-nt-driver-names

Identifies the 32-bit Windows print drivers that can submit a data stream to this actual destination.

GUI Label

Windows drivers

DSS

IPP, Passthrough

Type

Resettable, multi-valued

Input Synonyms

You can use the synonym windows-nt-drivers or nt-drivers.

Allowed Values

You can enter a text string that contains the string form of the Windows print driver for each permitted Windows print driver. Begin and end the string with single quotation marks.

Default Values

No default values

Usage Guidelines

Perform the following procedure to determine the valid Windows driver names:

1. Select **My Computer** from the desktop.

- 2. Select and open the Control Panel icon.
- 3. Select and open the Printers icon,
- 4. Select and open the **Add Printer** icon.
- 5. The values listed in the <u>Pprinters</u>: list box in the <u>Add Printer Wizard</u> are the names of the Windows destination drivers that you can install on the workstation; for example, <u>IBM 4039 LaserPrinter PS</u>.

Notes:

- 1. Other destination drivers are available and may not display in the list for a particular workstation.
- If you will be submitting jobs from the Windows client to a PSF actual
 destination, you should select a generic destination driver, such as a PostScript
 driver, instead of one for a specific type of destination. Otherwise, the driver
 may generate device-specific data streams that Infoprint cannot transform
 correctly.

x-image-shift-range-supported

Specifies, in millimeters, the lower and upper numeric boundaries for the X offset of a page. The X offset, along with the Y offset, sets the origin of the logical page on the physical page.

GUI Label

Move image right (inches) or (mm)

DSS

PSF, 3170, Email, Fax, Infoprint 2000

Туре

1:10

Resettable, single-valued, complex

Syntax

lower-limit:upper-limit

Separate values with colons, for example,

Components

lower-limit: Defines the minimum amount of image shift that you can specify with the document or default document attribute **x-image-shift** or **x-image-shift-back**.

Type: Single-valued

Allowed Values: You can enter a numeric value from -577.99 mm through 577.97 mm. The unit of measure is millimeters.

Default Value: 0

upper-limit: Defines the maximum amount of image shift that you can specify with the document or default document attribute **x-image-shift** or **x-image-shift-back**.

Type: Single-valued

Allowed Values: You can enter a numeric value from -577.99 mm through 577.97 mm. The unit of measure is millimeters.

Default Value: 577.97 mm

Usage Guidelines

- Infoprint compares the document attributes x-image-shift and x-image-shift-back to this attribute for validation and scheduling.
- You can use this attribute to restrict use of this actual destination.

y-image-shift-range-supported

Specifies, in millimeters, the lower and upper numeric boundaries for the Y offset of a page. The Y offset, along with the X offset, sets the origin of the logical page on the physical page.

GUI Label

Move image down (inches) or (mm)

DSS

PSF, 3170, Email, Fax, Infoprint 2000

Type

Resettable, single-valued, complex

Syntax

lower-limit:upper-limit

Separate values with colons, for example, 1:20

Components

lower-limit: Defines the minimum amount of image shift that you can specify with the document or default document attribute **y-image-shift** or **y-image-shift-back**.

Type: Single-valued

Allowed Values: You can enter a numeric value from -577.99 mm through 577.97 mm. The unit of measure is millimeters.

Default Value: 0

upper-limit:

Type: Single-valued

Allowed Values: You can enter a numeric value from -577.99 mm through 577.97 mm. The unit of measure is millimeters.

Default Value: 577.97 mm

Usage Guidelines

- Infoprint compares the document attributes **y-image-shift** and **y-image-shift-back** to this attribute for validation and scheduling.
- You can use this attribute to restrict use of this actual destination.

Attributes for Auxiliary-Sheet Objects

An auxiliary-sheet object represents:

- An auxiliary sheet that prints with a job sent to a PSF actual destination
- An exit program that generates information about the job for printing on an auxiliary sheet or writing to an accounting log or an audit log

An auxiliary sheet is a sheet of paper that prints at the beginning or end of output, or separating different parts of the output. The auxiliary sheet may have information printed on it identifying the output or may be blank.

The PSF DSS uses the names of auxiliary-sheet objects as values for actual destination attributes, such as **accounting-exit**, **audit-exit**, **start-sheets-supported**, and **printer-start-sheet**. The fax and email DSSs use the names of auxiliary-sheet objects as values for the **accounting-exit** and **audit-exit** actual destination attributes. AIX actual destinations print start and end sheets, and 3170 actual destinations print start sheets; but they do not use auxiliary-sheet objects.

Initially Settable Attribute Listing

There are no initially settable attributes for auxiliary-sheet objects.

Resettable Attribute Listing

You can set these attributes with the **pdcreate** command when you create an auxiliary-sheet object or you can modify them with the **pdset** command after you create the object.

descriptor psf-exit-form-definition psf-exit-page-mark psf-exit-program-name

associated-server

Indicates the name of the server where this auxiliary sheet resides.

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value when you create an auxiliary sheet for a given server. Infoprint assigns the *ServerName* portion of the argument from the **pdcreate** command used to create this auxiliary sheet object.

Default Value

No default value

auxiliary-sheet-identifier

Identifies the auxiliary sheet ID.

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value when you create an auxiliary sheet for a given server. Infoprint sets this value to the *AuxiliarySheet* portion of the argument used with the **pdcreate** command when this auxiliary sheet object was created. The value of this attribute must be unique within the server.

Default Value

No default value

descriptor

Provides a description of this auxiliary sheet.

Resettable, single-valued

Allowed Values

You can enter a text string of up to 4095 characters that describes this auxiliary sheet.

Default Value

No default value

Usage Guidelines

The use of this attribute is optional. However, a detailed description of this auxiliary sheet might be useful to other users or to someone who needs to modify its contents.

object-class

Identifies the object class to which this object belongs.

Non-settable, single-valued

Allowed Values

Infoprint sets this value to auxiliary-sheet.

Default Value

auxiliary-sheet

psf-exit-form-definition

Sets the form definition to use when printing this auxiliary sheet.

Type

Resettable, single-valued

Allowed Values

You can enter a text string of up to 255 characters that contains the name of the form definition. See "Appendix D. Form Definitions and Page Definitions Supplied with Infoprint" on page 723 for a list of available form definitions.

Default Value

No default value

Usage Guidelines

A form definition defines the placement of the data on the auxiliary sheet and other formatting information, such as a printer device bin number. You can use the form definition to select a bin for the auxiliary sheet that is different from the bin used for jobs. For example, you can print auxiliary sheets on a different colored paper than used for the jobs.

psf-exit-page-mark

Specifies whether you want page marks (black marks at the extreme edge of the page used for sorting) to print on this auxiliary sheet.

Auxiliary Sheet

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

false no true yes

Default Value

No default value

Usage Guidelines

Page marks are useful for printer devices that cannot perform offset stacking, such as continuous form printers. The marks allow printer operators to see the boundaries of jobs.

psf-exit-program-name

Sets the name of the exit program used to generate this auxiliary sheet.

Type

Resettable, single-valued

Allowed Values

You can enter a text string of up to 4095 characters that contains a name of a user exit program, an empty string, or no value.

Names of some user exit programs that you can use with AIX:

Accounting:

/usr/psf/bin/ainuxacc2

Full style

/usr/psf/bin/ainuxacc

Brief style

/usr/ps/bin/ainuxaccp

Job ticket

/usr/lpp/psf/bin/ainacclog

Log

Auditing:

/usr/lpp/psf/bin/ainuxaud2

Full style

/usr/lpp/psf/bin/ainuxaud

Brief style

/usr/lpp/psf/bin/ainuxaudp

Job ticket

/usr/lpp/psf/bin/ainaudlog

Log

Start Sheets:

/usr/lpp/psf/bin/ainuxhdr2

Full style

/usr/lpp/psf/bin/ainuxhdr

Brief style

/usr/lpp/psf/bin/ainuxhdrp

Job ticket

/usr/lpp/psf/bin/ainuxhdrx

Start sheet without vertical lines for IBM 64xx printers

/usr/lpp/psf/bin/pduxblkh

Blank

Separator Sheets:

/usr/lpp/psf/bin/ainuxsep2

Full style

/usr/lpp/psf/bin/ainuxsep

Brief style

/usr/lpp/psf/bin/ainuxsepp

Job ticket

/usr/lpp/psf/bin/ainuxsepx

Separator sheet without vertical lines for IBM 64xx printers

/usr/lpp/psf/bin/pduxblks

Blank

End Sheets:

/usr/lpp/psf/bin/ainuxtlr2

Full style

/usr/lpp/psf/bin/ainuxtlr

Brief style

/usr/lpp/psf/bin/ainuxtlrp

Job ticket

/usr/lpp/psf/bin/ainuxtlrx

End sheet without vertical lines for IBM 64xx printers

/usr/lpp/psf/bin/pduxblkt

Blank

Input Data:

/usr/lpp/psf/bin/ainuxind

This example does not perform any tasks. Use it as a model for writing your own user exit program.

Output Data:

/usr/lpp/psf/bin/ainuxout

This example does not perform any tasks. Use it as a model for writing your own user exit program.

Names of some user exit programs that you can use with Windows NT or

Windows 2000: In these names, *install_path* indicates the path where you installed Infoprint Manager:

Accounting:

\install_path\bin\ainuxacc2

Full style

\install_path\bin\ainuxacc

Brief style

\install_path\bin\ainuxaccp

Job ticket

\install_path\bin\ainacclog

Log

Auditing:

\install_path\bin\ainuxaud2

Full style

Auxiliary Sheet

\install_path\bin\ainuxaud

Brief style

\install_path\bin\ainuxaudp

Job ticket

\install_path\bin\ainaudlog

Log

Start Sheets:

\install_path\bin\ainuxhdr2

Full style

\install_path\bin\ainuxhdr

Brief style

\install_path\bin\ainuxhdrp

Job ticket

\install_path\bin\ainuxhdrx

Start sheet without vertical lines

\install_path\bin\pduxblkh

Blank

Separator Sheets:

\install_path\bin\ainuxsep2

Full style

\install_path\bin\ainuxsep

Brief style

\install_path\bin\ainuxsepp

Job ticket

\install_path\bin\ainuxsepx

Separator sheet without vertical lines

\install_path\bin\pduxblks

Blank

End Sheets:

\install_path\bin\ainuxtlr2

Full style

\install_path\bin\ainuxtlr

Brief style

\install_path\bin\ainuxtlrp

Job ticket

\install_path\bin\ainuxtlrx

End sheet without vertical lines

\install_path\bin\pduxblkt

Blank

Input Data:

\install_path\bin\ainuxind

This example does not perform any tasks. Use it as a model for writing your own user exit program.

Output Data:

\install_ path\bin\ainuxout

This example does not perform any tasks. Use it as a model for writing your own user exit program.

Default Value

No default value

Usage Guidelines

• If the attribute has:

No value

The auxiliary sheet does not print.

An empty string (")

Infoprint uses the default user exit program:

Accounting For AIX, /usr/lpp/psf/bin/ainacclog; for Windows NT or

Windows 2000, \install_path\bin\ainacclog

Audit No default program

Start sheet For Aix, /usr/lpp/psf/bin/ainuxhdr; for Windows NT or

Windows 2000, \install_path\bin\ainuxhdr

Separator sheet

No default program

End sheet No default programInput data No default programOutput data No default program

Any other value

for end sheets.

Infoprint uses the specified user exit program to generate auxiliary sheets.

• While you can specify only one user exit program as a value for this attribute, the default auxiliary-sheet objects can invoke any of a set of user exit programs. For example with AIX, the brief default auxiliary-sheet object invokes /usr/lpp/psf/bin/ainuxacc for accounting exits, /usr/lpp/psf/bin/ainuxaud for audit exits, /usr/lpp/psf/bin/ainuxhdr for start sheets, /usr/lpp/psf/bin/ainuxsep for separator sheets, and /usr/lpp/psf/bin/ainuxtlr for end sheets. For example with Windows NT or Windows 2000, the brief default auxiliary-sheet object invokes \install_path\bin\ainuxacc for accounting exits, \install_path\bin\ainuxaud for audit exits, \bin\ainuxhdr for start sheets, \install_path\bin\ainuxsep for separator sheets, and \install_path\bin\ainuxtlr

Attributes for Documents and Default Documents

This section contains the attributes for both documents and default documents.

Document

An Infoprint document represents a grouping of data within a job. A job can contain one or more documents. The documents in a job can differ from each other in some ways. For example, they can contain different data. A document within a job can contain printable data or a resource that is not printable by itself.

Default Document

Use default documents to set default values for document attributes.

Default documents contain two types of attributes:

- · Attributes that describe the default document itself
- · Attributes that you can set as default values for document attributes

Attributes Not Displayed in the Infoprint Administrator's GUI

While all document and default document attributes and attribute values are supported for both basic and advanced Infoprint installations, neither Infoprint administrator's GUI displays a complete set.

- The basic Infoprint administrator's GUI displays only the attributes of greatest interest to Print on Demand (Commercial Printing) Infoprint administrators.
- The advanced Infoprint administrator's GUI displays most attributes and attribute values of greatest interest to Data Center (Production Printing) Infoprint administrators, but omits a few that are used primarily in basic Infoprint installations.

You can list the values of attributes not displayed in the Infoprint administrator's GUI using the pdls command or the pdq command. You can set the values of initially settable and resettable attributes using the pdcreate command or the pdpr command. You can change the values of resettable attributes using the pdmod command or the pdset command.

Initially Settable Attribute Listing

You can set these attributes with the **pdpr** command when you create a document.

document-file-name document-type initial-value-document transfer-method

There are no initially settable attributes for default documents.

Resettable Attribute Listing

You can set these attributes with the pdpr command when you create a document or with the pdcreate command when you create a default document. You can modify them with the pdset command after you create the document or the default document. You can also modify them for the document using the pdmod command.

account-text address1-text address2-text address3-text

address4-text base-printer bits-per-spot black-overprint building-text callback-number

carriage-control-type

chars

cms-proclink

cms-product

color-bits-per-plane

color-mapping-table

color-profile

color-toner-saver

compressed-output

content-orientation

control-strip

convert-to-ebcdic

copy-count

data-fidelity-problem-reported

default-character-mapping

default-input-tray

default-medium

default-printer-resolution

department-text

descriptor (default document only)

destination-company-text

destination-pass-through

document-comment

document-finishing

document-format

dot-shape

email-from-address

email-to-address

enable-settrap

fax-number

fax-to-name

font-fidelity-action

font-processing-messages

font-resolution

form-definition

halftone

image-center-x

image-center-y

image-fit

image-length

image-out-format

image-scale

image-width

input-exit

input-tray-select

jog-between-job-copies

list-of-managers (default document only)

maximum-messages-printed

maximum-transform-pages-ahead

message (default document only)

mvs-class mvs-destination mvs-forms mvs-segment-id name-text new-line-option node-id-text number-up originating-company-text other-transform-options output-appearance output-bin output-face-up output-format overlay overlay-back overlay-front overprint page-clip page-count (document only) page-definition page-media-select page-select (document only) plex print-quality programmer-text resource-context resource-context-font resource-context-form-definition resource-context-overlay resource-context-page-definition resource-context-page-segment resource-context-presentation-object-container resource-context-user resource-exit room-text scanner-correction screen-frequency segment-file-size shared-formdef shift-out-shift-in sides start-on-new-sheet subject-text table-reference-characters title-text transform-message-file-name transform-output-file-name user-id-text x-image-shift x-image-shift-back y-image-shift

y-image-shift-back

Per-Document Attribute Listing

These attributes can have a different value for each document in a job. For initially settable and resettable per-document attributes, you can specify a different value for each document in a job using the pdpr command. Specify -x "AttributeName=value" before the name of each file.

For example, to print a job consisting of two documents, one with an estimated size of 10 pages and the other with an estimated size of 15 pages, enter:

pdpr -x "page-count=10" -f File1 -x "page-count=15" File2

Note: All documents in a job must have the same value for all initially settable and resettable attributes if

- The job is submitted from tape
- The documents are in ASCII format

Initially Settable document-type

Resettable black-overprint carriage-control-type chars cms-proclink cms-product color-bits-per-plane color-profile color-toner-saver compressed-output content-orientation convert-to-ebcdic copy-count default-input-tray default-medium document-finishing document-format dot-shape

Non-Settable
document-content
document-content-list
document-sequence-number
initial-value-document
octet-count

enable-settrap image-center-x image-center-y image-fit image-length image-out-format image-scale image-width input-exit medium-map-name new-line-option other-transform-options output-appearance output-bin output-face-up overprint page-clip page-count page-definition page-select plex print-quality

resource-context-page-definition resource-context-presentation-object-containers

resource-context-user

resource-exit

sides

scanner-correction screen-frequency shift-out-shift-in start-on-new-sheet table-reference-characters transform-message-file-name transform-output-file-name x-image-shift x-image-shift-back

x-image-shift-back y-image-shift y-image-shift-back

All other document attributes are per-job attributes. They must have the same value for each document in the job.

account-text

Specifies account information that Infoprint prints in the **ACCOUNT**: field of an auxiliary sheet if the job uses the **full** auxiliary-sheet object.

GUI Label

Account

DSS

PSF, Email, Fax, Infoprint 2000

Туре

Resettable, single-valued, per-job

Allowed Values

You can enter a text string of up to 4095 characters that contains the account information.

Default Value

No default value

Usage Guidelines

- While you can specify more characters, you should limit the text string you supply to 20 characters or less to ensure that there is enough room available on the printed page for all of the account information.
- If the text string you specify contains blank spaces, enclose the text string in single quotation marks.

address1-text

Specifies address information that Infoprint prints on the first line of the **ADDRESS:** field of an auxiliary sheet if the job uses the **full** auxiliary-sheet object.

For Fax, this attribute maps to a user-defined customizable field.

GUI Label

Address line 1

DSS

PSF, Fax

Type

Resettable, single-valued, per-job

Allowed Values

You can enter a text string of up to 4095 characters that contains the address information.

Default Value

No default value

Usage Guidelines

- While you can specify more characters, you should limit the value you supply to 57 characters or less to ensure that there is enough room available on the printed page for all address information.
- If the text string you specify contains blank spaces, enclose the text string in single quotation marks.

address2-text

Specifies address information that Infoprint prints on the second line of the **ADDRESS:** field of an auxiliary sheet if the job uses the **full** auxiliary-sheet object.

For Fax, this attribute maps to a user-defined customizable field.

GUI Label

Address line 2

DSS

PSF, Fax

Type

Resettable, single-valued, per-job

Allowed Values

You can enter a text string of up to 4095 characters that contains the address information.

Default Value

No default value

Usage Guidelines

- While you can specify more characters, you should limit the value you supply to 57 characters or less to ensure that there is enough room available on the printed page for all address information.
- If the text string you specify contains blank spaces, enclose the text string in single quotation marks.

address3-text

Specifies address information that Infoprint prints on the third line of the **ADDRESS:** field of an auxiliary sheet if the job uses the **full** auxiliary-sheet object.

For Fax, this attribute maps to a user-defined customizable field.

GUI Label

Address line 3

DSS

PSF, Fax

туре

Resettable, single-valued, per-job

Allowed Values

You can enter a text string of up to 4095 characters that contains the address information.

Default Value

No default value

Usage Guidelines

- While you can specify more characters, you should limit the value you supply to 57 characters or less to ensure that there is enough room available on the printed page for all address information.
- If the text string you specify contains blank spaces, enclose the text string in single quotation marks.

address4-text

Specifies address information that Infoprint prints on the fourth line of the ADDRESS: field of an auxiliary sheet if the job uses the full auxiliary-sheet object.

For Fax, this attribute maps to a user-defined customizable field.

GUI Label

Address line 4

DSS

PSF, Fax

Resettable, single-valued, per-job

Allowed Values

You can enter a text string of up to 4095 characters that contains the address information.

Default Value

No default value

Usage Guidelines

- · While you can specify more characters, you should limit the value you supply to 57 characters or less to ensure that there is enough room available on the printed page for all address information.
- If the text string you specify contains blank spaces, enclose the text string in single quotation marks.

associated-server (Default Document Only)

Indicates the name of the server in which this default document resides.

DSS

All

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value to the ServerName: portion of the argument used with the pdcreate command when this default document is created.

Default Value

No default value

base-printer

Indicates the printer model you want to RIP the document for.

GUI Label

RIP for

DSS

PSF, Infoprint 2000

Type

Resettable, single-valued, per-job

Allowed Values

You can enter one of these fixed values:

InfoprintColor100AFP

InfoprintColor130Plus

Infoprint20

Infoprint21

Infoprint32

Infoprint40

Infoprint60

Infoprint70

Infoprint2000

Infoprint2000AFP

Infoprint3000

Infoprint4000

Infoprint4000-ID5-ID6

Infoprint4000-IR3-IR4

Default Value

The value of the **printer-model** attribute for the actual destination where the document prints.

Usage Guidelines

You can RIP a document for a different printer than you actually print it on. This is useful for printing proof documents.

bits-per-spot

Specifies the number of bits used to describe the gray value for each pixel.

GUI Label

Bits per spot

DSS

3170

Non-settable, single-valued, per-job

Allowed Values

You can enter an integer value of 2 or 4.

Default Value

No default value

Usage Guidelines

- A value of 2 means that each pixel can have one of four levels of gray from 0 to maximum density. A value of 4 means that each pixel can have one of sixteen levels of gray from 0 to maximum density.
- If you do not specify a value for this attribute, Infoprint uses the value in the file specified by the rip-ini-file actual destination attribute.

black-overprint

Indicates whether to print black over colors.

GUI Label

Black overprint

DSS

3170

Type

Resettable, single-valued, per-document

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

No default value

Usage Guidelines

- Specify true to print a colored background with black over it. Specify false to omit colors from areas where black will be printed.
- If you do not specify a value for this attribute, Infoprint uses the value in the file specified by the rip-ini-file actual destination attribute.

building-text

Specifies building information that Infoprint prints in the BUILDING: field of an auxiliary sheet if the job uses the full auxiliary-sheet object.

GUI Label

Building

DSS

PSF

Type

Resettable, single-valued, per-job

Allowed Values

You can enter a text string of up to 4095 characters that contains the building information.

Default Value

No default value

Usage Guidelines

- · While you can specify more characters, you should limit the value you supply to 24 characters or less to ensure that there is enough room available on the printed page for all building information.
- If the text string you specify contains blank spaces, enclose the text string in single quotation marks.

callback-number

Specifies the callback telephone number that appears on the cover sheet of a fax job.

DSS

Fax

Type

Resettable, single-valued, per-job

Allowed Values

You can enter a text string up to 4096 characters long that contains the telephone number.

Default Value

No default value

carriage-control-type

Identifies the type of carriage control characters that the printer device uses when interpreting and printing this document.

GUI Label

Type of carriage control characters

DSS

PSF, Email, Fax, Infoprint 2000

Type

Resettable, single-valued, per-document

Allowed Values

```
You can enter one of these fixed values:
    ansi-ascii
    ansi-ebcdic
    machine
    none
```

Default Value

none

Usage Guidelines

- Infoprint validates and schedules jobs using this attribute against the destination attribute carriage-control-types-supported.
- This attribute is valid only for line-data documents.

chars

Identifies from zero to four coded fonts used to print a line-data document.

Coded fonts are character set and code page pairs. Coded font names begin with a two-character prefix (X0 or XZ), followed by up to four alphanumeric characters. X042B2 is an example of a coded font name.

GUI Label

Fonts

DSS

PSF, Email, Fax, Infoprint 2000

Type

Resettable, multi-valued, per-document

Allowed Values

You can enter a text string that contains the name or global ID of the fonts. The name of each font can be one to four characters long. Omit the two-character prefix from the coded font name or the alternate coded font name.

For the names of coded fonts, refer to *IBM AFP Fonts: Font Summary*.

If you specify more than one coded font on the command line, separate the font names by spaces and surround the attribute and value with double quotation marks, for example:

"chars=GT10 GT12"

If you specify more than one coded font in the Infoprint administrator's GUI, separate the font names by commas, for example: GT10,GT12

Default Value

No default value

Usage Guidelines

- This attribute is valid only for line-data documents.
- · If the page definition does not identify fonts, you must specify fonts with this attribute if you want to print in more than one font.
- If you specify more than one coded font with the chars attribute, the file must contain table reference characters and you must specify the table-referencecharacters attribute value as true.
- Infoprint uses this attribute only if the page definition specifies no coded fonts. If you specify fonts with this attribute and the page definition also specifies fonts, Infoprint uses the fonts named in the page definition.

cms-proclink

Identifies the translation table used by the Xeikon color correction program.

GUI Label

Translation table

DSS

3170

Resettable, single-valued, per-document

Allowed Values

You can enter one of these fixed values:

matchp_ndtg2xkn_2

Match print, normal dot gain, 2 bits per spot

matchp_ndtg2xkn_4

Match print, normal dot gain, 4 bits per spot

swop_crom2xkn_2

SWOP Cromalin, 2 bits per spot

swop_crom2xkn_4

SWOP Cromalin, 4 bits per spot

Default Value

No default value

Usage Guidelines

- To enable Xeikon color correction, specify a value of **xeikon** for the **cms-product** attribute or in the file specified by the **rip-ini-file** actual destination attribute.
- If you do not specify a value for this attribute, Infoprint uses the value in the file specified by the **rip-ini-file** actual destination attribute.

cms-product

Identifies the color correction program.

GUI Label

Color correction

DSS

3170

Type

Resettable, single-valued, per-document

Allowed Values

You can enter one of these fixed values: **xeikon**

Default Value

No default value

Usage Guidelines

- When Xeikon color correction is enabled, you must specify a translation table
 using the cms-proclink attribute or in the file specified by the rip-ini-file actual
 destination attribute.
- If you do not specify a value for this attribute, Infoprint uses the value in the file specified by the **rip-ini-file** actual destination attribute.

color-bits-per-plane

Specifies whether the transform is to produce monochrome (fs10) or color images (fs42 or fs45)

GUI Label

Color bits per plane

DSS

PSF

туре

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

- **0-bits** (monochrome FS10)
- **1-bit** (color FS42)
- **8-bits** (color FS45)

Default Value

There is no default value.

Usage Guidelines

 If a document is already ripped, changing this attribute at the printer will not effect the document. To change a ripped document, modify the job and document properites to specify the new value. When released, the document will be re-ripped automatically.

color-mapping-table

Identifies the color mapping table (CMT) to be used when printing this document.

GUI Label

Color mapping table

DSS

PSF

Type

Resettable, single-valued, per-job attribute.

Allowed Values

You can enter a text string of up to 8 characters that contains the identification for this resource.

Default Value

There is no default value. If you omit this attribute or it contains no value, Infoprint uses the color mapping table defined by the actual destination color-mapping-table attribute, if any.

color-profile

Specifies that color profile, if any, is to be used by the PostScript transform.

GUI Label

Color profile

DSS

PSF

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

- SWOP
- Euroscale
- none

Default Value

There is no default value.

Usage Guidelines

• If a document is already ripped, changing this attribute at the printer will not effect the document. To change a ripped document, modify the job and document properites to specify the new value. When released, the document will be re-ripped automatically.

color-toner-saver

When cyan, magenta, and yellow (cmyk) are combined in a certain proportion, the result approximates black. When the **color-toner-saver** attribute is used, the proportion of cyan, magenta, and yellow are reduced and substituted with black toner, which reduces the amount of color toner used. This option only applies to non-cmyk PostScript (for example, RGB) for which a color rendering dictionary (CRD) is used to determine the cmyk values to use.

GUI Label

Color toner saver

DSS

PSF

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

With the **color-toner-saver** attribute, a value of **true** or **yes** substitutes black for common cyan, magenta, and yellow components to reduce consumption of toner and to reduce the cost per page; while a value of **false** or **no** uses the cmyk proportions specified.

Default Value

There is no default value.

Usage Guidelines

- If a document is already ripped, changing this attribute at the printer will not effect the document. To change a ripped document, modify the job and document properites to specify the new value. When released, the document will be re-ripped automatically.
- Setting color-toner-saver to True or Yes results in less vibrant process colors.

compressed-output

Indicates whether to compress the RIPped file.

GUI Label

Compress output

DSS

3170

Type

Resettable, single-valued, per-document

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

No default value

Usage Guidelines

If you do not specify a value for this attribute, Infoprint uses the value in the file specified by the rip-ini-file actual destination attribute.

content-orientation

Identifies the page presentation (the placement of data on a page) for the document.

GUI Label

Orientation

DSS

AIX, 3170

Type

Resettable, single-valued, per-document

Input Synonym

You can use the synonym **orientation**.

Allowed Values

You can enter one of these fixed values:

landscape portrait

reverse-portrait

reverse-landscape

Default Value

The first value of the destination attribute **content-orientations-supported** AIX 3170 No default value

Usage Guidelines

- Infoprint validates and schedules jobs using this attribute against the destination attribute content-orientations-supported.
- For the 3170 DSS, if you do not specify a value for this attribute, Infoprint uses the value in the file specified by the rip-ini-file actual destination attribute.

control-strip

Specifies the control strip to print with this document.

GUI Label

Control strip

DSS

3170

Type

Resettable, single-valued, per-job

Allowed Values

You can enter a text string of up to 255 characters that contains the name of the control strip.

Default Value

No default value

Usage Guidelines

- The control strip must be pre-RIPped and must reside in the collator.
- If you do not specify a value for this attribute, Infoprint uses the value in the file specified by the **rip-ini-file** actual destination attribute.

convert-to-ebcdic

Indicates whether to convert this file from ASCII to EBCDIC before the document prints.

GUI Label

Convert to EBCDIC

DSS

PSF, Email, Fax, Infoprint 2000

Туре

Resettable, single-valued, per-document

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

No default value

Usage Guidelines

- Infoprint validates and schedules jobs using this attribute against the destination attribute **convert-to-ebcdic-supported**.
- This attribute is valid only for line-data documents.

copies

See copy-count.

copy-count

Specifies the number of document copies printed per job copy.

GUI Label

Copy count

DSS

All

Type

Resettable, single-valued, per-document

Input Synonym

You can use the synonym copies.

Allowed Values

You can enter an integer from 1 through 2147483647.

Default Value

1

Usage Guidelines

- Infoprint validates and schedules jobs using this attribute against the destination attribute maximum-copies-supported.
- This attribute is not valid for AFP documents with inline resources. To print multiple copies of these documents, use the *job-copies* component of the **results-profile** job attribute.
- For BSD (by default), this document attribute maps to the qprt -N option.

data-fidelity-problem-reported

Indicates the type of data fidelity problems, print-positioning or invalid-character errors, that the destination reports while printing this document.

GUI Label

Data fidelity problem reported

DSS

PSF, Infoprint 2000

Type

Resettable, single-valued, per-job

Allowed Values

You can enter one of these fixed values:

Fixed Value Report

all Both print-positioning and invalid-character errors

character Only invalid-character errors

none No errors

position Only print-positioning errors

Default Value

none

Usage Guidelines

Infoprint validates and schedules jobs using this attribute against the destination attribute data-fidelity-problem-reported-supported.

default-character-mapping

Defines the character-mapping (codepage) used while printing an ASCII or double-byte character set (DBCS) ASCII document.

GUI Label

Default character mapping

DSS

AIX, PSF, Email, Fax, Infoprint 2000

Type

Resettable, single-valued, per-job

Allowed Values

You can enter one of these fixed values:

ibm-437

ibm-850

ibm-860

ibm-863

ibm-865

ibm-932

ibm-938 for Infoprint Manager for AIX only

ibm-euccn ibm-eucjp ibm-euckr ibm-euctw

Default Value

No default value

Usage Guidelines

Infoprint validates and schedules jobs using this attribute against the destination attribute character-mappings-supported.

default-input-tray

Identifies an input-tray on the printer device that contains the medium that Infoprint uses for normal document pages.

GUI Label

Input tray requested

DSS

AIX, PSF, Infoprint 2000

Type

Resettable, single-valued, per-document

Allowed Values

For AIX actual destinations, use one of these values:

auto-envelope-feed manual-envelope-feed automatic-tray middle auxiliary-envelope top auxiliary-paper tray-1 bottom tray-2 continuous-form-feed tray-3 tray-4 current-selected-tray tray-5 envelope capacity-2000-sheet large-capacity

manual

For PSF and Infoprint 2000 actual destinations, you can enter one of these values or any other value that maps to one of the actual destination psf-traycharacteristics attribute values.

Default Value

No default value

Usage Guidelines

- Infoprint validates and schedules jobs using this attribute against the destination attribute input-trays-supported.
- · For AIX actual destinations, any input tray selection in the data stream or form definition overrides the value you specify for this attribute.
- · For PSF actual destinations, the value you specify for this attribute overrides any input tray selection in the data stream or form definition, with one exception. If you specify different values for this attribute for each document in a job, and

also specify a value for the document **form-definition** attribute, Infoprint ignores the different values and uses the input tray selection in the form definition.

• If this attribute and the **default-medium** attribute have conflicting values, Infoprint uses the value of the **default-medium** attribute.

default-medium

Identifies the medium for document pages on which this document prints.

GUI Label

Medium requested

DSS

AIX, PSF, 3170, Infoprint 2000, Passthrough, IPP

Type

Resettable, single-valued, per-document

Allowed Values

AIX You can enter a text string of up to 255 characters that contains one of the values listed for the **medium-identifier** attribute for the medium object or a name of a medium you have created. Refer to the medium object **medium-identifier** attribute.

2000 You can specify any text string that is listed as a supported medium.

PSF You can specify any text string that is listed as a supported medium.

Passthrough

The Passthrough DSS uses this attribute for job validation and scheduling only. It does not affect print output.

Default Value

No default value

Usage Guidelines

- Infoprint validates the document against the logical destination attribute media-supported and the actual destination attribute media-supported.
- Infoprint schedules the document against the actual destination attributes media-supported and media-ready.
- For AIX actual destinations, any medium selection in the data stream or form definition overrides the value you specify for this attribute.
- For PSF actual destinations, the value you specify for this attribute overrides any
 medium selection in the data stream or form definition, with one exception. If
 you specify different values for this attribute for each document in a job, and
 also specify a value for the document form-definition attribute, Infoprint
 ignores the different values and uses the medium selection in the form
 definition.
- If this attribute and the **default-input-tray** attribute have conflicting values, Infoprint uses the value of this attribute.
- For Infoprint 2000 actual destinations, the value specified must map to an existing medium object.
- For the 3170 DSS, if you do not specify a value for this attribute, Infoprint uses the smallest medium that the image will fit on.

default-printer-resolution

Specifies the resolution, in pels, at which the printer device should print this document.

GUI Label

Printer resolution requested

DSS

PSF, 3170, Infoprint 2000

Туре

Resettable, single-valued, per-job

Allowed Values

You can enter one of these fixed values:

Fixed Value	DSS
240	PSF
300	PSF
480	PSF

600 PSF, 3170, Infoprint 2000

Default Value

PSF 240 3170 600 Infoprint 2000 600

Usage Guidelines

- This attribute is valid only for GIF, JPEG, PCL, PDF, PostScript, and TIFF documents
- This attribute applies only to image data. It has no effect on font resolutions.
- Infoprint validates jobs using this attribute against the destination attribute printer-resolutions-supported.
- Infoprint schedules jobs using this attribute against the destination attribute printer-resolutions-ready.

department-text

Specifies department information that Infoprint prints in the **DEPARTMENT:** field of an auxiliary sheet if the job uses the **full** auxiliary-sheet object.

GUI Label

Department

DSS

PSF

Type

Resettable, single-valued, per-job

Allowed Values

You can enter a text string of up to 4095 characters that contains the department information.

Default Value

No default value

Usage Guidelines

- While you can specify more characters, you should limit the value you supply to 24 characters or less to ensure that there is enough room available on the printed page for all department information.
- If the text string you specify contains blank spaces, enclose the text string in single quotation marks.

descriptor (Default Document Only)

Provides a description of this default document.

DSS

All

Type

Resettable, single-valued

Allowed Values

You can enter a text string of up to 4095 characters that describes this default document.

Default Value

No default value

Usage Guidelines

The use of this attribute is optional. However, a detailed description helps job submitters to determine if this is the default document they want to use.

destination-company-text

Specifies the name of the destination company that appears on the fax cover sheet.

DSS

Fax

туре

Resettable, single-valued, per-job

Allowed Values

You can enter a text string up to 4095 characters long that contains the name of the destination company.

Default Value

No default value

destination-initial-value-document (Document Only)

Identifies the default document associated with the logical destination to which you submitted the document and that Infoprint used to create the document.

GUI Label

Default document used

DSS

All

Type

Non-settable, single-valued, per-job

Input Synonym

You can use the synonym **printer-initial-value-document**.

Allowed Values

Infoprint sets this value to the name of the default document used.

Default Value

No default value

destination-pass-through

Allows you to submit specific DSS (print driver) information along with the document. Infoprint does not process the information, but passes it directly to the DSS.

For information on the use of **destination-pass-through** with **other-transform-options**, see 669.

GUI Label

Other options

DSS

AIX, BSD, PSF, Infoprint 2000

Type

Resettable, single-valued, per-job

Input Synonyms

You can use the synonym printer-pass-through or other-options.

Allowed Values

You can enter a text string of up to 4095 characters that contains the DSS information.

Default Value

No default value

Usage Guidelines

For BSD, Infoprint appends the contents of this attribute to the contents of the actual destination attribute **destination-command** after the mapped options.

document-comment

Provides information that Infoprint associates with this document.

DSS

AIX, BSD, PSF, Email, Fax, Infoprint 2000

Type

Resettable, single-valued, per-job

Allowed Values

You can enter a text string of up to 4095 characters that contains information about this document, such as the fonts it requires.

Default Value

No default value

document-content (Document Only)

Contains the document file identifier.

DSS

All

Type

Non-settable, single-valued, per-document

Allowed Values

Infoprint sets this value to an internal value that is not displayed on queries.

Default Value

No default value

document-content-list (Document Only)

Lists the files in a file-reference document.

DSS

All

Non-settable, multi-valued, per-document

Allowed Values

Infoprint sets this value to a list of file identifiers.

Default Value

No default value

Usage Guidelines

A file-reference document is a list of similar printable documents. All the printable documents must have the same format, because Infoprint processes them all the same way.

document-file-name (Document Only)

Provides the name you want to assign to the file (document).

GUI Label

File names

DSS

All

Type

Initally-settable, single-valued, per-document

Input Synonym

You can use the synonym file-name.

Allowed Values

You can enter a text string of up to 4095 characters that contains the file name or source specified with the pdpr command.

Default Value

The file name of the first document in the job.

document-finishing

Identifies the finishing options for this document.

GUI Label

Finishing options

DSS

PSF

Type

Resettable, multi-valued, per-document

Allowed Values

You can enter any of these fixed values: **z-fold**

Default Values

No default values

Usage Guidelines

- This attribute is not valid for ASCII documents.
- When you specify a value for **document-finishing**, Infoprint creates an inline form definition. Do not use the **form-definition** attribute to specify another form definition.
- Infoprint validates and schedules jobs using this attribute against the destination attribute **document-finishings-supported**.

document-format

Identifies the format (data type) of this document.

GUI Label

Format

DSS

All

Type

Resettable, single-valued, per-document

Input Synonym

You can use the synonym format.

Allowed Values

You can enter one of these fixed values:

Fixed Value	Input Synonym	DSS
ascii		AIX, BSD, PSF (except upload printers), Passthrough, IPP
dbcs-ascii		AIX, BSD, PSF, Infoprint 2000
ditroff		BSD, PSF DSS for AIX, email, fax, Infoprint 2000
d630		AIX, BSD
gif		BSD, PSF DSS for AIX, email, fax, Infoprint 2000
hpgl	hp-gl	AIX, BSD
iso-6429		AIX, BSD, Passthrough, IPP
jpeg		BSD, PSF DSS for AIX, email, fax, Infoprint 2000
kgl		BSD, Infoprint 2000
lcds		BSD
line-data		BSD, PSF, email, fax, Infoprint 2000
metacode		BSD
modca-p	afpds	BSD, PSF, email, fax, Infoprint 2000

Fixed Value	Input Synonym	DSS
passthru		AIX, BSD
pcl	hppcl, hp-pcl	AIX, BSD, PSF, email, fax, Infoprint 2000, Passthrough, IPP
pdf		BSD, PSF, email, fax, Infoprint 2000
postscript	ps	All
ppds		BSD
sap		BSD, PSF DSS for AIX, email, fax, Infoprint 2000,
		Passthrough
sap-abap		BSD, PSF DSS for AIX, email, fax, Infoprint 2000,
		Passthrough
simple-text	text	BSD, Passthrough, IPP
tiff		BSD, PSF DSS for AIX, email, fax, Infoprint 2000

Note: By default, BSD actual destinations support only a subset of the formats that the BSD DSS can print. You can update the destination attribute **document-format-supported** to include any or all of these values.

Default Value

The server identifies the document format. If the format cannot be determined, ascii

Usage Guidelines

- If you or a default document you specify do not provide a value for this attribute with the **pdpr** command, the server attempts to determine the file format. If it is unable to determine the format, Infoprint uses the default.
- Infoprint validates and schedules jobs using this attribute against the destination attribute **document-formats-supported**.
- You cannot print ASCII documents and documents with other formats in the same job.

document-number (Document Only)

See document-sequence-number.

document-sequence-number (Document Only)

Identifies this document in relation to the other documents of a multi-document job.

DSS

A11

Type

Non-settable, single-valued, per-document

Input Synonyms

You can use the synonym sequence-number or document-number.

Allowed Values

An integer from 1 through 2147483647.

Default Value

No default value

Usage Guidelines

Use this number as part of the local ID or global ID to identify a given document within a job.

document-type (Document Only)

Indicates that the document is either a printable document, a group of printable documents, a font, or some other resource.

GUI Label

Types

DSS

All

Type

Initially settable, single-valued, per-document

Input Synonym

You can use the synonym type.

Allowed Values

You can enter one of these fixed values:

Fixed Value DSS book-ticket-file 3170 color-mapping-table PSF cover-sheet Fax

document-definition PSF DSS for AIX, 3170, email, fax, Infoprint 2000

email-body Email email-signature Email file-reference All

font PSF, email, fax, Infoprint 2000 form-definition PSF, email, fax, Infoprint 2000 formatted-job-ticket PSF, 3170, email, fax, Infoprint 2000 insert-sheet PSF, email, fax, Infoprint 2000 job-ticket PSF, 3170, email, fax, Infoprint 2000 overlay PSF, email, fax, Infoprint 2000 overlay-back PSF, email, fax, Infoprint 2000 overlay-front PSF, email, fax, Infoprint 2000 page-definition PSF, email, fax, Infoprint 2000 page-segment PSF, email, fax, Infoprint 2000 page-shift-file PSF, email, fax, Infoprint 2000

printable All

resource PSF DSS for AIX, 3170, email, fax, Infoprint 2000

rip-ini-file 3170

variable-data PSF DSS for AIX, 3170, email, fax, Infoprint 2000

Default Value

printable

Usage Guidelines

A file-reference document is a list of similar printable documents. All the
printable documents must have the same format, because Infoprint processes
them all the same way.

Insert documents normally require media sheets from the insert input tray,
which is on the finisher. This means that you cannot print an insert with the rest
of the job. If you want printed inserts, preprint them and load the printed sheets
into the insert tray.

This does not mean that the insert document should not have any printable content. The insert document should be a MO:DCA-P, PostScript, or TIFF (not ASCII) file containing text like this:

This is an insert sheet.

A MO:DCA-P insert document is supplied with Infoprint Submit. If you submit jobs in other ways, create your own insert document.

If the **insert** input tray is not available (for example, if you are proofing a job on a printer without a finisher), Infoprint prints the insert document on a sheet from the default input bin, so that you can easily see where sheets from the insert tray will be inserted in the final job.

- To print a booklet with a cover, specify **insert** as the document format of the first document in the job.
- A fax job must not include more than one cover-sheet document.
- An email job must not include more than one **email-body** document or more than one **email-signature** document.
- Infoprint validates and schedules jobs using this attribute against the destination attribute **document-types-supported**.
- As Infoprint processes your job, it creates a book-ticket file. To override this file, specify the book-ticket-file allowed value and include your own book-ticket file with the job. By specifying your own book-ticket file, you can specify the files that you want Infoprint to process, and then provide other files that you do not want Infoprint to process for the actual destination. The other files are printed at the actual destination. Remember to ensure that the other files are available at the actual destination, because Infoprint does no checking for files that you do not include with the book-ticket file.
- As Infoprint processes your job, it also creates a temporary rip-ini file. Infoprint
 uses this temporary rip-ini file to contain the defaults associated with each
 actual destination and the job attributes supplied with the job.

To override this temporary rip-ini file, specify the **rip-ini-file** allowed value and include your own rip-ini file with the job. By specifying your own rip-ini file, you can specify the job attributes that you want Infoprint to use when ripping the job. The rip-ini file you supply takes effect on the document, and any subsequent documents, until another rip-ini file is provided.

When you supply a rip-ini file, Infoprint reads in the defaults associated with the actual destination, merges in the attributes from the supplied rip-ini file, and then applies the attributes from the document that affect the rip. This combined rip-ini file is used to process the document.

dot-shape

Indicates the shape of pixels.

GUI Label Dot shape

DSS 3170

Type

Resettable, single-valued, per-document

Allowed Values

You can enter a customized value or one of these fixed values:

Fixed Value Equivalent

classic /c=r,170,15/m=r,170,75/y=r,170,90/k=r,170,45 combined /c=c,170,15/m=c,170,75/y=c,170,90/k=c,170,45 sofocles /c=l,158,15/m=l,158,75/y=l,158,90/k=l,158,45 sofocles-not-calibrated /c=ln,158,15/m=ln,158,75/y=ln,158,90/k=ln,158,45

Default Value

No default value

Usage Guidelines

• Customized values have the following format:

```
/color,=shape,lpi,angle...
```

for example:

```
/c=r,170,15/m=r,170,75/y=r,170,90/k=r,170,45
```

where:

Indicates the dot color: color

> C Cyan m Magenta Yellow y Black b

shape Indicates the dot shape:

> Round r Combined C 1 Line

ln Line not calibrated

lpi Is the screen frequency in lines per inch. Specify 600 for no screening.

Is the screen angle. angle

If you do not specify a value for this attribute, Infoprint uses the value in the file specified by the rip-ini-file actual destination attribute.

email-from-address

Specifies the electronic mailing address of the sender of this document.

DSS

Email

Resettable, single-valued, per-job

Allowed Values

You can enter a text string up to 4096 characters long that contains the electronic mailing address.

Default Value

No default value

email-to-address

Specifies the electronic mailing address of the recipient of this document.

DSS

Email

Type

Resettable, single-valued, per-job

Allowed Values

You can enter a text string up to 4096 characters long that contains the electronic mailing address.

Default Value

No default value

Usage Guidelines

This value is required for documents submitted to email destinations.

enable-settrap

Indicates whether to turn on trapping for Quark XPress jobs.

GUI Label

Enable Quark SetTrap

DSS

3170

Type

Resettable, single-valued, per-document

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

No default value

Usage Guidelines

- The InfoColor 70 receives composite PostScript jobs. Because Quark XPress cannot change the dimensions of PostScript elements to create chokes and spreads with composite PostScript, it sends PostScript codes to indicate what changes are needed. These changes are called the *settrap operators*.
- If you do not specify a value for this attribute, Infoprint uses the value in the file specified by the **rip-ini-file** actual destination attribute.

fax-number

Specifies the fax number of the recipient of this document.

DSS

Fax

Type

Resettable, single-valued, per-job

Allowed Values

You can enter a text string up to 4096 characters long that contains the fax number.

Default Value

No default value

Usage Guidelines

This value is required for documents submitted to fax destinations.

fax-to-name

Specifies the name of the person to whom this fax document is addressed.

DSS

Fax

Type

Resettable, single-valued, per-job

Allowed Values

You can enter a text string up to 4096 characters long that contains the person's name.

Default Value

No default value

file-name (Document Only)

See document-file-name.

font-fidelity-action

Indicates what Infoprint should do if a font required to print the document is not available in the resolution specified by the data stream, the font-resolution attribute, or the actual destination default-font-resolution attribute.

GUI Label

Font fidelity action

DSS

PSF

Resettable, single-valued, per-job

Allowed Values

You can enter one of these fixed values:

Fixed Value **Explanation**

Stop printing the job. stop

Attempt to substitute a similar font at a different continue

resolution.

Default Value

No default value. If you do not specify a value for this attribute, Infoprint uses the value in the data stream, then the value of the actual destination attribute default-font-fidelity-action.

font-processing-messages

Indicates whether Infoprint should issue messages when it substitutes a font with a different resolution for a font with the resolution specified by the data stream, the font-resolution attribute, or the actual destination default-font-resolution attribute.

GUI Label

Issue font processing messages

DSS

PSF

Type

Resettable, single-valued, per-job

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

false

font-resolution

Identifies the resolution of the fonts used to create this document.

GUI Label

Font resolution

DSS

PSF

Resettable, single-valued, per-job

Allowed Values

You can enter one of these fixed values:

240 300

outline

Default Value

No default value. If there is no font resolution specified in the data stream and you do not specify a value for this attribute, Infoprint uses the value of the actual destination attribute default-font-resolution.

Usage Guidelines

- The font resolution specified in the data stream overrides this attribute.
- Usually the font resolution and the printer resolution match, but there are two cases when they do not:
 - Some printer devices, for example, the Infoprint 60 and Infoprint 4000, can print fonts of any resolution, although the print head is always 600 pels.
 - It is possible to print a document created with fonts of one resolution on a printer with a different resolution by substituting fonts. Depending on the document, the output may or may not be acceptable.

• Infoprint validates and schedules jobs using this attribute against the destination attribute **font-resolutions-supported**.

form-definition

Identifies the form definition used when printing this document.

GUI Label

Form definition

DSS

PSF, Email, Fax, Infoprint 2000

Туре

Resettable, single-valued, per-job

Allowed Values

You can enter a text string of up to 8 characters that contains the identification for this resource.

Default Value

No default value. If you omit this attribute or if it contains no value, and if Infoprint does not create a form definition using the values of other document and job attributes, Infoprint uses the form definition defined by the actual destination attribute **form-definition**.

Usage Guidelines

- For PSF, if you specify a value for the **document-finishing** or **job-finishing** attribute, Infoprint creates its own form definition. Do not specify a value for this attribute.
- Infoprint does not support inline form definitions in multi-document jobs. If you want to print more than one PostScript document in a single job, configure the /usr/lpp/psf/ps2afp/ps2afpd.cfg file to include this line:

```
device controls = any
```

and use this attribute to specify a form definition when you submit the job to print.

• For Infoprint 2000, you can specify job-finishing with or without a form definition. Infoprint does not create a form definition for finishing on the Infoprint 2000.

format

See document-format.

halftone

Identifies the desired combination of screen name, output appearance, and calibration to use for printing halftones.

GUI Label

Halftone

DSS

PSF, Infoprint 2000

Type

Resettable, single-valued, complex, per-document

Syntax

screen-name:output-appearance:saved-calibration

Separate the values with colons, for example: ibm1061pi:dark

The saved-calibration value is used only for custom halftones.

Allowed Values

The value of a **halftone** attribute is a combination of screen name and output appearance in the format: *screen-name:output-appearance*. For custom halftones, the value can also be a combination of screen name, output appearance, and saved calibration in the format: *screen-name:output-appearance:saved-calibration*.

You can enter a customized value or one of these fixed values:

ibm71lpi:standard

ibm71lpi:highlight-midtones

ibm71lpi:dark

ibm85lpi:standard

ibm85lpi:highlight-midtones

ibm85lpi:dark

ibm106lpi:standard

ibm106lpi:highlight-midtones

ibm106lpi:dark

ibm141lpi:standard

ibm141lpi:highlight-midtones

ibm141lpi:dark

You can enter one of the following fixed values if you are using enhanced toner on the Infoprint4000 or Infoprint4000-IR3-IR4 printer:

ibm71lpi:standard.enhtoner

ibm71lpi:highlight-midtones.enhtoner

ibm71lpi:dark.enhtoner

ibm85lpi:standard.enhtoner

ibm85lpi:highlight-midtones.enhtoner

ibm85lpi:dark.enhtoner

ibm106lpi:standard.enhtoner

ibm106lpi:highlight-midtones.enhtoner

ibm106lpi:dark.enhtoner

ibm141lpi:standard.enhtoner

ibm141lpi:highlight-midtones.enhtoner

ibm141lpi:dark.enhtoner

Default Value

No default value

Usage Guidelines

- This document is used only for GIF, JPEG, PDF, PostScript, and TIFF documents.
- Infoprint validates and schedules jobs using this attribute against the actual destination attribute halftones-supported.

image-center-x

Indicates whether to center the image horizontally.

GUI Label

Center image horizontally

DSS

3170

Type

Resettable, single-valued, per-document

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

No default value

Usage Guidelines

- This attribute overrides the **x-image-shift** attribute.
- If you do not specify a value for this attribute, Infoprint uses the value in the file specified by the **rip-ini-file** actual destination attribute.

image-center-y

Indicates whether to center the image vertically.

GUI Label

Center image vertically

DSS

3170

Type

Resettable, single-valued, per-document

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

No default value

Usage Guidelines

- This attribute overrides the **y-image-shift** attribute.
- If you do not specify a value for this attribute, Infoprint uses the value in the file specified by the **rip-ini-file** actual destination attribute.

image-fit

Specifies how Infoprint adjusts a TIFF, GIF, or JPEG image to fit on the printed page.

GUI Label

Image fit

DSS

PSF, Email, Fax, Infoprint 2000

Type

Resettable, single-valued, per-document

Allowed Values

You can specify one of these fixed values: position-and-trim scale-to-fit

Default Value

No default value

Usage Guidelines

- When the value of image-fit is position-and-trim, images larger than the page size are trimmed to fit on any sides that extend beyond the page boundary. For example, if the top left corner of the image is aligned with the top left corner of the logical page, the right side and bottom of the image are trimmed off.
 - Use the **x-image-shift**, **x-image-shift-back**, **y-image-shift**, and **y-image-shift-back** attributes to adjust the positioning of the image on the page. Images smaller than the page size are not changed.
- Images larger than the page size are reduced proportionately in both dimensions to fit. The whole image is preserved, but it is smaller than the original.
 Images smaller than the page size are not changed.
- Infoprint validates and schedules jobs using this attribute against the destination attribute **image-fits-supported**.

image-length

Specifies the length of a page of PostScript, PCL, TIFF, GIF, JPEG, or PDF data after it has been transformed for Infoprint printing.

GUI Label

Finished page length (inches) or (mm)

DSS

PSF, 3170, Email, Fax, Infoprint 2000

Type

Resettable, single-valued, per-document

Allowed Values

The value you specify is in the form *nnnn.nnnu*

nnnn.nnn

is a number that can optionally contain a decimal point.

u is the units in inches (i) or millimeters (m). If you do not specify a unit, the default unit is pels. You cannot use a decimal point when the unit is pels.

For 240-pel resolution printers, valid values are:

 16 - 5280
 pels

 0.067 - 22.000
 inches

 1.701 - 588.852
 millimeters

For 300-pel resolution printers, valid values are:

16 - 6600 pels

0.053 - 22.000 inches **1.346 - 558.852** millimeters

For 480-pel resolution printers, valid values are:

 16 - 10560
 pels

 0.067 - 22.000
 inches

 0.838 - 558.852
 millimeters

For 600-pel resolution printers, valid values are:

 16 - 20400
 pels

 0.267 - 34.000
 inches

 1.346 - 863.6
 millimeters

Default Value

No default value

Usage Guidelines

- This attribute is valid only for GIF, JPEG, PCL, PDF, PostScript, and TIFF documents.
- This attribute is not valid for ASCII documents.
- If a text margin is already built into the file, try **image-length=11i** to set the length to 11 inches.
- For the 3170 DSS, if you do not specify a value for this attribute, Infoprint uses the value in the file specified by the **rip-ini-file** actual destination attribute.

image-out-format

Indicates which type of image data Infoprint produces.

GUI Label

Image out format

DSS

PSF, Infoprint 2000

Type

Resettable, single-valued, per-document

Allowed Values

For PSF, you can enter one of these fixed values:

Fixed Value Explanation

ioca-uncompressed Infoprint produces all image data in the Image

Object Content Architecture (IOCA) uncompressed

format.

im1 Infoprint produces all image data in IBM's IM

uncompressed format. This image format prints on

all Infoprint printers.

io1 Infoprint produces all image data in the Image

Object Content Architecture uncompressed format.

io1-g4 Infoprint produces all image data in the Image

Object Content Architecture compressed G4 Modified Modified Read (MMR) format.

In Committee the control of the cont

io1-mmr Infoprint produces all image data in the Image

Object Content Architecture compressed Modified

Modified Read (MMR) format.

asis

Infoprint produces all image data in the same format as it is in the input file.

For Infoprint 2000, you can only enter this fixed value: io1-g4

Default Value

No default value

Usage Guidelines

- This attribute is valid only for GIF, JPEG, line-data, PCL, PDF, PostScript, and TIFF documents.
- Infoprint validates and schedules jobs using this attribute against the destination attribute **image-out-formats-supported**.

image-scale

Specifies the scaling factor for the image.

GUI Label

Scale (%)

DSS

3170

1.2

Type

Resettable, single-valued, per-document

Allowed Values

You can enter a numeric value from 0 to 2147483647.

The value you specify is in the form *nnnn.nnn*, which is a number that can optionally contain a decimal point. For example, to scale 120%, enter:

Default Value

No default value

Usage Guidelines

If you do not specify a value for this attribute, Infoprint uses the value in the file specified by the **rip-ini-file** actual destination attribute.

image-width

Specifies the width of a page of PostScript, PCL, TIFF, GIF, JPEG, or PDF data after it has been transformed for Infoprint printing.

GUI Label

Finished page width (inches) or (mm)

DSS

PSF, 3170, Email, Fax, Infoprint 2000

Type

Resettable, single-valued, per-document

Allowed Values

The value you specify is in the form *nnnn.nnnu*

nnnn.nnn

is a number that can optionally contain a decimal point.

is the units in inches (i) or millimeters (m). If you do not specify a unit, the default unit is pels. You cannot use a decimal point when the unit is pels.

For 240-pel resolution printers, valid values are:

16 - 5280 pels 0.067 - 17.000 inches millimeters 1.701 - 431.852

For 300-pel resolution printers, valid values are:

16 - 6600 pels 0.053 - 17.000 inches 1.346 - 558.852 millimeters

For 480-pel resolution printers, valid values are:

16 - 10560 pels 0.033 - 17.000 inches 0.838 - 558.852 millimeters

For 600-pel resolution printers, valid values are:

16 - 20400 pels 0.267 - 34.000inches 1.346 - 863.6 millimeters

Default Value

No default value

Usage Guidelines

- This attribute is valid only for GIF, JPEG, PCL, PDF, PostScript, and TIFF documents.
- If a text margin is already built into the file, try image-width=8.5i to set the length to 8.5 inches.
- For the 3170 DSS, if you do not specify a value for this attribute, Infoprint uses the value in the file specified by the rip-ini-file actual destination attribute.

initial-value-document (Document Only)

Identifies a default document (within a given server) that Infoprint uses to create this document.

DSS

All

Initially settable, single-valued, per-document

Allowed Values

You can enter a text string of up to 255 characters that contains the name of the desired default document.

Default Value

No default value

Usage Guidelines

If you specify this attribute, Infoprint uses the attribute values from the default document to set the document attribute values, unless you override the default document attribute values by supplying attribute values at the command line.

initial-value-document-identifier (Default Document Only)

Identifies this default document.

DSS

All

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value to the *DefaultDocumentName* portion of the argument used with the **pdcreate** command when this default document is created.

Default Value

No default value

Usage Guidelines

The value for this attribute must be unique within the server.

input-exit

Specifies the name or the full path name of the input record exit program that Infoprint uses to process this line-data document. With Infoprint Manager for AIX, if you specify the file name without a path, Infoprint searches for the exit program in the paths specified by the **PATH** environment variable. With Infoprint Manager for Windows NT and Windows 2000, you must specify a fully-qualified path name for the exit program. If you do not specify this option, Infoprint does not use an input record exit program.

GUI Label

Input exit program

DSS

PSF, Email, Fax, Infoprint 2000

Type

Resettable, single-valued, per-document

Allowed Values

You can enter any valid input record exit program name. The exit program name is case-sensitive.

Default Value

No default value

Usage Guidelines

- This attribute is valid only for line-data documents.
- If the input file is unformatted ASCII, but the fonts you are using contain EBCDIC, not ASCII, code points (you specify **convert-to-ebcdic=yes**), you can specify:
 - For Infoprint Manager for AIX:

/usr/lpp/psf/bin/apka2e

Converts ASCII stream data to EBCDIC stream data.

/usr/lpp/psf/bin/asciinpe

Converts unformatted ASCII data into a record format and then converts the ASCII stream data to EBCDIC stream data.

- For Infoprint Manager for Windows NT and Windows 2000

\install_path\bin\apka2e

Converts ASCII stream data to EBCDIC stream data.

\install_path\bin\asciinpe

Converts unformatted ASCII data into a record format and then converts the ASCII stream data to EBCDIC stream data.

- If your input file uses fonts that have ASCII code points (you specify **convert-to-ebcdic=no**), you should *not* use the **apka2e** or **asciinpe** exit programs. However, if your unformatted ASCII file contains carriage returns and form feeds, you may want to specify the following exit program supplied with Infoprint:
 - For Infoprint Manager for AIX:

/usr/lpp/psf/bin/asciinp

Converts unformatted ASCII data that contains carriage returns and form feeds into a record format that contains an American National Standards Institute (ANSI) carriage control character. This exit encodes the ANSI carriage control character in byte 0 of every record.

For Infoprint Manager for Windows NT and Windows 2000:

\install path\bin\asciinp

Converts unformatted ASCII data that contains carriage returns and form feeds into a record format that contains an American National Standards Institute (ANSI) carriage control character. This exit encodes the ANSI carriage control character in byte 0 of every record.

input-tray-select

Use the default-input-tray attribute or default to the input tray specified in the data stream or form definition.

DSS

PSF

jog-between-job-copies

Indicates whether to jog stacked output between job copies.

GUI Label

Jog between copies

DSS

PSF

Type

Resettable, single-valued, per-job

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym true yes

false no

Default Value

No default value. If you omit this attribute or it contains no value, output is jogged between job copies on printers that support jog.

Usage Guidelines

This attribute controls whether stacked output is jogged (offset) between job copies. When used on printers that do not support jogging output, the value of this attribute is ignored. When used on printers that do support jogging output, if the value of this attribute is **true** or **yes**, the stacked output is jogged. If the value is **false** or **no**, the output is not jogged.

list-of-managers (Default Document Only)

Lists the people responsible for this default document.

DSS

All

Type

Resettable, multi-valued

Input Synonym

You can use the synonym managers.

Allowed Values

You can enter a text string up to 255 characters long, per value, that contains the name or user ID of the person responsible for this default document.

Default Values

No default values

Usage Guidelines

This attribute is useful if a user needs to contact someone to report a problem or to request a change.

logical-destinations-ready (Default Document Only)

Lists the enabled logical destinations that reference this default document.

DSS

All

Type

Non-settable, multi-valued

Input Synonym

You can use the synonym **logical-printers-ready**.

Allowed Values

Infoprint sets and updates this value with the destination names of the enabled logical destinations that reference this object.

Default Values

No default values

Usage Guidelines

- Infoprint sets this attribute when the destination attribute destination-initialvalue-document of an enabled logical destination references this default document.
- Infoprint removes the destination identification from the list if the destination is disabled.
- You cannot delete this default document while any of the logical destinations identified in this list are enabled.

logical-printers-ready (Default Document Only)

See logical-destinations-ready.

managers (Default Document Only)

See list-of-managers.

maximum-messages-printed

Specifies the maximum number of error messages Infoprint prints with the job.

GUI Label

Maximum messages printed

DSS

PSF, Infoprint 2000

Туре

Resettable, single-valued, per-job

Allowed Values

You can enter an integer from 0 through 9999.

Default Value

9999

Usage Guidelines

- This attribute Identifies how many error messages Infoprint prints, not how many messages Infoprint generates.
- If the value is:

0 No messages print9999 All messages print

maximum-transform-pages-ahead

Specifies the maximum number of pages by which the Infoprint transform programs can get ahead of the printing process.

GUI Label

Maximum pages to transform ahead

DSS

PSF

Type

Resettable, single-valued, per-job

Allowed Values

You can enter an integer from 500 through 2147483647.

Default Value

No default value

Usage Guidelines

- Pages that have been transformed but not printed are stored in a print buffer. Set a value for this attribute to keep the print buffer from overflowing.
- This attribute is not valid for ASCII documents.

message (Default Document Only)

Provides a message associated with this default document.

DSS

All

Type

Resettable, single-valued

Allowed Values

You can enter a text string of up to 4095 characters that contains information about this default document.

Default Value

No default value

mvs-class

For jobs originating on MVS systems and directed to Infoprint through the MVS Download program, this attribute contains the value specified for the MVS class parameter. Infoprint can print the class information on an auxiliary sheet if the job uses the **full** auxiliary-sheet object.

GUI Label

Class

DSS

PSF

Type

Resettable, single-valued, per-job

Allowed Values

You can enter a single alphanumeric character.

Default Value

If you do not specify a class value when you submit the job from the MVS system, MVS defaults the value of the **class** parameter to **A**.

Usage Guidelines

- See the *Print Services Facility/MVS: MVS Download Guide* for further information, including restrictions, on the MVS **class** parameter.
- You can use this attribute within a shell script used with MVS Download.

mvs-destination

For jobs originating on MVS systems and directed to Infoprint through the MVS Download program, this attribute contains the value specified for the MVS **dest** parameter. Infoprint can print the destination information on an auxiliary sheet if the job uses the **full** auxiliary-sheet object.

GUI Label

Destination

DSS

PSF

Type

Resettable, single-valued, per-job

Allowed Values

You can enter a one-to-eight character destination name.

Default Value

No default value

Usage Guidelines

- See the *Print Services Facility/MVS: MVS Download Guide* for further information, including restrictions, on the MVS **dest** parameter.
- You can use this attribute within a shell script used with MVS Download.

mvs-forms

For jobs originating on MVS systems and directed to Infoprint through the MVS Download program, this attribute contains the value specified for the MVS **forms** parameter. Infoprint can print the forms information on an auxiliary sheet if the job uses the **full** auxiliary-sheet object.

GUI Label

Forms

DSS

PSF

Type

Resettable, single-valued, per-job

Allowed Values

You can enter a one-to-eight character form name.

Default Value

If you do not specify a forms value when you submit the job from the MVS system, MVS defaults the value of the **forms** parameter to an installation-defined default.

Usage Guidelines

- See the *Print Services Facility/MVS: MVS Download Guide* for further information on the MVS **forms** parameter.
- You can use this attribute within a shell script used with MVS Download.

mvs-segment-id

For line-mode data jobs originating on MVS systems and directed to Infoprint through the MVS Download program, this attribute contains the value specified for the MVS **segment** parameter. The **segment** parameter specifies that output data is segmented into separate data sets consisting of the number of pages specified by the parameter value. The MVS Download program transmits each data set separately.

GUI Label

Segment ID

DSS

PSF

Type

Resettable, single-valued, per-job

Allowed Values

You can enter a one-to-ten character segment identifier representing the page count.

Default Value

No default value

Usage Guidelines

- See the *Print Services Facility/MVS: MVS Download Guide* for further information, including restrictions, on the MVS **segment** parameter.
- · You can use this attribute within a shell script used with MVS Download.

name-text

Specifies name information that Infoprint prints in the **NAME**: field of an auxiliary sheet if the job uses the **full** auxiliary-sheet object.

GUI Label

Name

DSS

PSF

Type

Resettable, single-valued, per-job

Allowed Values

You can enter a text string of up to 4095 characters that contains the name information.

Default Value

No default value

Usage Guidelines

- While you can specify more characters, you should limit the value you supply to 24 characters or less to ensure that there is enough room available on the printed page for all name information.
- If the text string you specify contains blank spaces, enclose the text string in single quotation marks.

new-line-option

Identifies how the document input data delimits lines.

GUI Label

New line option

DSS

PSF, Email, Fax, Infoprint 2000

Type

Resettable, single-valued, per-document

Allowed Values

You can enter one of these fixed values:

Fixed Value FILEFORMAT

two bytes RECORD (S/370 format record)

lf STREAM

record, n **RECORD**, n (S/370 format record data where each

line is *n* bytes long)

n is an integer from 1 to 32767

Default Value

16

Usage Guidelines

- This attribute is valid only for line-data documents.
- This attribute corresponds to the **fileformat** print submission parameter information for the **line2afp** transform.

node-id-text

Specifies node-identification information that Infoprint prints in the **NODEID:** field of an auxiliary sheet.

GUI Label

Node ID

DSS

PSF

Type

Resettable, single-valued, per-job

Allowed Values

You can enter a text string of up to 4095 characters that contains the node-identification information.

Default Value

No default value

Usage Guidelines

- While you can specify more characters, you should limit the value you supply to 10 characters or less to ensure that there is enough room available on the printed page for all node-identification information.
- If the text string you specify contains blank spaces, enclose the text string in single quotation marks.

number-up

Specifies the number of pages to print on a single side of the paper when the value of the **output-format** attribute is **side-by-side-copies** or **simple-n-up**.

GUI Label

Number up

DSS

PSF, Email, Fax, Infoprint 2000

Type

Resettable, single-valued, per-job

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym imposition-simple-1-up 1up imposition-simple-2-up 2up imposition-simple-3-up 3up imposition-simple-4-up 4up

Default Value

No default value

Usage Guidelines

- In two-sided jobs, the number of pages printed on each sheet is twice the number-up value.
- This attribute is not valid for ASCII documents.
- If you specify a value for the document form-definition attribute, Infoprint ignores the **number-up** attribute and uses the number-up value in the form definition.
- Infoprint validates and schedules jobs using this attribute against the destination attribute number-up-supported.

object-class

Identifies the object class to which this object belongs.

DSS

All

Type

Non-settable, single-valued, per-job

Allowed Values

Infoprint sets this value to document for a document or to initial-value-document for a default document.

Default Value

Document document

initial-value-document Default document

octet-count (Document Only)

Specifies the document size in octets (bytes).

GUI Label

Size (KBytes)

DSS

All

Non-settable, single-valued, per-document

Allowed Values

Infoprint computes this value when the it creates the document. The value can be an integer from 0 to 9223372036854775800.

Default Value

The size of the document in bytes (octets).

Usage Guidelines

- · Infoprint uses this attribute to compute total octet count for a job and to provide information about this document.
- For jobs consisting of two or more documents, you can query for the octet count of each document in the job by specifying -r octet-count with the pdls command.

offset-stacking-between-job-copies

See jog-between-job-copies.

orientation

See content-orientation.

originating-company-text

Specifies the name of the sending company that appears on the fax cover sheet.

DSS

Fax

Type

Resettable, single-valued, per-job

Allowed Values

You can enter a text string up to 4095 characters long that contains the name of the sending company.

Default Value

No default value

other-options

See destination-pass-through.

other-transform-options

Allows you to submit options for the transform that converts this document to the AFP data stream.

GUI Label

Transform options

DSS

PSF, Email, Fax, Infoprint 2000

Type

Resettable, single-valued, per-document

Allowed Values

You can enter a text string of up to 4095 characters that contains the transform options.

Default Value

No default value

Usage Guidelines

See "Chapter 6. Infoprint Transform Commands" on page 203 for information about transform options.

output-appearance

Use the **halftones** attribute to specify the **output-appearance** attribute values. (See "halftone" on page 496 for more information.) The **output-appearance** attribute is supported to maintain downward compatibility, but it is not the recommended attribute for specifying the desired style of the printed document.

Identifies the desired style of the printed document.

DSS

PSF (AIX Only)

Type

Resettable, single-valued, per-document

Allowed Values

You can enter a customized value or one of these fixed values: standard highlight-midtones dark

Default Value

No default value

Usage Guidelines

- This attribute is valid only for GIF, JPEG, PDF, PostScript, and TIFF documents.
- Infoprint validates and schedules jobs using this attribute against the destination attribute output-appearances-supported.

output-bin

Specifies the name of the output bin to which you want Infoprint to direct the output from your job.

GUI Label

Output bin requested

DSS

PSF, 3170, Infoprint 2000

Resettable, single-valued, per-document

Allowed Values

You can enter an output bin name of up to 255 characters that contains the name of an output bin, such as top or staple.

Default Value

No default value

Usage Guidelines

- The value you specify for the **output-bin** attribute overrides any output bin specified in the form definition Infoprint uses to process the job.
- This attribute is valid for ASCII documents within a job only if it is not changed between documents in the job.

- For PSF, Infoprint validates and schedules jobs using this attribute against the output-bins-supported actual destination attribute, which Infoprint sets according to the values supplied for the output-bin-numbers PSF actual destination attribute.
- For PSF, Infoprints maps the value to an actual bin number using the actual destination attribute output-bin-numbers.
- For 3170, if you do not specify a value for this attribute, Infoprint uses the value in the file specified by the rip-ini-file actual destination attribute.
- For Infoprint 2000,
 - If you don't specify this attribute or the job finishings=booklet-stitch-andfold or the booklet-stitch-fold-and-trim attribute, Infoprint uses the output bin specified in the destination attribute.
 - If a job requests stapling or some other finishing, the job goes to the appropriate finishing output bin regardless of what output bin is specified with the **output-bin** attribute.
 - If a job specifies a finishing output bin and no finishing is specified, the job is printed and sent to the top bin.

output-face-up

Indicates whether to start the document on the side of the sheet that faces up in the output bin.

GUI Label

Start face down

DSS

3170

Resettable, single-valued, per-document

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

No default value

Usage Guidelines

- A value of **true** for this attribute corresponds to a value of **0** for the outputfaceup keyword in the .ini file and results in face-up output. A value of false for this attribute corresponds to a value of 1 for the outputfaceup keyword in the .ini file and results in face-down output.
- You may want to specify true for this attribute when the value of the actual destination attribute reverse-output is true so that pages will be collated in the right order.
- When printing multiple-document duplex jobs, use this attribute to control whether a document starts on a new sheet. For example, if you specify output-face-up=false for the first document in the job, which is 3 pages long, specify output-face-up=false for the second document to make it start on a new sheet. Specify output-face-up=true for the second document to make it start on the reverse of the last page of the first document. If you specify the same value

for all the documents in the job, they will all start on new sheets whether the preceding document has an odd or even number of pages.

If you do not specify a value for this attribute, Infoprint uses the value in the file specified by the rip-ini-file actual destination attribute.

output-format

Used with the **number-up** attribute to specify how pages should be imposed on a sheet of paper.

GUI Label

Layout format

DSS

PSF, Email, Fax, Infoprint 2000

Resettable, single-valued, per-job

Allowed Values

You can specify one of these fixed values: side-by-side-copies

simple-n-up

booklet-print

booklet-print-with-integrated-cover

slit-and-merge

Note: You can only specify simple-n-up with the PSF DSS for Windows NT and Windows 2000.

Default Value

No default value

Usage Guidelines

- side-by-side-copies and simple-n-up both print as many pages on one sheet as the **number-up** value allows.
 - side-by-side-copies prints multiple copies of one page on the sheet.
 - **simple-n-up** prints multiple pages on the sheet in numerical order.
- booklet-print and booklet-print-with-integrated-cover arrange pages like this:

Page 2	Page n-1
backed by	backed by
Page 1	Page n

so that when the sheet is folded in half and collated with the rest of the booklet, the pages appear in sequence.

To print a booklet with a cover, specify insert as the document format of the first document in the job.

Note: When the Infoprint server adds blank pages to the job to make it a multiple of four with **booklet-print-with-integrated-cover**, Infoprint adds the blank pages inside of the back cover.

For PSF, to saddle-stitch the booklet, specify a value of saddle-stitch for the job-finishing job attribute.

For Infoprint 2000, specify **job-finishing=booklet-stitch-and-fold** or **booklet-stitch-fold-and-trim** to send the booklet to the bookletmaker finishing device.

booklet-print does not require a value for number-up.

• slit-and-merge arranges pages like this:

Page 1	Page 3
backed by	backed by
Page 2	Page 4

so that when the sheet is cut in half and the left half is stacked on top of the right half, the pages appear in sequence.

slit-and-merge does not require a value for number-up.

- You can specify one-sided or two-sided printing and simplex or tumble with any
 of these formats except booklet-print.
- This attribute is not valid for ASCII or KGL documents, or any combination of these documents.
- If you specify a value for the document **form-definition** attribute, Infoprint ignores the **output-format** attribute and uses the value in the form definition.
- Infoprint validates and schedules jobs using this attribute against the destination attribute **output-format-supported**.

overlay

Specifies the name of an overlay that Infoprint uses for each sheet-side in the document. An overlay contains predefined data, such as lines, shading, text, boxes, or logos that can merge with variable data on a page.

GUI Label

Medium overlay

DSS

PSF, Email, Fax, Infoprint 2000

Type

Resettable, single-valued, per-job

Allowed Values

You can enter an overlay name up to eight characters in length.

Default Value

No default value

Usage Guidelines

- This overlay prints in addition to any overlay specified by the form definition for the job, and in addition to the overlays specified in the overlay-front and overlay-back attributes.
- This attribute is valid for ASCII documents within a job only if it is not changed between documents in the job.

overlay-back

Specifies the name of an overlay that Infoprint uses for the back of each sheet in the document. An overlay contains predefined data, such as lines, shading, text, boxes, or logos that can merge with variable data on a page.

GUI Label

Medium overlay for back side

PSF, Email, Fax, Infoprint 2000

Type

Resettable, single-valued, per-job

Allowed Values

You can enter an overlay name up to eight characters in length.

Default Value

No default value

Usage Guidelines

- This attribute is not valid for ASCII documents.
- This overlay prints in addition to any overlay specified by the form definition for the job, and in addition to any overlays specified in the overlay and overlay-front attributes.

overlay-front

Specifies the name of an overlay that Infoprint uses for the front of each sheet in the document. An overlay contains predefined data, such as lines, shading, text, boxes, or logos that can merge with variable data on a page.

GUI Label

Medium overlay for front side

DSS

PSF, Email, Fax, Infoprint 2000

Resettable, single-valued, per-job

Allowed Values

You can enter an overlay name up to eight characters in length.

Default Value

No default value

Usage Guidelines

- This attribute is not valid for ASCII documents.
- This overlay prints in addition to any overlay specified by the form definition for the job, and in addition to any overlays specified in the overlay and overlay-back attributes.

overprint

Indicates how to handle overprinting.

GUI Label

Overprint

DSS

3170

Type

Resettable, single-valued, per-document

Allowed Values

You can enter one of these fixed values:

overprint-on Render objects as if they would truly overprint

each other

overprint-off Ignore overprinting

overprint-from-postscript Handle overprinting according to PostScript

specifications, knocking out in separations where

the object applies ink

Default Value

No default value

Usage Guidelines

If you do not specify a value for this attribute, Infoprint uses the value in the file specified by the **rip-ini-file** actual destination attribute.

page-clip

Indicates how to clip images that are too wide for the page.

GUI Label

Clipping

DSS

3170

Type

Resettable, single-valued, per-document

Allowed Values

You can enter one of these fixed values:

center-clip Center the image horizontally and clip both sides

right-clip Clip the right side of the image

error Issue an error message and end the job

Default Value

No default value

Usage Guidelines

If you do not specify a value for this attribute, Infoprint uses the value in the file specified by the **rip-ini-file** actual destination attribute.

page-count (Document Only)

Specifies the estimated length of the document in pages.

GUI Label

Page count

DSS

All

Type

Resettable, single-valued, per-document

Allowed Values

You can enter an integer from 1 through 2147483647.

Default Value

When Infoprint can determine a page count from the PostScript or PCL input, Infoprint sets the page count in this attribute.

Usage Guidelines

 Infoprint determines the size of a job based on the total number of octets (bytes) in the job. For operator job-management purposes, you may find that job size based on pages is easier.

Note: When Infoprint can not estimate document or job size in pages or use the page-count value you specify, the value for the page-count attribute should closely represent the actual number of pages in one copy of the document if the operator is to make valid decisions based on page count.

 Infoprint uses the value specified with the page-count attribute and the value specified with the **copy-count** document attribute (and the **job-copies** component in the results-profile) to calculate the value for the job-page-count attribute.

page-definition

Identifies the page definition used when printing a line-data document.

GUI Label

Page definition

DSS

PSF, Email, Fax, Infoprint 2000

Resettable, single-valued, per-document

Allowed Values

You can enter a text string of up to 8 characters that contains the name of the desired page-definition resource.

Default Value

No default value

Usage Guidelines

You must supply a value for this attribute for line-data documents. It is not valid for any other document format.

page-media-select

Use the **default-medium** attribute or default to the medium specified in the data stream or form definition.

DSS

PSF

page-select (Document Only)

Specifies the first and last page of a document that Infoprint prints.

GUI Label

Pages to process

PSF, Email, Fax, Infoprint 2000

Type

Resettable, single-valued, complex, per-document

Syntax

first-page:last-page

Separate the values with a colon, for example:

25:48

You can omit the first-page value or the last-page value, for example:

:6

10:

See "Usage Guidelines".

Components

first-page: Specifies the number of the page where printing starts.

GUI Label: Lower limit

Type: Single-valued

Allowed Values: You can enter a value of 1 through 2147483647.

Default Value: No default value

last-page: Specifies the number of the page where printing ends.

GUI Label: Upper limit

Type: Single-valued

Allowed Values: You can enter a value of 1 through 2147483647.

Default Value: No default value

Usage Guidelines

- Page numbering always starts at one, (1) even if the job you print uses an alternate numbering system, such as roman numerals or folio-by-chapter (1-1, 1-2, and so on) numbering. You cannot request a range of pages using page numbers from an alternate numbering system.
- This attribute is not valid for ASCII, KGL, metacode, or lcds documents.
- If you omit the first-page value, for example :6, Infoprint prints from the first page of the job through page 6.
- If you omit the last-page value, for example **6**:, Infoprint prints from page 6 through the last page of the job.
- Entering a combination of first-page last-page values where the first-page value is greater than the last-page value is an error.
- If Infoprint cannot find the first-page value in the document, no pages print and Infoprint issues an error.
- If Infoprint cannot find the last-page value in the document, it prints pages from first-page value to the end of the document. Infoprint does not issue an error.

plex

Indicates whether Infoprint conditions the page images of this document for one-sided or two-sided printing and the relative orientation of consecutive pages.

GUI Label

Plex to print

DSS

AIX, BSD, PSF, 3170, Infoprint 2000

Resettable, single-valued, per-document

Allowed Values

You can enter one of these fixed values:

simplex tumble

Default Value

The first value listed in the destination attribute plexes-supported

BSD No default value

2000 simplex PSF simplex

No default value 3170

Usage Guidelines

- · Infoprint validates and schedules jobs using this attribute against the destination attribute plexes-supported.
- This attribute is valid for ASCII documents within a job only if it is not changed between documents in the job.
- Infoprint uses this attribute in combination with the sides attribute. The results are:

plex Value	sides Value	Output
simplex	1	Simplex
simplex	2	Duplex
tumble	1	Not valid
tumble	2	Tumble duplex

- Infoprint uses plex specifications in this order:
 - 1. The plex document attribute unless you specify different values for this attribute for each document in a job, and also specify a value for the document form-definition attribute. In that case, Infoprint ignores the plex document attribute.
 - 2. For the 3170 DSS, the value in the file specified by the rip-ini-file actual destination attribute.
 - 3. The plex specification in the document or default document form definition.
 - 4. The plex specification in the actual destination form definition.
 - 5. **plex** actual destination attribute.

print-quality

Specifies the desired output quality of the printed document.

GUI Label

Print quality

DSS

AIX, BSD

Type

Resettable, single-valued, per-document

Allowed Values

You can enter one of these fixed values: draft high normal

Default Value

normal

Usage Guidelines

Infoprint validates and schedules jobs using this attribute against the destination attribute print-qualities-supported.

printer-initial-value-document (Document Only)

See destination-initial-value-document.

printer-pass-through

See destination-pass-through.

programmer-text

Specifies programmer information that Infoprint prints in the PROGRAMMER: field of an auxiliary sheet if the job uses the full auxiliary-sheet object.

GUI Label

Programmer

DSS

PSF

Resettable, single-valued, per-job

Allowed Values

You can enter a text string of up to 4095 characters that contains the programmer information.

Default Value

No default value

Usage Guidelines

- While you can specify more characters, you should limit the value you specify to 24 characters or less to ensure that there is enough room available on the printed page for all programmer information.
- If the text string you specify contains blank spaces, enclose the text string in single quotation marks.

resource-context

Defines the directory path location for all document-specific resources: fonts, form definitions, overlays, page definitions, and page segments.

GUI Label

Location of resources

PSF, Email, Fax, Infoprint 2000

Type

Resettable, single-valued, per-job

Allowed Values

You can enter the name of a resource-context object or a text string of up to 255 characters that contains a specific directory path name for resources.

Syntax

path:path on AIX path;path on Windows NT or Windows 2000

Separate multiple paths with a colon on AIX or a semicolon on Windows NT or Windows 2000, for example with AIX:

/res:/dept123/res

Default Value

With AIX, no default values, but Infoprint always searches /usr/lpp/psf/reslib.

With Windows NT or Windows 2000, no default values, but Infoprint always searches \install_path\reslib.

Usage Guidelines

- Because Infoprint searches the path specified by this attribute after the individual paths for different types of resources, you can use this attribute to locate default resources.
- You can use this attribute instead of specifying individual values for:

color-mapping-table

resource-context-font

resource-context-form-definition

resource-context-overlay

resource-context-page-definition

resource-context-page-segment

- Infoprint searches paths in this order:
 - 1. **color-mapping-table** document attribute
 - 2. resource-context-user document attribute
 - 3. resource-context-font, resource-context-form-definition, resource-context-overlay, resource-context-page-definition, or resource-context-page-segment document attribute, as appropriate for the type of resource
 - 4. resource-context document attribute
 - 5. **PSFPATH** environment variable
 - 6. resource-context-font, resource-context-form-definition, resource-context-overlay, resource-context-page-definition, or resource-context-page-segment actual destination attribute, as appropriate for the type of resource
 - 7. With AIX:
 - a. /usr/lpp/psf/reslib
 - b. /usr/lpp/afpfonts
 - c. /usr/lpp/psf/fontlib

- 8. With Windows NT or Windows 2000, where install_path indicates the path where you installed Infoprint Manager:
 - a. \install_path\reslib
 - b. \install_path\afpfonts
 - c. \install_path\fontlib
- If Infoprint cannot find the resource because none of the paths contain the resource, it still processes the job and prints error messages at the end of the job. Infoprint reports the job as completed.

resource-context-font

Defines the directory path location of the document-specific fonts.

GUI Label

Location of fonts

DSS

PSF, Email, Fax, Infoprint 2000

Resettable, single-valued, per-job

Allowed Values

You can enter the name of a resource-context object or a text string of up to 255 characters that contains a specific directory path name for fonts.

Syntax

path:path on AIX path;path on Windows NT or Windows 2000

Separate multiple paths with a colon on AIX or a semicolon on Windows NT or Windows 2000, for example with AIX:

/fonts:/dept123/fonts

Default Value

With AIX, no default values, but Infoprint always searches /usr/lpp/psf/reslib.

With Windows NT or Windows 2000, no default values, but Infoprint always searches \install_path\reslib.

Usage Guidelines

- You can specify fonts either within the job or in a page definition for the job.
- Infoprint searches paths in this order:
 - 1. resource-context-user document attribute
 - 2. resource-context-font document attribute
 - 3. **resource-context** document attribute
 - 4. **PSFPATH** environment variable
 - 5. **resource-context-font** actual destination attribute
 - 6. With AIX:
 - a. /usr/lpp/psf/reslib
 - b. /usr/lpp/afpfonts
 - c. /usr/lpp/psf/fontlib
 - 7. With Windows NT or Windows 2000, where install_path indicates the path where you installed Infoprint Manager:
 - a. \install_path\reslib

- b. \install_path\afpfonts
- c. \install_path\fontlib
- If Infoprint cannot find the resource because none of the paths contain the resource, it still processes the job and prints error messages at the end of the job. Infoprint reports the job as completed.

resource-context-form-definition

Defines the directory path location of the document-specific form definitions.

GUI Label

Location of form definitions

DSS

PSF, Email, Fax, Infoprint 2000

Resettable, single-valued, per-job

Allowed Values

You can enter the name of a resource-context object or a text string of up to 255 characters that contains a specific directory path name for form definitions.

Syntax

path:path on AIX path;path on Windows NT or Windows 2000

Separate multiple paths with a colon on AIX and a semicolon on Windows NT or Windows 2000, for example with AIX:

/form definition:/dept123/form definition

Default Value

With AIX, no default values, but Infoprint always searches /usr/lpp/psf/reslib.

With Windows NT or Windows 2000, no default values, but Infoprint always searches \install_path\reslib.

Usage Guidelines

- You can use either the document or the actual destination form-definition attribute to specify the form definition.
- Infoprint searches paths in this order:
 - 1. resource-context-user document attribute
 - 2. resource-context-form-definition document attribute
 - 3. resource-context document attribute
 - 4. **PSFPATH** environment variable
 - 5. **resource-context-form-definition** actual destination attribute
 - 6. For Infoprint Manager for AIX, /usr/lpp/psf/reslib; for Infoprint Manager for Windows NT and Windows 2000, \install_path\reslib.
- If Infoprint cannot find the resource because none of the paths contain the resource, it still processes the job and prints error messages at the end of the job. Infoprint reports the job as completed.

resource-context-overlay

Defines the directory path location of the document-specific overlays.

GUI Label

Location of overlays

DSS

PSF, Email, Fax, Infoprint 2000

Type

Resettable, single-valued, per-job

Allowed Values

You can enter the name of a resource-context object or a text string of up to 255 characters that contains a specific directory path name for overlays.

Syntax

path:path on AIX path;path on Windows NT or Windows 2000

Separate multiple paths with a colon on AIX and a semicolon on Windows NT or Windows 2000, for example with AIX:

/overlay:/dept123/overlay

Default Value

With AIX, no default values, but Infoprint always searches /usr/lpp/psf/reslib.

With Windows NT or Windows 2000, no default values, but Infoprint always searches \install_path\reslib.

Usage Guidelines

- You use a form definition for the job to specify the overlay.
- Infoprint searches paths in this order:
 - 1. resource-context-user document attribute
 - 2. resource-context-overlay document attribute
 - 3. **resource-context** document attribute
 - 4. **PSFPATH** environment variable
 - 5. resource-context-overlay actual destination attribute
 - 6. For Infoprint Manager for AIX, /usr/lpp/psf/reslib; for Infoprint Manager for Windows NT and Windows 2000, \install_path\reslib.
- If Infoprint cannot find the resource because none of the paths contain the resource, it still processes the job and prints error messages at the end of the job. Infoprint reports the job as completed.

resource-context-page-definition

Defines the directory path location for the document-specific page definitions.

GUI Label

Location of page definitions

DSS

PSF, Email, Fax, Infoprint 2000

Type

Resettable, single-valued, per-document

Allowed Values

You can enter the name of a resource-context object or a text string of up to 255 characters that contains a specific directory path name for page definitions.

Syntax

```
path:path on AIX
path;path on Windows NT or Windows 2000
```

Separate multiple paths with a colon on AIX and a semicolon on Windows NT or Windows 2000, for example with AIX:

/page definition:/dept123/page definition

Default Value

With AIX, no default values, but Infoprint always searches /usr/lpp/psf/reslib.

With Windows NT or Windows 2000, no default values, but Infoprint always searches \install_path\reslib.

Usage Guidelines

- This attribute is valid only for line-data documents.
- You use the page-definition document attribute to specify the page definition for the job.
- Infoprint searches paths in this order:
 - 1. resource-context-user document attribute
 - 2. resource-context-page-definition document attribute
 - 3. **resource-context** document attribute
 - 4. **PSFPATH** environment variable
 - 5. resource-context-page-definition actual destination attribute
 - 6. For Infoprint Manager for AIX, /usr/lpp/psf/reslib; for Infoprint Manager for Windows NT and Windows 2000, \install_path\reslib.
- If Infoprint cannot find the resource because none of the paths contain the resource, it still processes the job and prints error messages at the end of the job. Infoprint reports the job as completed.

resource-context-page-segment

Defines the directory path location of the document-specific page segments.

GUI Label

Location of page segments

PSF, Email, Fax, Infoprint 2000

Type

Resettable, single-valued, per-job

Allowed Values

You can enter the name of a resource-context object or a text string of up to 255 characters that contains a specific directory path name for page segments.

Syntax

```
path:path for AIX
path;path for Windows NT or Windows 2000
```

Separate multiple paths with a colon on AIX and a semicolon on Windows NT or Windows 2000, for example with AIX:

/page segment:/dept123/page segment

Default Value

With AIX, no default values, but Infoprint always searches /usr/lpp/psf/reslib.

With Windows NT or Windows 2000, no default values, but Infoprint always searches \install_path\reslib.

Usage Guidelines

- You specify the page segments within the job.
- Infoprint searches paths in this order:
 - 1. resource-context-user document attribute
 - 2. resource-context-page-segment document attribute
 - 3. resource-context document attribute
 - 4. **PSFPATH** environment variable
 - 5. resource-context-page-segment actual destination attribute
 - 6. For Infoprint Manager for AIX, /usr/lpp/psf/reslib; for Infoprint Manager for Windows NT and Windows 2000, \install_path\reslib.
- If Infoprint cannot find the resource because none of the paths contain the resource, it still processes the job and prints error messages at the end of the job. Infoprint reports the job as completed.

resource-context-presentation-object-container

Defines the directory paths that Infoprint searches for presentation object containers (or called data object resources in the *IPDS Reference*), such as EPS, IOCA images, or PDF pages, for the document.

GUI Label

Location of presentation object containers

DSS

PSF

Type

Resettable, single-valued

Allowed Values

You can enter the name of a resource-context-presentation object or a text string up to 255 characters long that defines the directory path to the resource-context-presentation object.

Syntax

path:path for AIX

path;path for Windows NT or Windows 2000

Separate path names with colons on AIX, for example:

/dor:/dept123/presentation-object-container

Separate path names with semicolons on Windows NT or Windows 2000, for example:

d:\dor;d:\dept123\presentation-object-container

Default Value

With AIX, no default values, but Infoprint always searches /usr/lpp/psf/reslib.

With Windows NT or Windows 2000, no default values, but Infoprint always searches \install_path\reslib.

Usage Guidelines

- You specify the presentation objects within the job.
- Infoprint searches paths in this order:
 - 1. resource-context-user document attribute
 - 2. resource-context-presentation-object-container document attribute
 - 3. **resource-context** document attribute
 - 4. **PSFPATH** environment variable
 - 5. resource-context-presentation-object-container actual destination attribute
 - 6. For AIX, /usr/lpp/psf/reslib
 - 7. For Windows NT or Windows 2000, \install_path\reslib
- If Infoprint cannot find the resource because none of the paths contain the resource, it still processes the job and prints error messages at the end of the job. Infoprint reports the job as completed.

resource-context-user

Defines the directory path location for all document-specific resources: fonts, form definitions, overlays, page definitions, and page segments.

GUI Label

Location of document resources

PSF, Email, Fax, Infoprint 2000

Type

Resettable, single-valued, per-document

Allowed Values

You can enter the name of a resource-context object or a text string of up to 255 characters that contains a specific directory path name for resources.

Syntax

path:path for AIX path;path for Windows NT or Windows 2000

Separate multiple paths with a colon on AIX and a semicolon on Windows NT or Windows 2000, for example with AIX:

/res:/dept123/res

Default Value

With AIX, no default values, but Infoprint always searches /usr/lpp/psf/reslib.

With Windows NT or Windows 2000, no default values, but Infoprint always searches \install_path\reslib.

Usage Guidelines

- This attribute is valid only for line-data documents.
- You should use this attribute only to migrate the PSF for AIX job script keyword userlib.
- Infoprint searches paths in this order:
 - 1. resource-context-user document attribute
 - 2. resource-context-font, resource-context-form-definition, resource-context-overlay, resource-context-page-definition, or resource-context-page-segment document attribute, as appropriate for the type of resource

- 3. **resource-context** document attribute
- 4. **PSFPATH** environment variable
- resource-context-font, resource-context-form-definition, resource-context-overlay, resource-context-page-definition, or resource-context-page-segment actual destination attribute, as appropriate for the type of resource
- 6. With AIX:
 - a. /usr/lpp/psf/reslib
 - b. /usr/lpp/afpfonts
 - c. /usr/lpp/psf/fontlib
- 7. With Windows NT or Windows 2000, where *install_path* indicates the path where you installed Infoprint Manager:
 - a. \install_path\reslib
 - b. \install_path\afpfonts
 - c. \install_path\fontlib
- If Infoprint cannot find the resource because none of the paths contain the resource, it still processes the job and prints error messages at the end of the job. Infoprint reports the job as completed.

resource-exit

Specifies the name or the full path name of the resource exit program that Infoprint uses to retrieve resources for this line-data document. If you specify the file name without a path, Infoprint searches for the exit program in the paths specified by the **PATH** environment variable. If you do not specify this option, the Infoprint does not use a resource exit program.

GUI Label

Resource exit program

DSS

PSF, Infoprint 2000

Type

Resettable, single-valued, per-document

Allowed Values

You can enter any valid input record exit program name. The exit program name is case-sensitive.

Default Value

No default value

Usage Guidelines

This attribute is valid only for line-data documents.

room-text

Specifies room information that Infoprint prints in the **ROOM**: field of an auxiliary sheet if the job uses the **full** auxiliary-sheet object.

GUI Label

Room

DSS

PSF

Type

Resettable, single-valued, per-job

Allowed Values

You can enter a text string of up to 4095 characters that contains the room information.

Default Value

No default value

Usage Guidelines

- While you can specify more characters, you should limit the value you supply to 24 characters or less to ensure that there is enough room available on the printed page for all room information.
- If the text string you specify contains blank spaces, enclose the text string in single quotation marks.

scanner-correction

Indicates how you calibrated the scanner used to scan input images so that Infoprint can make the appropriate modifications to halftones.

GUI Label

Scanner correction

DSS

PSF (AIX Only)

Type

Resettable, single-valued, per-document

Allowed Values

You can enter one of these fixed values:

Ricoh420 XeroxDocuimage620S none

Default Value

No default value

Usage Guidelines

- This attribute is valid only for GIF, JPEG, PDF, PostScript, and TIFF documents.
- Infoprint validates and schedules jobs using this attribute against the destination attribute scanner-corrections-supported.

screen-frequency

Use the **halftones** attribute to specify the **screen-frequency** attribute values. (See "halftone" on page 496 for more information.) The **screen-frequency** attribute is supported to maintain downward compatibility, but it is not the recommended attribute for specifying the screen frequency to use for printing halftones.

Indicates the screen frequency, in lines per inch, to use for printing halftones.

DSS

PSF (AIX Only)

Type

Resettable, single-valued, per-document

Allowed Values

You can enter one of these fixed values:

85

106

141

Default Value

85

Usage Guidelines

- This attribute is valid only for GIF, JPEG, PDF, PostScript, and TIFF documents.
- · Change the screen frequency if you see moire or two-dimensional repeating patterns in halftone images.
- Set the screen frequency to 106 if you see dark and light bands in printed output, with halftone images possibly showing a herringbone pattern under magnification.
- · Infoprint validates and schedules jobs using this attribute against the destination attribute screen-frequencies-supported.

segment-file-size

Specifies the minimum size in kilobytes of the segment files into which Infoprint breaks jobs for processing.

GUI Label

Size of segment file (KBytes)

DSS

PSF

Resettable, single-valued, per-job

Allowed Values

You can enter an integer from 1 to 102400.

Default Value

100

Usage Guidelines

- Small values can adversely affect performance; large numbers can detract from Infoprint's ability to send the beginning of a job to a destination while still processing the remainder of the job.
- This attribute is not valid for ASCII documents.

sequence-number (Document Only)

See document-sequence-number.

shared-formdef

For MO:DCA-P documents originating on MVS systems and directed to Infoprint through the MVS Download program, this attribute Indicates whether the form definition used to print or transmit this document should be processed the same way as PSF/MVS would process it.

GUI Label

Process form definitions same as MVS

PSF, Email, Fax, Infoprint 2000

Type

Resettable, single-valued, per-job

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

Default job No default value

false Job

Usage Guidelines

- A value of true ensures consistent page placement when multiple pages are printed or transmitted on a single side of the sheet.
- · If the document was created with a form definition defined specifically for the PSF DSS or for PSF for AIX, specify false.

shift-out-shift-in

Specifies the printer scanning modes used when processing EBCDIC line-data that prints with either a single-byte or a double-byte font.

GUI Label

Shift-out shift-in processing

DSS

PSF, Email, Fax, Infoprint 2000

Resettable, single-valued, per-document

Allowed Values

You can enter an 8-character alphanumeric string, which is passed to all ACIF user exits, or one of these fixed values:

Fixed Value **Explanation**

one The line2afp transform uses a value of SOSI1 for

the prmode= parameter. It converts each shift-out, shift-in code to a blank and a Set Coded Font Local

text control.

two The line2afp transform uses a value of SOSI2 for

> the **prmode=** parameter. It converts each shift-out, shift-in code to a Set Coded Font Local text control.

See "line2afp Command: Transforms S/370 Line Data and ASCII Data to AFP" on page 239 for more information about the prmode= parameter of the line2afp transform. Refer to AFP Conversion and Indexing Facility: User's Guide for information about ACIF user exits.

Default Value

No default value

Usage Guidelines

- This attribute is valid only for line-data documents.
- For the shift-in, shift-out process to work correctly, two coded fonts must be specified by the **chars** attribute or the page definition. The first must be a single-byte font and the second must be a double-byte font.

sides

Specifies the number of media sides on which this document prints.

GUI Label

Sides to print

DSS

AIX, BSD, PSF, 3170, Infoprint 2000

Type

Resettable, single-valued, per-document

Allowed Values

You can enter an integer value of 1 or 2.

Default Value

AIX :

BSD No value; the printer device defaults the value

PSF The value in the form definition

3170 No default value

Usage Guidelines

- Infoprint validates and schedules jobs using this attribute against the destination attribute sides-supported.
- This attribute is valid for ASCII documents within a job only if it is not changed between documents in the job.
- Infoprint uses this attribute in combination with the **plex** attribute. The results are:

sides Value	plex <i>Value</i>	Output
1	simplex	Simplex
2	simplex	Duplex
1	tumble	Not valid
2	tumble	Tumble duplex

- Infoprint uses sides specifications in this order:
 - The sides document attribute, unless you specify different values for this attribute for each document in a job and also specify a value for the form-definition document attribute. In that case, Infoprint ignores the sides document attribute.
 - 2. For the 3170 DSS, the value in the file specified by the **rip-ini-file** actual destination attribute.
 - 3. The sides specification in the document or default document form definition.
 - 4. The **sides** actual destination attribute.

start-on-new-sheet

Indicates whether to start printing this document on a new sheet of paper.

GUI Label

Start on new sheet

DSS

PSF, Infoprint 2000

Type

Resettable, single-valued, per-document

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

true

Usage Guidelines

- This attribute is not valid for ASCII documents.
- When you print multiple-document jobs and do not want blank pages between the end of one document and the beginning of the next, set this attribute to false.
- If you specify a form definition, it takes priority over the start-on-new-sheet attribute, and any value you specify with start-on-new-sheet is ignored. Infoprint ignores the start-on-new-sheet attribute and uses the value in the form definition.

subject-text

Specifies the subject text that appears on the cover sheet of fax jobs or the subject line of electronic mail jobs.

DSS

Email, Fax

Resettable, single-valued, per-job

Allowed Values

You can enter a text string up to 4095 characters long that contains the subject.

Default Value

No default value

table-reference-characters

Specifies whether the first character of each line in the document (or second character, if carriage control characters are used) is a table reference character. A table reference character selects a font character set named by the chars attribute or in the page definition used to print the job.

GUI Label

Table reference characters

DSS

PSF, Email, Fax, Infoprint 2000

Type

Resettable, single-valued, per-document

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

No default value

Usage Guidelines

- This attribute is valid only for line-data documents.
- Infoprint validates and schedules jobs using this attribute against the destination attribute table-reference-characters-supported.
- If the value of this attribute is **true** and the page definition does not identify fonts, you must specify fonts with the **chars** attribute.
- If the line data contains TRCs and you do not specify this attribute, your printed output will not be correct. Infoprint interprets the TRCs as text characters instead of font identifiers.

title-text

Specifies title information that Infoprint prints in the TITLE: field of an auxiliary sheet if the job uses the **full** auxiliary-sheet object.

GUI Label

Title

DSS

PSF

Type

Resettable, single-valued, per-job

Allowed Values

You can enter a text string of up to 4095 characters that contains the title information.

Default Value

No default value

Usage Guidelines

- While you can specify more characters, you should limit the value you supply to 55 characters or less to ensure that there is enough room available on the printed page for all title information.
- If the text string you specify contains blank spaces, enclose the text string in single quotation marks.

transfer-method (Document Only)

Identifies the method by which Infoprint transfers the document to the print server.

GUI Label

Transferred to server

DSS

All

Type

Initially settable, single-valued, per-job

Allowed Values

You can enter one of these fixed values: pipe-pull with-request

Default Value

pipe-pull

Usage Guidelines

Infoprint validates jobs using this attribute against the server attribute transfer-methods-supported.

transform-message-file-name

Specifies the file name where the transform that Infoprint uses to process this document writes messages.

GUI Label

Transform message file

DSS

PSF, Email, Fax, Infoprint 2000

Type

Resettable, single-valued, per-document

Allowed Values

You can enter a text string of up to 4095 characters that contains the file name.

Default Value

No default value. If you do not specify this attribute or if it has no value, the transform writes messages to \$PDBASE/servername/error.log for Infoprint Manager for AIX and \workspace path\servername\error.log for Infoprint Manager for Windows NT and Windows 2000.

Usage Guidelines

- This attribute is valid only for line-data documents.
- This attribute is not valid for ASCII documents.

transform-output-file-name

Specifies the file name of the output file produced by the Infoprint transform that converts this document to the AFP data stream.

GUI Label

Transform output file name

DSS

PSF, Email, Fax, Infoprint 2000

Type

Resettable, single-valued, per-document

Allowed Values

You can enter a text string of up to 4095 characters that contains the file name.

Default Value

No default value unless the output format is **side-by-side-copies** or **booklet-print**. In that case, Infoprint saves the transformed file in the directory specified by the **PDBASE** environment variable or in one of its subdirectories.

Usage Guidelines

- Use this attribute to save transformed files.
- Transform programs write output to a temporary file in the directory specified by the PDBASE environment variable or in one of its subdirectories. No single user can create a file larger than the amount of free space in the file system containing this directory. If many users are submitting print jobs that invoke transform programs, the directory may fill up and prevent all users from successfully running the transform programs.

type (Document Only)

See document-type.

user-id-text

Specifies user-identification information that Infoprint prints at the top of the page and in the **USERID**: field of an auxiliary sheet.

GUI Label

User ID

DSS

PSF

туре

Resettable, single-valued, per-job

Allowed Values

You can enter a text string of up to 4095 characters that contains the user-identification information.

Default Value

No default value

Usage Guidelines

- While you can specify more characters, you should limit the value you supply to 10 characters or less to ensure that there is enough room available on the printed page for all user-identification information.
- If the text string you specify contains blank spaces, enclose the text string in single quotation marks.

x-image-shift

Specifies the X offset, in millimeters, of the logical page origin to the right of the physical page origin.

GUI Label

Move image right (inches) or (mm)

DSS

PSF, 3170, Email, Fax, Infoprint 2000

Type

Resettable, single-valued, per-document

Allowed Values

You can enter a numeric value from -577.99 mm to 577.97 mm.

The value you specify is in the form *nnnn.nnn*, which is a number that can optionally contain a decimal point. Millimeters is the unit of measure for the value you specify.

Default Value

No default value

Usage Guidelines

- This attribute overrides any X-offset value in the form definition Infoprint uses for the job, with one exception. If you specify different values for this attribute for each document in a job, and also specify a value for the document **form-definition** attribute, Infoprint ignores the **x-image-shift** attribute and uses the X-offset value in the form definition.
- This attribute is valid for ASCII documents within a job only if it is not changed between documents in the job.
- For the 3170 DSS, the **image-center-x** attribute overrides this attribute.
- For the 3170 DSS, if you do not specify a value for this attribute, Infoprint uses the value in the file specified by the **rip-ini-file** actual destination attribute.
- Infoprint validates and schedules jobs using this attribute against the x-image-shift-range-supported actual destination attribute.

x-image-shift-back

Specifies the X offset, in millimeters, of the logical page origin to the right of the physical page origin on the back side of a double-sided sheet.

GUI Label

Move image right on back side (inches) or (mm)

DSS

PSF, Infoprint 2000

туре

Resettable, single-valued, per-document

Allowed Values

You can enter a numeric value from -577.99 mm to 577.97 mm.

The value you specify is in the form *nnnn.nnn*, which is a number that can optionally contain a decimal point. Millimeters is the unit of measure for the value you specify.

Default Value

No default value

Usage Guidelines

• This attribute is not valid for ASCII documents.

- If you specify a value for the document form-definition attribute, Infoprint
 ignores the x-image-shift-back attribute and uses the X-offset value in the form
 definition. This attribute overrides the X-offset value in any other form
 definition.
- Infoprint validates and schedules jobs using this attribute against the x-image-shift-range-supported actual destination attribute.

y-image-shift

Specifies the Y offset, in millimeters, of the logical page origin below the physical page origin.

GUI Label

Move image down (inches) or (mm)

DSS

PSF, 3170, Email, Fax, Infoprint 2000

Type

Resettable, single-valued, per-document

Allowed Values

You can enter a numeric value from -577.99 mm to 577.97 mm.

The value you specify is in the form *nnnn.nnn*, which is a number that can optionally contain a decimal point. Millimeters is the unit of measure for the value you specify.

Default Value

No default value

Usage Guidelines

- This attribute overrides any Y-offset value in the form definition Infoprint uses
 for the job, with one exception. If you specify different values for this attribute
 for each document in a job, and also specify a value for the document
 form-definition attribute, Infoprint ignores the y-image-shift attribute and uses
 the Y-offset value in the form definition.
- This attribute is valid for ASCII documents within a job only if it is not changed between documents in the job.
- For the 3170 DSS, the **image-center-y** attribute overrides this attribute.
- For the 3170 DSS, if you do not specify a value for this attribute, Infoprint uses the value in the file specified by the **rip-ini-file** actual destination attribute.
- Infoprint validates and schedules jobs using this attribute against the y-image-shift-range-supported actual destination attribute.

y-image-shift-back

Specifies the Y offset, in millimeters, of the logical page origin below the physical page origin on the back side of a double-sided sheet.

GUI Label

Move image down on back side (inches) or (mm)

DSS

PSF, Infoprint 2000

Type

Resettable, single-valued, per-document

Allowed Values

You can enter a numeric value from -577.99 mm to 577.97 mm.

The value you specify is in the form *nnnn.nnn*, which is a number that can optionally contain a decimal point. Millimeters is the unit of measure for the value you specify.

Default Value

No default value

Usage Guidelines

- This attribute is not valid for ASCII documents.
- If you specify a value for the document form-definition attribute, Infoprint ignores the y-image-shift-back attribute and uses the Y-offset value in the form definition. This attribute overrides the Y-offset value in any other form definition.
- Infoprint validates and schedules jobs using this attribute against the y-image-shift-range-supported actual destination attribute.

Attributes for Jobs and Default Jobs

This section contains the attributes for default jobs and jobs.

Default Job

Use default jobs to set default values for job attributes.

Default jobs contain two types of attributes:

- · Attributes that describe the default job itself
- Attributes that you can set as default values for job attributes

Job

A job is an Infoprint object that represents a request to print or transmit one or more documents in a single session.

Attributes Not Displayed in the Infoprint Administrator's GUI

While all job and default job attributes and attribute values are supported for both basic and advanced Infoprint installations, neither Infoprint administrator's GUI displays a complete set.

- The basic Infoprint administrator's GUI displays only the attributes of greatest interest to Infoprint administrators.
- The advanced Infoprint administrator's GUI displays most attributes and attribute values, but omits a few that are used primarily in basic Infoprint installations.

You can list the values of attributes not displayed in the Infoprint administrator's GUI using the pdls command or the pdq command. You can set the values of initially settable and resettable attributes using the pdcreate command or the pdpr command. You can change the values of resettable attributes using the pdmod command or the pdset command.

Initially Settable Attribute Listing

You can set these attributes with the pdpr command when you submit the job.

destination-name-requested initial-value-job

job-originator

job-owner

tape-exit

tape-format

tape-labeled

tape-max-block-size

tape-rewind-before

tape-rewind-unload

Note: There are no initially settable attributes for a default job.

Resettable Attribute Listing

You can set these attributes with the pdpr command when you submit a job or with the pdcreate command when you create a default job. You can modify them with the **pdset** command after Infoprint has accepted the job or after you create the default job. You can also use the pdmod command to modify a job after Infoprint accepts it.

actual-destinations-requested

```
auxiliary-sheet-selection
delete-segment-list
descriptor (default job only)
destination-locations-requested
destination-models-requested
dss-requested
estimated-processing-time (job only)
job-batch
job-client-id (job only)
job-comment
job-complexity (job only)
job-deadline-time (job only)
job-discard-time (job only)
job-end-message
job-finishing
iob-hold
job-media-sheet-count (job only)
job-message-from-administrator (job only)
job-message-to-operator
job-name
job-page-count (job only)
job-print-after (job only)
job-priority
job-retain-until (job only)
job-retention-period
job-rip-action
job-ripped-by-server
job-start-message
job-start-wait
list-of-managers (default job only)
message (default job only)
notification-profile
optimize-for-multiple-copies
results-profile
```

actual-destinations-requested

Identifies a list of actual destinations, any one of which Infoprint may use to process the job.

GUI Label

Actual destinations requested

DSS

All

Type

Resettable, multi-valued

Input Synonym

You can use the synonym physical-printers-requested.

Allowed Values

You can enter a text string of up to 255 characters, per value, that contains the name of an actual destination.

Default Values

No default values

Usage Guidelines

- Infoprint validates and schedules jobs using this attribute against the destination attribute destination-name.
- If you request more than one actual destination, the job will process on the first one that becomes available that can support the job.

associated-server (Default Job Only)

Indicates the name of the server in which this default job resides.

DSS

All

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value to the ServerName: portion of the argument used with the pdcreate command when this default job is created.

Default Value

No default value

auxiliary-sheet-selection

Identifies the combination of start, separator, and end sheets requested for this job. Whether Infoprint prints the requested sheets depends on the actual destination.

GUI Label

Auxiliary/Separator sheets

AIX, PSF, Passthrough

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value	Start	Separator	End
end	No	No	Yes
none	No	No	No
sep	No	Yes	No
sep-end	No	Yes	Yes
start	Yes	No	No
start-end	Yes	No	Yes
start-sep	Yes	Yes	No
start-sep-end	Yes	Yes	Yes

Default Value

Default job No default value Job start-sep-end

Usage Guidelines

Infoprint validates and schedules jobs using this attribute against the destination attribute auxiliary-sheet-selections-supported.

comment

See job-comment.

completion-time (Job Only)

Identifies the time when the job completed printing or transmitting.

GUI Label

Completed

DSS

All

Type

Non-settable, single-valued

Allowed Values

Infoprint sets the value for this attribute in the local time format; USA is "HH:MM:SS mm/dd/yy".

Default Value

No default value

Usage Guidelines

Provides status information.

current-job-state (Job Only)

Identifies the current state of the job.

GUI Label

State

DSS

All

Type

Non-settable, single-valued

Input Synonym

You can use the synonym job-state.

Allowed Values

Infoprint sets and updates this value as the job processes. The value set at a given time is one of these fixed values:

Fixed Value	Reason
cancelled	The job submitter or an operator cancelled the job. The job-state-reasons job attribute provides the reason.
held	The job is in a queue and Infoprint cannot schedule it. Either the job-hold job attribute is set to true or the job is held for some other reason, such as resources not ready. The job-state-reasons job attribute provides the reason.
imposing	Infoprint is arranging the job's pages so that they

will print on the press sheets in the right order for

final cutting, folding, and binding.

paused The job was paused with the **pdpause** command.

pending The job is in a queue and is waiting for Infoprint

to schedule and send it to an actual destination.

pre-processing Infoprint is creating the job.

printing The job is printing on a PSF or 3170 actual

destination. The **printing** state is not supported by the AIX, BSD, fax, email, or Infoprint 2000 DSS. Jobs printing on AIX or BSD actual destinations, or transmitting on fax or email destinations, are in the

processing state.

processing Infoprint has sent the job to an actual destination.

The job is processing and printing on an AIX, BSD, or Infoprint 2000 DSS actual destination, processing and transmitting on a fax or email destination, or processing on a PSF or 3170 actual destination. Depending on the output device, this can indicate that Infoprint has sent at least one document in the

job to the output device.

retained Infoprint has retained the job in the server after it

finished printing or transmitting or after it was

cancelled. Either the value of the

job-retention-period job attribute for the job is

greater than zero, or the value of the

job-retain-until job attribute for the job is a future

time.

ripping Infoprint is converting the job to raster image

patterns for printing. The **ripping** state is supported only by the PSF, 3170, fax, email, and

Infoprint 2000 DSS.

terminating The job is terminating, either because it has

finished processing or because it was aborted. The **job-state-reasons** job attribute provides the reason.

unknown The server does not know the state of the job

because it lost communication with the actual destination to which Infoprint sent the job.

Default Value

No default value

Usage Guidelines

Jobs are in the job state **cancelled**, **pre-processing**, and **terminating** for only a very short time. You may never see them as values for this attribute; however, you may see them as values for the **previous-job-state** job attribute.

current-page-printing (Job Only)

Reports the page number of the currently printing or transmitting page.

GUI Label

Page currently printing

DSS

PSF

Type

Non-settable, single-valued

Allowed Values

Infoprint sets and updates this value to an integer from 0 through 2147483647.

Default Value

No default value

Usage Guidelines

The differences between this attribute and pages-completed are:

- **current-page-printing** is the number of the page being printed or transmitted, while **pages-completed** is the number of pages placed in the stacker. For example, when page 12 of the first copy of a double-sided job is printing, the value of **current-page-printing** is 12 and the value of **pages-completed** is 10.
- **current-page-printing** is reset with every job copy, while **pages-completed** is cumulative within a job. For example, when page 6 of the second copy of a 10-page job is printing, the value of **current-page-printing** is 6. When the same page is stacked, the value of **pages-completed** is 16.

d-s-s-requested

See dss-requested.

deadline-in-jeopardy (Job Only)

Indicates whether the job is in danger of not completing before the time specified by the **job-deadline-time** attribute.

GUI Label

Deadline in jeopardy

DSS

PSF, Email, Fax, Infoprint 2000

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value to one of these fixed values:

true

false

Default Value

No default value

Usage Guidelines

Infoprint sets **deadline-in-jeopardy** to **true** under these conditions:

- If the queue attribute **assign-to-destination=true**, when the value of the **estimated-completion-time** attribute is later than the value of the **job-deadline-time** attribute.
- If the queue attribute assign-to-destination=false, when the current time is later than the value of the job-deadline-time attribute. Infoprint cannot calculate a value for the estimated-completion-time attribute if assign-to-destination=false.

delete-segment-list

Indicates whether to delete the segment list file, where Infoprint lists the segment files into which it breaks the job for processing, after the job is complete.

GUI Label

Delete segment list

DSS

PSF, Email, Fax, and Infoprint 2000

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

Default job No default value

Job false

descriptor (Default Job Only)

Provides a description of this default job.

DSS

All

Type

Resettable, single-valued

Allowed Values

You can enter a text string of up to 4095 characters that describes this default job.

Default Value

No default value

Usage Guidelines

The use of this attribute is optional. However, a detailed description helps job submitters to determine if this default job is the one they want to use.

destination-initial-value-job (Job Only)

Identifies the default job associated with the logical destination to which you submitted the job and used to create the job.

GUI Label

Default job used

DSS

All

Type

Non-settable, single-valued

Input Synonym

You can use the synonym **printer-initial-value-job**.

Allowed Values

Infoprint sets this value to the name of the default job used.

Default Value

No default value

destination-locations-requested

Identifies a list of destination locations. Infoprint may use a destination at any of these locations to process the job.

GUI Label

Actual destination locations requested

DSS

A11

Type

Resettable, multi-valued

Input Synonyms

You can use the synonym **printer-locations-requested** or **locations-requested**.

Allowed Values

You can enter a text string of up to 4095 characters, per value, that contains the actual location of each destination requested. Infoprint will process the job on a destination at one of the locations if the validation is successful.

Default Values

No default values

Usage Guidelines

- Infoprint validates jobs using this attribute against the logical and actual destination attribute destination-locations.
- Infoprint schedules the job against the actual destination attribute destination-locations.
- · Any individual value specified for this attribute can select more than one actual destination. For example, the output devices could all be in the same location, such as a printer room.
- The values for both the job and destination attributes are text strings that can include blanks. They must match exactly for validation to occur.

destination-models-requested

Identifies a list of destination make and model IDs. Infoprint may use any one of these destinations to process the job.

GUI Label

Actual destination models requested

DSS

All

Type

Resettable, multi-valued

Input Synonyms

You can use the synonym printer-models-requested or models-requested.

Allowed Values

You can enter a text string of up to 4095 characters, per value, that identifies the destination model.

Default Values

No default values

Usage Guidelines

- Infoprint validates jobs using this attribute against the logical and actual destination attribute **destination-model**. Only one value must match for Infoprint to validate the job.
- Infoprint schedules the job against the actual destination attribute **destination-model**. Only one value must match for Infoprint to schedule the job.
- This attribute is multi-valued whereas the destination attributes are single-valued.
- Any individual value specified for this attribute can select more than one actual destination.
- The value for this attribute and the values for the destination attributes for the BSD, PSF, 3170, email, and fax actual destinations are text strings that can include blanks. (The values for the AIX actual destination attribute never contain blanks.)
- The value for this attribute and the value for the destination attribute must match exactly for validation to occur.

destination-name-requested (Job Only)

Identifies the logical destination to which you submitted this job.

GUI Label

Submitted to

DSS

All

Type

Initially settable, single-valued

Input Synonyms

You can use the synonym **printer-name-requested**, **printer-requested**, or **logical-printer-requested**.

Allowed Values

You can enter a text string of up to 255 characters that contains the name of the logical destination.

Default Value

No default value

Usage Guidelines

 If you do not specify a value for this attribute, Infoprint uses the -p or -d value on the pdpr command, or the PDPRINTER environment variable of the job submitter

To move the job to a different logical destination, use the **pdresubmit** command.

destinations-assigned (Job Only)

Identifies the actual destination to which Infoprint assigned the job for processing.

GUI Label

Destination

DSS

All

Type

Non-settable, single-valued

Input Synonym

You can use the synonym printers-assigned.

Allowed Values

Infoprint sets this value to the name of the actual destination where it sent the job.

Default Values

No default value

Usage Guidelines

If the value for this attribute is blank, the job is still waiting for Infoprint to assign it to an actual destination.

destinations-used (Job Only)

Identifies the actual destination that printed or transmitted this job.

GUI Label

Destinations used

DSS

All

Type

Non-settable, multi-valued

Input Synonym

You can use the synonym **printers-used**.

Allowed Values

Infoprint sets this value to the names of the actual destinations where it sent the job.

Default Values

No default value

Usage Guidelines

Normally this value only contains one actual destination name. However, if Infoprint restarted the job on another actual destination because the first actual destination failed for some reason, this value could contain more than one actual destination name.

device-support-system-requested

See dss-requested.

discard-time (Job Only)

See job-discard-time.

dss-requested

Identifies the destination support system (DSS) requested for the job.

GUI Label

Actual destination type requested

All

Type

Resettable, single-valued

Input Synonyms

You can use the synonyms device-support-system-requested or d-s-s-requested.

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

aix piobe

bsd psf 3170 email fax IP2000

Default Value

No default value

Usage Guidelines

- Infoprint validates jobs using this attribute against the logical and actual destination attribute device-support-system.
- Infoprint schedules the job against the actual destination attribute device-support-system.

end-message

See job-end-message.

estimated-completion-time (Job Only)

Indicates the time when Infoprint expects the job to finish printing or transmitting.

GUI Label

Estimated completion time

DSS

All

Type

Non-settable, single-valued

Allowed Values

Infoprint sets the value for this attribute in the local time format; USA is "HH:MM:SS mm/dd/yy".

Default Value

No default value

Usage Guidelines

- Infoprint uses the values it calculated for the **estimated-processing-time** attribute of this job and the jobs ahead of it in the queue to estimate the job's completion time.
- Infoprint can calculate a value for this attribute only when the queue attribute assign-to-destination is set to true.

estimated-processing-time (Job Only)

Indicates how long the job should take to process.

GUI Label

Estimated processing time

DSS

All

Type

Resettable, single-valued

Allowed Values

You can enter a value using [HH:]MM. The unit is minutes or hours and minutes, separated by a colon.

Default Value

No default value

Usage Guidelines

- Infoprint uses the values of the **total-job-octets** and **job-complexity** attributes to estimate the job's processing time. You can change this value.
- Infoprint can calculate a value for this attribute only when the queue attribute assign-to-destination is set to true.

formatted-job-ticket-content (Job Only)

Contains the job ticket document for the job in human-readable format.

DSS

PSF, Email, Fax, 3170, Infoprint 2000

Type

Non-settable, single-valued

Input Synonyms

You can use the synonym job-ticket-content or ticket-content.

Allowed Values

Infoprint sets the value of this attribute to the contents of the formatted job ticket document.

Default Value

No default value

global-id (Job Only)

See job-identifier.

hold

See job-hold.

initial-value-job (Job Only)

Identifies the default job (within a given server) that Infoprint uses to create this job.

DSS

All

Type

Initially settable, single-valued

Allowed Values

You can enter the name of an existing default job.

Default Value

No default value

Usage Guidelines

If you specify a value for this attribute, the job uses the attributes and values from the specified object unless you override those with attribute values supplied at the command line.

initial-value-job-identifier (Default Job Only)

Identifies this default job within the server.

DSS

All

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value to the *DefaultJobName* value of the **pdcreate** command argument *ServerName:DefaultName* when this default job is created.

Default Value

No default value

Usage Guidelines

The value for this attribute must be unique within a server.

intervening-jobs (Job Only)

Indicates the number of jobs in the queue before this job.

GUI Label

Position in queue

DSS

All

Type

Non-settable, single-valued

Input Synonyms

You can use the synonym **position-in-queue** or **queue-position**.

Allowed Values

Infoprint sets and updates this value to an integer from 0 through 2147483647.

Default Value

No default value

Usage Guidelines

- This attribute provides status information.
- A value of zero (0) means that the job is currently printing or transmitting.

job-batch

Specifies that you have marked the job you are submitting as a specific type of job. Infoprint processes this job only on an actual destination that is ready to print or transmit that specified job-batch type.

GUI Label

Batch

DSS

All

Type

Resettable, single-valued

Allowed Values

You can enter a text string of up to 4095 characters that contains the job-batch name.

Default Value

No default value

Usage Guidelines

Infoprint schedules jobs using this attribute against the job-batches-ready actual destination attribute.

job-client-id (Job Only)

Identifies the local job identifier number for the job.

GUI Label

ID

DSS

All

Type

Resettable, single-valued

Allowed Values

Infoprint sets this value from 1 through the number specified as the value for the PDIDTABLE environment variable.

Default Value

No default value

job-comment

Provides information associated with this job.

GUI Label

Description

DSS

All

Type

Resettable, single-valued

Input Synonym

You can use the synonym **comment**.

Allowed Values

You can enter a text string of up to 4095 characters that contains information associated with this job.

Default Value

No default value

job-complexity

Indicates the relative complexity of the job, based on the contents of the documents in the job. For example, a job with many graphics is more complex than a job that is mostly text.

GUI Label

Complexity (1–10)

DSS

All

Type

Resettable, single-valued

Allowed Values

You can enter an integer from 1 to 9.

Default Value

3

Usage Guidelines

- The default value, 3, represents an average job. A job with complexity 1 is one-third as complex as the average job; a job with complexity 9 is three times as complex as average.
- Infoprint uses this value and the size of the job to estimate the job processing time.
- Infoprint uses this attribute only when the queue attribute assign-to-destination is set to true.

job-copies-completed (Job Only)

Indicates the total number of copies of the job that have finished printing or transmitting.

GUI Label

Copies completed

DSS

All

Type

Non-settable, single-valued

Allowed Values

Infoprint sets and updates this value to an integer from 0 through 2147483647

when:

AIX Each job copy completes. **BSD** Each result-set completes. Infoprint 2000 Each result-set completes. **PSF** Each job copy completes. 3170 Each result-set completes. **Email** Each result-set completes. Fax Each result-set completes. Passthrough Each result-set completes. **IPP** Each result-set completes.

Default Value

No default value

job-deadline-time (Job Only)

Specifies the time or time and calendar date by which you want the job to complete.

GUI Label

Deadline time

DSS

All

Type

Resettable, single-valued

Allowed Values

You can enter a value using the local time format. The USA format is HH:MM:SS or "HH:MM:SS mm/dd/yy". You must delimit the string with quotation marks if you specify a date. If you specify a time but no date, the date defaults to today.

Default Value

No default value

job-discard-time (Job Only)

Specifies the time or time and calendar date at which Infoprint discards the job even if it is not complete.

GUI Label

Discard time

DSS

All

Type

Resettable, single-valued

Input Synonym

You can use the synonym discard-time.

Allowed Values

You can enter a value using the local time format. The USA format is HH:MM:SS or "HH:MM:SS mm/dd/yy". You must delimit the string with quotation marks if you specify a date. If you specify a time but no date, the date defaults to today.

Default Value

No default value

job-end-message

Provides a message conveying information about output handling when the job is complete.

GUI Label

End message

DSS

A11

Type

Resettable, single-valued

Input Synonym

You can use the synonym end-message.

Allowed Values

You can enter a text string of up to 4095 characters that contains instructions to an operator, such as special output delivery instructions.

Default Value

No default value

Usage Guidelines

- Infoprint validates and schedules jobs using this attribute against the destination attribute **end-message-supported**.
- Infoprint sends this message if the attribute **end-message-supported** value is **true** for the actual destination to which Infoprint submitted the job.
- The destination attribute **notify-operator** identifies the operators that are to receive the message.

job-finishing

Identifies the finishing options for this job.

GUI Label

Finishing options

DSS

PSF, Infoprint 2000

Type

Resettable, multi-valued

Allowed Values

You can enter any of these fixed values for PSF-supported printers, that is printers that use the PSF DSS:

```
edge-stitch
edge-stitch-2
edge-stitch-3
edge-stitch-bottom
edge-stitch-left
edge-stitch-right
edge-stitch-top
saddle-stitch
```

```
staple-bottom-left
staple-bottom-right
staple-top-left
staple-top-right
```

You can enter any of these fixed values for printers that use the Infoprint 2000 DSS:

```
edge-stitch-2
saddle-stitch
staple-bottom-left
staple-top-left
booklet-stitch-and-fold
booklet-stitch-fold-and-trim
```

Default Values

No default values

Usage Guidelines

- edge-stitch-2, edge-stitch-3, and edge-stitch all staple one edge of the job. The difference is the number of staples: 2, 3, or the finisher default.
- This attribute is not valid for ASCII documents.
- The placement of staples in relation to the data depends on the image orientation and the way the paper is loaded in the printer. Letter and A4 paper are normally loaded long edge first, but are loaded short edge first when rotated. Long media sheets, like legal paper, are always loaded short edge first.
- While the PSF DSS and the IP2000 DSS support the job-finishing values listed, the way these values are implemented by the different printers may vary.
 Therefore, you may need to experiment. For specific details on finishing options with printers, see your printer documentation.
- For PSF DSS, **saddle-stitch** is valid only for the following medium sizes, all loaded short edge first:

```
A3
A4 (rotated)
ledger
legal
letter (rotated)
```

- For PSF DSS, when you specify a value for **job-finishing**, Infoprint creates an inline form definition. Do not use the document attribute **form-definition** to specify another form definition.
- Infoprint validates and schedules jobs using this attribute against the destination attribute **job-finishings-supported**.

job-hold

Indicates whether Infoprint can schedule the job for printing or transmission.

GUI Label

Hold

DSS

All

Type

Resettable, single-valued

Input Synonym

You can use the synonym hold.

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

Default job No default value

Job false

Usage Guidelines

- If **job-hold** is **true**, the **job-state** changes to **held** and Infoprint sets the **job-state-reasons** to **job-hold-set**.
- A held job remains in the queue until:
 - **job-hold** is set to **false** and the job is printed or transmitted.
 - The time set in the job-discard-time attribute is reached and the job is discarded.
- When a job with job-rip-action=rip-and-print-ignore-ready is placed in the held state after RIPping because a required resource is not ready, the value of job-hold remains false. The job is automatically released when all required resources become ready.

job-identifier (Job Only)

Identifies the global job identifier. The global job ID uniquely identifies the job within the server.

GUI Label

Global ID

DSS

All

Type

Non-settable, single-valued

Input Synonym

You can use the synonym global-id.

Allowed Values

Infoprint sets this value.

Default Value

No default value

job-log (Job Only)

Contains messages that Infoprint issues as this job is processed.

DSS

All

Type

Non-settable, multi-valued

Allowed Values

Infoprint sets the value of this attribute to the messages issued as the job is processed.

Default Values

No default value

Usage Guidelines

Infoprint creates this attribute when the value of the **delivery-method** component of the **notification-profile** attribute is **job-log**.

job-media-sheet-count (Job Only)

Identifies the estimated total number of sheets used to print the job.

GUI Label

Number of media sheets

DSS

All

Type

Resettable, single-valued

Input Synonym

You can use the synonym media-sheet-count.

Allowed Values

You can enter an integer from 1 through 2147483647.

Default Value

No default value

job-message-from-administrator (Job Only)

Describes the reasons that you are changing or have changed the job.

GUI Label

Message from administrator

DSS

All

Type

Resettable, single-valued

Input Synonym

You can use the synonym message-from-administrator.

Allowed Values

The administrator can enter a text string up to 4095 characters long that provides information concerning why a given action was taken. The administrator uses the **-m** flag or the command attribute **message** of certain Infoprint commands. See "Usage Guidelines" for how you can set the value.

Default Value

No default value

Usage Guidelines

Set this attribute by specifying a value with the **-m** flag or the **message** command attribute of these commands:

```
pdmod
pdpause
pdpromote
pdresume
pdrm
pdset
```

job-message-to-operator

Provides a message that Infoprint can send to an operator when it adds the job to the queue.

GUI Label

Message to operator

DSS

All

Type

Resettable, single-valued

Input Synonym

You can use the synonym message-to-operator.

Allowed Values

You can enter a text string of up to 4095 characters that contains information about job processing requirements, such as some type of special handling.

Default Value

No default value

Usage Guidelines

The queue attribute notify-operator identifies the operator who receives the message.

job-name

Provides a human-readable job identification.

GUI Label

Name

DSS

All

Type

Resettable, single-valued

Input Synonym

You can use the synonym name.

Allowed Values

You can enter a text string of up to 255 characters that contains the identification. The string can include any of the following characters:

Uppercase alphabetic characters (A-Z)

Lowercase alphabetic characters (a-z)

Numeric characters (0-9)

Underscore (_)

Hyphen (-)

Period (.)

Default Value

Default job No default value

Job The file name of the first document in the job

Usage Guidelines

For PSF, this identification may print on the start sheet in the **JOB NAME** field.

job-originator (Job Only)

Identifies the person who submitted the job or the program that initiated the job.

DSS

A11

Type

Initially settable, single-valued

Input Synonym

You can use the synonym originator.

Allowed Values

You can enter a text string up to 255 characters long that contains the name, login ID, or login ID and node of the person submitting the job, or the name of the program initiating the job.

Default Value

username@node of the person submitting the job.

Usage Guidelines

You can use this attribute to identify yourself by name or to identify the program that initiated the job.

job-owner (Job Only)

Identifies the person responsible for the job by name or login ID.

GUI Label

Sent by

DSS

A11

Type

Initially settable, single-valued

Input Synonym

You can use the synonym **owner**.

Allowed Values

You can enter a text string of up to 255 characters. Normally the string contains the username@node of the person that is responsible for this job.

Default Value

The value of the job attribute **job-originator**.

Usage Guidelines

- You can use this attribute to specify a person other than yourself who is responsible for the job.
- For BSD, Infoprint maps this attribute value to the **qprt -D** option.
- For PSF, this identification may print on the start sheet in the **USERID** field.

job-page-count (Job Only)

Identifies the estimated total number of pages in the job.

GUI Label

Number of pages

DSS

All

Type

Resettable, single-valued

Allowed Values

An integer from 1 through 2147483647.

Default Value

The total of the values of the **page-count** attribute for all documents multiplied times the value in the **copy-count** attribute (and the **job-copies** component in the **results-profile**) for all the documents in the job.

Usage Guidelines

- Infoprint calculates the value for **job-page-count** as follows:
 - Multiplying the value for the total number of printable pages specified with the page-count document attribute for all printable documents in the job times the value for the copy-count document attribute for all printable documents in the job.
 - 2. Infoprint then multiplies the value from step 1 times the **job-copies** component of the **results-profile** job attribute and inserts the result of this multiplication in the **job-page-count** attribute.
- If you choose to specify a value for the **job-page-count** attribute, the value should closely represent the total number of pages expected for the complete job.
- Infoprint determines the size of a job based on the total number of octets (bytes) in the job. For operator job-management purposes, you may find that job size based on pages is easier.

Note: This attribute overrides the page count that Infoprint calculates.

job-print-after (Job Only)

Specifies the time or time and calendar date after which Infoprint can schedule the job for printing or transmission.

GUI Label

Print after

DSS

All

Type

Resettable, single-valued

Input Synonym

You can use the synonym **print-after**.

Allowed Values

You can enter a value using the local time format. The USA format is *HH:MM:SS* or "*HH:MM:SS mm/dd/yy*". You must delimit the string with quotation marks if you specify a date. If you specify a time but no date, the date defaults to today.

Default Value

No default value

Usage Guidelines

- If you submit the job before the specified time, Infoprint sets the job-state to held and the job-state-reasons attribute value for the job is job-print-after-specified.
- If you submit the job after the specified time, the job is printed or transmitted as soon as possible.

job-priority

Specifies a number representing the scheduling priority for the job. Actual destinations that employ a priority-based scheduler use this attribute. A larger value specifies a higher priority.

GUI Label

Priority (1-100)

DSS

All

Type

Resettable, single-valued

Allowed Values

You can enter an integer from 1 to 100.

Default Value

Default job No default value

Job 50

Usage Guidelines

If you use DCE:

- A job submitter cannot set this value higher than 50 unless the job submitter is an administrator. If the job submitter specifies a value greater than 50, Infoprint sets the value to 50.
- · An administrator can set the value to any valid value.

job-retain-until (Job Only)

Specifies the time or time and calendar date until which Infoprint retains the completed job before the server discards it.

GUI Label

Retain until

DSS

All

Type

Resettable, single-valued

Allowed Values

You can enter a value using the local time format. The USA format is *HH:MM:SS* or "*HH:MM:SS mm/dd/yy*". You must delimit the string with quotation marks if you specify a date. If you specify a time but no date, the date defaults to today.

Default Value

No default value

Usage Guidelines

You can specify a value for either **job-retain-until** or **job-retention-period**, but not both.

job-retention-period

Specifies the period of time that Infoprint retains the job before the server discards it, whether it has completed or not.

GUI Label

Retain for

DSS

All

Type

Resettable, single-valued

Input Synonym

You can use the synonym retention-period.

Allowed Values

You can enter a value using [HH:]MM. The unit is minutes or hours and minutes, separated by a colon.

Default Value

No default value

Usage Guidelines

- You can specify a value for either **job-retain-until** or **job-retention-period**, but not both.
- The retention period starts when the job enters the **retained** state.

job-rip-action

Indicates that Infoprint should convert the job to raster image patterns and whether to hold the RIPped job, print or transmit it, or neither.

GUI Label

Rip option

DSS

PSF, Email, Fax, 3170, Infoprint 2000

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value

Explanation

rip-and-hold, rip-and-hold-ignore-ready

Infoprint RIPs the job and returns it to the scheduler in the **held** state. The value of the **job-state-reasons** attribute is **rip-and-hold-completed**.

rip-and-print

If all required resources are ready on an actual destination, Infoprint RIPs and prints the job. Otherwise, Infoprint returns the job to the scheduler in the **held** state, without RIPping it. The value of the **job-state-reasons** attribute is **required-resource-not-ready**.

rip-and-print-ignore-ready

If all required resources are ready, Infoprint RIPs and prints the job. Otherwise, Infoprint RIPs the job and returns it to the scheduler in the **held** state. The value of the **job-state-reasons** attribute is **rip-completed**. When the required resources become ready, Infoprint automatically releases the job to print.

rip-only, rip-only-ignore-ready

Infoprint RIPs the job and discards or retains it according to the values of the **job-retain-until** and **job-retention-period** attributes. For a retained job, the value of the **job-state-reasons** attribute is **completed**, **completed successfully**, or **completed with errors**.

Default Value

No default value

Usage Guidelines

- Use the rip-only and rip-only-ignore-ready values to test for RIPping errors.
- The **rip-and-hold** and **rip-and-hold-ignore-ready** values override a value of **false** for the server **save-rip-files** attribute.
- Infoprint validates and schedules jobs using this attribute against the destination attribute job-rip-actions-supported.

job-ripped-by-server

Indicates whether Infoprint should convert the job to MOD:CA-P and transmit it as email or to be printed with the Infoprint 2000 DSS. If this attribute is **true**, the server converts the job into MOD:CA-P. If this attribute is **false**, the server determines if the job can be printed directly by the Infoprint 2000 DSS or sent directly as email without converting to MOD:CA-P. When a job cannot be handled directly without conversion, the job is requeued on the spooler.

GUI Label

Override RIP at destination

DSS

Email, Infoprint 2000

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

true

Usage Guidelines

- When a job requires special processing of its input files, the server transforms the job into MOD:CA-P regardless of the **job-ripped-by-server** job attribute or the document formats listed in the **document-formats-ripped-at-destination** actual destination attribute.
- The following document formats cannot be converted to MOD:CA-P:

ASCII KGL LCDS

METACODE

Infoprint sends these document formats in passthru mode. For documents to print successfully in passthru mode, the **job-finishing** job attribute and the following document attributes must not be specified:

account-text

base-printer

carriage-control-type

chars

convert-to-ebcdic

default-character-mapping

default-medium

default-font-fidelity-action

form-definition

halftone

image-fit

image-length

image-width

input-exit

new-line-option

number-up

other-transform-options

output-bin

output-format

overlay

page-definition

page-select

plex

printer-pass-through

resource-context

resource-context-font

resource-context-form-definition

resource-context-page-definition

resource-context-page-segment

resource-context-overlay

resource-context-user

shift-out-shift-in

sides

start-on-new-sheet

subject-text

table-reference-characters

transform-message-file-name

transform-output-file-name

x-image-shift

```
x-image-shift-back
y-image-shift
y-image-shift-back
```

Note: If any of these attributes are specified, Infoprint converts the job to MOD:CA-P.

• When the **job-finishing** job attribute and the following document attributes are specified for an email with color, Infoprint converts the job into MOD:CA-P and presents the email in black and white:

```
account-text
address1-text
address2-text
address3-text
address4-text
carriage-control-type
chars
convert-to-ebcdic
default-character-mapping
font-fidelity-action
font-resolution
form-definition
image-fit
image-length
image-width
input-exit
new-line-option
number-up
other-transform-options
output-bin
output-format
overlay
page-definition
page-select
plex
resource-context
resource-context-font
resource-context-form-definition
resource-context-page-definition
resource-context-page-segment
resource-context-overlay
resource-context-user
shared-formdef
shift-out-shift-in
sides
table-reference-characters
transform-message-file-name
transform-output-file-name
x-image-shift
y-image-shift
```

Note: If any of these attributes are specified, Infoprint converts the job to MOD:CA-P.

In addition to the listed attributes, any of the following job characteristics also require that Infoprint converts the job into MOD:CA-P:

- Job contains more than one printable document.

- Job contains an insert sheet.
- Job contains a file-reference document.
- Job contains a document whose document-format is MOD:CA-P.
- Job requests job-rip-action=rip-and-hold, rip-only, rip-only-ignore-ready, or rip-and-hold-ignore-ready.
- Job requests more than one copy with the **copy-count** attribute.
- Job contains a variable data document.
- Job contains a resource document.
- Job contains a document-definition-document.

job-size (Job Only)

See total-job-octets.

job-start-message

Provides a message that Infoprint can send to an operator when the job starts printing or transmitting. This message can alert the operator to something special about the job, for example, that the job contains confidential information.

GUI Label

Start message

DSS

A11

Type

Resettable, single-valued

Input Synonym

You can use the synonym start-message.

Allowed Values

You can enter a text string of up to 4095 characters that contains information about the job such as:

"This job is very important; call me if there is a problem."

Default Value

No default value

Usage Guidelines

- Infoprint validates and schedules jobs using this attribute against the destination attribute **start-message-supported**.
- Infoprint sends a message if the actual destination attribute **start-message-supported** value is **true** for the actual destination to which Infoprint submitted the job.
- The destination attribute **notify-operator** contains the identity of the operators that are to receive the message.
- Sending the start message does not stop the job; normally the job is printed or transmitted without operator intervention.
- Sending a start message is particularly useful for AIX printer devices that have manual forms feed capabilities. The user can send a message alerting the operator to load a special type of paper before starting the job.
- Use this attribute with the **job-start-wait** attribute for jobs that require operator intervention, for example, loading special forms in the printer device. If the values of the **job-start-message** and **job-start-wait** are true, when the job is about to be printed or transmitted, Infoprint pauses the actual destination and

the person specified by the actual destination notify-operator attribute receives the message specified by the job-start-message attribute. When the operator resumes the actual destination, the job is printed or transmitted.

job-start-wait

Pauses the actual destination just before the job is printed or transmitted.

GUI Label

Wait to start job

DSS

A11

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

No default value Default job

Job false

Usage Guidelines

- Use this attribute with the **job-start-message** attribute for jobs that require operator intervention, for example, loading special forms in the printer device. If the values of the job-start-wait and job-start-message are true, when the job is about to be printed or transmitted, Infoprint pauses the actual destination and the person specified by the actual destination **notify-operator** attribute receives the message specified by the job-start-message attribute. When the operator resumes the actual destination, the job is printed or transmitted.
- Infoprint validates and schedules jobs using this attribute against the destination attribute job-start-wait-supported.

job-state (Job Only)

See current-job-state.

job-state-reasons (Job Only)

Identifies the reasons that a job is in the **held**, **terminating**, or **retained** state. If this attribute value is blank, the job is not in one of these states.

GUI Label

Reasons

DSS

All

Type

Non-settable, multi-valued

Input Synonyms

You can use the synonym state-reasons or reasons.

Allowed Values

Infoprint sets this value to any of these fixed values:

Explanation Fixed Value

aborted-by-system

The server aborted the job.

cancelled-by-operator

An operator or system administrator cancelled the job.

cancelled-by-user

The person who submitted the job cancelled the job.

completed

The job completed without any errors or warnings that Infoprint could detect. This does not guarantee that there were no errors of any kind.

completed-successfully

The job completed without any errors or warnings.

completed-with-errors

The job completed with errors. Based on the dss-job-messagedisposition actual destination attribute, the messages associated with the errors either print at the end of the job or in a message log. See "dss-job-message-disposition" on page 379.

deadline-in-jeopardy

The value of the **estimated-completion-time** attribute for the job is later than the time specified by the job-deadline-time attribute; or the time specified by the **job-deadline-time** attribute is past.

imposition-failed

Infoprint could not arrange the pages in the job on the press sheet.

Note: You will see this reason only if the job is retained or if the value of the **requeue-failed-jobs** queue attribute is **true**. When neither of these conditions is true, jobs that fail to impose are discarded.

job-hold-set

The job is in a queue and the job-hold job attribute of the job has a true value.

job-print-after-specified

The job is in a queue and the time specified by the job-print-after job attribute has not yet occurred.

required-resource-not-ready

The job is in a queue but Infoprint cannot schedule it because one or more of the resources required by the job (such as media, fonts, and so on) are not ready on any of the actual destinations that can accept the job. The job's required-resource-not-ready attribute identifies the resources that need to be made ready.

required-resource-not-supported

The job is in a queue but Infoprint cannot schedule it because none of the actual destinations that can accept the job support one or more of the resources required by the job (such as media, fonts, and so on). The job's required-resource-not-supported attribute identifies the resources that are not supported.

rip-and-hold-completed

The RIP has successfully converted the job. The job has not been

scheduled because the value of the job-rip-action attribute is rip-and-hold or is rip-and-hold-ignore-ready.

rip-completed A job with job-rip-action=rip-and-print-ignore-ready has been RIPped, but Infoprint cannot schedule it because one or more of the resources required by the job are not ready on any of the actual destinations that can accept the job. Jobs held for this reason are released automatically when the required resources become ready.

rip-failed

The RIP failed to convert the job.

Note: You will see this reason only if the job is retained or if the value of the requeue-failed-jobs queue attribute is true. When neither of these conditions is true, jobs that fail to rip are discarded.

Default Values

No default values

job-submission-complete (Job Only)

Indicates whether the server has received all documents of the job.

GUI Label

Submission complete

DSS

All

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value to one of these fixed values:

true false

Default Value

No default value

job-ticket-content

See formatted-job-ticket-content.

last-accessor (Job Only)

See name-of-last-accessor.

last-modifier (Job Only)

See name-of-last-accessor.

list-of-managers (Default Job Only)

Identifies the persons responsible for the maintenance of this default job.

DSS

All

Type

Resettable, multi-valued

Input Synonym

You can use the synonym managers.

Allowed Values

You can enter a text string up to 255 characters long, per value, that contains the name or user ID of the person responsible for this default job.

Default Values

No default values

Usage Guidelines

This attribute is useful if a user needs to contact someone to report a problem or to request a change.

locations-requested

See destination-locations-requested.

logical-destinations-ready (Default Job Only)

Lists the enabled logical destinations that reference this default job.

DSS

All

Type

Non-settable, multi-valued

Allowed Values

Infoprint sets or deletes a text string containing the global ID of any logical destination that references this default job when the logical destination is enabled or disabled.

Input Synonym

You can use the synonym logical-printers-ready.

Default Values

No default values

Usage Guidelines

- Infoprint adds a value when a logical destination that references this default job through its **destination-initial-value-job** attribute is enabled.
- · Infoprint removes a value when a logical destination that references this default job is disabled.
- · You cannot delete this default job until Infoprint has removed all logical destinations from this list.

logical-printer-requested

See destination-name-requested.

logical-printers-ready (Default Job Only)

See logical-destinations-ready.

managers (Default Job Only)

See list-of-managers.

media-sheet-count (Job Only)

See job-media-sheet-count.

media-sheets-completed (Job Only)

Reports the number of sheets that have been used to print this job.

GUI Label

Media sheets completed

PSF, Email, Fax, Infoprint 2000, Passthrough

Type

Non-settable, single-valued

Allowed Values

Infoprint sets and updates this value to an integer from 0 through 2147483647 at the completion of each result-set.

Default Value

No default value

Usage Guidelines

How this value relates to the value of pages-completed depends on the values of the output-format, number-up, and sides document attributes.

- For a single-sided, 1-up job, pages-completed is equal to media-sheetscompleted.
- For a single-sided, slit-and-merge (2-up) job, pages-completed is twice as large as media-sheets-completed.
- For a double-sided, 3-up job, pages-completed is six times as large as media-sheets-completed.

message (Default Job Only)

Provides a message associated with the default job.

DSS

All

Resettable, single-valued

Allowed Values

You can enter a text string of up to 4095 characters that provides information about this object.

Default Value

No default value

message-from-administrator (Job Only)

See job-message-from-administrator.

message-to-operator

See job-message-to-operator.

models-requested

See destination-models-requested.

modification-time (Job Only)

Identifies the time when the last modification to this job occurred.

GUI Label

Last modified

DSS

All

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value in the local time format; for example, "HH:MM:SS mm/dd/yy" in the USA.

Default Value

No default value

name

See job-name.

name-of-last-accessor (Job Only)

Identifies the person or program that submitted the job, or most recently modified the job.

GUI Label

Last modified by

DSS

All

Type

Non-settable, single-valued

Input Synonyms

You can use the synonym last-accessor or last-modifier.

Allowed Values

Infoprint sets this value to the login ID of the person or the name of the program that submitted or most recently modified the job.

Default Value

The login ID of the person or the name of the program that submitted or most recently modified the job.

new-job-identifier (Job Only)

Identifies the global job identifier for a job resubmitted to a logical destination on a different server than where you first submitted the job.

GUI Label

New ID

DSS

All

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value to the correct values for ServerName: JobIdentifier

Default Value

No default value

Usage Guidelines

If you resubmit the job to a logical destination on the same server, the job identifier remains the same.

notification-profile

Designates the people that Infoprint notifies when specified events relating to this job occur and how Infoprint notifies the people.

GUI Label

Notification profile

DSS

All

Type

Resettable, multi-valued, complex

Syntax

-x "notification-profile={event-identifiers=event ... delivery-address=name@node delivery-method=value event-comment='some text' locale=locale}"

For example,

-x "notification-profile={event-identifiers=class-state-changed job-completed delivery-address=joe@newhope delivery-method=message locale=En US.IBM-850}"

You can omit any of these components.

Components

event-identifiers: Specifies the events for which the addressee receives notification that something has taken place.

GUI Label: Events

Type: Multi-valued

Allowed Values: The values can be any of the job events or classes of job events listed for the server. See the events-supported attribute for the server for more information.

Default Values:

• For default jobs, this component has no default values.

• For jobs, the default values are **document-aborted-by-destination**, document-aborted-by-server, document-cancelled-at-destination, job-aborted-by-server, job-cancelled-by-operator, job-cannot-be-scheduled, job-completed, past-discard-time, destination-needs-attention, destination-needs-operator, destinations-not-ready-for-job

delivery-address: Specifies the address of the person that receives the event messages or the directory and file name where Infoprint sends the message.

GUI Label: Address

Type: Single-valued

Allowed Values: You can enter a text string that contains the name and node of the person that receives the information or the path to the file.

Default Value:

- For default jobs, this component has no default value.
- For jobs, the default value is the login ID of the person who submitted the job.

delivery-method: Specifies how the user or file receives event messages.

GUI Label: Method

Type: Single-valued

Allowed Values: You can enter one of these fixed values:

Fixed Value

Input Synonym e-mail, email

electronic-mail

file file-add-to job-log message sapcb none

Default Value: message

Usage Guidelines:

- If you specify a value of file or file-add-to, you must specify a value for the delivery-address component.
- If you specify a value of **job-log**, you cannot specify a value for the delivery-address component.
- The sapcb notification method causes the SAP callback daemon to return messages about job events to the SAP database. The SAP print command sets this value; you should never have to specify it.

event-comment: Provides information that Infoprint appends to the event message.

GUI Label: Comment

Type: Single-valued

Allowed Values: You can enter a text string of up to 4095 characters that supplies additional information.

Default Value: No default value

locale:

Type: Single-valued

Allowed Values: You can enter the name of any locale for which the Infoprint messages in the corresponding language are installed.

Default Value:

- For default jobs, this component has no default value.
- For jobs, the default value is the locale of the user who submitted the job.

Usage Guidelines

A default job can have a notification profile that only has one or two components set. When you request this default job for a job, Infoprint fills the remaining components with default values for that job.

number-of-documents (Job Only)

Identifies the number of documents in the job, including resource documents such as fonts.

GUI Label

Number of documents in job

DSS

All

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value to an integer from 1 through 2147483647.

Default Value

No default value

object-class

Identifies the object class to which this object belongs.

DSS

All

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value to **job** for a job or to **initial-value-job** for a default job.

Default Value

Iob job

Default job initial-value-job

octets-completed (Job Only)

Reports the number of octets (bytes) in this job that have been printed or transmitted.

GUI Label

KBytes completed

DSS

All

Type

Non-settable, single-valued

Allowed Values

Infoprint sets and updates this value to an integer from 0 to 9223372036854775800 when:

AIX You query the job or after each document copy completes.

BSD Each result-set completes.
 PSF Each result-set completes.
 3170 Each result-set completes.
 Email Each result-set completes.
 Fax Each result-set completes.

Passthrough

Each result-set completes. IPP Each result-set completes.

Default Value

No default value

optimize-for-multiple-copies

Used with the **optimize-for-multiple-copies** actual destination attribute to indicate whether the destination should save pages in order to print multiple copies of the job faster.

GUI Label

Optimize for copies

DSS

PSF

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

No default value

Usage Guidelines

• This attribute is used in combination with the **optimize-for-multiple-copies** actual destination attribute:

Job Attribute	Destination Attribute	Results
true	true	Pages are saved
true	false	Pages are not saved
false	true	Pages are not saved
false	false	Pages are not saved
No value	true	Pages are saved
No value	false	Pages are not saved

• If the actual destination cannot save pages, the job is printed and this attribute is ignored.

originator (Job Only)

See job-originator.

owner (Job Only)

See job-owner.

pages-completed (Job Only)

Reports the number of pages in this job that have been printed, and if you are using the PSF DSS, stacked.

GUI Label

Pages completed

DSS

AIX, PSF, Infoprint 2000, Email, Fax

Type

Non-settable, single-valued

Allowed Values

Infoprint sets and updates this value to an integer from 0 through 2147483647 when:

AIX You query the job or after each document copy completes.

PSF The number of pages specified by the actual destination attribute **ack-interval** have printed and at the completion of each result-set.

Default Value

No default value

Usage Guidelines

PSF DSS

The differences between this attribute and **current-page-printing** are:

- **current-page-printing** is the number of the page being printed or transmitted, while **pages-completed** is the number of pages placed in the stacker. For example, when page 12 of the first copy of a double-sided job is printing, the value of **current-page-printing** is 12 and the value of **pages-completed** is 10.
- current-page-printing is reset with every job copy, while pages-completed is cumulative within a job. For example, when page 6 of the second copy of a 10-page job is printing, the value of current-page-printing is 6. When the same page is stacked, the value of pages-completed is 16.

Note: Stacking is applicable only with the PSF DSS.

AIX DSS

The AIX DSS determines **pages-completed** in the following order:

- 1. If the page count presented by the backend is not zero, Infoprint uses that page count.
- 2. If the user specified a page count with the page-count document attribute, Infoprint uses that page count.
- 3. When Infoprint can determine a page count form the PostScript or PCL input, Infoprint uses that page count.

Email and Fax DSSs

Infoprint uses the number of pages completed when the email or fax is successful.

Note: Infoprint does not count unsuccessful emails or faxes.

Infoprint 2000 DSS

Infoprint uses the number of pages in the job when it has been spooled to the Infoprint 2000 DSS printer.

physical-printers-requested

See actual-destinations-requested.

position-in-queue (Job Only)

See intervening-jobs.

previous-job-state (Job Only)

Identifies the state of the job before the last job-state change.

GUI Label

Previous state

DSS

All

Type

Non-settable, single-valued

Input Synonym

You can use the synonym **previous-state**.

Allowed Values

Infoprint sets and updates this value to one of these fixed values:

cancelled

held

imposing

paused

pending

pre-processing

printing

processing

retained

ripping

terminating

unknown

See the current-job-state attribute for a description of these values.

Default Value

No default value

previous-state (Job Only)

See previous-job-state.

print-after (Job Only)

See job-print-after.

printer-initial-value-job (Job Only)

See destination-initial-value-job.

printer-locations-requested

See destination-locations-requested.

printer-models-requested

See destination-models-requested.

printer-name-requested

See destination-name-requested.

printer-requested

See destination-name-requested.

printers-assigned (Job Only)

See destinations-assigned.

printers-used (Job Only)

See destinations-used.

processing-time (Job Only)

Reports the amount of time that the job has been printing or transmitting on the output device. If processing has completed, this value is the total amount of time needed to process the job.

GUI Label

Processing time

DSS

All

Type

Non-settable, single-valued

Allowed Values

Infoprint sets and updates this value using [HH:]MM. The unit is minutes or hours and minutes, separated by a colon.

Default Value

No default value

Job/Default Job

Usage Guidelines

Infoprint updates this attribute when a user queries the job with the **pdls** command. Infoprint calculates the value by comparing the value of the **started-printing-time** job-attribute value with the current time.

queue-assigned (Job Only)

Identifies the queue to which Infoprint assigned the job.

GUI Label

Queue

DSS

All

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value to the name of the queue assigned.

Default Value

No default value

Usage Guidelines

If this attribute is blank, the job does not currently reside in a queue (it may be in the **retained** state).

queue-position (Job Only)

See intervening-jobs.

reasons (Job Only)

See job-state-reasons.

required-resources-not-ready (Job Only)

Lists attribute values that this job requires, but that are not ready on the actual destination to which this job is assigned, or if the job is not assigned, on the most suitable actual destination.

GUI Label

Resources not ready

DSS

All

Type

Non-settable, multi-valued

Allowed Values

Infoprint sets this attribute to the names of the resources that are not ready.

Default Value

No default value

Usage Guidelines

 When the value of the actual destination attribute force-destination-setup is true, Infoprint can assign a job to an actual destination even if the required resources are not ready. When the job is about to be printed or transmitted, Infoprint disables the actual destination and sends a message to the operator to make the destination ready. When the operator enables the destination, the job is processed.

When the value of the actual destination attribute force-destination-setup is
false for all suitable actual destinations, Infoprint holds jobs that require
resources that are not ready and sets required-resources-not-ready to a list of
those resources.

required-resources-not-supported (Job Only)

Lists attribute values that this job requires, but that are not supported by the actual destination to which this job is assigned, or if the job is not assigned, by the most suitable actual destination.

GUI Label

Resources not supported

DSS

All

Type

Non-settable, multi-valued

Allowed Values

Infoprint sets this attribute to the names of the unsupported resources.

Default Value

No default value

Usage Guidelines

- Jobs that require unsupported attribute values can be found in the queue under either of these conditions:
 - The value of the server attribute **accept-unsupported-jobs** is **true**.
 - Job, document, or actual destination attributes change after the job has been accepted.
- When the value of the actual destination attribute force-destination-setup is true, Infoprint can assign a job to an actual destination even if the required resources are not supported. When the job is about to be printed or transmitted, Infoprint disables the actual destination and sends a message to the operator to make the destination ready. When the operator enables the destination, the job is printed or transmitted.
- When the value of the actual destination attribute force-destination-setup is
 false for all suitable destinations, Infoprint holds jobs that require resources that
 are not supported and sets required-resources-not-ready to a list of those
 resources.

results-profile

Specifies the delivery method for the hardcopy output, and designates who receives output and the number of copies for the recipient.

DSS

All

Type

AIX, BSD, PSF, IPP, Passthrough

Resettable, multi-valued, complex

Job/Default Job

Infoprint 2000

Resettable, single-valued, complex

Syntax

-x "results-profile=name@node:method:number:'some text':bin"

For example:

-x "results-profile=nr6445@bld25:pickup:2:'Please read'"

Components

delivery-address: Specifies the address of the person who receives the job output.

Type: Single-valued

Allowed Values: You can enter a text string that contains the address.

AIX Prints the first 42 characters of the address. PSF Prints the first 8 characters of the address.

Default Value: The address of the person who submitted the job.

delivery-method:

Type: Single-valued

Allowed Values: You can only enter the fixed value of pickup.

Default Value: pickup

job-copies:

Type: Single-valued

Allowed Values: You can enter an integer identifying the number of copies. A value of **0** is an error.

Default Value: 1

results-set-comment: Supplies a text string that describes the results-set value. This information may print on start sheets.

Type: Single-valued

Allowed Values: You can enter a text string of up to 4095 characters that provides information such as "Please staple this document" for the operator, or information such as "Please read before meeting tomorrow" for the person who receives the document.

Default Value: No default value

output-bin: The server does not support this component.

Usage Guidelines

The only component that the BSD DSS uses from this complex attribute is the *job-copies* component.

retained-time (Job Only)

Identifies the time that the job entered the retained state.

GUI Label

Became retained

DSS

All

Type

Non-settable, single-valued

Allowed Values

Infoprint sets the value for this attribute in the local time format; USA is "HH:MM:SS mm/dd/yy".

Default Value

No default value

Usage Guidelines

Provides status information.

retention-period

See job-retention-period.

start-message

See job-start-message.

started-printing-time (Job Only)

Identifies the time when Infoprint sent the job to the output device.

GUI Label

Started printing

DSS

All

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value using the local time format. The USA format is "HH:MM:SS mm/dd/yy".

Default Value

No default value

state-reasons (Job Only)

See job-state-reasons.

submission-time (Job Only)

Identifies the time that Infoprint added the job to the queue.

GUI Label

Submit time

Job/Default Job

DSS

All

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value using the local time format. The USA format is "HH:MM:SS mm/dd/yy".

Default Value

No default value

Usage Guidelines

The AIX DSS prints this information on the start sheet.

tape-exit (Job Only)

Identifies the user exit program used for reading this job from tape.

DSS

PSF (AIX Only), Email, Fax, Infoprint 2000

Type

Initially settable, single-valued

Allowed Values

You can enter any valid program name.

Default Value

No default value

Usage Guidelines

- You must use this attribute if the tape is not in a standard format, or if you do not specify the format for an unlabeled tape.
- The **pdls** command does not display the value of this attribute.
- This attribute is not valid for ASCII documents.

tape-format (Job Only)

Identifies the format of the tape from which Infoprint reads this job.

DSS

PSF (AIX Only), Email, Fax, Infoprint 2000

Type

Initially settable, single-valued

Allowed Values

You can enter one of these fixed values:

- f IBM fixed-block format
- v IBM variable-block format
- j JES2 spool offload format
- a Auto-detect. For IBM standard labeled tapes, Infoprint determines the tape format.
- **p** Passthrough format. Data is passed from the tape to the tape exit program for formatting.

Default Value

IBM standard labeled tapes

a

Nonstandard and unlabeled tapes

p

Usage Guidelines

- The **pdls** command does not display the value of this attribute.
- This attribute is not valid for ASCII documents.

tape-labeled (Job Only)

Indicates whether the tape from which Infoprint reads this job is an IBM standard labeled tape.

DSS

PSF (AIX Only), Email, Fax, Infoprint 2000

Type

Initially settable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

true

Usage Guidelines

- The pdls command does not display the value of this attribute.
- This attribute is not valid for ASCII documents.

tape-max-block-size (Job Only)

Identifies the maximum block size of the tape from which Infoprint reads this job.

DSS

PSF (AIX Only), Email, Fax, Infoprint 2000

Type

Initially settable, single-valued

Allowed Values

You can enter an integer from 1 to 10485760.

Default Value

32768

Usage Guidelines

- The default value is acceptable for all IBM standard labeled tapes from MVS host systems. Use the **tdump** utility to determine the maximum block size for other tapes. See "tdump Utility: Outputs Tape Contents in Human-Readable Format in Infoprint Manager for AIX" on page 182.
- The pdls command does not display the value of this attribute.
- This attribute is not valid for ASCII documents.

tape-rewind-before (Job Only)

Indicates whether to rewind the tape before reading this job.

DSS

PSF (AIX Only), Email, Fax, Infoprint 2000

Type

Initially settable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

false

Usage Guidelines

- The pdls command does not display the value of this attribute.
- This attribute is not valid for ASCII documents.

tape-rewind-unload (Job Only)

Indicates whether to rewind and unload the tape after reading this job.

DSS

PSF (AIX Only), Email, Fax, Infoprint 2000

Type

Initially settable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

true

Usage Guidelines

- The **pdls** command does not display the value of this attribute.
- This attribute is not valid for ASCII documents.

ticket-content (Job Only)

See formatted-job-ticket-content.

total-job-octets (Job Only)

Identifies the size of the job, which is the sum of all printable octets (bytes) in the job.

GUI Label

Size (KBytes)

DSS

All

Type

Non-settable, single-valued

Input Synonym

You can use the synonym job-size.

Allowed Values

Infoprint sets this value to an integer from 0 to 9223372036854775800.

Default Value

No default value

Usage Guidelines

- The server computes this value by totaling the size of all printable documents, using this algorithm:
 - 1. For each printable document in the job, multiply the value of **octet-count** by the value of **copy-count**.
 - 2. Total the values from Step 1.
 - 3. Multiply the total by the value of **job-copies** component of the **results-profile** job attribute.
- Infoprint validates jobs using this attribute against the actual destination attribute **job-size-range-supported**.
- Infoprint schedules the job against the **job-size-range-ready** actual destination attribute and the **job-size-range-supported** actual destination attribute.

user-locale (Job Only)

Identifies the language of the information that appears on the start, separator, and end sheets printed with the job and the messages for the job.

GUI Label

Submitter locale

DSS

All

Type

Non-settable, single-valued

Allowed Values

The locale of the job submitter.

Default Value

Infoprint sets this value to the locale of the job submitter.

user-name (Job Only)

Identifies the login ID of the job submitter.

GUI Label

Submitter ID

DSS

All

Job/Default Job

Type Non-settable, single-valued

Allowed Values

Infoprint sets this value to the login ID of the job submitter: username@node.

Default Value

No default value

Attributes for Logs

Infoprint automatically creates logs when a server initializes. These logs contain and keep track of such things as error messages and trace messages for the server and objects contained in the server. You cannot create or delete these logs, but you can enable or disable them. Infoprint uses a configuration file to set the initial values of attributes for error and trace logs when servers start.

The following restrictions apply to log attributes:

- The log-severity attribute applies only to error logs.
- The **log-trace-groups** attribute applies only to trace logs.
- You cannot set the values for the following attributes with the pdset command for trace logs. You can specify values using configuration files that Infoprint uses during server initialization.

log-address log-size log-wrap

Initially Settable Attribute Listing

You set this attribute based on the object type. **log-type**

Resettable Attribute Listing

You can set these attributes with the **pdset** command after Infoprint creates the log. **descriptor log-severity log-size** (error logs only; non-settable for trace logs) **log-trace-groups log-wrap**

associated-server

Indicates the name of the server in which this log resides.

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value to the name of the server when it creates the log.

Default Value

No default value

descriptor

Provides a description of this log.

Type

Resettable, single-valued

Allowed Values

You can enter a text string of up to 4095 characters that describes this log.

Default Value

If you do not enter a value, Infoprint sets the value to:

Log Type

Value

Error 'This is the standard error log.'
Trace 'This is the standard trace log.'

Usage Guidelines

The use of this attribute is optional. However, a detailed description of the way you set up this log is useful to someone who wants to obtain information from the log.

enabled

Indicates if the log is enabled. An enabled log writes messages to a log file.

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value to one of these fixed values:

true false

Infoprint implicitly sets this value through the **pdenable** and **pddisable** commands.

Default Value

The default values are:

Log TypeValueErrortrueTracefalse

log-address

Specifies the pathname where the log resides.

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value to the pathname.

Default Value

The path defined by the **PDBASE** environment variable plus the ServerName (**\$PDBASE**/ServerName).

log-identifier

Uniquely identifies this log.

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value to the name of the log.

Default Value

Log TypeValueErrordefault_errorTracedefault_trace

log-messages

Contains error messages that Infoprint can return to you on a query.

Type

Non-settable, multi-valued

Allowed Values

Infoprint stores error log information as the value of this attribute.

Default Values

No default values

Usage Guidelines

Use this attribute in conjunction with the **pdls** command and its **message-count** attribute to query for error log information.

log-severity

Identifies the severity level of the messages that Infoprint logs in this error log.

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value	Explanation
error	This setting produces a minimum of logging. Infoprint only logs
	error messages. The letter E precedes each message. An error

error messages. The letter E precedes each message. An error referencing a job signals a condition that may prevent the job from completing successfully, depending on the setting of other

parameters.

warning Infoprint logs both error and warning messages. The letter W

precedes each warning message. A warning referencing a job signals a condition that will not prevent completion of the job, but

may require some action on the part of the user or operator.

audit This is the default log severity setting. Infoprint logs error, warning, and audit messages. The letter **A** precedes each audit

message.

debug This setting logs error, warning, audit, and debug messages.

Servers generate debug messages when they begin processing each command and when they communicate with other servers. Debug messages are useful for helping to track what command a server was processing when an error occurred. The letter **D** precedes each

debug messages.

info This setting logs error, warning, audit, debug, and informational

messages. Servers generate informational messages when potentially abnormal situations occur, such as when a server is unable to deliver a notification message to a user because the user is logged off. The letter I precedes each informational message.

Default Value

debug

Usage Guidelines

This attribute is only for error logs.

log-size

Specifies how large, in kilobytes, a log file can get before the file wraps, or Infoprint stops logging events. The attribute log-wrap determines whether a log file wraps or stops logging.

Type

Non-settable (trace logs) or resettable (error logs), single-valued

Allowed Values

For an error log, you can enter an integer from 1 through 2147483647 (value represents kilobytes)

Default Value

Log Type	Value
Error	1024
Trace	8192

Usage Guidelines

- The value specified in the configuration file, if one is specified, overrides the default value when Infoprint creates the server.
- If you change the value for this attribute, Infoprint renames the current log file from errorlogname to errorlogname.BAK, and creates a new log file.

log-trace-groups

Specifies the active trace groups for the selective tracing of Infoprint component groups.

Type

Resettable, multi-valued

Allowed Values

You can enter a text string of up to 4095 characters that contains trace group IDs that Infoprint traces. You should enter a value only at the request of an IBM Service Representative.

Default Value

???? -1 (All trace groups)

Usage Guidelines

This attribute is only for trace logs. You should use it only at the request of an IBM Service Representative.

log-type

Identifies the type of log.

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value to one of these fixed values: errorlog

tracelog

Default Value

No default value

log-wrap

Specifies whether the log file should wrap when it reaches the specified value in the log-size attribute.

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

true

Usage Guidelines

The value specified in the configuration file overrides the default value when Infoprint creates the server.

object-class

Identifies the object class to which this object belongs.

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value to log.

Default Value

log

Attributes for Logical Destinations

Infoprint uses logical destinations for job routing, defaulting, and job validation. Some logical destination attributes specify the values that the logical destination supports for the corresponding job and document attributes. Before accepting a job, Infoprint verifies that the logical destination supports the values of these job and document attributes.

Notes:

- 1. If a logical destination attribute has no value, the logical destination supports all values for the corresponding job or document attribute.
- 2. If the value of the server attribute **accept-unsupported-jobs** is **false**, Infoprint also verifies that at least one actual destination supports the job and document attribute values before accepting the job.
- 3. See "Appendix C. Job Validation and Scheduling" on page 719 for tables showing the attributes used for job validation.

Attributes Not Displayed in the Infoprint Administrator's GUI

While all logical destination attributes and attribute values are supported for both basic and advanced Infoprint installations, neither Infoprint administrator's GUI displays a complete set.

- The basic Infoprint administrator's GUI displays only the attributes of greatest interest to Infoprint administrators.
- The advanced Infoprint administrator's GUI displays most attributes and attribute values, but omits a few that are used primarily in basic Infoprint installations.

You can list the values of attributes not displayed in the Infoprint administrator's GUI using the **pdls** command. You can set the values of initially settable and resettable attributes using the **pdcreate** command. You can change the values of resettable attributes using the **pdset** command.

Initially Settable Attribute Listing

You can set this attribute with the **pdcreate** command when you create a logical destination.

destination-realization

Resettable Attribute Listing

You can set these attributes with the **pdcreate** command when you create a logical destination or modify them with the **pdset** command after you create the logical destination.

associated-queue
authorize-jobs
auxiliary-sheet-selections-supported
carriage-control-types-supported
character-mappings-supported
content-orientations-supported
convert-to-ebcdic-supported
data-fidelity-problem-reported-supported
descriptor
destination-initial-value-document
destination-initial-value-job
destination-locations
destination-model

destination-support-system document-formats-supported document-types-supported end-message-supported image-out-formats-supported input-trays-supported job-size-range-supported list-of-managers maximum-copies-supported media-supported message notification-profile os2-driver-names page-select-supported plexes-supported print-qualities-supported protected-attributes sides-supported start-message-supported table-reference-characters-supported windows-driver-names windows-nt-driver-names x-image-shift-range-supported y-image-shift-range-supported

associated-queue

Identifies the queue associated with this destination. Whenever Infoprint accepts a job submitted to this logical destination, it sends the job to the queue specified by this attribute.

GUI Label

Queue fed

Type

Resettable, single-valued

Allowed Values

You can enter a text string of up to 255 characters that contains the name of the queue.

Default Value

No default value

associated-server

Indicates the name of the server in which this logical destination resides.

GUI Label

Server

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value to the *DestinationName* portion of the argument when this logical destination was created.

Default Value

No default value

authorize-jobs

Indicates whether the person submitting the job requires DCE authorization to submit a job to this logical destination.

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

false

Usage Guidelines

When the server security level is **medium**, the following rules apply when the value for this attribute is:

true Infoprint uses the login ID of the job submitter to

check if the person has **read** authority for this destination. If the person does have **read** authority,

Infoprint authorizes the job.

false Infoprint automatically authorizes the job.

auxiliary-sheet-selections-supported

Identifies the combination of start, separator, and end sheets that this logical destination supports for jobs.

Type

Resettable, multi-valued

Allowed Values

You can enter any of these fixed values:

end none sep sep-end

start start-end

start-sep

start-sep-end

Default Values

No default values (all valid values supported).

Usage Guidelines

- If you do not specify a value, the corresponding actual destination attribute controls which auxiliary sheets a user can request. The default values for the actual destination attribute are all of the supported values.
- Infoprint compares the job attribute **auxiliary-sheet-selection** to this attribute for validation.

• You can use this attribute to restrict use of this logical destination.

carriage-control-types-supported

Identifies the types of carriage controls that this logical destination supports.

Type

Resettable, multi-valued

Allowed Values

```
You can enter any of these fixed values:
    ansi-ascii
    ansi-ebcdic
    machine
    none
```

Default Values

No default values (all valid values supported).

Usage Guidelines

- Infoprint compares the document attribute **carriage-control-type** to this attribute for job validation.
- You can use this attribute to restrict use of this logical destination.

character-mappings-supported

Identifies the character mappings (code pages) that this logical destination supports.

Type

Resettable, multi-valued

Allowed Values

You can enter any of these fixed values:

```
ibm-437
ibm-850
ibm-860
ibm-863
ibm-865
ibm-932
ibm-euccn
ibm-eucjp
```

IBM-euctw Default Values

No default values (all valid values supported).

Usage Guidelines

- Infoprint compares the document attribute **default-character-mappings** to this attribute for job validation.
- You can use this attribute to restrict use of this logical destination.

content-orientations-supported

Identifies the page presentations that this logical destination supports.

Type

Resettable, multi-valued

Input Synonym

You can use the synonym **orientations-supported**.

Allowed Values

You can enter any of these fixed values:

landscape portrait reverse-portrait reverse-landscape

Default Values

No default values (all valid values supported).

Usage Guidelines

- Infoprint compares the document attribute **content-orientation** to this attribute for job validation.
- If you do not specify a value for this attribute, the corresponding actual destination attribute controls orientations. The default for the actual destination attribute is **portrait**.
- Infoprint supplies attribute files that specify the values that a particular destination model supports.
- You can use this attribute to restrict use of this logical destination.

convert-to-ebcdic-supported

Indicates whether this logical destination supports converting document data from ASCII to EBCDIC.

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

No default value (all valid values supported).

Usage Guidelines

- Use this attribute to request conversion for line-data jobs sent to a PSF actual destination.
- If you do not specify a value for this attribute, the corresponding actual destination attribute controls conversion. The default value for the actual destination attribute is true.

Note: The corresponding document attribute, convert-to-ebcdic, defaults to no value. Users specify true only if they want to convert the content of the document from ASCII to EBCDIC. Validation only fails if the user sets convert-to-ebcdic to true and either this logical destination value or the actual destination attribute value is false.

- Infoprint compares the document attribute **convert-to-ebcdic** to this attribute for job validation.
- You can use this attribute to restrict use of this logical destination.

data-fidelity-problem-reported-supported

Indicates which type of data fidelity errors this logical destination can report.

Type

Resettable, multi-valued

Allowed Values

You can enter any of these fixed values:
all
character
none
position

Default Values

No default values (all valid values supported).

Usage Guidelines

• Use this attribute to specify whether Infoprint issues error messages for print-positioning and invalid-character errors that occur for channel-attached and TCP/IP-attached printer devices.

Print positioning errors occur when the print position for the data is beyond the valid printable areas as defined by the intersection of the physical and logical pages. (A logical page identifies the printing boundaries of a physical page.) Invalid-character errors occur when the code point does not map to a character in a font.

- Infoprint compares the document attribute **data-fidelity-problem-reported** to this attribute for validation.
- You can use this attribute to restrict use of this logical destination.

descriptor

Provides a textual description of this logical destination.

GUI Label

Description

Type

Resettable, single-valued

Allowed Values

You can enter a text string of up to 4095 characters that contains a description of this logical destination. You may want to include such information as:

- The name of the department or the account number of the users who use this logical destination.
- Usage information, such as whether the logical destination provides default values for jobs or restricts use of actual destination capabilities.

Default Value

No default value

Usage Guidelines

The use of this attribute is optional. However, a detailed description is useful if you have several logical destinations or have set up restriction for this logical destination.

destination-associated-destinations

Identifies the actual destinations that receive jobs from the queue associated with this logical destination.

Type

Non-settable, multi-valued

Input Synonym

You can use the synonym printer-associated-printers.

Allowed Values

Infoprint sets this value, and the queue attribute **actual-destinations-assigned** of the queue associated with this logical destination, when the actual destination registers.

Default Values

No default value

destination-initial-value-document

Associates a default document with this logical destination.

GUI Label

Default document

Type

Resettable, single-valued

Input Synonym

You can use the synonym **printer-initial-value-document**.

Allowed Values

You can enter a text string of up to 255 characters that contains the name of the default document.

Default Value

No default value

Usage Guidelines

The default document supplies values for attributes for documents submitted to this logical destination. These values override server defaults but are overridden by document attribute values specified on the command line.

destination-initial-value-job

Associates a default job with this logical destination.

GUI Label

Default job

Type

Resettable, single-valued

Input Synonym

You can use the synonym printer-initial-value-job.

Allowed Values

You can enter a text string of up to 255 characters that contains the name of the default job.

Default Value

No default value

Usage Guidelines

The associated default job supplies values for attributes of jobs submitted to this logical destination. These values override server defaults but are overridden by job attribute values specified on the command line.

destination-locations

Identifies the locations of output devices, or the areas they service, that this logical destination allows for jobs.

GUI Label

Actual destination locations

Type

Resettable, multi-valued

Input Synonyms

You can use the synonym printer-locations or locations.

Allowed Values

You can enter a text string of up to 4095 characters, per value, that contains the locations of the output devices associated with this logical destination.

Default Values

No default values (all valid values supported).

Usage Guidelines

- Infoprint compares the job attribute **destination-locations-requested** to this attribute for validation.
- You can use this attribute to restrict use of this logical destination.
- You can query this attribute to find where destinations are located.

destination-model

Identifies the make and model ID of an output device that can accept jobs submitted through this logical destination.

Type

Resettable, single-valued

Input Synonyms

You can use the synonym printer-model or model.

Allowed Values

You can enter a text string of up to 4095 characters, per value, that contains the make and model of an output device.

Default Value

No default value (all valid values supported).

destination-name

Identifies this logical destination.

Type

Non-settable, single-valued

Input Synonyms

You can use the synonym printer-name, printer, or logical-printer.

Allowed Values

Infoprint sets this value to the *DestinationName* portion of the argument specified by the **pdcreate** command used to create this logical destination.

Default Value

No default value

Usage Guidelines

- The logical destination name must be unique within the namespace.
- Infoprint compares the job attribute actual-destination-requested to this attribute for validation.

destination-realization

Indicates whether the destination is an actual destination or a logical destination.

Type

Initially settable, single-valued

Input Synonym

You can use the synonym printer-realization.

Allowed Values

You can enter one of these values:

actual logical

Default Value

logical

destination-support-system

Identifies the DSS (type of device driver) allowed for jobs submitted to this logical destination.

Type

Resettable, single-valued

Input Synonym

You can use the synonym device-support-system.

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym aix piobe

bsd psf 3170 email fax

Passthrough

IPP

Default Value

No default value (all valid values supported).

Usage Guidelines

Infoprint compares the job attribute **dss-requested** to this attribute for validation.

destinations-ready

Identifies the actual destinations associated with this logical destination that are ready to process a job.

Non-settable, multi-valued

Input Synonym

You can use the synonym **printers-ready**.

Allowed Values

Infoprint sets this value with the name of an actual destination when a registered actual destination is ready.

A ready actual destination is one that is enabled and whose state is idle, connecting-to-printer, or printing.

Default Values

No default value

device-support-system

See destination-support-system.

document-formats-supported

Identifies the document formats that this logical destination supports.

Resettable, multi-valued

Allowed Values

You can enter any of these fixed values:

Fixed Value Input Synonym ascii dbcs-ascii ditroff d630 gif hpgl hp-gl iso-6429 jpeg line-data modca-p afpds passthru pcl hppcl, hp-pcl

pdf

postscript ps

ppds sap

sap-abap

simple-text text

tiff

Default Values

No default values (all valid values supported).

Usage Guidelines

- Infoprint compares the document attribute document-format to this attribute for job validation.
- · All documents in a job must have the same format.
- You can use this attribute to restrict use of this logical destination.

document-types-supported

Identifies the types of documents that this logical destination supports.

Type

Resettable, multi-valued

Allowed Values

You can enter any of these fixed values:

cover-sheet

document-definition

email-body

email-signature

file-reference

font

form-definition

formatted-job-ticket

insert

job-ticket

overlay

page-definition

page-segment

page-shift-file

printable

resource

variable-data

Default Values

No default values (all valid values supported).

Usage Guidelines

- Infoprint compares the document attribute **document-type** to this attribute for job validation.
- You can use this attribute to restrict use of this logical destination.

enabled

Indicates whether this logical destination is enabled and can accept jobs.

Type

Non-settable, single-valued

Allowed Values

Infoprint sets and resets this value to one of these fixed values:

true

false

Infoprint sets and resets this value based on the **pdenable** and **pddisable** commands.

Default Value

false

end-message-supported

Indicates whether this logical destination supports the job attribute **job-end-message**.

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

No default value (all valid values supported).

Usage Guidelines

- When you set this attribute value to true, operators can receive messages that
 users specify with the job-end-message job attribute when they submit the job.
 Infoprint sends the message to the operators specified by the notify-operator
 attribute for this actual destination when the job finishes printing.
- Infoprint compares the job attribute **job-end-message** to this attribute for validation.
- You can use this attribute to restrict use of this logical destination.

image-out-formats-supported

Specifies the formats of the image data, produced by the program that converts line data to AFP data, that this logical destination supports.

Type

Resettable, multi-valued

Allowed Values

You can enter any of these fixed values:

ioca-uncompressed im1 io1 io1-g4 io1-mmr asis

Default Values

No default values (all valid values supported).

Usage Guidelines

• Infoprint compares the document attribute **image-out-format** to this attribute for job validation. You should use the document attribute when you print line-data documents.

• The value **io1-g4** applies only to the destination. You cannot request this value with the document attribute **image-out-format**. If the document format is **postscript** and the value **io1-g4** for this attribute is:

Present The PostScript transform produces IO1-G4

images.

Not present The PostScript transform produces IM1 images

instead of IO1-G4 images, which the printer device associated with an actual destination that receives jobs from the queue associated with this

logical destination cannot print.

input-trays-supported

Specifies the types of input trays that this logical destination supports.

Туре

Resettable, multi-valued

Allowed Values

You can enter any of these fixed values:

auto-envelope-feed manual-envelope-feed automatic-tray middle auxiliary-envelope top auxiliary-paper tray-1 bottom tray-2 continuous-form-feed tray-3 current-selected-tray tray-4 envelope tray-5 2000-sheet large-capacity

manual

or any input tray name, for example:

alternate

auto-envelope-feed

bottom

continuous-form-feed

envelope insert

large-capacity

manual

manual-envelope-feed

middle top

Default Values

No default values (all valid values supported).

Usage Guidelines

- You can use this attribute to restrict the use of this logical destination.
- If you do not specify a value for this attribute, the corresponding actual
 destination attribute determines which input trays the actual destination
 supports and users can request.
- Infoprint compares the document attribute default-input-trays or input-tray-select to this attribute for job validation.

job-size-range-supported

Defines the range of job sizes in bytes (octets) that this logical destination will accept.

Type

Resettable, single-value, complex

Syntax

lower-limit:upper-limit

Separate the limits by a colon (:), for example:

0:1000000000

You can omit either value, for example:

0:

:1000000000

Note: If you enter a single value without a colon (*integer:*), it is considered the lower limit.

Components

lower-limit: Provides the lower limit of the job size range.

Type: Single-valued

Allowed Values: You can enter an integer from 0 to 9223372036854775800. The lower limit must be less than or equal to the upper limit. The unit value is bytes (octets).

Default Value: No default value

upper-limit: Provides the upper limit of the job size range.

Type: Single-valued

Allowed Values: You can enter an integer from 0 to 9223372036854775800. The upper limit must be greater than or equal to the lower limit. The unit value is bytes (octets).

Default Value: 9223372036854775800

Usage Guidelines

- Infoprint compares the job attribute **total-job-octets** to this attribute for validation.
- You can use this attribute to restrict the use of this logical destination.

list-of-managers

Lists the people responsible for the configuration and operation of this logical destination.

GUI Label

Managers

Type

Resettable, multi-valued

Input Synonym

You can use the synonym managers.

Allowed Values

You can enter a text string up to 255 characters long, per value, that contains the name or user ID of the person responsible for this logical destination.

Default Values

No default values

Usage Guidelines

This attribute is useful if a user needs to contact someone to report a problem or to request a change.

locations

See destination-locations.

logical-printer

See destination-name.

managers

See list-of-managers.

maximum-copies-supported

Indicates the number of document copies, in a single job, that this logical destination allows.

Type

Resettable, single-valued

Allowed Values

You can enter an integer from 1 through 2147483647.

Default Value

No default value (all valid values supported).

Usage Guidelines

- You can use this attribute to restrict the use of this logical destination by limiting the number of document copies that a user can request for jobs submitted to this logical destination.
- If you do not specify a value for this attribute, the corresponding actual destination attribute controls the number of copies allowed.
- Infoprint compares the document attribute copy-count to this attribute for job validation.

media-supported

Identifies the types of media that this logical destination supports.

Type

Resettable, multi-valued

Allowed Values

You can enter a text string up to 255 characters long that contains the names of the media. These can be:

- The medium identifiers of medium objects created by the **pdcrmed** utility. For these fixed values, see the medium **medium-identifier** attribute.
- The medium identifiers of medium objects you created yourself.
- Any names that describe the media, even if no medium objects with those names exist.

Default Values

No default values (all valid values supported).

Usage Guidelines

- You can restrict the use of this logical destination by limiting the type of media that a user can request for jobs submitted to actual destinations.
- If you do not specify a value for this attribute, the corresponding actual destination attribute determines which media the actual destination supports and users can request.
- Infoprint compares the document attribute default-medium or page-media-select to this attribute for job validation.

message

Provides information associated with this logical destination.

Type

Resettable, single-valued

Allowed Values

You can enter a text string of up to 4095 characters that contains information about this logical destination.

Default Value

No default value

model

See destination-model.

notification-profile

Designates which persons Infoprint notifies of specific events related to this logical destination, and how Infoprint notifies them.

Type

Resettable, multi-valued, complex

Syntax

-x "notification-profile={event-identifiers=event ... delivery-address=name@node delivery-method=value event-comment='some text' locale=locale}"

For example:

-x "notification-profile={event-identifiers=class-logical-destination-status delivery-address=jim@staff delivery-method=e-mail event-comment='everything ok' locale=En_US.IBM-850}"

You can omit any of these components.

Components

event-identifiers: Specifies the events for which Infoprint issues notification

messages.

Type: Multi-valued

Allowed Values: You can enter any of the values listed for the server

events-supported attribute.

Default Values: object-deleted, object-cleaned

delivery-address: Identifies the address of the person who receives event messages or the directory and file name where Infoprint stores messages.

Type: Single-valued

Allowed Values: You can enter a name and node or a path and file name.

Default Value: The login ID of the user who created this logical destination.

delivery-method: Specifies how event messages are received.

Type: Single-valued

Allowed Values: You can enter one of these fixed values:

Fixed Value Input Synonym electronic-mail e-mail, email

file

file-add-to message none

Default Value: message

Usage Guidelines: If you specify a value of **file** or **file-add-to** for this component, you must specify a value for the **delivery-address** component.

event-comment: Provides a comment that Infoprint appends to the event message.

Type: Single-valued

Allowed Values: You can enter a text string of up to 4095 characters that contains the comment.

Default Value: No default value

locale: Defines the language and code page of notification messages.

Type: Single-valued

Allowed Values: You can enter any locale for which the Infoprint messages in the corresponding language are installed.

Default Value: The locale of the person who created this logical destination.

nt-drivers

See windows-nt-driver-names.

object-class

Identifies the object class to which this object belongs.

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value to **destination**.

Default Value

destination

orientations-supported

See content-orientations-supported.

os2-driver-names

Identifies the OS/2 print drivers that can submit a data stream to this logical destination.

GUI Label

OS/2 drivers

Type

Resettable, multi-valued

Input Synonym

You can use the synonym **os2-drivers**.

Allowed Values

You can enter a text string that contains the name of the OS/2 print driver in this format:

'filename.descriptive name'

Begin and end the string with single quotation marks.

Default Values

No default values

Usage Guidelines

- Perform the following procedure on the OS/2 workstation to determine the valid OS/2 driver names:
 - 1. Open the OS/2 **Templates** folder.
 - 2. Drag the Printer icon to your Desktop. The OS/2 Create a Printer window displays.
 - 3. Select the Install new destination driver... push button. The Install New Printer Driver window displays listing the names of destination drivers shipped with OS/2.

- If OS/2 does not provide the destination driver that you want to use, select the Other OS/2 destination driver radio button and load the diskette containing the driver. OS/2 refreshes the list with the drivers contained on the diskette.
- 4. Locate the destination driver or drivers you want to use for jobs submitted through the OS/2 client and record the names you will assign to the os2-driver-names logical destination attribute. The format of the name you will assign as a value for the logical destination attribute differs from the format in the OS/2 list. First, record the file name of the driver followed by a period, such as LASERJET. (all driver files listed have the DRV file extension). Next, record the descriptive name of the driver, such as IBM 4019 LaserPrinter E. For each driver listed by OS/2, the descriptive name appears twice on the same line, separated by a colon. Finally, surround the driver name and descriptive name with single quotation marks.

See the following examples of how to construct values for the **os2-driver-names** logical destination attribute:

- To use the destination driver listed as IBM 4019 LaserPrinter E: IBM 4019 LaserPrinter E (IBM4019.DRV), record the name 'IBM4019.IBM 4019 LaserPrinter E'
- To use the destination driver listed as IBM 4019 v52_1 (17 Fonts): IBM 4019 v52_1 (17 Fonts) (PSCRIPT.DRV), record the name 'PSCRIPT.IBM 4019 v52_1 (17 Fonts)'
- To use the destination driver listed as IBM 4029 (39 Fonts 600 Dpi): IBM 4029 (39 Fonts 600 Dpi) (PSCRIPT.DRV), record the name 'PSCRIPT.IBM 4029 (39 Fonts 600 Dpi)'
- 5. You must have any driver that you specify as a value for the os2-driver-names logical destination attribute installed on the OS/2 workstation. To determine if the driver is installed, select the Install push button.
 - If the driver is installed, OS/2 displays a message indicating this.
 - If the driver is not installed, OS/2 displays a window requesting that you load the media containing the driver. You must install the destination driver if you want to use it. Select the Help button in the window to access the OS/2 help information for installing destination drivers.

In most cases, you select the driver based on the data stream required by the output device. However, if you will be submitting jobs from the OS/2 client to a PSF actual destination, you should select a generic destination driver, such as **PSCRIPT.DRV**, instead of one for a specific device. Otherwise, the driver may generate device-specific data streams that Infoprint cannot transform correctly.

- 6. After you have recorded the OS/2 driver names and ensured that the drivers you want to use are installed, close all OS/2 windows that you opened during this procedure.
- You can use this attribute to restrict use of this logical destination.

os2-drivers

See os2-driver-names.

page-select-supported

Specifies the type of page number that this logical destination supports.

Type

Resettable, multi-valued

Allowed Values

You can enter a fixed value of numeric. This means that the value for the document attribute page-select can only be numeric.

Default Value

numeric

Usage Guidelines

Infoprint compares the document attribute page-select against this attribute for job validation and scheduling.

plexes-supported

Identifies the plexes that this destination supports. Plex indicates whether the page images of the output document are conditioned for eventual one-sided or two-sided printing, and the relative orientation of consecutive pages.

Resettable, multi-valued

Allowed Values

You can enter any of these fixed values:

simplex tumble

Default Values

No default values (all valid values supported).

Usage Guidelines

Infoprint compares the document attribute **plex** to this attribute for job validation.

print-qualities-supported

Identifies the levels of print quality that this logical destination supports.

Type

Resettable, multi-valued

Input Synonym

You can use the synonym qualities-supported.

Allowed Values

You can enter any of these fixed values:

draft high normal

Default Values

No default values (all valid values supported).

Usage Guidelines

- Infoprint compares the document attribute print-quality to this attribute for job validation.
- You can use this attribute to restrict use of this logical destination.

Logical Destination

printer

See destination-name.

printer-associated-printers

See destination-associated-destinations.

printer-initial-value-document

See destination-initial-value-document.

printer-initial-value-job

See destination-initial-value-job.

printer-locations

See destination-locations.

printer-model

See destination-model.

printer-name

See destination-name.

printer-realization

See destination-realization.

printers-ready

See destinations-ready.

protected-attributes

Specifies one or more logical destination attributes that DCE prevents Infoprint operators from setting or changing.

Type

Resettable, multi-valued

Allowed Values

You can enter one or more logical destination attribute names.

Default Values

This attribute always specifies itself, **protected-attributes**, as a value.

Usage Guidelines

Normally, anyone with DCE write permission for logical destinations can set values for logical destination attributes. By default, the <code>pd_admin</code> and <code>pd_operator</code> DCE groups both have write permission. Once you define a logical destination attribute as a protected attribute, you must have DCE <code>delete</code> permission to modify the attribute. Members of the <code>pd_operator</code> DCE group do not have <code>delete</code> permission unless the DCE administrator has modified the default permissions for that group.

qualities-supported

See print-qualities-supported.

sides-supported

Identifies whether this logical destination supports printing on one or both sides of the media.

Type

Resettable, multi-valued

Allowed Values

You can enter an value of 1, 2, or both.

Default Values

No default values (all valid values supported).

Usage Guidelines

- You can use this attribute to restrict use of this logical destination.
- If you do not specify a value for this attribute, the corresponding actual destination attribute controls the printable sides that users can request.
- Infoprint compares the document attribute sides to this attribute for job validation.

start-message-supported

Indicates whether this logical destination supports the job attribute job-start-message.

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

No default value (all valid values supported).

Usage Guidelines

- When you set this attribute value to true, operators can receive messages that users specify with the job-start-message job attribute when they submit the job. Infoprint sends the message to the operators specified by the **notify-operator** attribute for this actual destination when the job starts printing. Sending a start message does not stop the job from printing; normally the job prints without operator intervention.
- Infoprint compares the job attribute job-start-message to this attribute for validation.
- You can use this attribute to restrict use of this logical destination.

table-reference-characters-supported

Identifies whether this logical destination supports table-reference characters. Some line-data applications produce table-reference characters to specify font changes.

Type

Resettable, single-valued

Logical Destination

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

No default value (all valid values supported).

Usage Guidelines

• If you do not specify a value for this attribute, the corresponding actual destination attribute determines whether the actual destination can process table reference characters.

The corresponding document attribute, **table-reference-characters**, defaults to no value. The user specifies **true** only if the line data contains table reference characters that should be processed. Validation fails only if the user sets **table-reference-characters** to **true** and either this logical destination value or the actual destination attribute value is **false**.

- Infoprint compares the document attribute **table-reference-characters-supported** to this attribute for job validation.
- You can use this attribute to restrict use of this logical destination.

windows-driver-names

Identifies the Windows 3.1.1 or WIN-OS/2 print drivers that can submit a data stream to this logical destination.

GUI Label

Windows 3.1 drivers

Type

Resettable, multi-valued

Input Synonym

You can use the synonym windows-drivers.

Allowed Values

You can enter a text string that contains the string form of the Windows print driver for each permitted Windows print driver. Begin and end the string with single quotation marks.

Default Values

No default values

Usage Guidelines

- Perform the following procedure to determine the valid Windows driver names.
 - 1. For WIN-OS/2, start a WIN-OS/2 full-screen session to access the Windows **Program Manager**.
 - 2. Select and open the Control Panel icon from the main window.
 - 3. Select and open the **Printers** icon.
 - 4. Select the **Add** >> push button from the **Printers** dialog box.
 - 5. The values listed in the <u>List of Printers</u>: list box are the names of the Windows destination drivers that you can install on the workstation; for example, IBM 4039 LaserPrinter PS.

Notes:

- 1. Other destination drivers are available and may not display in the list for a particular workstation.
- 2. If you will be submitting jobs from the Windows client to a PSF actual destination, you should select a generic device driver, such as a PostScript driver, instead of one for a specific device. Otherwise, the driver may generate device-specific data streams that Infoprint cannot transform correctly.
- You can use this attribute to restrict use of this logical destination.

windows-drivers

See windows-driver-names.

windows-nt-driver-names

Identifies the 32-bit Windows print drivers that can submit a data stream to this logical destination.

GUI Label

Windows drivers

Type

Resettable, multi-valued

Input Synonyms

You can use the synonym windows-nt-drivers or nt-drivers.

Allowed Values

You can enter a text string that contains the string form of the Windows print driver for each permitted Windows print driver. Begin and end the string with single quotation marks.

Default Values

No default values

Usage Guidelines

- Perform the following procedure to determine the valid Windows driver names:
 - 1. Select **My Computer** from the desktop.
 - 2. Select and open the **Control Panel** icon.
 - 3. Select and open the Printers icon,
 - 4. Select and open the Add Printer icon.
 - 5. The values listed in the **Printers:** list box in the **Add Printer Wizard** are the names of the Windows destination drivers that you can install on the workstation; for example, IBM 4039 LaserPrinter PS.

Notes:

- 1. Other destination drivers are available and may not display in the list for a particular workstation.
- 2. If you will be submitting jobs from the Windows client to a PSF actual destination, you should select a generic destination driver, such as a PostScript driver, instead of one for a specific type of destination. Otherwise, the driver may generate device-specific data streams that Infoprint cannot transform correctly.
- You can use this attribute to restrict use of this logical destination.

Logical Destination

windows-nt-drivers

See windows-nt-driver-names.

x-image-shift-range-supported

Specifies, in millimeters, the lower and upper numeric boundaries for the X offset of a page. The X offset, along with the Y offset, sets the origin of the logical page on the physical page.

Type

Resettable, single-valued, complex

Syntax

lower-limit:upper-limit

Each value uses a format of *nnnn.nnn* where *nnnn.nnn* is the decimal millimeter value. Separate the values with a colon, for example:

1:10

Components

lower-limit: Defines the minimum amount of image shift that the document or default document attribute **x-image-shift** or **x-image-shift-back** can specify.

Type: Single-valued

Allowed Values: You can enter a numeric value from -577.99 mm through 577.97 mm.

Default Value: No default value

upper-limit: Defines the maximum amount of image shift that the document or default document attribute **x-image-shift** or **x-image-shift-back** can specify.

Type: Single-valued

Allowed Values: You can enter a numeric value from -577.99 mm through 577.97 mm.

Default Value: No default value

Usage Guidelines

You can use this attribute to restrict use of this logical destination.

y-image-shift-range-supported

Specifies, in millimeters, the lower and upper numeric boundaries for the Y offset of a page. The Y offset, along with the X offset, sets the origin of the logical page on the physical page.

Type

Resettable, single-valued, complex

Syntax

lower-limit:upper-limit

Logical Destination

Each value uses a format of nnnn.nnn where nnnn.nnn is the decimal millimeter value. Separate the values with a colon, for example: 1:20

Components

lower-limit: Defines the minimum amount of image shift that the document or default document attribute y-image-shift or y-image-shift-back can specify.

Type: Single-valued

Allowed Values: You can enter a numeric value from -577.99 mm through 577.97 mm.

Default Value: No default value

upper-limit: Defines the maximum amount of image shift that the document or default document attribute **y-image-shift** or **y-image-shift-back** can specify.

Type: Single-valued

Allowed Values: You can enter a numeric value from -577.99 mm through 577.97

Default Value: No default value

Usage Guidelines

You can use this attribute to restrict use of this logical destination.

Attributes for Media

A medium represents the type of media, that is, paper, envelopes, transparencies, or multi-part forms, on which a printer device prints.

Infoprint uses the names of media as values for actual destination attributes, such as media-supported. Actual destination attributes that reference media can use any name as long as the name is within syntax limits. The AIX and 3170 DSSs validate any actual destination attribute that references a medium to ensure that the object exists. The BSD and PSF DSSs accept values that are not the names of existing media.

You must create at least the default medium objects. The startsrv utility normally creates the default medium objects. If it fails to do so, use the pdcrdflt utility to create the default medium and auxiliary sheet objects.

Attributes Not Displayed in the Infoprint Administrator's GUI

While all medium attributes are supported for both basic and advanced Infoprint installations, the basic Infoprint administrator's GUI displays only the medium attributes of greatest interest to Infoprint administrators. The advanced Infoprint administrator's GUI does not display media.

You can list the values of attributes not displayed in the Infoprint administrator's GUI using the the pdls command. You can set the values of initially settable and resettable attributes using the pdcreate command. You can change the values of resettable attributes using the **pdset** command.

Initially Settable Attribute Listing

There are no initially settable attributes for a medium.

Resettable Attribute Listing

You can set these attributes with the pdcreate command when you create a medium or modify them with the pdset command after you create the medium.

descriptor medium-color medium-dimensions medium-form-parts medium-holes-count medium-sides medium-size medium-type medium-weight message

associated-server

Indicates the name of the server in which this medium resides.

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value to the value of the ServerName portion of the argument when you create the medium using the **pdcreate** command.

Default Value

No default value

descriptor

Provides a description of the medium.

Resettable, single-valued

Allowed Values

You can enter a text string up to 4095 characters long that describes this medium.

Default Value

No default value

Usage Guidelines

The use of this attribute is optional. However, a detailed description of this medium and its use is helpful to users who want to determine if this is the medium that they want to use.

medium-color

Indicates the color of this medium.

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values or some other color:

Fixed Value Input Synonym

blue buff goldenrod green pink

untinted transparent

white yellow

Default Value

No default value

Usage Guidelines

Specifying the color can be useful if you have configured a large number of AIX actual destinations and have used the media-supported and input-trays-medium attributes to identify the different types of media that the actual destination supports and the media currently loaded in the input trays of each printer device. This allows a user to query and filter for the colors of various medium objects to determine the medium to use for a job.

medium-dimensions

Specifies the physical size (width and length), in millimeters, of the medium.

Resettable, single-valued, complex

Syntax

You can enter two positive real numbers separated by a colon.

x-dimension:*y*-dimension

For example: 100.8:200.4

Components

x-dimension: Specifies the width of the medium, which is usually the shorter dimension in respect to how the medium is loaded into the printer device.

Type: Single-valued

Allowed Values: You can enter a positive real number, which may optionally contain a decimal point. The unit is millimeters.

Default Value: No default value

y-dimension: Specifies the height of the medium, which is usually the longer dimension in respect to how the medium is loaded into the printer device.

Type: Single-valued

Allowed Values: You can enter a positive real number, which may optionally contain a decimal point. The unit is millimeters.

Default Value: No default value

Usage Guidelines

- The medium must contain this value if AIX actual destinations use the medium.
- The **piobe** backend uses the value of this attribute to determine the printable area of the medium.
- How you specify the dimensions depends on the printer model and how the
 medium is loaded. If you get unexpected output from a printer device, try
 reversing the order in which you specify the dimensions for a medium that the
 actual destination references.

medium-form-parts

Indicates the number of form parts for this multi-part form medium.

Type

Resettable, single-valued

Allowed Values

You can enter an integer from 1 through 2147483647.

Default Value

No default value

Usage Guidelines

This attribute only applies to media whose **medium-type** is **multi-part-forms**.

medium-holes-count

Indicates the number of holes (if any), pre-punched in the medium.

Type

Resettable, single-valued

Allowed Values

You can enter an integer from 0 through 2147483647.

Default Value

No default value

medium-identifier

Uniquely identifies a particular medium within a server.

Non-settable, single-valued

Allowed Values

Infoprint sets this value to the MediumName portion of the argument when you create this medium. The value is either a text string up to 255 characters that you enter or one of these fixed values:

A0	B8	JPOSTD
A1	B9	ledger
A2	B10	legal
A3	C4-envelope	letter
A3-colored	C5-envelope	letter-tab
A4	a	manual
A4-colored	b	monarch-envelope
A4-tab	c	na-legal-colored
A4-transparent	d	na-letter-colored
A5	designated-long-envelope	na-letter-transparent
A5-colored	e	na-number-9-envelope
A6	executive	na-number-10-envelope
A7	folio	na-6x9-envelope
A8	hagaki	na-7x9-envelope
A9	invoice	na-9x11-envelope
A10	jis-b0-white	na-9x12-envelope
B0	jis-b1-white	na-10x13-envelope
B1	jis-b2-white	na-10x14-envelope
B2	jis-b3-white	na-10x15-envelope
B3	jis-b4-colored	quarto
B4	jis-b4-white	statement
B4-colored	jis-b5-colored	tabloid
B4-envelope	jis-b5-white	universal-paper
B5	jis-b6-white	universal-envelope
B5-colored	jis-b7-white	8x10.5
B5-envelope	jis-b8-white	8.5x12.4
В6	jis-b9-white	9x11
B7	jis-b10-white	12x18
	•	

Default Value

No default value

medium-sides

Indicates the number of printable sides for the medium.

Type

Resettable, single-valued

Allowed Values

You can enter an integer of 1 or 2.

Default Value

No default value

medium-size

Specifies the size of the medium by means of a predefined name for the size. Examples of values include **invoice**, which specifies a medium of 5.5 inches by 8.5 inches, and **ledger**, which specifies a size of 11 inches by 17 inches.

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

iso-a0	iso-b10	jis-b8
iso-a1	iso-c3	jis-b9
iso-a2	iso-c4	jis-b10
iso-a3	iso-c5	ledger
iso-a4	iso-c6	legal
iso-a5	a	letter
iso-a6	b	monarch-envelope
iso-a7	c	na-number-9-envelope
iso-a8	d	na-number-10-envelope
iso-a9	iso-designated-long	na-6x9-envelope
iso-a10	e	na-7x9-envelope
iso-b0	executive	na-9x11-envelope
iso-b1	folio	na-9x12-envelope
iso-b2	invoice	na-10x13-envelope
iso-b3	jis-b0	na-10x14-envelope
iso-b4	jis-b1	na-10x15-envelope
iso-b5	jis-b3	quarto
iso-b6	jis-b4	8x10.5
iso-b7	jis-b5	8.5x12.4
iso-b8	jis-b6	9x11
iso-b9	jis-b7	12x18

Default Value

No default value

medium-type

Identifies the medium type.

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value	Description
continuous-long	Continuous-forms paper with the forms connecting along the long edge of the form.

continuous-short Continuous-forms paper with the forms connecting

along the short edge of the form.

Medium

envelope Standard envelopes that may or may not have

preprinted information and that do not have

windows.

labels Any type of label.

multi-part-form Forms containing multiple layers that are not

attached to one another.

plain Separately cut sheets of paperstationery Separately cut sheets of paper

tab-stock Paper that has tabs.

transparency Separate sheets of a transparent material.

Default ValueNo default value

medium-weight

Identifies the medium weight.

Type

Resettable, single-valued

Allowed Values

You can enter a positive real number.

Default Value

No default value

message

Provides a message associated with this medium object.

Type

Resettable, single-valued

Allowed Values

You can enter a text string up to 4095 characters long that contains information about this medium object.

Default Value

No default value

object-class

Identifies the object class to which this object belongs.

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value to medium.

Default Value

medium

Attributes for Queues

A queue is an Infoprint object that manages a collection of jobs that are waiting to print. A queue receives jobs from one or more logical destinations and sends jobs to one or more actual destinations.

Initially Settable Attribute Listing

There are no initially settable attributes for queues.

Resettable Attribute Listing

You can set these attributes with the **pdcreate** command when you create the queue or modify them with the **pdset** command after you create the queue.

assign-to-destination backlog-lower-bound backlog-update-interval backlog-upper-bound descriptor list-of-managers message notification-profile notify-operator protected-attributes requeue-failed-jobs

actual-destinations-assigned

Lists the actual destinations that receive jobs from this queue.

Type

Non-settable, multi-valued

Input Synonym

You can use the synonym physical-printers-assigned.

Allowed Values

Infoprint adds the actual destination name to this value when each actual destination registers and its **associated-queue** attribute value is the name of this queue.

Default Values

No default values

actual-destinations-ready

Lists the ready actual destinations that can receive jobs from this queue.

Type

Non-settable, multi-valued

Input Synonym

You can use the synonym physical-printers-ready.

Allowed Values

Infoprint adds an actual destination name to this value for each actual destination that can receive a job from this queue. An actual destination becomes ready when it is enabled and the state is either **idle**, **connecting-to-destination**, or **printing**.

Default Values

No default values

assign-to-destination

Indicates whether the queue assigns jobs to actual destinations as soon as they are accepted or waits until an actual destination is available.

Type

Resettable, single-valued

Input Synonym

You can use the synonym assign-to-printer.

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

Basic true Advanced false

Usage Guidelines

• When the value of **assign-to-destination** is **true**, the queue assigns jobs to an actual destination as soon as the server accepts them (early binding), unless no actual destination supports a job's required attribute values. If something prevents the assigned actual destination from printing the job, or if another actual destination becomes available first, you must reassign the job using the Infoprint administrator's GUI.

Early binding is the defining characteristic of a basic Infoprint installation.

• When the value of **assign-to-destination** is **false**, the queue waits until a job is next to be scheduled to print, then assigns it to the first suitable actual destination to become available (late binding).

Late binding is the defining characteristic of an advanced Infoprint installation.

- A job must be assigned to an actual destination before Infoprint can calculate the estimated completion time for the job.
- The server accepts the job even when the **actual-destinations-requested** specifies a non-existent actual destination **only when accept-unsupported-jobs** is **true** and the print queue has **assign-to-printer** as **false**,

associated-server

Indicates the name of the server in which this queue resides.

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value to the *ServerName* portion of the argument you specify when you create this queue with the **pdcreate** command.

Default Value

No default value

backlog

See queue-backlog.

backlog-lower-bound

Identifies the limit (time to print jobs within the queue) below which you do not consider the queue backlogged. Infoprint resets a backlogged condition when the queue-backlog value is less than this value, if you enable backlog computing.

Type

Resettable, single-valued

Allowed Values

You can enter a value using [HH:]MM. The unit is minutes or hours and minutes, separated by a colon.

Syntax

backlog-lower-bound=[HH:]MM

For example:

backlog-lower-bound=70 backlog-lower-bound=1:10

Default Value

No default value

Usage Guidelines

- You must set the value for this attribute to less than or equal to the value you specify for the backlog-upper-bound attribute.
- Infoprint sets the value for the attribute backlogged to false when the value for the queue-backlog attribute becomes less than this value if you enable backlog computing (backlog-update-interval value not equal to 0).

backlog-update-interval

Specifies how often Infoprint computes the queue backlog.

Type

Resettable, single-valued

Allowed Values

You can enter a value using [HH:]MM. The unit is minutes or hours and minutes, separated by a colon.

Setting this value to 0 disables backlog computing.

Default Value

The greater value of the following:

The value of the **backlog-upper-bound** attribute divided by 30.

Usage Guidelines

- You must set the value for this attribute to be less than or equal to the value you specify for the backlog-upper-bound attribute.
- Infoprint sets this default value when you create the queue. If you change the value for the backlog-upper-bound attribute later with the pdset command, Infoprint does not change the value for this attribute.

backlog-upper-bound

Identifies the limit (time to print the jobs in the queue) above which you consider the queue backlogged.

Type

Resettable, single-valued

Allowed Values

You can enter a value using [HH:]MM. The unit is minutes or hours and minutes, separated by a colon.

Default Value

No default value

Usage Guidelines

- You must set the value for this attribute to be greater than or equal to the value you specify for the **backlog-lower-bound** attribute.
- Infoprint sets the value for the attribute **backlogged** to **true** when the value for the **queue-backlog** attribute exceeds this value if you enable backlog computing.

backlogged

Identifies whether the queue is backlogged.

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value to one of these fixed values:

true

false

Default Value

false

Usage Guidelines

- Infoprint sets this attribute value to **true** when you enable backlog computing (**backlog-update-interval** not equal to 0) and the **queue-backlog** value exceeds the **backlog-upper-bound** value.
- Infoprint sets this attribute value to **false** when the **queue-backlog value** falls below the **backlog-lower-bound** value.

current-backlog

See queue-backlog.

descriptor

Provides a description of this queue.

Type

Resettable, single-valued

Allowed Values

You can enter a text string of up to 4095 characters that describes this queue. You may want to specify such things as:

- The name of the department or the account number for the users of this queue.
- Any other information that is unique to your company or organization.

Queue

Default Value

No default value

Usage Guidelines

The use of this attribute is optional. However, a detailed description of this queue is helpful to users who want to determine where to submit a given job or administrators who want to determine which queue to associate with a logical destination.

list-of-managers

Lists the people responsible for the configuration and operation of this queue.

Type

Resettable, multi-valued

Input Synonym

You can use this synonym managers.

Allowed Values

You can enter a text string up to 255 characters long, per value, that contains the name or ID of the person responsible for this queue.

Default Values

No default values

Usage Guidelines

This attribute is useful if a user needs to contact someone to report a problem or to request a change.

logical-destinations-assigned

Lists the logical destinations associated with this queue.

Type

Non-settable, multi-valued

Input Synonym

You can use the synonym logical-printers-assigned.

Allowed Values

Infoprint adds to this value the logical destination name of a newly created logical destination if the associated-queue attribute value for that logical destination identifies this queue.

Default Values

No default values

logical-destinations-ready

Lists the enabled logical destinations that can send jobs to this queue.

Type

Non-settable, multi-valued

Input Synonym

You can use the synonym **logical-printers-ready**.

Allowed Values

Infoprint adds a logical destination name to this value for each logical destination that is assigned to the queue and that is enabled.

Default Values

No default values

Usage Guidelines

Infoprint changes this value as you enable or disable logical destinations.

logical-printers-assigned

See logical-destinations-assigned.

logical-printers-ready

See logical-destinations-ready.

managers

See list-of-managers.

message

Provides a message associated with this queue.

Type

Resettable, single-valued

Allowed Values

You can enter a text string of up to 4095 characters that contains information about this queue.

Default Value

No default value

notification-profile

Designates which persons Infoprint notifies of specific events related to this queue, and how Infoprint notifies them.

Type

Resettable, multi-valued, complex

Syntax

-x "notification-profile={event-identifiers=event ... delivery-address=name@node delivery-method=value event-comment='some text' locale=locale}"

For example:

-x "notification-profile={event-identifiers=queue-state-changed object-cleaned delivery-address=Kathy@test delivery-method=message event-comment='Better check' locale=En_US.IBM-850}"

You can omit any of these components.

Components

event-identifiers: Specifies the events for which the person receives messages.

Type: Multi-valued

Allowed Values: You can enter queue events listed for the server **events-supported** attribute.

Queue

Default Values: object-cleaned, object-deleted, queue-backlogged

delivery-address: Specifies the address of the person who receives the event messages or the directory location and file name where Infoprint stores the message.

Type: Single-valued

Allowed Values: You can enter the login ID and node of the person who is to receive the messages or the path of the directory and a file name.

Default Value: The login ID of the person who created this queue.

delivery-method: Specifies how the user receives the event messages.

Type: Single-valued

Allowed Values: You can enter one of these fixed values:

Fixed Value Input Synonym electronic-mail e-mail, email

file file-add-to message none

Default Value: message

Usage Guidelines: If you specify a value of **file** or **file-add-to** for this component, you must specify a value for the **delivery-address** component.

event-comment: Provides textual information that Infoprint appends to the event message.

Type: Single-valued

Allowed Values: You can enter a text string of up to 4095 characters that contains the information about the event.

Default Value: No default value

locale: Defines the language and code page of notification messages.

Type: Single-valued

Allowed Values: You can enter any locale for which the Infoprint messages in the corresponding language are installed.

Default Value: The locale of the person who created this queue.

notify-operator

Identifies people who are to receive the message defined by the job attribute **job-message-to-operator**.

Type

Resettable, multi-valued, complex

Input Synonym

You can use the synonym **operators**.

Syntax

delivery-method:delivery-address

Separate the components with a colon, for example: message:op3@fastpr

Components

delivery-method: Specifies how the person is to receive the messages.

Type: Single-valued

Allowed Values: You can enter one of these fixed values:

electronic-mail message none

Default Value: message

delivery-address: Specifies the address of the person who receives the message.

Type: Single-valued

Allowed Values: You can enter a text string that contains the login ID and node of the person who receives the message.

Default Value: The login ID of the person who created this queue.

object-class

Identifies the object class to which this object belongs.

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value to queue.

Default Value

queue

operators

See **notify-operator**.

physical-printers-assigned

See actual-destinations-assigned.

physical-printers-ready

See actual-destinations-ready.

protected-attributes

Specifies one or more queue attributes that DCE prevents Infoprint operators from setting or changing.

Type

Resettable, multi-valued

Allowed Values

You can enter one or more queue attribute names.

Default Values

This attribute always specifies itself, protected-attributes, as a value.

Usage Guidelines

Normally, anyone with DCE write permission for queues can set values for queue attributes. By default, the **pd_admin** and **pd_operator** DCE groups both have write permission. Once you define a queue attribute as a protected attribute, you must have DCE **delete** permission to modify the attribute. Members of the **pd_operator** DCE group do not have **delete** permission unless the DCE administrator has modified the default permissions for that group.

queue-backlog

Specifies the amount of time that this queue might be backlogged. This is a computed estimate of time it takes to print all of the jobs currently in the queue.

Type

Non-settable, single-valued

Input Synonyms

You can use the synonyms backlog or current-backlog.

Allowed Values

Infoprint sets this value to [HH:]MM. The unit is minutes or hours and minutes, separated by a colon.

Default Value

No default value

queue-name

Uniquely identifies this queue object.

Type

Non-settable, single-valued

Allowed Values

Infoprint set this value to the *QueueName* portion of the argument from the **pdcreate** command when this queue is created.

Default Value

No default value

Usage Guidelines

This queue name must be unique within the namespace.

queue-state

Identifies the current state of the queue.

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value to one of these fixed values:

Fixed Value Explanation

paused Infoprint will not schedule jobs in the queue to the

actual destinations associated with this queue. The queue will still receive jobs from its associated

logical destinations if they are enabled.

ready Infoprint can schedule jobs in the queue to the

actual destinations associated with this queue.

Default Value

No default value

requeue-failed-jobs

Indicates whether jobs that fail to RIP, impose, or print should be replaced in the queue.

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

Basic true Advanced false

Usage Guidelines

- When the value of **requeue-failed-jobs** is **true**, jobs that fail to print for any of these reasons:
 - The server cancels the job.
 - Infoprint fails to RIP the job.
 - Infoprint fails to impose the job.

are replaced in the queue in the **held** state.

- When the value of requeue-failed-jobs is false, jobs that fail to print for these reasons are retained if there is a value for the job-retain-until or job-retention-period job attribute. Otherwise, these jobs are discarded.
- For any value of **requeue-failed-jobs**, jobs that fail to print because of actual destination problems are replaced in the queue in the **pending** state. If another actual destination is available, these jobs are rescheduled.

Attributes for Resource Contexts

Infoprint uses resource contexts to determine the location of PSF resources. Actual destination attributes, such as **resource-context**, **resource-context-font**, or **resource-context-overlay**, reference the names of resource contexts.

The different types of AFP resources are:

Fonts A font is a single size and typeface in a particular type family including letters, numerals, punctuation marks, special characters, and ligatures.

Form definitions

Form definitions provide instructions on how output devices position data on the page. Form definitions can specify overlays, a paper source for cut-sheet printer devices, duplexing, text suppression, data position, and the number and modifications of pages.

Overlays

Overlays are collections of predefined data such as lines, shading, text boxes, or logos, that an output device can merge with variable data on a page or a form.

Page definitions

Page definitions contain the formatting controls for line data. Page definitions can include controls for the number of lines per logical page, font selection, print direction, and the mapping of individual fields to positions on the logical page.

Page segments

Page segments contain text and images that an output device can include at any addressable point on a page or an electronic overlay.

The resource context attribute **context-address** identifies the path name of the directory that contains the corresponding PSF resource. Instead of entering the full path name as the value of an actual destination attribute, you can reference the resource context. You can also reference resource contexts during print submission using certain document attributes.

Only PSF, fax, and email actual destinations use resource contexts.

Initially Settable Attribute Listing

There are no initially settable attributes for a resource context.

Resettable Attribute Listing

You can set these attributes with the **pdcreate** command when you create a resource context or modify them with the **pdset** command after you create the resource context.

context-address descriptor

associated-server

Indicates the server in which this resource context resides.

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value to the ServerName portion of the argument specified with the pdcreate command when this resource context is created.

Default Value

No default value

context-address

Defines the path for the location of this PSF resource.

Type

Resettable, single-valued

Allowed Values

You enter a text string up to 4095 characters long that contains the path name. Separate multiple path names with colons.

Syntax

path:path

For example:

/fonts:/dept123/fonts

Default Value

No default value

descriptor

Provides a description of this resource context.

Type

Resettable, single-valued

Allowed Values

You can enter a text string up to 4095 characters long that describes this resource context.

Default Value

No default value

Usage Guidelines

The use of this attribute is optional. However, a detailed description of the resource that this resource context references can be helpful to a users who need to determine which resource context to use.

object-class

Identifies the object class to which this object belongs.

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value to **resource-context**.

Default Value

resource-context

Resource Context

resource-context-identifier

Uniquely identifies this resource context within a server.

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value to the ResourceContextName portion of the argument specified with the pdcreate command when this resource context is created.

Default Value

No default value

Attributes for Servers

An Infoprint server is an object that represents the server that manages the validation, routing, and scheduling of jobs.

Initially Settable Attribute Listing

There are no specifiable attributes for a server.

Resettable Attribute Listing

You can modify these attributes with the **pdset** command after you create a server. **accept-unsupported-jobs**

auto-create-shared-printers (Windows NT and Windows 2000 only)

descriptor

job-submission-timer

list-of-managers

log-accounting-data

maximum-barco-rips

maximum-non-raster-rips

maximum-raster-rips

message

notification-profile

npm-server-ip-address

npm-server-port-number

protected-attributes

save-rip-files

security-level

smtp-server-host (Windows NT and Windows 2000 only)

smtp-server-port-number (Windows NT and Windows 2000 only)

snmp-discovery-during-startup

snmp-normal-poll-interval

snmp-problem-poll-interval

windows-nt-driver-names

accept-unsupported-jobs

Indicates whether the server accepts jobs even when no actual destination supports the required attribute values.

GUI Label

Accept unsupported jobs

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

Basic true Advanced false

Usage Guidelines

• When the value of the accept-unsupported-jobs is true, the server accepts jobs even when no actual destination supports the required attribute values. Infoprint holds these jobs and sets the required-resources-not-supported job attribute to a list of the unsupported values.

The server accepts the job even when the actual-destinations-requested specifies a non-existent actual destination only when accept-unsupported-jobs is true and the print queue has assign-to-printer as false.

- When the value of accept-unsupported-jobs is true, the actual destination **accept-job** attribute is ignored.
- When the value of accept-unsupported-jobs is false:
 - The server rejects jobs that require unsupported attribute values.
 - The **accept-job** actual destination attribute is honored if the **assign-to-printer** queue attribute is true.
- If changes to job or actual destination attributes after the job has been accepted produce unsupported attribute values, Infoprint holds the job and sets the required-resources-not-supported job attribute to the list of unsupported values.

actual-destinations-ready

Identifies the supported actual destinations that are ready to receive jobs from queues in this server.

Type

Non-settable, multi-valued

Input Synonym

You can use the synonym physical-printers-ready.

Allowed Values

Infoprint sets this value to the names of the actual destinations that are ready to accept jobs. A actual destination name is:

- Added when actual destinations associated with queues in this server are enabled and are in the idle, connecting-to-printer, or printing state.
- · Removed when you disable or pause an actual destination and one of these destination states (timed-out, needs-attention, or needs-key-operator) exists.

Default Values

No default values

actual-destinations-supported

Identifies the actual destinations that this server supports.

Type

Non-settable, multi-valued

Input Synonym

You can use the synonym **physical-printers-supported**.

Allowed Values

Infoprint sets this value to the names of the actual destinations associated with the queues contained in this server. Infoprint adds the destination name when an actual destination associated with queues in this server registers with this server.

Default Values

No default values

auto-create-shared-printers (Windows NT and Windows 2000 Only)

Indicates whether or not destinations created in this server that can be print submission targets should automatically create a corresponding Infoprint gateway shared printer.

GUI Label

Automatically create gateway printer

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

False

Usage Guidelines

- When the value of the **auto-create-shared-printers** is **true**, Infoprint automatically creates a corresponding Infoprint gateway printer with:
 - A windows print drvier with the first value in the server's windows-nt-driver-names attribute
 - A polling interval of 0

Note: The server accepts the job even when the actual-destinations-requested specifies a non-existent actual destination only when accept-unsupported-jobs is true and the print queue has assign-to-printer as false.

cancel-individual-document-supported

Indicates whether the server is capable of cancelling individual documents within a multi-document job.

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value to **false**.

Default Value

false

descriptor

Provides a description of this server.

Type

Resettable, single-valued

Allowed Values

You can enter a text string up to 4095 characters long that contains a description of this server. You may want to specify things such as:

- · The purpose of the server; which users, user groups, or departments will use the objects contained in this server.
- · Any other information that is unique to your company or organization.

Default Value

No default value

Usage Guidelines

The use of this attribute is optional. However, a detailed description is useful if you have a large number of servers or if you have many people managing your network printing system.

destination-states-supported

Identifies the destination states that this server supports.

Non-settable, multi-valued

Input Synonym

You can use the synonym printer-states-supported.

Allowed Values

```
Infoprint sets this value to any of these fixed values:
   connecting-to-printer
   idle
   needs-attention
   needs-key-operator
   paused
   printing
   shutdown
   timed-out
```

Default Values

No default values

destination-support-systems-supported

Identifies the DSSs that this server supports.

Type

Non-settable, multi-valued

Allowed Values

```
For AIX:
  bsd
  email
  fax
  ip2000
  aix
  psf
  3170
For Windows NT or Windows 2000:
  bsd
  psf
  passthrough
  ipp
```

Default Values

No default values

document-attributes-supported

Identifies the document attributes that the server supports.

Non-settable, multi-valued

Allowed Values

Infoprint sets these values to include all the document attributes supported by any actual destination registered with the server. These values are dynamic; Infoprint adds and removes values based on the values of registered actual destinations.

Default Values

No default values

events-supported

Lists the events that the server or the objects in the server support.

Non-settable, multi-valued

Allowed Values

Infoprint sets these values to the following events:

checkpoint-taken

class-aborted

class-actual-destination-attention

class-actual-destination-configuration

class-actual-destination-default

class-actual-destination-status

class-error

class-job-attention

class-job-default

class-job-problem

class-job-status

class-logical-destination-attention

class-logical-destination-configuration

class-logical-destination-default

class-logical-destination-status

class-queue-attention

class-queue-configuration

class-queue-default

class-queue-status

class-report

class-server-attention

class-server-configuration

class-server-default

class-server-status

class-state-changed

class-warning

close-to-discard-time

destination-disabled

destination-enabled

destination-function-unavailable

destination-needs-administrator

Server

destination-needs-attention destination-needs-operator destination-registered destination-shutdown-job-requeued destination-state-changed destination-timed-out destination-unregistered destinations-not-ready-for-job detailed-messages document-aborted-by-destination document-aborted-by-server document-cancelled-at-destination document-content file-transferred internal-server-error job-aborted-by-server job-assigned-to-destination job-assigned-to-destination-at-end job-assigned-to-queue job-cancelled-by-operator job-cancelled-by-user job-cannot-be-scheduled job-discarded job-modified job-paused job-promoted job-reordered job-requeued job-resubmitted job-resumed job-retained job-state-changed job-submission-not-complete job-unassigned no-document no-resource object-cleaned object-created object-deleted object-modified object-paused object-resumed other-error other-warning past-discard-time processing-started queue-backlogged queue-no-longer-backlogged queue-state-changed resource-needs-attention resource-needs-operator server-shutdown-complete server-shutdown-started server-startup-complete server-state-changed unable-to-register

unrecognized-resource

Default Values

See "Allowed Values".

hostname

See server-hostname.

i-p-address

See server-ip-address.

ip-address

See server-ip-address.

job-attributes-supported

Identifies the job attributes that this server supports.

Type

Non-settable, multi-valued

Allowed Values

Infoprint sets these values to include all the job attributes supported by any actual destination registered with the server. These values are dynamic; Infoprint adds and removes values based on the values of registered actual destinations.

Default Values

No default values

job-state-reasons-supported

Type

Non-settable, multi-valued

Allowed Values

Infoprint sets the value of this attribute to these fixed values:

aborted-by-system

cancelled-by-operator

cancelled-by-user

completed

completed-successfully

completed-with-errors

deadline-in-jeopardy

imposition-failed

job-hold-set

job-print-after-specified

required-resource-not-ready

required-resource-not-supported

rip-and-hold-complete

rip-failed

Default Values

See "Allowed Values".

job-states-supported

Identifies the job states that this server supports.

Type

Non-settable, multi-valued

Allowed Values

Infoprint sets the value of this attribute to these fixed values:

cancelled

held

imposing

paused

pending

pre-processing

printing

processing

retained

ripping

terminating

unknown

Default Values

See "Allowed Values".

job-submission-timer

Specifies the maximum time that the server will try to assemble a job before it will time out if it has not assembled all the documents.

GUI Label

Job submission timeout

Type

Resettable, single-valued

Allowed Values

You can enter a value using [HH:]MM. The unit is minutes or hours and minutes, separated by a colon.

Default Value

30

Usage Guidelines

If the server has not completed the assembly of a job within the specified time, it identifies the job submission as complete and sends the job to the queue.

list-of-managers

Lists the people that are responsible for the configuration and operation of this server.

Type

Resettable, multi-valued

Input Synonym

You can use the synonym managers.

Allowed Values

You can enter a text string up 255 characters long, per value, that contains the name or user ID of the person responsible for this server. You may also want to include the telephone number and office location of the person.

Default Values

No default values

Usage Guidelines

This attribute is useful if a user needs to contact someone to report a problem or to request a change.

locale

Identifies the locale for this server.

GUI Label

Locale

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value based on the environment variables for this server at startup time. The priority sequence to obtain the language for the locale from the environment variables is:

- 1. LC_ALL
- 2. LC MESSAGES
- 3. LANG

Default Value

No default value

log-accounting-data

Defines whether the accounting logs for all associated actual destinations are activated or deactivated by default. The actual destination attribute **log-accounting-data** setting if one overrides the setting of this value for that actual destination.

GUI Label

Log accounting data

Type

Resettable, single-valued

Allowed Values

You can enter one of these values:

Fixed Value Input Synonym

true yes false no

Default Value

false

Usage Guidelines

If the value for any actual destination associated with this server is set to the default attribute value (no value), the value set for this server attribute sets the condition for that actual destination.

The accounting log for each actual destination contains the following job attributes and values for each job submitted to that actual destination separated by commas:

actual destination name (up to 255 characters)

job owner (up to 255 characters)

Server

```
global job-id without ServerName
submission-time (GMT format)
submission-time (date in server's displayable locale and time zone)
submission-time (time in server's displayable locale and time zone)
completion-time (GMT format)
completion-time (date in server's displayable locale and time zone)
completion-time (time in server's displayable locale and time zone)
pages-completed
octets-completed
data stream (first document only)
job name (up ot 255 characters)
```

logical-destinations-ready

Identifies which logical destinations within this server are ready to accept jobs.

Non-settable, multi-valued

Input Synonym

You can use the synonym logical-printers-ready.

Allowed Values

Infoprint sets and resets this value as administrators enable or disable logical destinations within this server.

Default Values

No default values

logical-destinations-supported

Identifies the logical destinations that this server supports.

Type

Non-settable, multi-valued

Input Synonym

You can use the synonym logical-printers-supported.

Allowed Values

Infoprint sets and resets this value as administrators create or delete logical destinations within this server.

Default Values

No default values

logical-printers-ready

See logical-destinations-ready.

logical-printers-supported

See logical-destinations-supported.

managers

See list-of-managers.

maximum-barco-rips

Indicates the maximum number of PostScript jobs that Infoprint can RIP at one time for printing on a 3170 actual destination.

Type

Resettable, single-valued

Allowed Values

You can enter an integer from 0 through 2147483647.

Default Value

4

Usage Guidelines

- For good performance, this value should be the same as the number of AIX systems specified as values of the **rip-server** actual destination attribute.
- Infoprint reads this value the first time that a job is RIPped after the server is started. Therefore, whenever you change this value, you must restart the server.

maximum-non-raster-rips

Indicates the maximum number of jobs other than TIFF, GIF, or JPEG jobs that Infoprint can RIP at one time for printing on a PSF actual destination.

GUI Label

Maximum nonraster RIPs

Type

Resettable, single-valued

Allowed Values

You can enter an integer from 0 through 2147483647.

Default Value

No default value

Usage Guidelines

- You can limit the number of concurrent RIPs to improve performance.
- Infoprint reads this value the first time that a job is RIPped after the server is started. Therefore, whenever you change this value, you must restart the server.

maximum-raster-rips

Indicates the maximum number of TIFF, GIF, and JPEG jobs that Infoprint can RIP at one time for printing on a PSF actual destination.

GUI Label

Maximum raster RIPs

Type

Resettable, single-valued

Allowed Values

You can enter an integer from 0 through 2147483647.

Default Value

No default value

Usage Guidelines

- You can limit the number of concurrent RIPs to improve performance.
- Infoprint reads this value the first time that a job is RIPped after the server is started. Therefore, whenever you change this value, you must restart the server.

message

Provides information associated with this server.

Type

Resettable, single-valued

Allowed Values

You can enter a text string up to 4095 characters long that contains information about this server.

Default Value

No default value

modify-individual-document-supported

Indicates whether this server is capable of modifying individual documents within a multiple document job.

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value to true.

Default Value

true

multiple-documents-supported

Indicates whether this server supports multiple documents in a single job.

Non-settable, single-valued

Allowed Values

Infoprint sets this value to **true**.

Default Value

true

notification-delivery-methods-supported

Identifies the methods this server supports for sending messages to the person specified to receive the messages.

Type

Non-settable, multi-valued

Allowed Values

Infoprint sets this value to any of these fixed values:

electronic-mail

message

file

file-add-to

sapcb none

Default Values

No default values

Usage Guidelines

The **sapcb** notification method causes the SAP callback daemon to return messages about job events to the SAP database. It is used only for jobs submitted by SAP users.

notification-profile

Designates which users Infoprint notifies of specific events related to this server, and how Infoprint notifies them.

GUI Label

Notification profile

Type

Resettable, multi-valued, complex

Syntax

-x "notification-profile={event-identifiers=event ... delivery-address=name@node delivery-method=value event-comment='some text' locale=locale}"

For example:

-x "notification-profile={events-identifiers=class-server-status delivery-address=Tom@master delivery-method=message event-comment='Too much data' locale=En_US.IBM-850}"

You can omit any of these values.

Components

event-identifiers: Specifies the events for which the person receives messages.

Type: Multi-valued

Allowed Values: You can enter any of the values listed for the **events-supported** attribute.

Default Values: internal-server-error, object-cleaned, object-deleted, server-shutdown-complete, sapcbd-down

delivery-address: Specifies the address of the person who receives event messages concerning this server or the directory location and file name where Infoprint stores messages.

Type: Single-valued

Allowed Values: You can enter a text string that contains the login ID and node or the path to the directory and file name.

Default Value: The login ID of the user who created this server.

delivery-method: Specifies how the user receives the event messages.

Server

Type: Single-valued

Allowed Values: You can enter one of these fixed values:

Fixed Value Input Synonym electronic-mail e-mail, email

message file file-add-to none

Default Value: message

Usage Guidelines: If you specify a value of **file** or **file-add-to** for this component, you must specify a value for the **delivery-address** component.

event-comment: Provides information that Infoprint prepends to the event message.

Type: Single-valued

Allowed Values: You can enter a text string up to 4095 characters long that contains the comment.

Default Value: No default value

locale: Defines the language and code page of notification messages.

Type: Single-valued

Allowed Values: You can enter any locale for which the Infoprint messages in the corresponding language are installed.

Default Value: The locale of the person who created this server.

npm-server-ip-address

Identifies the Internet Protocol address (IP Address parameter) of the system where the Network Print Manager (NPM) server is running.

GUI Label

NPM server IP address

Type

Resettable, single-valued

Allowed Values

You can enter a text string up to 4095 characters long that is either of these types of address:

Dotted decimal address

9.99.12.85

A series of integers within the range of 0 to 255, each separated by a period, . (decimal address). For example:

Hostname

For example: leo.boulder.IBM.com

Default Value

127.0.0.1

Usage Guidelines

You must enter a value in order to display the Simple Network Management Protocol (SNMP) Printer Status dialog from the Infoprint Manager Operations GUI.

npm-server-port-number

Identifies the Port Number parameter on the system where the NPM server is running.

GUI Label

NPM server port

Type

Resettable, single-valued

Allowed Values

You can enter an integer from 1 through 2147483647, but you typically enter an integer from 5001 to 65535.

Default Value

6795

Usage Guidelines

You must enter a value in order to display the SNMP Printer Status dialog from the Infoprint Manager Operations GUI.

object-class

Identifies the object class to which this object belongs.

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value to server.

Default Value

server

object-classes-supported

Lists the object classes that this server supports.

Type

Non-settable, multi-valued

Allowed Values

Infoprint sets this value to these fixed values:

auxiliary-sheet

destination

document

initial-value-document

initial-value-job

job

log

medium

queue

resource-context

server

transform for Windows NT or Windows 2000 only

Default Values

See "Allowed Values".

physical-printers-ready

See actual-destinations-ready.

physical-printers-supported

See actual-destinations-supported.

printer-states-supported

See destination-states-supported.

problem-child

Indicates whether one of the objects that this server manages has a problem.

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value to one of these fixed values:

true

false

Default Value

No default value

Usage Guidelines

The Infoprint administrator's GUI uses this attribute value to determine the problem status of this server.

protected-attributes

Specifies one or more server attributes that DCE prevents Infoprint operators from setting or changing.

GUI Label

Protected attributes

Type

Resettable, multi-valued

Allowed Values

You can enter one or more server attribute names.

Default Values

This attribute always specifies itself, **protected-attributes**, as a value.

Usage Guidelines

Normally, anyone with DCE write permission for server can set values for server attributes. By default, the **pd_admin** and **pd_operator** DCE groups both have write permission. Once you define a server attribute as a protected attribute, you must have DCE **delete** permission to modify the attribute. Members of the **pd_operator** DCE group do not have **delete** permission unless the DCE administrator has modified the default permissions for that group.

queues-supported

Identifies the queues contained in this server.

Type

Non-settable, multi-valued

Allowed Values

Infoprint sets and resets this value when you create or delete queues.

Default Values

No default values

save-rip-files

Indicates whether this server saves the output files from jobs converted to raster image patterns.

GUI Label

Save ripped files

Туре

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

Basic true Advanced false

Usage Guidelines

- If you move a RIPped job from a server with **save-rip-files=true** to one with **save-rip-files=false**, the new server keeps the RIP files only until the job is printed, then discards them.
- RIPped files are saved in the directory specified by the PDBASE environment variable or in one of its subdirectories. No single user can create a file larger than the amount of free space in the file system containing this directory. If many users are submitting RIPped jobs, the directory may fill up and prevent all users from successfully RIPping files.

security-level

Identifies the security level for this server.

GUI Label

Security level

Type

Resettable, single-valued

Allowed Values

You can enter the following value for DCE:

medium DCE controls access to objects. Clients can execute all commands if

the client and server are in the same namespace. If they are not in

Server

the same namespace, the client can execute only the **pdls**, **pdpr**, **pdq**, **pdmod**, and **pdrm** commands.

You can enter one of these fixed values for non-DCE:

none No security checking is performed.

low Uses standard non-DCE access control list and group security

checking.

Default Value

With non-DCE low With DCE medium

server-hostname

Identifies the host processor on which this server is running.

Type

Non-settable, single-valued

Input Synonym

You can use the synonym hostname.

Syntax

node.node.node

For example:

boxer.denver.gym.

Allowed Values

Infoprint sets this value to the host name of the processor where this server was created.

Default Value

The host name of the processor where this server was created.

server-ip-address

Identifies the Internet Address of the host processor on which this server is running.

Type

Non-settable, single-valued

Input Synonyms

You can use the synonym ip-address or i-p-address.

Allowed Values

Infoprint sets this value to the IP address of the host on which this server was created. The value is in the format of integers in series within the range of 0 to 255. A period, . , separates each integer from the others in the format nn.nn.nn

For example:

9.99.9.143

Default Value

The IP address of the host on which this server was created.

server-name

Uniquely identifies this server.

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value to the name you enter when you create this server.

Default Value

No default value

server-state

Identifies the current state of this server.

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value to one of these fixed values:

initializing

ready

terminating

unavailable

Default Value

No default value

smtp-server-host (Windows NT and Windows 2000 Only)

Identifies the Domain Name System (DNS) hostname or Internet Protocol address of the system where the Simple Mail Transfer Protocol (SMTP) server or gateway is running.

Type

Resettable, single-valued

Allowed Values

You can enter a text string up to 4095 characters long that is either of these types of addresses:

Hostname

For example, leo.boulder.IBM.com.

Dotted decimal address

For example, 9.99.12.85.

Default Values

localhost

Usage Guidelines

• You must enter a value in order to receive notifications through the **electronic-mail** notification delivery method.

Note: Select client notifications use the **electronic-mail** notification delivery method.

smtp-server-port-number (Windows NT and Windows 2000 Only)

Identifies the port number on which the Simple Mail Transfer Protocol (SMTP) server is listening.

Type

Resettable, single-valued

Allowed Values

You can enter an integer from 1 through 2147483647, but you typically enter an integer from 5001 to 65535.

Default Values

Note: This is the Internet Assigned Numbers Authority (IANA) reserved port number for SMTP.

Usage Guidelines

 You must enter a value in order to receive notifications through the **electronic-mail** notification delivery method.

Note: Select client notifications use the **electronic-mail** notification delivery method.

snmp-aix-printer-models

Identifies the SNMP descriptive printer model names that the AIX DSS recognizes.

GUI Label

AIX printer models

Type

Non-settable, multi-valued

Allowed Values

Infoprint sets this value to a list of recognized SNMP printer models.

Default Values

A list of recognized SNMP printer models.

snmp-discovery-during-startup

Specifies that during startup, the server should issue an SNMP query for each SNMP printer to obtain the most up-to-date status.

GUI Label

Discover printers at startup

Resettable, single-valued

Allowed Values

Fixed Value Input Synonym

true yes false no

Default Value

true

Usage Guidelines

- When SNMP-discovery-during startup is true, the SNMP queries can cause long startup times, especially when there are lots of SNMP printers and a significant number of them are powered off or disconnected.
- When **SNMP-discovery-during startup** is **false**, the server bypasses the initial SNMP queries, and the SNMP printers show whatever their status was when the server was shutdown the last time. When set to **false**, the printer status becomes up-to-date over time as the SNMP polling loop runs.

snmp-normal-poll-interval

Indicates the number of seconds that the server should wait between polling output devices that use SNMP and that are not known to have a problem.

GUI Label

Normal poll interval (sec)

Type

Resettable, single-valued

Allowed Values

You can enter an integer from 0 through 2147483647.

Default Value

300

Usage Guidelines

- When normal polling finds that an output device has a problem, Infoprint
 disables the actual destination if necessary and transfers the device to the list of
 devices to be polled at the problem interval.
- Output devices with which the server has not established, or has lost, SNMP communication, are polled at the normal interval, not the problem interval.
- Set a value of **0** to disable normal polling.

snmp-problem-poll-interval

Indicates the number of seconds that the server should wait between polling output devices that use SNMP and that are known to have a problem.

GUI Label

Problem poll interval (sec)

Type

Resettable, single-valued

Allowed Values

You can enter an integer from 0 through 2147483647.

Default Value

60

Usage Guidelines

When problem polling finds that an output device no longer has a problem,
 Infoprint reenables the actual destination if necessary and transfers the device to

- the list of devices to be polled at the normal interval. To prevent Infoprint from reenabling the actual destination, manually disable it.
- Output devices with which the server has not established, or has lost, SNMP communication, are polled at the normal interval, not the problem interval.
- Set a value of **0** to disable problem polling.

snmp-trap-timeout

Indicates the number of seconds that the server should wait to receive SNMP device traps.

GUI Label

Trap timeout (sec)

Resettable, single-valued

Allowed Values

You can enter an integer from 0 through 2147483647.

Default Value

Usage Guidelines

- You must configure each output device that uses SNMP to send traps to the host where this server is running. The method of doing this depends on the device.
- Set a value of **0** if no actual destinations in this server use SNMP, or if the SNMP output devices are not configured to send traps to the host. In this case, Infoprint relies on SNMP polling to determine problems. If you also disable polling, Infoprint cannot detect problems until it attempts to send a job to the output device. It cannot detect that a serious problem has been corrected until you manually reenable the actual destination.

transfer-methods-supported

Identifies the transfer methods that this server supports.

Type

Non-settable, multi-valued

Allowed Values

Infoprint sets this value to any of these fixed values: pipe-pull

with-request **Default Values**

pipe-pull, with-request

Usage Guidelines

Infoprint compares the document attribute transfer-method to this attribute for validation.

windows-drivers

See windows-nt-driver-names.

windows-nt-driver-names

Identifies the 32-bit Windows print driver that can be used as the device driver for automatically created gateway shared printers on this server.

GUI Label

Windows drivers

Type

Resettable, single-valued

Input Synonyms

You can use the synonym windows-nt-drivers or nt-drivers.

Allowed Values

You can enter a text string that contains the string form of the Windows print driver.

Default Values

No default values

Usage Guidelines

- Perform the following procedure to determine the valid Windows driver names:
 - 1. Select **My Computer** from the desktop.
 - 2. Select and open the Control Panel icon.
 - 3. Select and open the Printers icon,
 - 4. Select and open the Add Printer icon.
 - 5. The values listed in the <u>Printers</u>: list box in the <u>Add Printer Wizard</u> are the names of the Windows destination drivers that you can install on the workstation; for example, <u>IBM 4039 LaserPrinter PS</u>.

Note: Other destination drivers are available and may not display in the list for a particular workstation.

windows-nt-drivers

See windows-nt-driver-names.

Attributes for Transforms (Windows NT or Windows 2000 only)

Infoprint uses transform objects to indicate how specific document formats sent to an associated actual destination are to be transformed before printing or storing.

Infoprint Manager for Windows NT and Windows 2000 includes a file called **xfmfltr.out** that contains information on the commands executed by a Configurable Transform Subsystem transform. This information may be helpful for troubleshooting transforms that are failing. The file can be found in Workspace Path defined in the Infoprint Manager Management Console under **Edit->Service Configuration...**

Initially Settable Attribute Listing

There aer no initially settable attributes for transforms.

Resettable Attribute Listing

You can set these attributes with the **pdcreate** command when you create a transform or modify them with the **pdset** command after you create the transform. You can also erase a transform with the **pddelete** command or list selectable attribute values for a transform with the **pdls** command.

descriptor document-formats-supported other-transform-options output-document-format terminating-transform

associated-server

Indicates the name of the server where this transform resides.

GUI Label

Server

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value when you create a transform for a given server. Infoprint assigns the *ServerName* portion of the argument from the **pdcreate** command used to create this transform object.

Default Value

No default value

descriptor

Provides a description of this transform.

GUI Label

Description

Type

Resettable, single-valued

Allowed Values

You can enter a text string up to 4095 characters long that describes this transform.

Default Value

No default value

Usage Guidelines

The use of this attribute is optional. However, a detailed description of the transform that this references can be helpful to a users who need to determine which transform to use.

document-formats-supported

Identifies the document formats that this transform supports.

GUI Label

Document formats allowed

Type

Resettable, multi-valued

Allowed Values

You can enter any of these fixed values:

Fixed Value Input Synonym

ascii dbcs-ascii ditroff d630 gif

hpgl hp-gl

iso-6429 jpeg kgl lcds line-data metacode

modca-p afpds

passthru

pcl hppcl, hp-pcl

pdf

postscript ps

ppds sap sap-abap

simple-text text

tiff

Default Values

ASCII, MODCA-P (AFPDS), PCL, PostScript

Usage Guidelines

• When a document's format it not supported, the document bypasses the transform.

object-class

Identifies the object class to which this object belongs.

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value to transform.

Default Value

transform

other-transform-options

Specifies the command line that executes when this transform is run.

GUI Label

Transform options

Type

Resettable, single-valued

Allowed Values

You can enter a text string of up to 4095 characters that contains the command line for this transform.

Default Value

No default value

Usage Guidelines

For transform-library=command-line-transform, this attribute contains the command line that specifies the transform. The supported substitution control sequences that may be used in **other-transform-options** follow:

- **%i** The name of the input-file to transform.
- %**o** The name of the file in which to store the output transform.

Note: If no data is stored in this file and this is a non-terminating transform, Infoprint Manager assumes that the transform did not want to modify the input data, so Infoprint Manager simply passes the input file on to the next transform in sequence.

- **%e** The name of the file in which to store any transform information or error messages. If anything is written to this file, it is logged in the Infoprint Manager server log.
- **%j** The name of the original print file name, minus the path (from **document-file-name** attribute).

Note: This file may not be accessible. This should only be used to construct another name, for example, for a temporary file.

%n The name of the original print file name, minus the path and minus the extension (from **document-file-name** attribute).

Note: This file may not be accessible. This should only be used to construct another name, for example, for a temporary file.

%d A string representing the document-format of the input file:

ascii ASCII
afpds AFPDS
pcl PCL
postscript
PS

%p The value of the **destination-pass-through** attribute. The value can be used as actual-destination specific or job specific information that can be passed to the transform.

For example, if you want to write one transform, but use it differently for different actual destinations or jobs, you can pass values into the transform with this parameter as follows to print pages 1 through 10 of the file report.ps:

```
pdpr -p LogPrtPSF -x destination-pass-through=-c10 report.ps
```

This example passes the -c 10 into the transform when you use %p when you define the transform.

%**q** The name of the actual destination that is doing this transform.

%# The job-identifier of the job.

Examples for other-transform-options: Use the following examples on the Windows NT or Windows 2000 command line:

 To run the ps2afp transform and print the generated AFP data, you would specify a one-step transform sequence consisting of a transform object as follows:

```
other-transform-options="ps2afp -o "%o" "%i""
```

- To run the ps2afp transform and also save a copy of the generated AFP data in "c:\afp*.afp", you could create a transform sequence consisting of two transform objects as follows:
 - 1. This step does the PostScript to AFP transform and stores the output in the designated output file, which becomes the input file for step 2:

```
other-transform-options="ps2afp -o "%o" "%i""
```

2. This step copies the AFP file from step 1. However, in this example, nothing is put in the %o file, so the %i file (the transformed AFP) is passed through to the DSS for printing.

```
other-transform-options="copy "%i" "c:\afp\%n.afp""
```

• To run a customized program that removes PostScript controls that may create a problem at the printer, you would use a one-step transform sequence consisting of a transform object as follows:

```
other-transform-options=\"d:\tools\my ps filter.exe "%i" "%o""
```

output-document-format

Identifies the format of the output file generated by the transform specified in **other-transform-options**. This is a required attribute.

GUI Label

Format of output file

Type

Resettable, single-valued

Allowed Values

You can enter any of these fixed values:

Fixed Value ascii dbcs-ascii ditroff d630 Input Synonym

Fixed Value Input Synonym

gif

hpgl hp-gl

iso-6429 jpeg kgl lcds line-data metacode

modca-p afpds

passthru

pcl hppcl, hp-pcl

pdf

postscript ps

ppds sap sap-abap

simple-text text

tiff

Default Value

No default value

terminating-transform

Indicates whether or not this is a terminating transform.

GUI Label

How to process jobs

Type

Resettable, single-valued

Allowed Values

You can enter one of these fixed values:

Fixed Value Input Synonym

true yes false no

Default Value

false

Usage Guidelines

When you specify **true** for **terminating-transform**, Infoprint Manager ends the transform sequence and marks the job complete without printing through the DSS backend.

When you are using a sequence of transforms, specify **false** as the value for **terminating-transform** to continue processing transforms that follow. The last transform in the sequence can be **true** when you want it to terminate without printing and **false** when you want it to print through the defined actual destination.

A terminating transform may be used to create an actual destination that only performs a transform and then stores/forwards the transformed data without ever printing it to an output device.

Since the DSS is never actually executed, a terminating transform can be associated with any type of DSS. You should associate a terminating transform with a BSD DSS destination to minimize unnecessary overhead, such as creating files, ports, and so on. When defining a BSD DSS destination for use with a terminating transform, you should not use a valid IP address or a valid command when creating the BSD DSS destination, which not only minimizes overhead, but also logs errors if it attempts to print a file.

Examples for terminating-transform

- For example, a BSD DSS destination could be created and associated with a transform that runs ps2afp and stores the resulting AFP file in a library.
- · As another example, you could also use a BSD DSS destination fed by one queue and associated with a transform that runs ps2afp and then pdpr's the resulting AFP file to a logical destination that feeds a real printer. This example gives you a way to do pre-spool transforms.

transform-identifier

Uniquely identifies this transform.

Type

Non-settable, single-valued

Allowed Values

Infoprint sets this value to the SimpleName portion of the argument specified with the **pdcreate** command when this transform is created.

Default Value

No default value

transform-library

Identifies the name of the DLL/Shared library that implements this transform.

Non-settable, single-valued

Allowed Values

command-line-transform

Default Value

command-line-transform

Chapter 8. Infoprint Environment Variables

Table 13, Table 14 on page 674, Table 15 on page 675, and Table 16 on page 676 describe the environment variables that affect how Infoprint processes commands and utilities.

Table 13. Infoprint Environment Variables Defaulted or Set for Infoprint Manager for AIX and Infoprint Manager for Windows NT and Windows 2000

Variable	Description
PATH	With Infoprint Manager for AIX, the directories that AIX searches for command files. Separate multiple directories by a colon, : . Commands: All Default: \$\PATH:\frac{\text{usr/lpp/pd/bin:/usr/lpp/psf/bin}}{\text{psf/bin}}, \text{ where \$\PATH\$ is the value when Infoprint is installed} With Infoprint Manager for Windows NT and Windows 2000, the directories that AIX searches for command files. Separate multiple directories by a semi-colon, ; . Commands: All Default: \$\PATH\%:install_path\pd\\bin;install_path\\psf\\bin}, \text{ where \$\PATH\% is the value when Infoprint is installed}
PDIDTABLE	Defines the upper limit (boundary) of local job identifiers that Infoprint can assign for each user before wrapping to 1. The maximum valid integer is 32767. If you do not set a value, Infoprint uses 100 as the upper limit. Setting the value to a lower value decreases memory usage but increases the chances of duplicate local job identifiers.
PDPATH	A path of directories that Infoprint searches for the file name specified by the -X attributes file name flag. Separate multiple directories by a colon, : . If the PDPATH environment variable does not exist, Infoprint uses the current working directory of the person submitting the command. Commands: All
PDPRINTER	Used as the default logical destination when you do not specify the -d DestinationName, the -p DestinationName flag, or the destination-name- requested job attribute. Commands: pdls, pdq, pdpr Infoprint also uses this variable to identify the server for other commands.
PD_CONFIRM_DELETE	Specifies whether Infoprint issues a confirmation message before deleting an object. Commands: pdclean, pddelete, pdrm Values: yes, no Default: yes

Table 13. Infoprint Environment Variables Defaulted or Set for Infoprint Manager for AIX and Infoprint Manager for Windows NT and Windows 2000 (continued)

Variable	Description
PD_ENABLE_TIMEOUT	Specifies the number of seconds that a server waits for an actual destination to register when the actual destination is enabled. Default: 15
PD_LISTEN_COUNT	Specifies the number of simultaneous requests that a server can process. If this number is exceeded, the server issues an error message. Default: 10
PD_SOCKET	Identifies the port number used by the Infoprint communications daemon. Internet services reserve socket numbers up to 255. Other non-Infoprint services reserve socket numbers in the range 256 through 1023. To determine the socket numbers already reserved before assigning a socket number to an Infoprint communications daemon, look at the contents of the /etc/services file. Default: 6874
PSFDBLANG	The language and code page used by the db2afp transform program. Values: j (Japanese, code page 932), c (Traditional Chinese, code page 938), je (Japanese EUC), ce (Traditional Chinese EUC), ke (Korean EUC)
PSFPATH	A path of directories that Infoprint searches for print resources (fonts, form definitions, overlays, page definitions, and page segments). Separate multiple directories by a colon, : . Commands: pdpr

Table 14. Infoprint Environment Variables Defaulted or Set in the /etc/environment File in Infoprint Manager for AIX

Variable	Description		
GIF2AFP_option	Specifies options for the GIF2AFP transform command. See "gif2afp Command: Transforms GIF Data to AFP in Infoprint Manager for AIX" on page 212.		
IPR_PREDPROD	Used during migration to specify the product that preceded Infoprint. Value: PSF (PSF for AIX)		
JPEG2AFP_option	Specifies options for the JPEG2AFP transform command. See "jpeg2afp Command: Transforms JPEG Data to AFP in Infoprint Manager for AIX" on page 226.		
MANPATH	A path of directories that AIX searches for man pages. Separate multiple directories by a colon, : . Commands: man		
PDBASE	Specifies the root directory where the Infoprint server stores all of its working files, such as log or trace files. Each server has its own subdirectory under this directory to avoid name conflicts when multiple servers are on the same AIX processor. Utilities: start_server, startsrv Default: /var/pd		

Table 14. Infoprint Environment Variables Defaulted or Set in the /etc/environment File in Infoprint Manager for AIX (continued)

Variable	Description	
PDNAMESP	Specifies the namespace. Commands: All Default: /var/pddir/default_cell (without DCE) /::/subsys/ipr (with DCE)	
PPO_DEFAULT_ENV	The fully qualified name of the Infoprint SMIT production print operations interface environment file, which contains a shell script that defines all other Infoprint SMIT production print operations interface environment variables. Default: /usr/lpp/pd/bin/ppo.env	
TIFF2AFP_option	Specifies options for the TIFF2AFP transform command. See "tiff2afp Command: Transforms TIFF Data to AFP in Infoprint Manager for AIX" on page 313.	
TYPESETTER	Determines how troff files are processed for printing. Values: afp, hplj, psc	
XBMLANGPATH	A path of directories that AIX searches for the icons used by graphical user interfaces. Separate multiple directories by a colon, : .	

Table 15. Infoprint Environment Variables Set in the Infoprint SMIT Production Print Operations Interface Environment File for Infoprint Manager for AIX

Variable	Description	
PPO_CANCEL_ALL_OPTION	Specifies whether operators have the option of cancelling all jobs. Values: 0 (no), 1 (yes) Default: 1 (yes)	
PPO_FORM	The list of forms (media) that your printing operation can use. Separate form names by blanks.	
PPO_JOB_BATCH	The list of job batches that your printing operation can use. Separate job batch names by blanks.	
PPO_JOB_DETAILS_ATTRS	The job and document attributes that are displayed in the Infoprint SMIT production print operations interface job status window. Separate attribute names by commas.	
PPO_LP	The name of the default logical destination to which the Infoprint SMIT production print operations interface resubmits print jobs.	
PPO_LPS	The names of logical destinations that are available for job submission. Separate logical destination names by blanks.	
PPO_PP_ATTRS	The actual destination attributes that are displayed in the Infoprint SMIT production print operations interface destination status window. Separate attribute names by commas.	
PPO_PPS	The names of the actual destinations that the Infoprint SMIT production print operations interface manages. Separate actual destination names by blanks.	
PPO_QUEUE	The name of the queue that the Infoprint SMIT production print operations interface manages.	

Table 15. Infoprint Environment Variables Set in the Infoprint SMIT Production Print Operations Interface Environment File for Infoprint Manager for AIX (continued)

Variable	Description	
PPO_QUEUE_ATTRS	The queue attributes that are displayed in the Infoprint SMIT production print operations interface queue status window. Separate attribute names by commas.	
PPO_QUEUE_INFO_FILE	In installations that use multiple queues, the name of the file that maps queues to their environment files.	
PPO_SERVER	The name of the server that the Infoprint SMIT production print operations interface manages.	
PPO_TRACE_FILE	The name of the file containing trace records for the Infoprint SMIT production print operations interface manages. Use this environment variable only under the direction of IBM service.	

Table 16. AIX Environment Variables

Variable	Description	
LANG	The name of the locale to use for locale categories when neither LC_ALL nor the corresponding environment variable beginning with LC_ specifies a locale. Used to determine the language, territory, or character set of messages and other information that Infoprint sends to a person. Commands: All	
LC_ALL	The name of the locale used to override any values for locale categories specified by the setting of LANG or any environment variables beginning with LC Commands: All	
LC_CTYPE	The name of the locale for character classification. Commands: All	
LC_MONETARY	The name of the locale containing monetary-related numeric editing information. Commands: All	
LC_NUMERIC	The name of the locale containing numeric editing, such as radix and character information. Commands: All	
LC_TIME	The name of the locale for date and time formatting information. Commands: All	
LC_MESSAGES	The name of the locale for STDERR messaging. Commands: All	
NLSPATH	A path of directories that AIX searches for locale-dependent files. Separate multiple directories by a colon, : .	

Querying Environment Variables

You can use the echo command to query the value of an environment variable. For example, to determine the default logical destination, enter: echo \$PDPRINTER

To query all environment variables that have values set, enter:

Setting Environment Variables

You can use the **export** command to set environment variables:

- If you are an administrator, in an environment file.
 - You can set AIX environment variables and many Infoprint environment variables in the /etc/environment file.
 - You can set some Infoprint environment variables that affect the Infoprint SMIT production print operations interface in the Infoprint SMIT production print operations interface environment file. The PPO DEFAULT ENV environment variable defines the name of this file.

Settings in the environment files apply to all sessions for all users, unless a user resets the environment variables in the .profile file or on the command line.

Note: These settings do not apply to processes that are already running when you edit the file. For example, a server is a process. To make your changes effective, stop and restart the server.

- In the .profile file in your home directory. Settings in the .profile file override settings in the /etc/environment file and the Infoprint SMIT production print operations interface environment file. These settings apply only to you and are in effect for all your AIX sessions, unless you reset the environment variables on the command line.
- On the command line for a single AIX session. Command line settings override settings in the /etc/environment file, the Infoprint SMIT production print operations interface environment file, and your .profile file. These settings apply only to you and are in effect only until you exit the session.

In a File

To set an environment variable in a file, you need to edit the file with an editor. If you do not know how to use an editor, or the editor you are using is not capable of saving in the plain text (ASCII) file format, do not start. Ask your administrator for assistance.

The following example shows how to set the PDPRINTER environment variable in your .profile file, using the vi editor.

- 1. Enter the following command to change to your home directory:
- 2. Make a backup copy of the file:

```
cp -p .profile .profile.org
```

The -p flag gives the copy the same file permissions and modification date and time as the original file.

3. Enter the following command:

vi .profile

4. A typical **.profile** file contains lines similar to the following:

PATH=::\$HOME/bin:/bin:/usr/bin:/etc:/usr/ucb:/usr/bin/X11:tools/ usr/bin:/usr/lpp/cmvc/bin:/usr/OV/bin:/usr/local/tools/rs6/bin:/usr /local/tools/rs6:/usr/dt/bin

export PATH export EDITOR=vi

5. Insert or modify the following line in the .profile file:

export PDPRINTER=LogicalDestinationName

where Logical Destination Name is the name of the logical destination you want to set as your default.

- 6. Save the change in plain text format and exit from the editor.
- 7. Make the change effective by entering the following command:
 - . .profile
- 8. Verify the change by entering the command:

echo \$PDPRINTER

The logical destination name you entered displays.

On the Command Line

To set the value of the environment variable PDPRINTER to Destination3 for a single AIX session, enter:

export PDPRINTER=Destination3

Chapter 9. Notification Events and Event Classes

Table 17 alphabetically lists the names of individual events that you can specify as values for the **event-identifiers** component of the **notification-profile** attribute. The information for each event includes a description, the event class or classes to which the event belongs, the Infoprint objects that support the notification of the event, and the text of the notification message that Infoprint generates for the event. Items in the message text shown in *italics* are variables for which Infoprint supplies values when it issues the message.

Table 17. Notification Events

Event	Event Class	Objects Supported		
	Description			
	Message			
checkpoint-taken	class-job-status class-report	Job		
	When this job was paused, the server saved checkpoint information for it. The server can restart the job at the checkpoint. Note: The server does not save checkpoint information for jobs terminated by errors.			
	5010-218 The server saved checkpoint in (ServerName:GlobalID).	5010-218 The server saved checkpoint information for job JobID (ServerName: GlobalID).		
close-to-discard-time	class-job-attention class-warning	Job Server		
	The date and time specified by the job-discard-time or the job-retention-period attribute is approaching. Infoprint will delete the job at the discard time.			
	5010-234 Job JobID (ServerName:GlobalID) is close to being discarded.			
destination-disabled	class-actual-destination-attention class-logical-destination-attention class-warning	Actual destination Logical destination Queue Server		
	Infoprint disabled a logical destination or actual destination and it will not accept new jobs.			
	5010-240 Successfully disabled destination ServerName: DestinationName.			
destination-enabled	class-actual-destination-status class-logical-destination-status class-report	Actual destination Logical destination Queue Server		
	Infoprint enabled a logical destination or actual destination and it now accepts jobs.			
	5010-226 Successfully enabled destination ServerName: DestinationName.			
	· · · · · · · · · · · · · · · · · · ·			

Table 17. Notification Events (continued)

Event	Event Class	Objects Supported	
	Description		
	Message		
destination-function-unavailable	class-actual-destination-status class-job-attention class-warning	Actual destination Server	
	The actual destination requires an output device function, such as duplex or offset stacking, that is not available. The function is disabled, but processing continues.		
	5010-307 The destination ServerName:Defunction that is not available.	estinationName requires a	
destination-needs-administrator	class-actual-destination-attention class-actual-destination-default class-job-attention class-warning	Actual destination Job Server	
	The server or actual destination detected a condition requiring administrator intervention. The actual destination is disabled.		
	5010-306 The destination ServerName: DestinationName needs administrator attention.		
destination-needs-attention	class-actual-destination-attention class-actual-destination-default class-job-attention class-job-default class-warning	Actual destination Job Server	
	The actual destination needs attention from a person, not necessarily the operator. The actual destination cannot process jobs until it receives attention.		
	5010-245 Actual destination ServerName: destinationname needs attention.		
destination-needs-operator	class-actual-destination-attention class-actual-destination-default class-job-attention class-job-default class-warning	Actual destination Job Server	
	An actual destination needs operator attention. The actual destination cannot process jobs until it receives attention.		
	5010-246 Actual destination ServerName: DestinationName needs operator attention.		
destination-registered	class-actual-destination-status class-report	Actual destination Queue Server	
	An actual destination has registered with this queue. The queue can now schedule jobs to this actual destination.		
	5010-223 Actual destination ServerName: DestinationName registered with queue ServerName: QueueName.		

Table 17. Notification Events (continued)

Event	Event Class	Objects Supported		
	Description			
	Message			
destination-shutdown-job-requeued	class-actual-destination-attention class-job-attention class-warning	Actual destination Job Server		
	The actual destination shut down after this job job was requeued and will be scheduled again.	started processing. The		
		5010-237 Actual destination ServerName: DestinationName was shut down after job JobID (ServerName: GlobalID) started processing.		
destination-state-changed	class-actual-destination-status class-state-changed	Actual destination		
	The actual destination state changed. Processing	continues.		
	5010-228 The state of actual destination ServerName:DestinationName changed to State			
destination-timed-out	class-actual-destination-attention class-actual-destination-default class-warning	Actual destination Server		
	The actual destination did not connect or get a response from the output device in the time specified by the destination-timeout-period actual destination attribute. Another application is using the output device or job progress at the output device has stopped. The actual destination continues its attempts to connect or print to the output device. The actual destination cannot process jobs until it connects to the device. Check the server error log for additional information.			
	5010-247 Actual destination ServerName: DestinationName has timed out.			
destination-unregistered	class-actual-destination-status class-warning	Actual destination Queue Server		
	This actual destination is no longer registered with this queue and the queue no longer sends jobs to this actual destination.			
5010-243 Actual destination ServerName:Destin longer registered with ServerName:QueueName.				
destinations-not-ready-for-job	class-job-attention class-job-default class-warning	Job Queue Server		
	There are no actual destinations currently available that can support the "ready" attributes for the job. Ready attributes include job-batch , total-job-octets , default-medium , and page-media-select .			
	5010-702 The job <i>JobID</i> (ServerName:GlobalID) cannot be scheduled to an actual destination because resources are not currently ready.			
detailed-messages	class-job-attention class-report	Actual destination Job Server		
	The print backend has sent a message.			
	5010-302 Message from the print backend program			

Table 17. Notification Events (continued)

Event	Event Class	Objects Supported		
	Description			
	Message			
document-aborted-by-destination	class-aborted class-job-attention class-job-default	Actual destination Job Server		
	The actual destination deleted the document wi transmitting it. Errors occurred during processir			
		5010-292 Document <i>DocNum FileName</i> in job <i>JobID</i> (ServerName:GlobalID) was aborted by the actual destination.		
document-aborted-by-server	class-aborted class-job-attention class-job-default	Actual destination Job (AIX DSS only) Server		
	The server aborted this document and deleted is	t.		
	5010-206 Document <i>DocNum</i> (<i>FileName</i>) in prin (<i>ServerName:GlobalID</i>) was aborted by the se			
document-cancelled-at-destination	class-aborted class-job-attention class-job-default	Actual destination Job Server		
	The document was cancelled at the actual destination.			
	5010-293 Document <i>DocNum</i> (<i>FileName</i>) in job <i>JobID</i> (<i>ServerName:GlobalID</i>) was cancelled at the actual destination.			
document-content	class-error class-job-problem	Actual destination Server		
	The server detected an error in the content of this file during printing. An example of this type of error is a syntax error in the page description language for this file.			
	5010-208 An error was detected in document <i>DocNum</i> (<i>FileName</i>) of job <i>JobID</i> (<i>ServerName:GlobalID</i>) during printing.			
file-transferred	class-job-status class-report	Job		
	A file transfer completed successfully. The file may now be modified without affecting the output.			
	5010-219 Server (ServerName) completed the transfer of document DocNum (FileName) in job JobID (ServerName:GlobalID).			
internal-server-error	class-error class-server-attention class-server-default	Server		
	A server error occurred. The process failed.			
	5010-215 An internal error was detected in server ServerName.			
job-aborted-by-server	class-aborted class-job-attention class-job-default	Actual destination Job Queue Server		
	The server aborted this job because job or output device errors occurred during printing or transmission.			
	5010-204 Job $\it JobID$ (ServerName: $\it GlobalID$) stopped printing due to job or device errors.			

Table 17. Notification Events (continued)

Event	Event Class	Objects Supported	
	Description		
	Message		
job-assigned-to-destination	class-report	Job	
	This job was assigned to this actual destination.		
	5010-660 The job <i>JobID</i> (ServerName:GlobalID) is assigned to destination ServerName:DestinationName		
job-assigned-to-destination-at-end	class-report	Job	
	This job is the last job assigned to this actual of	destination.	
	5010-659 The job <i>JobID</i> (ServerName:Globalianssigned to destination ServerName:Destination		
job-assigned-to-queue	class-job-status class-report	Job Queue Server	
	This job was assigned to this queue in this sta	te. Processing continues.	
	5010-301 The job JobID (ServerName:GlobalID) is assigned to queue ServerName:QueueName and is in the State state.		
job-cancelled-by-operator	class-aborted class-job-attention class-job-default	Actual destination Job Queue Server	
	The operator or administrator deleted the job.		
	5010-196 Job <i>JobID</i> (<i>ServerName:GlobalID</i>) was cancelled by the operator or administrator.		
job-cancelled-by-user	class-aborted class-job-attention	Actual destination Job Queue Server	
	The user deleted the job.		
	5010-197 Job <i>JobID</i> (ServerName:GlobalID) was cancelled by the user.		
job-cannot-be-scheduled	class-job-attention class-job-default class-warning	Job Queue Server	
	There are no longer any actual destinations available that can support the attributes for the job. The actual destination that supported the attributes for the job at submission is no longer available. The job remains in the queue. Resubmit the job to a logical destination that supports the attributes for the job.		
	5010-103 The job <i>JobID</i> (<i>ServerName:Globali</i> to an actual destination.	TD) cannot be scheduled	

Table 17. Notification Events (continued)

Event	Event Class	Objects Supported		
	Description	Description		
	Message			
job-completed	class-job-default class-job-status class-report	Actual destination Job Queue Server		
	The job completed processing. If more than one actual destination processed this job, the last actual destination is identified in the message. It may or may not have completed successfully. Check the output.			
	5010-055 Job name jobname with ID JobID (ServerName:GlobalID) completed on DestinationName.			
job-discarded	class-job-attention class-report	Job Queue Server		
	The date and time specified by the job-discard-time , the job-retain-until or the job-retention-period attribute passed. Infoprint deleted the job. The job may or may not have printed if it was discarded because of the job-retain-until or job-retention-period value.			
	5010-220 Job <i>JobID</i> (ServerName:GlobalID) was discarded by the server after it printed or the retention period expired.			
job-modified	class-job-status class-warning	Job		
	The job was modified. Processing co	ontinues.		
	5010-202 Job JobID (ServerName:Gl	lobalID) was modified.		
job-paused	class-job-attention class-warning	Job		
	The job was paused. If the job state was processing or printing , it stopped. Infoprint cannot schedule the job until it is resumed.			
	5010-203 Job JobID (ServerName:Gl	obalID) was paused.		
job-promoted	class-job-status class-report	Job Queue Server		
	The job was promoted to the highest position in the queue.			
	5010-198 Job JobID (ServerName:GlobalID) was promoted.			
job-reordered	class-job-status class-report	Job Queue Server		
	The job was successfully moved to a different actual destination or to the unassigned jobs area.			
	5010-846 Job JobID (ServerName:GlobalID) was moved from ServerName1:DestinationName1 to ServerName2:DestinationName2.			
job-requeued	class-job-status class-warning	Job		
	Infoprint added to the job to the queue for rescheduling because the actual destination that accepted the job can no longer print the job.			
	5010-322 Job <i>JobID</i> (<i>ServerName:GlobalID</i>) is added to the queue to be scheduled again.			

Table 17. Notification Events (continued)

Event	Event Class	Objects Supported	
	Description		
	Message		
job-resubmitted	class-job-status class-report	Job Queue Server	
	The job was successfully resubmitted to a different logical destination. Processing continues.		
	5010-222 Job JobID (ServerName:GlobalID) was resubmitted to logical destination ServerName:DestinationName from queue ServerName:QueueName.		
job-resumed	class-job-status class-report	Job Queue Server	
	The job was resumed. If the job state is pending, Infoprint can schedule the job to an actual destination.		
	5010-199 Job JobID (ServerName:GlobalID) w	as resumed.	
ob-retained	class-report	Job	
	The job is retained.		
	5010-199 The job JobID (ServerName:GlobalI	D) is retained.	
ob-state-changed	class-job-status class-state-changed	Job	
	The state of the job has changed. Processing continues.		
	5010-201 The state of job JobID (ServerName:GlobalID) changed to State.		
job-submission-not-complete	class-error class-job-problem	Job Server	
	The server waited for the amount of time specified in its job-submission-timer attribute to receive an indication that all of the document objects in a job have been sent. It did not receive that indication. The server will process the documents it has received as a complete job.		
	5010-209 The final document indication for (ServerName:GlobalID) was not received by server's job-submission-timer interval. Job continue.	the server within the	
job-unassigned	class-report	Job	
	This job has been placed in the server's unassigned jobs area.		
	5010-661 The job <i>JobID</i> (<i>ServerName:GlobalID</i>) is not assigned to any destination.		
no-document	class-error class-job-problem	Actual destination Job Server	
	The server could not access the document. The document and possibly the entire job have been aborted. Check the error log for messages related to this failure.		
	5010-210 Document <i>DocNum</i> (<i>FileName</i>) in job <i>JobID</i> (<i>ServerName:GlobalID</i>) could not be accessed by the server.		

Table 17. Notification Events (continued)

Event	Event Class	Objects Supported	
	Description	·	
	Message		
no-resource	class-error class-job-problem	Actual destination Server	
	A resource needed by this job is unavailable. Infoprint aborted the job. Check the error log for messages related to this failure.		
	5010-211 The resource Resource needed by job JobID (ServerName:GlobalID) was not available.		
object-cleaned	class-actual-destination-default class-actual-destination-status class-logical-destination-default class-logical-destination-status class-queue-default class-queue-status class-server-default class-server-default class-server-status class-warning	Actual destination Logical destination Queue Server	
	Infoprint deleted jobs from this object. Processing continues.		
	5010-244 Successfully cleaned object ObjectClass ServerName:ObjectName.		
object-created	class-actual-destination-configuration class-logical-destination-configuration class-queue-configuration class-report	Actual destination Logical destination Queue Server	
	The object was created.		
	5010-224 Successfully created object ObjectClass ServerName:ObjectName.		
object-deleted	class-actual-destination-configuration class-actual-destination-default class-logical-destination-configuration class-logical-destination-default class-queue-configuration class-queue-default class-server-configuration class-server-default class-report	Actual destination Job Logical destination Queue Server	
	The object was deleted.		
	5010-225 Successfully deleted object ObjectClass ServerName:ObjectName.		
object-modified	class-actual-destination-configuration class-logical-destination-configuration class-queue-configuration class-server-configuration class-warning	Actual destination Logical destination Queue Server	
	The object was modified.		
	5010-241 Successfully modified object ObjectClass ServerName:ObjectName.		

Table 17. Notification Events (continued)

Event	Event Class	Objects Supported		
	Description			
	Message	1		
object-paused	class-actual-destination-attention class-queue-attention class-warning	Actual destination Job Queue Server		
	Infoprint paused an actual destination or queue and it cannot process jobs.			
	5010-242 Successfully paused object ObjectClass ServerName:ObjectName.			
object-resumed	class-actual-destination-status class-queue-status class-report	Actual destination Job Queue Server		
	Infoprint resumed an actual destination of	Infoprint resumed an actual destination or queue.		
	5010-227 Successfully resumed object ServerName:ObjectName.	5010-227 Successfully resumed object ObjectClass		
other-error	class-error class-server-attention	Actual destination Server		
	An error occurred for this object that no other message describes. Check the error log for messages related to this failure.			
	5010-217 Server ServerName encountered an error.			
other-warning	class-server-attention class-warning	Actual destination Server		
	The object encountered a warning condition that no other event describes. This warning condition may precede an error. Check the error log for messages related to this failure.			
	5010-236 Server ServerName has encountered a warning condition.			
past-discard-time	class-error class-job-attention	Job Queue Server		
	The date and time specified by the job-discard-time job attribute passed before the job printed and Infoprint discarded the job.			
	5010-213 Job JobID (ServerName:GlobalID) was discarded before it printed.			
processing-started	class-job-status class-report	Actual destination Job Queue Server		
	The server has begun to process the job. Infoprint has scheduled the job to print on an actual destination.			
	5010-200 Job JobID (ServerName:GlobalID) is processing.			

Table 17. Notification Events (continued)

Event	Event Class	Objects Supported	
	Description		
	Message		
queue-backlogged	class-queue-attention class-queue-default class-warning	Job Queue Server	
	Infoprint calculates that there are too many jobs in this queue for all jobs to print within the amount of time specified for the object-class-backlog-upper-bound attribute. The queue continues to accept jobs, but there is a delay before they print.		
	5010-304 The queue ServerName:QueueName is backlogged.		
queue-no-longer-backlogged	class-queue-status class-report	Job Queue Server	
	The queue is no longer backlogged. Infoprint calculates that the jobs currently in the queue will print within the amount of time specified for the object-class-backlog-lower-bound attribute.		
	5010-299 The queue ServerName: QueueName is no longer backlogged.		
queue-state-changed	class-queue-status class-state-changed	Queue	
	The queue state changed. Processing continues.		
	5010-230 The state of queue ServerName: QueueName changed to State.		
resource-needs-attention	class-actual-destination-attention class-warning	Actual destination Server	
	This resource needs attention from a person, not necessarily the operator. Infoprint cannot process jobs requiring this resource until someone corrects the problem.		
	5010-238 Resource Resource on actual destination ServerName: DestinationName needs attention.		
resource-needs-operator	class-actual-destination-attention class-warning	Actual destination Server	
	This resource needs attention from an operator. Infoprint cannot process jobs requiring this resource until an operator corrects the problem.		
	5010-239 Resource Resource on actual destination ServerName: DestinationName needs operator attention.		
server-shutdown-complete	class-server-attention class-server-default class-report	Server	
	This server has shut down and is no longer available.		
	5010-295 Successfully shut down server ServerName.		
server-shutdown-started	class-server-attention class-warning	Server	
	This server has begun to shut down. It does not accept jobs.		
	5010-305 The server ServerName is shutting down.		

Table 17. Notification Events (continued)

Event	Event Class	Objects Supported	
	Description	Description	
	Message		
server-startup-complete	class-report class-server-configuration	Server	
	Infoprint started this server.	·	
	5010-294 Successfully started serve	r ServerName.	
server-state-changed	class-server-status class-state-changed	Server	
	The state of the server has changed.	The state of the server has changed.	
	5010-299 The state of server Server	5010-299 The state of server ServerName changed to State.	
unable-to-register	class-warning	Actual destination Server	
	amount of time specified for the destir	The actual destination could not register with the queue within the amount of time specified for the destination-register-threshold actual destination attribute. Infoprint cannot schedule jobs to the actual destination.	
	5010-437 The actual destination Ser register with the queue QueueName.	5010-437 The actual destination ServerName: DestinationName cannot register with the queue QueueName.	
unrecognized-resource	class-error class-job-problem	Actual destination Server	
	A resource required for this job is not known to the server. The job was aborted. Check the server error log for messages related to this failure.		
		5010-214 Resource Resource that is required for job JobID (ServerName:GlobalID) is not known to the server.	

An event class is an easy way to include multiple events in a value. Event classes group events based on the functions for which they provide notification. For example, some classes are specific to configuration tasks while other classes provide information about the status of Infoprint objects. Each event class name begins with class.

Note: An event identifier can occur in more than one class. For example, object-cleaned occurs in class-logical-destination-default, class-logical-destination-status, class-actual-destination-default, class-actual-destination-status, class-object-class-default, class-object-class-status, class-server-default, class-server-status, and class-warning. If the notification profile values list any of these event classes and you clean a logical destination, actual destination, queue, or server, Infoprint sends a message to the person identified in that value.

Notification Events

Table 18. Notification Event Classes

Event Class	Description
	Events
class-aborted	An aborted event occurs whenever a server aborts a job or document object, or when the user or operator cancels a job.
	document-aborted-by-destination document-aborted-by-server document-cancelled-at-destination job-aborted-by-server job-cancelled-by-operator job-cancelled-by-user
class-actual-destination-attention	These events indicate that problems exist with the actual destination. Such problems usually require an operator or administrator to intervene.
	destination-disabled destination-needs-administrator destination-needs-attention destination-needs-operator destination-shutdown-job-requeued destination-timed-out object-paused resource-needs-attention resource-needs-operator
class-actual-destination-configuration	These events have to do with the creation or deletion of an actual destination, or with modification of the attributes of an actual destination.
	object-created object-deleted object-modified
class-actual-destination-default	This is the default event class for actual destinations.
	destination-needs-administrator destination-needs-attention destination-needs-operator destination-timed-out object-cleaned object-deleted
class-actual-destination-status	This event class includes events that give detailed status about the actual destination. These changes in status are often routine and do not require intervention.
	destination-enabled destination-function-unavailable destination-registered destination-state-changed destination-unregistered object-cleaned object-resumed

Table 18. Notification Event Classes (continued)

Event Class	Description
	Events
class-error	An error event occurs whenever an error occurs. Generally, an error event signals a condition that may prevent the job from completing successfully, depending on the settings of other parameters.
	document-content internal-server-error job-submission-not-complete no-document no-resource other-error past-discard-time unrecognized-resource
class-job-attention	These events indicate that problems exist with a job. They usually require an operator or administrator to intervene.
	close-to-discard-time destination-function-unavailable destination-needs-administrator destination-needs-attention destination-needs-operator destination-shutdown-job-requeued destinations-not-ready-for-job detailed-messages document-aborted-by-destination document-aborted-by-server document-cancelled-at-destination job-aborted-by-server job-cancelled-by-operator job-cancelled-by-user job-cannot-be-scheduled job-discarded job-paused past-discard-time
class-job-default	This is the default event class for jobs. document-aborted-by-destination document-aborted-by-server document-cancelled-at-destination
	destination-needs-attention destination-needs-operator destinations-not-ready-for-job job-aborted-by-server job-cancelled-by-operator job-cannot-be-scheduled job-completed past-discard-time
class-job-problem	These are events in which the job has encountered a problem but will attempt to proceed.
	document-content job-submission-not-complete no-document no-resource unrecognized-resource

Notification Events

Table 18. Notification Event Classes (continued)

Event Class	Description
	Events
class-job-status	This event class includes events that give detailed status about the job. These changes in status are often routine and do not require intervention.
	checkpoint-taken file-transferred job-assigned-to-queue job-completed job-modified job-promoted job-reordered job-resubmitted job-resubmitted job-resumed job-state-changed processing-started
class-logical-destination-attention	This event indicates that a problem exists with the logical destination. An operator or administrator usually has to intervene.
	destination-disabled
class-logical-destination-configuration	These events have to do with the creation or deletion of a logical destination, or with modification of the attributes of a logical destination.
	object-created object-deleted object-modified
class-logical-destination-default	This is the default event class for logical destinations.
	object-cleaned object-deleted
class-logical-destination-status	This event class includes events that give detailed status about the logical destination. These changes in status are often routine and do not require intervention.
	destination-enabled object-cleaned
class-queue-attention	These events indicate that problems exist with the queue. An operator or administrator usually has to intervene.
	object-paused queue-backlogged
class-queue-configuration	These events have to do with the creation or deletion of a queue, or with the modification of the attributes of a queue.
	object-created object-deleted object-modified
class-queue-default	This is the default event class for queues.
	object-cleaned object-deleted queue-backlogged

Table 18. Notification Event Classes (continued)

Event Class	Description		
	Events		
class-queue-status	This event class includes events that give detailed status about the queue. These changes in status are often routine and do not require intervention.		
	object-cleaned object-resumed queue-no-longer-backlogged queue-state-changed		
class-report	A report event occurs whenever a significant point in processing occurs.		
	checkpoint-taken destination-enabled destination-registered detailed-messages file-transferred job-assigned-to-destination job-assigned-to-destination-at-end job-assigned-to-queue job-completed job-discarded job-promoted job-reordered job-resubmitted job-resubmitted job-resumed job-retained job-unassigned object-created object-created object-deleted object-resumed processing-started queue-no-longer-backlogged server-shutdown-complete		
class-server-attention	These events indicate that problems exist with the server. They usually require an administrator to intervene.		
	internal-server-error other-error other-warning server-shutdown-complete server-shutdown-started		
class-server-configuration	These events have to do with the creation or deletion of a server or with modification of the attributes for a server.		
	object-deleted object-modified server-startup-complete		
class-server-default	This is the default event class for servers.		
	internal-server-error object-cleaned object-deleted server-shutdown-complete		

Notification Events

Table 18. Notification Event Classes (continued)

Event Class	Description
	Events
class-server-status	This event class includes events that give detailed status about the server. These changes in status are often routine and do not require intervention.
	object-cleaned server-state-changed
class-state-changed	A state-change event occurs whenever the state of an actual destination, job, queue, or server changes.
	destination-state-changed job-state-changed queue-state-changed server-state-changed
class-warning	A warning event occurs whenever a condition arises which affects processing. Generally, a warning event signals a condition that does not prevent completion of the processing, but it may require some action by the operator or user.
	close-to-discard-time destination-disabled destination-function-unavailable destination-needs-administrator destination-needs-attention destination-needs-operator destination-shutdown-job-requeued destination-timed-out destination-unregistered destinations-not-ready-for-job job-cannot-be-scheduled job-modified job-paused job-requeued object-cleaned object-modified object-modified object-paused other-warning queue-backlogged resource-needs-attention resource-needs-operator server-shutdown-started unable-to-register

Appendix A. Attribute-to-Object Listing

Attribute	Objects	See Page
accept-jobs	Actual destination	340
accept-unsupported-jobs	Server	643
account-text	Default document Document	469 469
accounting-exit	Actual destination	340
ack-interval	Actual destination	341
actual-destinations-assigned	Queue	630
actual-destinations-ready	Queue Server	630 644
actual-destinations-requested	Default job Job	543 543
actual-destinations-supported	Server	644
add-carriage-returns	Actual destination	342
add-line-feeds	Actual destination	342
address1-text	Default document Document	469 469
address2-text	Default document Document	470 470
address3-text	Default document Document	470 470
address4-text	Default document Document	471 471
ascii-character-map	Actual destination	342
ascii-font-map	Actual destination	343
assign-to-destination	Queue	631
assign-to-printer	Queue	631
associated-queue	Actual destination Logical destination	344 599
associated-server	Actual destination Auxiliary sheet Default document Default job Log Logical destination Medium Queue Resource context Transform	344 458 471 544 593 599 624 631 640 666
attachment-type	Actual destination	345
attribute-map	Actual destination	346
audit-exit	Actual destination	347
authorize-jobs	Logical destination	600
auto-create-shared-printers	Server	600

Attribute	Objects	See Page
color-profile	Actual destination Default document Document	353 477 477
color-profiles-supported	Actual destination	354
color-toner-saver	Actual destination Default document Document	355 478 478
color-toner-saver-supported	Actual destination	355
command	Actual destination	360
color-rip-servers	Actual destination	354
comment	Default job Job	555 555
completion-time	Job	545
compressed-output	Default document Document	478 478
connection-timeout	Actual destination	356
content-orientation	Default document Document	479 479
content-orientations-supported	Actual destination Logical destination	356 601
context-address	Resource context	641
control-strip	Default document Document	479 479
convert-to-ebcdic	Default document Document	480 480
convert-to-ebcdic-supported	Actual destination Logical destination	357 602
copies	Default document Document	480 480
copy-count	Default document Document	480 480
current-backlog	Queue	638
current-job-state	Job	545
current-page-printing	Job	546
d-s-s-requested	Default job Job	551 551
data-fidelity-problem-reported	Default document Document	481 481
data-fidelity-problem-reported-supported	Actual destination Logical destination	358 603
deadline-in-jeopardy	Job	547
default-character-mapping	Default document Document	481 481
default-font-fidelity-action	Actual destination	358
default-font-resolution	Actual destination	359

Attribute	Objects	See Page
default-input-tray	Actual destination Default document Document	359 482 482
default-medium	Default document Document	483 483
default-printer-resolution	Default document Document	484 484
delete-segment-list	Default job Job	547 547
department-text	Default document Document	484 484
descriptor	Actual destination Auxiliary sheet Default document Default job Log Logical destination Medium Queue Resource context Server Transform	360 459 485 548 593 603 625 633 641 645 666
destination-associated-destinations	Logical destination	604
destination-command	Actual destination	360
destination-company-text	Default document Document	485 485
destination-data-stream	Actual destination	361
destination-initial-value-document	Document Logical destination	485 604
destination-initial-value-job	Job Logical destination	548 604
destination-locations	Actual destination Logical destination	362 605
destination-locations-requested	Default job Job	549 549
destination-model	Actual destination Logical destination	363 605
destination-models-requested	Default job Job	549 549
destination-name	Actual destination Logical destination	364 605
destination-name-requested	Job	550
destination-needs-attention-time	Actual destination	364
destination-needs-key-operator-attention-time	Actual destination	365
destination-pass-through	Actual destination Default document Document	365 486 486
destination-poll-interval	Actual destination	366

Attribute	Objects	See Page
destination-realization	Actual destination Logical destination	366 606
destination-register-threshold	Actual destination	366
destination-release-timer	Actual destination	367
destination-state	Actual destination	368
destination-states-supported	Server	646
destination-support-system	Actual destination Logical destination	369 606
destination-support-systems-supported	Server	646
destination-tcpip-internet-address	Actual destination	370
destination-tcpip-port-number	Actual destination	371
destination-timeout-period	Actual destination	371
destinations-assigned	Job	550
destinations-ready	Logical destination	607
destinations-used	Job	551
device-name	Actual destination	372
device-support-system	Actual destination Logical destination	369 606
device-support-system-requested	Default job Job	551 551
discard-time	Job	557
document-attributes-supported	Actual destination Server	373 647
document-comment	Default document Document	486 486
document-content	Document	486
document-content-list	Document	487
document-file-name	Document	487
document-finishing	Default document Document	487 487
document-finishings-supported	Actual destination	375
document-format	Default document Document	488 488
document-formats-ripped-at-destination	Actual destination Logical destination	376 607
document-formats-supported	Actual destination Logical destination Transform	376 607 667
document-number	Document	489
document-sequence-number	Document	489
document-type	Document	490
document-types-supported	Actual destination Logical destination	378 608
dot-shape	Default document Document	491 491

Attribute	Objects	See Page
dss-job-message-disposition	Actual destination	379
dss-job-message-log-size	Actual destination	379
dss-job-message-log-wrap	Actual destination	380
dss-requested	Default job Job	551 551
ebcdic-character-mapping	Actual destination	380
email-from-address	Default document Document	492 492
email-to-address	Default document Document	493 493
enable-settrap	Default document Document	493 493
enabled	Actual destination Log Logical destination	381 594 608
end-message	Default job Job	558 558
end-message-supported	Actual destination Logical destination	381 609
end-sheets-supported	Actual destination	382
estimated-completion-time	Job	552
estimated-processing-time	Job	553
events-supported	Server	647
fax-number	Default document Document	493 493
fax-to-name	Default document Document	494 494
file-name	Document	487
font-fidelity-action	Default document Document	494 494
font-processing-messages	Default document Document	495 495
font-resolution	Default document Document	495 495
font-resolutions-supported	Actual destination	383
force-destination-setup	Actual destination	383
force-printer-setup	Actual destination	383
form-definition	Actual destination Default document Document	384 496 496
format	Default document Document	488 488
formatted-job-ticket-content	Job	553
global-id	Job	560
halftone	Default document Document	496 496

Attribute	Objects	See Page
halftones-supported	Actual destination	384
hold	Default job Job	559 559
hostname	Server	660
i-p-address	Server	660
ip-address	Server	660
image-center-x	Default document Document	497 497
image-center-y	Default document Document	498 498
image-fit	Default document Document	498 498
image-fit-supported	Actual destination	386
image-length	Actual destination Default document Document	386 499 499
image-out-format	Default document Document	500 500
image-out-formats-supported	Actual destination Logical destination	387 609
image-scale	Default document Document	501 501
image-width	Actual destination Default document Document	388 501 501
initial-value-document	Document	502
initial-value-document-identifier	Default document	503
initial-value-job	Job	554
initial-value-job-identifier	Default job	554
input-data-user-exit	Actual destination	389
input-exit	Default document Document	503 503
input-tray-select	Default document Document	504 504
input-trays-medium	Actual destination	389
input-trays-supported	Actual destination Logical destination	391 610
intervening-jobs	Job	554
intervention-timer	Actual destination	391
ip-address	Server	660
job-attributes-supported	Actual destination Server	392 649
job-batch	Default job Job	555 555
job-batches-ready	Actual destination	392
job-client-id	Job	555

Attribute	Objects	See Page
job-comment	Default job Job	555 555
job-complexity	Default job Job	556 556
job-copies-completed	Job	556
job-deadline-time	Job	557
job-discard-time	Job	557
job-end-message	Default job Job	558 558
job-finishing	Default job Job	558 558
job-finishings-supported	Actual destination	393
job-hold	Default job Job	559 559
job-identifier	Job	560
job-log	Job	560
job-media-sheet-count	Job	561
job-message-from-administrator	Job	561
job-message-to-operator	Default job Job	562 562
job-name	Default job Job	562 562
job-originator	Job	563
job-owner	Job	563
job-page-count	Job	564
job-print-after	Job	564
job-priority	Default job Job	565 565
job-retain-until	Job	565
job-retention-period	Default job Job	566 566
job-retry-count-limit	Actual destination	394
job-retry-interval	Actual destination	394
job-rip-action	Default job Job	566 566
job-rip-actions-supported	Actual destination	395
job-ripped-by-server	Default job Job	567 567
job-size	Job	590
job-size-range-ready	Actual destination	395
job-size-range-supported	Actual destination Logical destination	396 611
job-start-message	Default job Job	570 570

Attribute	Objects	See Page
job-start-wait	Default job	571
	Job	571
job-start-wait-supported	Actual destination	397
job-state	Job	545
job-state-reasons	Job	571
job-state-reasons-supported	Server	649
job-states-supported	Server	649
job-submission-complete	Job	573
job-submission-timer	Server	650
job-ticket-content	Job	553
jog-between-job-copies	Default document Document	504 504
last-accessor	Job	576
last-modifier	Job	576
list-of-managers	Actual destination Default document Default job Logical destination Queue Server	398 505 573 611 634 650
locale	Server	651
locations	Actual destination Logical destination	362 605
locations-requested	Default job Job	549 549
log-accounting data	Actual destination Server	398 651
log-address	Log	594
log-identifier	Log	594
log-messages	Log	595
log-severity	Log	595
log-size	Log	596
log-trace-groups	Log	596
log-type	Log	596
log-wrap	Log	597
logical-destinations-assigned	Actual destination Queue	399 634
logical-destinations-ready	Default document Default job Queue Server	505 574 634 652
logical-destinations-supported	Server	652
logical-printer	Logical destination	605
logical-printer-requested	Job	550
logical-printers-assigned	Queue	634

Attribute	Objects	See Page
logical-printers-ready	Default document Default job Queue Server	505 574 634 652
logical-printers-supported	Server	652
managers	Actual destination Default document Default job Logical destination Queue Server	398 505 573 611 634 650
maximum-barco-rips	Server	653
maximum-concurrent-jobs	Actual destination	400
maximum-copies-supported	Actual destination Logical destination	401 612
maximum-fonts-to-keep	Actual destination	401
maximum-messages-printed	Default document Document	506 506
maximum-non-raster-rips	Server	653
maximum-overlays-to-keep	Actual destination	402
maximum-presentation-object-containers- to-keep	Actual destination	402
maximum-raster-rips	Server	653
maximum-segments-to-keep	Actual destination	403
maximum-transform-pages-ahead	Default document Document	506 506
media-ready	Actual destination	403
media-sheet-count	Job	561
media-sheets-completed	Job	575
media-supported	Actual destination Logical destination	404 612
medium-color	Medium	625
medium-dimensions	Medium	625
medium-form-parts	Medium	626
medium-holes-count	Medium	626
medium-identifier	Medium	627
medium-sides	Medium	627
medium-size	Medium	628
medium-type	Medium	628
medium-weight	Medium	629
message	Actual destination Default document Default job Logical destination Medium Queue Server	405 507 575 613 629 635 654

Attribute	Objects	See Page
message-font-type	Actual destination	405
message-form-definition	Actual destination	406
message-from-administrator	Job	561
message-to-operator	Default job Job	562 562
model	Actual destination Logical destination	363 605
models-requested	Default job Job	549 549
modification-time	Job	576
modify-individual-document-supported	Server	654
multiple-documents-supported	Server	654
mvs-class	Default document Document	507 507
mvs-destination	Default document Document	507 507
mvs-forms	Default document Document	508 508
mvs-segment-id	Default document Document	508 508
name	Default job Job	562 562
name-of-last-accessor	Job	576
name-text	Default document Document	509 509
new-job-identifier	Job	576
new-line-option	Default document Document	509 509
node-id-text	Default document Document	510 510
non-process-runout-timer	Actual destination	406
notification-delivery-methods-supported	Server	654
notification-profile	Actual destination Default job Job Logical destination Queue Server	407 577 577 613 635 655
notify-operator	Actual destination Queue	408 636
npm-server-ip-address	Server	656
npm-server-port-number	Server	657
nt-drivers	Logical destination	621
number-of-documents	Job	579
number-up	Default document Document	510 510

Attribute	Objects	See Page
number-up-supported	Actual destination	409
object-class	Actual destination Auxiliary sheet Default document Document	410 459 511 511
	Default job Job Log Logical destination Medium Queue	579 579 597 615 629
	Resource context Server Server	641 657 667
object-classes-supported	Server	657
octet-count	Document	511
octets-completed	Job	580
offset-stacking-available	Actual destination	410
offset-stacking-between-jobs	Default document Document	512 512
operators	Actual destination Queue	408 636
optimize-for-multiple-copies	Actual destination Default job Job	411 580 580
orientation	Default document Document	479 479
orientations-supported	Actual destination Logical destination	356 601
originating-company-text	Default document Document	512 512
originator	Job	563
os2-driver-names	Logical destination	615
os2-drivers	Logical destination	615
other-options	Actual destination Default document Document	365 486 486
other-transform-options	Default document Document Tranform	512 512 668
output-appearance	Default document Document	513 513
output-appearances-supported	Actual destination	412
output-bin	Actual destination Default document Document	412 513 513
output-bin-numbers	Actual destination	413
output-bins-supported	Actual destination	414
output-data-user-exit	Actual destination	414
•		

Attribute	Objects	See Page
output-document-format	Transform	669
output-face-up	Default document Document	514 514
output-format	Default document Document	515 515
output-format-supported	Actual destination	415
overlay	Actual destination Default document Document	416 516 516
overlay-back	Default document Document	516 516
overlay-front	Default document Document	517 517
overprint	Default document Document	517 517
owner	Job	563
page-clip	Default document Document	518 518
page-count	Document	518
page-definition	Default document Document	519 519
page-media-select	Default document Document	519 519
page-select	Document	519
page-select-supported	Actual destination Logical destination	416 616
pages-completed	Job	581
pcl-server-address	Actual destination	417
pcl-server-port	Actual destination	417
physical-printer	Actual destination	364
physical-printers-assigned	Queue	630
physical-printers-ready	Queue Server	630 644
physical-printers-requested	Default job Job	543 543
physical-printers-supported	Server	644
plex	Actual destination Default document Document	418 521 521
plexes-supported	Actual destination Logical destination	418 617
position-in-queue	Job	554
postscript-server-address	Actual destination	419
postscript-server-port	Actual destination	420
presentation-fidelity-problem-reported	Actual destination	420

Attribute	Objects	See Page
presentation-object-containers-extraction- mode	Actual destination	421
previous-job-state	Job	582
previous-state	Job	582
print-after	Job	564
print-edge-marks	Actual destination	421
print-qualities-supported	Actual destination Logical destination	421 617
print-quality	Default document Document	521 521
print-queue	Actual destination	422
print-queue-name	Actual destination	422
printer	Actual destination Logical destination	364 605
printer-associated-printers	Logical destination	604
printer-command	Actual destination	360
printer-data-stream	Actual destination	361
printer-end-sheet	Actual destination	423
printer-escape-codes	Actual destination	423
printer-initial-value-document	Document Logical destination	485 604
printer-initial-value-job	Job Logical destination	548 604
printer-locations	Actual destination Logical destination	362 605
printer-locations-requested	Default job Job	549 549
printer-memory	Actual destination	424
printer-model	Actual destination Logical destination	363 605
printer-models-requested	Default job Job	549 549
printer-name	Actual destination Logical destination	364 605
printer-name-requested	Default job Job	550 550
printer-needs-attention-time	Actual destination	364
printer-needs-key-operator-attention-time	Actual destination	365
printer-pass-through	Actual destination Default document Document	365 486 486
printer-realization	Actual destination Logical destination	366 606
printer-register-threshold	Actual destination	366
printer-release-timer	Actual destination	367

Attribute	Objects	See Page
printer-requested	Default job Job	550 550
printer-resolutions-ready	Actual destination	425
printer-resolutions-supported	Actual destination	426
printer-separator-sheet	Actual destination	427
printer-start-sheet	Actual destination	428
printer-state	Actual destination	368
printer-states-supported	Server	646
printer-s370-channel-device-address	Actual destination	429
printer-s370-channel-slot-number	Actual destination	430
printer-tcpip-internet-address	Actual destination	370
printer-tcpip-port-number	Actual destination	371
printer-timeout-period	Actual destination	430
printers-assigned	Job	550
printers-ready	Logical destination	607
printers-used	Job	551
problem-child	Server	658
problem-message	Actual destination	430
processing-time	Job	583
programmer-text	Default document Document	522 522
protected-attributes	Actual destination Logical destination Queue Server	431 618 638 658
psf-exit-form-definition	Auxiliary sheet	459
psf-exit-page-mark	Auxiliary sheet	459
psf-exit-program-name	Auxiliary sheet	460
psf-tray-characteristics	Actual destination	431
public-context-presentation-object- container	Actual destination	434
qualities-supported	Actual destination Logical destination	421 617
queue-assigned	Job	584
queue-backlog	Queue	638
queue-name	Queue	638
queue-position	Job	554
queue-state	Queue	638
queues-supported	Server	659
reasons	Job	571
register-threshold	Actual destination	366
registered-with-spooler	Actual destination	435
remote-queue	Actual destination	435

Attribute	Objects	See Page
screen-frequencies-supported	Actual destination	446
screen-frequency	Default document Document	531
security-level	Server	659
segment-file-size	Default document Document	532 532
separator-sheets-supported	Actual destination	447
sequence-number	Document	489
server-hostname	Server	660
server-ip-address	Server	660
server-name	Server	661
server-state	Server	661
shared-formdef	Default document Document	532 532
shared-printer-name	Actual destination	448
shift-out-shift-in	Default document Document	533 533
sides	Actual destination Default document Document	448 534 534
sides-supported	Actual destination Logical destination	449 619
smtp-server-host	Server	661
smtp-server-port-number	Server	662
snmp-active	Actual destination	450
snmp-aix-printer-models	Server	662
snmp-community-name	Actual destination	450
snmp-discovery-during-stamp	Server	662
snmp-normal-poll-interval	Server	663
snmp-problem-poll-interval	Server	663
snmp-retry-count	Actual destination	450
snmp-timeout	Actual destination	451
start-message	Default job Job	570 570
start-message-supported	Actual destination Logical destination	451 619
start-on-new-sheet	Default document Document	535 535
start-sheets-supported	Actual destination	452
started-printing-time	Job	587
state-reasons	Job	571
subject-text	Default document Document	535 535
submission-time	Job	587

Attribute	Objects	See Page
table-reference-characters	Default document Document	535 535
table-reference-characters-supported	Actual destination Logical destination	453 619
tape-exit	Job	588
tape-format	Job	588
tape-labeled	Job	589
tape-max-block-size	Job	589
tape-rewind-before	Job	590
tape-rewind-unload	Job	590
terminating-tranform	Transform	670
ticket-content	Job	553
timeout-period	Actual destination	430
title-text	Default document Document	536 536
total-job-octets	Job	590
transfer-method	Document	536
transfer-methods-supported	Server	664
transform-identifier	Transform	671
transform-library	Transform	671
transform-message-file-name	Default document Document	537 537
transform-output-file-name	Default document Document	537 537
transform-sequence	Actual destination	453
type	Document	490
use-snmp	Actual destination	454
user-id-text	Default document Document	538 538
user-locale	Job	591
user-name	Job	591
wait-for-job-completion	Actual destination	454
warning-message	Actual destination	455
windows-driver-names	Logical destination	620
windows-drivers	Logical destination Server	620 665
windows-nt-driver-names	Actual destination Logical destination Server	455 621 665
windows-nt-drivers	Logical destination Server	621 665
x-image-shift	Default document Document	538 538

Attribute	Objects	See Page
x-image-shift-back	Default document Document	539 539
x-image-shift-range-supported	Actual destination Logical destination	456 622
y-image-shift	Default document Document	540 540
y-image-shift-back	Default document Document	540 540
y-image-shift-range-supported	Actual destination Logical destination	457 622

Appendix B. Migrating PSF for AIX Job Script Keywords to Infoprint Equivalents

Table 19 and Table 20 on page 717 list the PSF for AIX job script keywords that the **jsmigr** utility (see "jsmigr Utility: Migrates PSF for AIX Job Scripts in Infoprint Manager for AIX" on page 149) migrates to Infoprint document and job attributes, or to flags and arguments of the **pdpr** command.

Notes:

- 1. See "jsmigr Utility: Migrates PSF for AIX Job Scripts in Infoprint Manager for AIX" on page 149 for notes on migration.
- 2. Keywords not listed in this table have no equivalent.

Table 19. PSF for AIX Keywords Used in Job Script Files and Infoprint Equivalents

,	s Used in Job Script Files and Infoprint Equivalents
PSF Keyword	Infoprint Attribute, Flag, or Argument
a_Cc a_Cctype	carriage-control-type
	ned together to generate carriage-control-type . If jsmigr assumes the default value of yes for cc .
a_Chars	chars
a_Fileformat	new-line-option
a_Imageout	image-out-format
a_InpExit	input-exit
a_OtherOptions	other-transform-options
a_Pagedef	page-definition
a_Parmdd	Attributes file
a_Pdeflib	resource-context-page-definition
a_Prmode	shift-out-shift-in
a_Trc	table-reference-characters
db_euc db_language	default-character-mapping
Note: db_euc and db_language must be used together to generate default-character-mapping.	
e_ConsoleMsg	job-start-message job-start-wait
e_FileMsg	job-start-message job-start-wait
e_Notify	notification-profile (delivery-method component)
e_PrintQueue	-p flag of pdpr command
e_Priority	job-priority
i_Exit	tape-exit
i_Filenames	Job scripts invoked by this keyword (extension .js) are migrated to attributes files invoked with the -X flag of the
	pdpr command. Print files are migrated to arguments of the pdpr command in the pdpr script.

Table 19. PSF for AIX Keywords Used in Job Script Files and Infoprint Equivalents (continued)

DOE I/	T C . A A A A TI A . A		
PSF Keyword	Infoprint Attribute, Flag, or Argument		
i_Format	No equivalent		
i_InputDevice	-f, -T, or - flag of pdpr command		
i_Labeled	tape-labeled		
i_MaxBlockSize	tape-max-block-size		
i_OutExit	No equivalent		
i_PgsAhead	maximum-transform-pages-ahead		
i_RewindBefore	tape-rewind-before		
i_RewindUnload	tape-rewind-unload		
JsFileType	document-format		
oa_Formdef	form-definition		
oa_SrchAFP	resource-context		
oa_SrchFd	resource-context-form-definition		
oa_SrchOvly	resource-context-overlay		
oa_SrchPs	resource-context-page-segment		
oa_SrchFO	resource-context-font		
oa_SrchSf	No equivalent		
o_Account	account-text		
o_Address1	address1-text		
o_Address2	address2-text		
o_Address3	address3-text		
o_Address3	address3-text		
o_Bin	destination-pass-through to ainbe		
o_Building	building-text		
o_Codeset	default-character-mapping		
o_Copies	results-profile (job-copies component)		
o_DataCk	data-fidelity-problem-reported		
o_Department	department-text		
o_Distribution	results-profile (delivery-address component)		
o_Duplex	plex sides		
o_Header	auxiliary-sheet-selection		
Note: o_Header, o_Separator, auxiliary-sheet-selection.	and o_Trailer are examined together to generate		
o_JobName	job-name		
o_MsgCount	maximum-messages-printed		
o_Name	name-text		
o_Nodeid	node-id-text		
o_Outbin	output-bin		
o_Overlay	overlay		
	·		

Table 19. PSF for AIX Keywords Used in Job Script Files and Infoprint Equivalents (continued)

<u> </u>			
PSF Keyword	Infoprint Attribute, Flag, or Argument		
o_PassThru	mvs-class		
	mvs-dest		
	mvs-forms		
	mvs-segment-id		
o_Programmer	programmer-text		
o_Room	room-text		
o_Separator	auxiliary-sheet-selection		
Note: o_Header, o_Separator, auxiliary-sheet-selection.	and o_Trailer are examined together to generate		
o_SetupFile	No equivalent		
o_Title	title-text		
o_Trailer	auxiliary-sheet-selection		
Note: o_Header, o_Separator, auxiliary-sheet-selection.	and o_Trailer are examined together to generate		
o_Userid	user-id-text		
o_Xoffset	x-image-shift		
o_Yoffset	y-image-shift		
p_Config	Attributes file		
	other-transform-options		
p_Length	image-length		
p_OtherOptions	other-transform-options		
p_OutputType	image-out-format		
Note: There is no equivalent for	or some values of p_OutputType .		
p_Resolution	default-printer-resolution		
p_Width	image-width		
s_SegSize	segment-file-size		

Table 20. PSF for AIX Keywords Used in parmdd Files

PSF Keyword	Infoprint Attribute, Flag, or Argument			
cc cctype	carriage-control-type			
	ned together to generate carriage-control-type . If jsmigr assumes the default value of yes for cc .			
chars	chars			
fdeflib	resource-context-form-definition			
fileformat	new-line-option			
fontlib	resource-context-font			
formdef	form-definition			
imageout	image-out-format			
inpexit	input-exit			
inputdd	No equivalent			
msgdd	transform-message-file-name			

Table 20. PSF for AIX Keywords Used in parmdd Files (continued)

PSF Keyword	Infoprint Attribute, Flag, or Argument		
outexit	No equivalent		
outputdd	transform-output-file-name		
ovlylib	resource-context-overlay		
pagedef	page-definition		
parmdd	Attributes file		
pdeflib	resource-context-page-definition		
prmode	shift-out-shift-in		
pseglib	resource-context-page-segment		
resexit	resource-exit		
reslib	resource-context		
trc	table-reference-characters		
userlib	resource-context-user		

Appendix C. Job Validation and Scheduling

Table 21 on page 720 and Table 22 on page 721 list the document, job, and destination attributes used to validate and schedule each job.

1. Infoprint validates the value of the document or job attribute in the first column against the values of the logical destination attribute in the second column. If the logical destination does not support the document or job attribute value, Infoprint rejects the job.

Note: If the logical destination attribute has no value, the logical destination supports all valid values of the document or job attribute.

- If the value of the server attribute accept-unsupported-jobs is false, Infoprint
 validates the value of the document or job attribute in the first column against
 the values of the actual destination attribute in the second column. If no actual
 destination supports the document or job attribute value, Infoprint rejects the
 job.
- 3. If the value of the queue attribute **assign-to-destination** is **true**, Infoprint assigns the job to an actual destination that supports all the job's attribute values.

Note: If the value of the **force-destination-setup** actual destination attribute is **true**, Infoprint assumes that the actual destination supports all valid attribute values.

- 4. Infoprint checks the attribute (or, for rescheduling, the checkpoint) in the first column against the attributes in the third column to determine if any actual destinations can process the job.
 - If the job has been assigned to an actual destination, Infoprint checks only that actual destination.
 - If the job has not been assigned to an actual destination, Infoprint checks all actual destinations that receive jobs from the queue.

Note: If the value of the **force-destination-setup** actual destination attribute is **true**, Infoprint assumes that the actual destination can process any job with valid attribute values.

- 5. Infoprint acts according to the result of step 4:
 - If a required resource is not ready, Infoprint holds the job. The required-resources-not-ready job attribute indicates the resources that a job or document attribute specifies and that are not ready on the actual destination to which the job is assigned, or, if the job is not assigned, on the most suitable actual destination.
 - If the value of the job attribute job-rip-action is rip-and-print-ignore-ready, Infoprint RIPs the job before placing it in the held state and sets the value of the job-state-reasons job attribute to rip-completed. The job is automatically released and scheduled for printing or transmission when the resources become ready.
 - Otherwise, Infoprint sets the value of the job-state-reasons job attribute to required-resource-not-ready. You must release the job after making the resources ready. Infoprint will not release it automatically.
 - If a required resource is not supported, Infoprint holds the job and sets the value of the **job-state-reasons** job attribute to **required-resource-not-supported**. The **required-resources-not-supported** job attribute indicates the

resources that a job or document attribute specifies and that are not supported on the actual destination to which the job is assigned, or, if the job is not assigned, on the most suitable actual destination.

This situation can arise when the value of the server attribute **accept-unsupported-jobs** is **true** or when you change document, job, or actual destination attribute values after Infoprint accepts a job.

You can change job, document, or actual destination attribute values so that at least one actual destination supports the job. You must then release the job before it can be printed or transmitted. Infoprint will not release it automatically.

- If at least one actual destination can handle the job, Infoprint schedules the job for printing or transmission.
- 6. If the job has not already been assigned to an actual destination, Infoprint assigns it to the first suitable actual destination to become available after the job reaches the top of the queue.
- 7. If the job is assigned to an actual destination with a value of **true** for the **force-destination-setup** attribute, Infoprint checks the attributes in the third column when the job is about to be printed or transmitted. If any resources are not ready or not supported, Infoprint disables the actual destination and sends a message to the operator. The operator changes the destination setup and enables the actual destination.
- 8. The job is printed or transmitted.

Table 21. Document and Destination Attributes Used for Validation and Scheduling

Document Attribute	Validation Attribute	Scheduling Attribute	
carriage-control-type	carriage-control-types-supported	carriage-control-types-supported	
content-orientation	content-orientation-supported	content-orientation-supported	
convert-to-ebcdic	convert-to-ebcdic-supported	convert-to-ebcdic-supported	
copy-count	maximum-copies-supported	maximum-copies-supported	
data-fidelity-problem- reported	data-fidelity-problem-reported- supported	data-fidelity-problem-reported- supported	
default-character-mapping	character-mappings-supported	character-mappings-supported	
default-input-tray	input-trays-supported	input-trays-supported	
default-medium	media-supported	media-ready media-supported	
default-printer-resolution	printer-resolutions-supported	printer-resolutions-ready printer-resolutions-supported	
document-finishing	document-finishings-supported ¹	document-finishings-supported	
document-format	document-formats-supported	document-formats-supported	
document-type	document-types-supported	document-types-supported	
font-resolution	font-resolutions-supported ¹	font-resolutions-supported	
image-fit	image-fit-supported ¹	image-fit-supported	
image-out-format	image-out-formats-supported	image-out-formats-supported	
input-tray-select	input-trays-supported	input-trays-supported	
number-up	number-up-supported ¹	number-up-supported	
output-appearance	output-appearances-supported ¹	output-appearances-supported	
output-bin	output-bins-supported ¹	output-bins-supported	
output-format	output-formats-supported ¹	output-formats-supported	

Table 21. Document and Destination Attributes Used for Validation and Scheduling (continued)

Document Attribute	Validation Attribute	Scheduling Attribute		
page-media-select	media-supported	media-ready media-supported		
page-select	page-select-supported	page-select-supported		
plex	plexes-supported	plexes-supported		
print-quality	print-qualities-supported	print-qualities-supported		
scanner-correction	scanner-corrections-supported ¹	scanner-corrections-supported		
screen-frequency	screen-frequencies-supported ¹	screen-frequencies-supported		
sides	sides-supported	sides-supported		
table-reference-characters	table-reference-characters-supported	table-reference-characters-supported		
x-image-shift	x-image-shift-range-supported	x-image-shift-range-supported		
x-image-shift-back	x-image-shift-range-supported	x-image-shift-range-supported		
y-image-shift	y-image-shift-range-supported	y-image-shift-range-supported		
y-image-shift-back	y-image-shift-range-supported	y-image-shift-range-supported		
All document attributes affecting the actual destination	document-attributes-supported ¹	document-attributes-supported		
This attribute applies only to actual destinations, not logical destinations.				

Table 22. Job and Destination Attributes Used for Validation and Scheduling

Job Attribute	Validation Attribute	Scheduling Attribute	
actual-destinations- requested	destination-name ²	destination-name	
auxiliary-sheet-selection	auxiliary-sheet-selections-supported	auxiliary-sheet-selections-supported	
destination-locations- requested	destination-locations	destination-locations	
destination-models- requested	destination-model	destination-model	
dss-requested	destination-support-system	destination-support-system	
job-batch		job-batches-ready	
job-end-message	end-message-supported	end-message-supported	
job-finishing	job-finishings-supported ¹	job-finishings-supported	
job-rip-action	job-rip-actions-supported ¹	job-rip-actions-supported	
job-start-message	start-message-supported	start-message-supported	
job-start-wait	job-start-wait-supported ¹	job-start-wait-supported	
total-job-octets	job-size-range-supported ¹	job-size-range-ready job-size-range-supported	
All job attributes affecting the actual destination	job-attributes-supported ¹	job-attributes-supported	
Checkpoint where the job was paused		checkpoint-formats-supported ³	

Table 22. Job and Destination Attributes Used for Validation and Scheduling (continued)

Job Attribute	Validation Attribute	Scheduling Attribute
---------------	----------------------	----------------------

- 1. This attribute applies only to actual destinations, not logical destinations.
- 2. This attribute applies to both logical destinations and actual destinations, but only the actual destination attribute is used for validation. If validation fails, Infoprint rejects the job even if the value of accept-unsupported-jobs is true.
- 3. This attribute is used to reschedule paused jobs.

Appendix D. Form Definitions and Page Definitions Supplied with Infoprint

This section describes the form definitions and page definitions that are supplied with Infoprint. Form definitions provide instructions on how printers position data on the page and are located in directory /usr/lpp/psf/reslib. Page definitions contain formatting controls for jobs and are also located in directory /usr/lpp/psf/reslib.

Default Form Definitions

Default form definitions are determined by the output data stream format accepted by the printer that Infoprint assigns to print the job:

Data Stream Default Form Definition

Intelligent Printer Data Stream (IPDS) F1ACIF
Personal Printer Data Stream (PPDS) F1PP0110
Printer Control Language 4 (PCL4) F1HP0111
PCL5 and PCL5C F1H50111

Table 23 describes the characteristics controlled by these form definitions.

Table 23. Default Form Definition Characteristics

Form Definition	Bin	Sides	Presentation Mode	Print Direction	Page Position (in inches from the top-left corner of the page)
F1ACIF	1	2	Portrait	Across	0.165, 0.165
F1PP0110	1	1	Portrait	Across	0.25, 0.165
F1HP0111	1	2	Portrait	Across	0.165, 0.2
F1H50111	1	2	Portrait	Across	0.165, 0.165

General-Purpose Form Definitions

You can specify different form definitions with jobs if the default form definitions do not satisfy your requirements. Table 24 lists the general-purpose form definitions that you can select.

Table 24. General-Purpose Form Definitions

Form Definition	Bin	Sides	Presentation Mode	Print Direction	Page Position (in inches from the top-left corner of the page)
F1A10110 ¹	1	1	Portrait	Across	0.165, 0.165
F1A10111 ¹	1	2	Portrait	Across	0.165, 0.165
F1A10112 ¹	1	Tumble	Portrait	Across	0.165, 0.165
F1A10120 ¹	2	1	Portrait	Across	0.165, 0.165
F1A10121 ¹	2	2	Portrait	Across	0.165, 0.165
F1A10122 ¹	2	Tumble	Portrait	Across	0.165, 0.165
F1A10130	3	1	Portrait	Across	0.165, 0.165
F1A10131	3	2	Portrait	Across	0.165, 0.165

Table 24. General-Purpose Form Definitions (continued)

Form Definition	Bin	Sides	Presentation Mode	Print Direction	Page Position (in inches from the top-left corner of the page)
F1A10132	3	Tumble	Portrait	Across	0.165, 0.165
F1A10140	4	1	Portrait	Across	0.165, 0.165
F1A10141	4	2	Portrait	Across	0.165, 0.165
F1A10142	4	Tumble	Portrait	Across	0.165, 0.165
F1A10150	5	1	Portrait	Across	0.165, 0.165
F1A10151	5	2	Portrait	Across	0.165, 0.165
F1A10152	5	Tumble	Portrait	Across	0.165, 0.165
F1ACIF ¹	1	2	Portrait	Across	0.165, 0.165
F1H50110 ²	1	1	Portrait	Across	0.165, 0.165
F1H50111 ²	1	2	Portrait	Across	0.165, 0.165
F1H50120 ²	2	1	Portrait	Across	0.165, 0.165
F1H50121 ²	2	2	Portrait	Across	0.165, 0.165
F1HP0110 ³	1	1	Portrait	Across	0.165, 0.2
F1HP0111 ³	1	2	Portrait	Across	0.165, 0.2
F1HP0120 ³	2	1	Portrait	Across	0.165, 0.2
F1HP0121 ³	2	2	Portrait	Across	0.165, 0.2
F1MG0110 ⁴	1	1	Portrait	Across	0.33, 0.33
F1MG0111 ⁴	1	2	Portrait	Across	0.33, 0.33
F1MG0120 ⁴	2	1	Portrait	Across	0.33, 0.33
F1MG0121 ⁴	2	2	Portrait	Across	0.33, 0.33
F1PP0110 ⁵	1	1	Portrait	Across	0.25, 0.165
F1PP0111 ⁵	1	2	Portrait	Across	0.25, 0.165
F1PP0120 ⁵	2	1	Portrait	Across	0.25, 0.165
F1PP0121 ⁵	2	2	Portrait	Across	0.25, 0.165

- 1. Designed for use with IBM 3820, 3827, and 3835 printers.
- 2. These form definitions are recommended for printer devices that support the PCL5 and PCL5C data streams. They position the page of data so that the data is not placed in the unprintable area.
- 3. These form definitions are recommended for printer devices that support the PCL4 and PCL5 data streams. They position the page of data so that the data is not placed in the unprintable area.
- 4. These form definitions are recommended for the message pages printed by Infoprint supported printers.
- 5. These form definitions are recommended for printer devices that support the PPDS data stream. They position the page of data so that the data is not placed in the unprintable area.

Form Definitions for Printing Envelopes

Use the form definitions in Table 25 to print envelopes and use the manual input bin on the IBM LaserPrinter 4028. You can use these form definitions with other printers that use bin 65 as the envelope bin and bin 100 as the manual feed bin.

Table 25. Form Definitions Supplied with Infoprint for Printing Envelopes

Form Definition	Bin	Sides	Presentation Mode	Print Direction	Page Position (in inches from the paper edge)
F1A000E0	Envelope	1	Landscape	Across	0, 0
F1A000M0	Manual	1	Landscape	Across	0, 0
F1A101E0	Envelope	1	Landscape	Across	0.165, 0.165
F1A101M0	Manual	1	Landscape	Across	0.165, 0.165

Form Definitions for 17 by 11 Inch Paper

Use the form definitions in Table 26 for jobs that require 17 by 11 inch paper.

Table 26. Form Definitions Supplied for 17 by 11 Paper

Form Definition	Bin	Sides	Presentation Mode	Print Direction	Page Position (in inches from the top-left corner of the page)		
F100LS	1, 2, 3, 4, 5	1	Landscape	Across	0, 0		
F100LD	1, 2, 3, 4, 5	2	Landscape	Across	0, 0		
F100LT	1, 2, 3, 4, 5	Tumble	Landscape	Across	0, 0		
F100LAND ¹	1, 2, 3, 4, 5	2	Landscape	Across	0, 0		
1. Used for N_UP of 1.							

Form Definitions Specifying a 0, 0 Offset

The form definitions in Table 27 specify a 0, 0 offset from the upper-left corner of the page. Use these form definitions if images or data in the job prints off-center or appears to be shifting on the page.

Table 27. Form Definitions Supplied with Infoprint Specifying a 0, 0 Offset

Form Definition	Bin	Sides	Presentation Mode	Print Direction	Page Position (in inches from the top-left corner of the page)
F100S	1, 2, 3, 4, 5	1	Portrait	Across	0, 0
F100D	1, 2, 3, 4, 5	2	Portrait	Across	0, 0
F100T	1, 2, 3, 4, 5	Tumble	Portrait	Across	0, 0
F1A00010	1	1	Portrait	Across	0, 0
F1A00011	1	2	Portrait	Across	0, 0
F1A00012	1	Tumble	Portrait	Across	0, 0
F1A00020	2	1	Portrait	Across	0, 0
F1A00021	2	2	Portrait	Across	0, 0
F1A00022	2	Tumble	Portrait	Across	0, 0
F1A00030	3	1	Portrait	Across	0, 0
F1A00031	3	2	Portrait	Across	0, 0
F1A00032	3	Tumble	Portrait	Across	0, 0
F1A00040	4	1	Portrait	Across	0, 0
F1A00041	4	2	Portrait	Across	0, 0
F1A00042	4	Tumble	Portrait	Across	0, 0
F1A00050	5	1	Portrait	Across	0, 0
F1A00051	5	2	Portrait	Across	0, 0
F1A00052	5	Tumble	Portrait	Across	0, 0

Form Definitions Specifying N_UP Page Positioning

The form definitions in Table 28 have various N_UP values and page placement. Refer to IBM Page Printer Formatting Aid: User's Guide more information about N_UP printing.

Table 28. Form Definitions for N_UP Page Positioning

Form Definition	Bin	Sides	N_UP	Page Placement	Presentation Mode	Print Direction	Page Position ¹
F1BOOK ²	1	2	2	Page 1 at 1 Front Page 2 at 2 Front Page 3 at 2 Back Page 4 at 1 Back	Portrait	Across	0, 0
F1N2SST1 ²	1, 2, 3, 4, 5	Tumble	2	Page 1 at 1 Front Page 2 at 1 Back Page 3 at 2 Front Page 4 at 2 Back	Portrait	Across	0, 0
F1N2SS11 ²	1, 2, 3, 4, 5	2	2	Page 1 at 1 Front Page 2 at 2 Back Page 3 at 2 Front Page 4 at 1 Back	Portrait	Across	0, 0
F1N2SS12 ²	1, 2, 3, 4, 5	2	2	Page 1 at 1 Front Page 2 at 2 Front Page 3 at 1 Back Page 4 at 2 Back	Portrait	Across	0, 0
F1N2SS13 ²	1, 2, 3, 4, 5	2	3	Page 1 at 1 Front Page 2 at 2 Front Page 3 at 3 Front Page 4 at 1 Back Page 5 at 2 Back Page 6 at 3 Back	Portrait	Across	0, 0
F1N20010	1	1	2	Default	Portrait	Across	0, 0
F1N20011	1	2	2	Default	Portrait	Across	0, 0
F1N20012	1	Tumble	2	Default	Portrait	Across	0, 0
F1N20110	1	1	2	Default	Portrait	Across	0.165, 0.165
F1N20111	1	2	2	Default	Portrait	Across	0.165, 0.165
F1N20112	1	Tumble	2	Default	Portrait	Across	0.165, 0.165
F1N20120	2	1	2	Default	Portrait	Across	0.165, 0.165
F1N20121	2	2	2	Default	Portrait	Across	0.165, 0.165
F1N20122	2	Tumble	2	Default	Portrait	Across	0.165, 0.165
F1N20130	3	1	2	Default	Portrait	Across	0.165, 0.165
F1N20131	3	2	2	Default	Portrait	Across	0.165, 0.165
F1N20132	3	Tumble	2	Default	Portrait	Across	0.165, 0.165
F1N20140	4	1	2	Default	Portrait	Across	0.165, 0.165
F1N20141	4	2	2	Default	Portrait	Across	0.165, 0.165
F1N20142	4	Tumble	2	Default	Portrait	Across	0.165, 0.165
F1N20150	5	1	2	Default	Portrait	Across	0.165, 0.165
F1N20151	5	2	2	Default	Portrait	Across	0.165, 0.165
F1N20152	5	Tumble	2	Default	Portrait	Across	0.165, 0.165
F1N201LA	1	1	2	Default	Landscape	Across	0.0, 0.5

Table 28. Form Definitions for N_UP Page Positioning (continued)

Form Definition	Bin	Sides	N_UP	Page Placement	Presentation Mode	Print Direction	Page Position ¹
F1N201LD	1	1	2	Default	Landscape	Down	0.0, 0.5
F1N201PA	1	1	2	Default	Portrait	Across	0.0, 0.5
F1N201PD	1	1	2	Default	Portrait	Down	0.0, 0.5

^{1.} Specified in inches from the top-left corner of the page.

Form Definitions for Printing on Prepunched Paper

Use the form definitions in Table 29 for jobs that require prepunched paper.

Table 29. Form Definitions for Prepunched Paper

Form Definition	Bin	Sides	Presentation Mode	Print Direction	Page Position (in inches from the top-left corner of the page)
F1H10110	1	1	Portrait	Across	1.000, 0.165
F1H10111	1	2	Portrait	Across	1.000, 0.165, 0.165, 0.165
F1H10112	1	Tumble	Portrait	Across	1.000, 0.165, 1.000, 0.165
F1H10120	2	1	Portrait	Across	1.000, 0.165
F1H10121	2	2	Portrait	Across	1.000, 0.165, 0.165, 0.165
F1H10122	2	Tumble	Portrait	Across	1.000, 0.165, 1.000, 0.165
F1H10130	3	1	Portrait	Across	1.000, 0.165
F1H10131	3	2	Portrait	Across	1.000, 0.165, 0.165, 0.165
F1H10132	3	Tumble	Portrait	Across	1.000, 0.165, 1.000, 0.165
F1H10140	4	1	Portrait	Across	1.000, 0.165
F1H10141	4	2	Portrait	Across	1.000, 0.165, 0.165, 0.165
F1H10142	4	Tumble	Portrait	Across	1.000, 0.165, 1.000, 0.165
F1H10150	5	1	Portrait	Across	1.000, 0.165
F1H10151	5	2	Portrait	Across	1.000, 0.165, 0.165, 0.165
F1H10152	5	Tumble	Portrait	Across	1.000, 0.165, 1.000, 0.165

^{2.} Used with printers that support enhanced N_UP values.

Form Definitions for Specific Models of IBM Printers

Use the form definitions in Table 30 with the IBM 3831 Page Printer, IBM 3835, and IBM 3900 Advanced Function Printers.

Table 30. Form Definitions Supplied for IBM 3831, 3835, and 3900 Printers

Form Definition	Printer Type Compatible with	Bin	Sides	Presentation Mode	Print Direction	Page Position ¹
F10GL ²	3800	1	1	Landscape	Across	0.0, 0.0
F10101LA	3800 wide forms	1	1	Landscape	Across	0.00, 0.50
F10101LD	3800 narrow forms	1	1	Landscape	Down	0.00, 0.50
F10101PA	3800 narrow forms	1	1	Portrait	Across	0.00, 0.50
F10101PD	3800 wide forms	1	1	Portrait	Down	0.00, 0.50
F1C10110 ³	Cut-sheet	1	1	Landscape	Down	0.165, 0.165
F1C10111 ⁴	Cut-sheet	1	2	Landscape	Down	0.165, 0.165
F1C10112 ⁴	Cut-sheet	1	Tumble	Landscape	Down	0.165, 0.165

- 1. Specified in inches from the paper edge.
- 2. Created using Overlay Generation Language (OGL). Positions sample overlays.
- 3. Designed for use with the IBM 3835 printer.
- 4. Designed for use with advanced function printers. Specify these form definitions when printing data that has been formatted for cut-sheet printers.

Use the form definitions in Table 31 with the IBM 3935 Advanced Function Printer and the IBM 3160 Advanced Function Printer.

Table 31. Form Definition Supplied for IBM 3935 and 3160 Printers

Form Definition	Bin	Sides	Presentation Mode	Print Direction	Page Position (in inches from the top-left corner of the page)
F1A1BIN2	2	1	Portrait	Across	0.165, 0.165
F1A1BIN3	3	1	Portrait	Across	0.165, 0.165
F1A1BIN4	4	1	Portrait	Across	0.165, 0.165
F1A1BIN5	5	1	Portrait	Across	0.165, 0.165

Page Definitions Supplied with Infoprint

Table 32 through Table 36 on page 732 list the page definitions that are supplied with Infoprint. The page definitions are grouped by the size of the paper on which the job prints.

Page Definitions for Letter-Sized Paper

Table 32. Page Definitions for Letter-Sized Paper

Page Definition	Printable Area (Width by Height, In Inches)	Print Lines per Page	Print Position: Down/Across	Recom- mended Font	Printing Direction	Page Presentation
P1A06462 1, 2	8.17 by 10.67	64 at 6.0 lpi	30/0	GT10	Across	Portrait
P1A08682 ³	8.17 by 10.67	86 at 8.2 lpi	24/0	GT12	Across	Portrait

- 1. This page definition is also valid for 9.5 by 11.0 inch continuous-form paper.
- 2. Designed for use with IBM 3812, 3816, 3820, 3825, 3827, 3835, 3900, 4028, 4224, and 4234 printers.
- 3. Designed for use with IBM 3820, 3827, and 3835 printers.

Page Definitions for A4-Sized Paper

Table 33. Page Definitions for A4-Sized Paper

Page Definition	Printable Area (Width by Height, In Inches)	Print Lines per Page	Print Position: Down/Across	Recom- mended Font	Printing Direction	Page Presentation
P1C09182 1	7.94 by 11.36	91 at 8.2 lpi	25/0	GT12	Across	Portrait
P1V0436B ²	10.67 by 7.11	43 at 6.1 lpi	30/0	GT10	Up	Landscape
P1V04863 1, 2	10.67 by 7.94	48 at 6.1 lpi	30/0	GT10	Down	Landscape
P1V0588B ²	10.67 by 7.11	58 at 8.2 lpi	24/0	GT12	Up	Landscape
P1V0598B ²	10.67 by 7.11	59 at 8.2 lpi	24/0	GT12	Up	Landscape
P1V0608B ^{2, 3}	10.67 by 7.11	60 at 8.5 lpi	24/224	GT15	Up	Landscape
P1V0618B ^{2, 3}	10.67 by 7.11	61 at 8.5 lpi	24/224	GT15	Up	Landscape
P1V06483 1, 2	10.67 by 7.94	64 at 8.2 lpi	24/0	GT12	Down	Landscape
P1V06683 1, 2, 3	10.67 by 7.94	66 at 8.5 lpi	24/224	GT15	Down	Landscape
P1X04763 ^{2, 4}	10.60 by 7.77	47 at 6.1 lpi	30/0	GT10	Down	Landscape

- 1. Designed to work with 3820, 3827, 3835 printers.
- 2. Designed to work for letter-sized and A4-sized paper.
- 3. The printable area is 9.74 by 7.94 inches because of the 224 logical unit offset in the "Print Position: Down/Across" column.
- 4. Designed for use with HPCL and PPDS data streams.

Page Definitions for Letter- and A4-Sized Paper with Multiple-Up of 2 and 4

Table 34. Page Definitions for Letter- and A4-Sized Paper with Multiple-Up of 2 and 4

Page Definition	Printable Area (Width by Height, In Inches)	Print Lines per Page	Print Position: Down/Across	Recom- mended Font	Printing Direction	Page Presentation
P1W1168B	10.67 by 7.11	58 at 8.2 lpi	Page 1 24/0 Page 2 24/1281	GT15	Up	Landscape
P1W1188B	10.67 by 7.11	59 at 8.2 lpi	Page 1 24/0 Page 2 24/1281	GT15	Up	Landscape
P1W120C2 1	7.94 by 10.67	60 at 12.0 lpi	Page 1 16/160 Page 2 1344/160	GT20	Across	Portrait
P1W12883 ¹	10.67 by 7.94	64 at 8.2 lpi	Page 1 24/0 Page 2 24/1281	GT15	Down	Landscape
P1W216FB	10.67 by 7.11	54 at 15.2 lpi	Page 1 16/48 Page 2 890/48 Page 3 16/1322 Page 4 890/1322	GT24	Up	Landscape
P1W220FB	10.67 by 7.11	55 at 15.2 lpi	Page 1 16/48 Page 2 890/48 Page 3 16/1322 Page 4 890/1322	GT24	Up	Landscape
P1W240F3 ¹	10.67 by 7.94	60 at 15.2 lpi	Page 1 16/48 Page 2 968/48 Page 3 16/1322 Page 4 968/1322	GT24	Down	Landscape

Page Definitions for Legal-Sized Paper

Table 35. Page Definitions for Legal-Sized Paper

Page Definition	Printable Area (Width by Height, In Inches)	Print Lines per Page	Print Position: Down/Across	Recom- mended Font	Printing Direction	Page Presentation
P1B0446B	13.67 by 7.34	44 at 6.0 lpi	30/0	GT10	Up	Landscape
P1B04963 ¹	13.67 by 8.17	49 at 6.0 lpi	30/0	GT10	Down	Landscape
P1B0608B	13.67 by 7.34	60 at 8.2 lpi	24/0	GT12	Up	Landscape
P1B06683 ¹	13.67 by 8.17	66 at 8.2 lpi	24/0	GT12	Down	Landscape
P1B08262 ²	8.17 by 13.67	82 at 6.0 lpi	30/0	GT10	Across	Portrait
P1B11082 ¹	8.17 by 13.67	110 at 8.2 lpi	24/0	GT12	Across	Portrait
P1R04763 ³	13.6 by 8.0	47 at 6.0 lpi	30/0	GT10	Down	Landscape

^{1.} Designed for use with IBM 3820, 3827, and 3835 printers.

^{2.} Designed for use with IBM 3812, 3816, 3820, 3825, 3827, 3828, 3835, 3900, 4028, and 4224 printers.

^{3.} Designed for use with HPCL and PPDS data streams.

Page Definitions for B4-Sized Paper

Table 36. Page Definitions for B4-Sized Paper

Page Definition	Printable Area (Width by Height, In Inches)	Print Lines per Page	Print Position: Down/Across	Recom- mended Font	Printing Direction	Page Presentation
P1D0556B	14.0 by 8.96	55 at 6.1 lpi	30/0	GT10	Up	Landscape
P1D06063 ¹	14.0 by 9.79	60 at 6.1 lpi	30/0	GT10	Down	Landscape
P1D0748B	14.0 by 8.96	74 at 8.2 lpi	24/0	GT12	Up	Landscape
P1D08083 ¹	14.0 by 9.79	80 at 8.2 lpi	24/0	GT12	Down	Landscape
P1D08462 1	9.79 by 14.0	84 at 6.0 lpi	30/0	GT10	Across	Portrait
P1D11382 ¹	9.79 by 14.0	113 at 8.2 lpi	24/0	GT12	Across	Portrait
1. Designed for use with IBM 3820, 3827, and 3835 printers.						

Glossary

This glossary provides definitions of specialized terms used by IBM Infoprint Control (Infoprint). This glossary does not define terms that are defined in non-technical dictionaries or that have no special meaning in information processing.

Sources and References

This glossary includes definitions from the following sources:

- Definitions reprinted from a published section of the International Organization for Standardization's (ISO) Vocabulary—Information Processing or from a published section of the ISO Vocabulary—Office Machines are identified by the symbol (I) following the definition.
- Definitions reprinted from working documents, draft proposals, or draft international standards of ISO Technical Committee 97, Subcommittee 1 (Vocabulary) are identified by (T), indicating that final agreement has not yet been reached among its participating members.
- Definitions from *Introduction to OSF DCE*, by Open Systems Foundation, published by Prentice-Hall, are identified by (OSF).
- Definitions from *Portable Operating System Interface (POSIX) System Administration Interface/Printing Standards Project* are identified by (P).
- Definitions from *Information* technology—Document printing application (DPA)—Part 1: Abstract-service definition and procedures are identified by (D).
- Definitions from AIX Version 4.1 Topic Index and Glossary are identified by (X).
- Definitions from *IBM Dictionary of Computing*.
- Definitions that are specific to IBM products are so labeled, for example, "in Infoprint", or "In DCE".

This glossary uses the following cross references:

Contrast with. This refers to a term that has an opposed or substantively different meaning.

Synonym for. This indicates that the term has the same meaning as a preferred term, which is defined in its proper place in the glossary.

Synonymous with. This is a backward reference from a defined term to all other terms that have the same meaning.

See. This refers you to multiple-word terms that have the same last word.

See also. This refers you to terms that have a related, but not synonymous, meaning.

Special Characters

.Guidefaults file. A file created by Infoprint in the home directory of a person using the Infoprint GUI. Infoprint uses this file to save and reference information about the servers you are monitoring and the windows you are working in.

Α

Access Control List (ACL). In computer security, a collection of all access rights for one object. In DCE. a list associated with each object in the namespace that specifies the access authorization level for each user or user group.

ACL. Access control list.

acl editor. A command line interface that allows you to view, add, update, and delete access authorization records in an ACL.

action. In the Infoprint GUI, an icon that represents an operation that you can perform on an Infoprint object. You drag and drop the action onto an object to initiate the operation for that object; for example, using the **Enable** action to enable a disabled actual destination.

actual destination. In Infoprint, an object that represents the output device that performs the printing or transmission function. See *email destination*, *fax destination*; see also *physical printer*, *printer device*; contrast with *logical destination*.

additive color system. A system that reproduces an image by mixing (adding) appropriate quantities of red, green, and blue light (the additive primary colors) to create all other colors of light, either direct or transmitted. When the additive primaries are superimposed on one another, they create white light. Contrast with *subtractive color system*.

administrator. In Infoprint, the person who creates and manages one or more components of a printing system, such as servers and actual destinations. By default, Infoprint gives administrators authorization to

perform some Infoprint operations and to access certain information that is not available to the operators or job submitters.

Adobe Acrobat. An Adobe software program that provides instant access to documents in their original format, independent of computer platform. With the Adobe Reader, you can view, navigate, print, and present any Portable Document Format (.pdf) file.

Adobe PageMaker. A desktop publishing program that produces PostScript documents.

Adobe PostScript Raster to Image Transform (RIP). See raster image processor (RIP).

ADSM/6000. Advanced Distributed Storage Manager.

Advanced Distributed Storage Manager (ADSM/6000). A program that provides storage management for archived files.

Advanced Function Common Control Unit (AFCCU). An IBM RISC-based control unit with code common to all printers that use the AFCCU.

Advanced Function Presentation (AFP). A set of licensed programs, together with user applications, that use the all-points-addressable concept to print data on a wide variety of printers or to display data on a wide variety of display devices. AFP includes creating, formatting, archiving, retrieving, viewing, distributing, and printing information.

Advanced Function Presentation data stream (AFP data stream). The printer data stream used for printing AFP data. The AFP data stream includes composed text, page segments, electronic overlays, form definitions, and fonts downloaded from the operating system to the printer. A presentation data stream that is processed in AFP environments. The AFP data stream includes MO:DCA-P-based data streams.

Advanced Interactive Executive (AIX). An operating system used with RS/6000 computers. The AIX operating system is IBM's implementation of the UNIX operating system.

AFCCU. Advanced Function Common Control Unit.

AFP. Advanced Function Presentation.

AFP data stream. Advanced Function Presentation data stream.

ainbe. The printer input/output backend program used by the PSF DSS to send jobs to printer devices. Depending on the incoming data stream of the job, the PSF DSS may have transformed the data stream of the job prior to the backend program sending it to the printer device.

AIX. Advanced Interactive Executive.

AIX-attached printer. A printer device, attached to an RS/6000 through the network or through a serial or parallel port, that receives jobs from an AIX print queue. In Infoprint, a PSF physical printer that represents an AIX-attached printer device. See also channel-attached printer, direct-attached printer, TCP/IP-attached printer, upload-SNA-attached printer, upload-TCP/IP-attached printer.

AIX destination support system. In Infoprint, the destination support system that communicates with the standard AIX print backend (piobe), or with certain variations of the rembak print backend, to print jobs.

AIX physical printer. In Infoprint, the object representing a printer device that uses the AIX destination support system.

aliasing. In a digitized image, the creation of diagonal lines by combining short, horizontal, and vertical line segments that approximate the path of the desired line.

all-points-addressability (APA). The capability to address, reference, and position text, overlays, and images at any defined point of the printable area of the paper or display medium.

alphameric. Synonym for alphanumeric.

alphanumeric. Pertaining to a character set containing letters, digits, and other symbols such as punctuation marks. Synonymous with alphameric.

AMPV. Average monthly print volume.

analog. Pertaining to a continuous variable sampling of information between two points that achieves an even smooth transition of photographic material.

analog color proof. An off-press color proof made from separation films.

anti-aliasing. The rendering of hard-edged objects so that they blend smoothly into the background. PhotoShop offers anti-aliasing when rasterizing an EPS file. Removing the jagged "stairstep" quality in diagonal lines produced on a computer screen by aliasing. This removal is affected by creating less densely shaded fields parallel to the diagonal line.

APA. All-points-addressability.

API. Application Program Interface.

Application Program Interface (API). The call interface between a client program and the procedures that implement the printing system, as defined by the specification. Clients use the API to access servers. (P)

architecture. The set of rules and conventions that govern the creation and control of data types such as text, image, graphics, font, fax, color, audio, bar code, and multimedia.

archiving. The transfer of digital information from an online system onto magnetic tape, floppy disk, compact disc, or other media for offline storage. The original copy is deleted from the online system. See also *retrieval*.

array inkjet. An ordered collection of multiple print heads used in an inkjet printer.

ASCII. American National Standard Code for Information Interchange. The standard code, using a coded character set consisting of 7-bit coded characters (8-bits including a parity check), that is used for information interchange among data processing systems, data communications systems, and associated equipment. The ASCII set consists of control characters and graphic characters.

asynchronous. Pertaining to two or more processes that do not depend upon the occurrence of specific events, such as common timing signals. (T) In Infoprint, occurring without a regular or predictable time relationship to a specified action. Contrast with *synchronous*.

attachment type. Defines the method by which a printer device is attached to the system from which it receives data. See *AIX-attached printer*, *channel-attached printer*, *TCP/IP-attached printer*, *direct-attached printer*, *upload-SNA-attached printer*, *upload-TCP/IP-attached printer*.

attribute. A defined characteristic of an object, such as the number of copies required of a job, or the document formats accepted by a physical printer.

attribute name. A string that identifies an attribute. Typically, in Infoprint attribute names consist of two or more words separated by hyphens.

attribute value. The element of an attribute that specifies the characteristics relating to the attribute.

authorization. In computer security, verification of the eligibility of a user to access an object.

authorized user. A person with the appropriate permissions to access an object or to issue a command.

automatic recovery. A function of printer logic that permits the printer to reprint a job if the job is misprinted or damaged or if a component has failed.

auxiliary sheet. In Infoprint, an object that represents a particular sheet of paper, blank or otherwise, that can precede a job, separate documents within a job, or follow a job.

auxiliary-sheet selections. A particular combination of start, separator, and end sheets that print with jobs on a particular printer device.

B

backend. In AIX, the program that is invoked by the **qdaemon** process to run a print or batch job. Synonymous with *backend program*.

backend program. Synonym for backend.

backlog. In Infoprint, the amount of time calculated by Infoprint that is required to print all of the jobs currently in a queue.

backspace. In Infoprint, the action used to back up and reprint pages in a job.

bar code. A code representing characters by sets of parallel bars of varying thickness and separation that are read optically by transverse scanning. In architecture, an array of parallel rectangular bars and spaces that together represent data elements or characters in a particular symbology. The bars and spaces are arranged in a predetermined pattern following unambiguous rules defined by the symbology.

BCOCA. Bar code object content architecture.

Bezier curves. A method of defining curves using anchor points, control handles, and tangent lines. The PostScript path passes through anchor points, and its approach direction is along the tangent lines that are controlled by the control handles. Many PC programs use this drawing method. Type 1 PostScript fonts are defined using Bezier curves.

binding. The cover and materials that hold a book together. See *edition binding*, *perfect binding*, *spiral binding*, *wire-o binding*. The process of applying the binding to a book. In Infoprint, assigning a job to an actual destination. See *early binding*, *late binding*. In DCE, pointers stored in a DCE cell that are used to connect clients to servers.

bitmapped. Pertaining to an image formed by a rectangular grid of pixels. Each pixel is assigned a value to denote its color. One-bit images are black and white; 8-bit images have 256 colors (or grays); 24-bit images have full color. CMYK images have 32 bits per pixel to encode 256 levels in each of four channels. Bitmapped images are also called raster images.

bleed. An extra amount of printed image that extends beyond the trim edge of the sheet. Bleed ensures that no white gap appears at the edge of the sheet.

boot. To prepare a computer for operating by loading an operating system.

BSD. Berkeley Software Distribution.

BSD destination support system. In Infoprint, the destinatin support system that generates a print command string that the shell runs to print jobs.

BSD physical printer. In Infoprint, the object representing a printer device that uses the BSD destination support system.

burn. In platemaking, an exposure. Burn is named because of the extremely bright ultraviolet lamps used to transfer images from film to plate. In photography, to lengthen the exposure time to increase the final density of print.

C

cathode ray tube (CRT). A vacuum tube in which a beam of electrons can be moved to draw lines or form characters or symbols on its luminescent (phosphor-coated) screen. CRTs are the heart of all modern computer display screens. Black and white displays have only white phosphor scanned by one electron beam, while color displays have RGB phosphors scanned by three beams.

CDE. Common Desktop Environment.

cell. Synonym for *DCE cell*.

Cell Directory Service. A DCE component that manages a database of information about resources within a cell.

channel-attached printer. A printer attached to an RS/6000 by cables, rather than through telecommunication lines. In Infoprint, a PSF physical printer that represents a channel-attached printer device. See also *AIX-attached printer*, *direct-attached printer*, *TCP/IP-attached printer*, *upload-SNA-attached printer*, *upload-TCP/IP-attached printer*.

child. See parent/child relationship.

choke. In color printing, an area whose dimensions have been reduced to avoid overlapping another color. Contrast with *spread*.

class. Synonym for object class.

clean. In Infoprint, an action used to remove all the jobs from specified servers, actual destinations, or queues, or all the jobs submitted to specified logical destinations.

CLI. Command Line Interface.

client. In Infoprint, the component of the print system that assembles a print request and submits the request to a server. The client generates the local ID numbers for each job, submits the jobs to the servers, and keeps track of where each user's jobs have been submitted. IBM Infoprint Control and IBM Infoprint Submit include clients; you can also install the IBM Infoprint Select clients on workstations.

CMY. Cyan, magenta, yellow.

CMYK. Cyan, magenta, yellow, black.

collator. In some printers, for example, the IBM InfoColor 70, a special-purpose hard drive disk array used to store RIPped files and later transfer them to the LED print heads for imaging.

color balance. The relative levels of cyan, magenta, and yellow channels in an image to produce accurate color rendition of an original image.

color correction. The adjustment of the color balance in an image to produce accurate color rendition of an original image. Color correction is used for two- or three-spot-color jobs.

color key. A color proof similar to Cromalin, but typically not laminated and not necessarily accurate in color. Color keys are used to verify that breaks or color assignments and traps have been made accurately.

Command Line Interface (CLI). A type of user interface where commands are specified on the command line. Contrast with *Graphical User Interface*.

Common Desktop Environment (CDE). A graphical user interface running on a UNIX operating system.

complex attribute. In Infoprint, an attribute that can have multiple values with each value containing multiple components.

constant data. Data that does not change between jobs and that is merged with variable data to produce personalized copies of documents. For example, a form letter (constant data) can be merged with a customer's name and address (variable data).

contextual help. A type of online help that provides specific information about each selectable object, menu choice, notebook tab, field, control and pushbutton in a window.

control strip. A strip of information that can be attached to a print job and used to measure registration and density.

Cromalin. The Dupont color proofing system. Four layers (CMYK) of light-sensitive material are exposed through final halftone negative films, then laminated together on an opaque backing to produce a color and trap-accurate final proof showing actual half-tone dot structure. Cromalin is sometimes called an analog proof.

crop. To remove unwanted areas of an image, usually indicated by crop marks on the original.

CRT. Cathode ray tube.

CTS. Cutter-trimmer-stacker.

cutter-trimmer-stacker (CTS). A post-processing device attached to a printer device and used for paper handling.

cyan, magenta, yellow (CMY). The subtractive primary colors.

cyan, magenta, yellow, black (CMYK). The four basic colors used in offset printing, as opposed to the three basic colors of light: red, green, and blue. Magenta, yellow, and cyan are the subtractive primaries. Black is addes to provide better density and to produce a true black.

ח

daemon. A program that runs unattended to perform a standard service. Some daemons are triggered automatically to perform their task; others operate periodically. Daemon processes generally provide service that must be available at all times to more than one task or user, such as sending data to a printer.

DAT. Digital audio tape.

DataBase 2/6000 (DB2*/6000). The component of the Infoprint Library that indexes data for easy retrieval.

data stream. All information (data and control commands) sent over a data link. A continuous stream of data that has a defined format. In Infoprint, pertaining to the incoming format of the job and the output format required by the printer device. Infoprint transforms the incoming format into the output format, as required. See also document format.

DB2*/6000. DataBase 2/6000.

DCE. Distributed Computing Environment.

DCE authority. The permission granted by DCE to access an object.

DCE cell. The basic unit of operation and administration in DCE. A group of DCE machines that work togetner and are administered as a unit. A cell represents a group of users, systems, and resources that typically have a common purpose and share common DCE services.

DCE login ID. The identifier of a person logging into DCE. DCE uses this ID to determine a user's authenticity and authorization levels for accessing and modifying data in the DCE cell.

DCE ticket. The time-limited DCE authority granted whenever a user logs into DCE. When the DCE ticket expires, the user must log into DCE again in order to access objects protected by DCE.

deadline. In Infoprint, a queuing technique where the next job assigned to the first position in the queue is

the one whose deadline is closest. Contrast with fifo (first-in-first-out), job-priority, longest-job-first, and *shortest-job-first.*

default document. In Infoprint, an object that represents default attribute values for a document within a job. Synonymous with initial value document.

default job. In Infoprint, an object that represents default attribute values for a job. Synonymous with initial value job.

default object. In Infoprint, a general term that refers either to an default document or an default job. Synonymous with initial value object.

default value. A value stored in the system that is used when no other value is specified.

delete. In Infoprint, an action used to delete default objects, jobs, logical destinations, actual destinations, or queues from the server.

desktop publishing. Performing print-related activities on a personal computer, including but not limited to layout, design, photo manipulation, creating fonts, editing text, color separation, scanning, and animation.

destination. See actual destination, logical destination.

destination support system (DSS). In Infoprint, the programs that an actual destination uses to communicate with the output device. Synonymous with device support system. See AIX destination support system, BSD destination support system, email destination support system, fax destination support system, PSF destination support system, 3170 destination support system.

device. An individual piece of equipment (hardware) that attaches to a computer, such as a printer device.

device address. The identification of an input or output device by its channel and unit number.

device driver. A file that communicates with a specific device such as a printer, disk drive, or display. An application that sends output to a device controls the actions of the device through the device driver. See printer driver.

device support system (DSS). Synonym for destination support system.

DFS. Distributed File Service.

digital. Pertaining to data represented by digits, sometimes with special characters and the space character.

digital audio tape (DAT). A high-capacity, low-cost megabyte bulk storage system used for archiving,

copying (for backup purposes), and transferring large files. Typical DAT units store 1.3 GB on inexpensive cassette tapes.

digital color proof. An off-press color proof made from a color printer attached to a computer.

digital printing. A filmless and plateless printing process in which digital data for each page is transferred directly to a light-sensitive drum and then to paper for a final image.

direct-attached printer. A printer device, attached to an RS/6000 through the network or through a serial or parallel port. In Infoprint, a PSF physical printer that represents a direct-attached printer device. See also AIX-attached printer, channel-attached printer, TCP/IP-attached printer, upload-SNA-attached printer, upload-TCP/IP-attached printer.

disable. In Infoprint, an action used to stop the acceptance of jobs on destinations, queues, or servers, or to stop writing information to logs.

Distributed Computing Environment (DCE). A software system from the Open Software Foundation (OSF). DCE provides the services that allow a distributed application to interact with a collection of possibly heterogeneous computers, operating systems, and networks as if they were a single system.

Distributed File System (DFS). A DCE component consisting of a single, integrated file system that is shared among all DCE users and host computers in a DCE cell. DFS allows users to access and share files stored in a network, without having to know the physical location of the files. It also prevents users from simultaneously modifying the same information.

distributed print system. A computer system with the ability to interchange print data and controls among different computing environments with the intent of printing the data on a different system from the one where the print request was generated. For example, in host-to-LAN distributed printing, data that resides on the host is printed on printers attached to a local area network.

dithering. A technique of filling the gap between two pixels with another pixel having an average value of the two to minimize the difference or add detail to smooth the result.

document. In Infoprint, an object representing a grouping of data within a job. A job can contain one or more documents. The documents in a job can differ from each other in some ways. For example, they can contain different data and can have different document formats. A document within a job can contain printable data or a resource that is not printable by itself. See *file-reference document, printable document*, and *resource document*.

document element. A portion of a document at least a single page in size.

document format. In Infoprint, a document format describes the type of the data and control characters in the document, such as line data or PostScript. The format of the data determines which printer devices are capable of printing the document and whether Infoprint must transform the format.

document identifier. A string that identifies a document within a job. It consists of a job ID followed by a period (.) and a document sequence number. For example, 12.2. Document sequence numbers are integers starting at 1.

Document Printing Application (DPA). An ISO/IEC 10175 standard that addresses those aspects of document processing that enable users in a distributed open systems environment to send electronic documents to shared, possibly geographically-dispersed printers. Infoprint supports the DPA standard.

document transfer method. In Infoprint, the transfer method describes how documents are transferred to, or acquired by, servers. See *pipe-pull* and *with-request*.

document type. In Infoprint, the document type describes the kind of data in the document. A *printable document* can only contain printable data. A *resource document* can only contain data such as fonts or form definitions that are not printable. A *file reference document* can only contain names of files entered on separate lines.

dot. The individual elements of a halftone.

dot gain. An increase in the size of a halftone dot during printing, caused by ink spreading. Generally, this value is known precisely, and the scanning and filming production process is calibrated to compensate for it. The Cromalin proofing system simulates this effect.

dots per inch (dpi). A measure of data density per unit distance. Typical values for desktop publishing work range from 200 to 300 dpi. Values for printing with the IBM InfoColor 70 range as high as 600 dpi.

DPA. Document Printing Application.

dpi. Dots per inch.

drag and drop. In graphical user interfaces, a procedure by which you perform actions and tasks. Using the mouse, you drag (move) an action or object icon to a new position where you want the action or task to occur.

DSS. Destination support system.

dummy. A rough paste-up or hand-drawn representation of the anticipated finished product. A dummy is used for basic design and pagination.

duplex printing. Printing on both sides of the paper. Contrast with *simplex printing* (1). Printing on both sides of the paper, placing output images on the media in a head-to-head format, so that the top of one image is at the same edge as the top of the next image. Contrast with *tumble duplex printing*; see also *simplex printing* (2).

E

early binding. In Infoprint, assigning a job to an actual destination as soon as it is accepted. Early binding permits Infoprint to estimate the time when the job will be completed. Contrast with *late binding*.

edition binding. A type of book binding in which printed sheets are folded into 16- or 32-page signatures. Four-page endleaves are pasted on the outside of the first and last signature. The signatures are then collated by machine and sewn together using special sewing machines. Contrast with *perfect binding*, *spiral binding*, *wire-o binding*.

electronic document. A document stored in a computer instead of printed on paper.

electronic mail. Correspondence in the form of messages transmitted between workstations over a network. Synonymous with *email*.

electrophotographic. Pertaining to a type of printer technology that creates an image on paper by uniformly charging the photoconductor, creating an electrostatic image on the photoconductor, attracting negatively charged toner to the discharged areas of the photoconductor, and transferring and fusing the toner to paper.

em. In composition, a unit of measurement exactly as wide and as high as the point size of the font being set. The name is derived from the fact that the letter M in early typefaces was usually cast on a square body.

email. Electronic mail.

email destination. In Infoprint, an actual destination representing an electronic mailing system.

email destination support system. In Infoprint, the destination support system that supports email destinations.

embellishments. Variable data added to all copies of assembled pages to make the unit seem like a whole; for example, headers, footers, page numbers, a table of contents, and chapter separations.

en. In composition, exactly one half an em.

enable. In Infoprint, the action that makes a destination, queue, or server able to accept jobs, or a log able to accept information.

end sheet. The sheet of paper, blank or otherwise, that can follow a job. See also *auxiliary sheet*.

Enhanced X-Windows. A tool designed to permit multiple application processes to operate within multiple windows displayed on a virtual terminal. See *X-Windows*.

environment variable. Any one of a number of variables that describe the way an operating system runs and the devices it recognizes.

error log. A data set or file in a product or system where error information is stored for later access.

estimate. The professional cost analysis made by a print shop in response to a customer's request for a price quotation on a print job.

event. In Infoprint, an occurrence in the printing system during an operation; for example, the completion of a command.

event log. In Infoprint, a collection of messages about events that have occurred.

event notification. The notification that is sent by Infoprint for an event.

extensions. An IBM program-provided software component that enables users to incorporate variable data into fixed-text documents to produce personalized or customized documents.

F

fax destination. In Infoprint, an actual destination representing a fax device.

fax destination support system. In Infoprint, the destination support system that supports fax destinations.

FIFO (first-in-first-out). In Infoprint, a queuing technique where the next job assigned to the first position in the queue is the job that has been in the queue for the longest time. Infoprint processes jobs in the order in which they are received. Contrast with *deadline*, *job-priority*, *longest-job-first*, and *shortest-job-first*.

file-reference document. In Infoprint, a file containing the names of other files, each entered on a separate line. Job submitters can specify this file for printing when they specify a document type of **file-reference**. Infoprint prints each file listed in the reference document.

File Transfer Protocol. In TCP/IP, the application protocol that makes it possible to transfer data to and from host computers and to use foreign hosts indirectly.

finisher. A hardware device attached to a printer that performs such operations as folding or stapling the printed page.

finishing. In a print shop, the final operations on a printed product, such as stapling, trimming, drilling, folding, embossing, varnishing, gluing, shrink wrapping, perforating, laminating, collating, and so on.

flag. A modifier of a command that specifies the action of the command. A dash usually precedes a flag. Synonymous with *option*. See also *keyword*.

FOCA. Font object content architecture.

folder. In the Infoprint GUI, an object that represents a container for a collection of similar objects. For example, the Retained Jobs folder contains retained jobs.

font. A family of characters of a given size and style; for example, 9-point Helvetica. One size and one typeface in particular type family, including letters, numerals, punctuation marks, special characters, and ligatures. A paired character set and code page that can be used together for printing a string of text characters. A double-byte font can consist of multiple pairs of character sets and code pages.

form definition. A resource object used by Infoprint that defines the characteristics of the form or printed media, which include: overlays to be used, the paper source (for cut-sheet printers), duplex printing, text suppression, and the position of composed-text data on the form.

forward space. In Infoprint, the action used to move ahead and skip the printing of a specified number of pages in a job.

FPO. Low-quality (sometimes photographic) images placed in a dummy to represent final images. Desktop publishing software produces images as display-screen resolution FPOs.

front panel. In the CDE, a workspace area containing controls that represent various tasks you can perform and workspace switches. In basic Infoprint installations, the front panel has been customized for Infoprint.

FTP. File Transfer Protocol.

G

GCR. Gray component replacement.

GIF. Graphics Interchange Format.

global change. In the Infoprint GUI, an action used to make changes to one or more attributes of several objects at once. You can also perform the same action on several objects of the same object class at the same time; for example, disabling two or more actual destinations at the same time.

global character. A character or set of characters used to specify an unknown number or set of characters in a search string. In Infoprint, a global character is represented by an asterisk (*).

global ID. Global job identifier.

global job identifier. An unambiguous job identifier. In Infoprint, it is represented as the name of the server managing the job followed by a colon (:) and a generated integer. This ID uniquely identifies the job within the Infoprint server.

glyph. An image, usually of a character, in a font.

GOCA. Graphics object content architecture.

graphic character. A visual representation of a character, other than a control character, that is normally produced by writing, printing, or displaying.

Graphical User Interface (GUI). A type of user interface that takes advantage of a high-resolution monitor and includes a combination of graphics to implement an object-action paradigm, the use of pointing devices, menu bars, overlapping windows, and icons. Contrast with *Command Line Interface*.

Graphics Interchange Format (GIF). A compresses graphics format widely used on the Internet.

gray component replacement (GCR). Synonym for *under color removal (UCR).*

gray scale. A strip of standard gray tones, ranging from white to black, placed at the side of the original copy during photography to measure the tonal range and contrast obtained.

GUI. Graphical User Interface.

gutter. The blank area or inner margin from the printing area to the binding.



halftone. A printing method that simulates continuous-tone shading using dots of varying sizes laid out on a regular grid. Larger dots simulate darker tones and smaller dots simulate lighter tones. Typical grid spacings are 85 lines per inch (lpi) (newspaper), 133 lpi (low end), 150 lpi (midrange), and 175+ lpi (high quality).

help. In the Infoprint GUI, an action used to display the online help for a specific template, object, action,

button, control or area in an application window. The name of a button used to access the online help.

hold. An indication determined by the **job-hold** attribute that is used to keep a job in the queue and prevent Infoprint from scheduling it.

hostname. The name given to an AIX system.

hot folder. A workstation directory where users copy jobs to submit them to print.

hypertext. A way of presenting information online with connections between one piece of information and another. These connections are called hypertext links. See also *hypertext link*.

hypertext link. A connection between one piece of information and another. Selecting a link displays the target piece of information.

IBM InfoColor 70. A duplex, process color, web-fed printer with 600 dpi pel resolution.

IBM Infoprint. A solution of software and hardware products that can supplement or replace the offset presses and copiers in print shops with high-quality, non-impact, black and white, or process color printers. Infoprint takes documents from creation to the published, kitted, and shipped product.

IBM Infoprint Control. The administration and management component of Infoprint Manager It runs on AIX and provides a complete set of system administrator and operator functions to control all aspects of a print environment, as well as job submitter printing functions to submit and control jobs.

IBM Infoprint Library. A component of Infoprint Manager. IBM Infoprint Library is a document archival and retrieval system in which job tickets and their associated resource files (graphics, fonts, images, and PostScript data) are stored and from which these data types can be retrieved for reuse.

Infoprint Manager. The software component of IBM Infoprint. Infoprint Manager handles the scheduling, archiving, retrieving, and assembly of a print job and its related resource files. It also tracks the finishing and packaging of the printed product.

Infoprint is based on Palladium technology developed at MIT/Project Athena. It conforms to the ISO DPA and POSIX standards.

IBM Infoprint Network. The local area network running TCP/IP protocol that InfoPrint uses to communicate among servers, clients, and output devices.

IBM Infoprint Scan. The component of Infoprint Manager that allows users to scan images as TIFF files to be included in jobs submitted by Infoprint Submit from a Windows workstation.

IBM Infoprint Select. The component of Infoprint Manager that allows users to submit jobs from an OS/2 or Windows workstation.

IBM Infoprint Submit. The component of Infoprint Manager that allows users to submit jobs with a job ticket from a Windows or Macintosh workstation.

IBM Infoprint 20. A black and white, large-format, cut-sheet workgroup laser printer with optional duplexing and 600-dpi resolution.

IBM Infoprint 4000. A duplex, black and white, continuous-forms printer with 600-dpi resolution.

IBM Infoprint 60. A duplex, black and white, cut-sheet printer with 600-dpi resolution.

icon. A graphic symbol displayed on a screen that a user can select to invoke a function or software application.

image. Toned and untoned pels arranged in a pattern.

image data. Rectangular arrays of raster information that define an image.

imagesetter. A high resolution (1270 dpi–3600+ dpi) printer that uses an Argon (green) laser to write to film using digital input. Imagesetting is the step before Cromalin proofing and platemaking.

imposition. The process of arranging pages on a press sheet to ensure the correct order during final cutting, folding, and binding. Electronic imposition builds press sheets automatically during the RIP and outputs film formatted for immediate use in platemaking.

Infoprint. IBM Infoprint In IBM Infoprint software publications, Infoprint Manager or any of its components, especially IBM Infoprint Control.

initial value document. Synonym for default document.

initial value job. Synonym for default job.

initial value object. Synonym for default object.

initially settable attribute. An attribute whose value can be established when an object is created but cannot be subsequently set or modified. See also *resettable* attribute; contrast with *non-settable attribute*.

input focus. The area of a window where user interaction is possible from either the keyboard or the mouse.

input tray. For a printer device, the container that holds the medium upon which the printer prints its output.

Intelligent Printer Data Stream (IPDS). An all-points-addressable data stream that enables users to position text, images, and graphics at any defined point on a printed page. Information that the host sends to IBM IPDS printers. This information generally contains basic formatting, error recovery, and character data and enables the printers to make decisions. An architected host-to-printer data stream that contains both data (text, image, graphics, and bar codes) and controls defining how the data is to be presented. IPDS provides a device-independent interface for controlling and managing all-points-addressable (APA) printers.

International Organization for Standardization (ISO).

An organization of national standards bodies from various countries established to promote development standards to facilitate international exchange of goods and services, and develop cooperation in intellectual, scientific, technological, and economic activity.

Internet. A wide area network connecting thousands of disparate networks in industry, education, government, and research. The Internet network uses TCP/IP as the protocol for transmitting information.

Internet Protocol. The set of rules that determines how to route data from its source to its destination in an Internet environment.

intervening jobs. In Infoprint, the number of jobs in a queue that are scheduled to print before the job in question.

IOCA. Image object content architecture.

IP address. The Internet Protocol address of the server in a dotted decimal format where each node is an integer. (For example, 9.99.9.143).

IPDS. Intelligent Printer Data Stream.

ISO. International Organization for Standardization.

J

job. In Infoprint, an object that represents a request to print or transmit one or more documents together in a single printing session. A job includes the data to be printed or transmitted and resources such as fonts, images, and overlays. Depending on how it was submitted, it may also include a job ticket. Synonymous with *job bundle*, *print job*.

job bundle. Synonym for *job*.

job data. The page descriptions, merge data, and embellishments that compose a document in a job, either directly or by reference.

job ID. A local or a global identifier that identifies a job to a job submitter, administrator, operator, or Infoprint. See *local job identifier*, *global job identifier*.

job-priority. In Infoprint, a queuing technique where the next job assigned to the first position in the queue is the one with the highest priority. Contrast with *deadline*, FIFO (*first-in-first-out*), *longest-job-first*, and *shortest-job-first*.

job submitter. In Infoprint, the person who submits jobs for printing. Often, this person is an application programmer who maintains applications that generate data to be printed.

job ticket. The customer's hardcopy or electronic instructions listing all the variables describing a print job, either directly or by reference. The print shop can add specifications to the job ticket and can print the job ticket.

Joint Photographic Experts Group (JPEG). A compressed graphics format widely used on the Internet.

JPEG. Joint Photographic Experts Group.

K

kerning. In typesetting, adjusting the relative spacing of two characters to improve their appearance and readability. Kerning pairs are specific sets of characters with built-in relative spacing. Some typefaces have as many as 100 kerning pairs.

keyword. A name or symbol that identifies a parameter. Part of a command operand that consists of a specific character string, such as **DSNAME=**.

kitting. In the print shop environment, packaging the completed published work with attendant binders, tabs, diskettes, and other equipment or information, before shipping the finished product.

LAN. Local Area Network.

laser (light amplification by stimulated emission of radiation). In IBM printers, a devices that emits a beam of coherent light that forms the image on the photoconductor that is subsequently transferred to the paper.

late binding. In Infoprint, waiting to assign a job to an actual destination until it is about to be processed. Late binding permits Infoprint to route a job to the first suitable actual destination that becomes available. Contrast with *early binding*.

LED. Light-emitting diode.

light-emitting diode (LED). The imaging device element for electrophotographic print units.

lines per inch (lpi). A measure of the density of the grid used to space halftone dots. Typical grid spacings are 85 lpi (newspaper), 133 lpi (low end), 150 lpi (midrange) and 175+ lpi (high quality).

Local Area Network (LAN). A computer network at one location that consisting of devices connected to one another and communicating. This network can also be connected to a larger network.

local ID. Local job identifier.

local job identifier. In Infoprint, a job identifier automatically generated by the server, identifying the job to the person who submitted it. Infoprint maps a local job ID to a global job ID.

locale. The human language and character set of information presented to a user. In Infoprint, the language Infoprint uses when sending notification and error messages or displaying the Infoprint graphical user interfaces.

log. A collection of messages or message segments added to a file for accounting or data collection purposes. To record messages in a file.

logical destination. In Infoprint, an object to which users submit their jobs. The destination routes jobs to one or more actual destinations representing output devices such as printers, electronic mail systems, or fax machines. See also *logical printer*; contrast with *actual destination*.

logical printer. In Infoprint, a type of logical destination. The logical printer routes jobs to one or more physical printers representing printing devices.

logical unit (LU). A type of network accessible unit that enables end users to gain access to network resources and communicate with each other.

logical unit (LU) 6.2. A type of logical unit that supports general communication between programs in a distributed processing environment. LU 6.2 is characterized by (a) a peer relationship between session partners, (b) efficient utilization of a session for multiple transactions, (c) comprehensive end-to-end error processing, and (d) a generic application program interface (API) consisting of structured verbs that are mapped into a product implementation.

longest-job-first. In Infoprint, a queuing technique where the next job assigned to the first position in the queue is the longest job in the queue. Contrast with *deadline*, FIFO (*first-in-first-out*), *job-priority*, and *shortest-job-first*.

lpi. Lines per inch.

LU. Logical unit.

M

magnetic-ink character recognition (MICR). Identification of characters printed with ink that contain particles of magnetic material.

mainframe processor. A functional unit that interprets and executes instructions in a large computer to which other computers are connected so that they can share the facilities the mainframe provides.

makeready. All the setup work involved in preparing a press for a print run.

manage. In the Infoprint GUI, the action used to put an object into a mode where its icon reflects changes of status.

mechanical. A camera-ready layout. The mechanical can consist of multiple sheets or overlays for each spot or process color used. Final images, if not stripped in later, should be at final size, cropped and screened to the correct final-line frequency.

medium. In Infoprint, an object representing the physical material upon which a job is printed.

merge data. Data that is unique to each copy of a document and that customizes the document; for example, serial numbers or mailing information. Merge data is typically a small percentage of the total data in a document.

message catalog. A file of all the possible messages than can display during the processing of an application.

MICR. Magnetic ink character recognition.

Mixed Object Document Content Architecture (MO:DCA). An architected, device-independent data stream for interchanging documents.

MO:DCA-P. Mixed Object Document Content Architecture Presentation.

modify. In Infoprint, an action used to modify the values of attributes within the object attributes notebook.

moire. Undesirable interference patterns caused by two overprinting halftone screens with incorrect halftone dot angles.

monospaced. In typesetting, a typeface in which all the characters have equal widths. Monospaced typefaces are useful for tabulating figures.

Multiple Virtual Storage (MVS). An operating system developed by IBM. The design of MVS incorporates an

addressing architecture that provides a unique address space to each job in the system.

MVS. Multiple Virtual Storage.

Ν

N_UP. Pertaining to the number of forms placed together in a layout. Typical layouts are 2_UP, 4_UP, 8_UP, 16_UP, and so on. N_UP printing is done to use the maximum area of the print sheet.

name service. The DCE service that administers the namespace and provides the network binding information that a client requires to access the server.

namespace. A global name repository available to all utilities and API procedures. The namespace contains mappings of object names to other related objects. For example, the namespace provides the mapping of a logical destination to the server in which it resides.

Network File System (NFS). A protocol developed by Sun Microsystems that uses Internet Protocol to allow a set of cooperating computers to access each other's file systems as if they were local.

newline options. The different ways in which the printer determines how lines are delimited in a document data stream.

NFS. Network File System.

non-process-runout (NPRO). A printer function that moves the last printed sheet to the stacker of the printer device.

non-settable attribute. An attribute that is neither initially settable nor resettable. The values for these attributes are controlled by Infoprint. Contrast with initially settable attribute, resettable attribute.

notification. The act of reporting the occurrence of events. In Infoprint, notification of events appears as messages in event logs or messages sent to administrators, operators, and job submitters. In the Infoprint GUI, notification of events also appears as changes to the appearance of icons.

notification-profile. In Infoprint, an attribute associated with an object that contains information designating the people to whom Infoprint sends notification about events for that object, which event information it sends, and how it sends the information.

NPRO. Non-process-runout.

object. A collection of attributes that represent a physical or logical entity in the print system. For example, a specific printer device is represented by an actual destination (physical printer) object. An object is identified by its object name. Objects are grouped into classes. See also object class.

object class. A group of objects that share a common definition and therefore share common properties, operations, and behavior as defined by their attributes. For example, all Infoprint queue objects are in the same object class and each queue has the same set of queue attributes. However, the values for those attributes can differ for each queue within the queue object class.

Object Identifier (OID). In architecture, a notation that assigns a globally unambiguous identifier to an object or a document component. The notation is defined in international standard ISO.IEC 8824(E).

object name. The alphanumeric term that identifies an object.

object state. The state of an object indicates its availability and readiness for performing its functions. An object can be in one of a number of states such as ready, busy, or unknown.

OCR. Optical character recognition.

octet. A byte that consists of eight binary digits (bits).

offset stacking. In certain printer devices, a function that allows the printer to offset the printed output pages for easy separation of the jobs.

OID. Object Identifier.

open destinations window. In the Infoprint GUI, the action used to open a new application window displaying the logical and actual destinations associated with a queue.

Open Prepress Interface (OPI). An industry standard for replacing low-resolution images in review documents with high-resolution images needed for high-quality final output.

Open Software Foundation (OSF). A nonprofit research and development organization created by a consortium of companies that work together to develop software in the open systems market. OSF developed the Distributed Computing Environment (DCE).

open window. In the Infoprint GUI, the action used to open a new application window representing one or more objects displayed in the currently open application window.

operation. An action performed on one or more data items.

operator. In Infoprint, the person responsible for printer devices. Also, this person performs a subset of tasks for Infoprint queues and actual destinations, and performs some job-related tasks.

OPI. Open Prepress Interface.

optical character recognition (OCR). Conversion of scanned text to editable ASCII characters.

option. A modifier of a command that specifies the action of the command. A dash usually precedes an option. Synonymous with *flag*. See also *keyword*.

orphan logical destination. In the Infoprint GUI, an object that represents a logical destination that is not associated with an existing queue.

orphan logical printer. In the Infoprint GUI, an object that represents a logical printer that is not associated with an existing queue.

OSF. Open Software Foundation

overlay. A collection of constant data, such as lines, shading, text, boxes, or logos, that is electronically composed in the host processor and stored in a library, and that can be merged with variable data during printing.

P

PAC. Privilege Attribute Certificate.

page definition. A resource that contains the formatting controls for line data. In Infoprint, a resource that defines the rules of transforming line data into composed pages and text controls.

page segment. A resource that contains composed text and images, prepared before formatting and included during printing.

Palladium. A distributed print system developed at MIT/Project Athena with participation from Digital Equipment Corporation (DEC), International Business Machines (IBM), and Hewlett-Packard (HP). It is a reference implementation for the OSI Document Printing Architecture (DPA) standard, ISO/IEC 10175. Infoprint was designed using Palladium concepts.

pane. In the Work Area of the Infoprint administrator's GUI, an area containing a group of objects of a specific type, such as an actual destinations pane.

parent/child relationship. In Infoprint, servers, queues, and destinations are related to one another in a parent/child relationship. For example, a server is the parent of all the queues that reside in that server and these queues are its children.

pass through. In Infoprint, referring to options submitted with a job that are used by the device driver, but not Infoprint. Infoprint does not process or validate this information; it passes it along to the device driver. See *device driver*.

path. The route used to locate files; the storage location of a file. A fully qualified path lists the drive identifier (if any), directory name, subdirectory name (if any), and file name with the associated extension.

pause. In Infoprint, the action used to temporarily halt the printing of jobs on physical printers or the distribution of jobs from servers or queues.

pdcrcds. In Infoprint, a utility used to create directories within the DCE namespace.

pdcreate. In Infoprint, the command used to create a new object and set its attributes to specified values.

PDF. Portable Document Format. Printer description file.

pdmsg. In Infoprint, a utility used to display information about a message.

pdpr. In Infoprint, the command used to create and submit a job, consisting of one or more documents, to a server for printing or transmission.

perfect binding. A type of book binding in which the pages are held together with flexible adhesive. Contrast with *edition binding*, *spiral binding*, *wire-o binding*.

permissions. In AIX, codes that determine who can access a file and what operations they can perform on the file

physical printer. In Infoprint, a type of actual destination that represents a printer device. See also *printer device*.

piobe. The standard printer input/output backend program used by AIX for printing. See also *ainbe*.

pipe-pull. In Infoprint, a document transfer method where Infoprint saves the documents in a file and transfers the address of the file to the server. Infoprint transfers the file to the server upon the request from the server. This is an efficient transfer method for large jobs and is the default transfer method at job submission. Contrast with *with-request*.

plex. A document or actual destination attribute used to define the placement of output images on the page. See the plex values *simplex* and *tumble*.

plug-ins. A component of Adobe PageMaker that enables users to incorporate variable data into fixed-text documents to produce personalized or customized documents.

Portable Document Format (PDF). An Adobe PostScript data format that can be viewed or printed.

Portable Operating System Interface for Computer Environments (POSIX). An Institute of Electrical and Electronics Engineers (IEEE) standard for computer operating systems.

POSIX. Portable Operating System Interface for Computer Environments.

PostScript. Adobe's page-description language. PostScript has become a standard for graphic design and layout software. PostScript files can contain both vector and raster data. Fonts are described using PostScript coding. Many desktop publishing systems produce PostScript data as their output data stream.

PostScript printer description (PPD). A file that contains options for printing PostScript data on various printer devices.

PPD. PostScript printer description.

preflight. To assess all resources for a job before the actual print run.

prepress. Work done in the print shop before printing a job, such as preparing data and art, page imposition, color retouching, electronic editing, and page layout.

print database. The set of files on disk which provide a permanent repository for the attributes of all print objects such as logical destinations, queues, and actual destinations.

print job. Synonym for *job*.

Print Quality Enhancement (PQE). A printer facility that provides edge smoothing along diagonal lines, fine fidelity protection, and independent boldness control.

Print Services Facility (PSF). Any of several programs, including PSF for AIX, PSF/MVS, PSF/VM, and PSF/VSE, that produce printer commands from the data sent to them.

print system. A group of one or more print servers and one or more printing devices, which may or may not be located in the same geographical area. The components of a print system are assumed to be interconnected in some manner, providing at least one network interface to print clients, and acting synergistically to supply the defined document print service. (D)

printable document. In Infoprint, an object that represents text or data to be printed by a job. Contrast with *resource document*.

printer description file (PDF). A file that contains options for printing PostScript data on a specific printer device.

printer device. The physical output device that performs the printing function. See also *physical printer*.

printer driver. A file that describes the physical characteristics of a printer or other peripheral device, and is used to convert graphics and text into device-specific data at the time of printing or plotting. Synonymous with *device driver*.

priority. In Infoprint, a number assigned to a job that determines its precedence in being printed. Jobs with higher priority numbers are handled before jobs with lower priority numbers.

Privilege Attribute Certificate (PAC). In DCE, a certified set of access privileges that can be presented by a user or administrator to establish access rights to objects.

process color. Color made up of CMYK inks simulating a specified color. This is the traditional method of reproducing continuous tone color images (color separations). Because of the nature of color inks, certain inks do not reproduce well.

processor. In a computer, a functional unit that interprets and executes instructions. A processor consists of at least an instruction control unit and an arithmetic and logic unit. (T)

promote. In Infoprint, an action used to advance a queued job to the beginning of the queue so it will print on the next available printer that can handle that job.

protocol. A set of semantic and syntactic rules that determines the behavior of functional units in achieving communication.

PSF. Print Services Facility.

PSF destination support system. In Infoprint, the destination support system that communicates with PSF for AIX to print jobs.

PSF physical printer. In Infoprint, the object representing a printer device that uses the PSF destination support system.

Q

QuarkXpress. A desktop publishing system produced by Quark, Incorporated.

queue. In Infoprint, an object that manages a collection of jobs that are waiting to print. A queue receives jobs from one or more logical destinations and sends jobs to one or more actual destinations. A line or list formed by items waiting for processing.

R

raster. A pattern of dots comprised of varying data depths. Black and white images are one-bit (on/off); grayscale images are 8-bit (256 levels); RGB images are 24-bit; CMYK images are 32-bit.

raster image processor (RIP). A processor in which a PostScript data stream is converted into dot patterns that are transferred to the final print medium. Infoprint

uses an Adobe RIP to convert PostScript to IPDS for such printers as the IBM Infoprint 4000 and IBM Infoprint 60.

rc.pd. In Infoprint, a utility used to start the Infoprint servers listed in the **/etc/pd.servers** file.

read-only. In Infoprint, describes an attribute value that cannot be set by the user but may change based on other activity.

ready. A state in which an object is ready and able to perform tasks. An available resource, such as a value of the **media-ready** attribute. Contrast with *supported*.

red, green, blue (RGB). The colors of CRT display phosphors. RGB images are for screen display only. They must be converted to CMYK images before printing.

registration. The accuracy of printing on paper relative to the edges of the paper. The accuracy of printing a single color (cyan, magenta, or yellow) relative to black. The accuracy of printing on one side of a page relative to printing on the reverse side of the page.

Remote Procedure Call (RPC). A DCE component that manages communication between clients and servers in a DCE environment. It allows requests from a client program to access a procedure anywhere in the network.

reprographics. The process of copying or duplicating documents or information.

requested. In Infoprint, pertaining to the specific values of attributes requested by a job when it is submitted. The requested attribute values of a job are validated against supported attribute values for a physical printer to determine if the printer can handle that job. Contrast with *supported*.

resettable attribute. An attribute whose value can be set or modified after an object has been created, assuming the object is in an appropriate state to be modified. See also *initially settable attribute*; contrast with *non-settable attribute*.

resource. In AFP, a file containing a collection of printing instructions used when printing a job. Resources include fonts, overlays, form definitions, page definitions, and page segments.

resource context. In Infoprint, an object that contains directory path information that helps the print system locate resources needed for printing a job. The resources include fonts, overlays, form definitions, page definitions, and page segments.

resource document. In Infoprint, an object that represents a resource, such as graphics or fonts, used by a job to print a printable document. Contrast with *printable document*.

resubmit. In Infoprint, an action used to reroute pending or retained jobs to a different logical destination than the one through which the job was originally submitted.

resume. In Infoprint, the action used to resume the printing of paused jobs or resume the distribution of jobs from paused servers or queues.

retained job. In Infoprint, an object that represents a job that is being stored in the print system, normally after the completion of printing the job, for a specified amount of time. A retained job does not reside in a queue.

retention. The process of storing data after completion of a process for a certain length of time.

retrieval. The process of bringing digital archived data out of storage and into online memory for reuse. See also *archiving*.

RGB. Red, green, blue.

RIP. Raster image processor. To convert data to dot patterns using a raster image processor.

root user. In the AIX environment, the system user with the most authority who can log in and execute restricted commands, shut down the system, and edit or delete protected files. Synonymous with *superuser*.

RPC. Remote Procedure Call.

RS/6000. A family of workstations and servers based on IBM's POWER architecture. They are primarily designed for running multi-user numerical computing applications that use the AIX operating system.

S

scanner. A device that converts hardcopy source data into digital format (halftone dots) to avoid retyping the data

scheduler. In Infoprint, the scheduling method that the queue uses when assigning a job to an actual destination.

separator sheet. The sheet of paper, blank or otherwise, that separates documents within a job. See also *auxiliary sheet*.

server. In Infoprint, the object that accepts configuration, management, and printing requests, performs the requested operations, and sends responses back as a result of the operation.

settable attribute. See *initially settable attribute, resettable attribute.*

severity. An indication of how serious an error condition is.

shell. In the AIX operating system, a command interpreter that acts as an interface between the user and the operating system. In Infoprint documentation, all shell examples use the Korn shell.

shift-out, shift-in code. Control characters used to indicate the beginning and end of a string of double-byte, ideographic characters.

shortest-job-first. In Infoprint, a queuing technique where the next job assigned to the first position in the queue is the shortest job in the queue. Contrast with *deadline*, FIFO (*first-in-first-out*), *job-priority*, and *longest-job-first*.

shut down. In Infoprint, the action used to halt all server or actual destination processes without deleting the server or actual destination.

signature. A group of pages that are printed, folded, cut, and bound together. Manual placement of pages on the signature is determined using a folding dummy.

simplex. In Infoprint, the value of the document or actual destination **plex** attribute indicating that output images are placed on the media in a head-to-head format, so that the top of one image is at the same edge as the top of the next image. Depending on the value of the document or actual destination **sides** attribute, the document may be printed on one or both sides of the paper. Contrast with *tumble*; see also *simplex printing* (2), *duplex printing* (2).

simplex printing. Printing on only one side of the paper. Contrast with *duplex printing* (1). Printing on one or both sides of the paper, placing output images on the media in a head-to-head format, so that the top of one image is at the same edge as the top of the next image. Contrast with *tumble duplex printing*; see also *duplex printing* (2).

SMIT. System Management Interface Tool.

SNA. Systems Network Architecture.

spiral binding. A type of book binding in which wire or plastic coils are threaded through a series of holes or slots in the binding edge. Contrast with *edition binding*, *perfect binding*, *wire-o binding*.

spot color. Individual colored inks formulated to exactly match a specified color. Spot color is used when CMYK process color is unable to produce a reasonable facsimile of the color or when vivid color is needed. Spot color also is used when fluorescent or metallic colors are needed.

spread. In color printing, an area whose dimensions have been enlarged to eliminate white space between it and another color. Contrast with *choke*.

start sheet. The sheet of paper, blank or otherwise, that can precede a job. See also *auxiliary sheet*.

state. Synonym for object state.

stripping. The process of mechanically assembling film into plate layouts. Page imposition takes place during stripping.

subnet mask. A bit template indicating which part of an IP address represents the network. A 1 in the subnet mask means that the corresponding bit in the IP address is part of the network address; a 0 means that it is not. For example, if the IP address is 9.99.12.137 and the subnet mask is 255.255.255.0, the network address is 9.99.12.0.

subnetwork. Any group of nodes that have common characteristics, such as the same network ID. In the AIX operating system, one of a group of multiple logical divisions of another network, such as can be created by TCP/IP.

subtractive color system. A system that reproduces an image by mixing (adding) appropriate quantities of cyan, magenta, and yellow paints on white paper. These paints reflect certain colors and absorb—or subtract—others. Contrast with *additive color system*.

superuser. Synonym for root user.

supported. In Infoprint, pertaining to the specific job attribute values that the actual destination can accept during job validation. Infoprint validates the requested attribute values of the job against the supported attribute values of the actual destination to determine whether the actual destination can handle that job. Contrast with *requested*.

synchronous. Occurring with a regular or predictable time relationship to a specified action. Contrast with *asynchronous*.

system administrator. Synonym for administrator.

System Management Interface Tool (SMIT). In the AIX operating system, an interface tool for installation, maintenance, configuration and diagnostic tasks. SMIT allows you to perform tasks without entering any commands.

Systems Network Architecture (SNA). The description of IBM's logical structure, formats, protocols, and operational sequences for transmitting units through, and controlling the configuration and operation of, networks.

Т

table reference character (TRC). An optional control character in a print data set. The TRC identifies the font used to print the record and can be used to select a font during printing.

Tagged Image File Format (TIFF). A digital format for storing scanned images. TIFF files are also referred to as raster format files (as opposed to vector format files). When used in desktop publishing, TIFF files produce only a low-resolution FPO image; the high-resolution data remains on the hard disk.

task help. A type of online help that provides a list of tasks that can be completed with a selected object. When you select a task, the help provides step-by-step information about how to complete the task.

TCP/IP. Transmission Control Protocol/Internet Protocol.

TCP/IP-attached printer. A printer device attached to an RS/6000 through telecommunication lines using the TCP/IP protocol. In Infoprint, a PSF physical printer that represents a TCP/IP-attached printer device. See also AIX-attached printer, channel-attached printer, direct-attached printer, upload-SNA-attached printer, upload-TCP/IP-attached printer.

template. In the Infoprint GUI, an object that represents a set of default attribute values that has been defined for creating a particular type of object, such as an actual destination.

ticket. See job ticket, DCE ticket.

TIFF. Tagged Image File Format.

Transmission Control Protocol/Internet Protocol (TCP/IP). A set of communication rules used in the Internet and in any network that follows the U.S. Department of Defense standards for inter-network protocol. TCP provides a reliable host-to-host protocol between hosts in packet-switched communications networks and in interconnected systems of such networks. It assumes that the Internet Protocol (IP) is the underlying protocol. See also *Internet Protocol*.

trapping. In desktop publishing, the amount of overlap in overprinting colors. Trapping prevents white paper showing through gaps caused by normal errors in registration. On sheet-fed presses, trapping is usually 0.25 point. See also *choke*, *spread*.

TRC. Table reference character.

tumble. In Infoprint, the value of the document or actual destination **plex** attribute indicating that output images are placed on the media in a head-to-toe format, so that the top of one image is at the same edge

as the bottom of the next image. The document must be printed on both sides of the paper. Contrast with *simplex*.

tumble duplex printing. Printing on both sides of the paper, placing output images on the media in a head-to-toe format, so that the top of one image is at the same edge as the bottom of the next image. Contrast with *simplex printing* (2), *duplex printing* (2).

U

UCR. Under color removal.

under color removal (UCR). Conversion of neutral color areas to black ink that reduces use of CMY inks, improves trapping, and reduces setup time. Generally, UCR is performed during image scanning, but some RIPs perform it during processing. Synonymous with gray component replacement (GCR).

unmanage. In the Infoprint GUI, the action used to put an object into a mode where its icon does not reflect the changes of status for the object.

upload printer. See upload-SNA-attached printer, upload-TCP/IP-attached printer.

upload-SNA-attached-printer. In Infoprint, a PSF physical printer that represents a printer device attached to an MVS system and managed by PSF/MVS. Infoprint communicates with the MVS system through the SNA network. See also AIX-attached printer, channel-attached printer, direct-attached printer, TCP/IP-attached printer, upload-TCP/IP-attached printer.

upload-TCP/IP-attached-printer. In Infoprint, a PSF physical printer that represents a printer device attached to an MVS system and managed by PSF/MVS. Infoprint communicates with the MVS system through the TCP/IP network. See also *AIX-attached printer*, *channel-attached printer*, *direct-attached printer*, *TCP/IP-attached printer*, *upload-SNA-attached printer*.



validate. In Infoprint, to compare the attribute values requested by a job with the supported attribute values of the actual destinations in the system and to determine whether there is an actual destination capable of printing or transmitting the job.

value. A specific characteristic of an attribute.

variable. A name used to represent a data item whose value can change while the program is running.

variable data. Data that can be changed between jobs. For example, a form letter (constant data) can be merged with variable data such as a customer's name and address to produce personalized copies of documents.

varnish. A protective layer applied to a finished sheet, usually for photos, but sometimes used as a design element due to its reflective nature. Varnishes can be tinted.

vector. An absolute coordinate point and line in space. PostScript files can contain vector artwork. Vector files are converted to rasters during the RIP process.

velox. A black and white photographic print made from a halftone negative, to be used as a proof copy.

vignette. An image with soft, fade-away edges.

Virtual Machine (VM). An IBM licensed product that manages the resources of a single computer so that multiple computing systems appear to exist. A virtual data processing system that appears to be at the exclusive disposal of a particular user, but whose functions are accomplished by sharing the resources of a real data processing system. (T)

Virtual Storage Extended (VSE). An IBM licensed program whose full name is the Virtual Storage Extended/Advanced Function. It is a software operating system controlling the execution of programs.

Visual Systems Management (VSM). In AIX, a type of graphical user interface that allows system management through the direct manipulation of objects.

VM. Virtual Machine.

VSE. Virtual Storage Extended.

VSM. Visual Systems Management.

W

web. A roll of paper used in web or rotary printing.

well. In the Infoprint administrator's GUI, an area within a pane that contains a group of objects related to the objects in the pane; for example, a queues well within a servers pane.

what you see is what you get (WYSIWYG). Refers to the fact that the composite image displayed on the screen at a computer workstation has the appearance of the final printed image.

window. A rectangular area of the screen that you can move about, place on top of, or pull under other windows, or reduce to an icon.

wire-o binding. A continuous double series of wire loops run through punched slots along the binding side of a booklet. Contrast with *edition binding*, *perfect binding*, *spiral binding*.

with-request. In Infoprint, a document transfer method where the client transfers the documents directly to the server. Contrast with *pipe-pull*.

workstation. A terminal or microcomputer, usually one that is connected to a mainframe or to a network, at which a user can use applications.

write access. A level of authorization that grants the ability to modify data.

WYSIWYG. What you see is what you get.



X-Windows. A network-transparent windowing system developed by MIT. It is the basis for Enhanced X-Windows, which runs on the AIX Operating System.

xerography. A dry printing process using corona-charged photoconductive surfaces to hold latent images that are developed with a dry toner and then transferred to paper and fused with heat.

Xstation. A terminal that is connected through a network to an RS/6000 system, from which a user can perform command-line functions and run X-Windows based applications.

Xtensions. A UNIX-provided software component that enables users to incorporate variable data into fixed-text documents to produce personalized or customized documents.

Numerics

3170 destination support system. The destination support system used by the IBM InfoColor 70 to print jobs.

3170 physical printer. A physical printer representing an IBM InfoColor 70 printer device.

Notices

Licenses

References in this publication to products or services of IBM do not suggest or imply that IBM will make them available in all countries where IBM does business or that only products or services of IBM may be used. Noninfringing equivalents may be substituted, but the user must verify that such substitutes, unless expressly designated by IBM, work correctly. No license, expressed or implied, to patents or copyrights of IBM is granted by furnishing this document. You can send license inquiries, in writing, to the IBM Director of Licensing, IBM Corporation, 500 Columbus Avenue, Thornwood, NY 10594, USA.

Licensees of this program who wish to have information about it for the purpose of enabling: (1) the exchange of information between independently created programs and other programs (including this one) and (2) the mutual use of the information, which has been exchanged, should contact: IBM Corporation, Printing Systems Legal Department, Mail Drop 002S, Boulder, Colorado 80301 USA. Such information may be available, subject to appropriate terms and conditions, including in some cases, payment of a fee.

Trademarks

The following are trademarks or registered trademarks of International Business Machines Corporation:

ACF/NCP

ACF/VTAM

ADSM/6000

Advanced Distributed Storage Manager/6000

Advanced Function Common Control Unit

Advanced Function Presentation

Advanced Peer-to-Peer Networking

AFCCU

AFP

APPN

AIX®

AIXwindows®

AIX/6000

Application System/400

AS/400

Bar Code Object Content Architecture

BCOCA

DB2*/6000

GXT150M

 $IBM^{\mathbb{B}}$

InfoColor®

InfoPrint[®]

Intelligent Printer Data Stream

IPDS

Magstar

Micro Channel

MO:DCA

NCP

NetView[®]

Operating System/400

OS/2

OS/400

POWERserver

POWERstation

Print Services Facility for AIX

Proprinter[®]

PS/2®

PSF

PSF for AIX

OuietWriter®

RS/6000®

System/370

SNA Gateway/6000

SNA Server/6000

SystemView

S/370

S/390

VTAM

WIN-OS/2

The following are trademarks of other companies:

- Acrobat, Adobe, Adobe PostScript Extreme. Adobe PageMaker, and PostScript are trademarks of Adobe Systems, Incorporated.
- Ethernet is a trademark of the Xerox Corporation.
- Helvetica is a trademark of Linotype-Hell Company.
- Hewlett-Packard, Hewlett-Packard Printer Control Language, HP, and LaserJet are trademarks of Hewlett-Packard Company.
- i-data is a trademark of i-data international a-s.
- Lotus Notes is a trademark of Lotus Development Corporation.
- Macintosh is a trademark of Apple Computer, Inc.
- Microsoft is a trademark of Microsoft Corporation.
- NFS and Sun are trademarks of Sun Microsystems, Inc..
- Novell is a trademark of Novell, Inc.
- OSF is a trademark of Open Software Foundation.
- QuarkXPress is a trademark of Quark Corporation.
- R/3, SAP, and SAPscript are registered trademarks of SAP AG.
- TIFF is a trademark of Aldus Corporation.
- Times New Roman is a trademark of Monotype Typography, Inc.
- UNIX is a trademark in the United States and other countries, licensed exclusively through X/Open Company Limited.
- Windows and Windows NT are registered trademarks of Microsoft Corporation.

Index

actual destinations, attributes of actual destinations, attributes of **Special Characters** (continued) (continued) * (wildcard) 6 audit-exit 347 dss-job-message-log-size 379 /etc/services file 177, 180, 674 automatic-postscript-modedss-job-message-log-wrap 380 /usr/lib/lpd/pio/predef directory 363 switch 347 ebcdic-character-mapping 380 /usr/lpd/pio/predef directory 377 auxiliary-sheet-selectionsenabled 381 /usr/lpp/pd/attr directory 336 supported 348 end-message-supported 381 booklet-fold 348 end-sheets-supported 382 **Numerics** cancel-individual-documentfont-resolutions-supported 383 supported 349 force-destination-setup 383 00000000.tab file 311 carriage-control-types-supported 349 force-printer-setup 383 240-pel character-mappings-supported 350 form-definition 384 output for PDF 294 checkpoint-at-stacker 350 halftones-supported 384 output for PostScript 294 checkpoint-formats-supported 351 image-fit-supported 386 300-pel color-bits-per-plane 352 image-length 386 output for PDF 294 color-bits-per-plane-supported 352 image-out-formats-supported 387 output for PostScript 294 color-mapping-table 353 image-width 388 3170 destination support system color-profile 353 input-data-user-exit 389 (DSS) 330 color-profiles-supported 354 input-trays-medium 389 40010000.tab file 311 color-rip-servers 354 input-trays-supported 391 40040000.tab file 311 color-toner-saver 355 intervention-timer 391 job-attributes-supported 392 color-toner-saver-supported 355 output for PDF 294 command 360 job-batches-ready 392 output for PostScript 294 connection-timeout 356 job-finishings-supported 393 600-pel content-orientations-supported 356 job-retry-count-limit 394 output for PDF 294 convert-to-ebcdic-supported 357 job-retry-interval 394 output for PostScript 294 job-rip-actions-supported 395 data-fidelity-problem-reportedsupported 358 job-size-range-ready 395 default-font-fidelity-action 358 job-size-range-supported 396 default-font-resolution 359 job-start-wait-supported 397 accept-jobs attribute default-input-tray 359 list-of-managers 398 actual destination 340 descriptor 360 locations 362 accept-unsupported-jobs attribute destination-command 360 log-accounting-data 398 server 643 destination-data-stream 361 logical-destinations-assigned 399 account-text attribute destination-locations 362 managers 398 default document 469 destination-model 363 maximum-concurrent-jobs 400 document 469 destination-name 364 maximum-copies-supported 401 accounting data maximum-fonts-to-keep 401 destination-needs-attention-time 364 reporting by destination 135 destination-needs-key-operatormaximum-overlays-to-keep 402 reporting by job 132 attention-time 365 maximum-presentation-objectreporting by user destination-pass-through 365 containers-to-keep 402 for all users 131, 136 destination-poll-interval 366 maximum-segments-to-keep 403 for specified user 133, 137 destination-realization 366 media-ready 403 accounting-exit attribute destination-register-threshold 366 media-supported 404 actual destination 340 destination-release-timer 367 message 405 accounting information destination-state 368 message-font-type 405 for a specific server 17 message-form-definition 406 destination-support-system 369 specified time 17 model 363 destination-tcpip-internetack-interval attribute address 370 non-process-runout-timer 406 actual destination 341 destination-tcpip-port-number 371 notification-profile 407 actual destinations, attributes of destination-timeout-period 371 notify-operator 408 accept-jobs 340 device-name 372 number-up-supported 409 accounting-exit 340 device-support-system 369 object-class 410 ack-interval 341 document-attributes-supported 373 offset-stacking-available 410 add-carriage-returns 342 document-finishings-supported 375 operators 408 add-line-feeds 342 optimize-for-multiple-copies 411 document-formats-ripped-atascii-character-mapping 342 destination 376 orientations-supported 356 ascii-font-map 343 document-formats-supported 376, other-options 365 associated-queue 344 output-appearances-supported 412 associated-server 344 document-types-supported 378 output-bin 412

dss-job-message-disposition 379

output-bin-numbers 413

attachment-type 345

attribute-map 346

actual destinations, attributes of	actual destinations, attributes of	afpsplit utility (continued)
(continued)	(continued)	syntax 130
output-bins-supported 414	rip-server 444	ainurpt1 utility
output-data-user-exit 414	scanner-corrections-supported 444	description 131, 135
output-format-supported 415	scheduler-sort-primary-order 445	examples 131, 135
overlay 416	scheduler-sort-secondary-order 445	syntax 131, 135
page-select-supported 416	schedulers-supported 446	ainurpt2 utility
pcl-server-address 417 pcl-server-port 417	screen-frequencies-supported 446 separator-sheets-supported 447	description 132, 136 examples 132, 136
physical-printer 364	shared-printer-name 448	syntax 132, 136
plex 418	sides 448	ainurpt3 utility
plexes-supported 418	sides-supported 449	description 133, 137
postscript-server-address 419	snmp-active 450	examples 133, 137
presentation-fidelity-problem-	snmp-community-name 450	syntax 133, 137
reported 420	snmp-retry-count 450	ainurpt4 utility
presentation-object-container-	snmp-timeout 451	description 139
extraction-mode 421	start-message-supported 451	examples 139
print-edge-marks 421	start-sheets-supported 452	syntax 139
print-qualities-supported 421	table-reference-characters-	ainurpt5 utility
print-queue 422	supported 453	description 140
print-queue-name 422	timeout-period 371	examples 140
printer 364	transform-sequence 453	syntax 140
printer-command 360	use-snmp 454	ainurpt6 utility
printer-data-stream 361	used for job scheduling 719	description 141
printer-end-sheet 423	used for job validation 719	examples 141
printer-escape-codes 423	wait-for-job-completion 454	syntax 141
printer-locations 362	warning-message 455	AIX destination support system
printer-memory 424	x-image-shift-supported 456	(DSS) 330
printer-model 363	y-image-shift-supported 457	AIX print queues
printer-name 364	actual-destinations-assigned attribute	migrating 160
printer-needs-attention-time 364	queue 630	ANSI carriage-control character
printer-needs-key-operator-attention-	actual-destinations-ready attribute	encoded in ASCII 243
time 365	queue 630	encoded in EBCDIC 243
printer-pass-through 365	server 644	apka2e exit program 251
printer-realization 366	actual-destinations-requested attribute	arguments
printer-register-threshold 366 printer-release-timer 367	default job 543 job 543	general description of 5
printer-resolutions-ready 425	actual-destinations-supported attribute	of commands
printer-resolutions-supported 426	server 644	lprafp 13
printer-s370-channel-device-	add-carriage-returns attribute	mkfntmap 15
address 429	actual destination 342	pdaccount 18
printer-s370-channel-slot-number 430	add-line-feeds attribute	pdclean 21
printer-separator-sheet 427	actual destination 342	pdcreate 25
printer-start-sheet 428	address1-text attribute	pddelete 29
printer-state 368	default document 469	pddisable 33
printer-tcpip-internet-address 370	document 469	pdenable 36
printer-tcpip-port-number 371	address2-text attribute	pdls 43
problem-message 430	default document 470	pdmod 52
protected-attributes 431	document 470	pdpause 58
psf-tray-characteristics 431	address3-text attribute	pdpr 65
public-context-presentation-object-	default document 470	pdpromote 71 pdq 75
container 434	document 470	pdreorder 78
qualities-supported 421	address4-text attribute	pdresubmit 81
register-threshold 366	default document 471	pdresume 84
registered-with-spooler 435	document 471	pdrm 87
remote-queue 435	admingui utility	pdset 92
resource-context 436, 437 resource-context-form-definition 438	arguments 129	pdshutdown 97
	description 129	pdspace 101
resource-context-overlay 439 resource-context-page-definition 440	examples 129	of utilities
resource-context-page-definition 440	flags 129	admingui 129
resource-context-presentation-object-	syntax 129	afpslplit 130
container 442	advancing a job to the top of a queue 70	cfu 143
reuse-inline-presentation-object-	afpsplit utility	jsmigr 150
container 443	arguments 130	opergui 152
reverse-output 443	description 130	pdcrdflt 156
rip-ini-file 444	examples 130	pdcrmed 157
*	flags 130	pdinitports 158

arguments (continued)	attributes (continued)	attributes (continued)
pdmigpp 160	address2-text	black-overprint
pdmincfg 162	default document 470	default document 472
sense 168, 170	document 470	document 472
start_server 178	address3-text	booklet-fold
startsrv 180	default document 470	actual destination 348
stop_server 181	document 470 address4-text	building-text
ascii-character-mapping attribute actual destination 342	default document 471	default document 473 document 473
ASCII characters	document 471	callback-number
conversion table for sap2afp	ascii-character-mapping	default document 473
transform 305	actual destination 342	document 473
ascii-font-map attribute	ascii-font-map	cancel-individual-document-supported
actual destination 343	actual destination 343	actual destination 349
asciinp exit program 251	assign-to-destination	server 645
asciinpe exit program 251	queue 631	carriage-control-type
assign-to-destination attribute	assign-to-printer	default document 474
queue 631	queue 631	document 474
assign-to-printer attribute	associated-queue	carriage-control-types-supported
queue 631	actual destination 344	actual destination 349
associated-queue attribute	logical destination 599	logical destination 601
actual destination 344	associated-server	character-mappings-supported
logical destination 599	actual destination 344	actual destination 350
associated-server attribute	auxiliary sheet 458	logical destination 601
actual destination 344	default document 471	chars
auxiliary sheet 458	log 593	default document 474
default document 471	logical destination 599	document 474
log 593	medium 624	checkpoint-at-stacker
logical destination 599	queue 631 resource context 640	actual destination 350
medium 624	attachment-type	checkpoint-formats-supported actual destination 351
queue 631	actual destination 345	cms-proclink
resource context 640	attribute-map	default document 475
attachment-type attribute	actual destination 346	document 475
actual destination 345	audit-exit	cms-product
attribute-map attribute	actual destination 347	default document 476
actual destination 346	authorize-jobs	document 476
attribute operators for filters on the pdls	logical destination 600	color-bits-per-plane
command 41	auto-create-shared-printers	actual destination 352
attributes	server 645	default document 476
accept-jobs	automatic-postscript-mode-switch	document 476
actual destination 340	actual destination 347	color-bits-per-plane-supported
accept-unsupported-jobs server 643	auxiliary-sheet-identifier	actual destination 352
account-text	auxiliary sheet 458	color-mapping-table
default document 469	auxiliary-sheet-selection	actual destination 353
document 469	default job 544	default document 477
accounting-exit	job 544	document 477
actual destination 340	auxiliary-sheet-selections-supported	color-profile
ack-interval	actual destination 348	actual destination 353
actual destination 341	logical destination 600 backlog	default document 477 color-profiles-supported
actual-destinations-assigned	queue 638	actual destination 354
queue 630	backlog-lower-bound	color-rip-servers
actual-destinations-ready	queue 632	actual destination 354
queue 630	backlog-update-interval	color-toner-saver
server 644	queue 632	document 478
actual-destinations-requested	backlog-upper-bound	command
default job 543	queue 633	actual destination 360
job 543	backlogged	comment
actual-destinations-supported	queue 633	default job 555
server 644	base-printer	job 555
add-carriage-returns	default document 471	completion-time
actual destination 342 add-line-feeds	document 471	job 545, 587
actual destination 342	bits-per-spot	complex, specifying 334
address1-text	default document 472	compressed-output
default document 469	document 472	default document 478
document 469		document 478

Index 755

attributes (continued)	attributes (continued)	attributes (continued)
connection-timeout	descriptor	destination-support-system
actual destination 356	actual destination 360	actual destination 369
content-orientation	auxiliary sheet 459	logical destination 606
default document 479	default document 485	destination-support-systems-
document 479	default job 548	supported
content-orientations-supported	log 593	server 646
actual destination 356	logical destination 603	destination-tcpip-internet-address
logical destination 601	medium 625	actual destination 370
context-address	queue 633	destination-tcpip-port-number
resource context 641	resource context 641	actual destination 371
control-strip	server 645	destinations-assigned
default document 479	transform 666	job 550
document 479	destination-associated-printers	destinations-ready
convert-to-ebcdic	logical destination 604	logical destination 607
default document 480	destination-command	destinations-used
document 480	actual destination 360	job 551
convert-to-ebcdic-supported	destination-company-text	device-name
actual destination 357	default document 485, 512	actual destination 372
logical destination 602	document 485, 512	device-support-system
copies	destination-data-stream	actual destination 369
default document 480	actual destination 361	logical destination 606
document 480	destination-initial-value-document	device-support-system-requested
copy-count	logical destination 604	default job 551
default document 480	destination-initial-value-job	job 551
document 480	job 548	discard-time
	logical destination 604	
current-backlog		job 557
queue 638	destination-locations	document-attributes-supported
current-job-state	actual destination 362	actual destination 373
job 545	logical destination 605	server 647
current-page-printing	destination-locations-requested	document-comment
job 546	default job 549	default document 486
d-s-s-requested	job 549	document 486
default job 551	destination-model	document-content
job 551	actual destination 363	document 486
data-fidelity-problem-reported	logical destination 605	document-file-name
default document 481	destination-models-requested	document 487
document 481	default job 549	document-finishing
data-fidelity-problem-reported-	job 549	default document 487
supported	destination-name	document 487
actual destination 358	actual destination 364	document-finishings-supported
logical destination 603	logical destination 605	actual destination 375
deadline-in-jeopardy	destination-name-requested	document-format
job 547	job 550	default document 488
default-character-mapping	destination-needs-attention-time	document 488
default document 481	actual destination 364	document-formats-ripped-at-
document 481	destination-needs-key-operator-	destination
default-font-fidelity-action	attention-time	actual destination 376
actual destination 358	actual destination 365	document-formats-supported
default-font-resolution	destination-pass-through	actual destination 376, 667
actual destination 359	actual destination 365	logical destination 607
default-input-tray	default document 486	document-number
actual destination 359	document 486	document 489
default document 482	destination-poll-interval	document-sequence-number
document 482	actual destination 366	document 489
default-medium	destination-realization	document-type
default document 483	actual destination 366	default document 490
document 483	logical destination 606	document 490
	ĕ	
default-printer-resolution default document 484	destination-register-threshold actual destination 366	document-types-supported actual destination 378
document 484	destination-release-timer	logical destination 608
delete-segment-list	actual destination 367	dot-shape
default job 547	destination-state	default document 491
job 547	actual destination 368	document 491
department-text	destination-states-supported	dss-job-message-disposition
default document 484	server 646	actual destination 379
document 484		

attributes (continued)	attributes (continued)	attributes (continued)
dss-job-message-log-size	formatted-job-ticket-content	intervening-jobs
actual destination 379	job 553	job 554
dss-job-message-log-wrap	global-id	intervention-timer
actual destination 380	job 560	actual destination 391
dss-requested	halftone	ip-address
default job 551	default document 496	server 660
job 551	document 496	job-attributes-supported
ebcdic-character-mapping	halftones-supported	actual destination 392
actual destination 380	actual destination 384	server 649
email-from-address	hold	job-batch
default document 492	default job 559	default job 555
document 492	job 559	job 555
email-to-address	hostname	job-batches-ready
default document 493	server 660	actual destination 392
document 493	i-p-address	job-client-id
enable-settrap	server 660	job 555
default document 493	image-center-x	job-comment
document 493	default document 497	default job 555
enabled	document 497	job 555
actual destination 381		,
	image-center-y default document 498	job-complexity
log 594		job 556
logical destination 608	document 498	job-copies-completed
end-message	image-fit	job 556
default job 558	default document 498	job-deadline-time
job 558	document 498	job 557
end-message-supported	image-fit-supported	job-discard-time
actual destination 381	actual destination 386	job 557
logical destination 609	image-length	job-end-message
end-sheets-supported	actual destination 386	default job 558
actual destination 382	default document 499	job 558
estimated-completion-time	document 499	job-finishing
job 552	image-out-format	default job 558
estimated-processing-time	default document 500	job 558
job 553	document 500	job-finishings-supported
events-supported	image-out-formats-supported	actual destination 393
server 647	actual destination 387	job-hold
fax-number	logical destination 609	default job 559
default document 493	image-scale	job 559
document 493	default document 501	job-identifier
fax-to-name	document 501	job 560
default document 494	image-width	job-log
document 494	actual destination 388	job 560
file-name	default document 501	job-media-sheet-count
document 487	document 501	job 561
font-fidelity-action	initial-value-document	job-message-from-administrator
default document 494	document 502	job 561
document 494		,
	initial-value-document-identifier	job-message-to-operator
font-processing-messages	default document 503	default job 562
default document 495	initial-value-job	job 562
document 495	job 554	job-name
font-resolution	initial-value-job-identifier	job 562
default document 495	default job 554	job-originator
document 495	input-data-user-exit	default job 563
font-resolutions-supported	actual destination 389	job 563
actual destination 383	input-exit	job-owner
force-destination-setup	default document 503	job 563
actual destination 383	document 503	job-page-count
force-printer-setup	input-tray-select	job 564
actual destination 383	default document 504	job-print-after
form-definition	document 504	job 564
actual destination 384	input-trays-medium	job-priority
default document 496	actual destination 389	default job 565
document 496	input-trays-supported	job 565
format	actual destination 391	job-retain-until
default document 488	logical destination 610	ioh 565

document 488

ittributes (continued)	attributes (continued)	attributes (continued)
job-retention-period	log-address	maximum-raster-rips
default job 566	log 594	server 653
job 566	log-identifier	maximum-segments-to keep
job-retry-count-limit	log 594	actual destination 403
actual destination 394	log-message	maximum-transform-pages-ahead
job-retry-interval	log 595	default document 506
actual destination 394	log-severity	document 506
job-rip-action	log 595	media-ready
default job 566	log-size	actual destination 403
job 566	log 596	media-sheet-count
job-rip-actions-supported	log-trace-groups	job 561
actual destination 395	log 596	media-sheets-completed
job-ripped-by-server	log-type	job 575
default job 567	log 596	media-supported
job 567	log-wrap	actual destination 404
job-size	log 597	logical destination 612
job 590	logical-destinations-assigned	medium-color
job-size-range-ready	actual destination 399	medium 625
actual destination 395	queue 634	medium-dimensions
job-size-range-supported	logical-destinations-ready	medium 625
actual destination 396	default document 505	medium-form-parts
	default job 574	medium 626
logical destination 611	,	
job-start-message	queue 634	medium-holes-count
default job 570	server 652	medium 626
job 570	logical-destinations-supported	medium-identifier medium 627
job-start-wait	server 652	
job 571	logical-printer	medium-sides
job-start-wait-supported	logical destination 605	medium 627
job 397	logical-printer-requested	medium-size
job-state	job 550	medium 628
job 545	logical-printers-assigned	medium-type
job-state-reasons	queue 634	medium 628
job 571	logical-printers-ready	medium-weight
job-states-supported	default document 505	medium-weight 629
server 649	default job 574	message
job-submission-complete	queue 634	actual destination 405
job 573	server 652	default document 507
job-submission-timer	logical-printers-supported	default job 575
server 650	server 652	logical destination 613
job-ticket-content	managers	medium 629
job 553	actual destination 398	queue 635
jog-between-job-copies	default document 505	server 654
default document 504	default job 573	message-font-type
document 504	logical destination 611	actual destination 405
last-accessor	queue 634	message-form-definition
job 576	server 650	actual destination 406
last-modifier	maximum-barco-rips	message-from-administrator
job 576	server 653	job 561
list-of-managers	maximum-concurrent-jobs	message-to-operator
actual destination 398	actual destination 400	default job 562
default document 505	maximum-copies-supported	job 562
default job 573	actual destination 401	model
logical destination 611	logical destination 612	actual destination 363
queue 634	maximum-fonts-to-keep	logical destination 605
server 650	actual destination 401	models-requested
locale	maximum-messages-printed	default job 549
server 651	default document 506	job 549
locations	document 506	modification-time
actual destination 362	maximum-non-raster-rips	job 576
logical destination 605	server 653	modify-individual-document-
locations-requested	maximum-overlays-to-keep	supported
default job 549	actual destination 402	server 654
job 549	maximum-presentation-object-	multiple-documents-supported
log-accounting-data	containers-to-keep	server 654
actual destination 398	actual destination 402	mvs-class
server 651		default document 507

attributes (continued)	attributes (continued)	attributes (continued)
document 507	object-class (continued)	output-format
mvs-destination	server 657	default document 515
default document 507	object-classes-supported	document 515
document 507	server 657	output-format-supported
mvs-forms	octet-count	actual destination 415
default document 508	document 511	overlay
document 508	octets-completed	actual destination 416
mvs-segment-id	job 580	default document 516
default document 508	of actual destinations 336	document 516
document 508	of default documents 464	overlay-back
name	of documents 464	default document 516
job 562	of jobs 542	document 516
name-of-last-accessor	of logical destinations 598	overlay-front
job 576	of logs 593	default document 517
name-text	of media 624	document 517
default document 509	of queues 630	overprint
document 509	of resource contexts 640	default document 517
new-job-identifier	of servers 643	document 517
job 576	of transforms 666	owner
new-line-option	offset-stacking-available	job 563
default document 509	actual destination 410	page-clip
document 509	operators	default document 518
node-id-text	actual destination 408	document 518
default document 510	queue 636	page-count
document 510	optimize-for-multiple-copies	document 518
		page-definition
non-process-runout-timer	actual destination 411	
actual destination 406	default job 580	default document 519
notification-delivery-methods-	job 580	document 519
supported	orientation	page-media-select
server 654	default document 479	default document 519
notification-profile	document 479	document 519
actual destination 407	orientations-supported	page-select
default job 577	actual destination 356	document 519
job 577	logical destination 601	page-select-supported
logical destination 613	originator	actual destination 416
queue 635	default job 563	pages-completed
server 655	job 563	job 581
notify-operator	os2-driver-names	pcl-server-address
actual destination 408	logical destination 615	actual destination 417
queue 636	os2-drivers	pcl-server-port
npm-server-ip-address	logical destination 615	actual destination 417
server 656	other-options	physical-printer
npm-server-port-number	actual destination 365	actual destination 364
server 657	default document 486	physical-printers-assigned
nt-drivers	document 486	queue 630
actual destination 455	other-transform-options	physical-printers-ready
logical destination 621	default document 512	queue 630
server 665	document 512	server 644
number-of-documents	output-appearance	physical-printers-requested
job 579	default document 513	default job 543
number-up	document 513	job 543
document 510	output-appearances-supported	physical-printers-supported
number-up-supported	actual destination 412	server 644
actual destination 409	output-bin	plex
object-class	actual destination 412	actual destination 418
actual destination 410	default document 513	default document 521
	document 513	document 521
auxiliary sheet 459		
default document 511	output-bin-numbers	plexes-supported
default job 579	actual destination 413	actual destination 418
document 511	output-bins-supported	logical destination 617
job 579	actual destination 414	position-in-queue
log 597	output-data-user-exit	job 554
logical destination 615	actual destination 414	postscript-server-address
medium 629	output-face-up	actual destination 419
queue 637	default document 514	logical destination 616
resource context 641, 667	document 514	

attributes (continued)	attributes (continued)	attributes (continued)
postscript-server-port	printer-needs-key-operator-attention-	public-context-presentation-object-
actual destination 420	time	container
presentation-fidelity-problem-reported	actual destination 365	actual destination 434
actual destination 420	printer-pass-through	qualities-supported
presentation-object-container-	actual destination 365	actual destination 421
extraction-mode	default document 486	logical destination 617
actual destination 421	document 486	queue-assigned
previous-job-state	printer-realization	job 584
job 582	actual destination 366	queue-backlog
previous-state	logical destination 606	queue 638
job 582	printer-register-threshold	queue-name
print-after	actual destination 366	queue 638
job 564	printer-release-timer	queue-position
print-edge-marks	actual destination 367	job 554
actual destination 421	printer-requested	queue-state
print-qualities-supported	job 550	queue 638
actual destination 421	printer-resolutions-ready	queues-supported
logical destination 617	actual destination 425	server 659
print-quality	printer-resolutions-supported	reasons
default document 521	actual destination 426	job 571
document 521	printer-s370-channel-device-address	register-threshold
	actual destination 429	actual destination 366
print-queue		
actual destination 422	printer-s370-channel-slot-number	registered-with-spooler
print-queue-name	actual destination 430	actual destination 435
actual destination 422	printer-separator-sheet	remote-queue
printer	actual destination 427	actual destination 435
actual destination 364	printer-start-sheet	requeue-failed-jobs
logical destination 605	actual destination 428	queue 639
printer-associated-printers	printer-state	required-resources-not-ready
logical destination 604	actual destination 368	job 584
printer-command	printer-states-supported	required-resources-not-supported
actual destination 360	server 646	job 585
printer-data-stream	printer-tcpip-internet-address	resource-context
actual destination 361	actual destination 370	actual destination 436
printer-end-sheet	printer-tcpip-port-number	default document 522
actual destination 423	actual destination 371	document 522
printer-escape-codes	printer-timeout-period	resource-context-font
actual destination 423	actual destination 371	actual destination 437
printer-initial-value-document	printers-assigned	default document 524
document 485	job 550	document 524
logical destination 604	printers-ready	resource-context-form-definition
printer-initial-value-job	logical destination 607	actual destination 438
job 548	printers-used	default document 525
logical destination 604	job 551	document 525
printer-locations	problem-child	resource-context-identifier
1	server 658	
actual destination 362		resource context 642
logical destination 605	problem-message	resource-context-overlay
printer-locations-requested	actual destination 430	actual destination 439
default job 549	processing-time	default document 525
job 549	job 583	document 525
printer-memory	programmer-text	resource-context-page-definition
actual destination 424	default document 522	actual destination 440
printer-model	document 522	default document 526
actual destination 363	protected-attributes	document 526
logical destination 605	actual destination 431	resource-context-page-segment
printer-models-requested	logical destination 618	actual destination 441
default job 549	queue 638	default document 527
job 549	server 658	document 527
printer-name	psf-exit-form-definition	resource-context-presentation-object
actual destination 364	auxiliary sheet 459	container 528
logical destination 605	psf-exit-page-mark	resource-context-user
printer-name-requested	auxiliary sheet 459	default document 529
job 550		document 529
printer-needs-attention-time	psf-exit-program-name	resource-exit
±	auxiliary sheet 460	
actual destination 364	psf-tray-characteristics	default document 530
	actual destination 431	document 530

attributes (continued)	att	ributes (continued)		attributes (continued)	
results-profile		sides-supported		timeout-period	
default job 585		actual destination		actual destination	371
job 585		logical destination	619	title-text	
retention-period		smtp-server-host		default document	536
default job 566		server 661		document 536	
job 566		smtp-server-port-num	ber	total-job-octets	
reuse-inline-presentation	-object-	server 662		job 590	
container		snmp-active		transfer-method	
actual destination 4	43	actual destination		document 536	
reverse-output		snmp-aix-printer-mode	els	transfer-methods-supp	orted
actual destination 4	43	server 662		server 664	
rip-ini-file		snmp-community-nam	ne	transform-message-file	-name
actual destination 4	44	actual destination	450	default document	537
rip-server		snmp-normal-poll-inte	erval	document 537	
actual destination 4	44	server 663		transform-output-file-n	ame
room-text		snmp-problem-poll-int	terval	document 537	
default document 53	30	server 663		transform-sequence	
document 530		snmp-retry-count		actual destination	453
save-rip-files		actual destination	450	type	
server 659		snmp-timeout		default document	490
scanner-correction		actual destination	451	document 490	
default document 53	31	snmp-trap-timeout		use-snmp	
document 531		server 664		actual destination	454
scanner-corrections-supp	orted	start-message		used for job scheduling	
actual destination 4	44	default job 570		used for job validation	_
scheduler-sort-primary-o		job 570		user-id-text	
actual destination 4		start-message-support	ed	default document	538
scheduler-sort-secondary	-order	actual destination		document 538	
actual destination 4		logical destination		user-locale	
schedulers-supported		start-on-new-sheet		job 591	
actual destination 4	46	default document	535	user-name	
screen-frequencies-suppo		document 535		job 591	
actual destination 4		start-sheets-supported		wait-for-job-completior	1
screen-frequency	10	actual destination		actual destination	
default document 50	31	started-printing-time	102	warning-message	101
document 531	51	job 587		actual destination	455
security-level		state-reasons		windows-driver-names	
server 659		job 571		logical destination	
segment-file-size		subject-text		windows-drivers	020
default document 50	32	default document	535	logical destination	620
document 532	32	document 535	333	windows-nt-driver-nan	
separator-sheets-support	ad	submission-time		actual destination	
1 11					
actual destination 4	4/	job 587 table-reference-charact	one	logical destination	021
sequence-number				servers 665	
document 489		default document	333	windows-nt-drivers	155
server-hostname		document 535		actual destination	
server 660		table-reference-charact		logical destination	621
server-ip-address		actual destination		server 665	
server 660		logical destination	619	x-image-shift	50 0
server-name		tape-exit		default document	538
server 661		job 588		document 538	
server-state		tape-format		x-image-shift-back	
server 661		job 588		default document	539
shared-formdef		tape-labeled		document 539	
default document 50	32	default job 589		x-image-shift-range-suj	
document 532		job 589		actual destination	
shared-printer-name		tape-max-block-size		logical destination	622
actual destination 4	48	default job 589		y-image-shift	
shift-out-shift-in		job 589		default document	540
default document 53	33	tape-rewind-before		document 540	
document 533		job 590		y-image-shift-back	
sides		tape-rewind-unload		default document	540
actual destination 4	48	job 590		document 540	
default document 53	34	ticket-content		y-image-shift-range-su	pported
document 534		job 553		actual destination	457
		÷		logical destination	622

attributes files, creating 149	booklet-fold attribute	collecting accounting information
audit data	actual destination 348	for a specific server 17
reporting by destination 139	braces in commands xxvii, xxviii	specified time 17
reporting by user	brackets in commands xxvii	colons in commands xxviii
for all users 140	BSD destination support system	color-bits-per-plane attribute
for specified user 141	(DSS) 330, 331	actual destination 352
audit-exit attribute	BSD-flag component	default document 476
actual destination 347	attribute-map attribute, actual	document 476
authorize-jobs attribute	destination 346	Color Mapping Table, building 144
logical destination 600	building-text attribute	color-mapping-table attribute
auto-create-shared-printers attribute	default document 473	actual destination 353
server 645	document 473	default document 477
automatic-postscript-mode-switch		document 477
attribute		color-profile attribute
actual destination 347	C	actual destination 353
auxiliary-sheet-identifier attribute		default document 477
auxiliary sheet 458	callback-number attribute	document 477
auxiliary-sheet-selection attribute	default document 473	color-profiles-supported attribute
default job 544	document 473	actual destination 354
job 544	cancel-individual-document-supported	color-rip-servers attribute
auxiliary-sheet-selections-supported	attribute	actual destination 354
attribute	actual destination 349	color-toner-saver attribute
actual destination 348	server 645	actual destination 355
logical destination 600	carriage control characters	
auxiliary sheets, attributes of	specifying presence 242	document 478
associated-server 458	specifying type 242	color-toner-saver-supported attribute
auxiliary-sheet-identifier 458	carriage-control-type attribute	actual destination 355
descriptor 459	default document 474	command attribute
object-class 459	document 474	actual destination 360
psf-exit-form-definition 459	carriage-control-types-supported attribute	command attributes 5, 332
psf-exit-page-mark 459	actual destination 349	command attributes, default values
psf-exit-program-name 460	logical destination 601	for 333
resettable attribute listing 458	cc option 242	command introduction 1
summary of 458	cctype option 242	command scripts, creating 149
Summing of 100	of a setility	commands
	cfu utility	Commands
	arguments 143	arguments
R		
В	arguments 143	arguments
backlog attribute	arguments 143 build file format 142	arguments lprafp 13
backlog attribute queue 638	arguments 143 build file format 142 description 142, 144	arguments lprafp 13 mkfntmap 15
backlog attribute queue 638 backlog-lower-bound attribute	arguments 143 build file format 142 description 142, 144 examples 143	arguments lprafp 13 mkfntmap 15 pdaccount 18
backlog attribute queue 638 backlog-lower-bound attribute queue 632	arguments 143 build file format 142 description 142, 144 examples 143 flags 142	arguments lprafp 13 mkfntmap 15 pdaccount 18 pdclean 21
backlog attribute queue 638 backlog-lower-bound attribute queue 632 backlog-update-interval attribute	arguments 143 build file format 142 description 142, 144 examples 143 flags 142 syntax 142	arguments lprafp 13 mkfntmap 15 pdaccount 18 pdclean 21 pdcreate 25
backlog attribute queue 638 backlog-lower-bound attribute queue 632 backlog-update-interval attribute queue 632	arguments 143 build file format 142 description 142, 144 examples 143 flags 142 syntax 142 channel-attached printers, sensing 168	arguments lprafp 13 mkfntmap 15 pdaccount 18 pdclean 21 pdcreate 25 pddelete 29 pddisable 33 pdenable 36
backlog attribute queue 638 backlog-lower-bound attribute queue 632 backlog-update-interval attribute queue 632 backlog-upper-bound attribute	arguments 143 build file format 142 description 142, 144 examples 143 flags 142 syntax 142 channel-attached printers, sensing 168 character-mappings-supported attribute	arguments lprafp 13 mkfntmap 15 pdaccount 18 pdclean 21 pdcreate 25 pddelete 29 pddisable 33 pdenable 36 pdls 43
backlog attribute queue 638 backlog-lower-bound attribute queue 632 backlog-update-interval attribute queue 632 backlog-upper-bound attribute queue 633	arguments 143 build file format 142 description 142, 144 examples 143 flags 142 syntax 142 channel-attached printers, sensing 168 character-mappings-supported attribute actual destination 350	arguments lprafp 13 mkfntmap 15 pdaccount 18 pdclean 21 pdcreate 25 pddelete 29 pddisable 33 pdenable 36 pdls 43 pdmod 52
backlog attribute queue 638 backlog-lower-bound attribute queue 632 backlog-update-interval attribute queue 632 backlog-upper-bound attribute queue 633 backlogged attribute	arguments 143 build file format 142 description 142, 144 examples 143 flags 142 syntax 142 channel-attached printers, sensing 168 character-mappings-supported attribute actual destination 350 logical destination 601	arguments lprafp 13 mkfntmap 15 pdaccount 18 pdclean 21 pdcreate 25 pddelete 29 pddisable 33 pdenable 36 pdls 43
backlog attribute queue 638 backlog-lower-bound attribute queue 632 backlog-update-interval attribute queue 632 backlog-upper-bound attribute queue 633 backlogged attribute queue 633	arguments 143 build file format 142 description 142, 144 examples 143 flags 142 syntax 142 channel-attached printers, sensing 168 character-mappings-supported attribute actual destination 350 logical destination 601 chars attribute	arguments lprafp 13 mkfntmap 15 pdaccount 18 pdclean 21 pdcreate 25 pddelete 29 pddisable 33 pdenable 36 pdls 43 pdmod 52 pdpause 58 pdpr 65
backlog attribute queue 638 backlog-lower-bound attribute queue 632 backlog-update-interval attribute queue 632 backlog-upper-bound attribute queue 633 backlogged attribute queue 633 barcode.tab configuration file	arguments 143 build file format 142 description 142, 144 examples 143 flags 142 syntax 142 channel-attached printers, sensing 168 character-mappings-supported attribute actual destination 350 logical destination 601 chars attribute default document 474 document 474	arguments lprafp 13 mkfntmap 15 pdaccount 18 pdclean 21 pdcreate 25 pddelete 29 pddisable 33 pdenable 36 pdls 43 pdmod 52 pdpause 58 pdpr 65 pdpromote 71
backlog attribute queue 638 backlog-lower-bound attribute queue 632 backlog-update-interval attribute queue 632 backlog-upper-bound attribute queue 633 backlogged attribute queue 633 barcode.tab configuration file ModWidth optional keyword 303	arguments 143 build file format 142 description 142, 144 examples 143 flags 142 syntax 142 channel-attached printers, sensing 168 character-mappings-supported attribute actual destination 350 logical destination 601 chars attribute default document 474 document 474 chars option 243, 259	arguments lprafp 13 mkfntmap 15 pdaccount 18 pdclean 21 pdcreate 25 pddelete 29 pddisable 33 pdenable 36 pdls 43 pdmod 52 pdpause 58 pdpr 65 pdpromote 71 pdq 75
backlog attribute queue 638 backlog-lower-bound attribute queue 632 backlog-update-interval attribute queue 632 backlog-upper-bound attribute queue 633 backlogged attribute queue 633 barcode.tab configuration file ModWidth optional keyword 303 Ratio optional keyword 303	arguments 143 build file format 142 description 142, 144 examples 143 flags 142 syntax 142 channel-attached printers, sensing 168 character-mappings-supported attribute actual destination 350 logical destination 601 chars attribute default document 474 document 474 chars option 243, 259 checkpoint-at-stacker attribute	arguments lprafp 13 mkfntmap 15 pdaccount 18 pdclean 21 pdcreate 25 pddelete 29 pddisable 33 pdenable 36 pdls 43 pdmod 52 pdpause 58 pdpr 65 pdpromote 71 pdq 75 pdreorder 78
backlog attribute queue 638 backlog-lower-bound attribute queue 632 backlog-update-interval attribute queue 632 backlog-upper-bound attribute queue 633 backlogged attribute queue 633 barcode.tab configuration file ModWidth optional keyword 303 Ratio optional keyword 303 barcode.tab file 303	arguments 143 build file format 142 description 142, 144 examples 143 flags 142 syntax 142 channel-attached printers, sensing 168 character-mappings-supported attribute actual destination 350 logical destination 601 chars attribute default document 474 document 474 chars option 243, 259 checkpoint-at-stacker attribute actual destination 350	arguments lprafp 13 mkfntmap 15 pdaccount 18 pdclean 21 pdcreate 25 pddelete 29 pddisable 33 pdenable 36 pdls 43 pdmod 52 pdpause 58 pdpr 65 pdpromote 71 pdq 75
backlog attribute queue 638 backlog-lower-bound attribute queue 632 backlog-update-interval attribute queue 632 backlog-upper-bound attribute queue 633 backlogged attribute queue 633 barcode.tab configuration file ModWidth optional keyword 303 Ratio optional keyword 303 barcode.tab file 303 bars in commands xxvii	arguments 143 build file format 142 description 142, 144 examples 143 flags 142 syntax 142 channel-attached printers, sensing 168 character-mappings-supported attribute actual destination 350 logical destination 601 chars attribute default document 474 document 474 chars option 243, 259 checkpoint-at-stacker attribute actual destination 350 checkpoint-formats-supported attribute	arguments lprafp 13 mkfntmap 15 pdaccount 18 pdclean 21 pdcreate 25 pddelete 29 pddisable 33 pdenable 36 pdls 43 pdmod 52 pdpause 58 pdpr 65 pdpromote 71 pdq 75 pdreorder 78 pdresubmit 81 pdresume 84
backlog attribute queue 638 backlog-lower-bound attribute queue 632 backlog-update-interval attribute queue 632 backlog-upper-bound attribute queue 633 backlogged attribute queue 633 barcode.tab configuration file ModWidth optional keyword 303 Ratio optional keyword 303 barcode.tab file 303 bars in commands xxvii base-printer attribute	arguments 143 build file format 142 description 142, 144 examples 143 flags 142 syntax 142 channel-attached printers, sensing 168 character-mappings-supported attribute actual destination 350 logical destination 601 chars attribute default document 474 document 474 chars option 243, 259 checkpoint-at-stacker attribute actual destination 350 checkpoint-formats-supported attribute actual destination 350 checkpoint-formats-supported attribute actual destination 351	arguments lprafp 13 mkfntmap 15 pdaccount 18 pdclean 21 pdcreate 25 pddelete 29 pddisable 33 pdenable 36 pdls 43 pdmod 52 pdpause 58 pdpr 65 pdpromote 71 pdq 75 pdreorder 78 pdresubmit 81 pdresume 84 pdrm 87
backlog attribute queue 638 backlog-lower-bound attribute queue 632 backlog-update-interval attribute queue 632 backlog-upper-bound attribute queue 633 backlogged attribute queue 633 barcode.tab configuration file ModWidth optional keyword 303 Ratio optional keyword 303 barcode.tab file 303 bars in commands xxvii base-printer attribute default document 471	arguments 143 build file format 142 description 142, 144 examples 143 flags 142 syntax 142 channel-attached printers, sensing 168 character-mappings-supported attribute actual destination 350 logical destination 601 chars attribute default document 474 document 474 chars option 243, 259 checkpoint-at-stacker attribute actual destination 350 checkpoint-formats-supported attribute actual destination 350 checkpoint-formats-supported attribute actual destination 351 cms-proclink attribute	arguments lprafp 13 mkfntmap 15 pdaccount 18 pdclean 21 pdcreate 25 pddelete 29 pddisable 33 pdenable 36 pdls 43 pdmod 52 pdpause 58 pdpr 65 pdpromote 71 pdq 75 pdreorder 78 pdresubmit 81 pdresume 84 pdrm 87 pdset 92
backlog attribute queue 638 backlog-lower-bound attribute queue 632 backlog-update-interval attribute queue 632 backlog-upper-bound attribute queue 633 backlogged attribute queue 633 barcode.tab configuration file ModWidth optional keyword 303 Ratio optional keyword 303 barcode.tab file 303 bars in commands xxvii base-printer attribute default document 471 document 471	arguments 143 build file format 142 description 142, 144 examples 143 flags 142 syntax 142 channel-attached printers, sensing 168 character-mappings-supported attribute actual destination 350 logical destination 601 chars attribute default document 474 document 474 chars option 243, 259 checkpoint-at-stacker attribute actual destination 350 checkpoint-formats-supported attribute actual destination 350 checkpoint-formats-supported attribute actual destination 351 cms-proclink attribute default document 475	arguments lprafp 13 mkfntmap 15 pdaccount 18 pdclean 21 pdcreate 25 pddelete 29 pddisable 33 pdenable 36 pdls 43 pdmod 52 pdpause 58 pdpr 65 pdpromote 71 pdq 75 pdreorder 78 pdresubmit 81 pdresume 84 pdrm 87 pdset 92 pdshutdown 97
backlog attribute queue 638 backlog-lower-bound attribute queue 632 backlog-update-interval attribute queue 632 backlog-upper-bound attribute queue 633 backlogged attribute queue 633 barcode.tab configuration file ModWidth optional keyword 303 Ratio optional keyword 303 barcode.tab file 303 bars in commands xxvii base-printer attribute default document 471 document 471 bin-name component	arguments 143 build file format 142 description 142, 144 examples 143 flags 142 syntax 142 channel-attached printers, sensing 168 character-mappings-supported attribute actual destination 350 logical destination 601 chars attribute default document 474 document 474 chars option 243, 259 checkpoint-at-stacker attribute actual destination 350 checkpoint-formats-supported attribute actual destination 350 checkpoint-formats-supported attribute actual destination 351 cms-proclink attribute default document 475 document 475	arguments lprafp 13 mkfntmap 15 pdaccount 18 pdclean 21 pdcreate 25 pddelete 29 pddisable 33 pdenable 36 pdls 43 pdmod 52 pdpause 58 pdpr 65 pdpromote 71 pdq 75 pdreorder 78 pdresubmit 81 pdresume 84 pdrm 87 pdset 92
backlog attribute queue 638 backlog-lower-bound attribute queue 632 backlog-update-interval attribute queue 632 backlog-upper-bound attribute queue 633 backlogged attribute queue 633 barcode.tab configuration file ModWidth optional keyword 303 Ratio optional keyword 303 barcode.tab file 303 bars in commands xxvii base-printer attribute default document 471 document 471 bin-name component output-bin-numbers attribute, actual	arguments 143 build file format 142 description 142, 144 examples 143 flags 142 syntax 142 channel-attached printers, sensing 168 character-mappings-supported attribute actual destination 350 logical destination 601 chars attribute default document 474 document 474 chars option 243, 259 checkpoint-at-stacker attribute actual destination 350 checkpoint-formats-supported attribute actual destination 351 cms-proclink attribute default document 475 document 475 cms-product attribute	arguments lprafp 13 mkfntmap 15 pdaccount 18 pdclean 21 pdcreate 25 pddelete 29 pddisable 33 pdenable 36 pdls 43 pdmod 52 pdpause 58 pdpr 65 pdpromote 71 pdq 75 pdreorder 78 pdresubmit 81 pdresume 84 pdrm 87 pdset 92 pdspace 101 attributes
backlog attribute queue 638 backlog-lower-bound attribute queue 632 backlog-update-interval attribute queue 632 backlog-upper-bound attribute queue 633 backlogged attribute queue 633 barcode.tab configuration file ModWidth optional keyword 303 Ratio optional keyword 303 bars in commands xxvii base-printer attribute default document 471 document 471 bin-name component output-bin-numbers attribute, actual destination 413	arguments 143 build file format 142 description 142, 144 examples 143 flags 142 syntax 142 channel-attached printers, sensing 168 character-mappings-supported attribute actual destination 350 logical destination 601 chars attribute default document 474 document 474 chars option 243, 259 checkpoint-at-stacker attribute actual destination 350 checkpoint-formats-supported attribute actual destination 350 checkpoint-formats-supported attribute actual destination 351 cms-proclink attribute default document 475 document 475 cms-product attribute default document 476	arguments lprafp 13 mkfntmap 15 pdaccount 18 pdclean 21 pdcreate 25 pddelete 29 pddisable 33 pdenable 36 pdls 43 pdmod 52 pdpause 58 pdpr 65 pdpromote 71 pdq 75 pdreorder 78 pdresubmit 81 pdresume 84 pdrm 87 pdset 92 pdshutdown 97 pdspace 101 attributes general description of 5
backlog attribute queue 638 backlog-lower-bound attribute queue 632 backlog-update-interval attribute queue 632 backlog-upper-bound attribute queue 633 backlogged attribute queue 633 barcode.tab configuration file ModWidth optional keyword 303 Ratio optional keyword 303 bars in commands xxvii base-printer attribute default document 471 document 471 bin-name component output-bin-numbers attribute, actual destination 413 bin-number component	arguments 143 build file format 142 description 142, 144 examples 143 flags 142 syntax 142 channel-attached printers, sensing 168 character-mappings-supported attribute actual destination 350 logical destination 601 chars attribute default document 474 document 474 chars option 243, 259 checkpoint-at-stacker attribute actual destination 350 checkpoint-formats-supported attribute actual destination 351 cms-proclink attribute default document 475 document 475 cms-product attribute default document 476 document 476	arguments lprafp 13 mkfntmap 15 pdaccount 18 pdclean 21 pdcreate 25 pddelete 29 pddisable 33 pdenable 36 pdls 43 pdmod 52 pdpause 58 pdpr 65 pdpromote 71 pdq 75 pdreorder 78 pdresubmit 81 pdresume 84 pdrm 87 pdset 92 pdspace 101 attributes
backlog attribute queue 638 backlog-lower-bound attribute queue 632 backlog-update-interval attribute queue 632 backlog-upper-bound attribute queue 633 backlogged attribute queue 633 barcode.tab configuration file ModWidth optional keyword 303 Ratio optional keyword 303 bars in commands xxvii base-printer attribute default document 471 document 471 bin-name component output-bin-numbers attribute, actual destination 413 bin-number component output-bin-numbers attribute, actual	arguments 143 build file format 142 description 142, 144 examples 143 flags 142 syntax 142 channel-attached printers, sensing 168 character-mappings-supported attribute actual destination 350 logical destination 601 chars attribute default document 474 document 474 chars option 243, 259 checkpoint-at-stacker attribute actual destination 350 checkpoint-formats-supported attribute actual destination 351 cms-proclink attribute default document 475 document 475 cms-product attribute default document 476 document 476 cmt utility	arguments lprafp 13 mkfntmap 15 pdaccount 18 pdclean 21 pdcreate 25 pddelete 29 pddisable 33 pdenable 36 pdls 43 pdmod 52 pdpause 58 pdpr 65 pdpromote 71 pdq 75 pdreorder 78 pdresubmit 81 pdresume 84 pdrm 87 pdset 92 pdshutdown 97 pdspace 101 attributes general description of 5
backlog attribute queue 638 backlog-lower-bound attribute queue 632 backlog-update-interval attribute queue 632 backlog-upper-bound attribute queue 633 backlogged attribute queue 633 barcode.tab configuration file ModWidth optional keyword 303 Ratio optional keyword 303 bars in commands xxvii base-printer attribute default document 471 document 471 bin-name component output-bin-numbers attribute, actual destination 413 bin-number component output-bin-numbers attribute, actual destination 413	arguments 143 build file format 142 description 142, 144 examples 143 flags 142 syntax 142 channel-attached printers, sensing 168 character-mappings-supported attribute actual destination 350 logical destination 601 chars attribute default document 474 document 474 chars option 243, 259 checkpoint-at-stacker attribute actual destination 350 checkpoint-formats-supported attribute actual destination 351 cms-proclink attribute default document 475 document 475 cms-product attribute default document 476 document 476 cmt utility build color mapping table 144	arguments lprafp 13 mkfntmap 15 pdaccount 18 pdclean 21 pdcreate 25 pddelete 29 pddisable 33 pdenable 36 pdls 43 pdmod 52 pdpause 58 pdpr 65 pdpromote 71 pdq 75 pdreorder 78 pdresubmit 81 pdresume 84 pdrm 87 pdset 92 pdshutdown 97 pdspace 101 attributes general description of 5 pdclean 21 pdcreate 25 pddelete 29
backlog attribute queue 638 backlog-lower-bound attribute queue 632 backlog-update-interval attribute queue 632 backlog-upper-bound attribute queue 633 backlogged attribute queue 633 barcode.tab configuration file ModWidth optional keyword 303 Ratio optional keyword 303 bars in commands xxvii base-printer attribute default document 471 document 471 bin-name component output-bin-numbers attribute, actual destination 413 bin-number component output-bin-numbers attribute, actual destination 413 bits-per-spot attribute	arguments 143 build file format 142 description 142, 144 examples 143 flags 142 syntax 142 channel-attached printers, sensing 168 character-mappings-supported attribute actual destination 350 logical destination 601 chars attribute default document 474 document 474 chars option 243, 259 checkpoint-at-stacker attribute actual destination 350 checkpoint-formats-supported attribute actual destination 351 cms-proclink attribute default document 475 document 475 cms-product attribute default document 476 document 476 cmt utility build color mapping table 144 flags 144	arguments lprafp 13 mkfntmap 15 pdaccount 18 pdclean 21 pdcreate 25 pddelete 29 pddisable 33 pdenable 36 pdls 43 pdmod 52 pdpause 58 pdpr 65 pdpromote 71 pdq 75 pdreorder 78 pdresubmit 81 pdresume 84 pdrm 87 pdset 92 pdshutdown 97 pdspace 101 attributes general description of 5 pdcreate 25
backlog attribute queue 638 backlog-lower-bound attribute queue 632 backlog-update-interval attribute queue 632 backlog-upper-bound attribute queue 633 backlogged attribute queue 633 barcode.tab configuration file ModWidth optional keyword 303 Ratio optional keyword 303 bars in commands xxvii base-printer attribute default document 471 document 471 bin-name component output-bin-numbers attribute, actual destination 413 bits-per-spot attribute default document 473 bits-per-spot attribute default document 473	arguments 143 build file format 142 description 142, 144 examples 143 flags 142 syntax 142 channel-attached printers, sensing 168 character-mappings-supported attribute actual destination 350 logical destination 601 chars attribute default document 474 document 474 chars option 243, 259 checkpoint-at-stacker attribute actual destination 350 checkpoint-formats-supported attribute actual destination 351 cms-proclink attribute default document 475 document 475 cms-product attribute default document 476 document 476 cmt utility build color mapping table 144 flags 144 syntax 144	arguments lprafp 13 mkfntmap 15 pdaccount 18 pdclean 21 pdcreate 25 pddelete 29 pddisable 33 pdenable 36 pdls 43 pdmod 52 pdpause 58 pdpr 65 pdpromote 71 pdq 75 pdreorder 78 pdresubmit 81 pdresume 84 pdrm 87 pdset 92 pdshutdown 97 pdspace 101 attributes general description of 5 pdclean 21 pdcreate 25 pddelete 29 pddisable 33 pdenable 36
backlog attribute queue 638 backlog-lower-bound attribute queue 632 backlog-update-interval attribute queue 632 backlog-upper-bound attribute queue 633 backlogged attribute queue 633 barcode.tab configuration file ModWidth optional keyword 303 Ratio optional keyword 303 bars in commands xxvii base-printer attribute default document 471 document 471 bin-name component output-bin-numbers attribute, actual destination 413 bits-per-spot attribute default document 473 bits-per-spot attribute default document 472 document 472	arguments 143 build file format 142 description 142, 144 examples 143 flags 142 syntax 142 channel-attached printers, sensing 168 character-mappings-supported attribute actual destination 350 logical destination 601 chars attribute default document 474 document 474 chars option 243, 259 checkpoint-at-stacker attribute actual destination 350 checkpoint-formats-supported attribute actual destination 351 cms-proclink attribute default document 475 document 475 cms-product attribute default document 476 document 476 cmt utility build color mapping table 144 flags 144 syntax 144 code page	arguments lprafp 13 mkfntmap 15 pdaccount 18 pdclean 21 pdcreate 25 pddelete 29 pddisable 33 pdenable 36 pdls 43 pdmod 52 pdpause 58 pdpr 65 pdpromote 71 pdq 75 pdreorder 78 pdresubmit 81 pdresume 84 pdrm 87 pdset 92 pdshutdown 97 pdspace 101 attributes general description of 5 pdclean 21 pdcreate 25 pddelete 29 pddisable 33 pdenable 36 pdls 40
backlog attribute queue 638 backlog-lower-bound attribute queue 632 backlog-update-interval attribute queue 632 backlog-upper-bound attribute queue 633 backlogged attribute queue 633 barcode.tab configuration file ModWidth optional keyword 303 Ratio optional keyword 303 bars in commands xxvii base-printer attribute default document 471 document 471 bin-name component output-bin-numbers attribute, actual destination 413 bits-per-spot attribute default document 473 bits-per-spot attribute default document 473	arguments 143 build file format 142 description 142, 144 examples 143 flags 142 syntax 142 channel-attached printers, sensing 168 character-mappings-supported attribute actual destination 350 logical destination 601 chars attribute default document 474 document 474 chars option 243, 259 checkpoint-at-stacker attribute actual destination 350 checkpoint-formats-supported attribute actual destination 351 cms-proclink attribute default document 475 document 475 cms-product attribute default document 476 document 476 cmt utility build color mapping table 144 flags 144 syntax 144 code page mapping ASCII to EBCDIC for	arguments lprafp 13 mkfntmap 15 pdaccount 18 pdclean 21 pdcreate 25 pddelete 29 pddisable 33 pdenable 36 pdls 43 pdmod 52 pdpause 58 pdpr 65 pdpromote 71 pdq 75 pdreorder 78 pdresubmit 81 pdresume 84 pdrm 87 pdset 92 pdshutdown 97 pdspace 101 attributes general description of 5 pdclean 21 pdcreate 25 pddelete 29 pddisable 33 pdenable 36
backlog attribute queue 638 backlog-lower-bound attribute queue 632 backlog-update-interval attribute queue 632 backlog-upper-bound attribute queue 633 backlogged attribute queue 633 barcode.tab configuration file ModWidth optional keyword 303 Ratio optional keyword 303 bars in commands xxvii base-printer attribute default document 471 document 471 bin-name component output-bin-numbers attribute, actual destination 413 bits-per-spot attribute default document 473 bits-per-spot attribute default document 472 document 472	arguments 143 build file format 142 description 142, 144 examples 143 flags 142 syntax 142 channel-attached printers, sensing 168 character-mappings-supported attribute actual destination 350 logical destination 601 chars attribute default document 474 document 474 chars option 243, 259 checkpoint-at-stacker attribute actual destination 350 checkpoint-formats-supported attribute actual destination 351 cms-proclink attribute default document 475 document 475 cms-product attribute default document 476 document 476 cmt utility build color mapping table 144 flags 144 syntax 144 code page	arguments lprafp 13 mkfntmap 15 pdaccount 18 pdclean 21 pdcreate 25 pddelete 29 pddisable 33 pdenable 36 pdls 43 pdmod 52 pdpause 58 pdpr 65 pdpromote 71 pdq 75 pdreorder 78 pdresubmit 81 pdresume 84 pdrm 87 pdset 92 pdshutdown 97 pdspace 101 attributes general description of 5 pdclean 21 pdcreate 25 pddelete 29 pddisable 33 pdenable 36 pdls 40

		1 / 1
commands (continued)	commands (continued)	commands (continued)
pdpromote 71	flags (continued)	syntax (continued)
pdq 74	pdpr 62	pdpr 61
pdreorder 78	pdpromote 70	pdpromote 70
pdresubmit 80	pdq 72	pdq 72,77
pdresume 84	pdreorder 77	pdresubmit 79
pdrm 87	pdresubmit 79	pdresume 83
pdset 91	pdresume 83	pdrm 86
pdshutdown 96	pdrm 86	pdset 89
1	1	pdshutdown 94
pdspace 100	pdset 90	1
description	pdshutdown 95	pdspace 99
lprafp 13	pdspace 100	syntax, general description of 4
mkfntmap 15	flags, general description of 4	commands, attributes
pdaccount 17	lprafp	object attributes
pdclean 20	description 13	pdcreate, documents 25
pdcreate 23	operators, filters	pdcreate, jobs 25
pddelete 28	pdls, filters 41	pdpr 65
pddisable 32	pdaccount	comment attribute
pdenable 35	description 17	
pdls 38	*	default job 555
± .	pdclean	job 555
pdmod 49	description 20	comments in option file 255
pdpause 54	pdcreate	completion-time attribute
pdpr 61	description 23	job 545, 587
pdpromote 70	pddelete	complex attributes
pdq 72	description 28	±
pdresubmit 79	pddisable	ascii-font-map attribute, actual
pdresume 83	description 32	destination 343
pdrm 86	pdenable	attribute-map attribute, actual
pdset 89	description 35	destination 346
±		input-trays-medium attribute, actual
pdshutdown 94	pdls	destination 389
pdspace 99	description 38	job-size-range-ready attribute
preorder 77	pdmod	actual destination 395
examples	description 49	job-size-range-supported attribute
lprafp 14	pdpause	actual destination 395
mkfntmap 16	description 54	
of documents, pdcreate 26	pdpr	logical destination 611
of jobs, pdcreate 26	description 61	notification-profile attribute
pdaccount 19	pdpromote	actual destination 407
pdclean 22	description 70	default job 577
pdcreate 26		job 577
	pdq	logical destination 613
pddelete 30	description 72	queue 635
pddisable 34	pdreorder	server 655
pdenable 37	description 77	notify-operator attribute
pdls 44	pdresubmit	actual destination 408
pdmod 52	description 79	queue 636
pdpause 60	pdresume	operators attribute
pdpr 66, 69	description 83	*
pdpromote 71	pdrm	actual destination 408
pdq 75	description 86	queue 636
pdreorder 78	pdset	output-bin-numbers attribute, actual
pdresubmit 82	description 89	destination 413
± .	pdshutdown	printer-resolutions-supported, actual
pdresume 85		destination 426
pdrm 87	description 94	psf-tray-characteristics attribute, actual
pdset 92	pdspace	destination 431
pdshutdown 97	description 99	results-profile attribute
pdspace 101	syntax	default job 585
flags	lprafp 13	job 585
lprafp 13	mkfntmap 15	*
pdaccount 17	pdaccount 17	specifying 334
pdclean 20	pdclean 20	components, complex attributes
pdcreate 24	pdcreate 23	bin name component,
pddelete 28	pddelete 28	output-bin-numbers attribute, actual
pddisable 32	pddisable 32	destination 413
1	1	bin number component,
pdenable 35	pdenable 35	output-bin-numbers attribute, actual
pdls 39	pdls 38	destination 413
pdmod 50	pdmod 49	BSD-flag component, attribute-map
pdpause 55	pdpause 54	attribute, actual destination 346
		attribute, actual destination 540

components, complex attributes	components, complex attributes	components, complex attributes
(continued)	(continued)	(continued)
delivery-address component	event-identifier component (continued)	medium-identifier component,
notification-profile attribute, actual	notification-profile attribute,	input-trays-medium attribute, actual
destination 407	default job 577	destination 390
notification-profile attribute,	notification-profile attribute,	output-bin component
default job 578	job 577	results-profile attribute, default
notification-profile attribute,	notification-profile attribute, logical	job 586
job 578	destination 614	results-profile attribute, job 586
notification-profile attribute, logical destination 614	notification-profile attribute,	results profile attribute default
notification-profile attribute,	queue 635 notification-profile attribute,	results-profile attribute, default job 586
queue 636	server 655	results-profile attribute, job 586
notification-profile attribute,	first-page component	tray-identification component,
server 655	page-select attribute,	input-trays-medium attribute, actual
notify-operator attribute, actual	document 519	destination 390
destination 409	font-escape component, actual	tray-number component,
notify-operator attribute,	destination 343	psf-tray-characteristics attribute,
queue 637	font-name component, actual	actual destination 433
operators attribute, actual	destination 343	upper-limit component
destination 409	Infoprint-attribute component,	job-size-range-ready attribute,
operators attribute, queue 637	attribute-map attribute, actual	actual destination 395
results-profile attribute, default	destination 346	job-size-range-supported attribute,
job 586	input-tray component,	actual destination 396
results-profile attribute, job 586	psf-tray-characteristics attribute,	job-size-range-supported attribute,
delivery-method component	actual destination 432	logical destination 611
notification-profile attribute, actual	job-bin-number component,	x-image-shift-range-supported
destination 407	psf-tray-characteristics attribute,	attribute, actual destination 456
notification-profile attribute,	actual destination 433	x-image-shift-range-supported
default job 578	job-copies component	attribute, logical destination 622
notification-profile attribute,	results-profile attribute, default	y-image-shift-range-supported
job 578	job 586	attribute, actual destination 457
notification-profile attribute, logical	results-profile attribute, job 586	y-image-shift-range-supported
destination 614	last-page component	attribute, logical destination 623
notification-profile attribute,	page-select attribute,	x-dimension component,
queue 636	document 519	medium-dimensions attribute,
notification-profile attribute,	locale component	medium 626
server 655	notification-profile attribute, actual	y-dimension component,
notify-operator attribute, actual	destination 408	medium-dimensions attribute, medium 626
destination 409	notification-profile attribute,	
notify-operator attribute, queue 637	default job 579	compressed-output attribute
operators attribute, actual	notification-profile attribute, job 579	default document 478
destination 409	notification-profile attribute, logical	document 478
operators attribute, queue 637	destination 614	configuration files
results-profile attribute, default	notification-profile attribute,	barcode.tab 303
job 586	queue 636	defcp.tab 305
results-profile attribute, job 586	notification-profile attribute,	fonts.tab 305
duplex-supported component,	server 656	for gif2afp transform 216
psf-tray-characteristics attribute,	lower-limit component	for jpeg2afp transform 230
actual destination 434	job-size-range-ready attribute,	for pcl2afp transform 276
event-comment component	actual destination 395	for pcl2afpd daemon 276
notification-profile attribute, actual	job-size-range-supported attribute,	for pdf2afp transform 297
destination 408	actual destination 396	for ps2afp transform 297
notification-profile attribute,	job-size-range-supported attribute,	for ps2afpd daemon 297
default job 578	logical destination 611	for sap2afp transform 302
notification-profile attribute,	x-image-shift-range-supported	for tiff2afp transform 318
job 578	attribute, actual destination 456	gif2afp.cfg 216
notification-profile attribute, logical	x-image-shift-range-supported	image.tab 308 jpeg2afp.cfg 230
destination 614	attribute, logical destination 622	pagedef.tab 309
notification-profile attribute,	y-image-shift-range-supported	pcl2afp 276
queue 636	attribute, actual destination 457	pcl2afpd 276
notification-profile attribute,	y-image-shift-range-supported	printer.tab 310
server 656	attribute, logical destination 623	ps2afp 297
event-identifier component	media-loaded component,	ps2afpd 297
notification-profile attribute, actual destination 407	psf-tray-characteristics attribute, actual destination 432	tiff2afp.cfg 318
desimation 40/	actual desiliation 432	xxxxyyyy.tab 311

configuring servers 155	data-fidelity-problem-reported-supported	default documents, attributes of
connection-timeout attribute	attribute (continued)	(continued)
actual destination 356	logical destination 603	email-from-address 492
content-orientation attribute	db2afp transform	email-to-address 493
default document 479	description 205	enable-settrap 493
document 479	files 208	fax-number 493, 494
content-orientations-supported attribute	flags 205	font-fidelity-action 494
actual destination 356	limitations 205	font-processing-messages 495
logical destination 601	syntax 205	font-resolution 495
context-address attribute	DCE (Distributed Computing	form-definition 496
resource context 641	Environment)	format 488
control currently printing sheets 99	authorize-jobs, logical	image-center x 497, 501
control-strip attribute default document 479	destination 600	image-center-y 498 image-fit 498
document 479	pdcrcds utility 154	image-lin 498 image-length 499
convert-to-ebcdic attribute	protected-attributes, actual	image-out-format 500
default document 480	destination 431	image-width 501
document 480	protected-attributes, logical	initial-value-document-identifier 503
convert-to-ebcdic-supported attribute	destination 618	input-exit 503
actual destination 357	protected-attributes, queue 638 protected-attributes, server 658	input-tray-select 504
logical destination 602	deadline-in-jeopardy attribute	job-start-wait 571
copies attribute	job 547	jog-between-job-copies 504
default document 480	,	list-of-managers 505
document 480	default-character-mapping attribute	logical-destinations-ready 505
copy-count attribute	default document 481 document 481	logical-printers-ready 505
default document 480		managers 505
document 480	default documents, attributes of	maximum-messages-printed 506
creating	account-text 469	maximum-transform-pages-
actual destinations 160	address2-text 470	ahead 506
commonly used media 157	address4 tout 470	message 507
default objects 155	address4-text 471 associated-server 471	mvs-class 507
Infoprint attributes files 149	base-printer 471	mvs-destination 507
Infoprint command scripts 149	bits-per-spot 472	mvs-forms 508
Infoprint directories 154	black-overprint 472	mvs-segment-id 508
Infoprint objects 23	building-text 473	name-text 509
current-backlog attribute	callback-number 473	new-line-option 509
queue 638	carriage-control-type 474	node-id-text 510
current-job-state attribute	chars 474	object-class 511
job 545 current-page-printing attribute	cms-proclink 475	orientation 479 originating-company-text 512
job 546	cms-product 476	other-options 486
customer fonts 307	color-bits-per-plane 352, 476	other-transform options 512
	color-bits-per-plane-supported 352	other-transform-options 668
D	color-mapping-table 477	output-appearance 513
	color-profile 353, 477	output-bin 513
d-s-s-requested attribute	color-profiles-supported 354	output-face-up 514
default job 551	color-toner-saver 355, 478	output-format 515
job 551	color-toner-saver-supported 355	overlay 516, 517
d2afp transform	compressed-output 478	overprint 517
description 209	content-orientation 479	page-clip 518
flags 210	control-strip 479 convert-to-ebcdic 480	page-definition 519
limitations 209 syntax 209	copies 480	page-media-select 519
daemons	copy-count 480	plex 521
mysprsd 188	data-fidelity-problem-reported 481	print-quality 521
pcl2apfd 190	default-character-mapping 481	printer-pass-through 486
ps2afpd 193	default-input-tray 482	programmer-text 522
startcbd 199	default-medium 483	resource context 522
startnotd 197	default-printer-resolution 484	resource-context-form-definition 525
stopcbd 201	department-text 484	resource-context-overlay 525
stopnotd 198	descriptor 485	resource-context-overlay 525 resource-context-page-definition 526
dashes in commands xxviii	destination-company-text 485	resource-context-page-definition 320
data-fidelity-problem-reported attribute	destination-pass-through 486	resource-context-user 529
default document 481	document-comment 486	resource-exit 530
document 481	document-finishing 487	room-text 530
data-fidelity-problem-reported-supported	document-format 488	scanner-correction 531
attribute	document-type 490	screen-frequency 531
actual destination 358	dot-shape 491	1 /

default documents, attributes of	default jobs, attributes of (continued)	description (continued)
(continued)	*	of commands (continued)
	results-profile 585	and the second s
segment-file-size 532	retention-period 566	pdpr 61
shared-formdef 532	start-message 570	pdpromote 70
shift-out-shift-in 533	default-medium attribute	pdq 72
sides 534	default document 483	pdreorder 77
start-on-new-sheet 535	document 483	pdresubmit 79
subject-text 535	default objects, creating 155	pdresume 83
table-reference-characters 535	default-printer-resolution attribute	pdrm 86
title-text 536	default document 484	pdset 89
transform-message-file-name 537	document 484	pdshutdown 94
type 490	default values for command and object	pdspace 99
user-id-text 538	attributes 333	of transforms
x-image-shift 538	defcp.tab file 305	d2afp 209
x-image-shift-back 539	1	db2afp 205
9	defining the attribute values of an	-
y-image-shift 540	object 89	gif2afp 212
y-image-shift-back 540	delete-segment-list attribute	jpeg2afp 226
default-font-fidelity-action attribute	default job 547	line2afp 240
actual destination 358	job 547	pcl2afp 264
default-font-resolution attribute	deleting Infoprint objects 28	pdf2afp 287
actual destination 359	delivery-address component	ps2afp 287
	notification-profile attribute	sap2afp 302
default-input-tray attribute	*	tiff2afp 313
actual destination 359	actual destination 407	of utilities
default document 482	default job 578	admingui 129
document 482	job 578	afpsplit 130
default jobs, attributes of	logical destination 614	1 1
actual-destinations-requested 543	queue 636	ainupod1 131
associated-server 544	server 655	ainupod2 132
auxiliary-sheet-selection 544	notify-operator attribute	ainupod3 133
	actual destination 408	ainurpt1 135
comment 555	queue 636	ainurpt2 136
d-s-s-requested 551	operators attribute	ainurpt3 137
delete-segment-list 547	actual destination 408	ainurpt4 139
descriptor 548		ainurpt5 140
destination-locations-requested 549	queue 636	ainurpt6 141
destination-models-requested 549	results-profile attribute	cfu 142
device-support-system-requested 551	default job 586	cmt 144
dss-requested 551	job 586	ipguiadv 146
end-message 558	delivery-method component	10
hold 559	notification-profile attribute	ipguiadvadm 147
initial-value-job-identifier 554	actual destination 407	ipguibasic 146
job-batch 555	default job 578	ipguibasicadm 147
job-comment 555	job 578	ipguidist 146
job-end-message 558	logical destination 614	ipguidistadm 147
,	queue 636	jsmigr 149
job-finishing 558	server 655	mvsprsd 188
job-hold 559		opergui 152
job-message-to-operator 562	operators attribute	pcl2afpd 190
job-originator 563	actual destination 408	pdadmin 153
job-priority 565	queue 636	pdcrcds 154
job-retention-period 566	results-profile attribute	pdcrdflt 155
job-rip-action 566	default job 586	pdcrmed 157
job-ripped-by-server 567	job 586	pdinitports 158
job-start-message 570	department-text attribute	1 1
list-of-managers 573	default document 484	pdmigpp 160
locations-requested 549	document 484	pdmincfg 162
logical-destinations-ready 574	description	pdmsg 164
logical-printers-ready 574	of commands	ps2afpd 193
		rc.iprsap 166
managers 573	lprafp 13	rc.pd 167
message 575	mkfntmap 15	setup 173
message-to-operator 562	pdaccount 17	start_server 177
models-requested 549	pdclean 20	startcbd 199
notification-profile 577	pdcreate 23	startnotd 197
object-class 579	pddelete 28	startppo 176
optimize-for-multiple-copies 580	pddisable 32	startsrv 179
originator 563	pdenable 35	stop_server 181
physical-printers-requested 543	pdls 38	
printer-locations-requested 549	pdmod 49	stopcbd 201
printer-models-requested 549	pdpause 54	stopnotd 198
1	L-L	

description (continued)	destination-state attribute	document-file-name attribute
t2file 185	actual destination 368	document 487
tdump 182	destination-states-supported attribute	document-finishing attribute
tlist 184	server 646	default document 487
descriptor attribute	destination-support-system attribute	document 487
actual destination 360	actual destination 369	document-finishings-supported attribut
auxiliary sheet 459	logical destination 606	actual destination 375
default document 485	destination support systems	document-format attribute
default job 548	3170 330	default document 488
log 593	AIX 330	document 488
logical destination 603	BSD 330, 331	document-formats-ripped-at-destination
medium 625	email 331	actual destination 376
queue 633	fax 331	document-formats-supported attribute
resource context 641	Infoprint 2000 330	actual destination 376, 667
server 645	IPP 331	logical destination 607
transform 666	Passthrough 331	document-number attribute
destination-associated-destinations	PSF 330, 331	document 489
attribute 604	destination-support-systems-supported	document-sequence-number attribute
logical destination 604	attribute	document 489
destination-command attribute	server 646	document-type attribute
actual destination 360	destination-tcpip-internet-address	default document 490
destination-company-text attribute	attribute	document 490
default document 485, 512	actual destination 370	document-types-supported attribute
document 485, 512	destination-tcpip-port-number attribute	actual destination 378
destination-data-stream attribute	actual destination 371	logical destination 608
actual destination 361	destinations-assigned attribute	documents, attributes of
destination-initial-value-document	job 550	account-text 469
attribute	destinations-ready attribute	address1-text 469
logical destination 604	logical destination 607	address2-text 470
destination-initial-value-job attribute	destinations-used attribute	address3-text 470
job 548	job 551	address4-text 471
logical destination 604	device-name attribute	base-printer 471
destination-locations attribute	actual destination 372	bits-per-spot 472
actual destination 362	device-support-system attribute	black-overprint 472
logical destination 605	actual destination 369	building-text 473
destination-locations-requested attribute	logical destination 606	callback-number 473
default job 549 job 549	device-support-system-requested attribute	carriage-control-type 474
destination-model attribute	default job 551	chars 474
actual destination 363	job 551 directories	cms-proclink 475
		cms-product 476
logical destination 605 destination-models-requested attribute	/usr/lpd/pio/predef 363	color-bits-per-plane 476
default job 549	/usr/lpd/pio/predef 377	color-mapping-table 477
job 549	/usr/lpp/pd/attr 336 font 247	color-profile 477
destination-name attribute	fonts 247	color-toner-saver 478
actual destination 364	form definition 245	compressed-output 478
logical destination 605	overlay 252	content-orientation 479
destination-name-requested attribute	overlays 252	control-strip 479
job 550	page definition 255	convert-to-ebcdic 480
destination-needs-attention-time attribute	page segment 256	copies 480
actual destination 364	user 259	copy-count 480
destination-needs-key-operator-attention-	directories, creating 154	data-fidelity-problem-reported 481
time attribute		default-character-mapping 481
actual destination 365	disabling destinations 32	default-input-tray 482
	discard-time attribute	default-medium 483
destination-pass-through attribute	job 557	default-printer-resolution 484
actual destination 365	displaying information about	department-text 484
default document 486	messages 164	destination-company-text 485
document 486	document-attributes-supported attribute	destination-initial-value-
destination-poll-intervall attribute	actual destination 373	document 485
actual destination 366	server 647	destination-pass-through 486
destination-realization attribute	document-comment attribute	document-comment 486
actual destination 366	default document 486	document-content 486
logical destination 606	document 486	document-content-list 487
destination-register-threshold attribute	document-content attribute	document-file-name 487
actual destination 366	document 486	document-finishing 487
destination-release-timer attribute	document-content-list attribute	document-format 488
actual destination 367	document 487	document-sequence-number 489

locuments, attributes of (continued)	documents, attributes of (continued)	end-message attribute
document-type 490	resource-context-presentation-object-	default job 558
dot-shape 491	container 528	job 558
email-from-address 492	resource-context-user 529	,
email-to-address 493	resource-exit 530	end-message-supported attribute
enable-settrap 493	room-text 530	actual destination 381
fax-number 493	scanner-correction 531	logical destination 609
fax-to-name 494	screen-frequency 531	end-sheets-supported attribute
	1 ,	actual destination 382
file-name 487	segment-file-size 532	
font-fidelity-action 494	sequence-number 489	environment variables
font-processing-messages 495	shared-formdef 532	GIF2AFP_option 674
font-resolution 495	shift-out-shift-in 533	IPR_PREDPROD 674
form-definition 496	sides 534	JPEG2AFP_option 674
format 488	start-on-new-sheet 535	LANG 676
halftone 496	subject-text 535	LC_ALL 676
image-center-x 497	table-reference-characters 535	LC_CTYPE 676
image-center-y 498	title-text 536	LC_MESSAGES 676
image-fit 498	transfer-method 536	LC_MONETARY 676
image-length 499	transform-message-file-name 537	
image-out-format 500	transform-output-file-name 537	LC_NUMERIC 676
ĕ	-	LC_TIME 676
image-scale 501	type 490	MANPATH 674
image-width 501	used for job scheduling 719	NLSPATH 676
initial-value-document 502	used for job validation 719	PATH 673
input-exit 503	user-id-text 538	PD_CONFIRM_DELETE 20, 28, 86
input-tray-select 504	x-image-shift 538, 539	673
jog-between-job-copies 504	y-image-shift 540	PD_ENABLE_TIMEOUT 674
maximum-messages-printed 506	y-image-shift-back 540	PD_LISTEN_COUNT 674
maximum-transform-pages-	dot-shape attribute	
ahead 506	default document 491	PD_SOCKET 674
mvs-class 507	document 491	PDBASE 674
		PDIDTABLE 673
mvs-destination 507	double quotation marks in	PDNAMESP 675
mvs-forms 508	commands xxviii	PDPATH 8, 673
mvs-segment-id 508	dss-job-message-disposition attribute	PDPRINTER 61, 72, 673
name-text 509	actual destination 379	PPO_CANCEL_ALL_OPTION 675
new-line-option 509	dss-job-message-log-size attribute	PPO_DEFAULT_ENV 675
node-id-text 510	actual destination 379	PPO_FORM 675
number-up 510	dss-job-message-log-wrap attribute	PPO_JOB_BATCH 675
object-class 511	actual destination 380	
octet-count 511	dss-requested attribute	PPO_JOB_DETAILS_ATTRS 675
orientation 479	default job 551	PPO_LP 675
	*	PPO_LPS 675
originating-company-text 512	job 551	PPO_PP_ATTRS 675
other-options 486	dummy form definition 250, 254	PPO_PPS 675
other-transform options 512	duplex-supported component	PPO_QUEUE 675
output-appearance 513	psf-tray-characteristics attribute, actual	PPO_QUEUE_ATTRS 676
output-bin 513	destination 434	PPO_QUEUE_INFO_FILE 676
output-face-up 514		PPO_SERVER 676
output-format 515		PPO_TRACE_FILE 676
overlay 516	E	PSFDBLANG 674
overlay-back 516		PSFPATH 674
overlay-front 517	ebcdic-character-mapping attribute	
overprint 517	actual destination 380	table of 673
	ellipsis in commands xxvii	TIFF2AFP_option 675
page-clip 518	email destination support system	TYPESETTER 675
page-count 518	(DSS) 331	XBMLANGPATH 675
page-definition 519	email-from-address attribute	equals signs in commands xxviii
page-media-select 519	default document 492	1 0
page-select 519	document 492	estimated-completion-time attribute
plex 521		job 552
print-quality 521	email-to-address attribute	estimated-processing-time attribute
printer-initial-value-document 485	default document 493	
printer-pass-through 486	document 493	job 553
	enable-settrap attribute	event-comment component
programmer-text 522	default document 493	notification-profile attribute
resource-context 522	document 493	actual destination 408
resource-context-font 524	enabled attribute	default job 578
resource-context-form-definition 525	actual destination 381	
resource-context-overlay 525		job 578
resource-context-page-definition 526	log 594	logical destination 614
resource-context-page-segment 527	logical destination 608	queue 636
100	enabling destinations 35	server 656

event-identifier component	examples (continued)	files (continued)
notification-profile attribute	of utilities (continued)	output (continued)
actual destination 407	setup 175	for ps2afp transform 293
default job 577	start_server 178	pagedef.tab 309
	startcbd 199	pcl2afp 276
job 577		
logical destination 614	startppo 176	pcl2afpd 276
queue 635	startsrv 180	printer.tab 310
server 655	stop_server 181	ps2afp 297
events-supported attribute	stopcbd 201	ps2afpd 297
server 647	t2file 185	readme xxiv
	tdump 182	S9148.CPA 307
examples	tlist 184	tiff2afp.cfg 318
of commands	exits	xxxxyyyy.tab 311
lprafp 14	input 250	files, MO:DCA-P, extracting pages 130
mkfntmap 16	output 252	0.10
pdaccount 19	resource 257	filters
pdclean 22	resource 237	operators, pdls command 41
pdcreate 26		first-page component
pddelete 30	_	page-select attribute
pddisable 34	F	document 519
1	fax destination support system	flags
pdenable 37	(DSS) 331	8
pdls 44	` /	general description of 4
pdmod 52	fax-number attribute	line2afp 242
pdpause 60	default document 493	of commands
pdpr 66, 69	document 493	lprafp 13
pdpromote 71	fax-to-name attribute	pdclean 20
pdq 75	default document 494	pdcreate 24
pdreorder 78	document 494	pddelete 28
pdresubmit 82	fdeflib option 245	pddisable 32
pdresume 85	file-name attribute	pdenable 35
1	document 487	±
pdrm 87	file names	pdls 39
pdset 92		pdmod 50
pdshutdown 97	of form definitions 249	pdpause 55
pdspace 101	of input file 251	pdpr 62
of transforms	of output file 252	pdpromote 70
line2afp 260	of page definitions 253	pdq 72
pcl2afp 278	specified with inputdd option 251	pdreorder 77
pdf2afp 299	specified with outputdd option 252	pdresubmit 79
ps2afp 299	specified with pagedef option 253	pdresume 83
sap2afp 312	file-reference document, definition 487,	pdrm 86
of utilities	490	pdset 90
	fileformat option 246	±
admingui 129		pdshutdown 95
afpsplit 130	files	pdspace 100
ainupod1 131	/etc/services 158	of transforms
ainupod2 132	barcode.tab 303	d2afp 210
ainupod3 133	defcp.tab 305	db2afp 205
ainurpt1 135	fonts.tab 305	pcl2afp 266
ainurpt2 136	for transforms	pdf2afp 289
ainurpt3 137	db2afp 208	ps2afp 289
ainurpt4 139	gif2afp 216	sap2afp 302
ainurpt5 140	jpeg2afp 230	of utilities
ainurpt6 141	line2afp 262	admingui 129
cfu 143	pcl2afp 276, 285	afpsplit 130
	1 1	
ipguibasic 146, 147	pdf2afp 297, 300	cfu 142
jsmigr 150	ps2afp 297, 300	cmt 144
mvsprsd 189	sap2afp 302	mvsprsd 188
opergui 152	tiff2afp 318	opergui 152
pcl2afpd 192	for utilities	pcl2afpd 190
pdadmin 153	pcl2afpd 192	pdcrdflt 155
pdcrcds 154	ps2afpd 195	pdinitports 158
pdcrdflt 156	gif2afp.cfg 216	pdmincfg 162
pdcrmed 157	image.tab 308	pdmsg 164
pdinitports 159	input	ps2afpd 193
pdmigpp 161	for line2afp 251	setup 173
1 011	1	
pdmincfg 162	jpeg2afp.cfg 230	start_server 177
pdmsg 164	output	startspl 176
ps2afpd 195	for line2afp transform 252	startsrv 179
sense 169, 171	for pdf2afp transform 293	stop_server 181

7 () ()		- A
flags (continued)	gif2afp transform (continued)	Infoprint Installer, starting 173
t2file 185	syntax 212	Infoprint Manager Administration GUI,
tdump 182	global characters (wildcards) 6	starting 147
tlist 184	global-id attribute	Infoprint Manager Operations GUI,
_	job 560	starting 146
font-escape component		9
actual destination 343	global job identifier	Infoprint SMIT production print
font-fidelity-action attribute	global-id, job-attribute 560	operations interface, starting 176
default document 494	job-identifier, job-attribute 560	initial-value-document attribute
document 494	new-job-identifier, job-attribute 576	document 502
font map file keyword on ps2afp or	glossary 733	initial-value-document-identifier attribute
pdf2afp transform 290		default document 503
font-name component		initial-value-job attribute
actual destination 343	Н	job 554
	**	
font-processing-messages attribute	halftone attribute	initial-value-job-identifier attribute
default document 495	default document 496	default job 554
document 495	document 496	initially settable attribute listing
font-resolution attribute	halftones-supported attribute	actual destination 337
default document 495	actual destination 384	document 464
document 495	height	job 542
font-resolutions-supported attribute	0	log 593
actual destination 383	PostScript image 292	logical destination 598
fontlib option 247	highlighting conventions xxvi	inline resources
	hostname attribute	
fonts	server 660	for PDF jobs 300
converting ASCII to EBCDIC 251	hostname of the server 660	for PostScript jobs 300
directory 247	HRI character 303	form definition 250
search path for line data	human readable interface (HRI)	page definition 254
transform 247	character 303	inpexit option 250
specifying with chars 243	character 505	input-data-user-exit attribute
fonts.tab file 305		actual destination 389
force-destination-setup attribute		
	1	input exit 250
actual destination 383	i-p-address attribute	input-exit attribute
force-printer-setup attribute	server 660	default document 503
actual destination 383		document 503
form-definition attribute	image-center-x attribute	input files
actual destination 384	default document 497	specifying file name 251
default document 496	document 497	specifying format 246
document 496	image-center-y attribute	input-tray component
form definitions	default document 498	psf-tray-characteristics attribute, actual
	document 498	
default 723	image-fit attribute	destination 432
file name 249	default document 498	input-tray-select attribute
for 11 by 17 inch paper 725		default document 504
for envelopes 725	document 498	document 504
for n_up page positioning 727	image-fit-supported attribute	input-trays-medium attribute
for pre-punched paper 728	actual destination 386	actual destination 389
general purpose 723	image-length attribute	input-trays-supported attribute
inline 250	actual destination 386	actual destination 391
printer-model specific 729	default document 499	logical destination 610
1	document 499	0
search path for line data	image-out-format	inputdd option 251
transform 245	default document 500	installer, starting 173
specified with formdef option 249		internet address of the host
supplied with Infoprint 723	document 500	processor 660
with a 0,0 offset 726	image-out-formats-supported	intervening-jobs attribute
format	actual destination 387	job 554
of input file 246	logical destination 609	intervention-timer attribute
format attribute	image output 250	
default document 488	image-scale attribute	actual destination 391
	default document 501	ip-address attribute
document 488	document 501	server 660
formatted-job-ticket-content attribute		ipguiadv utility
job 553	image.tab file 308	description 146, 147
formdef option 249	image-width attribute	syntax 146, 147
	actual destination 388	
G	default document 501	ipguibasic utility
G	document 501	description 146, 147
gif2afp transform	imageout option 250	examples 146, 147
configuration file 216	images	syntax 146, 147
description 212	resolution 294	ipguidist utility
limitations 217	Infoprint 2000 destination support system	description 146, 147
	(÷
options 217	(DSS) 330	syntax 146, 147

IPP destination support system (DSS) 331	job-priority attribute (continued) job 565	jobs, attributes of <i>(continued)</i> estimated-processing-time 553
(200) 001	job-retain-until attribute	formatted-job-ticket-content 553
1	job 565	global-id 560
	job-retention-period attribute	hold 559
job-attributes-supported attribute	default job 566	initial-value-job 554
actual destination 392	job 566	intervening-jobs 554
server 649	job-retry-count-limit attribute	job-batch 555
job-batch attribute	actual destination 394	job-client-id 555
default job 555 job 555	job-retry-interval attribute	job-comment 555
job-batches-ready attribute	actual destination 394	job-complexity 556
actual destination 392	job-rip-action attribute	job-copies-completed 556
job-bin-number component	default job 566	job-deadline-time 557
psf-tray-characteristics attribute, actual	job 566	job-discard-time 557
destination 433	job-rip-actions-supported attribute	job-end-message 558
job-client-id attribute	actual destination 395	job-finishing 558
job 555	job-ripped-by-server attribute	job-hold 559 job-identifier 560
job-comment attribute	default job 567 job 567	job-log 560
default job 555	job scripts, PSF for AIX, migrating 149	job-nedia-sheet-count 561
job 555	job-size attribute	job-message-from-administrator 561
job-complexity attribute	job 590	job-message-to-operator 562
job 556	job-size-range-ready attribute	job-name 562
job-copies-completed attribute	actual destination 395	job-originator 563
job 556	job-size-range-supported attribute	job-owner 563
job-copies component	actual destination 396	job-page-count 564
results-profile attribute	logical destination 611	job-print-after 564
default job 586	job-start-message attribute	job-priority 565
job 586	default job 570	job-retain-until 565
job-deadline-time attribute	job 570	job-retention-period 566
job 557	job-start-wait attribute	job-rip-action 566
job-discard-time attribute	job 571	job-ripped-by-server 567
job 557	job-start-wait-supported attribute	job-size 590
job-end-message attribute	job 397	job-start-message 570
default job 558	job-state attribute	job-start-wait 571
job 558	job 545	job-state 545
job-finishing attribute	job-state-reasons attribute	job-state-reasons 571
default job 558	job 571	job-submission-complete 573
job 558 job-finishings-supported attribute	job-states-supported attribute	job-ticket-content 553
actual destination 393	server 649	last-accessor 576
job-hold attribute	job-submission-complete attribute	last-modifier 576
default job 559	job 573	locations-requested 549
job 559	job-submission-timer attribute	logical-printer-requested 550
job-identifier attribute	server 650	media-sheet-count 561
job 560	job-ticket-content attribute	media-sheets-completed 575 message-from-administrator 561
job-log attribute	job 553	message-to-operator 562
job 560	jobs, attributes of	models-requested 549
job-media-sheet-count attribute	actual-destinations-requested 543	modification-time 576
job 561	auxiliary-sheet-selection 544	name 562
job-message-from-administrator attribute	comment 555	name-of-last-accessor 576
job 561	completion-time 545	new-job-identifier 576
job-message-to-operator attribute	current-job-state 545	notification-profile 577
default job 562	current-page-printing 546	number-of-documents 579
job 562	d-s-s-requested 551	object-class 579
job-name attribute	deadline-in-jeopardy 547	octets-completed 580
job 562	delete-segment-list 547	optimize-for-multiple-copies 580
job-originator attribute	destination-initial-value-job 548	originator 563
default job 563	destination-locations-requested 549 destination-models-requested 549	owner 563
job 563 job-owner attribute	destination-models-requested 549 destination-name-requested 550	pages-completed 581
job 563	destination-name-requested 550 destinations-assigned 550	physical-printers-requested 543
job-page-count	destinations-used 551	position-in-queue 554
job 564	device-support-system-requested 551	previous-job-state 582
job-print-after attribute	discard-time 557	previous-state 582
job 564	dss-requested 551	print-after 564
job-priority attribute	end-message 558	printer-initial-value-job 548 printer-locations-requested 549
default job 565	estimated-completion-time 552	Printer-rocations-requested 347

jobs, attributes of (continued)	keywords (continued)	locale component
printer-models-requested 549	ps2afp transform (continued)	notification-profile attribute
printer-name-requested 550	output file 293	actual destination 408
printer-requested 550	port 293	default job 579
printers-assigned 550	resolution 294	job 579
printers-used 551	selected pages 294	logical destination 614
processing-time 583	server name 294	queue 636
queue-assigned 584	server time out 295	server 656
queue-position 554	width of image 295	locations attribute
reasons 571	X offset 296	actual destination 362
required-resources-not-ready 584	Y offset 296	logical destination 605
required-resources-not-supported 585		locations-requested attribute
results-profile 585		default job 549
retained-time 587	L	job 549
retention-period 566	last-accessor attribute	log-accounting data attribute
start-message 570	job 576	actual destination 398
started-printing-time 587	last-modifier attribute	server 651
state-reasons 571	job 576	log-address attribute
submission-time 587		log 594
tape-exit 588	last-page component	log-identifier attribute
tape-format 588	page-select attribute	log 594
tape-labeled 589	document 519	log-message attribute
tape-maximum-block-size 589	length	log 595
tape-rewind-before 590	PostScript image 292	log-severity attribute
tape-rewind-unload 590	length keyword	log 595
ticket-content 553	pdf2afp transform 292	log-size attribute
total-job-octets 590	ps2afp transform 292	log 596
used for job scheduling 719 used for job validation 719	limitations	log-trace-groups attribute
user-locale 591	of transforms	log 596
user-name 591	d2afp 209	log-type attribute
jog-between-job-copies	db2afp 205	log 596
default document 504	gif2afp 217	log-wrap attribute
document 504	jpeg2afp 231	log 597
jpeg2afp transform	pcl2afp 265	logical destinations, attributes of
configuration file 230	pdf2afp 289	associated-queue 599
description 226	ps2afp 289	associated-server 599
limitations 231	tiff2afp 319	authorize-jobs 600
options 231	line data	auxiliary-sheet-selections-
syntax 226	examples of printing	supported 600
jsmigr utility	S/370 file 260	carriage-control-types-supported 601
arguments 150	unformatted ASCII 260	character-mappings-supported 601
description 149	search paths for resources	content-orientations-supported 601
examples 150	AFP resources 259	convert-to-ebcdic-supported 602
syntax 149	fonts 247	data-fidelity-problem-reported-
	form definitions 245	supported 603
	overlays 252	descriptor 603
K	page definitions 255	destination-associated- destinations 604
keywords	page segments 256	
pdf2afp transform	system resources 258	destination-initial-value- document 604
height of image 292	line2afp transform	destination-initial-value-job 604
length of image 292	examples 260	destination-locations 605
maximum memory 293	files 262	destination-nodel 605
output file 293	flags 242	destination-model 605
port 293	syntax 239, 240	destination-realization 606
quiet 294	list-of-managers attribute	destination-support-system 606
resolution 294	actual destination 398	destinations-ready 607
selected pages 294	default document 505	device-support-system 606
server name 294	default job 573	document-formats-supported 607
server time out 295	logical destination 611	document-types-supported 608
width of image 295	queue 634	enabled 608
X offset 296	server 650	end-message-supported 609
Y offset 296	listing attribute values 38	image-out-formats-supported 609
ps2afp transform	listing of attributes used of job validation	input-trays-supported 610
height of image 292	and scheduling 719	job-size-range-supported 611
length of image 292	locale attribute	list-of-managers 611
maximum memory 293	server 651	locations 605

logical destinations, attributes of	logs, attributes of (continued)	maximum-presentation-object-containers-
(continued)	log-address 594	to-keep attribute
logical-printer 605	log-identifier 594	actual destination 402
managers 611	log-messages 595	maximum-raster-rips attribute
maximum-copies-supported 612	log-severity 595	server 653
media-supported 612	log-size 596	maximum-segments-to-keep attribute
message 613	log-trace-groups 596	actual destination 403
model 605	log-type 596	maximum-transform-pages-ahead
notification-profile 613	log-wrap 597	attribute
nt-drivers 455, 621	object-class 597	default document 506
object-class 615	lower-limit component	document 506
orientations-supported 601	job-size-range-ready attribute	media, attributes of
os2-driver-names 615	actual destination 395	associated-server 624
os2-drivers 615	job-size-range-supported attribute	descriptor 625
page-select-supported 616	actual destination 396	medium-color 625
plexes-supported 617	logical destination 611	medium-dimensions 625
print-qualities-supported 617	x-image-shift-range-supported	medium-form-parts 626
printer 605	attribute	medium-holes-count 626
printer-associated-printers 604	actual destination 456	medium-identifier 627
printer-initial-value-document 604	logical destination 622	medium-sides 627
printer-initial-value-job 604	y-image-shift-range-supported	medium-size 628
printer-initial-value-job 604 printer-locations 605	attribute	medium-type 628
printer-model 605	actual destination 457	medium-wight 629
*		=
printer-name 605 printer-realization 606	logical destination 623	message 629 object-class 629
1	lprafp command	,
printers-ready 607 protected-attributes 618	arguments 13 examples 14	media, creating commonly used 157 media-loaded component
qualities-supported 617	files 14	psf-tray-characteristics attribute, actual
sides-supported 619	flags 13	destination 432
start-message-supported 619	syntax 13	media-ready attribute
table-reference-characters-	Sylitax 13	actual destination 403
supported 619		media-sheet-count attribute
± ±	R/I	
used for job validation 719	M	job 561
windows drivers 620	machine code carriage-control	media-sheets-completed attribute
windows at driver names 455, 621	characters 243	job 575
windows nt drivers 455, 621	managers attribute	media-supported attribute
windows-nt-drivers 455, 621	actual destination 398	actual destination 404
x-image-shift-supported 622	default document 505	logical destination 612
y-image-shift-supported 622	default job 573	medium-color attribute medium 625
logical-destinations-assigned	logical destination 611	
actual destination 399	queue 634	medium-dimensions attribute medium 625
logical-destinations-assigned attribute	server 650	
queue 634	margins of PDF images	medium-form-parts attribute
logical-destinations-ready attribute	X offset 296	medium 626
default document 505	Y offset 296	medium-holes-count attribute
default job 574	margins of PostScript images	medium 626
queue 634	X offset 296	medium-identifier attribute
server 652	Y offset 296	medium 627
logical-destinations-supported attribute	maximum-barco-rips attribute	medium-identifier component
server 652	server 653	input-trays-medium attribute, actual
logical-printer attribute	maximum-concurrent-jobs attribute	destination 390
logical destination 605	actual destination 400	medium-sides attribute
logical-printer-requested attribute	maximum-copies-supported attribute	medium 627
job 550	actual destination 401	medium-size attribute
logical-printers-assigned attribute	logical destination 612	medium 628
queue 634	maximum-fonts-to-keep attribute	medium-type attribute
logical-printers-ready attribute	actual destination 401	medium 628
default document 505	maximum memory keyword	medium-weight attribute
default job 574	pdf2afp transform 293	medium-weight 629
queue 634	ps2afp transform 293	message attribute
server 652	maximum-messages-printed attribute	actual destination 405
logical-printers-supported attribute	default document 506	default document 507
server 652	document 506	default job 575
logs, attributes of	maximum-non-raster-rips attribute	logical destination 613
associated-server 593	server 653	medium 629
descriptor 593	maximum-overlays-to-keep attribute	queue 635
enabled 594	actual destination 402	server 654
CHADICA J/T	actual acottitation 402	3C1 V C1 UJ-4

message-count, command attribute pdls 42 message-font-type attribute actual destination 405 message-font-definition attribute actual destination 406 message-fone-administrator attribute actual destination 406 message-fone-administrator attribute default document 509 mode-id-text attribute default document 509 document 509 mode-id-text attribute default document 500 document 500 model attribute actual destination about 164 migrating an existing printer 160 migrating PSF for AIX job scripts 149 mkfntmap command arguments 15 description 15 examples 16 syntax 15 description 15 examples 16 syntax 15 doserone default document 509 document 509 model-attribute actual destination 605 model-sr-quested attribute actual destination 605 model-sr-quested attribute default job 549 giob 549 modification-time attribute server 654 modify-individual-document-supported attribute server 654 modify-individual-document-supported attribute server 654 modify-individual-document-supported attribute server 654 modify-individual-document-supported attribute default document 507 document 507 document 507 document 507 mws-destination attribute default document 507 document 507 mws-destination attribute default document 507 mws-destination attribute default document 507 mws-destination attribute default document 508 document 508 document 508 missessement 508 model-actual destination 608 missessement 508 missessement 508 missessement 508 missessement 486 missessement 508 document 508 missessement 486 missessement 508 missessement 486 missessement 508 missessement 508 missessement 486 missessement 508 missessement 486 missessement 509 missessement 486 missessement 509 missessement 509 missessement 509 missessement 509 missessement 486 missessement 509 missesseme	ciptions of 3 ribute s of 3
message-form-definition attribute actual destination 405 message-form-definition attribute actual destination 406 message-toop-rand-ministrator attribute default document 509 document 509 new-line-option attribute default document 509 document 509 node-id-text attribute default document 509 node-id-text attribute default document 510 non-process-runout-timer attribute actual destination 406 notational conventions xxvii notification client daemon 151 notification-delivery-methods-supported attribute actual destination 406 notational conventions xxvii notification client daemon 151 notification client daemon 151 notification-delivery-methods-supported attribute server 654 notification profile 334 notification profile 334 notification-profile attribute actual destination 363 logical destination 363 logical destination 406 notational conventions xxvii actual destination 406 notational conventions xxvii notification client daemon 151 notification client daemon 151 notification profile 334 notification profile 334 notification-profile attribute actual destination 407 default job 549 job 549 modification-time attribute default job 549 job 549 modification-time attribute default job 549 job 550 modification-time attribute default document-supported attribute server 654 modifying attributes of submitted jobs 49 ModWildh optional keyword attribute actual destination 408 queue 636 queue 636 queue 636 queue 636 queue 637 notify-operator attribute actual destination 408 queue 636 queue 636 queue 636 poptions of transforms git2afp 217 jop2afp 231 tiff2afp 219 orientation attribute default document 475 document 509 officet-stacking-available at actual destination 416 notational conventions xxvii actual destination 407 default job 577 logical destination 407 offication-profile attribute actual destination 408 queue 636 queue 636 queue 636 queue 636 primitive	riptions of 3 ribute s of 3 ribute
actual destination 405 message-from-administrator attribute actual destination 406 message-from-administrator attribute job 561 message-to-operator attribute default job 562 job 562 messages specifying where written 252 messages specifying where written 252 messages, displaying information about 164 migrating PSF for AIX job scripts 149 minimum configuration, setting up 162 mk/fmtap command arguments 15 description 15 examples 16 syntax 15 description 15 examples 16 syntax 15 model attribute actual destination 363 logical destination 605 model-srequested attribute default job 577 job 577 modification-time attribute job 576 modification-time attribute job 576 modify-individual-document-supported attribute server 654 notification profile 334 notification profile 334 notification profile 334 notification-profile attribute actual destination 407 default job 577 job 577 modify-individual-document-supported attribute server 656 modify-individual-document-supported attribute server 657 modify-individual-document-supported attribute server 656 modify-individual-document-supported attribute server 657 modify-individual-document-supported attribute server 656 modify-individual-document-supported attribute server 657 modify-individual-document-supported attribute job 579 modify-individual-document-supported attribute job 580 job 580 job 580 options of transforms gif2afp 217	riptions of 3 ribute s of 3 ribute
message-form-definition attribute actual destination 406 message-form-administrator attribute job 561 message-to-operator attribute default job 562 messages, displaying information about 164 migrating PSF for AIX job scripts 149 minimum configuration, setting up 162 migrating an existing printer 160 migrating PSF for AIX job scripts 149 minimum configuration, setting up 162 more description 15 examples 16 syntax 15 syntax 15 syntax 15 syntax 15 classes 689 list of 679 notification events oberary for file attribute actual destination 407 default job 577 logical destination 613 queue 635 oprators attribute default document supported	riptions of 3 ribute s of 3 ribute
actual destination 406 message-from-administrator attribute job 561 message-to-operator attribute default job 562 job 562 messages specifying where written 252 messages, displaying information about 164 migrating an existing printer 160 migrating PSF for AIX job Scripts 149 minimum configuration, setting up 162 minimum configuration is 5 description 15 examples 16 syntax 15 description 15 examples 16 syntax 15 notification events classes 689 list of 679 notification events classes 689 list of 679 notification profile 334 notification-profile attribute actual destination 407 default job 577 job 577 models-requested attribute default document-supported attribute actual destination 613 queue 636 queue 636 poptimize for-multiple-copi actual destination 410 default job 580 job 580 options options of transforms gif2afp 217 job 580 optimize for-multiple-copi actual destination 410 default job 580 job 580 options of transforms gif2afp 217 job 580 ofset-stasses-supported attribute actual destination 406 document 510 non-process-runout-timer attribute actual destination 406 notational conventions xxvii notification events classes 689 list of 679 notification events classes 689 list of 679 notification events classes 689 list of 679 notification profile 334 notification-profile attribute actual destination 613 queue 635 server 655 notify-operator attribute server 655 notify-operator attribute server 657 notify-operator attribute server 657 notification events classes 689 list of 679 notification events classes 689	ribute s of 3 ribute
message-from-administrator attribute job 561 message-to-operator attribute default job 562 messages specifying where written 252 messages specifying where written 252 messages, displaying information about 164 migrating printer 160 motheration deliteration 150 mothication deliteratio	ribute s of 3 ribute
job 561 default document 509 document 509 document 509 mode-id-text attribute default job 562 job 562 messages specifying where written 252 messages, displaying information about 164 migrating PS for AIX job scripts 149 minimum configuration, setting up 162 mkfntmap command arguments 15 description 15 examples 16 syntax 15 MO:DCA-P files, extracting pages 130 model stribute actual destination 363 logical destination 605 model-srequested attribute default job 549 modiffication-time attribute job 576 modiffication-time attribute job 579 modiffication-time attribute job 576 modiffying attributes of submitted jobs 49 modiffying attributes of submitted pobs 654 modifying attributes of submitted pobs 659 multiple-documents-supported attribute server 657 mt-divers attribute default document 507 document 507 mvs-destination attribute default document 508 default document 508 default document 508 default document 509 object-classes-supported attribute default document 510 object-classes-supported attribute default document 511 obtification-profile attribute actual destination 406 opergui utility description 152 examples 152 flags 152 optimize for-multiple-copi actual destination 410 operators attribute default job 577 optimize for-multiple-copi primation-410 operators attribute default job 577 optimize for-mult	ribute s of 3 ribute
message-to-operator attribute default job 562 messages messages displaying information about 164 migrating an existing printer 160 migrating printer 160 motational conventions xxvii notification client daemon 151 notification-delivery-methods-supported attribute server 654 notification-profile attribute actual destination 407 default job 577 job 580 offset-stacking-available at actual destination 410 opergui utility description 152 desc	s of 3
default job 562 job 562 messages specifying where written 252 messages, displaying information about 164 migrating PSF for AIX job scripts 149 minimum configuration, setting up 162 miffirmap command arguments 15 description 15 examples 16 syntax 15 model attribute actual destination 363 logical destination 363 logical destination 605 models-requested attribute default job 576 modiffication-time attribute actual destination 407 altribute server 654 modiffy-individual-document-supported attribute server 654 modiffying attributes of submitted job 576 modiffication-time attribute default document 510 document 510 non-process-runout-timer attribute actual destination 406 notational conventions xxviii notification client daemon 151 notification-delivery-methods-supported attribute server 654 notification events classes 689 list of 679 notification-profile attribute actual destination 407 default job 577 default job 577 modiffication-time attribute actual destination 613 queue 635 queue 636 queue example 315 notify daemon 197, 198 notify-operator attribute server 657 modify-individual-document-supported attribute server 657 modify-individual-document 507 document 510 nounber-of-documents attribute default document 507 movs-destination attribute default document 507 movs-destination attribute default document 507 movs-destination 508 document 510 nounber-up-supported attribute actual destination 409 actual destination 61 description 152 examples 152 description 152 examples 16 poptination 410 exerci 636 opergui utility examples 16 poptination 613 queue 635 queue 636 opergui utility examples 16 poptination 613 q	ribute
greifying where written 252 messages displaying information about 164 migrating an existing printer 160 migrating an existing printer 160 migrating personal formation are migrating an existing printer 160 migrating printer 150 notification client daemon 151 notification delivery-methods-supported artiribute server 654 morphocological destination 363 logical destination 363 logical destination 605 modell-requested attribute actual destination 407 default job 549 gib 549 modification-time attribute server 654 modification-time attribute job 576 modify-individual-document-supported attribute server 654 modify-individual-document-supported attribute server 654 modify-individual-document-supported attribute server 654 modify-individual-document-supported attribute server 655 modify-operator attribute server 656 multiple-document-supported attribute default document 507 modecument 507 movs-destination attribute default document 507 movs-destination attribute default document 508 document 508 default document 508 document 508	ribute
messages specifying where written 252 non-process-runout-timer attribute actual destination 406 notational conventions xxvii notification delivery-methods-supported attribute actual destination 416 notational conventions xxvii notification delivery-methods-supported attribute actual destination 416 notational conventions xxvii notification delivery-methods-supported attribute attribute server 654 notification events classes 689 description 15 examples 16 syntax 15 notification or events classes 689 description 152 examples 16 syntax 15 notification profile attribute actual destination 407 default job 577 default job 577 pob 577 of 16 logical destination 613 queue 636 opergui utility arguments 152 description 152 examples 152 flags 152 syntax 152 optimize for-multiple-copi actual destination 407 points of transforms git2afp 217 jpeg2afp 231 tiff2afp 319 orientation attribute default document 507 document 507 number-up-attribute actual destination 621 server 656 number-of-documents attribute default document 507 number-up-attribute actual destination 409 document 486 document 508	
messages, displaying information about 164 migrating PSF for AIX job scripts 149 minimum configurations, setting up 162 minimum configuration 15 description 15 examples 16 soyntax 15 classes 689 list of 679 notification profile 334 notification-profile attribute actual destination 407 default job 577 optimize for-multiple-copi actual destination 410 default job 579 point server 655 point server 655 point server 655 point server 654 point server 654 point server 654 point server 655 point server 655 point server 655 point server 654 point server 655 point server 654 point server 655 point server 656 point	
messages, displaying information about 164 notational conventions xxvii migrating an existing printer 160 migrating PSF for AIX job scripts 149 minimum configuration, setting up 162 mkfntmap command arguments 15 description 15 examples 16 list of 679 notification events classes 689 list of 679 notification profile attribute actual destination 363 description 605 pob 577 notification profile attribute actual destination 605 pob 577 default job 577 default job 577 notification-time attribute actual destination 605 pob 570 notification profile attribute actual destination 605 pob 577 notification-profile attribute actual destination 605 pob 577 notification-profile attribute actual destination 605 pob 577 notification-profile attribute actual destination 407 default job 577 notification-time attribute actual destination 613 queue 635 pob 580 poptions of transforms gif2afp 217 pigeg2afp 231 tiff2afp 319 orientations-supported attribute server 654 nomes-erver-port-number attribute server 656 number-op-document attribute default document 507 document 507 number-up-supported attribute actual destination 612 server 665 number-of-documents attribute default document 507 document 507 number-up-attribute actual destination 612 server 665 number-of-documents attribute default document 507 document 507 number-up-supported attribute actual destination 612 server 657 number-of-documents attribute default document 507 number-up-supported attribute actual destination 612 sexamples 152 description 152 examples 152 syntax 152 optimize for-multiple-copi actual destination 407 default job 577 pob 579 notification-profile attribute actual destination 613 queue 635 pob 580	
about 164 migrating an existing printer 160 migrating PSF for AIX job scripts 149 minimum configuration, setting up 162 minimum configuration setting up 162 minimum configuration, setting up 162 minimum configuration setting up 162 modification-delivery-methods-supported attribute classes 689 log-fery 152 description 152 examples 152 flags 152 sprynta 152 optimize for-multiple-copi actual destination 410 operators attribute queue 636 opergui utility arguments 152 description 152 examples 152 flags 152 optimize for-multiple-copi actual destination 410 operators attribute queue 636 opergui utility arguments 152 description 152 examples 152 flags 152 optimize for-multiple-copi actual destination 410 operators attribute queue 636 opergui utility arguments 152 description 152 examples 152 flags 152 sprynta 152 optimize for-multiple-copi actual destination 410 operators attribute queue 636 opergui utility arguments 152 description 152 examples 152 flags 152 sprynta 152 optimize for-multiple-copi actual destination 411 operators attribute queue 636 opergui utility actual destination 401 operators attribute queue 636 operators attribute queue 636 operation actual d	
migrating PSF for AIX job scripts 149 minimum configuration, setting up 162 mkfntmap command arguments 15 description 15 examples 16 syntax 15 MO:DCA-P files, extracting pages 130 model attribute actual destination 605 logical destination 605 logical destination 605 modelis-requested attribute default job 549 job 549 modify-individual-document-supported attribute server 654 modifying attributes of submitted jobs 49 modifying attributes of submitted parcode.tab configuration file 303 msgdd option 252 mws-class attribute default document 507 models-trace for a cutal destination 450 document 507 mws-forms attribute default document 507 move-form attribute default document 507 mws-forms attribute default document 507 document 508 document 508	
migrating PSF for AIA job scripts 149 minimum configuration, setting up 162 mkfntmap command arguments 15 description 15 examples 16 syntax 15 MO:DCA-P files, extracting pages 130 model attribute actual destination 363 logical destination 605 logical destination 613 default job 549 job 549 modification-tenine attribute job 576 modify-individual-document-supported attribute server 654 modifying attributes of submitted jobs 49 modifying attributes of submitted barcode tab configuration file 303 msgdd option 252 multiple-documents-supported attribute spooler 654 mvs-class attribute default document 507 document 507 mvs-destination attribute default document 507 mvs-forms attribute default document 507 document 508 document 508	s attribute
mikintunt command arguments 15 description 16 description 16 description 16 default job 577 actual destination 411 default job 580 job 580 options orientation attribute default document 475 doc	s attribute
arguments 15 description 15 examples 16 syntax 15 MO:DCA-P files, extracting pages 130 model attribute actual destination 363 logical destination 605 logical destination 613 default job 577 actual destination 417 default job 577 actual destination 417 default job 577 actual destination 417 default job 580 job 580 job 580 pitions modification-time attribute job 549 modify-individual-document-supported attribute server 654 attribute logical destination 408 attribute logical destination 408 pm-server-ip-address attribute server 656 notifyd daemon 197, 198 modifying attributes of submitted jobs 49 ModWidth optional keyword barcode:tab configuration file 303 msgdd option 252 multiple-documents-supported attribute spooler 654 multiple-documents-supported attribute spooler 654 multiple-document 507 mvs-destination attribute default document 507 mvs-forms attribute default document 508 document 508	s attribute
description 15 examples 16 syntax 15 MO-DCA-P files, extracting pages 130 model attribute actual destination 363 default job 577 logical destination 363 default job 577 modification-profile attribute actual destination 407 default job 577 default job 577 default job 577 model attribute actual destination 613 default job 549 job 576 modify-individual-document-supported attribute server 654 modifying attributes of submitted jobs 49 ModWidth optional keyword barcode-tab configuration file 303 msgdd option 252 multiple-documents-supported attribute spooler 654 mvs-class attribute default document 507 mvs-forms attribute default document 508 document 508	s attribute
examples 16 syntax 15 MO:DCA-P files, extracting pages 130 motification profile 334 motification profile attribute actual destination 363 logical destination 605 model attribute default job 549 giob 549 modification-time attribute giob 576 modify-individual-document-supported attribute modifying attributes of submitted jobs 49 ModWidth optional keyword barcode.tab configuration file spooler 654 multiple-documents-supported attribute spooler 654 multiple-documents-supported attribute spooler 654 multiple-documents-supported attribute spooler 654 multiple-documents-supported attribute default document 507 document 507 mvs-forms attribute default document 507 document 507 mvs-forms attribute default document 507 mvs-forms attribute default document 507 mvs-forms attribute default document 508 document 508	s attribute
syntax 15 MO:DCA-P files, extracting pages 130 model attribute actual destination 363 logical destination 605 logical destination 613 default job 577 logical destination 613 default job 549 modification-time attribute job 549 modify-individual-document-supported attribute server 654 modify-individual-document-supported attribute server 654 modifying attributes of submitted jobs 49 notification-profile attribute actual destination 407 default job 577 poptimize for-multiple-copt actual destination 613 queue 635 pob 580 potions of transforms gif2afp 217 jpeg2afp 231 tiff2afp 319 orientation attribute default document 479 document 479 document 479 document 479 document 479 modify-ndividual-document 479 document 507 modify-individual-document 479 modify-individua	s attribute
MO:DCA-P files, extracting pages 130 model attribute actual destination 363 default job 577 models-requested attribute default job 549 job 549 modification-time attribute job 576 modify-individual-document-supported attribute server 654 modifying attributes of submitted jobs 49 ModWidth optional keyword barcode-tab configuration file 303 msgdd option 252 multiple-documents-supported attribute spooler 654 mvs-class attribute default document 507 mvs-destination attribute default document 507 mvs-destination attribute default document 507 mvs-forms attribute default document 507 document 507 mvs-forms attribute default document 508 notification-profile attribute actual destination 407 default job 577 actual destination 411 default job 580 options of transforms gif2afp 217 jpeg2afp 231 tiff2afp 319 orientation attribute default document 479 document 479 orientation attribute default document 479 orientation attribute default document 507 number-up-attribute document 507 number-up attribute default document 507 number-up-supported attribute actual destination 61 os2-driver-names attribute logical destination 61 os2-driver-names attribute logical destination 61 other-options attribute actual destination 486	s attribute
model attribute actual destination 407 actual destination 407 logical destination 605 job 577 actual destination 411 default job 549 job 549 job 549 job 576 modiffication-time attribute job 576 modiffy-individual-document-supported attribute server 654 modify-individual-document-supported attribute server 654 modifying attributes of submitted jobs 49 ModWidth optional keyword barcode.tab configuration file 303 msgdd option 252 mvs-class attribute server 657 mvs-class attribute default document 507 mvs-clestination attribute default document 507 mvs-croms attribute default document 507 mvs-forms attribute default document 508 document 508	s attribute
actual destination 363 default job 577 optimize for-multiple-copi actual destination 605 job 577 actual destination 411 default job 580 job 580	s attribute
logical destination 605 job 577	
models-requested attribute default job 549 job 549 modification-time attribute job 576 modify-individual-document-supported attribute server 654 modifying attributes of submitted jobs 49 modWidth optional keyword barcode.tab configuration file spooler 654 multiple-documents-supported attribute spooler 654 multiple-document 507 mvs-destination attribute default document 507 mvs-destination attribute default document 507 mvs-destination attribute default document 507 mvs-forms attribute default document 507 mvs-forms attribute default document 508 document 508 modification-time attribute actual destination 408 gif2afp 217 jpeg2afp 231 tiff2afp 319 orientation attribute default document 479 document 97, 198 orientation attribute default document 479 document 479 orientations-supported attribute actual destination 455 logical destination 60 originator attribute default document 507 number-of-documents attribute default document 507 number-up attribute default document 507 number-up attribute default document 507 number-up attribute default document 507 number-up-supported attribute default document 508 document 508	
default job 549 job 549 job 549 server 655 server 655 options modification-time attribute job 576 actual destination 408 actual destination 409 actual destination 408 actual destination 409 ac	
modification-time attribute job 576 modify-individual-document-supported attribute server 654 modifying attributes of submitted jobs 49 ModWidth optional keyword barcode-tab configuration file 303 msgdd option 252 multiple-documents-supported attribute spooler 654 mvs-class attribute default document 507 mvs-destination attribute default document 507 mvs-destination attribute default document 507 mvs-destination attribute default document 507 mvs-forms attribute default document 507 mumber-up-supported attribute default document 508 document 508	
job 576 modify-individual-document-supported attribute server 654 modifying attributes of submitted jobs 49 ModWidth optional keyword barcode.tab configuration file 303 msgdd option 252 multiple-documents-supported attribute spooler 654 mvs-class attribute default document 507 mvs-destination attribute default document 507 mvs-destination attribute default document 507 mvs-forms attribute default document 507 mvs-forms attribute default document 508 document 508 actual destination 408 gif2afp 217 jpeg2afp 231 tiff2afp 319 orientation attribute default document 479 document 479 document 479 orientations-supported attribute orientations-supported attribute actual destination 455 logical destination 60 originator attribute default job 563 job 563 os2-driver-names attribute logical destination 61 os2-drivers attribute actual destination 409 mumber-up-supported attribute actual destination 409 modify-individual-document 479 jpeg2afp 231 tiff2afp 319 orientation attribute default document 479 document 479 orientations-supported attribute originator attribute default job 563 job 563 os2-driver-names attribute logical destination 61 os2-drivers attribute actual destination 409 server 656 number-up-supported attribute actual destination 409 actual destination 409 default document 479 orientation attribute orientations-supported attribute actual destination 409 orientation attribute default document 479 document 479 orientation attribute orientation 479 actual destination 621 gif2afp 217 jpeg2afp 231 tiff2afp 319 orientation attribute default document 479 orientations-supported attribute originator attribute originator attribute default job 563 job 563 os2-driver-names attribute logical destination 61 os2-drivers attribute actual destination 410 os2-drivers attribute actual destination 410 os2-driver-names attribute actual destination 410 os2-driver-names attribute actual destination 410 os2-driver-names attribute actual destination 410	
modify-individual-document-supported attribute server 654 notifyd daemon 197, 198 orientation attribute default document 507 mvs-destination attribute default document 507 mvs-forms attribute default document 508 document 508 document 508 document 508	
attribute server 654 notifyd daemon 197, 198 orientation attribute default document 507 mvs-destination attribute default document 507 mvs-forms attribute default document 507 mvs-forms attribute default document 507 mvs-forms attribute default document 508 documen	
server 654 modifying attributes of submitted jobs 49 ModWidth optional keyword barcode.tab configuration file 303 msgdd option 252 multiple-documents-supported attribute spooler 654 movs-class attribute default document 507 mvs-destination attribute default document 507 mvs-destination attribute default document 507 mvs-forms attribute default document 507 mvs-forms attribute default document 508 document 508 notifyd daemon 197, 198 orientation attribute default document 479 orientations-supported attribute actual destination 455 logical destination 60 originator attribute default job 563 job 563 os2-driver-names attribute logical destination 61 os2-drivers attribute actual destination 409 other-options attribute actual destination 365 default document 479 orientation attribute default document 479 orientation attribute default document 479 orientation attribute actual destination 409	
modifying attributes of submitted jobs 49 ModWidth optional keyword submodifying attribute server 656 ModWidth optional keyword sharcode.tab configuration file 303 msgdd option 252 multiple-documents-supported attribute spooler 654 mvs-class attribute default document 507 mvs-destination attribute default document 507 mvs-forms attribute default document 507 mvs-forms attribute default document 508 document 508 mpm-server-ip-address attribute server 656 npm-server-port-number attribute server 657 nt-drivers attribute actual destination 455 logical destination 60 originator attribute default job 563 job 563 os2-driver-names attribute logical destination 61 os2-driver-names attribute actual destination 409 other-options attribute actual destination 365 default document 479 orientations-supported attribute originator attribute default destination 60 originator attribute default job 563 job 563 os2-driver-names attribute logical destination 61 os2-drivers attribute actual destination 409	
jobs 49 ModWidth optional keyword barcode.tab configuration file 303 msgdd option 252 multiple-documents-supported attribute spooler 654 mvs-class attribute default document 507 mvs-destination attribute default document 507 mvs-forms attribute default document 507 mvs-forms attribute default document 507 mvs-forms attribute default document 508 document 508 server 656 npm-server-port-number attribute actual destination 455 logical destination 60 originator attribute default dostination 61 server 665 number-of-documents attribute job 579 number-up attribute document 510 number-up-supported attribute actual destination 409 server 656 npm-server-port-number attribute actual destination 455 logical destination 60 originator attribute default job 563 job 563 os2-driver-names attribute logical destination 61 os2-drivers attribute actual destination 61 other-options attribute actual destination 365 default document 479	
ModWidth optional keyword barcode.tab configuration file 303 msgdd option 252 multiple-documents-supported attribute spooler 654 mvs-class attribute default document 507 mvs-destination 4507 mvs-forms attribute default document 507 mvs-forms attribute default document 507 mvs-forms attribute default document 508 document 508 mpm-server-port-number attribute server 657 nt-drivers attribute actual destination 455 logical destination 60 originator attribute default job 563 job 563 os2-driver-names attribute logical destination 61 os2-drivers attribute actual destination 61 os2-drivers attribute actual destination 61 other-options attribute actual destination 365 default document 486	
barcode.tab configuration file 303 msgdd option 252 mt-drivers attribute spooler 654 mvs-class attribute default document 507 mvs-destination 357 mvs-destination attribute default document 507 mvs-forms attribute default document 507 mvs-forms attribute default document 508 document 508 server 657 nt-drivers attribute actual destination 455 logical destination 60 originator attribute default job 563 job 563 os2-driver-names attribute logical destination 61 os2-drivers attribute actual destination 366 default document 61 os2-drivers attribute actual destination 366 default document 486	1 .
msgdd option 252 nt-drivers attribute actual destination 455 originator attribute default document 507 number-up attribute default document 507 number-up-supported attribute actual destination 409 nt-drivers attribute actual destination 409 nt-drivers attribute description 252 nt-drivers attribute actual destination 409 nt-drivers attribute actual destination 409 descriptions attribute actual destination 365 default document 4860 nt-drivers attribute actual destination 409 descriptions attribute actual destination 365 default document 4860 nt-drivers attribute actual destination 409 descriptions attribute actual destination 365 default document 4860 nt-drivers attribute actual destination 409 nt-drivers attribute 400 nt-drivers attribute	bute
multiple-documents-supported attribute spooler 654 logical destination 455 originator attribute default document 507 number-of-documents attribute default document 507 number-up attribute default document 507 number-up attribute default document 507 number-up-supported attribute default document 507 number-up-supported attribute default document 507 number-up-supported attribute default document 508 document 508	
spooler 654 logical destination 621 default job 563 mvs-class attribute server 665 job 563 default document 507 number-of-documents attribute document 507 number-up attribute default document 507 number-up-supported attribute default document 507 number-up-supported attribute default document 507 number-up-supported attribute default document 508 document 508	
mvs-class attribute server 665 job 563 default document 507 number-of-documents attribute document 507 number-up attribute default document 507 number-up attribute default document 507 number-up-supported attribute default document 507 number-up-supported attribute default document 508 document 508 document 508 mvs-class attribute server 665 job 563 os2-driver-names attribute logical destination 61 os2-drivers attribute logical destination 61 other-options attribute actual destination 409 default document 508 default document 486	
default document 507 number-of-documents attribute job 579 logical destination 61. mvs-destination attribute default document 507 number-up attribute document 507 number-up-supported attribute default document 508 document 508 mvs-forms attribute default document 508 default document 508	
document 507 job 579 logical destination 61. mvs-destination attribute default document 507 document 507 number-up-supported attribute default document 507 number-up-supported attribute default document 508 document 508 document 508 logical destination 61. os2-drivers attribute logical destination 61. other-options attribute actual destination 409 default document 486.	615
mvs-destination attribute default document 507 document 507 mvs-forms attribute default document 508 document 508 number-up attribute document 510 number-up-supported attribute actual destination 409 os2-drivers attribute logical destination other-options attribute actual destination 365 default document 486	010
default document 507 document 510 logical destination 61. mvs-forms attribute default document 508 document 508 document 508 document 510 logical destination 61. other-options attribute actual destination 365 default document 486	
mvs-forms attribute actual destination 409 other-options attribute actual destination 365 document 508 default document 486	
default document 508 document 508 default document 486	
document 508 default document 486	
document 500	
mvs-segment-id attribute default document 508 other-transform-options at	ribute
document 508 object attributes 332 default document 513	
mysprsd daemon 188 object attributes, default values for 333 document 512	
mysprsd utility object attributes of commands examples 669	
description 188 pdcreate other-transform-option	668
examples 189 documents 25 outexit option 252	
flags 188 gods 25 output appearance attribu	2
syntax 188 pupi 65	
document 513	
auxiliary sneet 459 output-appearances-sudde	
default document 311 default job 579 actual destination 412	ted attribute
name attribute document 511 output-bin attribute	ted attribute
job 562 job 579 actual destination 412	ted attribute
Joe do	ted attribute
name-of-last-accessor attribute log 597 actual destination 412	ted attribute

output-bin component	page-select attribute	pdcrcds utility
results-profile attribute	document 519	description 154
default job 586	page-select-supported attribute	examples 154
job 586	actual destination 416	syntax 154
output-bin-numbers attribute	pagedef option 253	pdcrdflt utility
actual destination 413	pagedef.tab file 309	arguments 156
output-bins-supported attribute	pages, extracting from MO:DCA-P	description 155
actual destination 414	files 130	examples 156
output-data-user-exit attribute	pages-completed attribute	flags 155
actual destination 414	job 581	syntax 155
output exit 252 output-face-up attribute	parmdd option 255	pdcreate command
default document 514	Passthrough destination support system	arguments 25 attributes 25
document 514	(DSS) 331	command attributes 25
output files	paths	description 23
for PostScript 293	font directory 247	examples 26
specifying file name 252	form definition directory 245	flags 24
output-format attribute	overlay directory 252	syntax 23
default document 515	page definition directory 255	pdcrmed utility
document 515	page segment directory 256	arguments 157
output-format-supported attribute	resource directory 258	description 157
actual destination 415	user directories 259	examples 157
outputdd option 252	pausing jobs, actual destinations, servers,	syntax 157
overlay attribute	or queues 54	pddelete command
actual destination 416	pcl-server-address attribute actual destination 417	arguments 29
default document 516		command attributes 29
document 516	pcl-server-port attribute	description 28
overlay-back attribute	actual destination 417	examples 30
default document 516	pcl2afp transform	flags 28
document 516	configuration files	syntax 28
overlay-front attribute default document 517	pcl2afp file 276 pcl2afpd file 276	pddisable command
document 517	description 264	arguments 33
overlays	examples, complex 279	command attributes 33
directory 252	examples, simple 278	description 32
overprint attribute	files 276, 285	examples 34
default document 517	flags 266	flags 32 syntax 32
document 517	limitations 265	pdeflib option 255
ovlylib option 252	syntax 264	pdenable command
owner attribute	pcl2afpd daemon 190, 265	arguments 36
job 563	configuration file 276	command attributes 36
	pcl2afpd utility	description 35
D	configuration file 190	examples 37
P	description 190	flags 35
page-clip attribute	examples 192	syntax 35
default document 518	files 192	PDF
document 518	flags 190	inline resources 300
page-count attribute	syntax 190	margins
document 518	PD_CONFIRM_DELETE environment	X offset 296
page-definition attribute	variable 20, 28, 86	Y offset 296
default document 519	pdaccount command	resolution of output 294
document 519	arguments 18	transforming and printing 299
page definitions	description 17 examples 19	width of image 295
directory 253, 254	flags 17	pdf2afp transform
for R4 732	syntax 17	configuration files
for B4 732 for legal-sized paper 731	pdadmin utility	ps2afp file 297
for letter-sized paper 730	description 153	ps2afpd file 297
for multiple-up 731	examples 153	description 287
inline 254	syntax 153	examples 299 files 297, 300
specified with pagedef option 253	pdclean command	flags 289
supplied with Infoprint 723	arguments 21	keywords
page-media-select attribute	command attributes 21	height of image 292
default document 519	description 20	length of image 292
document 519	examples 22	maximum memory 293
page segments	flags 20	output file 293
directory 256	syntax 20	port 293

mdDafm twomsforms (continued)	DDDDINITED anxinonma	nt rraniable 61	non document attribute listing. 467
pdf2afp transform (continued)	PDPRINTER environme	nt variable 61,	per-document attribute listing 467
quiet 294	72		physical-printer attribute
resolution 294	pdpromote command		actual destination 364
selected pages 294	arguments 71		physical-printers-assigned attribute
server name 294	command attributes	71	queue 630
server time out 295	description 70		physical-printers-ready attribute
width of image 295	examples 71		queue 630
Y offset 296	flags 70		server 644
limitations 289	syntax 70		physical-printers-requested attribute
syntax 287	pdq command		default job 543
pdf2fp transform	arguments 75		job 543
keywords	command attributes	74	physical-printers-supported attribute
X offset 296	description 72		server 644
pdinitports utility	examples 75		plex attribute
arguments 158	flags 72		actual destination 418
description 158	syntax 72, 77		default document 521
examples 159	pdreorder command		document 521
-	arguments 78		plexes-supported attribute
flags 158	command attributes	78	actual destination 418
syntax 158	description 77	70	
pdls command	examples 78		logical destination 617
arguments 43	flags 77		port number keyword
attribute operators for filters 41	0		pdf2afp transform 293
command attributes 40	pdresubmit command		ps2afp transform 293
description 38	arguments 81	0.0	position-in-queue attribute
examples 44	command attributes	80	job 554
flags 39	description 79		PostScript
syntax 38	examples 82		height of image 292
pdmigpp utility	flags 79		inline resources 300
arguments 160	syntax 79		length of image 292
description 160	pdresume command		margins
examples 161	arguments 84		X offset 296
syntax 160	command attributes	84	Y offset 296
-	description 83		resolution of output 294
pdmincfg utility	examples 85		
arguments 162	flags 83		transforming and printing 299
description 162	syntax 83		width of image 295
examples 162	pdrm command		postscript-server-address attribute
flags 162	arguments 87		actual destination 419
syntax 162	command attributes	87	logical destination 616
pdmod command	description 86	07	postscript-server-port attribute
arguments 52	examples 87		actual destination 420
command attributes 51	flags 86		presentation-fidelity-problem-reported
description 49			attribute
examples 52	syntax 86		actual destination 420
flags 50	pdset command		presentation-object-container-extraction-
syntax 49	arguments 92	0.4	mode attribute
pdmsg utility	command attributes	91	actual destination 421
	description 89		previous-job-state attribute
description 164	examples 92		job 582
examples 164	flags 90		previous-state attribute
flags 164	syntax 89		1
syntax 164	pdshutdown command		job 582
PDPATH environment variable 8	arguments 97		Print Administration window,
pdpause command	command attributes	96	opening 129
arguments 58	description 94		print-after attribute
command attributes 56	examples 97		job 564
description 54	flags 95		print-edge-marks attribute
examples 60	syntax 94		actual destination 421
flags 55	pdspace command		Print Management window,
syntax 54	arguments 101		opening 152
pdpr command	command attributes	100	print-qualities-supported attribute
<u>-</u>	description 99	100	actual destination 421
arguments 65			logical destination 617
command attributes 64	examples 101		print-quality attribute
description 61	flags 100		
examples 66, 69	syntax 99		default document 521
flags 62	pel output		document 521
object attributes 65	for PostScript 294		print-queue-name attribute
syntax 61	output for PDF 294		actual destination 422

print queues	printer-separator-sheet attribute	ps2afpd utility
migrating 160	actual destination 427	configuration file 193
printer-associated-printers attribute	printer-start-sheet attribute	description 193, 197, 199
logical destination 604	actual destination 428	examples 195, 199, 201
printer attribute	printer-state attribute	files 195
actual destination 364	actual destination 368	flags 193
logical destination 605	printer-states-supported attribute	syntax 193, 197
printer-command attribute	server 646	pseglib option 256
actual destination 360	printer.tab file 310	PSF destination support system
printer-data-stream attribute	printer-tcpip-internet-address attribute	(DSS) 330, 331
actual destination 361 printer-end-sheet attribute	actual destination 370	psf-exit-form-definition attribute
actual destination 423	printer-tcpip-port-number attribute actual destination 371	auxiliary sheet 459
printer-escape-codes attribute	printer-timeout-period attribute	psf-exit-page-mark attribute auxiliary sheet 459
actual destination 423	actual destination 371	psf-exit-program-name attribute
printer-initial-value-document attribute	printers, attributes of	auxiliary sheet 460
document 485	used for job scheduling 719	PSF for AIX job scripts, migrating 149
logical destination 604	used for job validation 719	psf-tray-characteristics attribute
printer-initial-value-job attribute	printers, channel-attached, sensing 168	actual destination 431
job 548	printers-assigned attribute	public-context-presentation-object-
logical destination 604	job 550	container
printer-locations attribute	printers-ready attribute	actual destination 434
actual destination 362	logical destination 607	
logical destination 605	printers-used attribute	
printer-locations-requested attribute	job 551	Q
default job 549	prmode option 256	qualities-supported attribute
job 549	problem-child attribute	actual destination 421
printer-memory attribute	server 658	logical destination 617
actual destination 424	problem-message attribute	querying the status of jobs 72
printer-model attribute	actual destination 430	queue-assigned attribute
actual destination 363	processing-time attribute	job 584
logical destination 605 printer-models-requested attribute	job 583	queue-backlog attribute
default job 549	programmer-text attribute	queue 638
job 549	default document 522	queue-name attribute
printer-name attribute	document 522	queue 638
actual destination 364	promoting a job to the top of a	queue-position attribute
logical destination 605	queue 70	job 554
printer-name-requested attribute	protected-attributes attribute	queue-state attribute
job 550	actual destination 431	queue 638
printer-needs-attention-time attribute	logical destination 618 queue 638	queues, attributes of
actual destination 364	server 658	actual-destinations-assigned 630
printer-needs-key-operator-attention-time	ps2afp transform	actual-destinations-ready 630
attribute	configuration files	assign-to-destination 631
actual destination 365	ps2afp file 297	assign-to-printer 631 associated-server 631
printer-pass-through attribute	ps2afpd file 297	backlog 638
actual destination 365	description 287	backlog-lower-bound 632
default document 486	examples 299	backlog-update-interval 632
document 486	files 297, 300	backlog-upper-bound 633
printer-realization attribute actual destination 366	flags 289	backlogged 633
logical destination 606	keywords	current-backlog 638
printer-register-threshold attribute	height of image 292	descriptor 633
actual destination 366	length of image 292	list-of-managers 634
printer-release-timer attribute	maximum memory 293	logical-destinations-assigned 634
actual destination 367	output file 293	logical-destinations-ready 634
printer-requested attribute	port 293	logical-printers-assigned 634
job 550	resolution 294	logical-printers-ready 634
printer-resolutions-ready attribute	selected pages 294	managers 634
actual destination 425	server name 294	message 635
printer-resolutions-supported attribute	server time out 295 width of image 295	notification-profile 635
actual destination 426	X offset 296	notify-operator 636 object-class 637
printer-s370-channel-device-address	Y offset 296	operators 636
attribute	limitations 289	physical-printers-assigned 630
actual destination 429	syntax 287	physical-printers-ready 630
printer-s370-channel-slot-number attribute	ps2afpd daemon 193, 289	protected-attributes 638
actual destination 430	configuration file 297	queue-backlog 638
	<u> </u>	- ~

queues, attributes of (continued)	resource-context-font attribute (continued)	SAP callback daemons, starting 166
queue-name 638	document 524	sap2afp transform
queue-state 638	resource-context-form-definition attribute	configuration files barcode.tab 303
requeue-failed-jobs 639 queues-supported attribute	actual destination 438 default document 525	defcp.tab 305
server 659	document 525	fonts.tab 305
quiet keyword	resource-context-identifier attribute	image.tab 308
pdf2afp transform 294	resource context 642	pagedef.tab 309
r	resource-context-overlay attribute	printer.tab 310
	actual destination 439	xxxxyyyy.tab 311
R	default document 525	converting ASCII to EBCDIC 305
R/3 output device	document 525	description 302
mapping to a logical destination 310	resource-context-page-definition attribute	examples 312
Ratio optional keyword	actual destination 440	flags 302
barcode.tab configuration file 303	default document 526	mapping bar codes to BCOCA 303
rc.iprsap utility	document 526	syntax 302
description 166	resource-context-page-segment attribute	save-rip-files attribute
syntax 166	actual destination 441	server 659
rc.pd utility	default document 527 document 527	scanner-correction attribute
description 167		default document 531
syntax 167	resource-context-presentation-object- container attribute	document 531 scanner-corrections-supported attribute
reasons attribute	actual destination 442	actual destination 444
job 571	default document 528	scheduler-sort-primary-order attribute
reassigning jobs to actual destination 77	document 528	actual destination 445
register-threshold attribute	resource-context-user attribute	scheduler-sort-secondary-order attribute
actual destination 366	default document 529	actual destination 445
registered-with-spooler attribute	document 529	
actual destination 435	resource contexts, attributes of	schedulers-supported attribute
related publications xix	associated-server 640	actual destination 446
remote printing 13	context-address 641	scheduling of jobs, attributes used for 719
remote-queue attribute	descriptor 641	screen-frequencies-supported attribute
actual destination 435 removing jobs	object-class 641, 667	actual destination 446
pdclean command 20	resource-context-identifier 642	screen-frequency attribute
pdrm command 86	resource directory, paths 258	default document 531
requeue-failed-jobs attribute	resource-exit attribute	document 531
queue 639	default document 530	search order for resources
required-resources-not-ready attribute	document 530	line data 245, 247, 252, 255, 256, 258
job 584	restarting servers 167	259
required-resources-not-supported	resubmitting jobs 79	security-level attribute
attribute	results-profile attribute	server 659
job 585	default job 585 job 585	segment-file-size attribute
resettable attribute listing	results-set-comment component	default document 532
actual destination 337	results-profile attribute	document 532
auxiliary sheet 458	default job 586	selected pages keyword
default document 464	job 586	pdf2afp transform 294
document 464	resuming paused objects 83	ps2afp transform 294
job 542	retention-period attribute	sense utility
log 593	default job 566	examples 169, 171
logical destination 598 medium 624	job 566	flags 168, 170
	reuse-inline-presentation-object-containter	messages 168, 170
queue object 630 resource context 640	actual destination 443	return codes 168, 170
server 643	reverse-output attribute	syntax 168, 170
transform 666	actual destination 443	sensing channel-attached printers,
resexit option 257	rip-ini-file attribute	sensing 168
reslib option 258	actual destination 444	separator-sheets-supported attribute
resolution keyword	rip-server attribute	actual destination 447
pdf2afp transform 294	actual destination 444	sequence-number attribute
ps2afp transform 294	room-text attribute	document 489
resource-context attribute	default document 530	server
actual destination 436	document 530	port number 293
default document 522		time out keyword 295
document 522	S	server, shutting down 181
resource-context-font attribute	3	server, starting 177, 179
actual destination 437	SAP Callback daemon 199, 201	server-hostname attribute
default document 524	SAP Callback Daemon 199, 201	server 660

server-ip-address attribute	servers, attributes of (continued)	start-message-supported attribute
server 660	snmp-aix-printer-models 662	actual destination 451
server name 661	snmp-discovery-during-startup 662	logical destination 619
server-name attribute	snmp-normal-poll-interval 663	start-on-new-sheet attribute
server 661	snmp-problem-poll-interval 663	default document 535
server name keyword	snmp-timeout 664	document 535
pdf2afp transform 294	transfer-methods-supported 664	start_server utility
ps2afp transform 294	windows-nt-driver-names 665	arguments 178
server state 661	windows-nt-drivers 665	description 177
server-state attribute	servers, configuring 155	examples 178
server 661	servers, restarting 167	flags 177
servers, attributes of	Servers window, opening 153	syntax 177
accept-unsupported-jobs 643	setting the attribute values of an	start-sheets-supported
actual-destinations-ready 644	object 89	actual destination 452
actual-destinations-supported 644	setting up a minimum configuration 162	startcbd utility
auto-create-shared-printers 645	setup utility	arguments 199, 201
cancel-individual-document-	description 173	syntax 199
supported 645	examples 175	started-printing-time attribute
descriptor 645	flags 173	job 587
destination-states-supported 646	syntax 173	starting a server 177, 179
destination-support-systems-	shared-formdef attribute	starting Infoprint SMIT production print
supported 646	default document 532	operations interface 176
document-attributes-supported 647	document 532	starting SAP callback daemons 166
events-supported 647	shared-printer-name attribute	starting the Infoprint Installer 173
hostname 660	actual destination 448 shift-out-shift-in attribute	starting the Infoprint Manager
i-p-address 660	default document 533	Administration GUI 147
ip-address 660		starting the Infoprint Manager Operations
job-attributes-supported 649	document 533	GUI 146
job-states-supported 649	shutting down a server 181 shutting down destinations 94	startppo utility description 176
job-submission-timer 650	shutting down servers 94	examples 176
list-of-managers 650	sides attribute	flags 176
locale 651	actual destination 448	syntax 176
log-accounting-data 651	default document 534	startsrv utility
logical-destinations-ready 652	document 534	arguments 180
logical-destinations-supported 652	sides-supported attribute 448, 449	description 179
logical-printers-ready 652	actual destination 449	examples 180
logical-printers-supported 652	logical destination 619	flags 179
managers 650	single quotation marks in	syntax 179
maximum-barco-rips 653	commands xxviii	state of the server 661
maximum-non-raster-rips 653	smtp-server-host	state-reasons attribute
maximum-raster-rips 653	server 661	job 571
message 654	smtp-server-port-number	stop_server utility
modify-individual-document-	server 662	arguments 181
supported 654	snmp-active attribute	description 181
multiple-documents-supported 654	actual destination 450	examples 181
notification-delivery-methods-	snmp-aix-printer-models attribute	flags 181
supported 654	server 662	syntax 181
notification-profile 655	snmp-community-name attribute	stopcbd utility
npm-server-ip-address 656	actual destination 450	description 201
npm-server-port-number 657	SNMP-discovery-during-startup	syntax 201
nt-drivers 665	server 662	stopnotd utility
object-class 657	server 662	description 198
object-classes-supported 657	snmp-normal-poll-interval attribute	syntax 198
physical printers ready 644	server 663	subject-text attribute
physical-printers-supported 644 printer-states-supported 646	snmp-problem-poll-interval attribute	default document 535
1 11	server 663	document 535
problem-child 658 protected-attributes 658	snmp-retry-count attribute	submission-time attribute
	actual destination 450	job 587
queues-supported 659	snmp-timeout attribute	submitting jobs 61
save-rip-files 659 security-level 659	actual destination 451	syntax
security-level 659 server-hostname 660	snmp-trap-timeout attribute	of commands
server-ip-address 660	server 664	lprafp 13
server-name 661	special characters in commands xxviii	mkfntmap 15
server-state 661	start-message attribute	pdaccount 17
smtp-server-host 661	default job 570	pdclean 20
smtp-server-port-number 662	job 570	pdcreate 23
1 1	,	1

syntax (continued)	syntax (continued)	tlist utility (continued)
pddelete 28	of utilities (continued)	examples 184
pddisable 32	startppo 176	flags 184
pdenable 35	startsrv 179	syntax 184
pdls 38	stop_server 181	total-job-octets attribute
pdmod 49	stopcbd 201	job 590
pdpause 54	stopnotd 198	transfer-method attribute
pdpr 61	t2file 185	document 536
pdpromote 70	tdump 182	transfer-methods-supported attribute
pdq 72, 77	tlist 184	server 664
± ±	syntax for attribute values	
pdresubmit 79		transform, attributes of
pdresume 83	complex 334	associated-server 666
pdrm 86	notification-profile, complex 334	descriptor 666
pdset 89	overview 334	other-transform-options 668
pdshutdown 94	system resource directories, paths 258	output-document-format 669
pdspace 99	_	terminating-transform 670
of transforms	Т	transform-identifier 671
d2afp 209	t2file utility	transform-library 671
db2afp 205		transform-identifier attribute 671
gif2afp 212	description 185	transform-message-file-name attribute
jpeg2afp 226	examples 185	default document 537
line2afp 239	flags 185	document 537
pcl2afp 264	syntax 185	transform-output-file-name attribute
pdf2afp 287	table reference characters 259	document 537
ps2afp 287	table-reference-characters attribute	transform-sequence attribute
sap2afp 302	default document 535	actual destination 453
tiff2afp 313	document 535	transforms
of utilities	table-reference-characters-supported	d2afp 209
admingui 129	attribute	db2afp 205
afpsplit 130	actual destination 453	gif2afp 212
ainupod1 131	logical destination 619	jpeg2afp 226
ainupod2 132	tape-exit	line2afp 239
ainupod3 133	job 588	pcl2afp 264
ainurpt1 135	tape-format	pdf2afp 287
ainurpt2 136	job 588	ps2afp 287
ainurpt3 137	tape-labeled	sap2afp 302
ainurpt4 139	job 589	tiff2afp 313
	tape-max-block-size	Transmission Control Protocol/Internet
ainurpt5 140	job 589	Protocol
ainurpt6 141 cfu 142	tape-rewind-before	
	job 590	port number 293
cmt 144	tape-rewind-unload	tray-identification component
ipguiadv 146	job 590	input-trays-medium attribute, actual
ipguiadvadm 147	TCP/IP	destination 390
ipguibasic 146	port number 293	tray-number component
ipguibasicadm 147	tdump utility	psf-tray-characteristics attribute, actual
ipguidist 146	description 182	destination 433
ipguidistadm 147	examples 182	trc option 259
jsmigr 149	-	type attribute
mvsprsd 188	flags 182	default document 490
opergui 152	syntax 182	document 490
pcl2afpd 190	terminating-transform attribute 670	
pdadmin 153	ticket-content attribute	
pdcrcds 154	job 553	U
pdcrdflt 155	tiff2afp transform	un doulines in commande verriii
pdcrmed 157	configuration file 318	underlines in commands xxviii
pdinitports 158	description 313	upper-limit component
pdmigpp 160	options 319	job-size-range-ready attribute
pdmincfg 162	syntax 313	actual destination 395
pdmsg 164	time outs	job-size-range-supported attribute
ps2afpd 193	server 295	actual destination 396
rc.iprsap 166	timeout-period attribute	logical destination 611
rc.pd 167	actual destination 371	x-image-shift-range-supported
sense 168, 170	title-text attribute	attribute
setup 173	default document 536	actual destination 456
start_server 177	document 536	logical destination 622
start_server 177	examples 671	y-image-shift-range-supported
	tlist utility	attribute
startnotd 197	description 184	actual destination 457
	1	

upper-limit component (continued)	V
logical destination 623	validation of jobs, attributes used
use-snmp attribute actual destination 454	for 719
user-exit programs	vertical bars in commands xxvii
for ACIF 262	
user exits	W
input 250	
output 252	wait-for-job-completion attribute
resource 257	actual destination 454
user-id-text attribute	warning-message attribute actual destination 455
default document 538	width
document 538 user-locale attribute	PDF image 295
job 591	PostScript image 295
user-name attribute	width keyword
job 591	pdf2afp transform 295
userlib option 259	ps2afp transform 295
utilities	wildcards (global characters) 6 windows-driver-names attribute
admingui 129	logical destination 620
afpsplit 130	windows-drivers attribute
ainupod1 131	logical destination 620
ainupod2 132	windows-nt-driver-names 665
ainupod3 133	windows-nt-driver-names attribute
ainurpt1 135 ainurpt2 136	actual destination 455
ainurpt3 137	logical destination 621
ainurpt4 139	servers 665 windows-nt-drivers attribute
ainurpt5 140	actual destination 455
ainurpt6 141	logical destination 621
cfu 142	server 665
cmt 144	
ipguiadv 146 ipguiadvadm 147	V
ipguibasic 146	X
ipguibasicadm 147	x-dimension component
ipguidist 146	medium-dimensions attribute,
ipguidistadm 147	medium 626
jsmigr 149	x-image-shift attribute default document 538
mkfntmap 15 mvsprsd 188	document 538
opergui 152	x-image-shift-back attribute
pcl2afpd 190	default document 539
pdadmin 153	document 539
pdcrcds 154	x-image-shift-range-supported attribute
pdcrdflt 155	actual destination 456
pdcrmed 157	logical destination 622 X offset keyword on ps2afp or pdf2afp
pdinitports 158	transform 296
pdmigpp 160 pdmincfg 162	xxxxyyyy.tab file 311
pdmsg 164	
ps2afpd 193	V
rc.iprsap 166	Υ
rc.pd 167	y-dimension component
sense 168	medium-dimensions attribute,
setup 173	medium 626
start_server 177 startcbd 199	y-image-shift attribute
startcotd 199 startnotd 197	default document 540 document 540
startipo 176	y-image-shift-back attribute
startsrv 179	default document 540
stop_server 181	document 540
stopcbd 201	y-image-shift-range-supported attribute
stopnotd 198	actual destination 457
t2file 185	logical destination 622
tdump 182	Y offset keyword on ps2afp or pdf2afp
tlist 184	transform 296

Readers' Comments — We'd Like to Hear from You

Infoprint Manager Reference Publication No. S544-5475-05 Overall, how satisfied are you with the information in this book? Very Satisfied Satisfied Dissatisfied Very Neutral Dissatisfied Overall satisfaction How satisfied are you that the information in this book is: Very Satisfied Satisfied Neutral Dissatisfied Very Dissatisfied Accurate Complete Easy to find Easy to understand Well organized Applicable to your tasks \Box Please tell us how we can improve this book: Thank you for your responses. May we contact you? ☐ Yes When you send comments to IBM, you grant IBM a nonexclusive right to use or distribute your comments in any way it believes appropriate without incurring any obligation to you.

Address

Phone No.

Company or Organization

Name

Readers' Comments — We'd Like to Hear from You S544-5475-05



Cut or Fold Along Line

Fold and Tape

Please do not staple

Fold and Tape



Haddlaaddallaandlldaladaadllaadalld

NO POSTAGE NECESSARY IF MAILED IN THE UNITED STATES

BUSINESS REPLY MAIL

FIRST-CLASS MAIL PERMIT NO. 40 ARMONK, NEW YORK

POSTAGE WILL BE PAID BY ADDRESSEE

IBM Corporation Information Development IBM Printing Systems Department H7FE Building 003G PO Box 1900 Boulder, CO 80301-9817



Fold and Tape

Please do not staple

Fold and Tape

IBW.

Program Number: 5765-E42

5639-I27



Printed in the United States of America on recycled paper containing 10% recovered post-consumer fiber.

S544-5475-05

